G.M. 1881



Percy Ashworth B.Sc.

June 1885.

Portion of Senior Physiology Prize.

A TEXT-BOOK

OF

PHARMACOLOGY, THERAPEUTICS,

AND

MATERIA MEDICA.



54800

A TEXT-BOOK

OF

PHARMACOLOGY, THERAPEUTICS,

AND

MATERIA MEDICA

BY

T. LAUDER BRUNTON, M.D., D.Sc., F.R.S.,

Fellow of the Royal College of Physicians; Assistant Physician and Lecturer on Materia Medica at St. Bartholomew's Hospital; Examiner in Materia Medica in the University of London, in the Victoria University, and in the Royal College of Physicians, London; Late Examiner in the University of Edinburgh.

ADAPTED TO THE

UNITED STATES PHARMACOPŒIA.

BY

FRANCIS H. WILLIAMS, M.D., BOSTON, MASS.

London

MACMILLAN AND CO.

1885

The Right of Translation is Reserved

MATERIA MEDICA, Texts : 19 cent
THERAPEUTICS, Texts : 19 cent
PHARMACOLOGY, Texts : 19 cent

- 61726 -

RICHARD CLAY AND SONS,
BREAD STREET HILL, LONDON, E.C.,
And at Bungay, Suffolk.

WELLCOME HISTORICAL MEDICAL LIBRARY

M15558 GM1881

WELLCOME INSTITUTE LIBRARY
Coll. welMOmec
Call No. QV4 1885 B91t

TO

THE MEMORY OF

SIR ROBERT CHRISTISON, BART., &C.,

HIS HONOURED TEACHER,

AND TO

CARL LUDWIG,

HIS BELOVED MASTER,

This Book is gratefully Dedicated

BY

THE AUTHOR.

PREFACE.

SOME apology is required for the long delay in the appearance of this work, for a number of years have now elapsed since it was advertised as being in the press. More than fifteen years ago, I had a work on *Materia Medica* completely written out and ready for the printer. Some time afterwards, all the arrangements had been made for its publication, and in the course of a few weeks it was to have been issued from the press. Just as I was about to send it to the printer, however, I asked for a little delay in order that I might make some improvements and remove some redundancies, for the work as it then stood was considerably larger than the present one.

As I went through it, I found so many unsatisfactory statements and uncertainties regarding the mode of action of drugs, which I thought I could decide by a few experiments, that I wished for a little time in order that those doubtful points might be settled; but as I went on the labour grew, other engagements became pressing, and longer and longer delay was required. From greater experience as a teacher and examiner also, I came to the conclusion that the plan of the work might be altered with advantage; and so finally the whole manuscript was thrown aside, and the book entirely re-written.

In the original work I discussed the physiological and therapeutical actions of each drug separately, in the same way as in the third part of the present work, though on a much more

extended scale. I found, however, that this plan necessitated a good deal of repetition regarding the experimental methods by which the action of the drugs had been ascertained.

Moreover, the physician does not want to know only what the actions of any one drug are; he rather requires a knowledge of drugs, and of the manner in which the actions of the individual classes of members of a class differ from each other. He requires, in fact, a knowledge of the ways in which the various functions of the body can be influenced by drugs both in health and disease, in order that he may restore health to his patients.

It has appeared to me, therefore, better to devote a complete section of the work to a discussion of the methods by which the action of drugs is determined; to the manner in which each function of the body can be modified by drugs; and to the general *rationale* of the use of drugs in disease, *i.e.* to devote a section to general pharmacology and general therapeutics.

Considerable experience both in teaching and examining have shown me that students sometimes find a difficulty in applying physiology to pharmacology and therapeutics, and I find that many others are, like myself, apt to forget those parts of physiology which they are not constantly studying. I have therefore thought it well, for the sake both of students and practitioners, to give a short account of the normal functions of the different parts of the body, before I proceeded to discuss the alterations which are produced in them by drugs, or which they undergo in disease. In the case of the heart and the kidneys also, where the action of drugs is complicated and difficult, I have found it necessary to enter a little more fully into the physiology of these organs than is done in the ordinary text-books.

I have found that a similar difficulty occurs with pathology as with physiology, and I have therefore occasionally discussed pathological questions when I have thought that by doing so I could render the action of drugs in disease more intelligible, and thus aid the student of rational therapeutics.

In the second part of the work on general pharmacy, I have

classed together the various pharmaceutical preparations and given lists of them for reference. It is by no means my intention that these should be learned by heart by any student, and indeed I think it is well to take this opportunity of protesting against the injustice of the demands which are sometimes made upon the memories of students.

It is probable that the majority of the best and most successful practitioners would be very much puzzled if they were required to state the exact quantity of every ingredient in each pill or each ointment that they prescribe, or the exact quantity of the crude drug from which the infusions or tinctures which they use have been made. They know the action of the pill or ointment, they know the action of the infusion or tincture, and they do not trouble themselves about details which are only useful to the chemist who is making up the preparation.

It is very greatly to be regretted, for it is a stumbling-block in the way of true progress, that students who have afterwards to become medical practitioners and not pharmaceutical chemists, should be asked at examinations the quantities of crude drugs from which particular preparations are made—quantities which even the manufacturing chemist himself would never dream of carrying in his memory, but would obtain by reference to his books whenever he required them. As the late Professor Sharpey used very truly to say, "You may as well require of a medical student a knowledge of the whole art of cutlery before you set him to dissect." Medical science is now advancing in every direction, and unless we cut off some of the less useful kinds of information, which medical students were formerly obliged to acquire, it becomes impossible for them to learn all that is truly valuable. In Materia Medica we now oblige them to learn the physiological action of drugs, a subject regarding which, until quite recently, little or nothing was known, and to oblige them to learn all this, in addition to what they were formerly expected to know, is to treat them as Pharaoh treated the Israelites, and compel them to make the same number of bricks, while giving them no straw.

I am so much impressed with the necessity of lessening the amount of unnecessary work sometimes required as a preparation for examinations, that at first I omitted from this book all reference to the composition of pharmaceutical preparations. But as it is intended not only as a text-book for students, but also for the use of practitioners, I afterwards considered that it might be convenient to have the composition of some pharmaceutical preparations, at least, for the purpose of reference. I have omitted the composition of such preparations as are likely to be got ready-made from a chemist, but have inserted the composition of infusions which often need to be prepared when required. I have also given the composition of various compound pills, but only for the purpose of reference.

In consequence of this change in the plan of the work while it was passing through the press, the preparations of rhubarb have been omitted from their proper place at page 924, and are to be found at page 1005.

In the preparation of this work I have to acknowledge my obligations to the admirable works of Bartholow, Binz, Buchheim, Dujardin-Beaumetz, Edes, Husemann, Nothnagel and Rossbach, Ringer, Schmiedeberg, and H. C. Wood. Messrs Chapman, Soutter, Spencer, Steinthal, Stubbs, Wells, and Wright for the excellent notes they took of my lectures; to Dr. D'Arcy Power for the verification of references; to Dr. Mitchell Bruce, Mr. T. W. Shore, and Mr. H. W. Gardner for much kind assistance in the preparation of the work, and to Prof. Matthew Hay, of Aberdeen, whose criticisms and suggestions have been invaluable. To Dr. Francis H. Williams, of Boston, Mass., I am indebted for the adaptation of this work to the United States Pharmacopœia, which by tending to familiarise medical men on each side of the Atlantic with the preparations employed in both countries may, I trust, tend to facilitate the introduction of an International Pharmacopœia.

T. Lauder Brunton.

March, 1885.

CONTENTS.

PAGE

INTRODUCTION 1

SECTION I.

GENERAL PHARMACOLOGY AND THERAPEUTICS.

CHAPTER I.

GENERAL RELATIONS BETWEEN THE ORGANISM AND SUBSTANCES AFFECTING IT, pp. 9—24.

List of Elements 9
Nature of Elements 10
Classification of Elements 14
Mendelejeff's Classification of the Elements 17
Organic Radicals 19
Chemical Reactions and Physiological Reactions 19
Relation between Atomic Weight and Physiological Action 21
,, ,, Spectroscopic Characters and Physiological Action . . 21
Connection between Chemical Constitution and Physiological Action . . 22
Relation between Isomorphism and Physiological Action 23

CHAPTER II.

CIRCUMSTANCES WHICH AFFECT THE ACTION OF DRUGS ON THE ORGANISM, pp. 25—42.

Interaction of Various Functions 25
Direct and Indirect Action 26
Local and Remote Action 26
Relation of Effect to Quantity of the Drug 26
Homœopathy 27
Dose 27
Size 28

PAGE

Mode of Administration 28
Cumulative Action 30
Effect of Different Preparations 31
,, Fasting 31
,, Habit 32
,, Temperature 32
,, Climate 36
,, Time of Day 36
,, Season 36
,, Disease 37
Use of Experiments 37
Comparative Pharmacology 37
Idiosyncrasy 38
Objections to Experiment 39
Erroneous Deductions from Experiments 41

CHAPTER III.

ACTION OF DRUGS ON PROTOPLASM, BLOOD, AND LOW ORGANISMS, pp. 43—87.

Action of Drugs on Albumen 43
,, ,, Protoplasmic Movements 45
Method of Experimentation 45
Leucocytes 47
Effect of Drugs on Leucocytes 47
Movements of Leucocytes in the Blood Vessels 47
,, Red Blood Corpuscles 49
Action of Drugs on Infusoria 49
Relations of Motion and Oxidation 51
Oxidation of Protoplasm 53
Oxygen-carrying Power of Protoplasm 54
Ozonising Power of Protoplasm 54
Action of Drugs on Oxidation 54
Action of Drugs on Blood 55
Catalysis—Fermentation—Inorganic Ferments 58
Ferments, Organic and Organised 59
Action of Drugs on Enzymes 61
Zymogens 65
Organised Ferments 65
Yeasts 66
Moulds 66
Bacteria 68
Action of Drugs on the Movements of Bacteria 70
,, ,, Reproduction of Bacteria 71
,, ,, ,, ,, Mode of Experimenting on . 71
,, ,, Particular Species of Bacilli 74
,, ,, ,, ,, Mode of Experimenting on . 74
,, ,, Development and Growth of Bacilli 77
Influence on Antiseptics of the Solvent 78

PAGE

Influence on Antiseptics of the Admixture 78
,, ,, ,, Temperature 78
Alterations in Bacteria by Heat and Soil 78
Possible Identity of different Forms of Bacteria 79
Action of Bacteria and their Products on the Animal Body 80
Alkaloids formed by Putrefaction—Ptomaïnes 81
Effect of Drugs on the Action of Bacteria in the Animal Body . . . 82
Antiseptics—Antizymotics—Disinfectants—Deodorizers 83
Uses of Antiseptics 84
Disinfectants 86
Deodorizers 86
Antiperiodics 87

CHAPTER IV.

ACTION OF DRUGS ON INVERTEBRATA, pp. 88—94.

Action of Drugs on Medusæ 88
,, ,, Mollusca 92
,, ,, Ascidians 93
,, ,, Annulosa 93

CHAPTER V.

ACTION OF DRUGS ON MUSCLE, pp. 95—118.

Action of Drugs on Voluntary Muscle 95
Irritability of Muscle 96
Contraction of Muscle 96
Latent Period of Muscle 97
Summation of Stimuli 99
Curve of Muscular Contraction 99
Effect of Fatigue and Temperature 100
Contracture 101
Tetanus 102
Muscular Poisons 103
Massage 107
Propagation of the Contraction Wave in Muscle 108
Rythmical Contraction of Muscle 108
Connection between Chemical Constitution and Physiological Action on Muscle 110
Action of Drugs on Muscle is Relative and not Absolute 111
,, ,, on Involuntary Muscular Fibre 112
Effect of Stimuli 113
Relation of Contractile Tissue to the Nerves 114
Propagation of Contraction Waves 115
Artificial Rhythm 115
Hypothetical Considerations regarding the Action of Drugs on Muscle . . 116

CHAPTER VI.

ACTION OF DRUGS ON NERVES, pp. 119—128.

PAGE

Action of Drugs on Motor Nerves 119
Paralysis of Motor Nerve-Endings by Drugs 121
Irritation of Motor Nerve-Endings 125
Action of Drugs on the Trunks of Motor Nerves 125
,, ,, Sensory Nerves 126
Local Sedatives and Local Anæsthetics 127
timulating Action of Drugs on the Peripheral Ends of Sensory Nerves . . 128

CHAPTER VII.

ACTION OF DRUGS ON THE SPINAL CORD, pp. 129—151.

Action on the Conducting Power of the Cord 129
Action of Drugs on Reflex Action 133
Direct, Indirect, and Inhibitory Paralysis of the Spinal Cord by Drugs . . 134
Indirect Paralysis 134
Direct ,, ... 134
Spinal Depressants and their Uses 135
Inhibitory Paralysis 135
Nature of Inhibition 137
Interference in Nervous Structures 139
Effect of Altered Rate of Transmission 139
Opposite Conditions produce Similar Effects 140
The Same Conditions may cause Opposite Effects 140
Stimulation and Inhibition merely Consequences of Relation . . . 140
Test of the Truth of the Author's Hypothesis regarding Inhibition . . . 140
Explanation of the Action of Certain Drugs on this Hypothesis . . . 141
Stimulating Action of Drugs on the Reflex Powers of the Cord . . . 147
Localisation of the Action of Strychnine by Magendie 147
Spinal Stimulants 151

CHAPTER VIII.

ACTION OF DRUGS ON THE BRAIN, pp. 152—183.

Functions of the Brain in the Frog 152
,, ,, ,, ,, Higher Animals 153
Depressant Action of Drugs on Motor Centres in the Brain 155
Irritant ,, ,, ,, ,, ,, ,, ... 156
Convulsions 157
Action of Drugs on the Sensory and Psychical Centres in the Brain . . . 159
Drugs which Increase the Functional Activity of the Brain 160
Nerve Stimulants 160
Cerebral Stimulants 160
Drugs which Lessen the Functional Activity of the Brain 163

PAGE

Hypnotics or Soporifics 164
Narcotics 167
Anodynes or Analgesics 168
Adjuncts to Anodynes 170
Anæsthetics 171
Stages of their Action 174
Uses of Anæsthetics 175
Dangers of Anæsthetics 175
Mode of Administering Anæsthetics 177
Anæsthesia in Animals 177
History of the Discovery of Anæsthesia 179
Antispasmodics 180
Action of Drugs on the Cerebellum 182

CHAPTER IX.

ACTION OF DRUGS ON THE ORGANS OF SPECIAL SENSE, pp. 184—196.

Action of Drugs on the Eye 184
,, ,, ,, Conjunctiva 184
,, ,, ,, Lachrymal Secretion 184
Projection of the Eyeball 184
Action of Drugs on the Pupil 185
,, ,, ,, Accommodation 190
,, ,, ,, Intra-ocular Pressure 190
Uses of Mydriatics and Myotics 191
Action of Drugs on the Sensibility of the Eye 192
,, ,, in Producing Visions 193
,, ,, on Hearing 193
,, ,, on Smell 194
,, ,, on Taste 195

CHAPTER X.

ACTION OF DRUGS ON RESPIRATION, pp. 197—220.

Respiratory Stimulants and Depressants 197
Comparative Anatomy of the Respiratory Centre 197
Action of Drugs on the ,, ,, ... 205
,, ,, ,, Respiratory Nerves 209
Sternutatories or Errhines 210
Pulmonary Sedatives 211
Pathology of Cough 211
Expectorants 215
Action of Drugs on the Bronchial Secretion 216
,, ,, ,, Expulsive Mechanism 219
Adjuncts 219

CHAPTER XI.

ACTION OF DRUGS ON THE CIRCULATION, pp. 221—296.

PAGE

Arteries and Veins 221
Blood-pressure 222
Fainting and Shock 223
Scheme of the Circulation 224
Circulation in the Living Body 226
Mode of Ascertaining the Blood-pressure 227
Fallacies 228
Alterations in Blood-pressure 229
Relation of Pulse-rate and Arterioles to Blood-pressure 230
Effect of the Arterioles on Pulse Curves 234
Investigation of the Action of Drugs on the Arterioles 236
Method of Measurement by Rate of Flow 239
Action of Drugs on Vaso-motor and Vaso-dilating Nerves 242
Action of Other Parts on the Blood-pressure 243
Reflex Contraction of Vessels 244
Action of Drugs on Reflex Contraction of Vessels 245
Comparative Effect of Heart and Vessels on Blood-pressure in Different Animals 246
Influence of Nerves on Blood-pressure 248
Causes of Alteration in Blood-pressure and Pulse-rate 251
Action of the Heart on Blood-pressure 252
Effect of Drugs on the Pulse-rate 253
Action of Drugs on the Cardio-inhibitory Action of the Vagus 254
Reflex Stimulation of the Vagus 255
Causes of Quickened Pulse 255
Action of Drugs on Vagus Roots 255
Action on Accelerating Nerves 256
Stimulating Effect of Asphyxial Blood on the Medulla 256
Stimulation of the Heart by Increased Blood-pressure 256
Palpitation 257
The Heart of the Frog 258
Action of Drugs on the Heart of the Frog 259
,, ,, its Muscular Substance 263
Differences Between the Heart Apex and the Heart 266
Action of Drugs on the Vagus of the Frog 268
Action of Drugs on Inhibition of the Heart 268
Theories Regarding the Mode of Action of Drugs on the Heart . . . 270
Drugs which Act on the Vagus Centre 274
,, ,, ,, ,, Accelerating Centre 274
,, ,, ,, ,, Vaso-motor ,, ... 274
,, ,, ,, ,, Vagus Ends in the Heart 275
,, ,, ,, ,, Inhibitory Ganglia 275
,, ,, ,, ,, Motor Ganglia 275
Drugs which Act on the Cardiac Muscle 276
,, ,, ,, ,, Vaso-motor Nerves 276
,, ,, ,, ,, Capillaries 277
Stannius's Experiments 277

PAGE
General Considerations regarding the Heart 280
Regulating Action of the Nervous System 281
Hypothesis regarding the Action of the Vagus 283
Inhibition in the Heart 285
Therapeutic Uses of Drugs acting on the Circulation 285
Cardiac Stimulants 286
Vascular ,, ... 287
Cardiac Tonics 288
Risks Attending the Administration of Digitalis and other Cardiac Tonics . 292
Vascular Tonics 293
Pathology of Dropsy 293
Cardiac Sedatives 295
Vascular ,, ... 296

CHAPTER XII.

REMEDIES ACTING ON THE SURFACE OF THE BODY, pp. 297—307.

Irritants and Counter-irritants 297
Rubefacients 301
Vesicants 302
Pustulants 302
Caustics 302
Emollients and Demulcents 303
Astringents 305
Styptics 306

CHAPTER XIII.

ACTION OF DRUGS ON THE DIGESTIVE SYSTEM, pp. 308—358.

Action of Drugs on the Teeth 308
Sialogogues 309
Excretion by the Saliva 313
Refrigerants 315
Pathology of Thirst 315
Antisialics 316
Gastric Tonics 317
Appetite 317
Action of Drugs on Secretion in the Stomach 319
,, ,, ,, the Movements of the Stomach 320
Absorption from the Stomach 320
Antacids 321
Emetics 321
Gastric Sedatives and Anti-emetics 327
Carminatives 328
Action of Drugs on the Intestines 330
Intestinal Movements and Secretion 330
Paralytic Secretion 331

PAGE
Constipation 335
Action of Drugs on Absorption from the Intestines 337
Intestinal Astringents 337
Purgatives 339
Action of Purgatives 340
Uses of Purgatives 344
Action of Irritant Poisons 345
Peculiarities in the Action of different Irritant Poisons 347
Secondary Effects of Irritant Poisoning 348
Action of Drugs on the Liver 349
Hepatic Stimulants 352
Cholagogues 353
Adjuncts to Cholagogues 355
Uses of Hepatic Stimulants and Cholagogues 356
Hepatic Depressants 356
Action of Drugs on the Pancreas 357
Anthelmintics 357

CHAPTER XIV.

DRUGS ACTING ON TISSUE CHANGE, pp. 359—368.

Tonics 359
Hæmatinics 361
Alteratives 362
Antipyretics—Febrifuges 365

CHAPTER XV.

ACTION OF DRUGS ON EXCRETION, pp. 369—392.

Action of Drugs on the Kidneys 369
Circumstances Modifying the Secretion of Urine 374
Mode of Action of Diuretics 378
Adjuvants to Diuretics 381
Action of Drugs on Albuminuria 381
Lithontriptics 382
Action of Drugs on the Skin 383
Diaphoretics and Sudorifics 383
Excretion by the Sweat Glands 385
Relation between Sweat Glands and Kidneys 386
Action of the Skin in Regulating Temperature 386
Antihydrotics or Anhydrotics 387
Pathology of Night Sweats 388
Action of Drugs on the Bladder 390
Urinary Sedatives and Astringents 392

CHAPTER XVI.

ACTION OF DRUGS ON THE GENERATIVE SYSTEM, pp. 393—401.

	PAGE
Aphrodisiacs and Anaphrodisiacs	393
Aphrodisiacs	395
Anaphrodisiacs	396
Emmenagogues	397
Ecbolics	398
Action of Drugs upon Milk	399

CHAPTER XVII.

METHODS OF ADMINISTERING DRUGS, pp. 402—427.

Application of Drugs by the Skin	402
Epidermic Application	402
Baths	404
Cold Bath	405
Cold Pack	407
Cold Sponging	408
Cold Douches	408
Local Application of Cold	409
Cold Sitz Bath	409
,, Foot Bath	410
,, Compresses	410
Tepid Baths	411
Warm ,,	411
Hot ,,	411
Hot Foot-Bath	411
,, Sitz-Bath	412
Poultices	412
Medicated Baths	413
Sea-bathing	413
Acid Bath	413
Alkaline Bath	413
Sulphurous Bath	413
Mustard Bath	413
Pine Bath	414
Vapour Baths	414
Calomel Fumigation	414
Air Baths—Turkish Bath	415
Friction and Inunction	415
Massage	416
Inunction	417
Endermic Application of Drugs	417
Hypodermic Administration of Drugs	418
Objections to Hypodermic Injections	419

PAGE

Application of Drugs to the Eye 420
,, ,, Ear 420
,, ,, Nose 421
,, ,, Larynx 422
,, ,, Lungs 423
,, ,, Mouth and Pharynx 424
Masticatories—Gargles 425
Application of Drugs to the Stomach 425
Stomach-pump 425
Gastric Syphon 426
Application of Drugs to the Intestine 426
Enemata 426
Suppositories 427
Application of Drugs to the Urethra 427
,, ,, Vagina and Uterus 427

CHAPTER XVIII.

Antidotes, pp. 428—433.

Antidotes to Poisonous Gases 428
,, ,, Acids 429
,, ,, Alkalies 429
,, ,, Metallic Salts, Alkaloids, &c. 430

CHAPTER XIX.

Antagonistic Action of Drugs, pp. 434—437.

CHAPTER XX.

Dosage, p. 438.

SECTION II.

GENERAL PHARMACY.

CHAPTER XXI.

PHARMACEUTICAL PREPARATIONS, pp. 441—469.

	PAGE
Abstracta—Abstracts	443
Aceta—Vinegars	443
Alkaloidea—Alkaloids	443
Aquæ—Waters	444
Cataplasmata—Poultices	445
Cerata—Cerates	445
Chartæ—Papers	446
Collodia—Collodions	446
Confectiones—Confections—Electuaries	446
Decocta—Decoctions	446
Elixiria—Elixirs	447
Emplastra—Plasters	447
Enemata—Injections—Enemas—Clysters	448
Essentia—Essences	448
Extracta—Extracts	448
Glycerina—Glycerita—Glycerines	452
Infusa—Infusions	452
Injectio Hypodermica—Hypodermic Injection	453
Linimenta—Liniments—Embrocations	453
Liquores—Solutions	455
Massæ—Masses	455
Mellita—Honeys	455
Misturæ—Mixtures	456
Mucilagines—Mucilages	456
Olea—Oils, Fixed and Volatile	457
Oleata—Oleates	458
Oleoresinæ—Oleoresins	458
Oxymel	458
Pilulæ—Pills	459
Pulveres—Powders	460
Resinæ—Resins	460
Spiritus—Spirits	461
Suppositoria—Suppositories	461
Succi—Juices	462
Syrupi—Syrups	462
Tincturæ—Tinctures	463
Triturationes—Triturations	466
Trochisci—Lozenges	466
Unguenta—Ointments	467
Vapores—Vapours—Inhalations	468
Vina—Wines	469

SECTION III.

INORGANIC MATERIA MEDICA.

CHAPTER XXII.

HYDROGEN, OXYGEN, OZONE, CARBON, SULPHUR, AND THE HALOGENS, pp. 473—492.

	PAGE
Hydrogen	473
Oxygen	473
Ozone	475
Peroxide of Hydrogen	476
Carbon	477
Sulphur	479
Sulphuretted Hydrogen	481
Halogen Elements—General Source and Characters	483
Mode of Preparation	484
General Action	484
Chlorine	485
Chlorinated Lime	486
,, Soda	487
Bromine	488
Iodine	489
Iodide of Sulphur	490
Action of Iodine	490

CHAPTER XXIII.

ACIDS, pp. 493—517.

General Characters of Acids	493
,, Preparation of Acids	493
,, Action ,, ,,	495
Sulphuric Acid	498
Sulphurous ,,	499
Hydrochloric Acid	500
Nitric ,,	501
Nitro-hydrochloric Acid	503
Acetic ,,	503
Phosphoric ,,	505
Tartaric ,,	506
Citric ,,	507
Oxalic ,,	507
Gallic ,, (*vide* p. 943)	507
Tannic ,, (*vide* p. 941)	507

PAGE

Boric or Boracic Acid 508
Chromic ,, ... 508
Carbonic ,, ... 509
Hydrocyanic ,, ... 512
Arsenious ,, (*vide* p. 646) 516
Benzoic ,, (*vide* p. 879) 516
Chrysophanic ,, (*vide* p. 823) 516
Lactic ,, ... 516
Hydrobromic ,, ... 516
Oleic ,, ... 517
Carbolic ,, (*vide* p. 734) 517
Salicylic ,, (*vide* p. 740) 517

CHAPTER XXIV.

METALS, pp. 518—574.

General Classification of the Metals 518
General Tests for Acid Radicals in Metallic Salts 519
Metals of the Alkalis. Their Characters and Reactions 522
General Physiological Action of the Alkalis 522
,, ,, ,, ,, Alkaline Group of Salts 523
,, ,, ,, ,, Chlorides ,, ,, ... 525
,, ,, ,, ,, Sulphates ,, ,, ... 527
Comparative Action of the Alkaline Metals 528
Monad Metals, Group I., Potassium, Sodium, Lithium 529
Potassium, General Sources and Reactions of its Salts 529
Preparation of Potash Salts 530
General Action of Potash ,, ... 531
Characters, Action and Uses of Officinal Potash Salts . . . . 533—548
Sodium, General Sources and Reactions of its Salts 548
Preparation of its Salts 549
General Impurities, Tests and Action 550
Characters, Actions and Uses of Soda Salts . . . . . 550—561
Lithium, Sources, Reactions, Impurities and Tests of its Salts 561
General Action of Lithium Salts 562
Characters, Actions, and Uses of Officinal Lithium Salts . . . . 562—563
Monad Metals, Group II., Ammonium 564
Nature of Ammonium Salts 564
Sources, Reactions and Preparation 565
Impurities, Tests and Actions 566
Characters, Actions and Uses of Officinal Ammonium Salts . . . 567—574

CHAPTER XXV.

METALS (*continued*), CLASS II., DYAD METALS—GROUPS I. AND II., METALS OF THE ALKALINE EARTHS AND EARTHS, pp. 575—592.

Reactions of the Metals in Class II. 576
Class II., Group I., Metals of the Alkaline Earths 576
General Action of ,, ,, ,, ,, ... 576
Calcium, Reactions, Preparation, Impurities and Tests of its Salts . . 577, 578

PAGE
Characters, Action and Uses of Officinal Lime Salts . . . . . 578—585
Class II., Group I., Appendix—Aluminium 585
General Sources, Preparation, Reactions, Impurities and Tests of Alum Salts 585
Characters, Actions and Uses of Officinal Alum Salts . . . . . 585—588
Cerium, Action and Uses of its Oxalate 588
Class II., Group II., Magnesium 589
Sources, Reactions and Preparation of Magnesium Salts 589
Impurities, Tests and Action ,, ,, ,, ... 590
Characters, Actions and Uses ,, ,, ,, . . . 590—592

CHAPTER XXVI.

METALS (*continued*), THE HEAVY METALS, CLASS II., GROUPS III. AND IV. AND CLASS IV., pp. 593—634.

General Actions of Heavy Metals 592
,, ,, ,, Class II., Group III., Zinc, Copper, Cadmium and Silver . 596
Zinc, its Sources 597
General Reactions and Preparation of Zinc Salts 598
,, Impurities, Tests and Action ,, ,, ... 599
Characters, Action and Uses of Officinal Zinc Salts . . . . . 599—603
Copper, its Sources, Reactions, Impurities and Tests 604
Characters, Actions and Uses of Officinal Salts of Copper . . . 604, 605
Cadmium, Characters, Action and Use of its Iodide 606
Silver, Characters, Action and Uses of its Salts . . . . . 606—610
Class II., Group IV., Mercury 610
General Sources and Reactions of Salts of Mercury 610
,, Impurities, Tests and Action ,, ,, ... 611
Characters, Actions and Uses of Officinal Salts of Mercury . . . 616—627
Class IV., Tetrad Metals, Lead and Tin 627
General Actions 627
Lead, its Sources, Reactions, Impurities, Tests and Action 628
Characters, Actions and Uses of Officinal Salts of Lead . . . . 630—634
Tin, Action and Uses of its Chloride 634

CHAPTER XXVII.

CLASS V., PENTAD ELEMENTS—NITROGEN, PHOSPHORUS, ARSENIC, ANTIMONY, AND BISMUTH, pp. 635—660.

Nitrogen and its Compounds 635
Nitrous Oxide 636
Phosphorus, its Preparation, Characters and Action 637
Uses of Phosphorus 640
Arsenic, its Sources and Tests 640
General Action of Arsenic 640
Probable Mode of Action of Arsenic in Phthisis 645

PAGE
Characters, Actions and Uses of Officinal Preparations of Arsenic . . 646—648
Antimony, its Sources and Reactions 648
General Action 649
Characters, Action and Uses of its Officinal Preparations . . . 654—657
Bismuth, its Action 657
Sources, Reactions, Preparation and Uses of its Salts 658
Character, Action and Uses of its Officinal Preparations 659, 660

CHAPTER XXVIII.

METALS (*continued*), CLASS VIII., IRON, MANGANESE, pp. 661—679.

Iron, its Sources and Reactions 661
Impurities, Tests and Preparation of its Salts 662
General Action 665
Character, Action and Uses of its Officinal Preparations . . . . 666—678
Manganese 678
Class VIII., Group II., Gold and Platinum 679
Gold, Preparation and Characters of its Chloride 679
Platinum, Preparation, Uses and Action of its Chloride 680

SECTION IV.

ORGANIC MATERIA MEDICA.

CHAPTER XXIX.

CARBON COMPOUNDS—FATTY SERIES, pp. 685—729.

Chemistry of Carbon Compounds 685
General Action of Carbon Compounds 686
Bi-sulphide of Carbon 686
Hydro-Carbons 686
Benzin 688
Petrolatum (Vaseline) 688
Alcohols 689
Methyl Alcohol 691
Alcohol, General Sources and Preparation 691
General Impurities, Tests and Action 692
Effect of Impurities on its Action 695
Chronic Alcoholic poisoning 696
Causes and Treatment of Alcoholism 697
Uses of Alcohol 698
Alcohol as a Stimulant 699
Officinal Alcoholic Preparations . . . . . 700—703
Aldehydes, Ethylaldehyde and Paraldehyde 703

PAGE

Simple Ethers, Ether . . . . . 704—707
Saline Ethers 707
Ethereal Oil and Hoffman's Anodyne 707
Acetic Ether 707
Nitrites of Ethyl and Amyl 708
Nitro-glycerine 712
Haloid Compounds 713
Bromide of Ethyl 713
Iodide of Ethyl 714
Chloral Hydrate, its Preparation and Characters 714
Its Action 715
Treatment of Chloral poisoning 717
Bromal Hydrate 718
Butyl Chloral Hydrate 718
Bichloride of Methylene 718
Chloroform, its Preparation, Characters, Impurities and Tests 719
Action of Chloroform 720
Dangers of ,, ... 723
Precautions in using Chloroform 724
Uses of Chloroform 726
Iodoform 727

CHAPTER XXX.

CARBON COMPOUNDS—AROMATIC SERIES, pp. 730—742.

General Chemistry of the Aromatic Series 730
General Action ,, ,, ,, ... 734
Carbolic Acid 734
Its Action 735
Creosote 738
Resorcin 739
Hydroquinone 740
Pyrocatechin 740
Salicylic Acid 740
Naphthalin 742
Naphthol 742
Hydrochlorate of Rosaniline 743
Chinoline 743
Kairin 743
Antipyrin 744

SECTION V.

VEGETABLE MATERIA MEDICA.

CHAPTER XXXI.

SUB-KINGDOM I., PHANEROGAMS.

CLASS EXOGENS, DIVISION I., ANGIOSPERMS, SUB-CLASS I., THALAMIFLORÆ, pp. 747—808.

	PAGE
Ranunculaceæ	748
Aconite	748
Staphisagria	752
Pulsatilla	752
Adonis Vernalis	753
Cimicifuga	753
Podophyllum	754
Hydrastis	755
Magnoleaceæ	756
Illicium	756
Oil of Anise	756
Menispermaceæ	756
Menispermum	756
Calumba	756
Pareira	758
Picrotoxin	758
Berberidaceæ	759
Caulophyllum	759
Papaveraceæ	759
Poppy Capsules	759
Opium	760
Preparations of Opium	760
Morphine	763
Apomorphine	765
Codeine	766
Action of Opium	767
Diagnosis of Opium Poisoning	769
Treatment ,, ,,	769
Circumstances Modifying the Action of Opium	772
Action of the Alkaloids of Opium	774
Uses of Opium	775
Rhœas—Red Poppy	778
Sanguinaria—Blood Root	778
Chelidonium—Celandine	779
Cruciferæ	779
Sinapis—Mustard	779
Armoracia—Horseradish	782

PAGE
Violaceæ 782
Viola—Pansy 782
Linaceæ 782
Linseed—Flaxseed 782
Geraniaceæ 783
Geranium—Cranesbill 783
Polygalaceæ 784
Senega 784
Krameria—Rhatany 785
Sapindaceæ 786
Guarana 786
Erythroxylaceæ 786
Erythroxylon—Coca—Cuca 786
Malvaceæ 788
Gossypium—Cotton 788
Pyroxylin—Gun Cotton 789
Collodion 790
Althæa—Marshmallow 790
Aurantiaceæ 791
Orange 791
Oil of Bergamot 793
Lemon 794
Bael Fruit 795
Sterculiaceæ (Byttneriaceæ) 796
Theobroma—Cacao 796
Ternströmiaceæ 796
Tea 796
Caffeine 797
Guttiferæ 799
Cambogia—Gamboge 799
Canellaceæ 799
Canella Alba 799
Vitaceæ 800
Uvæ—Raisins 800
Vinum Xericum 800
Vinum Rubrum 800
Zygophyllaceæ 800
Guaiacum 800
Meliaceæ 802
Azedarach 802
Rutaceae 802
Ruteæ 802
Oil of Rue 802
Cusparia 802
Diosmeæ 803
Buchu 803
Xanthoxyleæ 804
Xanthoxylum—Prickly Ash 804
Pilocarpus—Jaborandi 804
Simarubaceæ 808
Quassia 808

CHAPTER XXXII.

CLASS I., EXOGENÆ, SUB-CLASS II., CALYCIFLORÆ, pp. 808—852.

	PAGE
Rhamnaceæ	809
Rhamnus—Frangula—Buckthorn	809
Cascara Sagrada	810
Celastraceæ	810
Euonymus—Wahoo	810
Aquifoliaceæ	810
Prinos—Black Alder	810
Terebinthaceæ	811
Anacardiæ	811
Mastiche	811
Rhus Glabra—Sumach	811
Rhus Toxicodendron—Poison Ivy	812
Amyridaceæ or Burseraceæ	812
Myrrh	812
Elemi	813
Leguminosæ	813
Papilionaceæ	813
Glycyrrhiza—Liquorice	813
Scoparius—Broom	814
Tragacanth	815
Pterocarpus—Santalum—Red Sandal-wood or Red Saunders	816
Kino	816
Balsam of Peru	816
Balsam of Tolu	817
Abrus—Jequirity	817
Physostigma—Calabar Bean	818
Hæmatoxylon—Logwood	822
Chrysarobinum—Chrysophanic Acid—Goa Powder	823
Cæsalpinæ	823
Senna	823
Cassia—Purging Cassia	825
Tamarind	825
Copaiba—Copaiva	826
Piscidia Erythrina—Jamaica Dogwood	827
Mimoseæ	828
Acacia	828
Catechu	828
Erythrophlœum—Casca—Sassy	829
Indigo	829
Rosaceæ	829
Pomeæ	829
Cydonium—Quince	829
Dryadeæ	830
Rubus—Blackberry	830
Rubus Idæus—Raspberry	830

Rosaceæ—(*continued*). PAGE
Roseæ 830
Oil of Rose 830
Rosa Centifolia—Cabbage Rose—Pale Rose 830
Rosa Gallica—Red Rose 831
Rosa Canina—Dog Rose 831
Cusso—Brayera 831
Quillaia—Soap Bark 832
Amygdaleæ 833
Amygdala Dulcis—Sweet Almond 833
Amygdala Amara—Bitter Almond 834
Prune 835
Prunus Virginiana—Wild Cherry 835
Laurocerasus—Cherry Laurel 836
Papayaceæ (Passifloræ) 836
Papayotin—Papain 836
Myrtaceæ 837
Caryophyllus—Cloves 837
Pimenta—Allspice 838
Cheken 838
Oleum Myrti—Oil of Myrtle 839
Oleum Cajuputi—Oil of Cajuput 839
Eucalyptus 840
Granatum—Pomegranate 841
Cucurbitaceæ 841
Colocynth 841
Ecbalium—Elaterium 843
Pepo—Pumpkin 844
Bryonia—Bryony 844
Umbelliferæ 845
Campylospermæ 845
Conium 845
Orthospermæ 847
Assafœtida—Asafetida 847
Galbanum 848
Ammoniacum 848
Foeniculum—Fennel 849
Anise 849
Anethum—Dill 850
Carum—Caraway 850
Sumbul 851
Cœlospermæ 852
Coriander 852

CHAPTER XXXIII.

CLASS I., EXOGENÆ (*continued*), SUB-CLASS III., COROLLIFLORÆ, pp. 853—922.

PAGE

Caprifoliaceæ 853
Sambucus 853
Cornaceæ 853
Cornus—Dogwood 853
Rubiaceæ 854
Cinchoneæ (Cinchonaceæ) 854
Cinchona Pallida—Pale Cinchona 854
,, Flava—Yellow ,, ... 854
,, Rubra—Red ,, ... 855
Quinine 856
Coffeæ 863
Ipecacuanha 863
Coffee 865
Pale Catechu 866
Valerianaceæ 866
Valerian 866
Caprifoliaceæ 868
Viburnum—Black Haw 868
Compositæ 868
Pyrethrum 868
Absinthium—Wormwood 868
Tanacetum—Tansy 869
Santonica—Santonin 869
Anthemis—Chamomile 871
Matricaria—German Chamomile 871
Eupatorium—Thoroughwort 871
Taraxacum—Dandelion 872
Lactuca—Lettuce 872
Arnica 873
Calendula—Marygold 874
Grindelia 874
Inula—Elecampane 875
Lappa—Burdock 875
Lobeliaceæ 876
Lobelia 876
Ericaceæ 877
Uva Ursi—Bearberry 877
Chimaphila—Pipsissewa 878
Oleum Gaultheriæ—Oil of Wintergreen 878
Sapotaceæ 879
Gutta-percha 879
Styraceæ 879
Benzoin—Benzoic Acid 879
Verbenaceæ. 881
Lippia Mexicana 881

PAGE

Oleaceæ 881
Olive Oil 881
Hard Soap 882
Soft Soap 882
Glycerin 882
Manna 883
Loganiaceæ 884
Nux Vomica 884
Ignatia 884
Strychnine 884
Gelsemium 890
Spigelia—Pinkroot—Maryland Pink 891
Apocynaceæ 891
Apocynum—Canadian Hemp 891
Quebracho 892
Asclepiadaceæ 892
Asclepias—Pleurisy Root 892
Asclepias Incarnata—White Indian Hemp 892
Hemedesmus 892
Condurango 893
Gentianaceæ 893
Gentian 893
Chiretta 894
Convolvulaceæ 895
Scammony 895
Jalap 897
Solanaceæ 898
Dulcamara 898
Capsicum 898
Atropaceæ 899
Belladonna—Atropine 899
Hyoscyamus 904
Stramonium 906
Tobacco 906
Scrophulariaceæ 908
Digitalis 908
Leptandra 916
Labiatæ 916
Rosemary 917
Lavender 917
Peppermint—Menthol 918
Spearmint 919
Thymol 919
Hedeoma—Pennyroyal 920
Marrubrum—Horehound 921
Melissa—Balm 921
Origanum—Wild Marjoram 921
Salvia—Sage 922
Scutellaria—Skull-cap 922
Pedalaceæ 922
Oleum Sesami 922

CHAPTER XXXIV.

CLASS I., EXOGENÆ, SUB-CLASS IV., APETALÆ, pp. 923—948.

PAGE

Polygonaceæ 923
Rheum—Rhubarb 923
Rumex—Yellow Dock 924
Phytolaccaceæ 924
Phytolacca—Poke berry 924
Chenopodiaceæ 925
Chenopodium—American Wormseed 925
Myristicaceæ 925
Myristica—Nutmeg 925
Macis—Mace 926
Lauraceæ 926
Cinnamon 926
Coto 927
Camphor 928
Monobromated Camphor 929
Sassafras 930
Nectandra—Bebeeru 931
Aristolochiaceæ 932
Serpentary 932
Asarabacca 932
Santalaceæ 932
Oleum Santali 932
Euphorbiaceæ 933
Cascarilla 933
Stillingia 933
Croton Oil 933
Castor Oil 934
Kamala 935
Piperaceæ 936
Pepper—Piperine 936
Cubebs 937
Matico 938
Salicaceæ 938
Salix—Salicin 938
Juglandaceæ 939
Juglans—Butternut 939
Hamamelaceæ 940
Hamamelis 940
Balsamifluæ 940
Styrax 940
Cupuliferæ 941
Quercus—Oak 941
Galls 941
Tannic Acid 941
Gallic Acid 943
Castanea—Chestnut 944

PAGE

Urticaceæ 944
Ulmeæ 944
Ulmus 944
Moreæ 945
Morus—Mulberry 945
Artocarpeæ 945
Ficus—Fig 945
Cannabineæ 946
Cannabis Indica—Indian Hemp 946
Cannabis Americana—American Cannabis 946
Humulus—Lupulus—Hop 947

CHAPTER XXXV.

Exogens (*continued*), Division II., Gymnosperms.

Coniferæ 949
Terebinthina Canadensis—Canada Balsam 949
Thus Americanum—Common Frankincense 949
Turpentine 950
Oil of Turpentine 950
Oil of Scotch Fir 951
Sanitas 952
Oleum Succini—Oil of Amber 952
Resin 952
Larch Bark 952
Burgundy Pitch 953
Canada Pitch 953
Tar 953
Oil of Tar 954
Thuja—Arbor Vitæ 954
Juniper 954
Savin 955

CHAPTER XXXVI.

Class II.—Endogens.

Smilaceæ 957
Sarsaparilla 957
Liliaceæ 958
Allium—Garlic 958
Squill 958
Aloe 959
Veratrum Viride 963
Cevadilla—Sabadilla—Veratrine 964
Colchicum 967

PAGE

Orchidaceæ 969
Vanilla 969
Cypripedium 969
Zingiberaceæ 970
Zingiber—Ginger 970
Turmeric 970
Iridaceæ 971
Crocus—Saffron 971
Iris 972
Palmaceæ 972
Areca 972
Araceæ 973
Calamus—Sweet Flag 973
Graminaceæ 973
Wheat—Flour—Bread—Starch 973
Couch Grass 974
Pearl Barley 974
Malt 975
Sugar 975
Treacle 976
Oatmeal 976

CHAPTER XXXVII.

Sub-Kingdom II., Cryptogams.

Filices 978
Male Fern 978
Lichenes 979
Cetraria—Iceland Moss 979
Litmus 979
Fungi 979
Ergot 979
Ustilago 983
Beer Yeast 983
Algæ 984
Chondrus—Irish Moss 984

SECTION VI.

ANIMAL KINGDOM.

CHAPTER XXXVIII.

PAGE

Class Mammalia 987
Order Rodentia 987
Castor 987
Order Ruminantia 987
Musk 987
Suet 988
Curd Soap 988
Milk—Koumiss—Milk Sugar 988, 989
Pepsin 990
Ox Gall 991
Keratin 992
Order Pachydermata 993
Lard 993
Order Cetaceæ 994
Spermaceti 994
Class Aves 995
Order Gallinæ 995
Egg Albumen and Yolk 995
Class Pisces 996
Order Sturiones 996
Ichthyocolla—Isinglass 996
Order Teleosteæ—Family Gadidæ 996
Cod Liver Oil 996
Class Insecta 998
Order Hymenoptera 998
Honey 998
Wax 999
Order Hemiptera 1000
Coccus—Cochineal 1000
Order Coleoptera 1000
Cantharis—Spanish Flies 1000
Class Annelida 1003
Hirudo—the Leech 1003
Preparations of Rhubarb omitted from p. 924—*vide* Preface 1005

GENERAL INDEX 1009
INDEX OF DISEASES AND REMEDIES 1079
BIBLIOGRAPHICAL INDEX 1119

INTRODUCTION.

By **Materia Medica** we understand a knowledge of the remedies employed in medicine. This knowledge may be subdivided into several divisions: Materia Medica proper, Pharmacy, Pharmacology, and Therapeutics.

By **Materia Medica proper** we mean an acquaintance with the remedies used in medicine, the places whence they come, the crude substances or plants which yield them, the methods by which they are obtained, and the means of distinguishing their goodness or purity, or of detecting fraudulent adulteration.

By **Pharmacy** we mean the methods by which drugs are prepared and combined for administration.

Pharmacology is a knowledge of the mode of action of drugs upon the body generally, and upon its various parts. It is of comparatively recent growth, but is now one of the most important subdivisions of Materia Medica.

By **Therapeutics** we understand a knowledge of the uses of medicines in disease.

Therapeutics may be either *empirical* or *rational*. By **empirical** we mean that drugs are tried haphazard, or with little knowledge of their action in some cases, and, being found successful, are again administered in other cases which seem to be similar.

Perhaps the best example of the empirical use of a remedy is that of quinine in ague. We do not know with certainty what the pathological conditions are in this disease, nor how quinine acts upon them; all we know is that it has proved useful in cases of ague before, and therefore we give it again.

Rational therapeutics consists in the administration of a drug because we know the pathological conditions occurring in the disease, and know also that the pharmacological action of the drug is such as to render it probable that it will remove or counteract these conditions.

As an example, we may take the use of nitrite of amyl in certain forms of angina pectoris. The obvious symptoms in this disease are intense pain in the region of the heart, and fear of impending death. Sphygmographic tracings of the pulse taken during this condition show that the tension within the heart and vessels begin to increase as the pain comes on, and reaches such a height that the heart can barely empty itself. Observations on animals have shown that nitrite of amyl lessens the tension of the blood in the vessels; and we therefore give it in angina pectoris with the expectation that it will diminish the tension and remove the pain, and we find that it succeeds.

But this example shows us only the first stage of rational therapeutics. We have removed by a remedy the pathological condition which immediately gives rise to the pain and danger of the patient, but the antecedent alterations of the heart, blood-vessels, and nervous system, which led to the occurrence of the pain, are unaltered by the remedy. In order that our therapeutics should be completely successful, we must seek still further for something which will restore the circulation and nervous system to its normal condition and bring the patient back to a state of perfect health. But sometimes this is impossible. The organic changes which have occurred in the course of the disease may be so great, that we can hardly hope that any remedy will ever be discovered sufficiently powerful to remove them. We must therefore try to prevent them.

Preventive medicine, or **prophylaxis,** is daily becoming more important, and, probably before the end of this century, medical men will be employed more to prevent people from becoming ill than to cure them when disease has become fairly established.

The advance of this branch of medicine has been greatly aided by the recent increase in our knowledge of the life-history of microbes and their action in causing disease. Our power to prevent disease will become greater when we know accurately the action of various drugs in destroying these microbes or preventing their growth.

Pharmacology has made such rapid advances of late years that it is exceedingly difficult for many men who are engaged in practice to understand thoroughly either the methods by which it is studied, or its results. Many students also, although they may be able to pass a good examination in physiology, find it difficult to apply their physiological knowledge to pharmacology; and therefore in discussing the action of drugs upon the various functions of the body, I have sometimes entered more fully into the physiology of those functions than may seem to some at all either necessary or advisable.

In discussing pharmacological questions, we are accustomed to speak of the **action** of a drug on the body, or on its various parts,

but we must remember the effect produced is not due to a one-sided action—that what we actually mean is the **Re-action** between the drug and the various parts of the body.

In some instances we know that the drug itself is changed in the body, as well as the function of the body modified by the drug; and even in those cases where the drug itself is eliminated from the body apparently unaltered, it is probable that it has entered into various chemical combinations within the body while circulating in the blood or present in the tissues.

MATERIA MEDICA AND THERAPEUTICS.

SECTION I.

GENERAL PHARMACOLOGY AND THERAPEUTICS.

CHAPTER I.

GENERAL RELATIONS BETWEEN THE ORGANISM AND SUBSTANCES AFFECTING IT.

In discussing the inter-action between the animal organism and the substances which act upon it, it may be well to take a slight glance first at the substances which compose its environment, although these will be afterwards considered more in detail.

Of the **elements** composing the earth on which we live we at present know about seventy whose existence appears well established. They are as follows:—

	Symbol.	Atomic Weight.		Symbol.	Atomic Weight.
*Aluminium	Al	27·3	Gallium	Ga	68 (?)
*Antimony	Sb	122·0	*Gold	Au	196·2
*_Arsenic_	_As_	74·9	Holmium		
*Barium	Ba	136·8	*_Hydrogen_	_H_	1·0
Beryllium or Glucinum	Be or G	9·4	Indium	In	113·4
			*_Iodine_	_I._	126·53
*Bismuth	Bi	210·0	Iridium	Ir	196·7
*_Boron_	_B_	11·0	*Iron	Fe	55·9
*_Bromine_	_Br_	79·75	Lanthanum	La	139·0
*Cadmium	Cd	111·6	*Lead	Pb	206·4
Cæsium	Cs	133·0	*Lithium	Li	7·01
*Calcium	Ca	39·9	*Magnesium	Mg	23·94
*_Carbon_	_C_	11·97	*Manganese	Mn	54·8
*Cerium	Ce	141·2	*Mercury	Hg	199·8
*_Chlorine_	_Cl_	35·37	Molybdenum	Mo	95·6
*Chromium	Cr	52·4	Nickel	Ni	58·6
Cobalt	Co	58·6	Niobium	Nb	94·0
*Copper	Cu	63·0	*_Nitrogen_	_N_	14·01
Didymium	Di	147·0	Osmium	Os	198·6
Erbium	Er or Eb†	169·0	*_Oxygen_	_O_	15·96
Fluorine	_F_	19·1	Palladium	Pd	106·2

Those marked with * are contained, either simply or in combination, in the British Pharmacopœia. Those printed in italics are non-metallic elements.

† Er, Roscoe and Schorlemmer, *Treatise on Chemistry*, vol. i. p. 54. Eb, Fownes, edited by Watts, 12th ed. vol. i. p. 401.

	Symbol.	Atomic Weight.
**Phosphorus*	*P*	30·96
*Platinum	Pt	196·7
*Potassium	K	39·04
Rhodium	Rh	104·1
Rubidium	Rb	85·2
Ruthenium	Ru	103·5
Samarium		
Scandium		
Selenium	*Se*	78·0
*Silver	Ag	107·66
Silicon	*Si*	28·0
*Sodium	Na	22·99
Strontium	Sr	87·2
**Sulphur*	*S*	31·98
Tantalum	Ta	182·0
Tellurium	*Te*	128·0
Terbium		
Thallium	Tl	203·6
Thorium	Th	231·5
Thulium		
*Tin	Sn	117·8
Titanium	Ti	48·0
Tungsten	W	184·0
Uranium	U	240·0
Vanadium	V	51·2
Yttrium	Y	93·0
Ytterbium		
*Zinc	Zn	64·9
Zirconium	Zr	90·0

Nature of the Elements.

Considerable additions have been made to the number of elements during late years. The reason of this is that the spectroscope has indicated the presence of metals previously unknown, and by the use of proper means they have been obtained in a separate condition. These substances are termed elements because we do not at present know how to split them up in such a manner as to prove that they are compounds. But it is not improbable that they are compounds, just as we now know that potash and soda are compounds ; although before Sir Humphrey Davy split them up into oxygen and a metal they were supposed to be elements. Indeed, recently much evidence has been brought to show that the substances which we call elements are really compounds.

It is from an examination of the spectroscopic character of the elements at different degrees of temperature that Lockyer has been able to obtain sufficient data to justify the definite formulation of the **hypothesis** that all the **elements** we know, are really compounds, or to speak perhaps more precisely, are really **different forms** of aggregation of one kind **of matter.**[1] According to this hypothesis the matter of which the universe is composed was at one time equally distributed through space, and uniform in kind. The atoms then coalesced in various groups of two, three, or more ; and these, again grouping themselves together still further, formed aggregates of more and more complex composition. These aggregates are, it is supposed, the elements with which we are acquainted. Most of those complex molecules are perfectly stable at ordinary temperatures ; and so their composition remains constant under the conditions usual at the surface of this earth.

But when they are subjected to increased temperatures in the laboratory, rising from that of the Bunsen lamp to the electric arc, and then to the electric spark or to still higher temperatures in the sun, their spectroscopic appearances give evidence of decomposition into simpler molecules. When the elements are subjected to cold and pressure the molecules which compose them come closer together, and we get them forming a solid substance. Heat tends by communicating vibrations to them to shake the molecules further apart, and to produce a liquid condition. Still greater heat shakes the molecules further apart still, and produces a gaseous condition.

In all those conditions the molecules of the element become more complex

[1] Lockyer, *Phil. Trans.* 1874, p. 492, &c.

by reduction of temperature or increase of pressure, and simpler by increase in temperature or reduction in pressure.[1] Exceedingly great heat or electricity appears to shake apart still further the constituents of the element, so as to resolve it into simpler combinations of the elementary substance of which, according to the hypothesis, it is composed.

This shaking apart of the component elements is known to exist in compounds, and to it the name of **dissociation** has been given. Thus when chalk or limestone is exposed to the action of heat it becomes dissociated into carbonic acid and lime, $CaCO_3 = CaO + CO_2$. This process is readily reversible by reversing the conditions. Thus the lime and carbonic acid which are dissociated by heat readily recombine in the cold $CaO + CO_2 = CaCO_3$.

When matter is **solid** the molecules of which it is composed are supposed to be large and close together. When in the state of vapour or **gas**, these molecules are smaller and much further apart.

Solid, liquid, or densely gaseous matter, when its molecules are agitated by heat, gives a continuous spectrum. Gaseous and vaporous matters, when their molecules are agitated at lower pressures or higher temperatures by heat or electricity, give a discontinuous spectrum consisting of bands or lines.

Between those extremes we have, as a rule, three other intermediate kinds of spectra: first, a continuous spectrum in the red; next, a continuous spectrum in the blue; next, a fluted spectrum, and after that the line spectrum already mentioned.

In all those kinds of spectrum, however, we are supposing that the elementary molecules are still intact, they are only more or less separated.

Compound bodies, like simple bodies, give definite spectra. The spectrum of a simple metal consists of lines which increase in number and thickness as the pressure of the vapour or its quantity in a given space is increased. The spectrum of a compound body consists chiefly of channelled spaces and bands which increase in the same manner. The greater the number of molecules in a cubic inch or cubic millimetre, and the more violently they are agitated, the more complex is the spectrum until it becomes continuous.

The smaller the number of molecules in a given space, the more simple is the spectrum, which then consists of a few lines only.

When a compound is exposed to heat, so as to dissociate it into its component parts the spectroscopic bands characteristic of the compound become thinner, and the lines of the metal increase in number, as shown in the accompanying diagram where the bands exhibited by calcium chloride in the flame of a Bunsen's burner, disappear, and are replaced by lines only, when an electric spark is used. When an element is treated with more and more heat and electricity it likewise gives exactly the same kind of evidence of dissociation—



FIG. 1.—Spectrum of calcium chloride. (1) In the flame of a Bunsen's burner, showing the channelled spaces and bands of a compound. (2) In an electric spark, showing the lines of the element calcium. (After Roscoe.)

bands disappearing, and lines becoming thinner. Besides this, new lines make their appearance with every large increase of temperature.

[1] According to another hypothesis, bodies are supposed to have molecules of one degree of complexity, and the difference between solid, liquid, and gaseous bodies is supposed to depend on the difference in the free path of the molecule. But according to the new view, the difference in the complexity of the molecule itself is sufficient to explain the phenomena.

This behaviour of the element appears to show that it also is a compound, but that it is stable under ordinary conditions, and is only dissociated at a high temperature.

Other proofs of this hypothesis are derived from a comparison of the spectra of the elements as observed in our laboratories with their spectra in the sun.

A comparison of the two hypotheses shows us that as on the old hypothesis each element represents a species and is unvariable, its spectrum ought to be always the same in our laboratories and in the sun : and the same in sun-spots as in prominences, and the same at all periods of the sun's activity.

Under the new hypothesis the spectra of metals in our laboratories and in the sun should not resemble each other ; they should be different in sun-spots and in prominences, because the spot is cooler than the prominence ; and they should vary at the time of the sun's activity because the sun is hotter at the maximum of the sun-spot period, and therefore there should be a greater amount of dissociation amongst the elements at that period.

As a matter of fact we find that the spectra in our laboratories and in the sun do not resemble each other (Fig. 2); that those of the same element



FIG. 2.—Diagram of the spectrum of lithium under various conditions of temperature (after Lockyer, *Roy. Soc. Proc.* Dec. 12, 1878).

in the sun-spot and prominences are as dissimilar as of any two elements ; and that the spectra of the elements in the sun do vary with the maximum of the sun-spot period.

On the old hypothesis the spectra of prominences should also consist of lines familiar to us in our laboratories, because solar and terrestrial elements are the same, while, according to the new hypothesis the spectra of prominences should be unfamiliar, because the prominences represent outpourings from a body hot enough to prevent the atoms of which our elements are composed from coming together.

As a matter of fact, the lines in the prominences, with the exception of those of hydrogen, magnesium, calcium, and sodium, are either of unknown origin, or are feeble lines in the spectra of known elements. Spectroscopic observation, therefore, leads to the belief that the so-called elements are really compounds, the component parts of which are kept apart by high temperatures in the sun and stars, but unite when the temperature decreases.

By the powerful vibrations imparted to them by the electric spark, they may be dissociated in the laboratory, but, as no means has yet been devised of separating the components, they again unite to form the original body, just as hydrogen and oxygen, into which steam is dissociated by passing it through a strongly heated tube, almost instantly again combine to form water unless they are separated by means of the more rapid diffusion of hydrogen through a porous tube.

The difficulty in accepting this evidence lies in the fact that we have hitherto been unable to isolate the substances into which the elements are supposed to be dissociated ; as these after their dissociation at once recombine and again form the original substance.

One proof, however, that the supposed components of the element calcium may remain permanently separated, is afforded by the fact that in the spectra of two stars, Sirius (Fig. 3) and α Lyræ, which are very bright, and probably very hot, only one of the ultra-violet lines of calcium is represented.

But we have also other evidence of the compound nature of the elements, which, although it was not sufficient of itself to force us to abandon our old

ideas of their simple nature, is yet strongly corroborative of the spectroscopic evidence. Thus we find that oxygen is broken up by electricity, and that the atoms of which its molecules are composed, rearrange themselves so as to form what is to all intents and purposes a new element, ozone, having a much closer resemblance to chlorine than to oxygen in its activity, although its compounds with metals appear to be identical with those of oxygen.



FIG. 3.—Diagram of the spectrum of calcium under various conditions of temperature. In the spectrum of Sirius the line K is absent, while it is very strongly marked in the solar spectrum.

At a high temperature its atoms are again dissociated, and recombine to form ordinary oxygen. When it combines with other substances, the heat of combination appears to be sufficient to dissociate the atoms of ozone (O_3), so that in the compound we meet with simple oxygen, O.

Phosphorus also affords us an example of an element which occurs in two forms, so different that we should call them distinct bodies, were it not that we find that one can be transformed into the other.

The two forms, red and yellow phosphorus, differ from each other, not only in their colour, but in their density, specific heat, readiness of combustion, and heat of combustion. They differ also in the yellow phosphorus being exceedingly poisonous, whereas the red phosphorus is not poisonous.

They are in many respects, then, different bodies, but we have hitherto been content to call them allotropic forms of the same element.

In combination we find that phosphorus is sometimes *pentad* and sometimes *triad;* that its compounds with oxygen are sometimes poisonous, at other times not. Thus orthophosphoric acid, H_3PO_4, is not poisonous; pyrophosphoric acid, $H_4P_2O_7$, and metaphosphoric acid, HPO_3, are both poisonous.

The most striking example, however, is carbon, which we not only find in three forms, differing enormously from each other, as diamond, charcoal, and graphite, but which we find in various compounds playing the most varied parts. This we at present explain by saying that carbon unites with itself in the formation of the various radicals; and thus comes to form what are practically new elements.

Another example is afforded us by ammonia, the salts of which are just as well characterised as those of potash or soda. The amalgam which it forms with mercury possibly indicates that we have in it also a real metal, ammonium, corresponding to sodium or potassium, though this is uncertain.

The three metals, sodium, potassium, and ammonium (if it exist), agree in the readiness with which they are oxidised, so that it is difficult to preserve the pure metal, although the oxide is stable. They differ, however, in the oxides of potassium and sodium being solid, and that of ammonium gaseous. Ammonium has not been isolated, and it is put down in the text-books as a hypothetical substance, but ammonium salts are tangible enough, and the question which we have to keep before us is, whether potassium, sodium, and all the other so-called elements, are not in reality compounds like ammonium.

Some people still regard species as immutable, and look upon Darwin's hypothesis of evolution as unproven.

The evidence in favour of the evolution of elements from one simple form of matter, is as yet, perhaps, much less strong than that in support of the evolution of species; but it has this advantage, that it explains certain phenomena which have hitherto been very perplexing.

It may be at least convenient in discussing the physiological action of drugs to bear this hypothesis in mind, and to remember that what we have hitherto been accustomed to call elements, may be really like the so-called organic radicals in constitution, with this difference, that we can split up

organic radicals with tolerable facility, while we cannot do this—at least to any great extent—with elements.

It also shows us that we must as pharmacologists pay attention to molecular as well as to empirical composition and take into consideration crystalline form and physical aggregation in all observations regarding the relations between elements or compounds and living organisms. It is not sufficient for example to speak of the action of phosphorus on the organism as if this were invariable, for it varies with the molecular composition of the body in the red or yellow form, and isomeric organic substances may be utterly different in action.

Classification of the Elements.

THE vegetable and animal kingdoms are divided into various groups. Formerly, men tried to arrange them in linear succession so that there should be an unbroken line from the lowest to the highest members of the vegetable kingdom, thence to the lowest member of the animal, and onwards up to the highest member of the animal kingdom. Such an arrangement as this, however, was found to be unnatural. Instead of the highest members of the vegetable kingdom being connected with the lowest members of the animal kingdom, it is found that the lowest members of each kingdom are closely connected, and that the divergence becomes greater as development proceeds towards the highest members in each kingdom. The doctrine of **evolution** at once rendered this arrangement natural and easily understood.

Starting from one common point of origin in structureless protoplasm, the various organisms became more and more unlike in each successive stage of development, their resemblance being at all only recognisable in their embryonic condition.

Various attempts have been made to arrange inorganic substances in natural orders. One mode of **arrangement** is according to their **atomic weight**—as in the following table :—

Element.	Atomic Weight.	Difference.	Element.	Atomic Weight.	Difference.	Element.	Atomic Weight.	Difference.	Element.	Atomic Weight.	Difference.
H	1		Ca	40	1	Ce	92	2·5	V	137	0
Li	7	6	Ti	50	10	La	92	0	Ta	138	1
G or Be	9	2	Cr	52·5	2·5	Di	96	4	W	184	46
			Mn	55	2·5	Mo	96	0	Nb	195	11
B	11	2	Fe	56	1	Ro	104	8	Au	196	1
C	12	1	Co	58·5	2·5	Ru	104	0	Pt	197	1
N	14	2	Ni	58·5	0	Pd	106·5	2 5	Ir	197	0
O	16	2	Cu	63·5	5	Ag	108	1·5	Os	199	2
Fl	19	3	Y	64	0·5	Cd	112	4	Hg	200	1
Na	23	4	Zn	65	1	Sn	118	6	Tl	203	3
Mg	24	1	As	75	10	U	120	2	Pb	207	4
Al	27·5	3·5	Se	79·5	4·5	Sb	122	2	Bi	210	3
Si	28	0·5	Br	80	0·5	I	127	5	Th	238	28
P	31	3	Rb	85	5	Te	129	2			
S	32	1	Sr	87·5	2·5	Cs	133	4			
Cl	35·5	3·5	Zr	89·5	2	Ba	137	4			
K	39	3·5									

From this it will be seen that the atomic weights of the different elements form a series, the members of which in most cases differ from one another by 1, 2, 3, or 4. There are a few exceptions in which the differences are much greater, and these probably represent blanks which may yet be filled up as our

knowledge of the elements increases. This mode of classification, however, reminds us of the Linnæan system in plants, and is artificial rather than natural. In it, the elements which are placed close together possess very different properties, whereas those which are separated from each other present considerable resemblances.

The first important attempt at a **natural classification** of the elements was made by Newlands in 1864.[1] He then arranged them in **groups**, between the members of which there was a close connection in regard to their chemical properties, and a curious relation in regard to their atomic weights. These presented differences which were generally multiples of the atomic weight of hydrogen, and generally equal to, or multiples of, that of oxygen.

Member of a Group having Lowest Equivalent.		One immediately above the preceding.		Difference. H = I.	Difference. O = I.
Magnesium	24	Calcium	40	16	1
Oxygen	16	Sulphur	32	16	1
Lithium	7	Sodium	23	16	1
Carbon	12	Silicon	28	16	1
Fluorine	19	Chlorine	35·5	16·5	1·031
Nitrogen	14	Phosphorus	31	17	1·062
Lowest term of Triad.		**Highest term of Triad.**			
Lithium	7	Potassium	39	32	2
Magnesium	24	Cadmium	112	88	5·5
Molybdenum	96	Tungsten	184	88	5·5
Phosphorus	31	Antimony	122	91	5·687
Chlorine	35·5	Iodine	127	91·5	5·718
Potassium	39	Cæsium	133	94	5·875
Sulphur	32	Tellurium	129	97	6·062
Calcium	40	Barium	137	97	6·062

A curious relationship had also been pointed out by M. Dumas[2] between the members of the potassium group, their atomic weights being equal to multiples of those of lithium and potassium added together.

Li + K = 2Na, or in figures, 7 + 39 = 46
Li + 2K = Rb ,, ,, 7 + 78 = 85
2Li + 3K = Cs ,, ,, 14 + 117 = 131
Li + 5K = Tl ,, ,, 7 + 195 = 202
3Li + 5K = 2Ag ,, ,, 21 + 195 = 216

A similar relation was also pointed out by Mr. Newlands between lithium and the calcium group; as follows:—

Li + Ca = 2Mg, or in figures, 7 + 40 = 47
Li + 2Ca = Sr ,, ,, 7 + 80 = 87
2Li + 3Ca = Ba ,, ,, 14 + 120 = 134
Li + 5Ca = Pb ,, ,, 7 + 200 = 207

[1] Newlands, *Chemical News*, July 30, 1864.
[2] Dumas, quoted by Newlands, *op. cit.*

But Mr. Newlands's most important table is the following one, in which he has arranged the elements in ten **series**:—

			Triad.			
			Lowest term.	Mean.	Highest term.	
I		Li 7	+ 17 = Mg 24	Zn 65	Cd 112	
II.		B 11				Au 196
III.		C 12	+ 16 = Si 28		Sn 118	
IV.		N 14	+ 17 = P 31	As 75	Sb 122	+ 88 = Bi 210
V.		O 16	+ 16 = S 32	Se 79·5	Te 129	+ 70 = Os 199
VI.		F 19	+ 16·5 = Cl 35·5	Br 80	T 127	
VII.	Li 7	+ 16 = Na 23	+ 16 = K 39	Rb 85	Cs 133	+ 70 = Tl 203
VIII.	Li 7	+ 17 = Mg 24	+ 16 = Ca 40	Sr 87·5	Ba 137	+ 70 = Pb 207
IX.			Mo 96	V 137	W 184	
X.			Pd 106·5		Pt 197	

Seven of these series nearly correspond in their first members with those of Mendelejeff, to whom and to Lothar Meyer we owe the complete development of this mode of classification. Mr. Newlands also pointed out that the eighth element starting from a given one, was a kind of repetition of the first, like the eighth note of an octave in music.[1]

Mendelejeff has not only greatly developed this system of classification, but has afforded convincing proof of its value by not only predicting the existence of an unknown element, but actually describing its physical characters and chemical reactions—a prediction the correctness of which was proved by the discovery of gallium, and by the agreement of its characters and reactions with those which Mendelejeff had foretold.

The various members of the animal kingdom can all be arranged in a few series: Protozoa, Coelenterata, Annuloida, Annulosa, Molluscoida, Mollusca, and Vertebrata. These series all differ more or less from one another, but a certain agreement is observed between their members, and similarly the **elements** may be arranged in **series.**

Mendelejeff points out, that if we take those elements having the lowest atomic weight, and omit hydrogen, between which and lithium there is a great gap, the seven elements, lithium, glucinum, boron, carbon, nitrogen, oxygen, and fluorine, may be regarded as typical elements forming a series representing the lowest members of seven groups. The next seven elements may be arranged in a similar way:—

Li = 7 : G = 9·4 : B = 11 : C = 12 : N = 14 : O = 16 F = 19
Na = 23 : Mg = 24 : Al = 27·3 : Si = 28 : P = 31 : S = 32 : Cl = 35·5

To each group of seven elements Mendelejeff gives the name of a **small period** or **series.** In each series the characters of the elements vary gradually and regularly as their atomic weights increase. This variation is periodical, *i.e.* varies in the same way in each series, so that the elements which have corresponding places in each series, correspond also to a certain extent in their properties, and form similar compounds. The atomicity is least in the first, and greatest in the last members of each series. Thus the first members of the series form monochlorides, the second dichlorides, the third trichlorides, and so on.

In the accompanying table R represents radical or element, and R^{i} indicates that the element is monatomic, so that one atom combines with one of Cl to form a monochloride, RCl. R^{ii} indicates that the element is diatomic, and so on.

[1] *Chem. News*, Aug. 20th, 1864, p. 94.

MENDELEJEFF'S CLASSIFICATION OF THE ELEMENTS.

Series.	Group I. $R^{i}_{2}O$ $R^{i}Cl$	Group II. $R^{ii}O$ $R^{ii}Cl_{2}$	Group III. $R^{iii}_{2}O_{3}$ $R^{iii}Cl_{3}$	Group IV. $R^{iv}H_{4}$ $R^{iv}O_{2}$ $R^{iv}Cl_{4}$	Group V. $R^{v}H_{3}$ $R^{v}_{2}O_{5}$ $R^{v}Cl_{5}$	Group VI. $R^{vi}H_{2}$ $R^{vi}O_{3}$ $R^{vi}Cl_{6}$	Group VII. $R^{vii}H$ $R^{vii}_{2}O_{7}$ $R^{vii}Cl_{7}$	Group VIII. —— $R^{viii}O_{4}$ $R^{viii}Cl_{8}$
1	H = 1							
2	Li = 7	G or Be = 9·4	B = 11	C = 12	N = 14	O = 16	F = 19	
3	Na = 23	Mg = 24	Al = 27·3	Si = 28	P = 31	S = 32	Cl = 35·5	
4	K = 39	Ca = 40	— = 44	Ti = 48	V = 51	Cr = 52	Mn = 55	Fe = 56 Co = 54 Ni = 59 Cu* = 63
5	(Cu* = 63)	Zn = 65	—† = 68	— = 72	As = 75	Se = 78	Br = 80	
6	Rb = 85	Sr = 87.	? Yt = 88	Zr = 90	Nb = 94	Mo = 96	— = 100	Ru = 104 Rh = 104 Pd = 106 Ag* = 108
7	(Ag* = 108)	Cd = 112	In = 113	Sn = 118	Sb = 122	Te = 125	I = 127	
8	Cs = 133	Ba = 137	? Di = 138	? Ce = 140	—	—	—	— — — —
9	(—)	—	—	—	—	—	—	
10	(—)	—	? Er = 178	? La = 180	Ta = 182	W = 184	—	Os = 195 Ir = 197 Pt = 198 Au* = 199
11	(Au* = 199)	Hg = 200	Tl = 204	Pb = 207	Bi = 208	—	—	
12	—	—	—	Th = 231	—	U = 240	—	—

* Cu, Ag, and Au are included in Group I. on account of their forming cuprous, argentous, and aurous oxides, but on account of their resemblance in many respects to the metals in Group VIII. they are also included in it.

† This blank has now been filled up by the discovery of Gallium.

But a difference is to be observed between the even and the uneven series. Corresponding members of even series, such as the fourth and sixth, agree with each other, and members of uneven series like the fifth and seventh agree. This agreement is greater than between the members of an even series, such as the fourth, and those of an uneven series like the fifth, although the fifth is more closely placed to the fourth than the sixth is. Thus Ca and Sr belonging to the fourth and sixth series have a greater resemblance to each other than they have to Zn or Cd, which belong to the fifth and seventh series, and these metals on the other hand have a greater resemblance to each other than they have to Ca or Sr. The members of even series are less metalloidal or more metallic than those of uneven series, *e.g.* Mn of the fourth series is less metalloidal than Br of the fifth series. In the even series the metallic or basic character predominates, whilst the corresponding members of the uneven series rather exhibit acid properties. The members of the even series, so far as we know, form no volatile compounds with hydrogen or alcohol radicals, while the corresponding members of the uneven series do form such compounds.

The last members of the even series resemble in many respects (in their lower oxides, etc.), the first members of the uneven series, thus chromium and manganese in their basic oxides are analogous to copper and zinc. But there are great differences between the last members of the uneven series (haloids), and the first members of the next even series (alkali metals). Now between the last members of the even series there occur, according to the order of atomic weights, all those elements which cannot be included in the small periods. Thus between Cr and Mn in the one series, and Cu and Zn in the next, there come the elements Fe, Co, Ni, and in a similar way after the sixth series come Ru, Rh, Pd, and after the tenth Os, Ir, Pt. Mendelejeff gives the name of a **long period** to two such series with three intervening members, forming seventeen in all.

From the difficulty of arranging all the elements in this system, it cannot be regarded as yet perfect, but the fact that Mendelejeff was able so correctly to foretell the properties of gallium, shows that it must contain a large element of truth. At the time that he drew up his table there was a blank in the third group of the fifth series.

The relationships of the metal which Mendelejeff believed would fill this gap will be more easily seen by omitting the even series on either side of it, and taking only the odd series with which it will, as already mentioned the more closely correspond.

Series.	Group II.	Group III.	Group IV.	Group V.
3	Mg	Al	Si	P
5	Zn	—	—	As
7	Cd	In	Sn	Sb

As it stands between zinc with an atomic weight of sixty-five, and arsenic with one of seventy-five, while it is separated from the latter by a blank, its atomic weight must be about sixty-eight. As it is atom-analogous with Al, its salts should have a similar constitution. It should form an oxide x_2O_3, and a sulphide x_2S_3. It will be precipitated from its solution by ammonium sulphide. The metal should be easily reduced by carbon or sodium, it should have a specific gravity of 5·9, and decompose water at a red heat. As it belongs to an odd series, it should, like zinc, form volatile compounds with organic radicals, and form also anhydrous chlorides.

On the discovery of the metal gallium, it was found to agree in almost every respect with the prediction of Mendelejeff, and this fact is not interesting to chemists only, but also to pharmacologists. For the great **object of pharmacology** is to obtain such a knowledge of the relations between the physical and chemical characters of bodies, and their actions upon the living organism, that we may be able to predict their **actions** with certainty, and to know

the modifications which alterations in their physical and chemical characters will produce on their physiological action.

Mendelejeff's present classification is imperfect, because we find that by it the members of some natural groups, such as those of the earthy metals, are separated from one another, although they agree in their chemical characters.

We find also that metals having similar pharmacological actions, as copper, zinc and silver, do not fall naturally together in this arrangement. But, on the other hand, we find also that by this classification, elements are brought together which do not at first seem to have any resemblance to each other, and are yet found by recent investigations to have a physiological connection. Thus mercury and calcium do not appear to resemble one another, yet Prevost has shown that in acute poisoning by mercury, the calcareous matter disappears from the bones, and in the process of elimination by the kidneys produces calcification of these organs.[1]

Organic Radicals.—Whether the so-called elements be compounds or not, it is certain that several of them have the power of uniting with themselves and with others in such a way as to form bodies called compound radicals which resemble elements in many respects. These groups of atoms may enter into and again pass out of combination with other substances just as elements do. These radicals are not known in the free state. The chief of them are hydroxyl, OH, from which may be formed, by replacement of the hydrogen, potassoxyl, KO, and zincoxyl, OZnO; amidogen, NH_2; imidogen, NH; nitroxyl, NO_2; sulphuryl, SO_2; and phosphoryl, PO. Then come innumerable compounds of carbon, among which may be mentioned cyanogen, CN; the radicals of the marsh-gas series, methyl, CH_3, etc.; carbonyl, CO; carboxyl, $\left.\begin{matrix}CO\\H\end{matrix}\right\}O$, important in the formation of acids, &c.

Chemical Reactions and Physiological Reactions.—Each element and each of its compounds has chemical reactions special to itself, by which it can be recognised and distinguished from all others. The number of these chemical reactions is therefore very great, but there are a few reactions which are common to a great number of the elements. We shall find that something similar occurs in their physiological reactions.

The number of possible actions which may be exerted on the body by the elements and their compounds is very great, yet we shall find that there are certain physiological reactions which are common to so many that their repetition under the head of each drug becomes monotonous.

Varied as the **chemical reactions** of the metallic elements are, we find that they can be at once divided into two groups by the use of hydrogen sulphide or ammonium sulphide, for all of them, with the exception of ammonium, lithium, potassium, sodium, magnesium, barium, calcium, and strontium, are precipitated by one or other of these reagents. These groups can be subdivided

[1] Prevost, *Revue Médicale de la Suisse Romande*, p. 553, Nov. 15th; p. 605, Dec. 15th, 1882; p. 5, Jan. 15th, 1883.

by the use of other reagents into sub-groups. The small group, already mentioned, which is not precipitated either by hydrogen sulphide or ammonium sulphide, can be divided into two sub-groups by the use of carbonate of ammonia, which precipitates barium, calcium, and strontium, and does not precipitate the others.

The other large group, which is precipitated by H_2S or $(NH_4)HS$, can also be subdivided in a similar manner.

The individual members of each sub-group, again, can all be distinguished from one another by further reactions.

The **physiological reactions** which occur between the elements or other compounds and the tissues of the body can also be divided into large **groups.**

Thus we find that a very great number of substances, when used in large quantity, paralyse muscles and motor nerves. This large group can again be subdivided into those which paralyse muscle, while affecting the nerves but slightly, or those which paralyse the nerves and leave muscle uninjured.

Another large group is that which acts specially on nerve-centres, and has little effect either on muscles or motor nerves. This contains sub-groups of substances which affect the brain, medulla, or spinal cord by exciting, paralysing, or disturbing the functions.

Another group is that which affects the secretions, with sub-groups of substances affecting the secretions from the sweat and mammary glands, salivary, gastric, or intestinal glands, liver, or kidneys.

Another group still is that which acts chiefly upon the circulation.

These groups are all more or less distinct, although they, to a certain extent, may run into, or overlap, each other.

Individual members of the same group may differ very widely, in their physiological action, even when they all finally paralyse muscle, nerves, and nerve-centres. For while they may produce the same final result, the course of their action will be different, and the symptoms they occasion will depend very greatly upon the part of the organism which they affect first. Thus atropia and curare both completely paralyse motor or efferent nerves, but, while a very large dose of curare is required to paralyse the cardiac and vascular nerves, a very small dose paralyses those going to the muscles, and produces increasing weakness, gradually passing into death. On the other hand, an enormous dose of atropine is required to paralyse the motor nerves of muscles, but very small doses are sufficient to affect the nerves of the heart and other involuntary muscles, and thus we get rapid circulation, dilated pupil, and restless delirium.

The physiological action of any drug depends to a great extent, not merely on its general affinities for classes of tissues,

but upon its particular affinity, or power of acting on one tissue or organ first. The organ first affected may, through its functional activity, greatly alter the effects of the drug upon the others.

As an example of this we may take the effects produced by very large and by moderate doses of veratrine on the frog. A moderate dose will produce great stiffness of the muscles, while a very large dose may have comparatively little effect. Yet if the large dose were applied directly to the muscles it would act more powerfully than the moderate dose. The reason that it does not do so in the living body is that the large dose paralyses the heart so quickly that the circulation stops, and therefore the poison, not being conveyed to them, has no action on the muscles.

Relation between Atomic Weight and Physiological Action.

As long ago as 1841, Blake thought that the toxic action of inorganic substances increased in proportion to their atomic weight, and this idea was again advanced by Rabuteau. Both of them afterwards qualified this when they found it was incorrect, by saying that the poisonous action increased with the atomic weight amongst elements belonging to the same group. Thus potassium is more poisonous than sodium, and barium than calcium. But it has been shown by Husemann that lithium is much more poisonous than sodium or potassium, and his results have been confirmed by Richet. It is evident that the relationship between atomic weight and physiological action is no simple one. But indeed, on looking into the matter more closely, we could hardly expect it would be. For the toxic action of an element may depend upon its effect on the muscles, nerves, nerve centres, blood, or on the digestive or excreting systems. These differ from one another in their composition, and while it is possible that the elements belonging to a certain group may have relations varying with their atomic weight to individual organs or structures, we can hardly expect those relationships to be the same to all organs.

Thus an element with one atomic weight may prove fatal, by affecting the muscular power of an animal, while another with an atomic weight either higher or lower, may be still more deadly by affecting the nervous system or heart.

What we want, therefore, is not a general relationship between atomic weight and toxic action, but a knowledge of the particular relationships of each group of elements to each organ and tissue of the body.

Relation between Spectroscopic Characters and Physiological Action.

The quickness with which a pendulum oscillates is greater or less in proportion to its length, a long one oscillating slowly, and a short one quickly. The vibrations of a string or pipe are also slow or quick, and the note which it yields is low or high, according as it is long or short.

Similarly, according to Lecoq de Boisbaudran, the rate of vibrations of molecules, and the wave-lengths of the light which they emit, are determined by their weight. When the molecular weight is high, the vibrations of the molecules are slow, and the light which they emit has long wave-lengths, and is situated towards the red end of the spectrum. When the weight is low the vibration of the molecules is rapid ; and the light they emit lies towards the violet end of the spectrum.

In the same family of elements the mean length of the wave of light which they emit is a function of their atomic weight, so that for bodies of the same chemical type the general form of the spectrum persists, but is gradually modified by the mass of the molecules. As the atomic weight diminishes, the spectrum will tend to ascend towards the violet, and, as it increases, the spectrum will tend to descend towards the red.

Until recently, our observations on the spectra of bodies were limited to the visible spectrum, but the application of photography now enables us to extend our observations both above and below the visible spectrum, and to ascertain the presence of definite spectra in the ultra red and ultra violet, when nothing of the sort is visible to the eye. In most musical sounds besides the fundamental note we have a number of harmonics having a much greater rapidity of vibration than it. Similarly, in the spectrum there appear harmonics as well as the fundamental spectral lines, and so instead of one line or band there may be a number. According to the author already quoted, the corresponding harmonies in a series of analogous spectra have mean wave lengths which increase in proportion to the weight of the molecules.

It might appear therefore, that a relation might be observed between the spectroscopic characters and physiological action of an element, and this idea was propounded by Papillon. His idea was, however, to a great extent based on the experiments of Rabuteau already alluded to, and just as no definite relation can be at present traced between the atomic weight and the toxic action of a metal, so no definite relation can be observed between its spectroscopic characters and its physiological action.

Further consideration, however, will show us that this is not at all to be wondered at, for in physiological experiments we are not working with the same molecules which yield the spectrum.

In spectral analysis, when line spectra are in question, according to one view we are in presence of phenomena produced by the chemical atom, whereas this atom exists only molecularly combined at lower temperatures. According to another view, that put forward by Lockyer, we are in presence of phenomena produced by a series, possibly a long series, of simplifications, brought about by the temperature employed, and this simplification can begin at very low temperatures, and is indeed indicated by Dalton's law of multiple proportions.

Such molecular simplifications and differences are represented by ozone and oxygen, ordinary and amorphous phosphorus, the various forms of sulphur and so on, and it is therefore at this lower range of temperature—one studied, chiefly by absorption, and not by radiation—that we must look for connections between molecular structure and physiological action if any such connection exists.

Some of the absorption bands which occur in the spectra of bodies at ordinary temperatures may be in the visible spectrum, like those observed in alcoholic and aromatic substances ;[1] but others may be quite invisible, and only recognisable by the aid of photography in the ultra-red or ultra-violet.[2]

Connection between Chemical Constitution and Physiological Action.—It has long been known that **different metals** exercise **different actions** on the body ; that mercury, for example, causes salivation, and antimony sickness. But an immense step has been made of late years in our knowledge of the relation between chemical constitution and physiological action by the discoveries of Crum-Brown, Fraser, and Schroff, who have shown that by modifying artificially the chemical constitution of a drug,

[1] Russell and Lapraik, *Journ. Chem. Soc.* April, 1881.
[2] Abney and Festing, *Phil. Trans.* 1882, p. 887.

it is possible to modify also its physiological action. And not only so, but they have shown that similar modifications in the chemical constitution of various drugs induce similar modifications in the action of their derivatives; thus they have found that by introducing methyl into the molecule of strychnine, brucine, and thebaine, the convulsive action exerted by these substances on the spinal cord was changed into a paralysing one exerted on the ends of the motor nerves. Other alkaloids, also, which do not exhibit a convulsive action, nevertheless exhibit a paralysing one when their constitution is altered by means of methyl; thus methyl-codine, methyl-morphine, methyl-nicotine, methyl-atropine, methyl-quinine, methyl-veratrine, and several others, all exhibit this paralysing action.

From a number of experiments on this subject by Cash and myself, we find as a general rule that most of the compound radicals formed by the union of amidogen with the radicals of the marsh-gas series possess a paralysing action on motor nerves.

The subject of the connection between chemical constitution and physiological action is the most important one in pharmacology, and we shall have to return to it in considering the actions of various groups of organic substances.

Relation between Isomorphism and Physiological Action.—From a number of experiments made by Dr. Blake, he concluded that when inorganic salts were injected directly into the circulation, the intensity of their physiological action increased in proportion to their molecular weight, but only in those groups of elements where the salts were isomorphic, or, in other words, crystallised in the same forms. Thus groups whose salts were crystallised in different forms had quite different physiological actions. He divided the elements into nine groups, the physiological action of the different groups differing in kind, whilst that of the individual members of the same group agree in kind but differ in degree. Thus he states[1] that the salts of the first group increase in activity in the order mentioned, silver being the most active, and lithium the least.

These groups are as follows:—

Group 1. Lithium, sodium, rubidium, thallium, cæsium and silver According to him they produce death by acting on the lungs and impeding the pulmonary circulation. None of them affect the nervous system excepting cæsium; nor do any affect the pulmonary circulation excepting silver.

Group 2. Magnesia, ferrous salts, manganous salts, nickel, cobalt, copper, zinc and cadmium, are increasingly lethal in the order mentioned. They kill by arresting the action of the heart.

Group 3. Beryllium, alumina, yttria, cerium and ferric salts both impede the systemic and pulmonary circulation.

Group 4. Calcium, strontium, barium, and lead salts kill by paralysing the ventricles of the heart.

[1] Blake, *American Journal of Science and Arts*, vol. vii. March, 1874 (corrected reprint).

Group 5. Palladium, platinum, osmium, and iridium act on the heart, respiration, circulation, and blood.

Group 6. Ammonia and potash paralyse the heart and cause convulsions.

Group 7. Hydrochloric, hydriodic, bromic, and iodic acids impede the circulation and kill by arresting the circulation.

Group 8. Phosphoric acid, arsenic acid, and antimony kill by arresting the pulmonary circulation.

Group 9. Sulphuric and selenic acid impede the pulmonary circulation.

These experiments are open to the same objections as those of Rabuteau. The author's statements regarding their mode of action, show that their physiological action has not been clearly investigated, and his results as to the lethal dose are probably only approximate and may want reinvestigation; but while we cannot accept at present all his results or conclusions as final, yet his last and chief conclusion is one of great interest, viz.:—that in living matter we possess a reagent capable of aiding us in our investigations on the molecular properties of substances.

CHAPTER II.

CIRCUMSTANCES WHICH AFFECT THE ACTION OF DRUGS ON THE ORGANISM.

The Inter-action of various functions in the body is one of the greatest difficulties in the way of our readily understanding the action of drugs.

One function alters another, and the second reacts upon the first, so that in some cases it is almost impossible to say precisely how far the alteration in any function is due to the direct effect of the drug upon it, and how far to some indirect action. Thus curare when applied to a wound usually kills without producing any convulsion whatever. It paralyses the ends of the motor nerves, so that all the muscles in the body become powerless. But when it is given by the stomach, and excretion through the kidneys prevented, death is preceded by convulsions. These convulsions are not caused by any direct irritating action of the curare itself upon the nerve-centres, they are due to irritation of these centres by a venous condition of the blood. This venosity of the blood is due to imperfect respiration, produced by paralysis of the respiratory muscles through the action of curare on the motor nerves.[1]

The effect of curare is a purely paralysing one, both when the animal dies quietly and when it dies with convulsions. In both cases it paralyses the motor nerves of the respiratory muscles and of the extremities. In both cases it causes death by arresting the respiration and producing asphyxia. But in the latter case the motor nerves of the extremities being only partially paralysed when asphyxia occurs, they respond by convulsive movements to the irritation of the nerve-centres, which the venous blood produces. In the former, the paralysis of the limbs being complete, the muscles remain perfectly quiet, notwithstanding the irritation of the nerve-centres.

Convulsions also sometimes occur previous to death from narcotic poisons; and in a description of the action of these poisons we frequently meet with the phrase, "coma, convulsions,

[1] Hermann, *Arch. f. Anat. u. Physiol.* 1867, 64, 650.

and death." In such cases the convulsions are also caused by the irritation of the nerve-centres by asphyxial blood.

The drug causes the coma; the coma causes imperfect respiration; imperfect respiration renders the blood venous; and the venous blood causes convulsions.

Direct and Indirect Action.—The **direct** action of a drug is the effect it produces on any organ with which it comes in contact. Thus sulphuric acid applied to the skin, or taken into the stomach, will, according to its degree of concentration, irritate or destroy the mucous membrane which it touches. Its *direct* action upon them is therefore that of an irritant or caustic.

Curare, when applied to the ends of a motor nerve in a muscle, paralyses them. It does this either when the muscle is soaked in a solution of curare, or when the curare is carried through the substance of the muscle by means of the blood circulating in it.

Paralysis is therefore the direct effect of curare on the motor nerves.

Indirect Action.—The convulsions which sometimes occur in poisoning by curare are caused by its *indirect* action. It has no stimulating effect on the nerve-centres, when applied to them directly or carried to them by the blood, but by paralysing the muscles of respiration, and thus causing asphyxia, it indirectly irritates the nerve-centres and causes convulsions.

Local and **Remote Action.**—The **local** action of a drug is that which it exerts on the part to which it is applied. Thus sulphuric acid has a direct irritant or destructive action, and when applied to the skin or mucous membrane will produce local redness, inflammation, or sloughing. When swallowed, it produces weakness of the circulation, stoppage of the heart, and death.

This effect on the circulation is not due to the direct action of the acid upon the heart, the vessels, or the nervous system, after its absorption: it is due to the reflex action exerted upon them by the irritation of the nerves of the stomach which the sulphuric acid produces. This action on different parts through the nervous system is termed its **remote** action, in contradistinction to the local action of the acid upon the gastric mucous membrane.

Relation of Effect to Quantity of the Drug.—The effect of drugs varies very much according to the quantity employed. Sometimes this is due to the inter-action of different parts of the body on one another as already mentioned in regard to veratrine (page 21). Sometimes it is due to the different effects upon individual cells or tissues. Thus we find, very generally, that any substance or form of energy, whether it be acid or alkali, heat or electricity, which in moderate quantity increases the activity of cells, destroys it when excessive.

But varying doses do not always produce opposite effects. We sometimes find that exceedingly small and exceedingly large doses have a similar effect, which differs from that produced by

moderate doses. Thus very minute quantities of atropia render the pulse somewhat slow; larger quantities make it exceedingly rapid, and very large quantities again render it slow.

Moderate quantities of digitalis slow the pulse, larger quantities quicken it, and still larger quantities render it slow again. We find a similar effect produced by variation in temperature. Great cold disturbs the mental faculties, so that men exposed to it present symptoms which cannot be distinguished from those of intoxication. Ordinary temperatures do not disturb the functions of the brain, but high temperatures do, as we see in the delirium of fever, which in many cases immediately ceases when the temperature of the patient is reduced by cold baths.

Homœopathy.—This opposite action of large and small doses seems to be the basis of truth on which the doctrine of homœopathy has been founded. The irrational practice of giving infinitesimal doses has of course nothing to do with the principle of homœopathy—*similia similibus curantur:* the only requisite is that mentioned by Hippocrates, when he recommended mandrake in mania; viz. that the dose be smaller than would be sufficient to produce in a healthy man symptoms similar to those of the disease. Now in the case of some drugs this may be exactly equivalent to giving a drug which produces symptoms opposite to those of the disease; and then we can readily see the possibility of the morbid changes being counteracted by the action of the drug and benefit resulting from the treatment. For example, large doses of digitalis render the pulse extremely rapid, but moderate ones slow it.[1] The moderate administration, when there is a rapid pulse, is sometimes beneficial: this might be called *homœopathic* treatment, inasmuch as the dose administered is smaller than that which would make the pulse rapid in a healthy man, but it might also be called *antipathic,* inasmuch as the same dose administered to a healthy person would also slow the pulse.

Homœopathy can therefore not be looked upon as a universal rule of practice, and the adoption of any such empirical rule must certainly do harm by leading those who believe in it to rest content in ignorance instead of seeking after a system of rational therapeutics.

Dose.—The amount of a drug, which actually comes in contact with and affects the tissues, depends upon several conditions—(1) the **quantity** actually given; (2) its **proportion** to the body-weight; (3) the rapidity of its **absorption** by the blood from the place of introduction; (4) the condition of the **circulation** in various parts of the body, which determine the quantity of the drug carried to each; (5) the rate of its absorption by the **tissues;** (6) the rapidity of **excretion.**

The word **dose,** as employed in medicine, usually means the quantity given at one time, but sometimes this may be very

[1] *Vide* Traube, *Med. Centr. Ztg.* xxx. p. 94, 1861, and Brunton *On Digitalis,* p. 21.

different from what actually produces any effect. It is the amount of the drug existing in the blood at any given time, or rather the proportion of it that actually comes in contact with or is absorbed by the tissues, which really acts. We must therefore consider more in detail the circumstances which affect this proportion.

Size.—As the action which a drug has on the body is not dependent on its absolute amount, but on the proportion it bears to the body on which it is to act, an amount which is a small dose for one person is a very large one for another.[1] Thus if a grain of some active substance be injected at the same time into the veins of a full-grown man and into those of a boy of only half his weight, it will be distributed through twice as much blood in the man as in the boy, and each tissue will only receive half as much of it. The dose of a drug must therefore be regulated by the weight of the patient; and thus women, being lighter, require a smaller amount than men, and children less than adults. Though it would be more exact, it is not always convenient, to weigh patients; but in experiments on animals we usually weigh the animal carefully and describe the dose in terms of the body-weight. For example, in describing the lethal dose of physostigmia we do not say that it is so many grains for an animal, but that it is 0·04 grains per pound weight of a rabbit. This relation, however, is not always an exact one, and other circumstances must be taken into account. Thus the **species** of the animal must be considered, for the same dose which would kill one kind of animal will not kill another. In animals of the same species the state of **nutrition** must be taken into account, for two animals of the same species which would be nearly of the same size when equally nourished, may have very different weights if the one is fat and the other is lean. But the fat is a comparatively inner tissue, and if we give to each animal a dose regulated by its body-weight, the vital organs, brain, heart, and spinal cord of the fat animal will get a larger share in proportion than those of the lean one.

In testing the action of poisons on frogs, also, it must be remembered that a female frog with a quantity of spawn will be very heavy, but the spawn, like the fat, is not to be reckoned as tissue; and a dose given in proportion to the actual weight would be much larger than the same proportion given to the frog after spawning.

Mode of Administration.—If a substance be **injected** into the **veins,** the whole of it mixes with the blood and becomes active immediately, and the maximum effect is thus at once obtained and will again diminish as the substance is excreted. But the case is different if it be injected **subcutaneously,** and if it be given by the **stomach** or any other **mucous cavity** the difference is still greater; for as soon as some of it is absorbed excretion begins, and thus one portion of the drug is passing out of the

[1] Buchheim, *Arzneimittellehre*, 3rd edit. p. 54.

blood while another portion is being taken in. The amount in the blood is, then, only the difference between that absorbed and that excreted in a given time, and absorption may be so slow, or excretion so quick, that there is never a sufficient amount of the substance in the blood to produce any effect. Thus Bernard found that a dose of curare which would certainly paralyse an animal when injected into the veins, or even subcutaneously, would have no effect when introduced into the stomach;[1] and showed that this was due to the kidneys excreting the poison as fast as it was absorbed from the stomach, by extirpating the kidneys,[2] when the animal became paralysed as surely as if the poison had been introduced at once into the veins, though not so quickly. Hermann also discovered, without being acquainted with Bernard's observations, that curare taken into the stomach would produce paralysis if excretion were prevented by ligature of the renal vessels.



FIG. 3.—Diagram to illustrate absorption and excretion. The arrows show the direction of the currents. The absorbents from which the blood passes directly into the general circulation are represented diagrammatically by the veins of the lungs and of the general body surface in the figure. The absorbents by which the drug must pass through the liver, and possibly be partly excreted or destroyed, are represented by the veins of the stomach and intestine. The excreting channels by which the drug may pass directly from the body without re-absorption occurring are represented by the vessels of the lung and by the ureter. Those, by which excretion takes place into cavities from which much re-absorption may occur, are represented by the arteries to the intestine and the stomach.

The **absorption** of drugs from the stomach and intestines may be considerably retarded, and their action diminished, by the liver. Before reaching the general circulation, drugs absorbed from the intestinal canal must all pass through the liver (Fig. 3). In their passage they may be partly arrested and excreted again into the intestine along with the bile. They may be also partially destroyed. A larger quantity of a drug may thus be necessary to produce similar effects when introduced by the stomach than when injected directly into the circulation or under the skin, (1) because it may be absorbed more slowly by the vessels of

[1] Bernard, *Leçons sur les Effets des substances toxiques*, p. 282.
[2] Bernard, *Revue des Cours Scientifiques*, 1865.

the gastric or intestinal mucous membrane, (2) because a part of it may be arrested in the liver and excreted into the intestine along with the bile, (3) because a part of it may be actually destroyed in the liver.

The more rapid the absorption or the slower the excretion, of any drug, the greater will be its effect. Thus the effect produced by the same dose of a medicine will be in proportion to the rapidity of its absorption from the different parts to which it has been applied, unless the differences be so slight that there has not been time for the excretion of any considerable quantity from the blood during the process. On this account we must diminish the dose of a medicine in order to obtain the same effect, according to the rapidity of absorption from the place to which we apply it. Absorption is quickest from serous membranes, next from intercellular tissue, and slowest from mucous membranes. The vascularity and rate of absorption from intercellular tissue is greater on the temples, breast, and inner side of the arms and legs than on their outer surfaces, or on the back.[1] It should not be forgotten that any drug introduced into the stomach, but not absorbed into the blood, is as much outside the body as if it were in the hand, for any effect it will have on the system, provided always it have no local effect on the gastric walls. For if it act directly on the walls of the stomach, it may have an effect which it would not have when held in the hand or applied to the skin. Thus mustard, which would produce redness and burning of the skin, will cause vomiting when swallowed; but opium, which does not act on the stomach itself, except by diminishing its sensibility, produces no apparent effect until after it has been absorbed.

By the difference between absorption and excretion under different circumstances or in different individuals,[2] the cumulative action of drugs, the effect of idiosyncrasy, habit, climate, condition of body, as fasting, &c., disease, and form of administration, can to a certain extent, though not entirely, be explained; but experiments on some of these points are deficient, and the explanations now given are to some extent theoretical.

Cumulative Action.—If a substance be naturally so slowly excreted from the body that the whole of the dose in ordinary use is not excreted before another is given, the amount present in the body will gradually increase, just like the curare in Hermann's experiment, and will produce an increasing or cumulative effect. Examples of this are to be found in metallic preparations, such as those of mercury or lead, which are excreted very slowly; or in some of the organic alkaloids, if given in sufficiently large and frequent doses. The size of the dose and the frequency with which it must be repeated in order to produce a cumulative effect,

[1] Eulenburg, *Hypodermatische Injection der Arzneimittel*. 3rd edit. p. 65.

[2] Children absorb more quickly than adults, so opium is more dangerous to them. Marx, *Lehre von den Giften*, vol. ii. p. 117.

will differ according to the rapidity with which the drug is excreted; for, if excretion be rapid, a larger dose or more frequent repetition will be required. Sometimes the symptoms of the physiological action of a drug instead of increasing gradually may do so suddenly, and it is to this kind of action that the term cumulative action is most usually applied. This may sometimes be due to a sparingly soluble drug accumulating in the intestinal canal, and being suddenly dissolved and absorbed on account of some change occurring in the intestinal contents; at other times it may be due to arrest of excretion, as in the case of the two vegetable active principles, digitalin and strychnine, to which an especial cumulative action is ascribed. After moderate doses of these drugs have been taken for some time, it is found that instead of the effects they produce increasing gradually, as we would expect from a gradual accumulation in the blood, the symptoms of poisoning become suddenly developed, in somewhat the same way as if the dose had been suddenly increased. It is evident that a diminution in the quantity excreted will produce this effect as readily as an increase in the quantity taken, and this is probably the true cause of the phenomenon. When digitalin has been taken for some time and accumulated to a certain extent in the blood, it causes a diminution in the amount of urine excreted, and this diminution is either accompanied or quickly followed by the other symptoms of poisoning.[1] The effect, indeed, seems exactly the same as Hermann would have obtained in his experiment if he had only partially compressed the renal arteries instead of ligaturing them completely. For digitalin appears to diminish the secretion of urine by causing a powerful contraction of the renal vessels,[2] and in large doses may completely arrest the secretion of urine,[3] and probably also the circulation through the kidneys. Strychnine has a similar action on the vessels.[4]

Effect of different preparations.—When a drug is given in a soluble form, and in small bulk, it is more quickly absorbed and will have greater effect than when given in a less soluble form or much diluted. Thus drugs given in solution as tinctures will act, as a rule, more quickly than when given in the form of pill or powder.

Effect of Fasting.—When a drug is given upon an empty stomach, it is usually absorbed much more rapidly. Thus the same quantity of alcohol which would have no effect on a man if taken during or after dinner, might intoxicate him if taken on an empty stomach, and especially if he were thirsty, so that absorption occurred rapidly. Curare, although it is usually inert when placed in the stomach, is sometimes absorbed so rapidly from an empty stomach as to produce a certain amount of paralysing effect.

[1] Brunton, *On Digitalis*, p. 39.

[2] Brunton and Power, *Proceedings of Royal Soc.*, 1874, No. 153, and *Centralblatt d. Med. Wiss.*, 1874, p. 497. [3] Christison, *Edin. Med. Journ.*, vii. 149.

[4] Grützner, *Pflüger's Archiv.* 1876, Bd. xi. p. 601. Gärtner, *Separat Abdruck a. d.* lxxx. *Bd. d. k. Akad. d. Wiss.* III. Abt. Dec. Heft. Jahrg. 1879.

Besides the effect of absorption we have to consider also the local effects on the stomach itself, and the reflex effects which may be produced through its nerves on other organs. Thus where we give a drug for its local action on the stomach itself, it is administered with the greatest effect during fasting, as it will come in contact with all parts of the gastric mucous membrane. An example of this is the use of a small dose of arsenic for gastric neuralgia or lientery.

But when we wish to prevent local action on the stomach, as, for example, when we give arsenic for its general effect on the system, in cases of skin disease, we administer it after meals, so that it may be diluted by the food, and not irritate the stomach too much.

Effect of Habit.—The tissues seem to have a certain power of adapting themselves to changes in their surroundings. Thus salt-water amœbæ will die when placed at once in fresh water, but if the fresh water be added very gradually, they may by and by become accustomed to live in it. Fresh-water amœbæ also have the power of becoming gradually accustomed to increasing quantities of salt gradually added to the water in which they live, and which would at once kill them if added suddenly. A similar power seems to be possessed by the tissues of the higher animals, in regard to some drugs at least. Thus the arsenic eaters of Styria are able to consume—not only without injury, but with apparent benefit to themselves—a quantity of arsenic which would prove fatal to one unaccustomed to it. The same is the case with opium and morphia. With these latter drugs there seems to be hardly any limit to the quantity which can be taken after the habit has been once established, and after a certain dose has been exceeded.

It is possible, however, that in addition to a process of accommodation going on in the tissues, there is a slower absorption, and perhaps more rapid excretion, going on at the same time; for it is observed in the case of opium that sometimes the effect is not only diminished, but the time which elapses before it occurs is lengthened when persons have become accustomed to the drug.

In regard to the possibility of very slow absorption we must remember the power of the liver to arrest and excrete, or to destroy poisons, especially as it is chiefly in the case of vegetable poisons that their power is lessened by habit, which has much less effect on inorganic substances. The **tolerance** of some inorganic drugs, and especially of tartar emetic in disease or after repeated doses, may be due to fever or the drug itself lessening the acidity of the stomach, and consequently the action of the drug which acts most strongly in presence of an acid.

The Effect of Temperature.—The effect of temperature on the action of drugs is very great. At different temperatures the administration of the same drug may be followed by different

results, and it is probable that a great number of the **contradictory observations** which we find in pharmacological works are due to this most important factor having been neglected in making the experiments. It is of the greatest importance to the physician also, as many of the cases of disease which he has to treat are accompanied by a rise in temperature which may have a very important effect upon the action of the drugs which he administers.

The alteration produced in the effect of drugs by warmth, was first noticed by Alexander von Humboldt, who observed that warmth not only acted as a stimulant to the heart in increasing the power and rapidity of its contractions, but noticed that warmth increased the rapidity with which alcohol destroyed the irritability of a nerve, and potassium sulphide that of a muscle. Bernard observes generally that poisons act slightly on frogs when cooled down, and become more active the higher the temperature. The effect of warmth in stimulating the movements of protoplasmic structures, such as amœbæ and cilia was investigated by Kühne; and, in an important research, Luchsinger has experimented on the influence of warmth on the action of poisons on many organs, and found that the ciliary motion in the pharynx of the frog becomes paralysed by chloral, potassium carbonate, and tartrate of copper and soda more and more quickly in proportion to the rise in temperature. On cooling down the ciliary movement again returned.

Dr. Cash and I have found that the action of veratrine or barium on muscle is very much altered by heat and cold. At ordinary temperatures contraction is greatly prolonged, but under the influence of either great heat or great cold the contraction again becomes nearly or quite normal.

Many, if not all, muscular poisons act more quickly with increased temperature; and frogs poisoned with chloral, copper, manganese, potash, and zinc, are paralysed more quickly when the temperature is high, than when it is low, whether the alterations be produced artificially, or be due to differences in the season at which the experiments are made.

Rabbits poisoned with copper or potash also die more quickly when placed in a warm chamber, than when left at the ordinary temperature.

The terminations of motor nerves in the muscles are also greatly affected by temperature.

Guanidine produces in the frog fibrillary twitchings of the muscles, which persist even in excised muscles, but are removed by curare, and are therefore in all probability dependent on an affection of the terminal ends of the motor nerves in the muscle. Luchsinger has found that when four frogs are poisoned in this way, and one is placed in ice-water, another in water at 18°, a third at 25°, and a fourth at 32°, the fibrillary twitchings soon disappear

from the muscles of the frog at 0°, and only return when its temperature is raised to about 18°. In the one at 18° convulsions occur, which are still greater in the one at 25°. In the frog at 32°, on the other hand, no abnormal appearance is to be remarked, and five times the dose may be given without doing it any harm.

This poison then resembles veratrine in acting only at ordinary temperatures, and in its action being abolished by excess of heat or cold.

The effect of temperature on secreting nerves is well marked. When the sciatic is stimulated in an animal, the corresponding foot usually begins to sweat, but the sweating is very much less if the foot is cooled down than if it is warm. A similar action is exerted by temperature upon the sweating produced by pilocarpin—a drug which appears to act by stimulating the ends of the secreting nerves. When the animal is cooled, this drug is much less powerful than when it is warm.

Overheating appears to have an opposite action, and when the foot is heated up to a certain temperature it does not secrete nearly so readily, even though the glands themselves are not injured, and secretion may commence after the lapse of a little time.

The influence of poisons on the heart of the frog is also modified by temperature. Kronecker found that its beats were arrested by ether easily and quickly when the temperature was high, but with great difficulty when it was low. Ringer found that a small dose of veratrine greatly affects the ventricle at a moderate or high temperature, but at a low temperature produces no effect."[1]

Luchsinger noticed that when the frog's heart had been arrested by passing dilute solutions of chloral, copper, or potassium carbonate through at 25° C., the pulsations again began when the temperature was reduced to 15° C. When, on the contrary, the heart had been arrested in a similar manner, at a temperature of 5° C., pulsations could then be induced by warming it to 15°.

Some extraordinary observations on the effect of temperature upon the action of drugs on the spinal cord have been made by Kunde and Foster, who have found that, in a number of frogs poisoned with strychnia and exposed to different temperatures, raising the temperature diminishes the convulsions while cold increases them if small doses are employed. Raising the temperature, indeed, may not only diminish but entirely abolish the convulsions, while putting a frog in ice may bring them on, when they would not otherwise appear, and cause them to last for no less than twenty-four hours. When large doses are employed the opposite effect is produced; raising the temperature then increases the convulsions, while cooling the frog down to 0° abolishes them.

An observation similar in some respects, though differing in

[1] Ringer, *Archives of Medicine*, vol. vii. Feb. 1882, p. 5.

others, has been made on the effect of temperature on the action of picrotoxin by Luchsinger.[1] When this poison is given to three frogs, and they are then placed in water at 0°, 15°, and 32°, in a few minutes the convulsions occur in the one at 32°, shortly afterwards in that at 15°, while the one at 0° remains for a long time completely unaffected, and only exhibits signs of convulsion when the dose has been very great indeed, or when it is taken out of the cold bath.

The effect of warmth in accelerating death from **muscular** poisons has already been mentioned.

The power of warmth to preserve life in narcotic poisoning was observed by Hermann in relation to alcohol, which rabbits bear better when they are somewhat warmed.[2] Its extraordinary effect in preventing death in animals poisoned with chloral was noticed by Stricker, and more thoroughly worked out by myself at his suggestion.[3] Death by chloral appeared from my experiments to be in a great measure due to continued loss of heat from the animal. This seems to be the case also in **metallic** poisoning by copper, manganese, mercury, platinum, potassium, thallium, tungsten, and zinc. Its cause appears to be twofold: (1) the poisons lessen combustion in the body, and the amount of heat produced, as is shown by their diminishing the amount of carbonic acid excreted. (2) Besides disturbing the production they also disturb the regulation of heat, so that animals poisoned by them have less power of resisting the influence of external temperature, and therefore the temperature rises more quickly when they are put in a warm chamber, as well as sinks more quickly when they are exposed to cold.

All these things show that the **definition** of the **action of a drug**, already given p. 3, must be still further modified, and we must define it as the reaction between the drug and the various parts of the body **at a certain temperature.**

Thomas[4] found that digitalis has sometimes no action on the pulse in pneumonia. As the slowing of the pulse produced by this drug is to some extent effected through the vagi, it occurred to me that its want of action in this disease might be due to the paralysis of these nerves by heat. On testing the action of heat, however, on the vagus I found that it was not paralysed in rabbits deeply chloralised, at a temperature just sufficient to kill the animal.[5]

The reason why digitalis does not reduce the pulse in some cases of pneumonia has, therefore, still to be determined.

The abnormal effect which opium has in some cases of fever—

[1] Luchsinger, *Physiologische Studien*, Leipzig, 1882.
[2] Hermann, *Arch. f. Anat. u. Physiol.* 1867, p. 64.
[3] Lauder Brunton, *Journal of Anatomy and Physiology*, vol. viii.
[4] *Arch. f. Heilk.* vol. iv. 329, 1865.
[5] *St. Bartholomew's Hospital Reports*, 1871, p. 216.

causing excitement instead of sleep—is occasionally most distressing to the physician. It is possible that this may be partly due to the temperature, and that the combination of tartar emetic with the opium may owe some of its utility to its effect in lowering temperature, although not improbably both it and another useful combination with chloral also act more perfectly on account of the depressing action on the circulation. These are points, however, on which further observations are greatly needed.

Climate.—It is said that the action of narcotic drugs is greater in warm climates than in cold, and that smaller doses are therefore required to produce a similar effect. If this statement be true, it is in all probability due to the higher temperature, for Crombie has shown that in India the average temperature of the body is about half a degree higher than in England.

Time of Day.—In healthy persons fluctuations occur. The lowest temperatures occur at night between 10 P.M. and 1 A.M. and in the early morning between 6 and 8 A.M. The highest temperature occurs between four and five in the afternoon.

The action of drugs may be partially altered by the slight variations in temperature which occur within the body, and perhaps still more by the variations in tissue change, of which these fluctuations of temperature are the indication. Thus the necessity for great attention to the administration of stimulants in the early hours of the morning in cases of threatening collapse has long been recognised.

Effect of Season.—The action of drugs is altered by the changes in temperature due to the seasons. Galen supposed that the quantity of blood in the body was increased in spring, and in this country, till within recent years, it was a common custom for people to be regularly bled every spring. Purgatives were not unfrequently also administered at the same time. There are, no doubt, changes corresponding with the seasons in the human organisation, although these are better marked in the lower animals, *e.g.* deer; where the antlers bud regularly in spring and reach perfection just at the breeding season. It is possible that the abolition of the practice of bleeding in spring and the changes in other plans of treatment formerly adopted, may not be altogether due, as some suppose, to increased knowledge on our part, but rather to the occurrence of **a change of type** not only in diseases but also in slight ailments, and to the need for such treatment having disappeared. Formerly, before the introduction of coaches, and still more of railways, locomotion was difficult and transportation was expensive; in consequence of this the food consumed by the generality of people was different in character, loaf bread being very little used, and salt meat often used for weeks and months together during the winter, with comparatively few vegetables. Such a diet might naturally lead to a condition of body which would be benefited by bleeding and purgatives.

Effect of Disease.—The direct and indirect, the local and remote actions of drugs upon the complicated mechanism of a mammalian body is so perplexing, that the attempt to ascertain the precise mode of action of a drug by its *simple* administration either to a healthy man, or to healthy animals, and observation of its effects upon them, is hopeless.

Moreover the object that we really wish to attain is the power to relieve the human suffering, and to avert the premature death due to disease. But in disease we have new factors, changes are produced by it in the functions of the body, and the reaction of the diseased organism to the drugs which we administer is oftentimes different from that of a healthy one. To a man suffering from cholera, for example, enormous doses of drugs have been given without the least effect; and, in the wakefulness of fever, the opium which ought to produce sleep may simply cause excitement and delirium.

Use of Experiments.

As we have seen, the problems put before us are too complicated to be solved directly, and we must therefore simplify them.

This is done in four ways:—

1st, by observation of the effects of drugs on animals with a **simpler organism** than our own, such as amœbæ or frogs;

2ndly, by **applying** the drug to some **part** of an animal body more or less completely **separated** from the rest, such as, for example, the muscle and nerve, or the heart of a frog separated from the body; and,

3rdly, by **preventing** it from **reaching one part** of the body while it acts on the others, as by ligaturing an artery as in Bernard's or Kölliker's experiments on curare.

4thly, by producing artificial **changes** in the **relations** of the various parts of the body of higher animals, either before or after administration of a drug, as, for example, by dividing the vagi, in order to ascertain how far the change produced in the beats of the heart by a drug is due to its action upon it by these nerves.

Comparative Pharmacology.—It may seem almost absurd to those unacquainted with the subject, that so much attention should be devoted to experiments on the effect of drugs on the lower animals, when our object is, as we have just stated, to ascertain their action upon human beings, and their mode of employment in the diseases of man.

But in the study of Pharmacology, just as in Histology, very much is to be learned by comparative studies. In his lectures, Ranvier admirably defines General Anatomy as Comparative Histology, limited to a single organism. He illustrates this by showing

that the different modes of movement which occur in some of the lower classes of the animal kingdom are to be found united in the highest. Thus leucocytes of the blood move about like amœbæ. The epithelium of the respiratory passages is provided, like infusoria, with cilia; and while some muscles have the power of rapid contraction, others contract slowly, like those of some invertebrata.[1]

We have thus in certain parts of the bodies of the higher animals and of man, anatomical elements whose functions are performed in a way resembling that of organisms low in the scale of existence, and by examining the effect of drugs upon these low organisms we acquire knowledge which aids us in determining the action of drugs upon similar anatomical elements in the human body.

In his admirable lecture on Elementary Pathology, Sir James Paget draws attention to the distinction between the conditions of life and the essential properties of living things; and to the fact that, while the various parts of a complicated organism like the human body are closely connected together, and made to work in harmony for the common good of the organism in health, yet each part retains its own mode of life, and may sometimes develop to an excessive extent at the expense of the rest, and may destroy the organism, and itself as well. We see the power which each part possesses of carrying on individual life apart from the rest best in lower organisms, or in inorganic substances, where the parts are less dependent on the welfare of the whole.

Thus, in crystals, a chip which has been broken off is replaced, and the form of the crystal restored by putting it in a solution which will yield it the proper kind of material required. When a hydra is cut in two, each part grows into a perfect individual: a tail growing to the head part, and a head growing to the tail part. When a claw has been broken off a crab or lobster, a new one will by and by grow; but if the animal be divided in two, unlike the hydra it will die.

As we ascend in the scale of existence the power of repair becomes less perfect. But even in the human being we see that the different parts retain their individual life, and if put into proper conditions may live, although the original body from which they were obtained were to die. Teeth, for example, which have been extracted from one person have been transplanted and grown in the jaws of another; and the transplantation of hair, skin, or of periosteum, is perfectly practicable.

Idiosyncrasy.—In their onward development from the lowest forms of life, man and the higher animals have not only permanently retained in their bodies certain parts which resemble organisms low in the scale of existence, but every now and again a

[1] *Leçons d'anatomie générale sur le système musculaire*, par L. Ranvier. Paris, 1880, p. 46.

tendency to reversion appears in certain individuals, and we thus get anatomical abnormalities and malformations.

These were formerly inexplicable, but the doctrine of evolution has thrown much light on their probable causation.

Now and again we also meet with peculiarities in the reaction between drugs and parts of the human body in certain individuals.

Some persons, for example, are like pigeons—only slightly affected by opium—and can take enormous doses of it without any apparent effect. Others, again, are peculiarly sensitive to the action of certain medicines, and a dose of a mercurial preparation which would have but a slight purgative action on one, will produce intense salivation in another.

These personal peculiarities in regard to the action of drugs, or idiosyncrasies, as they are termed, have been, and are still, very perplexing to the medical practitioner. It is probable, however, that a more complete study of comparative pharmacology will enable us, to some extent at least, to recognise these, and thus to avoid the inconvenience which they occasion.

Objections to Experiment.—Some people object entirely to experiments upon animals. They do this chiefly on two grounds. The first is that such experiments are useless, and the second, that even if they were useful, we have no right to inflict pain upon animals.

The first objection is due to ignorance. Almost all our exact knowledge of the action of drugs on the various organs of the body, as well as the physiological functions of these organisms themselves, has been obtained by experiments on animals.

Their second objection is one which, if pushed to its utmost limits and steadily carried out, would soon drive man off the face of the earth.

The struggle for existence is constantly going on, not only between man and man, but between man, the lower animals and plants, and man's very being depends upon his success.

We kill animals for food. We destroy them when they are dangerous like the tiger or cobra, or destructive like the rat or mouse. We oblige them to work for us, for no reward but their food; and we urge them on by whip and spur when they are unwilling or flag. No one would think of blaming the messenger who should apply whip and spur to bring a reprieve, and thus save the life of a human being about to die on the scaffold, even although his horse should die under him at the end of the journey. Humane people will give an extra shilling to a cabman in order that they may catch the train which will take them to soothe the dying moments of a friend without regarding the consequences to the cab-horse. Yet if one tenth of the suffering which the horse has to endure in either of the cases just mentioned were to be inflicted by a physiologist in order to obtain the knowledge which would

help to relieve the suffering and lengthen the life, not of one human being only, but of thousands, many persons would exclaim against him. Such objections as these are due either to want of knowledge or want of thought on the part of people who make them. They either do not know the benefits which medicine derives from experiment, or they thoughtlessly (sometimes, perhaps, wilfully) ignore the evidence regarding the utility of experiment.

One of the most important objections that has been raised to this mode of experiment is that the action of drugs on the lower animals is quite different from their action on man. This objection has a certain amount of truth, but is in the main groundless. The action of drugs on man differs from that on the lower animals, chiefly in respect to the brain, which is so much more greatly developed in man.

Where the structure of an organ or tissue is nearly the same in man and in the lower animals, the action of drugs upon it is similar. Thus we find that carbonic oxide and nitrites produce similar changes in the blood of frogs, dogs and man, that curare paralyses the motor nerves alike in them all, and veratria exerts upon the muscles of each, its peculiar stimulant and paralysing action.

Where differences exist in the structure of the various organs, we find, as we would naturally expect, differences in their reaction to drugs. Thus the heart of the frog is simpler than that of dogs or men, and less affected by the central nervous system.

We consequently find that while such a drug as digitalis has a somewhat similar action upon the hearts of frogs, dogs and men, there are certain differences between its effect upon the heart of a frog and on that of mammals. In all it seems to affect the muscular substance and cause increased contraction. But while the frog almost invariably dies with the heart in a state of tetanic contraction, this is not the case with dogs or men, where the heart sometimes is found in diastole after death.

Ipecacuanha or tartar emetic will cause vomiting in man, but does not do so in rabbits. The reason of this is that the position of the stomach in the rabbit is different from that in man, and is such that the animal cannot vomit. In dogs, however, the position of the stomach agrees with that of man, and tartar emetic or ipecacuanha causes vomiting in both. Belladonna offers another example of apparent difference in action—a considerable dose of belladonna will produce almost no apparent effect upon a rabbit, while a smaller dose in a dog or a man, would cause the rapidity of the pulse to be nearly doubled. Yet in all three—rabbits, dogs and men—belladonna paralyses the power of the vagus over the heart. The difference is, that in rabbits the vagus normally exerts but little action on the heart, and the effect of its paralysis is consequently slight or hardly appreciable, the pulse being normally

almost as quick as it is after the vagus is paralysed. In dogs and men, on the contrary, the vagus is constantly exerting considerable restraining power over the heart, and the effects of its paralysis at once direct attention.

An example of the apparent difference in the effect of a drug on different animals is afforded by nitrite of amyl. If we measure the pressure of the blood in the arteries of a rabbit and of a dog, and then cause them to inhale nitrite of amyl, we find that the small vessels have become widened and allow the blood to pass easily out of the arterial system into the veins, so that the pressure sinks considerably in the rabbit, whereas it sinks only slightly in the dog. The action seems at first sight different; but when we examine it more closely, we find that the heart of the dog is no longer beating slowly, but very quickly, so as to keep up the pressure, notwithstanding the rapid flow of blood through the widened vessels, while the heart of the rabbit was going so fast before that it could not go much more quickly. If we cut the vagi in the dog, so that the heart goes as quickly as in the rabbit before it begins to inhale, the blood-pressure sinks during the inhalation, just as it does in the rabbit.[1]

By means of experiments upon animals, then, we are able to ascertain the action of drugs upon those organs of the body which are alike in man and animals; and the very differences which exist between various sorts of animals, help us to understand the action of drugs more thoroughly.

Erroneous Deductions from Experiments.—A great fault —and one which is only too common in the works of experimental pharmacologists—is that of drawing **general conclusions** from **limited data.**

One experimenter tries the effects of a drug, let us say tartar emetic, upon rabbits. He finds that they do not vomit, and instead of drawing the only warrantable conclusion, viz. that tartar emetic does not cause vomiting in rabbits, he draws the general one—tartar emetic does not cause vomiting in animals. Another tries it upon dogs, and he finds they all vomit. Instead of the limited conclusion that tartar emetic makes dogs vomit he draws the general conclusion that it makes animals in general vomit. The two observers are equally positive in regard to their facts—each is assured that he himself is right, and that the other is totally wrong. The reason of the discrepancy is simply that the conditions under which the experiments have been performed were different, but the observers have not taken these differences into account when drawing their conclusions. A third observer then comes, perhaps, and by further experiments reconciles the apparently contradictory statements. Thus one experimenter tries the effect of caffein upon frogs: he finds that it produces rigor mortis in the muscles.

[1] Lauder Brunton, "Action of Nitrite of Amyl on the Circulation," *Journal of Anatomy and Physiology*, vol. v. p. 95.

Another tries the same drug, and finds no such result. These two observations are completely contradictory, until a third tries the effect of the drug upon two species of frog, and finds that while the muscles of the *rana esculenta* are but slightly affected, those of the *rana temporaria* are rendered rigid.[1]

These apparent contradictions in the results of different observers are exceedingly puzzling to the student, but nothing is more instructive to those who are actually working at the subject.

The **utility** of **apparent exceptions** was fully recognised by Claude Bernard, who says: "In physiological studies we must always carefully note any fact which does not accord with received ideas. It is always from the examination and the discussion of this exceptional fact, that a discovery will be made, if there is one to make."[2]

[1] Schmiedeberg, *Arch. f. Exper. Path. u. Pharmak.* Bd. ii. p. 62.
[2] Bernard, *Liquides de l'organisme*, tom. i. p. 258.

CHAPTER III.

ACTION OF DRUGS ON PROTOPLASM, BLOOD, AND LOW ORGANISMS.

Action of Drugs on Albumen.

In all living bodies we find that the protoplasm is of a more or less albuminous nature.

Albuminous substances possess a very complex intra-molecular grouping, and very high atomic weights. Many different forms are found in animals, and along with albumens we must associate bodies like mucin, which probably have a very important relation to it, inasmuch as a body nearly, if not quite, identical with mucin, forms the nucleus of the red blood corpuscles in fowls, and a substance of an allied nature also occurs in the circulating fluid which represents the blood in the echinodermata. The albumen of serum may be taken as a representative of such substances; it is soluble in water, but, when boiled, is **coagulated** and precipitated. It is coagulated also by alcohol, but if the coagulum is quickly placed in water it redissolves; if allowed to remain for some time exposed to the action of the alcohol, it becomes permanent and insoluble. An insoluble precipitate also falls on the addition of tannic acid, lead acetate, mercuric chloride. These just mentioned precipitate almost all the albumens, even from somewhat dilute solutions; in strong solutions precipitates are also formed by silver nitrate, copper sulphate, and zinc chloride. When these are added to albumen containing only a small quantity of water, as for example, the white of an egg, they form with it a solid mass of albuminate. A small quantity of strong potash added to the white of egg produces a solid transparent jelly of albuminate of potash, and a similar but opaque jelly is formed by the use of caustic lime or baryta in the place of potash: these albuminates are, however, soluble in water.

Albumen dissolves in **alkalies** and may be partly precipitated by neutralising. The alkaline solution is not coagulated by heat, and, in fact, the substance present in the solution is no longer serum albumen, but a compound of the albumen with the alkali, or alkali-albuminate.

Albumen is precipitated by a small quantity and dissolved by excess of most mineral **acids,** forming with them acid albuminates; thus a watery solution of albumen is precipitated by concentrated nitric, sulphuric, or hydrochloric acid. It is also precipitated by acetic acid along with a considerable quantity of a neutral salt of an alkali or alkaline earth, or of gum-arabic or dextrin. This precipitation is perhaps best marked with nitric acid, but it only occurs with moderate quantities of nitric acid. When a minute quantity only of the acid is added, no precipitation takes place, and the solution remains clear; but a nitric-acid-albuminate containing a small quantity of acid is formed, and if the solution is now boiled, no coagulum will form. On the addition of more acid, however, a second nitric-acid-albuminate, insoluble in water, is produced, and a precipitate falls. On the addition of more acid still, the precipitate is redissolved, and a third nitric-acid-albuminate is formed, soluble in water, and not precipitated on boiling.

The temperature at which albumen coagulates is altered by acids and alkalies. Alkalies generally tend to raise the temperature of coagulation, and when added in large quantities prevent it altogether.

Very dilute acetic and phosphoric acid, on the other hand, tend to lower the coagulating point, although large quantities may interfere with coagulation.

Neutral salts, such as sodium chloride or sulphate, also lower the coagulating point.

The **organic alkaloids** which have such a powerful action on the animal body appear to resemble acids rather than alkalies in their effect upon albumen, because, according to Rossbach, they lower considerably instead of raising the point of coagulation.

Albumen undergoes an extraordinary change in consequence of the action of ozone, and becomes, after exposure to it, uncoagulable by boiling, and by acids, excepting in large quantities, and by metallic salts, with the exception of basic acetate of lead, and of alcohol.

The action of alkaloids upon this ozonized albumen is even more remarkable than upon ordinary albumen, for when mixed with it in small quantity, they restore its coagulability to the albumen and cause it to coagulate far under the boiling point. When added to the albumen before exposure to a stream of ozone, they prevent the albumen being altered by it, in the way which it would otherwise be, and it remains coagulable by heat, in the same way as if it had not been exposed to the action of ozone at all. It is therefore evident that the alkaloids not only increase the coagulability of ordinary albumen at a high temperature, but that they act upon it at ordinary temperatures (30°-40° C.) and destroy its affinity for ozone. This action will naturally interfere with the processes of oxidation, but the methods of examining this action will be described later on (page 54).

When a solution of pure albumen is added to a mixture of guaiac and vegetable protoplasm, it greatly lessens the blue colour, which would otherwise be produced. The cause of this appears to be that albumens or albuminous substances have such an affinity for ozone that they take it up instead of allowing it to act on the guaiac. This affinity for ozone is diminished by the action of alkaloids.

This is shown by taking several tubes containing an albuminous solution of a certain strength. Reserving one as a standard, the alkaloids are added to the others, and after a certain time has elapsed, so as to allow the alkaloid to affect the albumen, a small quantity of lettuce water is mixed with each and then a little guaiac. In the standard one the colour will be least, because the albumen not having been acted upon by the alkaloids will interfere with the reaction of the lettuce water and the guaiac upon each other. In the others a blue colour will appear with greater or less intensity, according as the albumen has been more or less affected by the alkaloid. This experiment, however, is not free from fallacy, because there is to be considered not merely the action of the alkaloid upon the albumen, but its action on the protoplasm as well, and it is therefore advisable to use it in a quantity which is small as compared with the amount of albumen employed.[1]

Action of Drugs on Protoplasmic Movements.

The **amœba** consists of a small mass of structureless protoplasm, without any distinct cell-wall.

It contains numerous granules and nucleus, with nucleolus, as well as one or more vacuoles, which appear to be small spaces filled with fluid.

Some amœbæ live in salt water, others in fresh water; and, although it may be impossible with the microscope to detect any marked difference between them, they exhibit a great difference in their reactions to drugs—the salt-water amœbæ being only slightly affected by them, while fresh-water amœbæ are readily susceptible to their action.

It is nourished by simply adhering to any particle of food, closing over it and digesting it, again opening out and ejecting the residue.

This protoplasmic mass is almost constantly altering in shape, pushing out projections at one point, and drawing them in at another. By this means, also, it moves about from place to place.

Method of Experimentation on Amœbæ and Leucocytes.—In experimenting on amœbæ, take a drop of the slimy sediment, such as found in the tanks of hothouses, and place it on the covering-glass of a microscope; this may then either be put on an object-glass, the excess of water removed by filter-paper, or still better, it may be inverted over the opening of a Stricker's warm stage.

When it is simply laid on the object-glass, a solution of any drug is added by putting a drop across the edge of the covering-glass, and allowing it to be drawn gradually underneath by capillary attraction.

---

[1] Rossbach, *Verhandl. d. phys. med. ges zu Würzburg*, N.F., 3 Band., p. 346.

Gases are best applied by means of a Stricker's stage, and it is also convenient for experiments on solutions.

In experimenting on **leucocytes** with its aid, a covering-glass is applied to the cut surface of a newt's tail, or to the surface of a drop of blood, so that a very minute quantity of blood adheres to it.

The drug to be tested is kept dissolved in a ·65—·75 per cent. solution of common salt (Na Cl). The salt solution of this strength is often called simply *normal* salt solution, and is used instead of water, because water itself has a very destructive action on those forms of protoplasm, which are usually nourished by saline solutions, like blood or serum.

A drop of the salt solution containing the drug is placed over the blood on the covering-glass, and inverted over the warm stage as already described. If the experiment is to continue long, a rim of oil should be drawn around the edge of the covering-glass with a camel-hair pencil, so as to prevent evaporation.

The advantage of using such a small quantity of blood is, first, that it mixes rapidly and perfectly with the solution; and secondly, that it does not dilute the solution of the drug, and we thus know the strength of the drug used.

If we used a large drop of blood, we should have to employ a solution of the drug twice the strength we desire, so that when a drop of equal size was added to the blood, the mixture would contain the proper proportion.

The **effect** of **heat** and **cold** upon the movements is very marked, cold rendering them slow, or arresting them altogether. Heat at first greatly quickens their movements, but when raised to 35° C. it causes them to fall into a state of tetanic contraction and assume a spherical form.

This state is one of heat tetanus, and if the temperature is now reduced, the movements will again reappear.

At a temperature of 40° C. they also become spherical and motionless. But their movements do not return when the temperature is reduced; they are in a state of heat rigor, the high temperature having coagulated the protoplasm.

Slight **electrical** shocks from a coil increase the rapidity of the protoplasmic movements; stronger ones cause tetanic contraction; and numerous or powerful ones produce coagulation.

Common **salt** in very small quantity (a drop of 1 per cent. solution slowly added) first quickens the protoplasmic movements and then causes sudden tetanic contraction, and the expulsion of any food they may contain at the moment, and sometimes even expulsion of the nucleus.

When **water** is added so as again to dilute the mixture the amœbæ resume their movements.

Both **acids** and **alkalies,** when very dilute, increase the protoplasmic movements and afterwards arrest them.

Hydrochloric acid has a more powerful action than a solution of potash of a similar strength. It causes the amœbæ to contract and form a ball with a sharp double contour. In it, twitching movements first occur, which expel any food present. It then becomes pale and lumpy, and breaks up.

Potash causes them to swell up and assume the form of large pale vesicles, which quickly burst.

A **constant current** of **electricity** causes contraction and imperfect tetanus; and, if powerful and long kept up, the positive pole produces in the amœbæ near it the same changes as dilute hydrochloric acid, and the negative pole the same changes as are produced by an alkali such as potash.

Oxygen appears to be necessary for their life; its removal by means of hydrogen deprives the amœbæ of their power of motion, and finally causes contraction and coagulation.

Carbonic acid alone has a similar action to removal of oxygen, and produces this effect both in the presence and absence of oxygen, but takes a longer time to do so when oxygen is present.[1]

Leucocytes.—In their appearance and movements leucocytes strongly resemble amœbæ: they are affected in a similar manner by heat, electricity, and drugs. Their resistance to the action of drugs varies somewhat in different animals. Those obtained from the blood of the newt for example are more resistant than those of the guinea-pig; and those of the female newt more resistant than those of the male to the action of quinine.[2] Heat and cold affect the movement of leucocytes in very much the same way as those of amœbæ.

The movements of leucocytes, like those of amœbæ, are of **two kinds**, viz., movements of the protoplasmic pseudopods, while the leucocyte remains *in situ*. The pseudopods in this instance are generally of a waxy look and knoblike form.

Secondly, movements of migration from place to place; these movements are accompanied, or accomplished, through the projection of numerous fine filaments.

Effect of Drugs.—Cinchona alkaloids—quinine, quinidine, cinchonine, and cinchonidine have a remarkable power of arresting these movements in the proportion of 1 in 1,500. They quickly stop the migratory movements of leucocytes from the newt, and in a much larger proportion will arrest the movements of the knoblike pseudopods.

No very marked difference is observed in the strength of the cinchona alkaloids, though quinine seems to be somewhat the most powerful.

Sulphate of bebirine is almost as powerful as the cinchona alkaloids.

Strychnine is very much less powerful than any of the alkaloids mentioned.

Potassic picrate and æsculin have but little action.[3]

Movements of Leucocytes in the Blood-vessels.—In the processes of **inflammation** leucocytes pass in great numbers through the walls of the capillaries.

[1] Kühne, *Protoplasma und Contractilität*, pp. 28-53.
[2] Geltowsky, *Practitioner*, vol. viii. pp. 325-330.
[3] Buchanan Baxter, *Practitioner*, vol. xi. p. 321.

The effect of quinine in arresting their movements, when mixed with them directly, naturally leads one to expect that it may arrest their migration from the capillaries, when injected into the blood, and this anticipation has been realised in the experiments of Professor Binz.

To observe this phenomenon, the brain of a frog is to be destroyed, and a little curare injected under the skin, in order to abolish any spinal reflex movements. It is then laid on a piece of cork, such as that shown in Fig. 5, with a hole at one side, over which a piece of glass is fastened about half an



FIG. 5.—Apparatus for examining the mesentery of the frog under the microscope.

inch higher, by means of two other pieces of cork and some sealing-wax. On this a piece of sheet cork of the form shown in the figure, and a round piece of glass are cemented so as to form a channel, in which the intestine lies. The body of the frog is fixed to the cork, the abdomen opened, the intestines drawn out, and the mesentery fastened with very fine pins over the aperture. In half an hour, or two hours, the leucocytes pass rapidly through the walls of the capillaries, and afterwards wander through the tissues.

The drug may then be injected into the lymph sac, or locally applied to the mesentery.

When quinine is applied locally to the mesentery in this condition it arrests the movements of the leucocytes, which have already emerged, but does not prevent those which are still within



FIG. 6.—Diagram to illustrate the action of quinine on leucocytes, modified from Binz (*Das Wesen der Chininwirkung*, Berlin, 1868). The thick lines represent the walls of the blood-vessel, and numerous leucocytes are shown both inside it and outside distributed through the adjoining tissues. *a* represents the vessel before, and *b* after the *local* application of quinine. The leucocytes outside the vessel have their movements arrested, and cannot wander on through the tissues, while those inside are not affected and continue to emigrate. *c* represents the effect of quinine injected into the circulation or lymph sac. The leucocytes inside the vessel are here affected first, and their emigration stopped, while those outside still continue to travel onwards.

the vessels from going out—they therefore form a dense accumulation around the vessel (Fig. 6, *b*). When injected into the circulation, on the contrary, the leucocytes which are in the vessels are prevented from passing from the capillaries, while those which have

already passed out continue to wander onwards, and thus a clear space is left outside the vessel (Fig. 6, *c*).

The quantity of quinine necessary to produce this effect is $\frac{1}{25000}$th to $\frac{1}{20000}$th of the animal's weight.

If quinine were given to stop the exit of leucocytes from the vessels in peritonitis, three or four grammes would be required to be given within a short time, to a man weighing 150 lbs.

In guinea-pigs a dose of quinine sufficient to kill the animal does not stop the movements of the leucocytes in its blood, which are seen to go on, when a drop of it is examined after death.

Red Blood Corpuscles.—The size of the red corpuscles is diminished by warmth, either applied locally on the hot stage of a microscope, or acting on them in the vessels of an animal suffering from fever, by carbonic acid and by morphia.

It is increased by cold, oxygen, hydrocyanic acid, and quinine; and an increase occurs also in cases of anæmia.[1]

The red corpuscles pass out of the capillaries like the white, but they do so very slowly indeed, and in small numbers, under ordinary circumstances. Excess of sodium chloride in the blood causes them to pass out much more quickly;[2] and rattle-snake poison, when locally applied, produces such sudden extravasation that it is impossible to follow the process: the whole field of the microscope becoming suddenly covered with blood.[3]

Action of Drugs on Infusoria.

Among the infusoria, like the amœbæ, each individual consists of a single mass of protoplasm, and not of a number of distinct cells; but the protoplasm is differentiated. Round the greater part of the animal it seems to be somewhat harder, so as to form a sort of skin, excepting at one place which is softer than the rest, serving for the ingress of food and the egress of egesta.

Instead of throwing out pseudopods, the body is either covered entirely with cilia or they are arranged round the mouth. Once it has entered by the mouth, the food finds its way all through the protoplasm of the body.

A contractile vesicle exists, which pulsates rhythmically.

Mode of Experimentation.—For the purpose of examining the action of drugs upon infusoria an infusion of hay is prepared some days previously. Two small pipettes are then made, which will deliver drops of equal size.



FIG. 7.—Diagram to show the way of making small pipettes.

This is done by heating a piece of glass tubing in the middle, drawing it out, and cutting it across by a scratch with a triangular file (Fig. 7). With one of these a drop of hay-infusion is placed on the covering glass, which is inverted on a Stricker's stage and examined. In order to ascertain the lethal strength

[1] Manassein, *Ueber die Dimensionen der Blutkörperchen unter verschiedenen Einflüssen.* Tübingen, 1872.

[2] *Prussak. Wiener. Akad. Sitzungsber.* lvi. 1867 (Abth. 2), p. 13.

[3] Brunton and Fayrer, *Proc. Roy. Soc.* February 1875, p. 271.

of a drug, a drop of a solution of the poison of a definite strength is then mixed with it, and the infusoria are examined again after a certain time.

If they continue moving, another experiment is made with a stronger solution; but if they have completely stopped, it is repeated with a weaker one until the solution is of such a strength that the movements become very slight and cease almost immediately after mixing, and cannot be restored by the addition of water. As the two drops of fluid were of equal size, the lethal strength of the solution is just one half of that which was last added. By repeating the experiments in exactly the same way with different drugs, their relative poisonous properties are ascertained.

Heat increases the rapidity both of the rhythmical contractions of the vesicle and of the ciliary motion and consequently of the movements from place to place of the infusoria. It seems as if the cilia were not equally affected by heat, those which produce a longitudinal movement appearing to be acted upon more quickly than those which cause a movement of rotation. Both kinds are first stimulated and then paralysed.

At temperatures between 25° and 30° the contractions of the vesicle are greatly quickened, and the animal moves with great rapidity in a longitudinal direction.

Between 30° and 35° its movements are still very rapid, but it seems to have lost the power of direction; all the cilia seem in full action, and the movements of the individual are determined simply by their anatomical arrangement.

Above 40° the cilia, which act longitudinally, appear to have stopped and the animal rotates, at first very rapidly, then slower and slower until all movements cease, and the protoplasm appears to become fluid; but when the heat is still further raised it coagulates.[1]

Cold lessens the quickness of the rhythmical contractions of the vesicle, of the ciliary motion and of the movements from place to place. Weak **electrical currents** first quicken the ciliary motion and cause movements of rotation, then swelling of the protoplasm, slower movements, and finally apparent solution of the protoplasm.

Moderate currents produce a tetanic contraction of the protoplasm and of the cilia, while the contractile vesicle is unaffected.

Strong currents cause liquefaction of the protoplasm.

Saline solutions appear rather, if we may say so, to alter the conditions under which the infusoria live than to affect the protoplasm itself. Strong solutions cause them to shrivel and then to swell up and become motionless. This effect appears to be due to the solution altering the quantity of water which the protoplasm contains.

Weaker saline solutions, on the contrary, quicken their movements, and instead of causing them to shrivel make them swell up at once. Chloride of sodium, chloride, bromide, and chlorate of potassium, as well as alum, all have this effect.

[1] Rossbach, "Die rhythmischen Bewegungserscheinungen der einfachsten Organismen," *Verh. d. Würzburger physik-med. Gesellsch*, N.F., Bd. ii., Separatabdruck, S. 23. This work contains a number of exceedingly interesting and valuable observations on the subject.

Acids in minute quantities cause contraction both of the body and of the vesicle. The cilary motion is at first quickened and then retarded; the rate of contraction of the vesicle is at once diminished.

Moderate quantities cause coagulation of the protoplasm with swelling and liquefaction after death.

Strong acids at once destroy the protoplasm.

Alkalies in minute quantities cause swelling of the protoplasm, dilatation and slowness of the contractile vesicle.

Moderate quantities at once arrest the movements, cause liquefaction of the protoplasm, and destroy its differentiation, the contractile vesicles and vacuoles disappearing. They then cause swelling, and finally solution.

In large quantities they produce immediate liquefaction of the whole body.

Other drugs appear to affect the protoplasm itself, and arrest its movements without producing any apparent change in it.

The most active are chlorine, bromine, corrosive sublimate, iodine and permanganate of potash, and creasote.

Quinine is much less powerful than these, though it is much more so than most other organic alkaloids.

Strychnia has only one-fourth the power of quinine.

Cobra poison at first greatly quickens the movements of infusoria and then arrests them, causing just before death a contraction of the protoplasm, which then expands to its ordinary size.

Relations of Motion and Oxidation.

All animals, from the lowest to the highest, evidence their life by motion at one time or another; and the energy required for this motion is maintained by processes of combustion.

The materials for this combustion, viz. oxygen, and fuel of some sort, or food, are derived from the external medium in which the animal lives; and in order to enable these substances to be available for each part of the animal body, we must have some kind of respiration and circulation going on in it.

In unicellular organisms, consisting of a single mass of protoplasm, the oxygen is derived from the water in which they swim, and both it and the nutritive material derived from the digestion of inclosed masses are circulated through the protoplasm by contractile vacuoles.

In sponges, where the organism no longer consists of one but of several cells united into a community, some of these are furnished with cilia, in order to send a current containing oxygen and food to the other cells having a less favoured position.

In higher animals, where many cells are built up to form one organism, we find a circulatory and respiratory apparatus fully developed.

The medium in which unicellular organisms live is the water in which they swim. The medium in which the cells composing the main parts of the bodies of higher animals, such as man, live, is not the air which surrounds the body, but the intercellular fluid in which the cells themselves are bathed.

As Claude Bernard points out with his usual clearness, the cells of the human body and the lowest unicellular organisms alike live in a liquid medium. From the layer of fluid surrounding it, the cell takes up the oxygen and food which this layer can yield. The supply being exhausted, an unicellular organism can move on elsewhere, but the cells in higher animals, being fixed and unable to move, require fresh portions of oxygen and of nutritive fluid to be brought to them.

This is effected by the slow circulation of the lymph in which the cells themselves are bathed and by the supply to the lymph of oxygen and nutritive material from the blood.

The circulation of the lymph is aided in many lower organisms by the motion of cilia, and this is found persisting in some parts of the higher animals, *e.g.* the central canal of the spinal cord.

Between the blood and the lymph an interchange goes on, oxygen passing from the blood to the lymph or unicellular fluid, and carbonic acid from the lymph to the blood.

This interchange of gases between the blood, the intercellular fluid, and the cells is termed **internal respiration.**

In order to maintain this, a constant current of blood must take place; and when its circulation is locally arrested it becomes deprived of oxygen and loaded with carbonic acid, so that the cells in the district in which the stagnation occurs suffer from local asphyxia, while the other parts of the body may be perfectly healthy.

When the general circulation is arrested by stoppage of the heart, by obstruction of the pulmonary arteries, or by the rupture of an aneurism draining the blood away, the whole body suffers in a similar manner from general asphyxia by the cessation of internal respiration.

If oxygen were simply dissolved in the blood, the quantity which would be conveyed to the tissues would be too small for their wants, and we therefore have as an oxygen-carrier a substance capable of taking up a large quantity of oxygen, of readily forming a loose compound with it, and of again giving off readily to oxidisable substances.

In man and mammals and many of the lower animals this substance is hæmoglobin. In some annelids it is a green substance, chlorocruorin; and in the octopus it is a blue body, hæmocyanin.[1]

In order to remove carbonic acid taken up from the tissues and

[1] For further details *vide Physiological Chemistry*, by A. Gamgee, vol. i. 1880, p 130.

obtain a fresh supply of oxygen, an interchange takes place between the blood and the external air in the lungs; this is **external respiration.** Without any direct influence being exerted upon the cells of the animal body themselves, they may be affected and their **nutrition** greatly **modified** by:

1st. Alterations in the circulation of the intercellular fluid or lymph in which they are bathed.

2nd. In the greater or less rapidity of circulation of blood locally.

3rd. In the circulation generally from changes in the heart and blood-vessels generally.

4th. Changes in the oxygen-carrying power of the blood, either from alterations in its power to take up or give off oxygen.

5th. Changes in the external respiration.

All these conditions may be altered by drugs, or at least by therapeutic measures. Thus the circulation of lymph in a part may be increased by shampooing, and its accumulation in a case of dropsy may be removed by incision, by puncture, or by drainage.

The circulation of blood may be arrested locally and gangrene induced by the continuous use of ergot. It may be increased by the use of local stimulants or irritants.

The circulation generally may be affected by the large class of vascular stimulants and depressants, to be afterwards discussed, and sometimes by stoppage of the pulmonary circulation through minute embola.

Alterations in the oxygen-carrying power of the blood will be discussed presently, and those in the external respiration later on.

Oxidation of Protoplasm.—The movements of protoplasm are intimately connected with processes of oxidation going on in it.

By these processes chemical energy is converted into the mechanical energy exhibited in the movements, and this is sometimes very considerable.

The oxygen which takes part in these processes is not always derived from the surrounding medium at the exact moment when the movements take place; it may have been obtained some time before, and the movements may continue for a little while after all oxygen has been removed.

It therefore appears that protoplasm has the power of absorbing and storing up within itself, in some manner or other, oxygen, which it can afterwards utilise for the purpose of liberating mechanical energy.

This storage of oxygen takes place not only in the protoplasm of unicellular organism, but also in the tissues of the higher animals, *e.g.* the muscles.

The exact way in which storage occurs is not known, but it has been well compared by Professor Ludwig to the storage of oxygen in gunpowder. The oxygen is there contained in the nitrate of potash, a compound which is readily decomposable by

the application of heat, and then gives rise to the evolution of mechanical energy; and this it does perfectly well in an inclosed space, like a gun-barrel, where no air is present.

The power of storing up oxygen is very limited, and although protoplasmic movements continue for a little while after all external oxygen has been removed, yet they will not continue long.

A convenient way of ascertaining this fact has been devised by Kühne, who adds a small quantity of blood or of hæmoglobin solution to a drop of water containing protoplasmic organisms or cells placed on a covering-glass. This is then observed under the microscope with a micro-spectroscope. The hæmoglobin solution exhibits the two bands characteristic of oxy-hæmoglobin. When all the oxygen is removed by means of a stream of hydrogen, kept up for some time, the spectrum of oxy-hæmoglobin passes into that of reduced hæmoglobin.

The occurrence of this change indicates the moment when all the oxygen has disappeared from the liquid. By reckoning from this moment onwards, we are able to estimate the length of time during which the movements continue in the absence of oxygen.

Oxygen-carrying Power of Protoplasm.—Not only does protoplasm possess the power of taking up oxygen readily and assimilating it to itself, but it has also the power of taking up and giving off oxygen to other substances when these substances would be unable to take it themselves.

We may understand this action better by comparing it in a very rough way with that of a man whose greater strength enables him to seize fruit or break off pieces of sweetmeat and give them to his child, which thus enjoys what it could not have obtained for itself, however desirous of them it might be.

Method of Experimenting.—Guaiac resin, when finely divided and oxidised, becomes of a blue colour. It has, however, only a slight power of attracting oxygen to itself from the air, or from water in which the oxygen is dissolved, and thus the blue colour is developed slowly.

On the addition of protoplasm to the water containing the guaiac, the blue colour is developed rapidly. The reason of this possibly is, that the protoplasm has taken up oxygen from the water and given it over to the guaiac. This process reminds us of the action of spongy platinum in causing oxidation of hydrogen or formic acid.

Ozonizing Power of Protoplasm.—It has been supposed that in addition to its power of oxidising such substances as guaiac by giving to them oxygen which it has already taken up, protoplasm has the power of actually breaking up the molecules of oxygen and forming ozone.

The rapid oxidation which protoplasm causes has been attributed to this power. A similar action to this is observed during the slow oxidation of phosphorus. Phosphorus appears to break up the molecule of oxygen, taking to itself one atom and freeing another, which unites with two more in order to form ozone.

Action of Drugs on Oxidation.—A convenient way of testing the effect of drugs upon oxidation is to use the protoplasm of potato, of lettuce, or of dandelion. The most active part of the potato lies just under the skin, as

is seen by pouring some freshly prepared tincture of guaiac over its cut surface. A ring of blue first forms close to the skin, and is always darkest there, although it may extend over the whole of the cut surface. The ammoniated tincture of the British Pharmacopœia will not answer. The tincture must be made with spirit only. When potato is used, the whole of the potato may be pounded with water, or, still better, the peel alone may be cut off and rubbed up with water in a mortar and then filtered through linen. When lettuce or dandelion is



FIG. 8.—Test glasses for examining the action of drugs on oxidation.

used, the fresh leaves are triturated in a mortar with five or ten times their bulk of water, and the solution is then filtered. A row of test-tubes or test-glasses having been prepared, a measured quantity of water is put into the first. In this glass the protoplasm is not mixed with any foreign substance, and it therefore serves as the standard with which to compare the others; and into the others is put a similar quantity of solutions of the drugs to be tested. Each test-glass is distinguished by a label bearing either a number or the name of the drug which it contains attached to it. To each glass a measured quantity of the lettuce-water is added and the contents mixed by shaking. All are allowed to stand for a period varying from a few minutes to some hours. Then a small drop of freshly-prepared tincture of guaiac is added to each, mixed by shaking, and allowed to stand for one or two minutes; the glasses are then arranged in the order of depth of colour.

In this way it is found that many drugs greatly lessen or almost completely abolish the oxidising power of protoplasm, so that while the lettuce-water in the standard-glass assumes a dark-blue colour, that in the others exhibits varying shades of blue, or may even retain the creamy-white colour caused by the guaiac without showing any blue whatever.

The colour is deeper and the reaction is more readily obtained when the tincture of guaiac is mixed with some substance capable of giving off oxygen readily, such as a solution of peroxide of hydrogen in ether, usually called ozonic ether.

A number of experiments made with potato-water by Cash and myself showed that oxidation in potato solution was diminished most powerfully by strychnine, then by quinine and coniine; next by morphine, codeine, cinchonine, and atropine, each of which had almost exactly the same action; next by nicotia, and then by veratrine. Aconitine seemed neither to retard nor accelerate oxidation, and presented exactly the same degree of coloration as the standard solution. Caffeine, picrotoxin, and digitalin appeared somewhat to hasten oxidation (*St. Bartholomew's Hospital Reports*, 1882.)

Action of Drugs on Blood.

The hæmoglobin of blood has also the power of taking up oxygen readily and giving it freely off again. Hæmoglobin free from oxygen, or, as it is sometimes called, **reduced hæmoglobin,** is recognised by the simple band which it gives between D and E, when examined spectroscopically.

Hæmoglobin combined with oxygen, or **oxyhæmoglobin,** gives two bands, situated in nearly the same portion of the field of the

spectroscope. These are separated from one another by a clear space, and are more sharply defined and darker than the spectrum of hæmoglobin.

The oxygen of oxyhæmoglobin may be replaced by other gases. Thus:—**Carbonic oxide** drives out the oxygen from oxyhæmoglobin and forms carbonic oxide hæmoglobin (CO-hæmoglobin). This is a comparatively stable compound. It presents spectroscopic bands nearly the same as those of oxyhæmoglobin, but which are slightly nearer to the violet end of the spectrum. This compound, being stable, circulates in the blood without performing the functions of respiration. It neither takes up oxygen in the lungs nor gives off oxygen to the tissues.

Animals poisoned by CO therefore die of asphyxia, the internal respiration being arrested, and their blood remains for a long time of a florid colour.

Hydrocyanic acid appears also to form a compound with hæmoglobin, which is much less stable than that of carbonic oxide. There has been a good deal of discussion about this compound, and its existence, indeed, has been denied. The spectrum of this compound consists of a single band resembling reduced hæmoglobin but nearer the violet end of the spectrum.

Solutions of hæmoglobin when boiled are completely decomposed into hæmatin and a proteid body or bodies.

Hæmatin gives a single band, which differs according as the solution is alkaline or acid, and according as the solvent is water or ether.

Acids split up hæmoglobin into hæmatin and a proteid. It is sometimes possible to get these to recombine and to again form hæmoglobin, but this is far from being always the case.

Methæmoglobin appears either to be a product of the incomplete decomposition of hæmoglobin or of its excessive oxidation. Some think that it contains more oxygen than hæmoglobin, but less than oxyhæmoglobin. Others think that it is a per-oxyhæmoglobin containing more oxygen than oxyhæmoglobin. At all events the oxygen is more firmly combined in methæmoglobin than it is in oxyhæmoglobin.

This body is distinguished by a spectroscopic band nearly in the same place as that of acid hæmatin.

When the solution is made alkaline by ammonia this band disappears, and is replaced by another fine one near D.

Methæmoglobin appears to be converted again into hæmoglobin by the action of reducing agents and subsequent oxidation. When its solution is treated with reducing agents, it shows the spectrum of reduced hæmoglobin; and on shaking this with air oxyhæmoglobin is formed, as shown by the appearance of its characteristic bands.

When blood is allowed to stand for a length of time, it assumes a brownish colour and gives the bands of methæmoglobin. When

nitrites are mixed with freshly-drawn blood, they impart to it a chocolate colour, and it then exhibits the bands of methæmoglobin.

As the oxygen in methæmoglobin is more firmly combined with it than in oxyhæmoglobin, substances such as the nitrites interfere with internal respiration, and thus in large doses will cause symptoms of asphyxia; but their action differs from that of carbonic oxide in one very important particular, viz., that it is altered by asphyxia, whilst that of carbonic oxide is not. Reducing substances are constantly present in the blood and tissues, and these accumulate to a greater extent during the process of asphyxia. Carbonic-oxide hæmoglobin, being a stable compound, remains unaffected by these, and the blood continues to circulate unchanged.



FIG. 9.—Chart showing the spectroscopic absorption-bands of hæmoglobin and its derivatives. (After McMunn.)

But methæmoglobin, which is produced by the action of the nitrites, becomes reduced by these substances and forms the normal reduced hæmoglobin ordinarily present in venous blood. When this reaches the lungs it again takes up oxygen, forming normal arterial blood, by which the internal respiration is again restored. Thus, unless new supplies of nitrites are constantly added to the blood, the asphyxia they occasion quickly passes away. That caused by carbonic oxide, on the contrary, is much more permanent. It is not removed by artificial respiration, and in order to save the life of the animal or person poisoned by it, a quantity of the poisoned blood must be withdrawn from the veins and healthy blood introduced by transfusion.

A method of ascertaining the effect of drugs on **oxidation** in the **blood** consists in estimating the rate at which **acid** is developed in it after its removal from the body.

In this way Binz and his scholars, Zuntz, Scharrenbroich, and Schulte, have found that both quinine and sodium nitropicrate stop the formation of acid; cinchonine lessens it.[1]

The alterations effected in the **interchange** between **blood** and the **air** have also been observed by simply allowing the blood mixed with the drug to stand for a certain time in a closed receiver, partially filled with air, and afterwards analysing the gases which the receiver contains at the end of the experiment.

By this mode of experimentation, Harley[2] found that hydrocyanic acid diminished or arrested the processes of oxidation in the blood. Alcohol, chloroform, quinine, morphia, nicotin, strychnia, and brucia, all had a similar action, though varying in extent, all of them diminishing both the amount of oxygen absorbed and of carbonic acid given out.

Uric acid and snake poison had a contrary effect, increasing the absorption of oxygen and the evolution of carbonic acid. Curare appeared to lessen the absorption of oxygen, but increased the evolution of carbonic acid. Mercuric chloride lessened the carbonic acid, but increased the absorption of oxygen. Arsenious acid and tartar emetic diminished the absorption of oxygen, but arsenious acid appeared also to lessen the evolution of carbonic acid, while tartar emetic appeared to increase it.

Catalysis.—Fermentation.—Inorganic Ferments.

There are many examples of chemical reactions which only occur between two bodies when a third is present, which may nevertheless be found unchanged at the end of the process. Notwithstanding the fact that the third body is found unchanged at the end of the process, it may have undergone changes during the continuance of the process. Thus alcohol is not converted into ether and water by boiling alone, but it does undergo this conversion by boiling with sulphuric acid. The acid is found unchanged at the end of the process, but is changed during it into ethyl sulphuric acid, which, combining with alcohol, again yields sulphuric acid along with ether.

In other cases, however, we cannot show that the substance has undergone change. Thus starch is converted into dextrin and sugar and cane-sugar into grape-sugar by boiling with acids, but we do not at present know that the acid has undergone any change during the process as it does in the preparation of ether. Peroxide of hydrogen is rapidly decomposed by finely divided platinum or silver, and finely divided platinum will, on the other hand, cause oxygen and hydrogen to unite rapidly. Such actions, where the

[1] A very complete list of the literature of this subject is given by Binz in his work *Das Chinin*, Berlin, 1875.

[2] Harley, *Phil. Trans.* 1865, p. 678.

third substance seems to act by its mere contact with the other substances, and without undergoing change itself, are called **catalytic.** They are probably due to an attraction of some kind bordering both on chemical and physical between the molecules.

Thus some organic substances would resist the oxidising action of the air for a considerable time, but they are readily oxidised by charcoal. It is usually said that the charcoal has the power of attracting oxygen and condensing this gas upon its surface. It does not unite with the oxygen chemically so as to form CO_2, but merely attracts it, holds it for a while, and then gives it off readily to any oxidisable substance. Platinum, palladium, rhodium, and iron absorb hydrogen, palladium doing so to an enormous extent, especially when it is in a spongy form. The hydrogen is supposed by some to be simply condensed within the metal, while others think that the hydrogen and metal unite to form a hydride. The hydrogen is given off from the metal in a nascent form, and has very strong affinities. Thus palladium-hydrogen readily reduces ferric to ferrous salts, the hydrogen taking oxygen from the ferric salt and forming water. But when the hydrogen is liberated from palladium or rhodium in presence of oxygen, it appears to convert the oxygen into ozone, and greatly increases its oxidising power. Thus palladium-hydrogen with oxygen colours a mixture of potassium iodide and starch paste blue, and oxidises hæmoglobin to methæmoglobin and ammonia to nitric acid. Spongy rhodium, or iridium saturated with hydrogen, cause formic acid to be oxidised to carbonate, calcium formate being changed into calcium carbonate. Exactly the same action is possessed by an organic ferment, and in the conversion of the formic into carbonic acid the ferment and the spongy rhodium or iridium are alike unchanged. Spongy platinum, palladium, rhodium, and iridium may thus be regarded as **inorganic ferments.**[1]

Ferments Organic and Organised.

The mechanical energy displayed in the movements of protoplasm is supplied by processes of chemical change, and chiefly of oxidation.

By these processes some of the substances contained in the protoplasm are destroyed, and their place must be supplied by fresh material. This material is obtained from the food, but, in order to render it available for the protoplasm, its atoms must be more or less disintegrated in order that they may again be assimilated. As Hermann very well puts it, the bricks of which the old house is built must be pulled asunder before they can be built up again into the new. In the present case, the bricks are the atoms of protoplasm in some other organism, living or dead, which is

[1] Hoppe-Seyler, *Ber. d. Deutsch. Chem. Gesellsch.* 1883, Feb. 12, p. 117.

being used as food by some larger mass of protoplasm, as, for example, a bacillus which has been absorbed by an amœba. (Fig. 10.)



FIG. 10.—An amœba figured at two different periods during movement. *n*, nucleus; *i*, ingested bacillus.

In order to render the protoplasm in the bacillus available for the nutrition of the amœba, the atoms of which it is composed must be, to some extent, decomposed. This process appears to be effected by enzymes or, as they are sometimes called, organic ferments.

Ferments are bodies which split up carbon compounds at moderate temperatures and lead to the formation of other carbon compounds, most of which are of a simpler constitution than the first.

In this definition we require to introduce the term "moderate temperature," because excessive heat alone will cause the atoms of a complex carbon compound to fly asunder and form simpler compounds, as in the process of dry distillation. A less heat than this, but aided by the action of powerful chemicals, will also produce the same effect. For example, fibrine heated with diluted hydrochloric acid under pressure yields peptones; but the same change is effected at the temperature of the mammalian body by the aid of pepsin. Trypsin from the pancreas effects a similar change when mixed with water alone without the aid of an acid, though its action is certainly aided by alkalies. Neither pepsin nor trypsin are alive, but they contain carbon, and are therefore called **organic ferments.** But this term easily leads to confusion with ordinary living or organised ferments, and so the term **enzymes** has been lately introduced to signify ferments such as diastase, ptyalin, and pepsin, which, though they contain carbon and are therefore called organic, are not alive and have no definite structure or, in other words, are not organised. The term **unformed ferments** has also been applied to them.

By **organised ferments** we mean minute living organisms, which in the course of their life-processes cause decomposition of the substances in which they live. They have also been called **formed** ferments. Examples of these are yeast and bacteria.

The processes of **fermentation** have been divided by Hoppe-Seyler into **two kinds :—**

(1) Those in which water is taken up; and (2) those in which oxygen is transferred from the hydrogen to the carbon atom.

The hydration in the **first** case is produced by the ferment acting either (*a*) like a dilute mineral acid at a high temperature, as in diastatic and investive ferments and in the decomposition of glucosides; or (*b*) like caustic alkalies at a high temperature, as in the splitting up of fats or the decomposition of amide compounds. These processes of fermentation by hydration are chiefly carried on by enzymes.

The **second** class of fermentative changes by the transference of oxygen from the hydrogen to the carbon, as in lactic and alcoholic fermentation and in putrefactive processes, are chiefly produced through the agency of organised ferments. The action of the latter may be to a certain extent imitated by spongy platinum, which absorbs oxygen readily, and readily gives it off again to oxidisable substances. Thus acetic fermentation usually produced by an organised ferment may be also brought about by spongy platinum.

The **products** formed by the action of organised ferments on the media in which they live are poisonous to them; and when these products accumulate above a certain proportion they kill the ferments. Just as a fire will be smothered in its own ashes, or an animal in a confined space will be poisoned by the carbonic acid which it has itself produced, so the yeast plant, when living in a solution of sugar, is killed by the alcohol, which it produces, as soon as this amounts to 20 per cent., and other organised ferments have their lives limited in a similar way.

Action of Drugs on Enzymes.—Although, with the exception of a kind of pepsin in the naked protoplasm of *Æthalium septicum*, a species of myxomycetes,[1] enzymes have not been shown to be present in the protoplasm of the lowest organisms, it is probable that the processes of life in all living beings from the lowest to the highest are carried on by their means. A ferment, which is evidently of the greatest importance in the animal economy, has been recently discovered in the blood by Schmiedeberg. He has given to it the name of Histozyme, and he believes that its function is to split up nitrogenous substances preparatory to their oxidation.[2] The chief enzymes in the animal body are the following:—

Diastatic or Amylolytic	Which convert starch and amyloids into maltose ...	Diastase from malt. Ptyalin from saliva. Amylopsin from pancreas. Other ferments having a similar action from other parts of the body.
	Which convert maltose into glucose	From small intestine.

[1] Krukenberg, *Untersuch. a. d. physiol. Inst. d. Univ. Heidelberg*, Bd. II. 1878, p. 273.

[2] Schmiedeberg, *Arch. f. exper. Path. u. Pharm.* Bd. xiv. s. 379.

- **Inversive Ferments**
  - Which convert cane sugar into dextrose and levulose
    - Invertin from the intestinal juice.
    - ,, ,, mucin of the mouth.
    - ,, ,, tissue of the testis.
  - Which decompose glucosides
    - Emulsin from bitter almonds.
    - Myrosin from mustard.
- Decomposing sugar ..... Rennet.
- Decomposing fats .....
  - From stomach.
  - From pancreas (Stearopsin).
- **Proteolytic Ferments**
  - Which decompose proteids and form peptones .....
    - Pepsin from stomach.
    - Trypsin from pancreas.
    - Others from saliva.
    - Histozyme.

The action of drugs on enzymes is ascertained by taking two portions of a solution containing the enzyme and the substance to be acted upon. To one of these a quantity of the drug to be tested is added, the other acts as a standard with which to compare it. If the drug is in solution, a corresponding quantity of water must be added to the standard solution in order that both may be alike. They are then placed in a warm chamber and the rapidity of digestion is noted.

The action of some of the more important drugs on the action of enzymes will be readily seen from the following table from Wernitz, quoted by Meyer.[1] In it the proportion is shown of the drugs which arrest in watery solution the action of enzymes; thus, one part of chlorine in 8,540 parts of a watery solution will arrest the action of ptyalin upon starch paste, while creasote has no action on it even in saturated solution, and corrosive sublimate is so enormously destructive as to arrest its action, even in one part in 52,000.

[1] Hermann Meyer, "Ueber das Milchsäureferment u. sein Verhalten gegen Antiseptica," *Inaug. Diss.* Dorpat, 1880.

	Emulsin.	Myrosin.	Diastase.	Invertin.	Ptyalin.	Pepsin.	Pancreatin.	Rennet.
Chlorine	1:35614	1:38888	1:7411	1:5980	1.8540	1:27167	—	—
Corrosive sublimate... ...	1:65000	1:13000	1:50000	1:17500	1.52000	1:1766	1:21600	1:720
Iodine	1:5500	1:24070	1:4125	1:1000	1.4166	1:7817	—	—
Hydrochloric acid	—	—	—	—	—	—	—	—
Eucalyptus oil	1:100	Acted only in excess.		—	—	—	—	—
Bromine	1·12654	1:28490	1:5070	1:2840	1:5580	1:16777	—	1:31100
Mustard oil...	Only lessens action in saturated solution.			—	—	—	—	—
Copper sulphate	1:11000	1:8100	1:6500	—	1:7500	1:110	1:6600	1:200 Has no action.
Salicylic acid	1:7600	1:2600	1:5100	1:166	1:1250	1:250	1:9000	1:333 No action.
Sulphurous acid	1:21666	1:20485	1:8600	1:1940	1:8600	1:1317	—	—
Benzoic acid	1:2100	1:1100	1:1025	1:400	1:2600	1:200	1:2600	1:300 Has no action.
Chloride of lime	1:36713	1:34333	1.6613	1:4950	1:6613	—	—	1·28400
Creasote	1:60	No action even in saturated solution.				1:65	—	—
Thymol	1:100	Slight action, or none, even in saturated solution.				—	—	—
Carbolic acid	1:20	1:33	1:30	1:34	1:25	1:50	—	1:100
Borax	1:100	1:110	1:100	1:3580	1:100	—	—	1:1000
Benzoate of soda	1:100	1:20 Only weakens	1:100	1:65	1:86	—	—	1:50
Turpentine water	1:2	—	—	—	—	—	—	—
Chloroform...	Little or no action, even in saturated solution.			—	—	1.60	—	—
Alcohol	1:28	1:35	1:3	1:10	—	1:6	1:3	—
Glycerine	1:3	1.2	1:2 Weakens.	1:2 Weakens.	1:3 Weakens only.	1:3	—	—
Acetate of aluminium ...	1:50 Weakens.	1:50 No action.	1:380 No action.	1:100 Weakens.	No action.	—	—	—

The different action which the same drug exerts upon formed and unformed ferments is of great importance, because upon it depends our power to use the drug in medicine. Thus creasote, which appears from the preceding table not to destroy the digestive power of ptyalin and to have but a weak action upon that of pepsin, has been found by Werneke to destroy yeast in a dilution of one part to 500 of water: and by Bucholtz to kill bacteria in a dilution of one part to 1,000 of water. This difference enables us to arrest fermentation in the stomach depending on the presence of low organisms, while the digestive action of the pepsin is not interfered with, or only very slightly. The following diagram shows the action of drugs on enzymes and on the lactic ferment, which is a bacillus :—



FIG. 11.—Diagram to show the different action of drugs on different enzymes. The nature of the line showing the action of each drug is shown under its name.

Zymogens.

As several enzymes act readily in neutral or slightly alkaline fluids, it is evident that if they existed free in every part of the animal body, they would soon lead to its speedy destruction. Accordingly, we find that they do not normally exist free, except at the times and places they are required.

This fact was first discovered by Kühne in relation both to the stomach and pancreas, and was announced by him in the course of lectures which he delivered at Amsterdam in 1868-69, which I attended. In my note-books of those lectures I find that he stated that there seems to exist "a pepsin-giving substance," because if a "slice of stomach is thrown directly into dilute HCl of 4 parts to 1,000 of water at 40° C. no digestion takes place,"[1] a fact which shows that pepsin is not always present in it. In regard to the pancreas, he not only recognised the existence of a ferment-yielding body, but described a mode of obtaining ferment from it in the following words:—"Glands which have no action on fibrine can be made active by digesting in very dilute acid and then neutralising or alkalising, there seeming to exist a *ferment-forming* substance in the pancreas."

Kühne's discovery of the existence of ferment-yielding bodies does not seem to have become widely known, and it was again made independently by Liversedge[2] in regard to the amylolytic ferment of the pancreas, and by Heidenhain in regard to trypsin. These observers found that when glands which did not contain ferment were exposed to the air ferments were formed.

Heidenhain[3] also investigated more fully these ferment-forming substances, and gave to them the name of zymogens.

The methods by which we **obtain ferments from zymogens** are, therefore, exposure to air and treatment with acids.

Organised Ferments.

The chief organised ferments are the **yeast** plant, which produces alcohol and carbonic acid from grape sugar, and various kinds of **bacteria,** one of which produces butyric, another lactic, and another acetic fermentation. Both yeast and bacteria belong to the lowest class of plants, the protophytes. To this class also belong moulds, the action of drugs upon which is sometimes important, inasmuch as moulds give rise to some skin diseases.

Yeasts, moulds, and bacteria have been variously classified by different authors, and the classification is apt to undergo changes as our knowledge of the life-history of these different organisms increases.

At present it is not certainly known whether the various kinds of bacteria, for example, are genetically or specifically different, or whether they can, by altered cultivation, be transformed into one another or not.

[1] Just after this there is unfortunately a blank in my notes, but Professor Kühne has kindly supplied the deficiency, and informs me that he was then speaking of slices taken from the external surface of the stomach, and therefore containing the lower ends only of the gastric glands.

[2] Liversedge (Nov. 1872), *Journ. of Anat. and Physiol.* Nov. 1873, p. 23.

[3] Heidenhain, *Pflüger's Archiv,* Bd. xi. p. 557.

Koch, who has cultivated them by the dry process on gelatine instead of in liquid, and has thus been able to avoid admixture of different kinds of bacteria, has come to the conclusion that each kind possesses distinctive characters; but Klein has shown that even when cultivated in this way bacteria may vary much in form. Thus the bacillus anthracis may form torula-like cells, from which ordinary bacilli are again produced. The numerous names used in treatises on the subject of organised ferments are apt to lead to confusion, hence some of the names are given here simply for the purpose of reference. Thus Brefeld's classification is:—

(1) Phycomycetes = algoid fungi; (2) Mycomycetes = true higher fungi; (3) Myxomycetes = gelatinous fungi; (4) Blastomycetes = yeast fungi; (5) Schizomycetes = bacteria.

Although the classification on the following page may not be botanically correct, it is convenient for our present purpose.

Yeasts.—The yeast plant, to which various names have been given, as torula cerevisiæ, saccharomyces, consists of ovoid cells, which multiply by budding. The buds may remain attached, forming torula-chains, but when they attain the size of the parent cell they fall off and begin to multiply anew. When placed in saccharine solutions the plant decomposes the sugar during the process of growth and forms alcohol and carbonic acid.

In this process oxygen is usually absorbed from the air in considerable quantities, but fermentation can occur in saccharine solutions even when oxygen is excluded, though under such conditions the torula grows slowly. When plenty of oxygen is present, and the layer of fluid shallow, the torula grows luxuriously, but there is very little fermentative change; while, on the other hand, when free oxygen is excluded the torula grows slowly, but there is marked fermentation.

Another plant nearly allied to yeast is the mycoderma vini, the ferment which changes alcohol into acetic acid. The mycoderma is not regarded by Naegeli as a species distinct from torula, and it is considered by Grawitz to be the same as the fungus found in the aphthous patches which occur about the mouth and throat of children suffering from thrush, although this fungus is usually said to be an oïdium.

To test the action of drugs on alcoholic fermentation, equal quantities of a solution of grape sugar with yeast are introduced into two test tubes, and to one of them a little of the substance to be tried is added. These are then inverted over mercury and kept in a warm place for several days. The amount of gas developed is then measured, and the power of the drug to prevent fermentation is estimated by the diminution in the amount of carbonic acid produced as compared with the standard.

Mould Fungi, or **Hyphomycetes.**—These form long filaments or hyphæ, which become agglomerated into a mycelium or mass of compact tufts. They multiply not only by gemmation, but by the formation of spores.

FIG. 12.

Blastomycetes, or Yeasts ..... } ..... { Torula, or Saccharomyces (Fig. 12), or Mycoderma.



FIG. 13.

Hyphomycetes, or Moulds..... } ..... { Mucor. Penicillium. Oïdium. Achorion. Trichophyton. Microsporon.



FIG. 14.

Schizomycetes, or Bacteria..... {

Sphaerobacteria (globular cells)..... ... } Micrococcus (1 (*a* & *b*) & 2, Fig. 14).
Sarcina (3).

Microbacteria, or Bacteria proper (small, rod-like cells)..... } Bacterium..... { Bacterium termo (4). B. lineola (5).

Desmobacteria, or Filobacteria (larger rod-like or thread-like cells)..... } Bacillus (straight) ..... { B. subtilis (6). B. anthracis (7) B. septicæmia. B. malariæ (8). B. tuberculosis (12). B. lepræ.

Vibrio (wavy) ..... Vibrio serpens (9)

Spirobacteria (twisted or spiral cells)..... { Spirochæta (long, flexible, close-wound spirals) ..... } Spirochæta Obermeyeri (10).
Spirillum (short, stiff, open spirals) ..... } S. volutans (11).

These moulds vary considerably according to the soil in which they grow, and the amount of oxygen present. Thus, if the spores of the common white mould, mucor mucedo, are sown in a liquid containing sugar and exposed to the air, they grow on the surface, forming branched hyphæ without septa, and the liquid absorbs oxygen. But if the mycelium be immersed, or the oxygen withdrawn, septa develop in the hyphæ, and they break up into segments which multiply by budding, forming a kind of yeast with large cells, and, like the true yeast, decomposing sugar into alcohol and carbonic acid.

They may be trained to thrive on substances on which they do not usually grow by gradually altering the composition of the soil. Thus, the commonest of all moulds, penicillium glaucum, although it does not usually grow on blood, may be trained to do so by transplanting it from bread to peptone, and then to blood.

Heat destroys them, but a much higher temperature is required to kill the spores than the perfect plant, and in order to destroy the spores a temperature of 110°—115° C., kept up for an hour, is requisite.

The mould fungi cause some local diseases in the body, and especially skin diseases such as favus, tinea tonsurans, tinea versicolor, tinea sycosis, and onychomycosis, and the madura foot or fungus foot of India. They also occur in the fur of the tongue.

Bacteria, or **Schizomycetes.**—Bacteria are every day becoming more and more important on account of the relation in which they are found to stand to various **diseases.** Anthrax, diphtheria, phthisis and typhoid fever, are probably all due to various species of bacteria introduced into the body, and affecting various organs in it. It is, therefore, of the greatest possible importance that their life history should be learned, and that we should know what the conditions are under which they thrive best, and what the conditions are which will destroy their life and prevent their development.

They appear to increase in two ways: First, by simple multiplication of their parts, and secondly, by forming spores.

Bacteria require water, organic matter and salts, for their life. Some of them also require the presence of free oxygen, others do not, hence they have been divided by Pasteur into two classes: **aërobious** and **anaërobious.** To the anaërobious bacteria oxygen is not merely unnecessary but hurtful, and even the aërobious bacteria, although they require oxygen in a certain quantity, are injured or destroyed by it when it is in excess.

The soil which is most favourable to different classes of bacteria varies with each class. A **struggle for existence** goes on between bacteria and other organised ferments, and between different kinds of bacteria themselves, just as it does amongst higher plants. Just as an abundant crop of one kind of higher plants will occupy a whole field and choke other plants, so that kind of bacterium which grows most readily in a particular soil

will choke others and prevent them growing at the same time with itself. During their growth they alter the soil or substance in which they grow, either by exhausting the nutriment it affords, or by forming in it new substances which are injurious to themselves, and thus they gradually die out.

But the soil which is no longer suitable for one kind of bacterium then becomes suitable for another, and the spores, which may have lain without germinating during the time the first kind was growing, now begin to grow actively.

Thus, if a number of germs of different classes of fungi be added at the same time to a saccharine solution, the bacteria only will grow and set up lactic fermentation. If a small quantity of tartaric acid be now added ($\frac{1}{2}$ per cent) the yeast alone will grow and alcoholic fermentation begins. If more lactic acid is added (4—5 per cent) the alcoholic fermentation stops, and mould begins to grow. In this process neither the bacteria nor the yeast are killed by the addition of tartaric acid, which, in different proportions, merely renders the liquid more favourable for the growth of the yeast and mould respectively, and enables them to flourish best, although the others are still present.

In fresh grape juice many germs are present, but the composition of the liquid being more favourable to the growth of the yeast plant than to other fungi, it alone grows. When it has converted the sugar into alcohol its growth stops, and bacteria may then multiply and convert the alcohol into acetic acid. This in turn checks the growth of the bacteria, and mould fungi then find the soil favourable. In their growth they consume the lactic acid, and the liquid once more affords a favourable soil for bacteria, which may then grow and cause putrefaction.

The same struggle for existence occurs between the different species of bacteria themselves. Thus micrococci may be prevented from growing by micro-bacteria, and bacilli may be killed by bacterium termo when the supply of oxygen is insufficient for both.[1]

It is to be noted, however, that in the struggle for existence the formation of poisonous products by bacteria may be, and probably is, beneficial to them. No doubt these poisonous products check their own growth and finally destroy them; but in the struggle for existence between bacteria and living tissues these poisons may be beneficial to the bacteria by killing the tissues, and thus giving the bacteria a more ample supply of nutriment.

In investigating any problem it is always best to take the simplest case, and if we look at the struggle for existence between bacilli and an amœba, or white blood-corpuscle, we shall see that the formation of poisonous products by the bacteria may enable them to destroy the amœba or leucocyte instead of their being destroyed by it (Fig. 10, p. 60).

[1] Ziegler's *Pathological Anatomy*, translated and edited by MacAlister, p. 272. This work contains a very lucid and complete account of disease-germs.

These **poisonous products** in fact may prepare the soil for bacteria, and this supposition is confirmed by the observations of Rossbach and Rosenberger. Rossbach found that when papain was injected into the vessels, micrococci developed in the blood with extraordinary rapidity, the ferment seeming to have altered the blood to such an extent that it became an exceptionally favourable soil for the micrococci. A similar result was observed by Rosenberger from the injection of sterilised septic blood. In this blood the bacteria themselves were destroyed, but the poisonous substances which they had formed were present, and these seemed to have a similar action to the papain.

The **septic poisoning** which occurs from wounds is not due merely to bacteria entering the blood from them, but is due chiefly to the absorption of the poisons which the bacteria have formed in the wound. The dead or enfeebled tissues which occur in the wound afford a soil favourable to the growth of the bacteria, and for the formation of their deadly products. When these are absorbed they not only poison the tissues generally, but, by doing so, convert the whole body into a soil suitable for the growth and development of bacteria, as is shown by the fact that the tissues of animals killed by the injection of sepsin decompose very quickly, and swarm with bacteria shortly after death.

Action of Drugs on the Movements of Bacteria.

Mode of Experimenting.—In order to test the effect of a drug on the movements of bacteria already developed, a drop of the solution containing bacteria may be mixed under the microscope with a drop of the solution of a drug in the way already described at page 49, and the strength of solution necessary to destroy their movements estimated in the same manner.

In order to combine experiments on the movements, and on the reproduction, so as to ascertain whether the bacteria which have been rendered motionless by heat or drugs, are really dead, or are only torpid, the covering-glass in the experiment just described is taken up with a pair of sterilised forceps, and dropped into some sterilised Cohn's solution (*vide* p. 72). It is then put along with the standard solution into a warm chamber, and left for a day or two. If the bacteria have been destroyed, it will remain clear like the standard solution, but if they have only become torpid, it will be more or less opalescent or milky.

In performing this experiment, great care must be taken that the solution of the drug has been sterilised by boiling ; and that the covering-glass, glass slide, all the instruments, and indeed everything used in the experiments, have been also thoroughly sterilised by heating.

The bacteria grown in different fluids are not all equally sensitive to drugs.

A **temperature** of 66° to 70° C. usually arrests the movements of bacteria, and if continued for an hour destroys adult organisms though not spores. A temperature of 100° C. usually destroys the spores as well, but this is not always the case.

If the bacteria are moist, this temperature generally kills them, but not if they happen to be dry, and a much higher temperature is then required. They may become dry, before being killed, by a little solution containing them having flowed or spurted into the higher part of the tube or flask, where the water evaporates and leaves them dry before the temperature has been sufficiently raised to destroy them.

The most destructive substances to bacteria are corrosive sublimate, chlorine, bromine, and iodine. Quinine and the other cinchona alkaloids also destroy bacteria, their power diminishing in the following order:—quinia, quinidia, and lastly cinchonia.

Bebeerin is nearly as powerful, and potassic picrate is even superior to quinine when used with Cohn's solution. When bacteria are cultivated in beef-tea instead of Cohn's solution, potassic picrate is less powerful.

Sulphocarbolates and strychnia have considerable power though a good deal less than quinia, bebeerin and æsculin have hardly any power to destroy bacteria at all. Sodic hyposulphite has very little action; sodic sulphate has a destructive action, but it is about ten times less strong than quinine.

Action of Drugs on the Reproduction of Bacteria in general.

The spores of bacteria have very enormous resisting power to agents destructive of vitality, very much greater than that of the fully-developed bacteria; and thus it happens that a quantity of an antiseptic, which is quite sufficient not only to prevent the spores of bacteria from developing so long as they remain in it, but to destroy fully-formed bacteria, will not destroy the vitality of the spores or hinder them from germinating as soon as they are removed from the influence of the antiseptic and transferred to a proper soil.

Yet the power to destroy the vitality of the spores completely is what is required in an antiseptic, for we wish to destroy the infectious material, and prevent it from causing disease, rather than to administer substances to an animal which will hinder the germs from developing in the blood after their introduction into it; although this may be desirable when infection has already taken place.

It is therefore necessary to test the effect of drugs in destroying the germs completely.

Method of Experimenting.—This is done by adding to a fluid, containing bacteria and their spores, varying quantities of an antiseptic, and allowing the mixture to stand for a longer or shorter time. A drop of this fluid is then introduced by a sterilised platinum wire or glass pipette into some sterilised

Cohn's fluid or beef-tea. This is watched to see whether bacteria will develop in it or not. If they do develop, it is clear that the spores have not been killed by the admixture with the disinfectant in the original fluid, if they do not develop, then the disinfectant has been sufficiently powerful to destroy them.

The plan usually employed is to take a number of test-tubes, plug their orifices with cotton-wool, and destroy any germs that may be attached to them by thoroughly heating them to about 300° F. in a hot chamber, or in the flame of a Bunsen's lamp. They are then allowed to cool, and a small quantity of a liquid (about 5 cc.) in which bacteria readily grow is placed in each. This also must be previously thoroughly boiled, in order to destroy any germs which may be present in it. The **liquid** recommended by **Cohn** consists of ammonium tartrate one gramme, potassic phosphate and magnesic sulphate of each five grammes, calcic phosphate ·05 grammes, distilled water 100 cc. This is filtered and boiled before use. To the tubes the different agents to be tested are added, the solutions of each having been carefully sterilised by boiling, and the pipette used being super-heated in each case before it is employed. If the drugs are added in solution, a similar quantity of boiled water must be added to the first tube, which is to serve as a standard. To each of them is then added a single drop of a liquid containing bacteria.

The mouths of the tubes are then stopped with the cotton-wool and placed for a few days in a warm chamber at about 40° C. The standard liquid will then be found to be opalescent or milky. The degree of the opalescence in the other tubes will be less according to the effect of the drug which has been added, in preventing the development of bacteria.

Where it has completely hindered the development, the solution will remain quite clear, and as its strength diminishes, the opalescence will become greater until it is equal to that of the standard.

In performing this experiment it is best to use one definite form of bacterium, instead of a mixture of several unknown kinds. This is referred to again in speaking of the experiments of Dr. Koch, who generally employs the micrococcus prodigiosus as an example of an organism easily acted upon, and the spores of bacillus anthracis, or of a bacillus found in earth, as examples of resistant ones.

It is found by this mode of experiment that a smaller quantity of **poison** will prevent the development of bacteria than will destroy them after they are developed.

By experiments on the comparative action of different drugs on bacteria the results contained in the following table have been obtained by N. de la Croix, and these have been to a considerable extent confirmed by Koch.

It will be seen by looking at the table that the exact limit of the power of each drug to destroy bacteria is not determined, but that two concentrations of each antiseptic are given, one of which is sufficient to do it, and the other is insufficient. The disinfecting limit therefore lies between the two experiments. But the limit of disinfection is not an invariable one for each drug, as its power to destroy bacteria is modified not only by the concentration of the solution employed, but by the length of **time** during which it acts, and by the **temperature.**

	Prevent the development of bacteria taken from meat infusion.	Do not.	Prevent the reproduction of undeveloped bacteria.	Do not.	Kill developed bacteria.	Do not.	Prevent the reproduction of developed bacteria.	Do not.	Prevent development of spores in boiled meat infusion.	Do not.	Prevent reproduction of spores.	Do not.	Prevent development of spores in unboiled meat infusion.	Do not.	Prevent reproduction.	Do not.
Corrosive sublimate . .	1:25250	1:50250	1:10250	1:12750	1:5805	1:6500	1:1250	1:5250	1:10250	1:12750	1:6500	1:10250	1:7168	1:8358	1:2525	1:3358
Chlorine	1:30208	1:37649	1:4911	1:6824	1:22768	1:30208	1:431	1:460	1:28881	1:34589	1:1008	1:1027	1:15606	1:23182	1:1061	1:1364
Chlorinated lime . . .	1:11135	1:13092	1:488	1:578	1:3720	1:4460	1:170	1:258	1:3148	1:4716	1:109	1:134	1:286	1:519	1:153	1:286
Sulphurous acid . . .	1:5448	1:8515	1:135	1:223	1:2009	1:4985	1:190	1:273	1:8515	1:12649	1:325	1:422	1:12649	1:16782	1:135	1:223
Bromine	1:6308	1:7844	1:769	1:1012	1:2550	1:4050	1:336	1:550	1:13931	1:20875	1:493	1:603	1:5597	1:8875	1:875	1:1153
Sulphuric acid	1:5734	1:8020	1:205	1:306	1:2020	1:3355	1:116	1:205	1:5734	1:8020	1:306	1:420	1:3353	1:5734	1:72	1:116
Iodine	1:5020	1:6687	—	1:2010	1:1548	1:2010	1:410	1:510	1:10020	1:20020	1:510	1:724	1:2010	1:2867	1:843	1:919
Aluminium acetate . . .	1:4268	1:5435	1:59	1:80	1:427	1:585	1:64	1:92	1:4268	1:4778	1:937	1:1244	1:6310	1:7535	1:478	1:584
Oil of mustard	1:3353	1:5734	1:220	1:306	1:591	1:820	1:28	1:40	1:3353	1:5734	1:77 ?	1:108 ?	1:3353	1:5734	1:40 ?	1:60 ?
Benzoic acid	1:2867	1:4020	1:50	1:77	1:410	1:510	1:121	1:210	1:2877	1:4020	1:50	1:77	1:1439	1:2010	1:77	1:121
Borosalicylate of soda .	1:2860	1:3777	1:303	1:394	1:72	1:110	1:30	1:50	1:1343	1:1694	1:35	1:50	1:2860	1:3777	1:35	1:50
Picric acid	1:2005	1:3041	1:706	1:841	1:1001	1:1483	1:150	1:200	1:2005	1:3041	1:200	1:300	1:2005	1:3041	1:100	1:117
Thymol	1:1340	1:2229	1:109	1:212	1:109	1:212	1:20	1:36	1:1340	1:2229	1:109	1:212	1:1340	1:2229	1:20	1:36
Salicylic acid	1:1003	1:1121	1:343	1:454	1:60	1:78	—	1:35	1:3003	1:6004	1:603	1:1003	1:1121	1:1677	1:343	1:450
Permanganate of potash .	1:1001	1:1433	1:100	1:150	1:150	1:200	1:150	1:200	1:2005	1:3041	1:101	1:150	1:300	1:403	1:35	1:50
Carbolic acid	1:669	1:1002	1:22	1:42	1:22	1:42	1:266	1:4	1:402	1:502	1:22	1:42	1:502	1:669	—	1:10
Chloroform	1:90	1:112	—	1:03	1:112	1:134	—	1:08	—	—	—	—	1:103	1:134	—	1:122
Borax	1:62	1:77	—	1:14	1:48	1:69	—	1:12	1:30	1:43	—	1:14	1:107	1:161	—	1:37
Alcohol	1:21	1:35	1:44	1:8	1:44	1:6	—	1:118	1:11	1:21	1:177	1:203	1:21	1:30	—	1:142
Eucalyptol	1:14	1:20	—	1:203	1:116	1:205	—	1:583	1:20	1:29	—	1:14	1:205	1:308	—	1:30
Chlorate of potash . .	—	1:30	—	—	—	—	—	—	—	—	—	—	1:13	—	—	—

Action of Drugs on particular species of Bacilli.

In these experiments of De la Croix, however, the nature of the bacteria experimented on was not determined, and there might be a mixture of several sorts. Koch has therefore sought to ascertain the action of disinfectants upon definite forms of microzymes by cultivating them in pure crops before applying the disinfectant. Those which he has chiefly experimented on are the red micrococcus prodigiosus, the bacteria of blue pus, and the bacillus anthracis.

The first two do not form spores, and are easily destroyed by disinfectants. The bacillus anthracis forms spores, and was therefore employed to test the action of disinfectants upon them.

Mode of Experimenting on the Action of Drugs on Reproduction of Bacilli.—In order to avoid admixture with other species, Koch cultivated the first two on slices of potato, instead of in a solution. Upon one piece of potato the unaltered microzymes were sown, and upon the others similar microzymes which had been exposed to the action of disinfectants. If the microzymes had been destroyed by the disinfectants, no result occurred, but if not, then a crop was obtained, which in comparison with the control specimen was more or less abundant, according as the action of the disinfectant had been less or more complete.

For the cultivation of the anthrax bacilli, Koch used as a soil gelatine mixed with some other nutritive substance, usually meat infusion and peptone sterilised and spread upon a slip of purified glass, and exposed to such a heat as just to solidify it. Koch did not use his solidified blood-serum in these experiments. This could be placed under the microscope, and the growth of bacilli observed from day to day. Middle-sized test-tubes were then partially filled with the disinfecting solutions, and silk threads, steeped in a fluid containing bacilli and then dried, were placed in them; from time to time a thread was removed from the tubes by means of a previously heated platinum wire and placed on the slide, which was then subjected to microscopical observation. In this way it was easy to determine what strength of solution, and what time of exposure to its action, was required to destroy the spores.

The results of experiments made in this way with carbolic acid were very surprising. It was to be expected that carbolic acid would readily destroy the spores, but this was not the case. A 1 per cent. watery solution had almost no action upon them even after they had been exposed to it for 15 days; 2 per cent. slightly retarded their growth, but it did nothing more; 3 per cent. killed the spores in 7 days; 4 per cent. in 3 days; and 5 per cent. in 1 day.

This comparatively slight action of carbolic acid on spores and the long time that it requires to destroy them, shows that it cannot be relied upon as a universal disinfectant. But it has nevertheless great power in destroying microzymes which have not formed spores.

The fresh blood of an animal which has died from anthrax contains only bacilli and no spores. When it is mixed with its own bulk of a 1 per cent. solution of carbolic acid, it can very soon

afterwards be injected into an animal without producing almost any symptoms. A $\frac{1}{2}$ per cent. solution will not do this, so that the limit lies between ·5 and ·25 per cent. for the mixture.

The action of carbolic acid on other fully-developed microzymes, or on the spores, is almost the same as on the anthrax bacilli.

The following table gives the result of Koch's experiments with other substances; the figures indicating the number of days during which the spores had been submitted to the action of the antiseptic previous to cultivation. The black-faced figures indicate that the spores were destroyed, and their germination prevented by exposure to the disinfectant for that number of days; a * indicates that their vitality was diminished, and that the crop from them was scanty; a † indicates that their growth was retarded; *† that it was both scanty and retarded. The disinfectants are divided into three groups. The first contains the group of fluids; the second of solutions in water; and the third of solutions in alcohol, ether, or oil.

GROUP I.—FLUIDS.

Distilled water	7	15	20	35	90						
Alcohol (absolute)	1	3	5	10	12	20	30	40	50	65	110
Alcohol (1 to 1 of water) ...	1	3	20	30	40	50	65	110			
Alcohol (1 to 2 of water) ...	1	3	20	30	40	50	65	110			
Ether	1	5	8*	**30**							
Acetone	2	5*									
Glycerine	1	3	10	20	30	40	50	65	110		
Butyric acid	1	5									
French salad oil	5	30	90								
Bisulphide of carbon	1	5	10	20							
Chloroform	1	3	10	20	100						
Benzol	1	5	10	20							
Petroleum ether	1	5									
Turpentine oil	1*	**5**	**10**								

GROUP II.—SOLUTIONS IN WATER.

Chlorine water (freshly made)	**1**	**5**					
Bromine (2 p. c. in water)	**1**	**5**					
Iodine water (1 in 7,000)	**1**						
Hydrochloric acid (2 p. c. in water)	1	5	**10**				
Ammonia	1	5	10				
Ammonium chloride (5 p. c. in water)	1	5	10	25			
Common salt (saturated solution)	1	5	10	20	0		
Calcium chloride (saturated solution)	1	5	20	40			
Barium chloride (5 p. c. in water)	5	10	45	100			
Ferric chloride (5 p. c. in water)	2†	**6**					
Potassium bromide (5 p. c. in water)	5	10	25				
Potassium iodide (5 p. c. in water)	5	10	25	80			
Corrosive sublimate (1 p. c. in water)	**1**	**2**					
Arsenic (1 p. c. in water)	1	6	**10**				
Lime water	5	10	15*†	20*†			
Chloride of lime (5 p. c. in water)	1†	2*†	**5**				
Sulphuric acid (1 p. c. in water)	1	3	10*	20*			
Zinc sulphate (5 p. c. in water)	1	5*	10*				
Copper sulphate (5 p. c. in water)	1	5*	10*				
Ferrous sulphate (5 p. c. in water)	2	6					
Sulphate of aluminium (5 p. c. in water)	1	5	12				
Alum (4 p. c. in water)	1	5	12				

Potassium chromate (5 p. c. in water)	1	2				
Potassium bichromate (5 p. c. in water)	1	2				
Chrome alum (5 p. c. in water)	1	2				
Chromic acid (1 p. c. in water)	1	2				
Potassium permanganate (5 p. c. in water)	**1**					
Do. do. (1 p. c. in water)	1	2				
Potassium chlorate (5 p. c. in water)	2	6				
Osmic acid (1 p. c. in water)	**1**					
Boracic acid (5 p. c. in water) not quite dissolved	1	2	6†	10†		
Borax (5 p. c. in water)	5	10	15			
Sulphuretted hydrogen water	1	5*				
Ammonium sulphide	1	2	**5**			
Oil of mustard with water	1	5	10*			
Formic acid (sp. gr. 1·120)	1	2	**4**	**10**		
Acetic acid (5 p. c. in water)	1	5				
Potassium acetate (saturated solution)	1	4	10			
Lead acetate (5 p. c. in water)	1	5	12			
Soft (potash) soap (2 p. c. in water)	1	5	12			
Lactic acid (5 p. c. in water)	1	2	5			
Tannin (5 p. c. in water)	1	5	10			
Trimethylamine (5 p. c. in water)	1	5	12			
Chloropicrin (5 p. c. in water)	1	2	**6**	**12**		
Benzoic acid (saturated solution in water)	1	5	10	45	90	
Benzoate of sodium (5 p. c. in water)	1	2	5	10		
Cinnamic acid (2 p. c. in water 60 and alcohol 40 parts)	1	3	5	10		
Indol (in excess in water)	1	5	10	25	80	
Skatol (in excess in water)	1	5	10	25	80	
Leucin (½ p. c. in water)	1	5	10			
Quinine (2 p. c. in water and 40 alcohol 60 parts)	1*†	5*†				
Quinine (1 p. c. in water with HCl)	1	5	**10**			

GROUP III.—SOLUTIONS IN ALCOHOL, OR ETHER, OR OIL.

Iodine (1 p. c. in alcohol)	1*	2*				
Valerianic acid (5 p. c. in ether)	1	5				
Palmitic acid (5 p. c. in ether)	1	5				
Stearic acid (5 p. c. in ether)	1	5				
Oleic acid (5 p. c. in ether)	1	5				
Xylol (5 p. c. in alcohol)	1	5	30	50	90	
Thymol (5 p. c. in alcohol)	1	6	10	15		
Salicylic acid (5 p. c. in alcohol)	1	6	10	15		
Salicylic acid (2 p. c. in oil)	5	10	20	80		
Oleum animale (Dippel's oil, 5 p. c. in alcohol)	1	5	12			
Ol. menth. pip. (5 p. c. in alcohol)	1	5	12			

From this table it appears that the ordinary method of separating between formed and unformed ferments by precipitation with alcohol and solution in glycerine cannot be relied upon as a trustworthy means of separating them, since neither alcohol nor glycerine destroy the activity of formed ferments.

It is remarkable that ether and turpentine oil, which are both ozone carriers, should have such a marked action in comparison with other fluids. This is in harmony with some recent observations of Paul Bert and Regnard, that oxygenated water in sufficient quantity destroys the bacteria of anthrax.

The spores of anthrax bacilli resist in an extraordinary way the action of certain substances which usually are fatal to life, as hydrochloric acid (2 per cent.), salicylic acid (1 per cent.), concentrated

solutions of chloride of sodium, chloride of calcium, metallic solutions, borax, boracic acid, chloride of potassium, benzoic acid, benzoate of sodium, cinnamic acid, and quinine.

Action of Drugs on the Development and Growth of Bacilli.—In order to test the action of disinfectants on the development and growth of bacteria, Koch put into a number of small watch-glasses, or rather crystallisation glasses with flat bottoms, a few drops of blood-serum, or a solution of extract of meat and peptone, mixed with varying quantities of the disinfectant. Into each of these a silk thread, which had been dipped in the fluid containing bacteria and dried, was placed. In one glass serum alone, without any disinfectant, was placed, in order to ascertain, by comparison with the growth which takes place in it, how the disinfectant in the other classes had interfered with the growth of the bacilli.

In experiments of this sort a difference was found between anthrax bacilli and other microzymes. A dilution of carbolic acid 1 in 1,250 and 1 in 850 sufficed to prevent the growth of anthrax bacilli, while a strength of 1 in 500 was required to prevent the growth of others.

Other species are therefore more resistant than anthrax bacilli to the action of carbolic acid. The following table shows the strength of various disinfectants required to hinder or entirely prevent the development of anthrax bacilli :—

	Hinders.	Prevents.
Iodine	1 to 5,000	—
Bromine	1 to 1,500	—
Chlorine	1 to 1,500	—
Osmic acid	1 to 1,500	—
Permanganate of potash	1 to 3,000	—
Corrosive sublimate	1 to 1,000,000	1 to 300,000
Allyl alcohol	1 to 167,000	—
Oil of mustard	1 to 330,000	1 to 33,000
Thymol	1 to 80,000	—
Peppermint oil	1 to 33,000	—
Oil of turpentine	1 to 75,000	—
Oil of cloves	1 to 5,000	—
Arsenite of potash	1 to 100,000	1 to 10,000
Chromic acid	1 to 10,000	1 to 5,000
Picric acid	1 to 10,000	—
Hydrocyanic acid	1 to 40,000	1 to 8,000

The following are about the same strength as carbolic acid :—

Fluid.	Hinders.	Prevents.
Boracic acid	1 to 1,250	1 to 800
Borax	1 to 2,000	1 to 700
Hydrochloric acid	1 to 2,500	1 to 1,700
Salicylic acid	1 to 3,300	1 to 1,500
Benzoic acid	1 to 2,000	—
Camphor	1 to 2,500	—
Eucalyptol	1 to 2,500	—
Soft soap	1 to 500	1 to 5,000
Quinine	1 to 830	1 to 625
Hydrate of chloral	1 to 1,000	—
Chlorate of potash	1 to 250	—
Acetic acid	1 to 250	—
Benzoate of soda	1 to 200	—
Alcohol	1 to 100	1 to 12·5
Acetone	1 to 50 No action.	—
Chloride of sodium	1 to 64	—

Influence of the Solvent.—Although a 5 per cent. solution of carbolic acid in water has a well-marked destructive action on the spores, and a strong destructive action on fully-developed anthrax bacilli, a similar solution in oil or alcohol has not the least disinfectant action. A similar influence with regard to iodine is observable in the previous tables.

Effect of the Fluid with which Disinfectants are mixed.—This is sometimes very marked, especially in the case of free iodine, bromine, or chlorine. These in watery solutions are powerful disinfectants, but when mixed with fluids which contain alkalies, as *e.g.* blood-serum, they are converted into bromides, iodides, and chlorides, and their action is very greatly diminished. The action of corrosive sublimate, however, and of ethereal oils is not altered.

Influence of Temperature on the Action of Antiseptics.—The action of antiseptics is greatly increased by a high temperature. Spores of anthrax bacilli exposed to the vapour of carbolic acid at 15°—20° C. remain unchanged even after 45 days' exposure. When exposed to the vapour of carbolic acid at a temperature of 55° C. the case is very different. Half an hour's exposure does not seem to harm them at this temperature, but many are destroyed by an exposure of an hour and a half, and very few will stand 3 hours' exposure, so that probably an exposure of 5 or 6 hours would destroy the whole of them.

Alterations in Bacteria by Heat and Soil.—By careful cultivation of a slip taken from a wild fruit-tree through successive generations, the chemical processes of growth may be so modified in it that the fruit will lose its acrid character, and become edible and pleasant. What is true of higher plants is true also of lower in this respect, and bacilli are much modified by the conditions under which they are cultivated; for example, Pasteur has found that the bacilli of anthrax develop and multiply in beef-tea best at 25°—40° C. Their development is retarded at higher or lower temperatures than these, and is completely arrested at 15° and 45° C. When cultivated at a temperature where development occurs with difficulty, such as 42°—43°, the bacilli no longer form resting spores, but only grow into long threads.

Fresh bacilli injected into an animal rapidly cause death from anthrax, but the longer they have been previously kept at this high temperature the more does their virulence decrease, and at the end of four or six weeks they die.

When some of the first crop of bacilli are put into fresh beef-tea, the second crop retains the degree of virulence of the first, and a third crop taken from the second, and again grown in fresh beef-tea, has exactly the same morbific power, and so on.

When the bacilli are cultivated at 35°, the microzymes not only multiply quickly, but they form spores of a definite degree of virulence, and these spores may be kept unaltered for years in

sealed tubes, whereas the threads of developed bacilli die when air is excluded.

When an animal is inoculated with anthrax bacilli whose virulence has been diminished by cultivation at a high temperature, they produce merely temporary illness instead of death. By the growth of these non-virulent bacteria in the body, its constitution appears to undergo some alteration, and virulent bacteria subsequently injected have a much less powerful action on it. If the first injection be made with bacteria having a very slight amount of virulence, the animal may still die if infected a second time with virulent bacteria, but if inoculated first with a non-virulent bacteria and a second time with bacteria rather more powerful, a slight disturbance is produced by each inoculation, and a subsequent injection of virulent bacteria no longer causes death.

The changes which are produced by **inoculation** with modified anthrax or with vaccine matter in the blood and tissues, although probably very slight, are sufficient to confer on the organism **immunity** from further infection. This is usually permanent, although the immunity may diminish with the course of years, unless the advancing age of the animal in itself tends to lessen its liability to infection.

A similar immunity against infection with different bacilli is sometimes conferred by **age.** Thus young dogs are easily infected with anthrax, but old ones are not.

A difference of **species** also confers immunity. Thus rats and field mice are not liable to infection with anthrax, while house mice are highly so. Algerian sheep also resist infection with anthrax, while French sheep do not.

We do not as yet know whether it is possible by the action of drugs to alter the blood and tissues in such a way as to render the animal proof against infection by pathogenic bacteria: but this is one of the directions in which further research is likely to yield interesting results.

Possible Identity of Different Forms of Bacteria.

It has already been mentioned that we are not quite certain whether all the species, genera, or even orders of bacteria are natural divisions, or whether the same organism under various conditions of nutrition and development may not present such different appearances as to be included in different orders and under different names. Yet this is a matter of very great importance in regard to the causation of disease, for if it be true that organisms which are usually innocuous may undergo an opposite process to that which occurs in anthrax bacilli by cultivation, and may in certain conditions of soil be changed from innocuous into pathogenous forms, we can understand how diseases may appear to originate *de novo.*

It has been stated by Naegeli that bacteria may be so modified by cultivation as to form entirely different fermentative products. Thus he says that the bacterium which produces lactic acid fermentation in milk may be changed by cultivating it in extract of meat and sugar, so that it will no longer produce a lactic but an ammoniacal decomposition in milk. He considers also that innocuous may be transformed into virulent bacteria, and back again into an innocuous form, and Buchner thinks that he has succeeded in transforming the ordinary hay-bacillus (bacillus subtilis) into anthrax bacillus by cultivating it for a number of generations in Liebig's meat extract, peptone, and sugar. This observation is denied by Klein [1] and others, but observations which partly support Buchner and partly Klein have been made by F. Köhler,[2] who finds that, while the ordinary hay-bacillus (bacillus subtilis) is not altered in its appearance by repeated cultivations, it acquires a progressive virulence which renders it so fatal to animals as to resemble the anthrax bacillus in its deadly properties.

H. C. Wood and Formad [3] have also come to the conclusion that the micrococci found in diphtheria resemble those on furred tongues in all respects excepting in their greater tendency to grow. When cultivated successively, they lose their contagious power and grow less readily. These authors, therefore, consider that circumstances outside the body are capable of converting the slower growing or common micrococcus into the rapidly growing micrococcus of diphtheria, which, when cultivated again, reverts to the common type.

Action of Bacteria and their Products on the Animal Body.—When bacteria are injected into the animal body, they produce different effects according to the original nature of the bacteria or bacilli, the conditions under which they have been cultivated, and the quantity introduced. There is probably another factor of no less importance which, however, still requires to be investigated, viz. the condition of the body into which they are introduced. In considering the effect of an injection into the living body of a solution containing bacilli, we must be careful to distinguish between the effect of the bacilli themselves, after their introduction into the circulation upon the tissues and organs of the body, and the effect of the substances which they have already formed in the solution before their injection.

We must distinguish between those two things in the same way as we would have to distinguish between the effects of the particles of the yeast plant, and the effects of the alcohol which it had formed if we were to inject a solution in which yeast was growing into the veins of an animal. The yeast or the bacteria would have one

[1] Klein, *Quarterly Journ. of Microscopic Science*, Jan. 1883.
[2] *Inaugural Dissertation* (Göttingen), 1881.
[3] *National Board of Health Bulletin, Supplement* No. 17, Jan. 21, 1882.

effect upon the animal, the alcohol or the septic products of the bacteria would have another.

Solutions of putrid organic matter containing numerous bacteria cause high fever and often death.

The course of the fever depends on the specific nature of the bacteria, *e.g.* septic bacteria, anthrax bacilli, &c.

It is difficult at present to ascertain exactly how far all the following diseases are due to the presence of microbes or their products; but it has been found that micrococci cause erysipelas, acute necrosis, gonorrhœa, gonorrhœal ophthalmia, contagious ophthalmia, ophthalmia neanotorum, and are present in pyæmia, puerperal fever, ulcerative endocarditis, infective myositis, and contagious pneumonia. When malignant œdema or traumatic gangrene occur, bacilli are usually found. Micrococci are also supposed by some to be the cause of vaccinia and of diphtheritic inflammation. The bacillus anthracis produces anthrax; bacillus septicæmiæ, blood poisoning; bacillus malariæ, ague and malarious diseases; bacillus tuberculosis, phthisis; bacillus lepræ, leprosy; and another bacillus is the cause of glanders. In relapsing fever the spirochæta obermeyeri is found in the blood, and is probably the cause of the disease.

Alkaloids formed by Putrefaction.—Ptomaïnes. From decomposing organic matter substances can be separated which have all the characters of alkaloids. Thus albuminous substances yield during putrefaction various poisons which have different physiological actions according to the stage of decay at which they are produced.

Some of these, like the sepsin separated from putrefying yeast by Bergmann and Schmiedeberg cause vomiting, diarrhœa, and bloody stools.

The extract from putrefied maize has a tetanic and narcotic action which appears to be due to two different substances. These are not present in the same proportion, so that sometimes the tetanising action, and at other times the narcotic action, is most marked.

Another alkaloid, resembling atropine in its action, has been separated by Sonnenschein and Zuelzer from decomposing animal matter; and this has also been found in the bodies of persons dying from typhus fever.

Another which resembles curare in its action has been separated by Guareschi and Mosso[1] from putrefying brain.

Another substance causing tetanic symptoms has also been obtained from animal matter.

These alkaloids produced by decomposition are known by the name of **ptomaïnes.**

[1] *Les Ptomaïnes*, Turin, 1883.

Effect of Drugs on the Action of Bacteria in the Animal Body.

So long as bacteria are outside the body, we may use drugs of any strength we please to destroy them, but the case is quite different when they have once gained entrance, and are no longer outside but inside the body, because then the nature of the drug and the amount we can employ is limited by its effect on the organism itself, and we cannot administer very large doses of antiseptics lest we should injure or kill the patient at the same time that we destroy the bacteria which are causing the disease. All that we can hope to do is to **turn the scale**, if possible, in favour of the organism in the struggle for existence between the cells which compose it and the bacteria which have invaded it.

Our hope of doing this rests on the fact that drugs which may be injurious both to the tissues and to the bacteria, are **not** equally so to each. Thus excess of temperature is injurious to the organism, but it is also destructive to bacteria; and, as Fokker[1] has pointed out, the febrile reaction which occurs on the introduction of bacteria into the blood may be a means of destroying the microbes and preserving the animal. There is often a germ of truth in apparently foolish plans of treatment, and the old practice of treating scarlet fever, small-pox, and measles by warm drinks, hot rooms, and abundant clothing, may have been a blind effort to aid the natural processes of cure, just as the irritating ointment of the Middle Ages seems to have been an attempt at antiseptic surgery. The extraordinary destructive power of corrosive sublimate, and the fact that it continues to act in blood-serum just as it does in distilled water, seem to indicate that it might be used to destroy bacilli in the body, especially as Schlesinger has found that it may be injected subcutaneously into rabbits and dogs daily for several months without doing them any harm, even in doses of 1 cc. of a $\frac{1}{2}$ per cent. solution. Koch's experiments on this point, however, have as yet led to a negative result, the animals inoculated with anthrax dying of the disease, notwithstanding the injection of the sublimate.

The extraordinary effect of **allyl alcohol,** and the less powerful but still great action of **ethereal oils,** indicate, however, that we may look forward with hope to the discovery of some organic substances which may so hinder the development of bacteria in the body after their inoculation, as to allow of their gradual destruction in the organism, and prevent the sickness or death which they would otherwise have occasioned.

In relation to this, the observations of the late Dr. W. Farr in his Report are very interesting: "Alcohol appears to arrest the

[1] International Medical Congress, 1881.

action of zymotic diseases, as it prevents weak wines from fermenting; like camphor, alcohol preserves animal matter—this is not now disputed. But may it not do more? May it not prevent the infection of some kinds of zymotic disease?"

Experiments have shown that alcohol itself has but a slight power in destroying bacilli, but it is possible that even the slight traces of the ethers which are present in wine or spirits may have some beneficial action in cases of septic poisoning.

Antiseptics, Antizymotics, Disinfectants, Deodorizers.

These classes of remedies are often confounded together. It is well, however, to distinguish their meanings:—

Antizymotics are remedies which arrest fermentation.

It has already been mentioned (p. 60) that fermentative processes may depend upon either enzymes, or organised ferments, and that organised ferments may be subdivided into several classes, such as those consisting of yeast, innocuous bacteria, and pathogenic bacteria.

The class of antizymotics includes all substances which arrest fermentative processes due to these bodies. It contains two sub-classes: antiseptics and disinfectants.

Antiseptics are remedies which arrest septic decomposition. They do this by preventing the development, or completely destroying the bacilli on which septic decomposition depends.

Disinfectants are remedies which destroy the specific poisons of communicable diseases. Many of those poisons, perhaps all of them, belong to the class of microbes, and so disinfectants may be regarded as a sub-class of antizymotics.

Deodorizers or **deodorants** are remedies which destroy disagreeable smells. Such smells often accompany the decomposition of various organic substances, which septic organisms cause. These foul-smelling products may be injurious to health in themselves by acting as poisons; but they are not to be confounded with the bacteria which produce them. Moreover, the disagreeable nature of the smell is not always to be relied upon as an index of its poisonous nature. M. Gustav le Bon made some experiments with hashed meat and water, over which he put some small animals. As the meat decomposed, the liquid teemed with organisms, was very fatal when injected into an animal, and emitted a very foul smell, which, however, did not seem to be very injurious. Afterwards the organisms present in the liquid died, and the foul smell became much less disagreeable, but the emanations from the liquid appeared to become much more poisonous, although the liquid itself, when injected into an animal, had no longer the same virulent power as at first.

Uses of Antiseptics.—Antiseptics are employed externally in order to destroy microbes before their entrance into the body, and are administered internally with a like object, or for the purpose of at least preventing the free development and multiplication of the microbes.

They are employed externally in **surgical operations,** with the object of destroying any organisms which might find a nidus in the wound, and there give rise to the formation of poisonous substances. Both these substances and the bacteria themselves will not only have an injurious local action in the wound, but by undergoing absorption may prove injurious or fatal to the organism as a whole. The antiseptic plan of treatment has been empirically practised in a limited manner for a very long period without its principle being recognised: for the well-known Friar's balsam has antiseptic properties. It is to Lister that we owe the introduction of such a mode of treatment, not based upon mere empiricism, but upon scientific knowledge. The reason why it had fallen into disuse probably was, that some of the antiseptic substances used for dressing wounds in the Middle Ages were irritants, as well as antiseptics. Those who employed them did not know the reason why they were beneficial, and supposed that their virtue was due to their irritating properties. The ointments were accordingly made more and more irritating: and thus more harm than good was done, until they were discarded by Ambrose Paré. The antiseptic most commonly employed is carbolic acid. Not only are all the instruments to be employed disinfected, but the operation itself is conducted under a spray of the dilute acid, so as to render innocuous any organisms which may be present in the air. The wound is then covered with an antiseptic dressing. Whenever this requires to be removed, it must always be done under the spray. The reason of these great precautions is obvious: if any germs, however few, gain an entrance they will soon multiply and prove as deadly as a great number, the only difference being one of time.

The great danger which may arise from an exceedingly minute portion of septic matter renders great caution necessary on the part of those who might, by a little indiscretion, convey it from one to another. Thus a number of years ago a medical man was nearly driven mad by an epidemic of puerperal fever which he had in his practice: one patient dying after the other. In order to get rid of any infection he burnt all his clothes and went away for three months. During his absence, everything went well. On his return the epidemic again broke out: on careful investigation he found the only thing he had forgotten to burn was his gloves, and these had acted as a reservoir of infection. The hands, imperfectly cleaned in the first instance, had conveyed the septic matter into the gloves, and there it remained, reinfecting the hands every time the gloves were put on. In the same way a thermo-

meter case may prove a cause of continual reinfection unless the thermometer be carefully washed, and if necessary disinfected, each time it is used and before it is put into the case. In a similar manner it has been found that gonorrhœal matter may remain in the vagina and infect several persons without the woman herself ever suffering. One of the best antiseptics for disinfection in such cases is permanganate of potash. This may be used to wash out abscesses, if there is any fear of danger from absorption of carbolic acid; and also as a lotion for ulcers or wounds about the mouth, the urethra or anus, where the carbolic acid might be too irritating; as is evident from Koch's experiment, however (*vide* page 76), a solution of the strength ordinarily used—one per cent, *i.e.* four grains to the ounce—is not sufficient to destroy the septic organism, although one of five times the strength will do so.

Another way in which septic poisoning may be produced is by the introduction of a catheter into the bladder, where this cannot be completely emptied naturally on account either of paralysis, enlarged prostate, or stricture. So long as the contents of the bladder have not come in contact with any foreign matter they may remain in the bladder for some time without undergoing decomposition, but if a dirty catheter should be passed, and thus a few organisms introduced into the bladder, decomposition may set up in the urine and septic poisoning ensue. A solution of carbolic acid in oil is sometimes trusted to for the disinfection of catheters, but, as Koch's experiments (page 78) show that such a solution has little or no antiseptic power, the catheters should be disinfected by a strong solution of carbolic acid in water and afterwards oiled before their introduction.

The use of antiseptics **internally** is limited by the resistance of the organism itself, as already mentioned (page 82). In the stomach antiseptics are used for the purpose of preventing decomposition, and by thus lessening the production of irritating products they diminish irritation of the stomach and arrest vomiting. Those which are chiefly employed for this purpose are creasote, carbolic acid, and sulphurous acid, but all bitter tonics seem to have this effect to a greater or less extent. In the intestine antiseptics are useful in arresting putrefaction, and thus preventing the harm caused locally to the intestine by the products of decomposition as well as the injury due to their subsequent re-absorption. They therefore tend to check diarrhœa and dysentery. It is probably to its antiseptic action that corrosive sublimate owes its curative power in cases of infantile dysentery, and it is not improbable that the beneficial action of calomel is due to a similar action, for it has been found by Wassilieff greatly to retard the decomposition due to low organisms.

The beneficial action of mercurials in such cases may be partly due to their antiseptic power not being greatly diminished by admixture with fæcal matters as that of other antiseptics. After

absorption into the blood antiseptics are chiefly employed in febrile conditions, in order, if possible, both to lessen the growth of the septic organism and to remove the danger to the individual which the fever itself would occasion. The principal antiseptics used for this purpose are alcohol, eucalyptol, quinine, salicine, salicylic acid, and salicylates. Carbolic acid and creasote can hardly be used, as their action on the organism is too poisonous, but hydroquinone, cresotinic acid, kairine, pyrocatechin, and resorcin are not markedly poisonous, and are antipyretic. They may thus be useful although not largely employed at present (*vide* also Antipyretics). Eucalyptol has sometimes appeared to me to be more beneficial in cases of septic poisoning than quinine; at any rate, I have seen patients recover under its use who had not been benefited by quinine.

Disinfectants.—These are generally employed in order to destroy the germs of disease in the excreta of a patient suffering from an infectious disease, or those germs which may be adhering to articles of clothing or to furniture or to walls of a room in which the patient has been lying. Probably the most efficient and generally applicable to articles of clothing is heat. The heat employed is usually from 230° to 250° F., but as a general rule it should be as hot as the fabrics will bear without injury, and should be continued as long as is necessary to raise the central parts of the articles to be disinfected to the temperature of the chamber in which it is placed. As the presence of **moisture** aids the destructive action of heat upon septic organisms, superheated steam appears to be the best disinfectant under ordinary circumstances. The only disinfectant that seems to be really trustworthy for destroying septic organisms when it is simply washed over them, is corrosive sublimate: even in a dilution of one to a thousand it appears to destroy microzymes and their spores by a single application for a few minutes.

Deodorizers.—Deodorizers are mainly strong oxidizing and deoxidizing substances, as chlorine and its oxides, sulphurous acid, nitrous acid, ozone, peroxide of hydrogen, permanganate of potash. Charcoal, in addition to oxidizing, absorbs and condenses the foul-smelling gas. Those which are most commonly used as deodorizers for the air of rooms are chlorine or its oxides set free from chlorinated lime.

For removing smells from the hands, carbolic acid is to be preferred to others, and for deodorizing fœcal matters, permanganate of potash, carbolic acid, or charcoal. A mixture of eight or nine parts calcined dolomite (magnesia and lime) with one or two of peat or wood charcoal is not only an excellent deodorizer, but increases the value of the fæcal matters as manure.

Antiperiodics.

These are remedies which lessen the severity or prevent the return of attacks of certain diseases which tend to recur periodically.

The chief of these are:

Cinchona bark and its alkaloids:—

Quinine.	Arsenic.
Cinchonine.	Salicylic acid.
Quinidine.	Salicylates.
Cinchonidine.	Salicin.

Bebeeru bark and its alkaloid:—

Bebeerine.	Eucalyptol.

Action.—The mode in which antiperiodics act is not at present definitely ascertained, nor yet is the pathology of the diseases which they prevent. Remittent fever, however, has been shown to depend upon the presence of a spirillum in the blood, and there is considerable evidence for considering that malarious conditions are connected with the presence of a bacillus. The periodical return of the attacks in such diseases would appear, then, to be associated with the growth of successive crops of these protophytes, and the action of antiperiodics might be explained by supposing that they interfere with the development of these pathogenic organisms.

Uses.—Quinine and cinchona bark are often regarded as almost specific in the various affections due to malarious poisoning, *i.e.* intermittent fevers, periodic headaches, neuralgias, etc. In tropical remittent fever of malarious origin, quinine is also the best remedy we possess. It must be given in very large doses however, and is less certainly curative than in intermittent fever. The other cinchona alkaloids have a similar action to quinine, but are not quite so powerful: they, as also quinine, may be used as prophylactics in order to prevent the recurrence of ague in persons travelling through or living in malarious districts as well as for the purpose of curing malarious conditions already present.

Arsenic is sometimes even more powerful than quinine, but as a rule it answers best in malarious conditions which are sometimes known as masked or latent malaria, and which manifest themselves in neuralgia and nervous or digestive disturbance rather than in well-marked ague fits.

Adjuncts.—Emetics and purgatives aid the action of antiperiodics and sometimes, indeed, can replace them and cure ague without their aid. Antiperiodics rarely succeed if the functions of the liver are disturbed unless they are aided by emetics or purgatives, and especially cholagogues.

CHAPTER IV.

ACTION OF DRUGS ON INVERTEBRATA.

THE study of the action of drugs on invertebrata has not been carried out methodically to any great extent, but it offers a very promising field for investigation, and probably in the course of a few years may yield very valuable results.

Action of Drugs upon Medusæ.

This subject has been worked at, almost exclusively by Romanes[1] and Krukenberg.[2] At present it has little practical bearing, but it promises to be of great service by enabling us to understand better the action of drugs on contractile structures generally, and on the heart in particular.

In medusæ the swimming organ consists of a bell-shaped mass of contractile substance, within which the polyp hangs like the clapper. Around the margin of this bell are a number of ganglia connected with one another by nervous filaments.



FIG. 15.—Medusa (Sarsia) natural size.

In the normal state of the animal, the bell alternately contracts and dilates rhythmically, so that the animal is propelled through the water.

When the marginal strip containing the ganglia is removed, the bell becomes entirely motionless. The bell thus resembles, as we shall see afterwards, the ventricle of the frog's heart, both in the relation of ganglia to it, and in its rhythmical movements. Oxygen accelerates, and carbonic acid slows and finally stops, the rhythmical movements.

[1] Romanes, *Phil. Trans.* vol. clxvi. part 1, and vol. clxvii. part 2, 1866 and 1867.
[2] Krukenberg, *Vergleichend. Physiologische Studien,* Heidelberg, 1880.

When the bell, paralysed by the removal of the ganglia which supply its normal stimulus to motion, is momentarily stimulated by a single induction shock, it invariably responds by a single contraction.

When successive shocks are employed at regular intervals the effect of each increases until the maximum is reached.



FIG. 16.—Shows the increasing contractions of the tissue of medusa when stimulated by repeated weak induction shocks of the same intensity. The first two shocks had no apparent effect, and the first feeble contraction seen in the figure was caused by the third shock. (From paper by Romanes in *Phil. Trans.*)

But if an additional **constant stimulus** is supplied to it by the addition of acid to the water in which it is floating ; by the passage of a constant or of an interrupted electrical current through it ; or by alcohol or glycerine dropped upon its surface, it commences to beat regularly, rhythmically and continuously. When rhythmical action is thus artificially induced in the paralysed bell, its rate is increased by raising the **temperature**, and reduced by cooling it. Temperatures below 20° or above 85° arrest the rhythm.

When the marginal strip containing the ganglia is cut off and left attached only at one point, a stimulus applied to its end travels along the strip and finally causes the bell to contract. The **stimuli** which pass along may be



FIG. 17.—Diagram of a medusa (tiaropsis), about one-third natural size, with a strip of contractile tissue cut from the bell, but left attached at one end.

of two kinds—they may occur separately or together. The first kind is a wave of contraction in the contractile tissue of the strip itself. If the stimulus is applied to a portion of the strip the contraction will pass along like a wave until it reaches the bell, which it excites to contraction. The second is a rudimentary form of nervous activity. This may occur along with the contraction wave, and when this is the case it is seen to pass along in front of the contractile wave. But it may also occur when no wave of contraction takes place. Its occurrence is rendered visible by the movements of the tentacles which fringe the strip, and are much more sensitive than the contractile tissue of the strip itself. This wave of stimulation without contraction passing along the strip, will cause the bell to contract on reaching it, provided there is a marginal ganglion in the bell, but not if the bell is paralysed. The wave of stimulation is more easily excited than that of contraction, so that it may occur from stimuli too weak to excite a wave of contraction. The passage of stimuli along the strip may be impeded or prevented altogether by compressing the

strip, by making transverse incisions into it so as to narrow the band of tissue by which the wave is transmitted, or by injuring the tissue by straining. Sometimes the contraction wave may be blocked by the injury before the stimulus wave, and sometimes the stimulus wave may be blocked before the contraction wave. When the block is only partial it frequently happens that two or three waves will pass along the strip up to the block without being able to cross it, but after a long time their effect appears to penetrate so that a wave at last crosses it.

As Gaskell has shown, a similar occurrence takes place in the frog's heart, and stimuli proceeding from the auricle to the ventricle may also be blocked by compression.

The influence of **poisons** can be studied either upon the bell containing the ganglia, or upon this marginal strip.

In healthy medusæ chloroform first arrests the spontaneous movements of the bell. When now irritated it answers by a single contraction, instead of by a series, to such stimulation.

After the bell has ceased to respond, nipping its margin causes the polyp to contract.

After stimulation of any part of the bell ceases to produce response in any part of the organism, the polyp will respond to stimuli directly applied to it. Nitrite of amyl also produces effects which in many respects are similar to those of chloroform. There are, however, certain exceptions ; the first is that, before the spontaneous movements are abolished, the rhythm becomes quickened, and the strength of the pulsations is diminished. The movements also die out more gradually than under chloroform, and before they entirely cease they become localised to the muscular tissue close to the margin.

When the dose is large, spasmodic contractions are produced which obliterate the gradual paralysing action of the drug. Caffeine first causes an increase in the rate of pulsation, and diminishes its strength after a few seconds. This condition passes off, and the spontaneous movements become gradually abolished. They still remain for a long time sensitive to stimulation, and at first respond by *several* feeble contractions to each stimulus ; afterwards by a single response ; and afterwards they do not respond at all.

As medusæ paralysed by removal of the ganglia never respond to a single stimulus with more than a single contraction, the increased number of contractions which at first appear after the application of the stimulus, are probably due to increased reflex irritability.

Caffeine causes the tentacles and polypi to lose their tonus, and become relaxed, which is not the case with chloroform. Medusæ anæsthetized with chloroform when put into a solution of caffeine also lose their tonus, but their irritability is restored, though their spontaneity is not.

The effects of strychnine differ in different species of medusæ. In Sarsia it accelerates the rhythmical contractions which occur in groups separated by intervals of quiescence. This quiescence finally becomes continuous, and during it, it does not respond to irritation of the tentacle, but does so to direct muscular stimulation.

Veratrine causes first increase both in the number and power of the contractions ; afterwards it diminishes both.

Digitalin first quickens them, then renders them regular, causes persistent spasms, and produces death in strong systole.

Atropine causes first acceleration, then convulsions, then feeble contractions, and finally death in systole.

Nicotine causes violent and continuous spasm, with numerous minute rapid contractions superimposed upon it. These latter soon die away, leaving the bell in strong systole.

After spontaneous movements have disappeared, the bell no longer responds to stimulation of the tentacles, but responds to direct stimulation.

Alcohol first greatly increases the rapidity of the contractions, so much so that the bell has no time to expand properly between them, and they are in

consequence feeble and gradually die out. The reflex stimulation shortly ceases to produce any effect, but muscular irritability is longer maintained.

Cyanide of potassium first quickens and then enfeebles the contractions; spontaneous movements rapidly cease, and the bell soon becomes irresponsive either to irritation of the tentacles, or to direct irritation. For a long time after it has become irresponsive, the nervous connections between the tentacles and polyp remain intact as also do the nervous connections of these organs, with all parts of the bell.

The sensory organs are therefore not paralysed by this drug.

The effects of poisons on medusæ were localised by Romanes in two ways: one way was to divide the medusa almost into two halves, connected only by a narrow strip of tissue. These halves were plunged into two beakers filled with water, pure in one and poisoned in the other. The connecting strip rested upon the edges of the beaker. When curare was employed as a poison in this way, it was found to have an action similar to that which it exerts on mammals: apparently paralysing the motor nerves, while it left the sensory nerves capable of action. Thus, on nipping the half of a medusa which was plunged in the curare solution, it remained absolutely motionless, while the other half at once responded by a peculiar contraction to the stimulus. Here, also, however, just as in mammals, the sensory fibres are also paralysed by a large dose, so that if much poison be used, irritation of the poisoned part will have no effect either upon it or upon the unpoisoned part. When experimenting in this way with strychnine, Krukenberg found that the excitability of the poisoned part was increased, so that when he touched the connecting strip lightly with a needle no effect was produced on the unpoisoned half, but the poisoned half responded by several energetic contractions. Veratrine had a similar action to that of curare, so that irritation of the poisoned half caused no movement in it, but caused movement in the unpoisoned half. The irritability of the contractile tissue is also diminished so that it no longer reacts so readily in the poisoned half to electrical stimuli. Nicotine appears to paralyse the ganglionic structures and not the nerves.

It has already been mentioned that the rhythmical movements of medusæ depend upon the ganglia: when these are all cut off the movements cease, but even if one be left the movements continue. In the medusa divided into two halves, as already described, it is evident that if the ganglia are removed from one half, or one half rendered functionally inactive by poison, that half will still continue to contract, so long as it remains connected with the other half, but will cease to move when it is completely divided from the half which still contains ganglia. The effect of nicotine is such as one would expect if the poison paralyses the ganglia, for it is found that when one half of a medusa is steeped in water containing nicotine, both halves still continue to pulsate rhythmically; so soon as the connecting band of tissue is divided, the poisoned half at once ceases to move, while the other half continues to pulsate.

The second way in which Romanes localised the action of poisons on medusæ was by applying them to a strip of contractile tissue. He found that various poisons applied to the strip, or injected into it, caused a blockage of contractile waves, preceded by a progressive slowing of the rate of transmission along the poisoned part. Chloroform, ether, alcohol, morphine, strychnine, and curare, all have this effect.

General Results.—The most marked results of experiments on medusæ are, that the contractile tissue **contracts** rhythmically when stimulated by ganglia. It ceases to do so when the ganglia are removed and the contractile tissue left under ordinary conditions, but a constant stimulus, either chemical or electrical, applied to it after the removal of the ganglia, will cause it to beat rhythmically just as if the ganglia were present. This appears to

show that the rhythmical contractile power is a function of the contractile tissue and not merely of the ganglia. Besides its power of contracting once on the application of a single stimulus, or rhythmically from continued stimulation, the contractile tissue also possesses the power to **conduct** stimuli. This is seen in the passage of the contraction wave along a strip of medusæ which, on reaching the bell, causes it to contract. When two contraction waves travelling along the contractile strip in opposite directions meet one another they arrest each other. This mutual extinction may be regarded either as a process of **inhibition** or interference, or as a consequence of exhaustion of the tissue which possibly may be unable to contract twice with such a short interval between.

The power of the contractile tissue to transmit stimuli is diminished or destroyed by cutting it more or less completely across, by compression, by stretching, by very high or low temperatures, and by poisons such as chloroform, morphine, nitrite of amyl, caffeine, strychnine, curare, and indeed almost any foreign substance added to the water in which the strip is immersed.

There are, however, **two conducting channels,** along which stimuli may be transmitted ; the first, already mentioned, is the contractile tissue ; the second is the nervous tissue. The passage of stimuli along the second is rendered evident by the movements of the tentacles. These nervous or tentacular waves and the contractile waves may exist either together or separately. These nervous waves are excited by stimuli which are too weak to excite contraction waves, and it is to be particularly remarked that when this is the case they only travel at half the rate at which a contraction wave travels, although, when the stimulus is strong enough to excite a contraction wave also, both the nervous and the contractile waves travel at the same rate, the nervous one being a little ahead of the other. The passage of nervous stimuli may also be diminished or completely blocked by section or compression just as in the case of contraction waves.

The transmission of stimuli along nerves is also affected by poisons. It appears to be destroyed by anæsthetics, though more slowly than that of the contractile tissue. The ganglia may be paralysed, *e.g.* by nicotine, before the transmission of nervous stimuli from them is diminished. The contractile tissue alone may be paralysed.

Action of Drugs on Mollusca.

In the **lamellibranchiata,** instead of a chain of ganglia as in the medusæ, we have three pairs of ganglia : cerebral at the mouth, pedal in the foot, and parietal splanchnic supplying the bronchial apparatus and viscera. The heart has distinct chambers, but apparently consists of protoplasmic substance without distinct nerves or ganglia. The application to it of an interrupted

current will arrest the rhythmical pulsation and cause stoppage in diastole.[1] This effect is prevented by atropine. Warmth up to 104° quickens the heart, when raised higher it destroys reflex movement in the animal, and afterwards arrests the heart also. Pure water without salts quickly paralyses the muscles and causes death in salt-water mollusks. Curare in small doses has no effect, large doses quicken, but do not abolish movement, and do not affect the heart. Strychnine somewhat stimulates movement, and may cause some local contractions, but never any general tetanus. Nicotine acts in a similar way, but in large doses appears to paralyse the muscles and cause death; it also appears to cause contraction of the vessels, so that the heart becomes more bulky and beats more quickly. Veratrine has a similar action. Digitalis has no action, excepting when applied to the heart directly, and then it renders the beats slower and sometimes stops them. Antiarine, like digitalis, has no general action, but stops the heart if applied to it directly. Muscarine generally causes muscular contractions in the body: first acceleration, quickly followed by retardation of the cardiac beats. Sulphocyanide of potassium diminishes reflex action, but has little effect on the excitability of the nerves. A small dose somewhat quickens the cardiac action; a large dose stops the heart in diastole and if it is directly applied to the heart the stoppage is permanent.

Action of Drugs on Ascidians.

The heart in ascidians consists of a tube open at both ends, and which, by its contraction, drives the visceral fluid alternately towards the visceræ and away from them. Its action does not seem to depend on the nervous ganglion lying between the oral and anal sac, or indeed upon nervous influence at all.

The application of an induced current causes it to beat for some time in one direction instead of alternately, but does not arrest its pulsations.[2] According to Krukenberg it is not affected either by atropine or muscarine. It is paralysed by veratrine, quinine, and strychnine: these poisons rendering the beats gradually weaker and more irregular. No evidences of tetanus are to be seen from the action of strychnine. The mode of action of the heart is affected by helleborin and nicotine: helleborin increases the number of the advisceral beats while nicotine diminishes them. Camphor and strychnine have possibly an action in this respect resembling helleborin.

Action of Drugs on Annulosa.

In annulosa the nervous system consists of ganglia in each segment united together by nervous bundles. These bundles in general appearance correspond with the gangliated cord of the sympathetic in higher animals, and the spinal cord is absent. We might therefore expect that drugs which act specially on the spinal cord in vertebrates would not have the same marked action on annelida, and this appears to be the case. It was found by Moseley

[1] M. Foster, Pflüger's *Archiv.* v. 191.
[2] Dew-Smith, *Roy. Soc. Proc.*, March 18, 1875, p. 336.

that strychnine had no action on cockroaches;[1] and leeches, when placed in water containing strychnine, become elongated but do not exhibit signs of tetanus. Some years ago I noticed that ants sprinkled with insect-powder died in violent convulsions, and it occurred to me that possibly substances which excite movements of the intestine in the higher animals might have a somewhat convulsant action on invertebrates. I therefore tried the effect of oil of peppermint on leeches, and it produced in them violent excitement. This appears to be of a somewhat convulsant nature: the animal at first flying rapidly hither and thither through the water, and afterwards, when it becomes quiet and nearly exhausted, there is a constant rhythmical twitching movement in the body which appears to last nearly until death. But if my idea had been correct, all carminatives should excite convulsions in annulosa. This is not the case, for the oils of peppermint, caraway and anise have no apparent effect on black-beetles than that of making them sluggish. Chloroform, ether, and other substances belonging to the alcohol group, act as anæsthetics on mammals, temporarily abolishing the functional activity of the brain, spinal cord, and medulla. On leeches they have a different effect, coagulating the muscular substance and rendering it stiff and hard before affecting the nerves. This has been shown in an ingenious way by Krukenberg, who applied chloroform to the middle part of the leech while he protected the two ends of the animal from the action of the vapour. The middle part then became stiff and rigid, but the movements of the two ends of the animal were perfectly co-ordinated, so that its actions were that of a single animal having a stiff girdle surrounding its middle. Ether and alcohol had a similar result. The co-ordination of the two ends showed that although the muscles had been rendered rigid by chloroform, the nerves which passed through the middle part of the body were still functionally active. When the middle part of the body was coagulated by the application of hot water, the muscles became rigid but the nerves were also destroyed, and the movements of the two ends of the animal were no longer co-ordinated, so that they appeared like two distinct animals connected by a rigid cylinder. Atropine has a similar action to chloroform, ether and alcohol, on the muscles of the leech. Veratrine appears to some extent to affect the muscles, so that after contraction they relax slowly. It appears also, however, to affect the nerve centres, and according to Krukenberg paralyses more especially the sensory centres. Camphor, strychnine, morphine, caffeine, copper sulphate, and mercuric chloride, act chiefly on the nervous system of leeches, although they also affect the muscles when applied for a length of time. Caffeine renders the muscles in the leech also rigid.

[1] Moseley, unpublished experiment made in C. Ludwig's laboratory.

CHAPTER V.

ACTION OF DRUGS ON MUSCLE.

Action of Drugs on Voluntary Muscle.

In the bodies of animals we find the protoplasmic masses or cells of which they are composed variously modified, in order to perform special functions.

In some the power of nutrition is chiefly developed: and these we find in glands. In others the power of contractility is developed: and these we find in muscles, striated and non-striated.

In the course of special development towards the fulfilment of a particular function, the protoplasm of the muscular cells undergoes marked changes. But it must always be borne in mind that the protoplasmic elements of the body, however different from one another, always tend more or less to retain all the functions which are seen in an organism consisting of a single cell, a reference to which may sometimes throw much light upon the mode of life of the more highly organised tissues. In amœbæ or leucocytes the protoplasm contracts in any direction. In muscle it contracts chiefly in one direction, viz. that of its length, though the probability of its contraction in a transverse direction also is to be borne in mind.

We distinguish in muscle its elasticity, a physical property; and its contractility, a vital property.

The word elasticity is applied to the tendency of the body both to resist change of its form, and to regain it when this change has been effected: so that ivory may be taken as the type of a very strongly elastic body. Indiarubber, on the other hand, is regarded as a feebly elastic body, because it does not strongly resist changes of form, although it tends very strongly to regain its original form after such changes. It is, however, popularly regarded as the perfect type of an elastic body. In talking of the **elasticity** of muscle, confusion is apt to occur; it is better then to avoid the term elasticity and to use the words suggested by Marey—extensibility and retractility. The **extensibility** of muscle is of two kinds—immediate and supplementary. When a weight is attached to it,

it extends considerably; this is its immediate extensibility: it then goes on slowly and gradually lengthening for a considerable time, and this is supplementary extensibility. When the weights are removed the retractile power of the muscle again becomes evident, and there is immediate **retractility** and supplementary retractility, the muscle at once contracting to a considerable extent, and then continuing to do so slowly and gradually for some time afterwards. The extensibility of a muscle is increased by stimulation, so that if a weight be hung on a muscle while it is contracted in consequence of stimulation, it will produce a greater extension than it would if applied to the same muscle in a state of rest. If a muscle, too, is loaded with a weight too great for it to raise, stimulation of it, instead of causing contraction, causes elongation. Heat renders the muscle less extensible and more retractile; cold has an opposite effect, rendering it more extensible and less retractile. Section of the nerve has a similar effect to that of cold. Fatigue increases the extensibility. Alkalis (potash or soda), in very dilute solutions, diminish extensibility; dilute acids (lactic acid) increase it. By the alternate application of alkalis and acids the muscle may be made to yield curves which, when recorded on a very slowly-revolving cylinder, are similar in form to the normal contraction curve recorded on a rapidly-revolving cylinder.

Irritability of Muscle.—In order to ascertain the irritability of muscle itself or the readiness with which it responds to various stimuli independently of the nerves within it, the muscle is first poisoned by curare, and then exposed to various conditions or to the action of drugs. The muscle thus poisoned by curare, woorara, woorali, or urari (for the poison has all these names), is much less sensitive to the action of faradaic currents. The readiest way of testing its excitability is by the making and breaking of a constant current, the strength of which can be estimated very exactly by using du Bois Reymond's rheochord. The excitability of muscles is **increased** by heat and **diminished** by cold. It is increased by physostigmin and diminished by most poisons which paralyse muscle.[1]

Contraction.—When the ends of the muscle are not kept apart by force too great for it to overcome, and it is stimulated by heat, mechanical injury, chemical irritants, or electricity, it contracts and then relaxes.

The form of this contraction varies according to the species of animal, and the particular muscle tested.

In cold-blooded animals, as a rule, the contraction is slower than in warm-blooded animals. It is not alike in all the muscles of the body of mammals. Thus in the rabbit there are two kinds of muscles—red and white; the white muscles contract more quickly and relax more quickly than the red ones. The muscle

[1] Harnack and Witkowski, *Arch. f. exp. Path. u. Pharm.* v. 1876, p. 402.

usually employed in experiments is the gastrocnemius of the frog, freshly prepared with the nerve and end of the femur attached to it.

The femur is fixed in a clamp, and the lower end of the muscle is attached to a writing lever usually loaded with a weight (Fig. 18). The end of this lever writes upon a revolving cylinder,



FIG. 18.—Apparatus for registering muscular contraction. It consists of an upright stand on which two horizontal bars may be moved by a rack and pinion. The upper bar ends in a clamp, the lower carries a delicate lever, the part near the hinge being of metal, and the part beyond of light wood tipped with quill or tinfoil. *a*, *a*, wires for exciting muscle; *b*, muscle; *c*, writing lever. In the figure no arrangement is shown for exciting the nerve, and for the sake of simplicity the weight is shown directly under the muscle. In actual experiment, however, the weight should be applied close to the axle, or on it, so as to lessen oscillation due to the inertia of the lever.

(Fig. 19), which is made to rotate with greater or less rapidity. The rate of revolution is usually ascertained by marking the time upon it by means of an electro-magnet (Fig. 20), communicating with a clock or metronome, or, when the revolution is quick, with a large tuning-fork, vibrating 100 times or more per second. When the cylinder is not in motion each contraction of the lever makes a straight line upon it (Figs. 21 *a* and 27); when the cylinder is moving, the lever describes a curve more or less elongated, according to the rapidity of the cylinder's rotation (Figs. 21 and 22).

Latent Period of the Muscle.—The mechanical energy developed by muscle during its contraction is derived from chemical energy liberated by changes in the constituents of the muscle itself. These are of the nature of oxidation, and during them oxygen is used up, and carbonic acid is liberated. But the oxygen is not necessarily present either around the muscle, or in the blood circulating through the muscle; it is stored up in some loose form of combination within the muscle.[1]

[1] It would appear that this force-yielding substance, or muscle-dynamite, as we may call it, is not present, at least in large quantity, in the muscles in a form in which it can be at once fired off. There appears rather to exist a substance yielding it, or dynamogen, which may be looked upon as corresponding to the zymogen of the

The form in which it is stored up has been compared by Ludwig to gunpowder, a small quantity of which is fired off at each contraction.

One of the final products is carbonic acid; but there are intermediate products, one of them being sarcolactic acid; and these products tend to cause muscular fatigue.



FIG. 19.—Revolving cylinder for recording movements. The screws at the top are for fixing the cylinder in position. The brass pin is for making or breaking a current at a given time in the revolution. It does this by striking against a small key. The curve is described by the lever, Fig. 18. The abscissa, or zero line, is drawn by a fixed point, and serves to show the height of the contraction.

When they are washed out of the muscle by a current of blood, or of simple saline solution, the fatigue of the muscle is removed; and this removal is effected even more perfectly when the internal oxidation is rendered more complete by adding permanganate of potash to the solution, or by the addition of minute

glands, while the muscle-dynamite may be regarded as corresponding to the ferments of glands. Irritation of a nerve appears both to liberate muscle-dynamite and to explode it, if we may so term it. The passage of a constant current through the muscle appears to liberate the muscle-dynamite from the dynamogen, but causes no expulsion except at the moment when the current is made or broken, or its strength altered. It must be carefully borne in mind that the idea of a muscle-dynamogen is at present simply theoretical, and must be looked upon not as a fact, but rather as a means of remembering facts. According to A. Schmidt, however, the contraction and relaxation of muscle is closely connected with formation and destruction of a ferment.

quantities of potash. A mere trace of veratrine has also a similar effect in restoring the muscle after fatigue.

We find that the muscle does not immediately respond to a stimulus, but that a period elapses between the stimulus and the commencement of the contraction, which is on the average about the 100th of a second. This is termed the latent period.

During this period a chemical change is probably going on in the muscle, and it is evidenced by an electrical change known as the negative variation, or diminution in the natural current which passes from the longitudinal to the transverse section of the muscle.

The latent period is altered by fatigue. Loading the muscle shortens the latent period, until the load is just sufficient to extend the muscle. An increase of load above this, lengthens the latent period. Cold lengthens it; heat shortens it. Small doses of strychnine or veratrine shorten the latent period. Large doses of strychnine or veratrine, and also curare, lengthen it.

Summation of Stimuli.—During the latent period, the stimulus applied to a muscle excites chemical changes which result



FIG. 20.—Electro-magnet (after Marey) for recording time on a cylinder. When used to record time, the current is made and broken alternately by clockwork or by a tuning-fork. It may be used also to record the time of irritating or dividing a nerve, or of injecting a poison, &c.

in contraction; but if the stimulus be very small, the chemical changes may be so slight that contraction does not occur. If the stimulus, however, be repeated several times, the changes which it induces in the muscle become sufficient to produce at first a slight contraction, and then one greater and greater, until the maximum effect is produced—this is called *summation*. It occurs not only in voluntary muscles, but in other contractile tissues, such as those of the medusæ, *vide* Fig. 16, p. 89. A similar phenomenon occurs also in the heart, and has there received the name of "the staircase."

Contraction of Muscle.—In the muscular curve we notice (1) the rapidity of its rise, which indicates the rapidity of contraction of the muscle; (2) its length, indicating the duration of contraction; (3) its height, indicating power of contraction; and (4) slowness of fall, indicating the condition of extensibility.

The muscular contraction is modified by numerous conditions.

One of these is the strength of **stimulus.**

The stimulus usually applied is electricity, as its strength can be more easily regulated, and it does not destroy the muscle so readily as mechanical or chemical irritants.

With a weak current, making (closing) has no action on the muscle, but breaking (opening) causes contraction.



FIG. 21.—Muscle curves, showing the different appearances they present according to the rate at which the recording cylinder revolves. *a* is a curve with a very slowly revolving cylinder; *b*, *c*, and *d* are curves with increasing speed of rotation. *c* is written with a lever pointing in the opposite direction from that with which *a* and *b* are recorded, and the curve therefore inclines to the other side.

A moderate current gives contraction both in making and breaking, but that of making is comparatively small (Fig. 22). With a strong current no difference is observed.



FIG. 22.—Shows effect of making and breaking shocks. These are normal muscle curves with a still quicker rotating cylinder than in Fig. 21. The first is caused by irritating the muscle by making (closing) a constant current, and the second by breaking (opening) it.

The more intense the stimulus, the higher and longer is the curve. The increase in height is shown in Fig. 23.



FIG. 23.—Tracing of the contractions of a muscle with stimuli of varying strength. The numbers indicate the distance in centimetres of the secondary from the primary coil in the induction apparatus. As and Des indicate the ascending and descending direction of the current.

Cold renders contraction slower, lower, and more prolonged (Fig. 24 *b*).

Heat renders it quicker, higher, and shorter (Fig. 24 *a*).

Fatigue.—Fatigue makes the ascent slow, the height less, and the descent slow (Fig. 25).

Exhaustion of the animal has a similar action; and dilute acids applied to the muscle produce the same effect.

The effect of fatigue is probably due in a considerable measure to the accumulation of acid products of muscular waste. When these



a *b*

FIG. 24.—Effect of heat and cold. In *a* the muscle has been artificially warmed, and in *b* it has been cooled.

are washed out by passing a weak solution of chloride of sodium through the vessels of the muscle, or removed to some extent by kneading, it regains to a great extent its normal power of contraction.



FIG. 25.—Effect of fatigue.

Oxidizing agents, such as permanganate of potash, added to the salt solution increase this power, and restore the muscle even more quickly and completely.[1]

Deprivation of blood has a similar action on the muscle to fatigue; and free circulation of blood tends to remove the effects of fatigue.

Contracture.—When the stimulation is exceedingly strong, the relaxation after contraction may become very slow, and the descent of the curve may be divided into two parts. At first it descends for a short time pretty quickly, and then falls very slowly indeed. This long contraction of the muscle is known as contracture. It is very strongly marked in muscles poisoned by veratrine or barium. It occurs, though to a less extent, in muscles poisoned by salts of calcium and strontium, by ammonia, and by the chloride, iodide, nitrite, nitrate, and cyanide of ammonium.[2]

The cause of contracture is not known; it is considered not to be a tetanic contraction, because, unlike an ordinary tetanised muscle it does not give rise to secondary tetanus in another frog's muscle, when the nerve of the latter is placed upon it. It is, however, an active contraction, not a mere alteration in the elasticity of the muscle preventing its relaxation; for, as Fick and Boehm have shown, a much greater amount of heat is developed during the long-continued contracture than in an ordinary contraction. Sometimes, and indeed not unfrequently, the contracture, instead

[1] Kronecker, Ludwig's *Arbeiten*, 1871, p. 183.
[2] Brunton and Cash, *Roy. Soc. Proc.* 1883.

of consisting of a single prolonged contraction, appears in the form of a prolonged contraction added on to an ordinary contraction before relaxation has had time to occur. This gives rise to a peculiar hump in the curve, as is well seen in the middle curve in Fig. 30. This appears to show that the contracture is really a double phenomenon, like the two contractions observed after a



FIG. 26.—Secondary contraction in the muscle of a crayfish. The thick part of the lower line shows the time during which the muscle was irritated by a tetanising current. It will be noticed that the secondary contraction occurs after the irritation has ceased, and after the tetanus caused by it has relaxed. It is not a simple continuous rise, but exhibits several waves indicative of a kind of rhythm. (After Richet.)

single stimulation in the muscle of the crayfish by Richet (Fig. 26). How far the contracture may depend upon irritation of the muscle by its own current has yet to be determined.

Tetanus.—If instead of a single stimulation a number of stimuli rapidly succeeding each other are applied either directly to the muscle itself or to its motor nerve, we get, in place of a single contraction, a continued contraction or tetanus. As this is due to a fresh contraction of the muscle occurring before the previous one has had time to relax, it is evident that the number of stimuli requisite to produce this will vary with the length of each single contraction in a muscle: thus in the muscles of the tortoise, which contract and relax very slowly, tetanus may be produced by 3 stimuli per second, while in the white muscles of rabbits 20 may be necessary, and in some muscles of birds 70 stimuli per second are insufficient. It has been said that with as rapid stimuli as 250 per second the tetanus ceases, and after a single initial contraction a muscle goes to rest just as if a constant instead of an interrupted current had been used. Kronecker and Stirling have shown that, with no less than 22,000 interruptions per second, still tetanus is obtained; but when such extremely rapid stimuli are applied, the muscle still contracts about the ordinary rate of 20 per second; and this is also the case when chemical stimuli are applied to the nerve, or when the muscle is irritated by the nerve centres, either voluntarily or by artificial stimuli applied to them. It seems therefore probable that the number of contractions of the muscles

in tetanus are not due to the number of stimuli sent down from the nerve centres, but that the rate is determined either by the ends of the nerve in the muscle or by the muscle itself.[1]

The form of a tetanus curve may be modified very considerably by the action of drugs: thus substances which diminish the contractile power of muscle cause the tetanus curve to fall very rapidly notwithstanding the continued application of stimuli either to the muscle itself or to its nerve (*vide* Ammonia).

Muscular Poisons.—We may distinguish several groups of muscular poisons, but at present the classification is difficult, and the division into six groups, based on that of Kobert, which I have adopted, although it possesses some advantages, is far from satisfactory, and can only be regarded as temporary.

GROUP I.—Leaves the irritability of the muscle unaffected, but diminishes the total amount of work it is able to do.

GROUP II.—Diminishes the excitability of the muscle as well as its capacity for work.

GROUP III.—Diminishes the capacity for work, and produces marked irregularity in its excitability.

GROUP IV.—Alters the form of the muscular curve.

GROUP V.—Increases the excitability.

GROUP VI.—Increases the capacity for work.



FIG. 27.—Tracings showing the gradual loss of contractile power from fatigue in a normal muscle, *a*, and in one poisoned by carbolic acid, *b*. Each section, 0′—1′, &c., shows the contractions in one minute. (After Gies.)

The poisons in Group I. do not alter the muscle curve, so that if the action of the poison were tested by a single contraction only, it would be supposed that the muscle was unaffected; they lessen, however, the amount of work which the muscle can yield.

The amount of work is estimated by the weight which a muscle raises multiplied into the number of times it is lifted and the height it is raised each time. These are ascertained by registering the contractions on a slowly revolving drum, as in Fig. 27, which shows the rapid exhaustion of a muscle poisoned by carbolic acid as compared with a normal one. The rapid exhaustion of muscles may also be observed in the form of the tetanus curve

[1] Wedenskii, *Archiv f. Anat. u. Physiol. Phys.* Abthlg. 1883, p. 325.

which, under the influence of such poisons, falls much more rapidly in height than that of the normal muscle.

This group contains a number of drugs having an emetic action.[1] These are: apomorphine, asclepiadine, cyclamine, delphinine, sanguinarine, and saponine, copper, zinc, and cadmium. Antimony has a somewhat similar action, but only in large doses, and after a great length of time. Arsenic, platinum, and probably mercury, act in the same way as antimony.[2] Tin, nickel,[3] cobalt,[3] manganese,[2] aluminium, and magnesium, have little or no action on muscle. Large doses of iron are nearly as powerful as arsenic, but in small doses it rather increases the amount of work the muscle can do.

Carbonic oxide at the atmospheric pressure does not affect muscular contractility, but abolishes it at a pressure of five atmospheres.

Perhaps we may take as a subdivision of this group those poisons which lessen the contractile power of the muscle without

FIG. 28.—(After Harnack.) Shows the action of lead on muscle. *a* shows the contraction of a normal muscle after eighty stimulations; *b*, the irregular contractions of a muscle poisoned by lead after ten to fifty stimulations; *c* shows the slow relaxation of the muscle after contraction in a muscle poisoned by lead after numerous stimulations.

altering its irritability. When a muscle poisoned by one of these is stimulated, it may contract quite as readily as a normal muscle, provided the weight that it has to raise is but slight, but it cannot raise such a heavy weight as a normal muscle. This is tested by loading it with a given weight, and the slightest contraction is ascertained by adjusting the lever of the myograph in such a way that if raised in the very least it breaks a connection in an electrical current and causes a bell to ring. In this way contractions quite imperceptible to the eye are readily appreciated. Digitalis has an action of this sort, as I found in some experiments carried on under the direction of Professor J. Rosenthal in 1868, but not published.

Group II. contains salts of potassium, lithium, ammonium, quinine, cinchonine, oil of mace, alcohol in large doses, chloroform, etc.

Chloral, chloroform, and ether, also belong to this group, but they might also be reckoned as belonging to Group IV., for they

[1] Harnack, *Archiv f. exp. Path. u. Pharm.* Bd. ii. p. 299, and iii. p. 44.
[2] Kobert, *Arch. f. exp. Path. u. Pharm.* Bd. xv. p. 22, and xvi. p. 361.
[3] Anderson Stuart, *Journ. of Anat. and Physiol.* vol. xvii. p. 89.

slow the ascent, lessen the height, and prolong the descent of the curve. Curare has a similar action.

It is usually stated that curare, while it paralyses motor nerves, leaves the excitability of the muscles unaffected, but this appears not to be quite correct, for, when very weak currents are employed, the muscle loses its excitability by them before the nerve, and the contractions of the muscle at the same time become unequal. It is perhaps not yet perfectly certain how far these appearances are due to the curare, and how far to the gradual death of the muscle.[1]

Group III. contains poisons of which lead is a typical example. These poisons cause the muscular contractions to become very unequal, although the stimuli are equal and regular. Emetine and cocaine have a similar action to lead. This action is probably due only to the gradual death of the muscle. It is produced also by ptomaines, and it may occur in muscles which are simply dying without being poisoned at all.[2]

Group IV. contains poisons which alter the form of the curve to a marked extent.

The action of veratrine is very peculiar: it does not lessen the rapidity of contraction, and even increases the height of the curve, but it prolongs the descent to an enormous extent.



FIG. 29.—Tracing of the contraction curve of a muscle poisoned by veratrine, showing enormous prolongation of the contraction, the recording cylinder making many complete revolutions before the muscle is completely relaxed.

This action of veratrine is most marked at moderate temperatures.

It is much diminished, and sometimes entirely removed, by cold; and it disappears also when the temperature of the muscle is considerably raised. When the muscle which has been cooled or heated is again brought back to a moderate temperature, the contracture sometimes returns, but occasionally does not, the effect of veratrine on the muscle appearing to be sometimes, but by no means always, destroyed by the heat or cold to which the muscle has been exposed.[3]

The result of this exceedingly prolonged contraction is that a frog poisoned with veratrine is able to jump with considerable

[1] Marey, *Travaux du Laboratoire*, 1878, p. 157.

[2] Mosso, *Les Ptomaïnes*, Turin, 1883.

[3] Brunton and Cash, *Journ. of Physiol.* vol. iv. p. 1, and *Centralblatt d. Med. Wiss.* 1883, No. 6.

power, but the extensor muscles, by which the movement is executed, remain contracted instead of relaxing. The animal therefore lies extended and stiff, and is only able very slowly to draw its legs up towards the body. After they have been drawn up, the flexors in their turn remain contracted for a while, and so the animal is unable to jump until some time further has elapsed.

Another remarkable point about the action of veratrine on muscle is, that although a single contraction lasts so long as seriously to interfere with the power of co-ordinated movement, yet if the muscle is made to contract a few times in rapid succession, the effect of the veratrine disappears, and it again acts normally. After a short rest the effect of veratrine again reappears.

A similar action to that of veratrine is exerted by salts of barium, which, when locally applied, cause the muscle to describe a curve resembling that of veratrine, not only in its form, but in the



FIG. 30.—Tracing of the contraction curves of a muscle poisoned by veratrine, showing the peculiarly elongated curve at a moderate temperature, and its restoration nearly to the normal by cooling and heating.

alterations produced by temperature and in its temporary disappearance after repeated contractions. A similar action is exerted also, though to a less extent, by strontium and calcium. Salts of potassium may at first increase the height of contraction, but afterwards both moderate and large doses shorten the muscular curve, and lessen its height, so as finally to abolish its contractile power altogether. When applied to a muscle poisoned by veratrine, barium, strontium, or calcium, salts of potash remove the excessive prolongation of the contraction which these drugs occasion, and restore the muscular curve again to its normal.[1]

Although veratrine alters the form of the muscular curve so greatly, it does not (excepting in large doses) paralyse the muscle,

[1] Brunton and Cash, *Roy. Soc. Proc.* 1883.

so that when a poisoned muscle is made to contract at regular intervals for a length of time, it is able to do as much work as a normal one.

Nearly allied to this is another group of muscular poisons, some of which have already been mentioned as a subdivision of Group I. It contains: digitalin, digitalein, digitaleresin, digitoxin, toxiresin, scillain, helleborein, oleandrin, adonidin, neriodorin, and neriodorein. Tanghinia, thevetin, and frynin, or toad poison, probably also belong to this class.

These drugs do not lessen the irritability of muscle, but appear to alter somewhat the form of the muscle curve, somewhat in the same way, but to a less extent than substances of the veratrine group. Some of them when applied in a concentrated form directly to the muscle cause a condition of rigor. This is especially the case with caffeine and digitalin. This rigor is well marked in the *rana temporaria*, and only to a comparatively slight extent in the *rana esculenta*. Although caffeine in concentrated solution produces *rigor mortis* in the muscle, yet in very dilute solutions it is a muscular stimulant, and as such is included in the sixth group.

Group V. contains physostigma, which increases the excitability of muscle to slight stimuli, but does not increase the amount of work it can do; on the contrary, in large doses it diminishes it.

Group VI.—Poisons belonging to this group in small doses increase muscular work, and cause the muscle to recover rapidly after exhaustion. Creatine has this power to a great extent; hypoxanthine has it also, though less powerfully. The effect of these substances is very interesting, because they are products of muscular waste. They also occur in beef-tea, and their action appears to show that beef-tea assists muscular power, as well as acts as a nervous stimulant.

Other members of this group are caffeine and glycogen: these have great power to increase muscular work. The relation of caffeine to hypoxanthine is very interesting. Xanthine, which is another substance derived from muscles, differs from hypoxanthine in containing one atom more oxygen. Theobromine, the active principle of cocoa, is dimethylxanthine; and caffeine, the active principle of tea and coffee, is trimethylxanthine. The restorative effects of beef-tea, coffee, tea, and cocoa have long been recognised empirically, although their action could not be explained. It now seems not at all improbable that it may be partly due to their restorative effect on the muscle.

Massage.—The effect of kneading a muscle so as to remove the waste products from it is very extraordinary.

When the muscles of an uninjured frog are stimulated to contraction by the rhythmic application of maximal induction currents until they are exhausted and no longer contract, kneading them, or massage, restores their contractility so that their contractions are nearly as powerful as at first, while simple rest without

massage has very little restorative effect. In man also, while a rest of fifteen minutes after exhausting labour had very little restorative action, massage during the same period increased double the work that could be done. Massage has a similar action to very complete and perfect circulation through the muscle, in removing the waste products and restoring its power.[1]

Propagation of the Contraction Wave in Muscle.—When a muscle is irritated at one point, the contraction wave which occurs at that point is conducted along the muscle in both directions.

This contraction wave, like that which occurs in the contractile tissue of the medusa, is independent of the nervous system. The completeness with which it is conducted, and the quickness with which it subsides at each point, are closely connected with the rapidity of the conduction, and they are also injuriously affected by anything which impairs it. It diminishes during the death of the muscle, and it is lessened also by fatigue, by cold, by injury, such as excessive stimulation. Certain poisons also lessen it, as cyanide of potassium, veratrine, and upas antiar.[2]

Heat increases the rapidity of the conduction.

Rhythmical Contraction of Muscle.—Rhythmical contraction is frequently regarded as a function of involuntary muscular fibre only; this, however, is not the case, for it is observed also in voluntary muscles. Rhythmical contraction of involuntary muscle is well marked in the heart and blood-vessels. It is very distinct in the intestines and bladder, and becomes still more marked after the influence of the central nervous system has been destroyed. In the case of the sphincter ani, for example, the rhythm is strong and regular, especially after the nerves have been divided and the muscle subjected to some mechanical distension by the introduction of the finger.

In voluntary muscle the tendency to large rhythmical pulsations is slight, although we see rapid contractions occurring in tetanus.

It is usually supposed that eighteen or twenty contractions per minute of the muscle when tetanised by stimulation of nerve centres is due to this number of stimuli being sent to it from the nerve centres.

From the observations of Wedenskii that irritation of the motor nerve of a muscle by exceedingly rapid stimuli still produces the same number of contractions in the muscle, it seems probable that this rate of contraction is due to the constitution either of the muscle itself, or of the nerve-endings within it. Under certain circumstances, however, the voluntary muscle may be made to contract with a slow rhythmical movement of considerable extent and closely resembling that of involuntary muscular fibre.

[1] Zabludowski, *Central. d. Med. Wiss.* 1883, No. 14, p. 241.

[2] Aeby, *Untersuchungen über die Fortpflanzungsgeschwindigkeit der Reizungen der Quergestreiften Muskelfaser.* Braunschweig, 1862, p. 52.

Thus voluntary muscle treated by veratrine tends to remain contracted for a length of time like an involuntary muscle; heat has a tendency to cause its relaxation, and sometimes, as is seen in the accompanying figure, these contending influences produce in the voluntary muscle a tendency to marked rhythmical contraction (Fig. 31).

A still more remarkable phenomenon has been noticed by Kühne,[1] who finds that when the uninjured sartorius of a frog is placed in a solution of 5 grammes NaCl, and 2·5 grammes of common alkaline crystallised phosphate of soda in a litre of water, it begins to contract at once, and after it has been transversely divided it beats with the regularity of the heart.

The action of various substances on the rhythmic action of muscle treated in this way has been investigated by Biedermann. He finds that the best fluid for the sartorius is 5 grs. NaCl, 2—2·5 grms. of $Na_2HP.O_4$, ·04—·05 grs. of Na_2CO_3. A low temperature not rising above ten degrees is best. The lower the temperature



FIG. 31.—Tracing of the contraction curve of a muscle poisoned by veratrine and exposed to a high temperature. The poison tends to cause prolonged contraction, and the high temperature to cause rapid relaxation of the muscle. The result is a somewhat rhythmical spontaneous contraction. The muscle was only irritated at the very beginning of the first contraction.

the slower is the rhythm and the more extensive the contraction. Heat quickens the rhythm and lessens the contraction. At about 18° to 20° C. the contractions become rapid and indistinct. When caustic soda is used instead of carbonate, the effect is similar, but the muscle dies much more quickly. Potassium carbonate and other potash salts only cause pulsations when greatly diluted. Lactic acid stops the pulsations; alkaline NCl solution again restores them. Veratrine and digitaline in a solution of NaCl also cause pulsations.[2]

Schönlein finds that, with a certain strength of current interrupted about 880 times in a second, the muscles of the water beetle are not tetanised but contract rhythmically from two to six times in a second.[3]

[1] *Untersuchungen aus dem Physiologischen Institute der Universität Heidelberg.* Sonderabdruck, 1879, p 16.

[2] *Sitzungsber. d. Wiener Akad.* Abth. lxxxii. pp. 257-275.

[3] Schönlein, du Bois Reymond's *Archiv*, 1882, s. 357.

Biedermann has succeeded in making a voluntary muscle, such as the sartorius, contract rhythmically by applying a solution of sodium bicarbonate (2 per cent.) to the tibial end, and then passing a constant ascending current through the muscle.[1]

Connection between Chemical Constitution and Physiological Action on Muscle.

I have already mentioned (page 21) that one can hardly look for a general relation between the atomic weights of metals and their lethal activity, so that what we want is really a knowledge of the particular relationship of each group of elements to the organs and tissues of the body.

In such an investigation it seems natural to take the muscles first, then the motor nerves, afterwards the nerve centres and individual organs. A number of experiments have been made by Cash and myself in order to do this for the alkalies and alkaline earths, and we have found that the contractile power of muscle, as shown by the height of the curve, is increased by rubidium, ammonium, potassium, and cæsium. It is slightly increased or unaffected by sodium, excepting in large doses, and is almost invariably diminished by lithium.

The duration of contraction, as shown by the length of the curve, is increased by rubidium in large doses, ammonium, sodium, and cæsium. It is shortened by ammonium, lithium, rubidium, in small doses, and potassium.

The *contracture*, or viscosity, is increased by rubidium in large doses, ammonium, lithium, and sodium. It is diminished by rubidium in small doses, ammonium, cæsium, and potassium.

Both ammonium and rubidium have two actions on muscle of an opposite character, sometimes increasing and sometimes diminishing both the duration of the contraction and of the *contracture*, or viscosity, which remains after the ordinary contraction has ceased. In the case of rubidium this appears to depend upon the dose, but we were not satisfied that it was so entirely in the case of ammonium salts.

In regard to the action of the alkaline-earths and earths, we found that the contractile power of muscle is increased by barium, erbium, and lanthanum. It is sometimes increased and sometimes diminished by yttrium and calcium. It is diminished by didymium, strontium, and beryllium.

The duration of contraction is increased by barium, calcium, strontium, yttrium, and erbium. It is unaffected, or slightly diminished, by beryllium, didymium, and lanthanum.

Contracture is increased by barium, calcium, strontium, yttrium, and beryllium.

[1] *Sitzungsber. d. Wien. Akad.* Bd. lxxxvii. Abt. iii. March, 1883.

The contracture produced by barium is enormous, resembling that produced by veratrine. It is, like that of veratrine, diminished by heat, cold, and potash, and may be abolished by these agents. It is by no means so well marked when the drug is injected into the circulation as when locally applied to the muscle.

The action of some of the more important of those drugs can be graphically represented by a spiral, the terminal members of which are potassium and barium, and these two are to a certain extent connected by ammonium as an intermediate link.



The effect of one member of one of these groups may be diminished or increased by the subsequent application of another. Potassium shortens the elongated curves caused by barium, calcium, sodium in large doses, and lithium, and reduces the *contracture* which these substances cause. The veratrine-like curve of barium is counteracted by almost all the substances which produce a shorter curve than itself.

Action of Drugs on Muscle is Relative and not Absolute.

In considering the action of drugs on muscle, the first point which comes clearly out is that the action of a drug on the muscle is not absolute, but merely relative. Thus veratrine and salts of barium are not to be regarded as absolute muscle poisons—they are only poisons under certain conditions of quantity and of temperature. An exceedingly small dose of veratrine instead of acting as a poison to muscle, acts rather as a food, and restores it when exhausted. Caffeine likewise in small doses has a restorative action, while in large doses it is a powerful poison. Veratrine and barium in moderate doses and at moderate temperatures are powerful muscular poisons, but at low temperatures and at high temperatures their action is to a great extent, or even completely, abolished. Nay more, moderate quantities of barium salts at moderate temperatures are poisonous to the normal muscle, but they are restorative to the muscle whose composition and functions have been already altered by rubidium. Acids and alkalies also

produce an effect on muscle, but their effect depends upon whether they are applied to the normal muscle or to one previously treated with a substance having an opposite reaction.

It is evident then that the whole question of the action of drugs on muscle is one involving the relation of the drug to the muscle at the time of application, and we must expect that if the temperature is different from the normal, or if the composition of the muscle should vary, the action of the drug will vary likewise. Now the composition of all the muscles in the body is not the same, as has been shown by Toldt and Nowak,[1] and the composition of the ash obtained by the combustion of different animals is also different, as has been shown by Lawes and Gilbert.[2] We may therefore expect that muscular poisons will not act alike at the normal temperature and in febrile conditions, nor alike upon all the muscles of an animal; nor will they always have the same action upon different animals—the relations being different the effects will be different. The effect of poisons upon muscles will also vary according to their chemical composition at the time. This composition may probably to a certain extent be altered by feeding —at least as far as regards the proportions of inorganic ingredients. We know that the quantity of sodium chloride in the body can be increased, for if an animal be fed with a larger quantity of salt than usual, it does not at once begin to excrete it, but stores it up for two or three days, and then the excretion rises. After the administration of the salt has been stopped the excretion still continues large for two or three days, and then returns again to the lower standard. It seemed probable that similar retention would take place with potash, and if this were so, we might expect to counteract to a great extent the effect of barium by feeding an animal on potash for some time before administering the barium. On trying this, Cash and I have found that this is the case to a certain extent, and although we have not been able completely to counteract the effect of a large dose of barium so as to prevent death from a lethal dose, we have been able to modify and diminish its action by the administration of potash for several days previously, so that the characteristic symptoms of barium poisoning do not occur until some hours after they would otherwise do so, and thus life is prolonged though not preserved.

Action of Drugs on Involuntary Muscular Fibre.

Contraction.—Involuntary muscles, with the exception of the heart, differ from voluntary not only in their anatomical structure but in their functional activity: instead of contracting or relaxing rapidly, both their contraction and relaxation are slow. We have seen that although voluntary muscle occasionally exhibits

[1] Quoted by Seegen, *Wien. Akad. Ber.* lxiii. Abt. ii. 11-43.
[2] *Roy. Soc. Proc.* xxxv. p. 344.

spontaneous rhythmical contractions, yet these occur only under exceptional circumstances, and but rarely. Involuntary muscle, on the other hand, has a much greater tendency to rhythmical contraction, although it may be regarded as doubtful whether some stimulus, however slight, is not required to induce this rhythm even in involuntary muscle. It has been already mentioned that the contractile tissue of medusa will beat rhythmically so long as it is connected with motor ganglia. When these ganglia are removed, the contractions cease, but will again reappear, notwithstanding the absence of the ganglia, if a constant stimulus be applied to the contractile tissue itself. This shows that the conditions for rhythm are contained in contractile tissue itself—that the rhythm may be independent of the ganglia with which the contractile tissue is connected (p. 89). The same appears to be the case with involuntary muscular fibre generally.

The ventricle of the frog's heart, containing ganglia, will beat rhythmically for a length of time after its removal from the body. If the ganglia which lie close to the auriculo-ventricular groove are cut off, the rhythmical action will cease just as in the medusa when the marginal ganglia are removed; but if a constant stimulus be applied to the apex of the heart, as for example by passing a constant current through it, or by distending it with serum, its rhythmical movement will again commence, mechanical distension appearing to have upon it the same exciting action that a little acid added to the water has upon the nerveless bell of the medusa.

Effect of Stimuli.—Mechanical distension appears to be one of the most powerful of all stimuli to excite rhythmical contraction in involuntary muscular fibre.

Luchsinger observed distinct pulsation in the veins of a bat's wing twenty hours after the death of the animal, if artificial circulation was kept up. This appears to show that the power of rhythmical contraction resides in the muscular fibres of the veins as it does in the nerveless apex of the frog's heart, and the contractile tissue of the medusa; but here also an external stimulus appears to be required to induce contraction. When the pressure by which artificial circulation was maintained fell to zero, the pulsation stopped, but if it were raised to forty or fifty centimetres of water, so as to distend the vascular wall, rhythmical pulsation again commenced. It appears possible, however, that when involuntary muscular fibre is perfectly healthy and possessing the highest degree of irritability, it may contract rhythmically without any extra stimulus. Thus Englemann[1] observed that the ureter, in which he could find no nerves at all, contracted rhythmically when freshly exposed, although it was not distended or subjected to any mechanical irritation; but if artificial respiration has been long kept up, and the animal is exhausted, so that the excitability of

[1] *Pflüger's Archiv*, 1869, Bd. 11, p. 251.

the ureter is diminished, then the effect of minimum distension in increasing its rhythm becomes very evident.

Cold causes the isolated non-striated muscles of animals to relax. **Heat** causes them to contract.[1]

The influence of heat and cold, however, does not seem to be constant, and in the non-striated muscle of frogs they have an opposite connection to that just described. It is probable that the different results may depend to a great extent upon the amount of heat or cold applied, and its relation to the condition of the tissues at the time of application; for mechanical stimulation has also an opposite effect, according to its amount; and while gentle stimulation of involuntary muscular fibre, such as that of the small blood-vessels, causes dilatation, more powerful irritation produces contraction.[2]

The influence of various drugs upon involuntary muscular fibre, as seen in the contraction of the blood-vessels, will be described when considering the circulation.

The Relation of the Contractile Tissue to the Nerves is different in voluntary and involuntary muscular fibre. In the latter there are no end plates, but the terminal twigs form a plexus around the fibres. The motor nerves of involuntary muscular fibre appear to be affected by atropine and its congeners in a similar way to those of voluntary muscle by curare. There appears also to be a certain relationship between the atropine and curare group. Small doses of atropine paralyse the motor nerves of involuntary muscle, while very large doses of curare are required. The converse is the case with voluntary muscle. These effects are usually supposed to be due to a definite paralysing action on the nerves themselves. There are difficulties, however, in the way of this hypothesis, and a more probable one, perhaps, is that these drugs disturb the relations between the nerves and the muscular fibres which they excite. On the idea of a specific action it seems hard to explain the results obtained by Szpilman and Luchsinger,[3] who found that atropine produces paralysis of the motor fibres of the vagi supplying the œsophagus, only in those parts of it where involuntary muscular fibre is present. Thus, the œsophagus of the frog and the crop of birds consist of involuntary muscular fibre, and atropine destroys the motor power of the vagus over them.

The œsophagus of the dog and rabbit contains striated muscular fibre, and atropine does not paralyse the motor nerves. The œsophagus of the cat contains striated muscular fibres in its upper three-fourths, and non-striated in its lower fourth; atropine destroys the motor action of the vagus upon the upper part, but not upon the lower fourth.[4]

[1] Luchsinger and Sokoloff, *Pflüger's Archiv*, Bd. 26, p. 465.
[2] Sigmund Meyer, *Hermann's Handb. d. physiol.* Bd. 5, Theil ii p. 476.
[3] Szpilman and Luchsinger, *Pflüger's Archiv*, Bd. 26, p. 459.
[4] Szpilman and Luchsinger, *Pflüger's Archiv*, Bd. 26, p. 249.

Propagation of Contraction Waves.—Although involuntary muscular fibre consists of short cells and not of long fibres like voluntary muscle, yet the contraction wave may be propagated along a strip of involuntary muscular tissue in both directions from the point of irritation, just as in voluntary muscle or in the contractile tissue of medusæ. This wave is transmitted more slowly in involuntary than in voluntary muscle; and its rate in the involuntary muscle of the heart, though slower than in ordinary striated muscle, is quicker than in unstriated muscle, so that in this respect the heart is intermediary between the two.[1]

The passage of contraction waves in involuntary muscular fibre is affected by the same conditions as voluntary muscle, the conduction of the contractile wave being rendered slower by fatigue and cold, while it is quickened by heat.

Cold and fatigue also render the rhythmical pulsations smaller and longer, while heat has an opposite effect. The passage of the contraction wave may also be diminished or arrested by section or pressure, just as in the contractile tissue of medusæ,[2] so that instead of each contraction wave passing the block produced by the sections or compression, only one out of several, or none at all, may pass. The proportion passing the block depends upon its completeness. If the tissue forming the bridge be dry as well as narrow, the block becomes more complete, and may be again diminished by moistening. Variations in the strength of the stimulus do not affect the passage of the contraction wave over the block, so that it would appear that the injury caused by the section, along with the narrowing of the conduction path, retards the re-establishment of the conductive power.

In experiments made upon the heart of a tortoise cut into a strip, it has been found by Gaskell that stimulation of the **vagus** removes the block, quickens the recovery of the tissue, and causes every contraction wave to pass. The effect upon the muscle therefore seems to be trophic.

A **weak interrupted current** applied to the muscle directly has the same action as stimulation of the vagus, *i.e.* it increases the conducting power of the muscle. Sometimes, however, both the vagus and a weak interrupted current have an opposite effect, and diminish instead of increasing the conducting power.

An **artificial rhythm** may be induced in a strip of involuntary muscular fibre cut from the heart of the tortoise by passing a weak interrupted current through it and then stimulating it at one end by induction shocks, at intervals of about five seconds. After a while, if the induction shocks are discontinued, the muscle still continues to contract rhythmically at the same rate. These contractions, at first weak, afterwards become strong, and may last

[1] *Hermann's Handbuch d. Physiologie*, Bd. 1, p. 56.

[2] Englemann, *Pflüger's Archiv*, 1875, Bd. 11, p. 465; Gaskell, *Journal of Physiology*, vol. iii. p. 367.

for many hours. Both the conducting and the contractile power of the muscle is diminished by muscarine. When a strip of it is stimulated by induction-shocks applied to one end, the contraction wave passes quickly along, but muscarine appears to block its transmission, so that while the part of the muscle between the electrodes contracts at every shock, the rest of the muscle contracts only at every second one. A weak interrupted current then sent through the muscle may lower its conducting power and still further reduce the force of the contractions, and not only block the passage of most of the contraction waves from the point of excitation, but may even prevent the contraction of the excited part itself.

Atropine has an opposite action and appears to increase the conducting power of involuntary muscle, so that when applied to a strip of the heart, the conducting power of which has been diminished by muscarine, the contractility is at once increased, and each contraction wave passes over the whole muscular strip each time that a single point is irritated. Large doses, however, appear to have a depressant action on the muscle.

Hypothetical Considerations regarding the Action of Drugs on Muscle.

The modifications which drugs produce in the functions of the animal body and of its parts, are so numerous and varied that we are unable fully to explain them on the basis of our present physiological knowledge. The results of pharmacological experiment furnish us indeed with a number of additional facts regarding the functions of organs and tissues which will ultimately lead us to a more correct and thorough knowledge of their physiology. At present, however, we can only explain them hypothetically, and indeed, in many cases we can do little more than guess at the explanation.

The advantage to be gained from hypothetical explanations is, that hypotheses not only lead to further experiment, but serve as guides for experiments, by which, if false, they may be soon disproved, or if true, may be maintained.

The disadvantage of hypotheses is, that they are sometimes apt to be taken for facts, and being made use of as bases for further speculation, may lead more and more astray from the truth. While bearing in mind the danger of speculation, it may be useful to make some guesses at the mode of action of drugs upon the muscle as guides to further research.

The most striking point about muscle is the motor function which it exercises by contracting, and the nature of its contraction must engage our attention. Throughout the universe we find that motion of nearly all sorts resolves itself into a series of vibrations, and the question arises whether the motion of muscle cannot be explained in the same way. When a muscle is stimulated it contracts and relaxes once, describing a wave-like curve upon the revolving cylinder. Frequently this first wave is followed by a second, and sometimes even by a third, which are usually ascribed to the simple elasticity of the muscle. Sometimes we can notice that the single contraction wave appears really to consist of two or more partially superimposed on each other, and sometimes we may find two distinct waves arise from one stimulation.

When a muscle is in a state of tetanic contraction it appears to the eye to be perfectly quiet, yet we know that during this period of apparent rest the

muscle is in a state of vibration, alternately tending to contract and elongate. These vibrations may succeed one another with a rapidity such that the muscle appears to the eye to be motionless, while a tracing taken upon the revolving cylinder shows distinct successive waves. If the vibrations are still more rapid, the waves may disappear, and we get the muscle describing a straight line. But even when a muscle is entirely relaxed, its parts may be in a state of vibration quite as continuous as in tetanic contraction. This is seen by examining muscular fibre under the microscope. The phenomenon which then presents itself was described by Porret and is often known by his name. On passing a constant current through a thin muscular slip a contraction is seen when the current is closed. During the whole time of the passage of the current, the muscle to the naked eye appears to be perfectly at rest, but under the microscope its parts are seen to be in constant motion, presenting an appearance almost exactly similar to the waving of a field of corn on a windy day, or to the motion of rows of cilia. At the same time an actual transference of material takes place in the muscle : the end next the positive pole growing smaller, and the end next the negative pole growing larger. When the current is suddenly reversed a sudden contraction of the whole muscle takes place, and it then returns to apparent rest, but microscopic observation shows the same cilia-like motion as before, but in an opposite direction.

This phenomenon reminds one very strongly of the crowding together of carriages in a railway train when it is set in motion or stopped by the locomotive pushing behind or stopping in front. We know that the apparent steady movement of the train is due to the backward and forward vibration of the piston in the cylinders of the locomotive, and the question occurs whether the contraction of the muscle as a whole at the moment of opening and breaking the current, is not due to an interference with the rhythmical vibration of its parts. The question also arises whether these vibrations are not to a great extent dependent upon the molecular weight of its constituents. This seems to a certain extent to be indicated by the curious relations between the effects of the alkalies, alkaline earths, and certain metals upon muscle. Thus Cash and I have found that potassium and calcium neutralise each other's action upon muscle, and if the hypothesis just expressed be correct we should expect that metals having a similar molecular weight to a mixture of calcium and potassium would have no action upon muscle. This appears to be the case. In researches made in Professor Schmiedeberg's laboratory, Anderson Stewart found that nickel and cobalt had no action upon muscle, and White found that tin also had little or none. On comparing then the atomic weights of potassium (39) calcium (40) nickel (59) cobalt (59) and tin (118) we get the following relationships.

$$K_2(78) + Ca(40) = Ni_2(118,) \text{ or, } Co_2(118,) \text{ or, } Sn(118).$$

Sodium in large doses lengthens the curve and increases the contracture when applied to a normal muscle. It adds to the length of the long curves caused by calcium and strontium. Rubidium in large doses produces a long curve with enormous contracture almost like that of barium. One would naturally have expected that the rubidium and barium would have increased each other's effect like sodium, calcium, or strontium, but the reverse is the case, for the abnormal curve caused by rubidium is reduced to the normal by the application of barium. If barium be applied to a greater extent than is sufficient to antagonise rubidium, it first abolishes the prolonged rubidium curve, reducing it to the normal, and then again elongates it, producing its own characteristic curve. Calcium and strontium, which also prolong the curve, though to a less extent than barium, do not antagonise one another's effect—they rather increase it ; but calcium reduces the barium curve to the normal before causing its own peculiar curve. At first sight these results seem to be independent of any rule, but a curious relation is to be observed between the atomic weights of these substances. Thus we have seen that rubidium in large doses has th

same effect as barium in causing a veratrine-like curve, but barium destroys the effect of rubidium before producing its own effect. On comparing the atomic weights of these elements we find that eight atoms of rubidium have nearly the same weight as five of barium, and by subtracting one from the other we get almost no remainder. Thus

Ba 137 × 5 = 685.
Rb 85·4 × 8 = 683·2.

Potassium is, as we know, an important constituent of muscle, and it seems possible that the reduction in the barium curve which calcium causes may be due to their union having resulted in a substance whose molecular weight is a multiple of that of potassium. Thus

Ba 137 × 2 = 274 - Ca 40 = 234.
K 39 × 6 = 234.

The alterations which occur in voluntary muscle from the action of such substances as calcium or barium appear to approximate it to some extent to involuntary muscle. Voluntary muscle is chiefly characterised by sudden and rapid contraction and relaxation. Involuntary muscle usually contracts and relaxes slowly. In the slowness of its relaxation, at least, the muscle poisoned by barium or calcium approaches involuntary muscle.

The power of summation which contractile tissues possess is strongly suggestive of the idea that rhythmical vibrations of gradually increasing intensity are going on within the tissue even before any movement becomes visible. A pendulum very gently struck at proper intervals will gradually begin to oscillate through a larger and larger arc. If touched on one side while oscillating, the effect of the touch will depend upon the time at which the touch is applied, for at one period of oscillation it will tend to impede, and at another to assist the oscillation. Possibly some unseen rhythm in the muscle itself may be the cause of the curious variations in excitability observed in dying muscles and in muscles poisoned by lead. Two pendulums connected together will swing harmoniously if their rate of oscillation is the same, but if one be loaded so as to alter its rate of oscillation they will interfere with each other. Possibly the effect of poisons in paralysing nerves may be due rather to alteration in the relative rhythms of the nerve and muscle than to any specific destructive power on the terminations of the nerve itself.

The opposite effects which Gaskell has noticed the vagus nerve and a weak induced current to produce upon the conducting power of the cardiac muscle, sometimes increasing and sometimes diminishing it, may be due to the interference or co-incidence of rhythm such as are discussed more fully further on under the head of Inhibition.

It is impossible to say at present what the true cause of the curious rhythmical contractions of voluntary muscle is ; and it must be borne in mind that the considerations contained in this section are purely hypothetical, and their only use is to indicate the direction in which we may possibly look for an explanation of the action of medicines on muscle.

CHAPTER VI.

ACTION OF DRUGS ON NERVES.

Action of Drugs on Motor Nerves.

In low organisms the contractile protoplasm fulfils the functions of both nerve and muscle, but as we ascend in the scale differentiation becomes more and more complete. From their original common origin, however, we might expect that the poisons which act on the muscles would also act on the motor nerves, and *vice versâ*, and we should hardly expect any poison to act entirely on the one without affecting the other. This is to a considerable extent the case, for very many substances paralyse them both. But, as one would also expect from the differentiation they have undergone, muscle and nerve are not equally affected in the higher animals. Thus we find that although most of the salts of ammonia, and the iodides, chlorides, and sulphates of the compound ammonias into which methyl and ethyl enter, paralyse both muscle and nerve, yet they paralyse the nerve before the muscle. In some cases the nerve is affected so much before the muscle that at first sight it might appear that the nerve alone was paralysed and the muscle left unaffected. More careful observation, however, shows us that most of the compound ammonias, and probably most of the organic alkaloids, affect muscle, motor nerves, and nerve centres, and if their action can be continued long enough, will paralyse all three. The symptoms they produce may, however, be entirely different, because these depend upon the order in which the different parts of the nervous system are affected, as has already been pointed out at page 20. The symptoms produced for example by strychnine and methyl-strychnine are utterly different, the former causing tetanic convulsions, and the latter gradually increasing torpor, weakness, and paralysis. Strychnine stimulates the spinal cord, and methyl-strychnine paralyses the motor nerves; yet if their action continue long enough it is found that both of them will ultimately cause paralysis of both spinal cord and motor nerves. The final result is thus the same in both cases, but the order in which the various parts of the nervous system are affected is different.

The readiness with which a muscle responds to a stimulus depends both on the condition of the muscle itself, and on the terminations of motor nerves within it. A faradaic current readily stimulates the nerve endings, but does not act at all readily on the muscle. The making and breaking of a constant current, on the other hand, has comparatively slight action on the nerves, but a powerful action on the muscle. One of the questions which arises most constantly in connection with the action of drugs is:—whether or not they paralyse the ends of the motor nerves in muscle. This question was fully worked out by Bernard and also independently by Kölliker, in relation to **curare**.

The same **methods of experiment** were adopted by both. They were twofold, and consisted

First, in preventing the poison from reaching the part on which it probably acted:

Secondly, in applying the poison to that part alone.

The first of these methods was employed by ligaturing the artery of one leg in a frog, so as to prevent the poison from reaching the muscles and motor nerves in that leg (Fig. 34); the second was carried out by the local application of the drug to the muscles and motor nerves themselves (Figs. 32 and 33).

Both methods possess advantages of their own: the advantage of the first being that it affords information regarding the action of the poison upon the other parts of the nervous system, as well as upon the motor nerves. It also gives the order in which the poison affects the various nervous structures, and shows whether the quantity of poison conveyed to the nerves by the circulation is sufficient to paralyse them or not. For some substances, directly applied to the ends of the motor nerves, may paralyse them, although they do not have this effect when injected into the blood. The reason is that the quantity applied to the nerves directly, may be much greater than what reaches them through the circulation.

The effect of drugs in paralysing motor nerves is chiefly investigated on frogs as the action comes out much more distinctly in them.

Warm-blooded animals may die from paralysis of the motor nerves while the nerves still respond readily to faradaic stimuli applied to them, the faradaic stimulus being much greater than what is normally sent along the nerves from the nerve-centres. Thus after an animal has been killed by paralysing it with curare, its muscles will still respond readily to irritation of the motor nerves.

A fallacy to be guarded against in experiments on the results of preventing a poison from reaching one part of the body is that caused by diffusion. Even when the circulation is stopped in a frog's leg by ligature of the artery, poison introduced into the dorsal lymph sac may pass down the limb by diffusion and affect the parts below the ligature. This may be to a great extent

prevented by ligaturing the whole limb *en masse*, but carefully excluding the sciatic nerve from the ligature. Diffusion may also occur although circulation has been stopped throughout the whole body by removal of the heart and other viscera, and the anterior part of the spinal cord may be affected before the posterior when the poison is injected into the dorsal lymph sac.

The advantage of the second method, viz. that of local application, is that it allows us to deal with only one organ at a time, and the results are therefore less complicated than those of the first method. In some respects it is better to begin with the second method and work back from the simpler to the more complex organs.

Paralysis of Motor Nerve Endings.—Curare produces symptoms of paralysis. **Paralysis may be due to** the action of the drug on the **muscles** themselves, on the **motor nerves** which set them in action, or to the **nerve centres** which originate motor impulses. In order to decide this, Bernard applied electricity to the nerves and to the muscles of a frog poisoned by curare administered subcutaneously. He thus found that when the nerve was irritated no effect was produced on the muscles; but that when the muscle itself was stimulated, it contracted readily. In order to decide whether this loss of irritability in the nerve was due to a change in the nerve trunk, or in the terminations within the muscle, Bernard employed the method of **local application.** He placed a solution of curare in two watch-glasses; in one he immersed the trunk of the nerve, Fig. 32, and in the



FIG. 32.—Shows the method of applying a drug in solution locally to the trunk of a nerve.

other the muscle, so that the solution penetrating between the fibres could reach the nerve endings, Fig 33. He then irritated



FIG. 33.—Shows the method of applying a drug in solution locally to a muscle and the ends of motor nerves within it.

the nerve attached to both muscles, and found that irritation caused contraction readily enough in the case where the nerve trunk had been steeped in the solution of curare but had no effect when the curare had been allowed to reach the nerve ends by immersion of the muscle in the solution. The irritability of the muscle itself to mechanical stimuli or to the making and breaking

of a constant current directly applied to it remained quite unaltered, so that the muscular fibre had evidently not been affected by the action of the poison.

The other mode of testing the action of drugs upon motor nerves is to allow the drug to be carried to the muscles and nerve endings by the circulating blood in one leg of a frog, while it is prevented from reaching the other either by ligaturing (Fig. 34) the blood-vessels alone, or ligaturing the whole leg with the exception of the sciatic nerve. After some time has elapsed, the sciatic nerve is stimulated on each side. If the muscles of the poisoned



FIG. 34.—Diagram of the mode of experimenting on motor and sensory nerves in the frog.—The shaded part shows where the poison has been carried by the circulation. The unshaded left leg shows where the tissues have been protected from the poison by ligature of the artery just above the knee. The unbroken lines with arrows pointing to the spinal cord indicate the sensory nerves. The broken line with arrows pointing outwards indicates the motor nerve to the unpoisoned leg.

limb do not contract at all or do so more feebly than in the unpoisoned limb, it is evident that the poison has paralysed either them or the motor nerves. In order to decide whether the nerves or the muscles are paralysed the muscle is next stimulated directly; if it then contracts normally it is evident that the paralysis observed when the nerve was irritated is due to the action of the drug on the nerve endings. If the muscle is completely paralysed no definite conclusion can be drawn regarding the nerve endings, but if the muscle shows only partial paralysis, and the paralysis is greater when the nerve is stimulated than when the muscle is stimulated

directly, we conclude that the drug has acted upon both the muscular substance itself and the motor nerve-endings within it.

It is not so easy to prove positively that a drug has increased as that it has diminished the excitability of motor nerves. The fact that the nerves of the poisoned leg are found to be more excitable than those of the ligatured one in such experiments as those just described, does not prove it, for it must be borne in mind that the arrest of the circulation in the ligatured leg lessens the excitability of the muscles and the nerves in it. This effect of the ligature strengthens the proof that a drug has produced paralysis when we find that in spite of the freer circulation the poisoned leg is less irritable than the ligatured one, but it prevents our concluding that the drug has increased excitability when we find that the poisoned leg responds more readily to stimuli than the ligatured one.

To try whether a drug increases excitability we treat two muscles with saline solution, and after ascertaining that their excitability is alike we add the drug to be tested to the saline solution in which one muscle is steeped, and after some time test the excitability again. If the muscle in the poisoned saline solution becomes more excitable than the other, we conclude that the increase is due to the action of the drug. The muscles and ends of the motor nerves being thus protected in the ligatured leg from the action of the poison while it still remains in connection with the nerve centres by means of the sciatic nerve, it serves as an index to show what is going on in the nerve centres. Thus in a frog poisoned by curare it is found that the ligatured leg moves on irritation of the sensory nerves, while all the poisoned parts remain perfectly still. This shows that the afferent nerves are still capable of conveying impressions to the spinal cord, and the cord itself of reflex action, although the poisoned limbs give no indication of the changes which are occurring in the nerve centres. By and by irritation of a sensory nerve or root ceases to produce any movement even in the ligatured limb. This effect is shown to be due to paralysis of the nerve centres by observing the effect of irritation of the nerves in the ligatured limb, for the muscles still respond readily to irritation of the nerve by a moderate stimulus. We may conclude with tolerable certainty that the motions have ceased in the limbs because the nerve centres have become paralysed.

Many other drugs have an action somewhat similar to that of curare upon the motor nerves :—

Ammonium cyanide.[1]	Di-methyl ammonium chloride.[1]
„ iodide.	„ „ iodide.[1]
Ethyl ammonium chloride.[1]	„ „ sulphate.[1]
Amyl ammonium chloride.[1]	Di-ethyl „ chloride.[1]
„ „ iodide.[1]	„ „ iodide.[1]

[1] Brunton and Cash, *Roy. Soc. Proc.*

Amyl ammonium sulphate.[1]
Tri-methyl „ iodide.[2]
Tri-ethyl „ chloride.
„ „ iodide.
„ „ sulphate.
Tetra-methyl „ iodide.
Tetra-ethyl „ „
Anchusa.[3]
Methyl aniline.[4]
Ethyl „ [4]
Amyl „ [4]
Methyl atropine.[2]
Methyl brucine.[2]
Ethyl „ [3]
Camphor.
Methyl cinchonine.[3]
Amyl „ [3]
Chloroxethylene.
Methyl codeine.[2]
Collidine.
Conïne.
Di-methyl conïne.[2]
Cotarnine.[3]
Cynaglossine.[5]
Di-ethyl Ammonium sulphate.[1]
Curarine.[6]
Curare.[7]
Ditaïne.[8]
Methyl-delphinine.[3]
Echium.[3]
Erythrina coralledendron.[9]
Guachamachà.[10]
Lobeline.
Methyl morphine.[2]
Methyl nicotine.[2]
Ethyl „ [3]
Ptomaïnes.[11]
Methyl quinine.[3]
„ quinidine.[3]
„ piperidine.
Saponine.
Sparteine.
Methyl strychnine.[2] [12]
Ethyl strychnine.[2]
Methyl thebaïne.[2]
Methyl veratrine.[3]
Amyl „ [3]

Although the substances mentioned in the above list have all the power of paralysing motor nerves, they do not possess the same power as curara. In the case of the salts of ammonium and the compound ammonias, the curara-like action is accompanied by a paralysing effect upon the muscular substance and on the nerve centres. When salts of these substances are employed, their effect is somewhat modified by their acid radical, although this is not the case to the same extent in the salts of the compound ammonias and in the salts of ammonia itself. Thus, the iodide of ammonium has a much stronger paralysing action on the nerves than bromide, chloride, sulphate, or phosphate, and this is observed also, though to a less extent, in the salts of the compound ammonias.

[1] Brunton and Cash, *Roy. Soc. Proc.*
[2] Crum-Brown and Fraser, *Trans. of Roy. Soc. of Edinburgh.*
[3] Buchheim and Loos, Eckhard's *Beiträge*, Bd. v.
[4] Jolyet and Cahours, *Compt. Rend.* lxvi. p. 1181.
[5] Diedülin, *Med. Centralbt.* 1868, p. 211.
[6] Preyer, *Göttingen Ztschr. f. Chemie*, 1, p. 381.
[7] Bernard and Kolliker.
[8] Harnack, *Arch. f. Exp. Path. u. Pharm.* vii. p 126.
[9] Harnack, Buchheim's *Pharmacologie*, 3rd edition, p. 615.
[10] Sachs, *Archiv, f. Physiol.* 1877, p. 91 ; Schiffer, *Deutsch. Med. Wochenschr.* 1882, No. 28.
[11] Several authors quoted by Guareschi and Mosso, *Les Ptomaïnes*, 1883.
[12] Schroff, *Wochenblatt d. Ztschr. d. Aerzte zu Wien.* No. 14, 1866.

Irritation of Motor Nerve-endings by Drugs.—The peripheral terminations of motor nerves in muscle appear to be irritated by certain poisons, so that the excised muscle exhibits fibrillary twitchings. This might be due to irritation of the muscular structure itself, but as they are gradually abolished by curare they are supposed to depend upon irritation of the terminations of motor nerves. The poisons which produce this effect are: aconitine, camphor, guanadine, nicotine, pilocarpine, pyridine. Physostigmine produces it most markedly in warm-blooded animals, but does not seem to cause it in frogs.

Action of Drugs on the Trunks of Motor Nerves.—Nerve trunks are as a rule very much less affected by poison than the end plates; but they may, nevertheless, be also acted upon by strong solutions of poison. It appears necessary to apply the poison locally to them, and they are probably little if at all affected by poisons introduced into the system generally. The action of poisons is tested by placing a small piece of gutta-percha tissue under the nerve trunk, usually the sciatic of the frog, and applying the poison directly to it, or dipping the nerve into a weak solution of common salt, or of sodium phosphate, to which the poison has been added, and comparing the poisoned nerve with one dipped into a similar saline solution without the poison.

There are two methods of comparison. The first consists in using the contraction of the corresponding muscle as an index of the functional power of the nerve. The second, in ascertaining the effect of the poison on the normal electrical current in the nerve.

The motor fibres of a nerve appear to have their excitability abolished more readily than that of sensory nerves by changes in the body generally, and sometimes also by the local application of drugs to them. Thus in wounded nerves the motor function may be destroyed, while the sensory function is little altered, and where both sensibility and motion have been destroyed by a bruise of the nerve trunk, the sensibility may reappear, while the motor power does not. In rheumatic neuralgia there is not unfrequently motor paralysis with exaggerated sensibility. When a solution of physostigma is applied locally to the nerve trunk for a while, and the nerve is then irritated beyond the point of application, it is found that it will produce reflex movements of the body after it has ceased to do so in the limb supplied by the nerve, which shows that the sensory fibres can still conduct impressions, though the motor fibres cannot. Longer application of the poison will destroy the sensory fibres also. When a paste of theine is applied to the sciatic nerve, or the nerve is dipped in a solution of opium, similar results are observed.

By dipping nerves in a solution of poison Mommsen finds that atropine diminishes the irritability of the nerves, affecting first the intramuscular endings, and afterwards the trunks. Alcohol, ether, and chloroform, first increase and then diminish the irritability.

Action of Drugs on Sensory Nerves.

The general action of a drug on sensory nerves is much more difficult to ascertain with precision than its effect upon motor nerves, because the evidences of sensation we have in the lower animals, are cries, and movements either of the limbs or involuntary muscles, such as the iris, arteries or bladder, which ensue on irritation of sensory nerves.

In the production of these movements or cries, many structures are concerned, viz. sensory nerves, nerve centres, spinal or cerebral motor nerves, and muscles. It is comparatively easy to ascertain the local action of the drug upon sensory nerves, for in this case these other structures are not affected. By applying the substance to one part of the body, either by painting it upon, or injecting it under, the skin, and then comparing the effect of stimulation produced by pinching or by the application of heat or electricity upon that and other parts of the surface, we can see whether or not the sensibility of the sensory nerves has been affected by the drug.

But when the drug is absorbed into the circulation, it may affect all the other structures already mentioned, as well as the sensory nerves, and thus it may be impossible to decide with certainty whether these nerves are affected or not. But even here definite results are sometimes obtainable as in the case of curare. The method of experimenting is to ligature the sciatic artery of a frog and arrest the circulation in one leg. The animal is then poisoned with curare, or any drug the action of which is to be ascertained. The poison is carried by the circulation to all other parts of the body excepting the ligatured leg.

In the case of curare the motor nerves are paralysed by the drug, and it would be impossible to ascertain whether irritation of the sensory nerve produced any effect at all, were it not that the ligatured limb, retaining its irritability, serves as an index to the condition of the nerve centres. At first it is found that pinching the poisoned foot will cause movements in the non-poisoned leg. This shows that the sensory nerves retain their irritability and transmit the stimulation up to the spinal cord, whence it is reflected down the motor nerves to the non-poisoned foot.

As the poisoning becomes deeper, however, pinching the poisoned leg produces much less effect.

This might be due to paralysis of the spinal cord, but it is shown that this is not the case by pinching the ligatured leg just above and below the ligature.

It is found that a pinch just below the ligature causes marked reaction, while a pinch just above has little or no effect.

In this experiment all the structures concerned in the movement have been alike subjected to the action of curare with the

exception of the ends of the sensory nerves below the ligature, It is thus evident that the diminished reaction from pinching above the ligature is due to paralysis of the ends of the sensory nerve, in the part of the body to which the poison has had access, and which is shaded dark in the engraving (Fig. 34).

In the experiment just mentioned, the first of the two methods already described in the reference to motor nerves is employed, and the action of the drug on the ends of sensory nerves is ascertained by preventing the poison from reaching them; but the second method may also be employed and the action ascertained by applying the poison to the ends of the sensory nerves, while the nerve-trunks and nerve-centres are protected from its action. Thus, in the experiments of Liégeois and Hottot upon the action of aconitine on the sensory nerves, they ligatured the vein and injected the poison into the artery of a frog's leg; the poison was thus carried to the ends of the sensory nerves in the skin, while it was prevented from reaching the nerve centres. In this way they found that irritation of the poisoned skin ceased to produce any reflex action, while stimulation of the trunk of the nerve distributed to that leg still caused well-marked reflex action. Normally the terminations of a sensory nerve in the skin are much more sensitive than the trunk of the nerve; and this experiment therefore proves that aconitine paralyses the ends of the sensory nerves.

The local action of drugs on the sensory nerves in man is ascertained by producing, when applied locally, either diminution in pain which may be present at the time, or insensibility which is usually ascertained by the æsthesiometer. This is simply a pair of compasses with blunt points and a scale by which the distance of the points from one another can be read off.

When the sensation is acute, the points are distinctly felt as two, even when they are but slightly separated from one another; but when the sensation is blunt, they are felt as one, when they are at a considerable distance apart.

In frogs it is ascertained by dipping one leg for some time in the solution to be tested, and then comparing the effect of irritating corresponding points in the two feet or legs by pinching, or the application of acids, or a faradaic current. Where the drug is very powerful, and a sufficient quantity, its action on the nerve centres might complicate the result; if a sufficient quantity should be absorbed into the blood, the circulation may be entirely arrested by excision or ligature of the heart. In this way it has been ascertained that hydrocyanic acid has a powerful local action in paralysing sensory nerves.

Local Sedatives and Local Anæsthetics.—Local sedatives are substances which diminish, and local anæsthetics are substances which destroy, the sensibility of the skin for the time being.

Local Sedatives.
Aconite.
Atropine.
Belladonna.
Carbolic acid.
Chloroform.
Chloral.
Morphine.
Opium.
Veratrine.

Local Anæsthetics.
Extreme cold.
Ice.
Ether spray.
Carbolic acid.

Action.—Their effect in some degree is due to a paralysing action upon the terminal branches of the cutaneous nerves. It is probably, to some extent, also due to an effect upon the vessels and tissues analogous to that which is produced by rubbing or scratching, which, as every one knows, gives temporary relief to itching. Sweating also relieves the itching, which is sometimes felt just before it begins.

Uses.—Local sedatives are employed to relieve itching and to lessen pain, whether it be due to neuralgia or inflammation. Local anæsthetics are employed temporarily to abolish the sensibility of the skin, and allow slight incisions or operations to be made painlessly.

Stimulating Action of Drugs on the Peripheral Ends of Sensory Nerves. — The peripheral terminations of sensory nerves appear to become more sensitive when the supply of blood to the part is increased. This is markedly seen, not only in inflammation, where the part becomes exceedingly tender, but in cases where turgescence of the vessels occurs under physiological conditions. Besides the class of irritants which act on the peripheral terminations of sensory nerves so as to cause pain when locally applied, there are several drugs which appear to have a special irritant action on the ends of sensory nerves when introduced into the circulation: these are aconite and aconitine, which give rise to a peculiar tingling and numbness in the tongue, lips, cheeks, and indeed in all parts supplied by the fifth nerve. Veratrine also causes peculiar sensations in the sensory nerves when taken internally, but these are felt more in the fingers and toes, and in the joints, than in the tongue.[1]

[1] Von Schroff, *Pharmacologie*, 4th Ed. p. 584.

CHAPTER VII.

ACTION OF DRUGS ON THE SPINAL CORD.

In the spinal cord we have to distinguish three functions: that of **conduction,** that of **reflex action,** and that of **origination** of nerve force, as in the sweat centres, &c., contained in it.

The spinal cord **transmits** sensory or afferent impulses **upwards** to the medulla and brain; and motor impulses **downwards** to the muscles as well as other efferent impulses to the glands. It transmits reflex impulses **across,** either from behind forwards, or laterally from one half of the cord to the other. Transmission from behind forwards occurs when the impulse passes from the sensory to the motor columns on the same side, as in the case of reaction of a sensory stimulus on the same side of the body. It occurs laterally when the sensory stimulus produces motion, not on the same side, but on the opposite side of the body.

Action on the Conducting Power of the Cord.—Its **conducting** power for **motor** impulses is assumed to be impaired when it is noticed that any drug causes partial paralysis of the hinder extremities of an animal before the anterior extremities.

It is usually tested by irritating the spinal cord at its upper end, either mechanically with the point of a needle, or by a galvanic or faradaic current passed through electrodes inserted into it close together, and observing whether irritation of the cord itself in this way causes contraction in the muscles of the legs.

When no contraction is produced by irritation of the cord itself, while direct irritation of the motor nerves can still produce vigorous contraction, it is evident that the cause of the paralysis must be that the spinal cord has lost its power to conduct motor impulses.

These experiments may be made in a frog, the cerebrum of which has been previously destroyed; and they may be confirmed in warm-blooded animals where sensibility has been destroyed by a section of the cord, just below the medulla, and respiration is kept up artificially. The spinal cord is then exposed, and the anterior columns are irritated in the ways already mentioned.

The power of the cord to **conduct sensory impressions** is ascertained by exposing it under anæsthetics and allowing their influence to pass so far off that the animal is capable of giving evidence of sensation. The posterior roots are then irritated before and after the injection of the poison into the circulation.

When it is found that after the poison is injected, the irritation of the posterior roots which previously caused evidence of sensation, no longer produces any effect, while irritation of the anterior columns still produces motion: the conclusion appears to be just, that the poison has paralysed the conducting power of the sensory columns of the cord.

This action appears to be possessed by caffeine, for Bennett found that while irritation of the posterior roots of the cord caused violent struggles and loud cries in a rabbit before the injection of caffeine into the circulation, similar irritation, after the injection, caused only a slight quiver. That this effect was not due to motor paralysis was shown by the fact that irritation of the anterior columns caused violent muscular contractions after the injection as well as before it.[1]

The action of drugs on the power of the spinal cord to **conduct reflex stimuli** both transversely and longitudinally has been carefully investigated by Wundt. He first ascertains the time which elapses between the application of a stimulus to a motor nerve and the contraction of a muscle, the nerve used being the sciatic, and the muscle the gastrocnemius of a frog. This time, which includes that requisite for the stimulus to travel down the motor nerve and to set the muscle in action, he terms the direct latency. He next stimulates a sensory root of the spinal cord at the same level and on the same side as the motor nerve, taking care that the stimulus does not act on the motor nerve directly but only reflexly through the cord. The time between the application of the stimulus and the commencement of contraction he terms the total latency. By deducting the direct latency from the total latency he ascertains the time required for the stimulus to pass through the grey matter of the cord from the posterior to the anterior horn of the same side. This he calls the **reflex time.**

The time required for **transverse** conduction is ascertained by applying the stimulus to a posterior root on the other side and comparing the latency with that of stimulation to a posterior root on the same side.

The time required for **longitudinal** conduction is ascertained by applying a stimulus to the brachial nerve, so that it has to travel down the greater part of the length of the spinal cord before it can excite the sciatic nerve. By comparing the latent period of excitation in the brachial nerve with that of the sciatic on the

[1] Hughes-Bennett, *Edin. Med. Journ.* Oct. 1873.

same side[1] the length of time required for longitudinal transmission of stimuli in the cord is ascertained. The mode of ascertaining the time of ordinary reflex and transverse transmission in the cord is shown diagrammatically in Fig. 35.



FIG. 35.—Diagram to show the method of investigating reflex and transverse conduction in the spina cord. The motor nerve is first irritated at 1. As the cylinder revolves at a known rate, and a mark is made upon it by an electromagnet at the instant the nerve is irritated, the distance between this mark and the commencement of the muscle curve indicates the time required for the irritation to travel down the motor nerve to the muscle and set it in action. The irritation is next applied to the posterior root on the same side (2). The distance between the commencement of contraction in this case and in that where the motor nerve was irritated gives the time required for simple reflex transmission of the stimulus from the posterior to the anterior horn of the cord. The stimulus is then applied to the posterior root on the opposite side at 3, and the distance between the commencement of the consequent contraction and that of the curve obtained by irritating at 2 gives the time required for transmission across the cord.

The differences in the latent period and in the form of the muscle curve obtained by irritation of the motor nerve, and by simple transverse, and longitudinal reflex stimulation, are shown diagrammatically in Fig. 36. Wundt found that when a motor nerve was



FIG. 36.—Diagram to show the difference between the length of the latent period and form of the curve in contraction induced, B, by direct irritation of the motor nerve; C, by simple reflex from irritation of the cord on the same side; and D, by cross reflex from irritation of the cord on the opposite side to that from which the motor nerve proceeds, as shown in Fig. 35. E shows combined transverse and longitudinal reflex; A indicates the moment at which the stimulus was applied in each case.

irritated at the point distant from the muscle the resulting contraction had not only a longer latent period but was less in height and longer in duration than when the nerve was irritated close to

[1] For convenience' sake both the sciatic and the brachial nerves are taken in this experiment on the opposite side from the muscle, so that the time of longitudinal conduction is ascertained by deducting the transverse from the combined transverse and longitudinal conduction.

the muscle. From a comparison of the curves it will be seen that a **small portion of grey matter** has a **similar effect** upon the stimulus which passes through it that a **great length of nerve fibre** would have. In all reflex actions, therefore, in the normal animal, the contraction of the muscle has a longer latent period, less height, and longer duration than that produced by direct irritation of the motor nerve. The increase in the latent period, diminution in height, and longer duration are greater in the case of transverse than of simple reflex, and greater still in the case of combined transverse and longitudinal reflex.

In the normal frog a stronger stimulus is necessary to produce reflex contraction than would be sufficient if it were applied directly to the motor nerve, and strong and weak stimuli will produce strong and weak muscular contractions. The spinal cord has a power of **summation** similar to that already referred to in the case of contractile tissue of medusæ, so that a stimulus which would be powerless to produce a reflex contraction if applied once to a posterior root or to a sensory nerve will be effectual if repeated several times in close succession. Strychnine has an effect on the conducting power of the spinal cord which we should hardly expect, and so have other convulsant poisons. It increases the excitability so much that slighter stimuli than before will produce reflex action, and it destroys to a considerable extent the power of summation, so that instead of each stimulus producing a contraction in proportion to its strength all have the same effect—a weak one which is just strong enough to produce an effect at all causing as great a contraction as the most powerful. The time required for the transmission of stimuli through the cord is enormously increased, so that the latent period of ordinary reflex, and still more of transverse and longitudinal reflexes, is greatly increased, sometimes, indeed, to as much as ten times the normal. The retardation of transverse conduction is not absolutely greater than of longitudinal conduction, but, as the distance through which the stimulus has to pass in the former case is much greater than in the latter, it follows that strychnia increases the resistance more transversely than longitudinally. Morphine in small doses has no very marked action upon the cord, but larger doses have an action almost exactly like that of strychnine, causing increased reflex irritability, tetanic contractions, and prolonged latency. Veratrine has a similar action. Nicotine and coniine in small doses have a similar action to strychnine, but this is quickly masked by the rapid appearance of paralysis. When large doses are used, paralysis occurs almost immediately, and is usually accompanied by fibrillary twitchings. Atropine has at first an action similar to strychnine in causing increased excitability, prolonged latency, and tetanic contraction. It differs from strychnine in causing more rapid diminution in the irritability of the grey substance of the spinal cord and in diminishing the conducting power of peripheral nerves. In

consequence of this, irritation of the sciatic nerve in a frog poisoned by atropine causes two contractions, one direct and one reflex, separated from each other by a distinct interval, whereas, in a frog poisoned by strychnine, these two contractions begin almost at the same moment and appear superimposed upon each other.

Ordinary impressions of touch, temperature, and muscular action are transmitted through the posterior roots of the spinal cord to the ganglia of the posterior horn of the grey substance, and thence upwards by the fibres of the lateral columns. Painful sensations, however, appear to be transmitted upwards through the grey substance of the cord. The afferent nerves, which transmit impressions from one part of the cord to another so as to produce co-ordinated reflex movement, are contained in the posterior columns of the cord.

It is evident that any injury or poison which chiefly affects the grey matter so as to diminish its conducting power may abolish pain while reflex action still persists. This condition may be produced by division of the grey matter of the cord, and it occurs also at a certain stage of the action of anæsthetics such as chloroform and ether.



FIG. 37.—Diagram to show the effect of chloroform, chloral, and other anæsthetics on conduction of painful impressions in the spinal cord.

Action of Drugs on the Reflex Action of the Cord.—The action of drugs upon the reflex action of the spinal cord, is usually estimated by the time which elapses between the application of a stimulus and the occurrence of reflex action, before and after the administration of a drug. Longer time indicates diminished, and shorter time increased, excitability of the cord.

Method of Experimenting.—The method usually employed is called Türck's method. The cerebral lobes in a frog are destroyed, and after some time has elapsed so as to allow it to recover from the shock, it is suspended either by the head or fore-legs, so that the hind-legs hang down. A very dilute solution of sulphuric acid, the acid taste of which can be little more than perceived by the tongue, is put in a small beaker and raised until one foot of the frog is completely immersed in it. The time is then counted by means of a metronome, between the immersion of the foot in the acid solution, and the time when the leg is drawn up out of it. As soon

as the foot is drawn up, the acid is carefully washed off with some fresh water in order to prevent any injury to the skin, and after a minute or two, the experiment may be repeated. When the time seems constant the drug is injected into the lymph sac, and the experiment is repeated again. The greater or less time which is required for the withdrawal of the foot from the acid after the injection of the poison, as compared with the time required before, shows the extent to which the reflex action of the spinal cord has been diminished or increased by the poison.

Direct, Indirect, and Inhibitory Paralysis of the Spinal Cord by Drugs.—When it is found that the reflex action of the cord is greatly diminished or apparently entirely abolished, it must not be at once concluded that this is necessarily due to the **direct** paralysing action of the drug itself upon the nervous substance of the cord. This may be the case, and is so when methyl-conïne is employed, but it may be due to the **indirect** action of the drug upon the heart, weakening the circulation, and lessening the function of the cord by interfering with its blood supply.

In order to ascertain whether this is the case or not, it is usual to take two frogs as nearly alike as possible, to destroy the brain in each, and after waiting until they have recovered from the immediate shock of the operation, to inject into one the drug to be tested, and, at the moment when it stops the beating of the heart, to tie a ligature around the heart of the other. The persistence of reflex action is then tested in the usual manner, and if it is found that it disappears much sooner in the poisoned frog than in the other one where the heart has been ligatured, it is concluded the drug has paralysed the substance of the cord itself.

Indirect Paralysis.—The spinal cord is very rapidly paralyzed in mammals if the blood supply to it is stopped. This is readily shown by Stenson's experiment of gently compressing the abdominal aorta in a rabbit with the thumb or finger, so as to arrest the circulation for four or five minutes. On releasing the animal its hinder extremities are found to be paralyzed, and this paralysis, though it may be partly due to interference with the blood supply of the muscles and nerves of the lower extremities themselves, is chiefly due to the arrest of circulation in the spinal cord. The spinal cord in frogs is less rapidly affected, but if the circulation be arrested for half an hour or so symptoms of paralysis usually begin to appear, the time varying, however, with the temperature and other conditions. Indirect paralysis is produced by aconitine, digitalin, and large doses of quinine, which arrest the circulation. It is frequently difficult to decide how far paralysis is due to the action of a drug on the circulation and how far to its direct action on the spinal cord itself.

Direct Paralysis.—Paralysis of reflex movement is produced by a number of substances, some of which produce little or no previous excitement; others, however, markedly increase the excitability of the spinal cord first, and are thus classed as spinal stimulants.

Spinal Depressants.—The following drugs belong to this class: —

Depress without marked previous excitement.	Excite first and afterwards paralyze.
Antimony.	Ammonia.
Emetine.	Apomorphine.
Ergot.	Alcohol.
Hydrocyanic acid.	Arsenic.
Methylconïne.	Camphor.
Saponine.	Morphine.
Physostigmine.	Carbolic acid.
Turpentine.	Chloral.
Zinc.	Nicotine.
Silver.	Potassium.
Sodium.	Veratrine.
Lithium.	Mercury.
Cæsium.	

Uses of Spinal Depressants.—Such substances as morphine, chloral, &c., which diminish the conducting power of the grey matter of the cord for painful impressions, are useful as anodynes, though their action in lessening pain is probably often due to their effect on the brain as well as on the spinal cord. Spinal depressants which lessen reflex action are employed in diseases where there seems to be increased excitability of various parts of the cord, as evidenced by spasm either tonic or clonic. They are therefore employed in tetanus, trismus neonatorum, chorea, writer's cramp, and paralysis agitans. The pathology of many nervous diseases is imperfectly known, and as the action of spinal depressants is frequently a complex one of combined stimulation and depression, some of the drugs included in this class are used in paraplegia due to myelitis, locomotor ataxy, and general paralysis.

They are also used as antagonists in cases of poisoning by spinal stimulants like strychnine.

Inhibitory Paralysis.—The higher parts of the nervous system have the power of lessening the action of the lower, and in the frog this power seems to be especially marked in the optic lobes. Irritation of these either mechanically by a needle, chemically by a grain of salt laid upon them, or electrically, will lessen or entirely abolish the reflex action in the cord, but this again returns when the irritation is removed, or when its influence is destroyed by cutting the cord across, below the point of irritation. This fact was discovered by Setschenow, and thus parts of the optic lobes concerned in this inhibitory action are known as Setschenow's centres.

An inhibitory action appears to be exerted by the cranial centres in higher animals also, for McKendrick observed that on decapitating a pigeon the body lies comparatively still for a second or two, and then violent convulsions set in. If the body be held

firmly during these convulsions, and a moderately strong faradaic current be applied to the upper part of the spinal cord, the convulsions may be altogether arrested while it continues, again commencing when it stops. In this experiment the application of the current to the cut end of the cord is regarded as supplying a stimulus in place of that which would normally pass downwards from the brain.

Quinine causes great depression of reflex excitability, and this was stated by Chaperon to be due to the action of the drug on Setschenow's centres.



FIG. 38.—Nervous system of a frog, showing the cerebral and optic lobes, the medulla oblongata, and the spinal cord with nerve-roots. The brain is shown on a larger scale at p. 153.

Almost immediately after injection of quinine into the dorsal lymph sac, the reflex excitability of the frog becomes very greatly reduced or almost entirely abolished, but if the spinal cord be now cut across at its upper part, just below the medulla oblongata, the reflex excitability becomes as great, or even greater, than the normal.

This loss of excitability has been ascribed by Binz to the action of quinine on the heart, causing weakening of the circulation, and thus indirectly producing paralysis of the cord. This kind of paralysis does occur with large doses and after considerable time, but it is quite different from the inhibitory paralysis described by Chaperon, which comes on almost immediately after the injection of the drug into the lymph sac, and disappears immediately on section of the cord below the medulla.

I have repeated Chaperon's experiments, and can fully confirm their accuracy. In doing so, however, it struck me that the result was most marked when a solution of quinine was concentrated and somewhat strongly acid. It therefore appeared probable that the inhibition was not due to the direct action of the quinine upon Setschenow's centres after it had been carried to them by the blood, but only to its reflex action upon them. It irritates locally the sensory nerves of the lymph sac into which it is injected, and this stimulus being transmitted to the optic lobes excites them so that they produce inhibition of that reflex action which would usually occur in the cord when the foot is irritated by acid. On testing this hypothesis by injecting acid alone into the lymph sac, Mr. Pardington and I found that it also caused reflex inhibition like that produced by quinine. We may therefore conclude that

there is nothing special in the action of quinine upon the inhibitory centres; it merely acts like other irritants on sensory nerves.[1] Probably digitalis and sanguinaria also act in a similar way.

NATURE OF INHIBITION.

Inhibition and the action of drugs on inhibitory centres play a very important part indeed in pharmacology, and on the present hypothesis they are very puzzling.

By inhibition we mean the power of restraining action which some parts of the nervous centres possess. At present it is usually supposed that certain parts of the nerve centres, instead of having a sensory or motor function, have an inhibitory one peculiar to themselves. As it is found, however, that inhibitory powers are not confined to Setchenow's centres, already mentioned, page 135, but that almost any part of the nervous system may have an inhibitory action on other parts, it becomes almost necessary to abandon the old hypothesis. It is found, for example, that not only is reflex action more active in the frog when the optic lobes are removed, but that when the spinal cord is taken away in successive slices from above downwards, the reflex action in the part below goes on increasing. On the old hypothesis we are almost obliged to assume that each nerve cell has two others connected with it, one of which has the function of increasing or stimulating, and the other of inhibiting its action. Most of the phenomena which we find can be explained in a much simpler way by supposing that nervous stimuli consist of vibrations in the nerve fibres or nerve cells, just as sound consists of vibrations.

Interference.—In the case of both sound and light we find that if two waves should fall upon one another so that their crests coincide, the intensity of the sound or light is increased (Fig. 39),



FIG. 39.—Diagram to show increased intensity of vibration by coincidence of waves.



FIG. 40.—Diagram to show abolition of vibration by interference of waves.

while if they fall on each other so that the crest of one wave fills up the trough of the other, they interfere so as to destroy each other's effect (Fig. 40); and thus two sounds produce silence, or two waves of light, darkness. This is shown in the case of sound by a tube (Fig. 41), which divides into two branches, and these

[1] *St. Bartholomew's Hospital Reports*, 1876, p. 155.

again re-unite. The length of one branch may be altered at will so that the sound travelling through one branch has further to go than the other. It may thus be retarded so far as to throw it half a wave-length behind the other, and silence is produced. If lengthened still further, so as to throw the one sound a whole



FIG. 41.—Diagram of apparatus for demonstrating the interference of waves of sound. A and B, branches of a tube; C, sliding piece by which the branch B can be lengthened or shortened at will; D, tuning-fork; E, the ear.

wave-length behind the other, the crests again coincide, and the sound is again heard. Increasing the length still further, so that the one sound is thrown a wave-length and a half behind the other, they again interfere, and silence is again a second time produced. This may be repeated *ad infinitum*, silence occurring whenever the one sound falls behind the other, by an odd number of half wave-lengths.



FIG. 42.—Diagram showing the beats or alternate increase and diminution of the wave-heights by the interaction of two systems of waves of different wave-lengths. At A two systems, having a relation to each other of 3 to 1, are indicated separately by dotted and complete lines. At B the resultant of the interaction of the two systems is shown. With such a relation as that shown in the diagram, and with those of a vibrating rod generally, such as n, 3n, 5n, &c., the interference of the systems is not complete, and silence cannot be produced by the interference of sounds. (From Ganot's *Physics*.)

In the case just mentioned, the waves are of the same length, but if they are of different lengths, instead of constantly reinforcing and interfering with others, they may sometimes strengthen and sometimes weaken each other. The result is more or less rhythmical increase and diminution of action, or as it is termed "beats." This is shown in the accompanying diagram (Fig. 42).

Instances of rhythm occur in the body, which strongly remind us of this condition, for example, the different rhythms of the heart under various conditions.

Interference in Nervous Structures.—Supposing nervous stimuli to consist of vibrations like those of light or sound, the action which any nerve cell would have upon the others connected with it would be stimulant or inhibitory according to its position in relation to them. If its relation be such that a stimulus passing from it to another cell will there meet with a stimulus from another quarter in such a way that the waves of which they consist coincide, the nervous action will be doubled: but if they interfere the nervous action will be abolished. If they meet so as neither completely to coincide nor to interfere, the nervous action will be somewhat increased, or somewhat diminished, according to the degree of coincidence or interference between the crests of the waves.

Thus if the relations of the nerve cells S, S′ and M, M′ in the diagram (Fig. 43) are such that when a stimulus passes from a



FIG. 43.—Diagram to illustrate inhibition in the spinal cord. *s*, *s′*, and *s″* are sensory nerves, *m*, *m′*, and *m″* are motor nerves, S, S′, and S″ are sensory cells, M, M′, and M″ are motor cells in the spinal cord, SB is a sensory, and MB a motor cell in the brain.

sensory nerve *s* to a motor nerve *m*, one part of it travels along the path *s*, S, M, *m*, and another along *s*, S, S′, M, *m*, or *s*, S, S′, M, M, *m*, at such a rate that the crests of the waves coincide at the motor cell M, they will increase each other's effect. If they interfere, the effect of both will be diminished or destroyed, *i.e.* inhibition will occur.

Effect of Altered Rate of Transmission.—But it is evident that the coincidence or interference of nervous stimuli travelling along definite nerve paths, will vary according to the rate at which they travel, so that when stimuli, which ordinarily interfere with one another, are made to travel more slowly, one may be thrown a whole wave-length, instead of half a wave-length, behind the other: and thus we get coincidence and stimulation, instead of interference and inhibition. When stimuli, whose waves ordinarily coincide and strengthen each other's action, are made to travel more slowly, one may be thrown half a wave-length behind

the other, and thus we shall have interference and inhibition instead of stimulation.

On the other hand, when the stimuli travel more quickly, the one which was half a wave-length behind the other, and interfered with it, may be thrown only a small fraction of a wave-length behind it. It will thus, to a great extent, coincide and cause stimulation, while the one which normally coincides with, and helps another, may, by travelling with increased rapidity, get half a wave-length in front of the other, and cause inhibition.

Opposite Conditions Produce Similar Effects.—We see then that results, apparently exactly the same, may be produced by two opposite conditions, increased rapidity or greater slowness of transmission of stimuli.

The Same Conditions may Cause Opposite Effects.—We see also that the same conditions may produce entirely opposite effects, by acting more or less intensely. Thus, the application of cold, or of any agent which will render the transmission of stimuli along nervous channels slower than usual, may throw one which ordinarily coincided with another a small fraction of a wave-length behind it, then half a wave-length, then three-quarters, next a whole wave-length, and then in addition to the whole wave-length it will throw it as at first a small fraction or a half wave-length behind, and so on.

We will thus have the normal stimulation passing into partial, then into complete inhibition, which will gradually pass off as the crests of the waves come more nearly together, until they coincide, when we will again have stimulation as at first. As the action proceeds, this second stimulation will again pass into inhibition. In the same way a gradual retardation of transmission will cause impulses which normally interfere, gradually to coincide until inhibition gives place to complete stimulation, and this again passes into inhibition. By quickening the transmission and throwing one wave more or less in advance of another, various degrees of heat will likewise produce opposite effects.

Stimulation and Inhibition on this Hypothesis are merely Consequences of Relation.—They are not due to any particular stimulating or inhibitory centres, they are merely dependent on the wave-length of nervous stimuli or the rapidity of transmission, and on the lengths of the paths along which they have to travel. Any nerve cell may therefore exercise an inhibitory or stimulating action on any other nerve cell, and the nature of this action will be merely a question of the length and arrangement of its connections, and the rapidity with which stimuli travel along them.

Test of the Truth of the Hypothesis.—If the hypothesis be true we ought to be able to convert inhibition into stimulation, and *vice versâ* by either quickening or slowing the transmission of stimuli. We can quicken transmission by heat, and we can render it slower by cold.

On this hypothesis we would expect to find that either excessive quickening or excessive slowing of the passage of stimuli between the cells of the nerve centres might cause a number of stimuli which would ordinarily interfere to coincide and produce convulsions. This is what actually does occur, for extreme heat and extreme cold both cause convulsions. But it is unsafe to lay too much stress upon this point, as the cause of convulsion may be very complex. We find, however, that, as we would expect on this hypothesis, the inhibitory action of the vagus is destroyed by cold.[1]

Explanation of the Actions of Certain Drugs on this Hypothesis.

There are certain phenomena connected with the action of drugs on the spinal cord which are almost inexplicable on the ordinary hypothesis, but which are readily explained on that of interference. Thus belladonna when given to frogs causes gradually increasing weakness of respiration and movement, until at length voluntary and respiratory movements are entirely abolished, and the afferent and efferent nerves are greatly weakened. Later still, both afferent and efferent nerves are completely paralysed, and the only sign of vitality is an occasional and hardly perceptible beat of the heart, and retention of irritability in the striated muscles. The animal appears to be dead, and was believed to be dead, until Fraser made the observation that if allowed to remain in this condition for four or five days, the apparent death passed away, and was succeeded by a state of spinal excitement. The fore-arms passed from a state of complete flaccidity to one of rigid tonic contraction. The respiratory movements reappeared; the cardiac action became stronger, and the posterior extremities extended. In this condition a touch upon the skin caused violent tetanus, usually opisthotonic, lasting from two to ten seconds, and succeeded by a series of clonic spasms. A little later still the convulsions change their character and become emprosthotonic. These symptoms are due to the action of the poison upon the spinal cord itself, for they continue independently in the parts connected with each segment of the cord when it has been divided.

This action may be imitated by a combination of a drug which will paralyse the motor nerves with one which will excite the spinal cord. Fraser concludes that the effects of large doses of atropine just described, are due to a combined stimulant action of this substance on the cord, and a paralysing one on the motor nerves. The stimulant action on the cord is masked by the paralysis of the motor nerves, and only appears after the paralysis has passed off. He thinks that the difference in the relations of

[1] Horwath, *Pflüger's Archiv*, 1876, xii. p. 278.

these effects to each other, which are seen in different species of animals, may be explained by this combination acting on special varieties of organisation. In support of his views he administered to frogs a mixture of strychnine which stimulates the spinal cord, and of methyl strychnine, which paralyses the motor nerves, and found that the mixture produced symptoms similar to those of atropine. Notwithstanding this apparently convincing proof it would appear that the paralysis in the frog is due to the action of the atropine on the spinal cord, and not to a paralysing effect on the motor nerves. For Ringer and Murrell have found that when the ends of the motor nerves in one leg are protected from the action of the poison by ligature of the artery there is no difference between it and the unpoisoned leg, while if Fraser's ideas were correct the unpoisoned leg ought to be in a state of violent spasm.

A condition very nearly similar to that caused by atropine is produced by morphine. When this substance is given to a frog, its effects are exactly similar to those produced by the successive removal of the different parts of the nervous system from above downwards. Goltz has shown that when the cerebral lobes are removed from the frog, it loses the power of voluntary motion, and sits still; when the optic lobes are removed it will spring when stimulated, but loses the power of directing its movements. When the cerebellum is removed, it loses the power of springing at all; and when the spinal cord is destroyed, reflex action is abolished.

Now these are exactly the effects produced by morphine, the frog poisoned by it first losing voluntary motion, next the power of directing its movements, next the power of springing at all, and lastly, reflex action. But after reflex action is destroyed by morphine, and the frog is apparently dead, a very remarkable condition appears, the general flaccidity passes away, and is succeeded by a stage of excitement, a slight touch causing violent convulsions just as if the animal had been poisoned by strychnine.[1]

The action of morphine here appears to be clearly that of destroying the function of the nerve centres from above downwards, causing paralysis first of the cerebral lobes, next of the optic lobes, next of the cerebellum, and next of the cord. But it seems probable that the paralysis of the cord first observed is only apparent and not real, and in order to explain it on the ordinary hypothesis we must assume that during it the inhibitory centres in the cord are intensely excited so as to prevent any motor action, that afterwards they become completely paralysed, and thus we get convulsions occurring from slight stimuli.

Ammonium bromide also causes first complete loss of voluntary movement and reflex action, but at a later stage in the poisoning convulsions occur.

[1] Marshall Hall, *Memoirs on the Nervous System*, p. vii. (London, 1837). Witkowski, *Archiv. für exper. Path. und Pharm.* Band. vii. p. 247.

On the hypothesis of interference, the phenomena produced both by atropine and by morphine can be more simply explained. These drugs, acting on the nervous structures, gradually lessen the functional activity of the nerve-fibrils which connect the nerve-cells together; the impulses are retarded, and thus the length of nervous connection between the cells of the spinal cord, which is calculated to keep them in proper relation in the normal animal, just suffices at a certain stage to throw the impulses half a wave-length behind the other, and thus to cause complete inhibition and apparent paralysis.

As the action of the drug goes on, the retardation becomes still greater, and then the impulses are thrown very nearly, but not quite, a whole wave-length behind the other, and thus they coincide for a short time, but gradually again interfere, and therefore we get, on the application of a stimulus, a tonic convulsion followed by several clonic ones, and then by a period of rest. This explanation is further borne out by the fact observed by Fraser, that the convulsions caused by atropine occurred more readily during winter, when the temperature of the laboratory is low and the cold would tend to aid the action of the drug in retarding the transmission of impulses.[1]

The effect of strychnine in causing tetanus is very remarkable; a very small dose of it administered to a frog first renders the animal most sensitive to reflex impulses, so that slight impressions which would normally have no effect, produce reflex action. As the poisoning proceeds, a slight stimulus no longer produces a reflex action limited to a few muscles, but causes a general convulsion throughout all the body, all muscles being apparently put equally on the stretch. In man the form assumed by the body is that of a bow, the head and the heels being bent backwards, the hands clenched, and the arms tightly drawn to the body.

My friend Dr. Ferrier has shown that this position is due to the different strengths of the various muscles in the body. All being contracted to their utmost, the stronger overpower the weaker, and thus the powerful extensors of the back and muscles of the thighs keep the body arched backwards and the legs rigid, while the adductors and flexors of the arms and fingers clench the fist and bend the arms, and draw them close to the body.[2] The convulsions are not continuous, but are clonic; a violent convulsion coming on and lasting for a while, and then being succeeded by an interval of rest, to which after a little while another convulsion succeeds. The animal generally dies either of asphyxia during a convulsion, or of stoppage of the heart during the interval.

When the animal is left to itself, the convulsions—at least in frogs—appear to me to follow a certain rhythm, the intervals remaining for some little time of nearly the same extent.

[1] *Transactions of the Royal Society of Edinburgh*, vol. xxv. p. 467.
[2] *Brain*, vol. iv. p. 313.

A slight external stimulus, however, applied during the interval —or at least during a certain part of it—will bring on the convulsion. But this is not the case during the whole interval. Immediately after each convulsion has ceased I have observed a period in which stimulation applied to the surface appears to have no effect whatever.

It is rather extraordinary, also, that although touching the surface produces convulsions, irritation of the skin by acid does not do so.[1]

The cause of those convulsions was located in the spinal cord by Magendie in an elaborate series of experiments, which will be described later on (p. 147).

Other observers have tried to discover whether any change in the peripheral nerves also took part in causing convulsion; but from further experiments it appears that the irritability of the sensory nerves is not increased.[2]

According to Rosenthal, strychnine does not affect the rate at which impulses are transmitted in peripheral nerves; according to him, however, it lessens the time required for reflex actions. Wundt came to the conclusion that the reflex time was on the contrary increased.

In trying to explain the phenomenon of strychnine tetanus on the hypothesis of interference, one would have been inclined by Rosenthal's experiments to say that strychnine quickened the transmission of impulses along those fibres in the spinal cord which connect the different cells together.

The impulses which normally by travelling further round fell behind the simple motor ones by half a wave-length, and thus inhibited them, would now fall only a small fraction of a wave-length behind, and we should have stimulation instead of inhibition.

Wundt's results, on the other hand, would lead to the same result by supposing that the inhibitory wave was retarded so as to fall a whole wave-length behind the motor one. On the assumption, however, that the fibres which pass transversely across from sensory to motor cells, and those that pass upwards and downwards in the cord connecting the cells of successive strata in it, are equally affected, we do not get a satisfactory explanation of the rhythmical nature of the convulsions. By supposing, however, that these are not equally affected, but that the resistance in one—let us say—that in the transverse fibres is more increased than in the longitudinal fibres, we shall get the impulses at one time thrown completely upon each other, causing intense convulsion, at another half a wave-length behind, causing complete relaxation, which is exactly what we find.

[1] Eckhard, Hermann's *Handb. d. Physiol.* Band ii. Th. 2, p. 43.

[2] Bernstein, quoted by Eckhard, *op. cit.* p. 40. Walton, Ludwig's *Arbeiten*, 1882.

This view is to some extent borne out by the different effect produced by a constant current upon these convulsions, according as it is passed transversely or longitudinally through the spinal cord. Ranke found that when passed transversely, it has no effect, but when passed longitudinally in either direction, it completely arrests the strychnine convulsions, and also the normal reflexes which are produced by tactile stimuli.

Ranke's observations have been repeated by others with varying result, and this variation may, I think, be explained by the effect of temperature.

The effect of warmth and cold upon strychnine tetanus is what we would expect on the hypothesis of interference. With small doses of strychnine warmth abolishes the convulsions, while cold increases them. When large doses are given, on the contrary warmth increases the convulsions, and cold abolishes them.[1]

We may explain this result on the hypothesis of interference in the following manner :—

If a small dose of strychnine retard the transmission of nervous impulses so that the inhibitory wave is allowed to fall rather more than half a wave-length, but not a whole wave-length, behind the stimulant wave, we should have a certain amount of stimulation instead of inhibition. Slight warmth, by quickening the transmission of impulses, should counteract this effect, and should remove the effect of the strychnine. Cold, on the other hand, by causing still further retardation, should increase the effect. With a large dose of strychnine, the transmission of the inhibitory wave being still further retarded, the warmth would be sufficient to make the two waves coincide, while the cold would throw back the inhibitory wave a whole wave-length, and thus again abolish the convulsions.

The effect of temperature on the poisonous action of guanidine is also very extraordinary, and is very hard to explain on the ordinary hypotheses, although the phenomena seem quite natural when we look at them as cases of interference due to alterations in the rapidity with which the stimuli are transmitted along nervous structures.

Another cause of tetanus that is difficult to understand on the ordinary hypothesis of inhibitory centres is the similar effect of absence of oxygen and excess of oxygen. When an animal is confined in a closed chamber without oxygen, it dies of convulsions ; when oxygen is gradually introduced before the convulsions become too marked, it recovers. But when the pressure of oxygen is gradually raised above the normal, the animal again dies of convulsions. This is evidently not the effect of mere increase in atmospheric pressure, but the effect of the oxygen on the animal, inasmuch as twenty-five atmospheres of common air are required

[1] Kunde and Virchow, quoted by Eckhard, *op. cit.* p. 44 ; Foster, *Journal of Anatomy and Physiology*, November 1873, p. 45.

to produce the oxygen convulsions, while three atmospheres of pure oxygen are sufficient. This effect is readily explained on the hypothesis of interference, by supposing that the absence of oxygen retards the transmission of impulses in the nerve-centres; so that we get those which ought ordinarily to inhibit one another, coinciding and causing convulsions. Increased supply of oxygen gradually quickens the transmission of impulses until the waves first reach the normal relation, and then, the normal rate being exceeded, the impulses once more nearly coincide, and convulsions are produced a second time.[1]

The effect of various agents also in arresting or inhibiting muscular action suggests the possibility that such inhibition is due to interference with vibrations in muscle. The vibrations of the parts which occur in the muscle during the passage of a constant current have already been mentioned. When a constant current is passed for a length of time and then stopped, tetanic contraction of the muscle occurs and lasts for some time, but it can be at once arrested by again passing the constant current through the muscle.

The idea that coincidence or interference of contractile waves in muscle have much to do with the presence or absence of contraction of a muscle has been advanced by Kühne in order to explain the phenomenon observed by A. Ewald. When the sartorius of a frog is stimulated at each end by electric currents passing transversely through the ends, the secondary contraction which can be obtained from it is strongest in the middle of the muscle, while the points exactly intermediate between the middle and the end, do not produce any secondary contraction at all. This absence of secondary contraction Kühne thinks is due to interference, and the powerful secondary contraction from the middle to coincidence of waves.[2]

Inhibition may also be produced by direct irritation of involuntary muscular fibre. Thus I have noticed under Ludwig's direction that stimulation of veins as a rule very frequently causes dilatation at the point of irritation, and if the muscular fibre of a frog's heart be injured by pinching at one point, that point is apt to remain dilated when the rest is contracted. Protoplasmic structures appear to be similarly affected, and the passage of an interrupted current through the heart of a snail will arrest its rhythmical pulsations, although the heart in this animal appears to be a continuous protoplasmic structure and destitute of nerves.[3]

[1] For other observations on interference as a cause of inhibition, *vide* Wundt, *Untersuchungen zur Mechanik der Nerven und Nerven centren.* 1876. (Stuttgart: T. Enke); Ranvier, *Leçons d'Anatomie Générale. Année* 1877-78. (Paris: J. B. Baillière et Fils); and Lauder Brunton, "On the Nature of Inhibition and the Action of Drugs upon it." (*Nature*, March, 1883, and reprint.)

[2] *Untersuchungen a.d. Physiolog. Inst.*, Heidelberg, 1879. *Sonderabdruck*, p. 40.

[3] M. Foster, *Pflüger's Archiv.*

Stimulating Action of Drugs on the Reflex powers of the Cord.

The reflex action of the cord is greatly increased by certain drugs, more especially by ammonia and by strychnine. The action of strychnine was first investigated by Magendie and his research is not only the first example of the systematic investigation of the physiological action of a drug leading to its therapeutical employment, but is such a model of this method of research that it is worth giving in detail.

He first introduced a little of the upas poison, of which strychnine was the essential ingredient, under the skin of the thigh of a dog, and found that for the first three minutes no symptoms at all were produced. Then the action of the poison began to manifest itself by general malaise succeeded by marked **symptoms.** The animal took shelter in a corner of the laboratory; and almost immediately afterwards convulsive contraction of all the muscles of the body occurred, the fore-feet quitting the ground for a moment on account of the sudden extension of the spine.

This contraction was only momentary, and almost immediately afterwards ceased; the animal remained calm for several seconds, and was then seized with a second convulsion, more marked and prolonged than the first. These convulsions succeeded each other at short intervals, gradually becoming more severe. The respiration was hurried, the pulse quick, and it was observed that each time the animal was touched, a convulsion immediately followed. Finally, death occurred at an interval increasing with the age and strength of the animal. These symptoms suggested to Magendie the following **explanation** of the action of the poison. It was, he thought, absorbed from the wound into the blood, by which it was carried to the heart, and thence to all the organs of the body. On arriving at the spinal cord, it acted upon it as a violent excitant, producing the same symptoms as mechanical irritation or the application of electricity. Magendie was not content until he had tested his theory by experiment. The first question to be settled was **whether the poison were absorbed or not.**

To test this supposition he applied the poison first to the serous membranes, the peritoneum and pleura, from which, as he had learned by previous experience, absorption takes place with extreme rapidity. The result showed that his supposition was correct. The symptoms appeared almost immediately after the injection of the poison into the pleura, and within twenty seconds after it had been injected into the peritoneum. In order to ascertain whether absorption took place from mucous as well as from serous surfaces, he isolated a loop of small intestine by means of two ligatures, and injected a little of the poison into the part between them. In six minutes, symptoms of poisoning appeared, showing that absorption

had occurred, but they were less intense than when the poison was applied to a serous surface.

Further experiments showed that absorption took place from the large intestine, from the bladder, and from the vagina; but that it was comparatively feeble and slow. When introduced into the stomach along with food upas invariably caused death; but the symptoms did not appear until half an hour after it had been taken. This delay might have been due either to absorption from the stomach having taken place very slowly or not at all, so that the drug had passed on to the small intestine, and thence been absorbed into the blood. To determine this point, he isolated the stomach by ligatures applied to its cardiac and pyloric orifices, and then injected a little of the poison into its cavity.

Under such conditions, symptoms of poisoning were only observed after the lapse of an hour. This showed that while absorption from the stomach did occur, it was much slower than from the small intestine.

The second question was, **Does the poison act through the circulation?** If so, reasoned Magendie, the first symptoms of the action of the poison will come on more slowly when it has far to travel to the spinal cord from the point of introduction, and *vice versâ*. On testing this by experiment, he found that when the poison was injected into the jugular vein, tetanus occurred almost instantaneously, and death took place in less than three minutes, for the upas had only to pass through the pulmonary circulation and heart to the arteries of the cord. When injected into the femoral artery (at D, Fig. 44) the distance to be travelled before reaching the cord would be greatly increased, for the poison must first pass through the artery itself, through the capillaries, and along the vena cava, traversing the whole distance marked D A B



FIG. 44.—Diagram illustrating Magendie's method of investigating the mode of action of upas (strychnine). A, femoral vein; B, peritoneum; C, pleura; D, femoral artery; E, F, G, spinal cord, to which small arteries are seen passing from the aorta. At F is indicated a point of section of the cord.

in Fig. 44 before it reached the point where it entered the circulation when it was injected into the jugular. Under these conditions the action should be slow, and experiment showed this to

be actually the case, for no symptoms appeared until seven minutes after the injection. Although these experiments of Magendie's appear to prove completely that the upas poison acts through the circulation, a number of persons nevertheless considered that the symptoms were produced through the nervous system by means of so-called sympathy. In order to remove their doubts, Magendie narcotised a dog by means of opium, and then divided all the structures of one leg with the exception of the artery and vein. Into this almost isolated limb he then introduced a little of the poison. This was followed by the usual symptoms almost exactly as if the limb had been intact. By pressing upon the vein which passed from the limb to the body when the symptoms of tetanus appeared he was able to arrest their further development, and by releasing the vessel and allowing circulation to have free course, the symptoms reappeared. Lest by any chance the poison might have acted through nerves or lymphatics contained in the walls of the artery and vein, he divided these structures also, connecting their several ends by means of quills through which circulation then took place. When the poison was applied to the severed limb connected with the body only by these quills, the same succession of phenomena occurred as when the limb was uninjured. The possibility of the action being due to sympathy between the nervous system and the point of application of the poison was thus completely excluded, and the operation of the poison through the circulation triumphantly demonstrated.

The next question was **whether the convulsions were caused by the action of the drug on the brain or the cord.** To ascertain its action upon the brain, a little of the solution was injected into the carotid artery. The effects produced were the same as those of any irritating liquid. The intellectual faculties disappeared, the head was laid between the paws, and the animal rolled over and over like a ball. These effects passed off as the circulating blood removed a quantity of the drug from the brain, and were succeeded by the ordinary tetanic convulsions when sufficient time had elapsed for it to reach the spinal cord. The question **whether it really acted upon the cord**, still remained to be put to a crucial test. If its effects were really due to its action upon the spinal cord they ought to cease upon the destruction of that part of the nervous system, and to occur when the drug was applied to it alone. The cord was therefore destroyed by running a piece of whalebone down the vertebral canal at the moment of injection. When this was done, no tetanus occurred. In another experiment, Magendie waited until the tetanic spasms had been induced by the upas, and then destroyed the spinal cord by slowly pushing the whalebone down the vertebral canal. As the whalebone advanced, the tetanus disappeared, first in the fore-legs, when the dorsal part of the cord was destroyed, and then

in the hind-legs, when the whalebone had reached the lumbar vertebræ.

In another experiment, an animal was narcotised by means of opium, and the spinal canal laid freely open. The upas was then directly placed on a part of the spinal cord. Tetanus immediately occurred in that part of the body, and in that part only to which the nerves arising from this portion of the cord were distributed. When the poison was successively applied to other parts of the cord, the convulsions spread to the corresponding regions of the body.

The question **whether a drug exercises a convulsant action through the brain or spinal cord** is now frequently tested, not by destroying the whole cord as Magendie did, but simply by dividing the spinal cord transversely between the occiput and the atlas. Convulsions depending upon stimulation of the motor centres in the brain and medulla oblongata then cease after section, while those dependent upon the spinal cord, do not.

The experiment of dividing the spinal cord transversely about its middle is also sometimes performed in order to test whether the convulsions are of really spinal origin. If they are, they should persist in both the anterior and posterior parts of the body, but if they are of cerebral origin, they occur in the anterior but not in the posterior part.

The effect of strychnine and allied substances upon the cord is usually ascribed to increased excitability of the nerve cells, but it is not improbably due partly to alteration in the comparative rate at which stimuli are transmitted from one cell to another; but this subject has already been more fully discussed under "Inhibition," *q.v.*

Some curious results obtained by Dr. A. J. Spence may be explained on the latter hypothesis which would be inexplicable on the former. After removing the blood from the body of a frog, and exposing the brain, he placed some nux vomica upon it, so that it could gradually diffuse along the spinal cord. As it passed downwards he observed that at first, irritation of the fore-feet caused spasm only in them; later it caused spasm of both front and hind-feet, while irritation of the hind-feet still produced ordinary reflex; and later still irritation of the fore-feet caused no spasm in the hind legs while irritation of the hind-feet would still cause spasm in the fore-legs.[1]

The action of strychnine on the conducting power of the spinal cord has already been discussed. It **diminishes** or abolishes the power of **summation,** but **increases** the **reflex** excitability, so that stimuli will produce reflex action which are too feeble to do so when the spinal cord is in its normal condition. The difference between the reaction to strong and weak stimuli is also to a great extent abolished, and both produce tetanic contractions. This condition, however, is absent for a short time after the application of each

[1] *Edin. Med. Journ.*, July, 1856.

stimulus, and then strong and weak stimuli produce corresponding strong and weak action, much as in the normal cord.[1]

The effect of nicotine as a spinal stimulant is very extraordinary; for Freusberg found that when frogs had been decapitated for twenty-four hours, and reflex action was almost entirely gone, the injection of a small quantity of the poison increased the reflex excitability so much that irritation of the skin caused well-marked movements. This increase lasted from one to three days, and the bodies of frogs poisoned by nicotine retained a fresh appearance for a long time.

Spinal Stimulants.

Spinal stimulants are remedies which increase the functional activity of the spinal cord.

Ammonia.	Thebaine.
Strychnine.	Gelsemine.
Brucine.	Buxine.
Absinthe.	Calabarine.
Nicotine.	

The most marked of these are strychnine, brucine, and thebaine, which in small and moderate doses greatly increase the reflex excitability, and in large doses cause tetanic convulsions. Besides these there are some others, such as opium, morphia, and belladonna, which, although they appear at first to have a sedative action, when given in very large doses produce convulsions.

Uses.—The want of an exact knowledge of the intimate pathology of spinal diseases renders the rational use of spinal stimulants difficult. They are employed in cases of general debility without any evidence of distinct disease, and in paralysis where there is no evidence of inflammation: this paralysis may be local, or affect the whole side of the body, as in hemiplegia, or the lower half, as in paraplegia.

When strychnine is given in cases of paralysis until it begins to exhibit its physiological action in slight muscular twitches, these twitches begin sooner and are more marked in the paralysed than the healthy parts.

[1] Ludwig and Walton, *Ludwig's Arbeiten*, 1882.

CHAPTER VIII.

ACTION OF DRUGS ON THE BRAIN.

We are able to judge to a certain extent of the order and kind of action of drugs upon the different parts of the nerve centres, by watching their effect upon the movements of animals after their injection.

By removal of successive portions of the nervous system in the **frog,** Goltz has shown that the cerebral lobes have the function of voluntary movement, so that when they are removed, the animal lies quiet, unless acted upon by some external stimulus.

The optic lobes, which correspond to the corpora quadrigemina of the higher animals, have the function of directing and co-ordinating movements but not of originating them, so that a frog in which they are uninjured, but from which the cerebral lobes have been removed, will remain perfectly quiet, except on the application of an external stimulus, when it will leap like a normal frog.

As the optic lobes have the power of directing and co-ordinating movements, when they are destroyed the animal will jump, but will be unable to direct its movements.

The cerebellum has also the power of co-ordination, so that when it is removed the animal cannot jump at all, although one leg may answer by a kick or other motion to the application of a stimulus. But even when all those parts have been removed, the frog will still recover its ordinary position after it has been laid upon its back.

The co-ordination requisite for this power of retaining or recovering its ordinary position appears to be situated in the medulla oblongata, for when this is removed the frog will lie upon its back, and will not attempt to recover its ordinary position.

The legs will still respond by movements to irritation applied to the foot, but when the spinal cord is now destroyed these reflex movements also cease.

In frogs poisoned by opium, the movements are gradually abolished in the order just mentioned, and we therefore conclude that opium affects the nerve-centres in the order of their development, the highest being paralysed first, and the lowest last. This order is usually not quite the same in higher animals, inasmuch as the last centre to be paralysed by opium or other anæsthetics is usually the medulla oblongata, and more especially that part of it which keeps up the respiratory movements. As we shall afterwards see, however, the respiratory centre is really a lower or more fundamental centre than either the brain or spinal cord.

In **higher animals,** such as rabbits and guinea-pigs, the cerebral hemispheres are comparatively much more developed than in the frog, and their removal interferes very much with the animal's motions. At first it is utterly prostrate, but after some time its power of movement returns to some extent, though it remains much



FIG. 45.—Diagram of the higher nerve-centres of the frog.

less than in the normal animal. As we should expect, the weakness is most marked in those parts of the body that are most under the control of the cerebrum, and least in those whose movements are regulated by the lower centres. Thus in rabbits the fore-paws are capable of being used for complex motions at the will of the animal, such as washing the face, holding food, and so on, and in them the weakness caused by removal of the cerebrum is much more marked than in the hind limbs, which are simply used for progression. After the operation the animal can still stand, although it is unsteady, and the fore legs tend to sprawl out. When pinched it bounds forward, but unlike the frog it is unable to avoid any obstacle in its path. If it be pinched at all severely, it not only moves, but will cry loudly and plaintively, and this condition is frequently noticed in rabbits under chloroform, although

1. The eyes open widely, the pupils dilate, and head and eyes turn towards opposite side.
2. Extension forward of the opposite arm and hand, as if to reach something in front.
3. Movements of tail (and trunk).
4. Retraction with adduction of opposite arm.
5. Supination and flexion of the fore-arm, by which the arm is raised towards the mouth.
6. Action of zygomatics, by which the angle of mouth is retracted and elevated.
7. Elevation of ala of nose and upper lip.
8. Opening of mouth with protrusion of tongue.
9. Retraction of tongue.



13. Complex movements of thigh, leg, and foot.
12. Advance of the opposite hind limb.
11. Retraction and adduction of opposite arm.
a, *b*, *c*, *d*, Prehensile movements.
10. Retraction of opposite angle of mouth.

FIG. 46.—Brain of monkey, showing the position of the motor and sensory centres as ascertained by Ferrier. The actions all occur on the side of the body opposite to the part of the brain irritated.

they have received no injury whatever. The pupils contract on the stimulus of light, and the eyes wink if the finger is brought near them. Bitter substances cause movements of the tongue and mouth, and ammonia to the nostrils may cause the head to be drawn back, or the animal to rub its nostrils with its toes.[1]

Where the cerebral hemispheres are still more developed, as in cats, dogs, and monkeys, their removal causes so much prostration, and interferes so greatly with motor power as almost entirely to destroy equilibrium and co-ordinate progression.

The motor and sensory centres of the brain have been more exactly localised in monkeys by Ferrier, Fritsch, Hitzig, and others, and the results of their experiments, especially those of Ferrier, agree so well with those of pathological observation in men that we may assume that there is a general agreement between the position of the centres in man and monkey.

The **motor centres** are arranged along the two sides of the fissure of Rolando, the order of their arrangement being exactly what is required for the purpose of (1) seeing food; (2) conveying it to the mouth; (3) masticating it; (4) throwing away the refuse; and (5) advancing to get more [2] (*vide* Fig. 46, brain of monkey).

The **sensory centres** lie in the posterior and lower parts of the brain. The centre for sight is situated in the angular gyrus and is marked 14 and 15 in the diagram; that for hearing is situated in the superior temporo-sphenoidal and is marked 16 in the diagram; those for smell and taste lie at the tip of the temporal sphenoidal lobe, and the centre for general sensation appears to be towards the interior of the brain, in the hippocampal region.

When the motor centres in the monkey are slightly irritated by a faradic current, a single co-ordinated movement is produced, but if the irritation be continued longer, and especially if a strong current be used, epileptiform convulsions may occur, succeeded by choreic movements after the current has ceased. Epileptic convulsions are easily produced by irritation of the cerebral cortex in the cat and dog as well as the monkey. It is difficult to produce them by cortical irritation in the guinea-pig or rabbit, and impossible in birds, frogs, and fish.[3]

Depressant Action of Drugs on the Motor Centres.

The **excitability of the brain** may be altered either by conditions which modify the nerve cells or the circulation. A deficient circulation greatly depresses the excitability, and it is very low when much hæmorrhage has occurred.

[1] Ferrier, *Functions of the Brain*, p. 38.

[2] Lauder Brunton, "On the Position of the Motor Centres in the Brain in regard to the Nutritive and Social Functions," *Brain*, vol. iv. p. 1.

[3] François Franck and Pitres, *Arch. de Physiol.*, July, 1883, p. 39.

One method of investigating the action of drugs on the excitability of the brain consists in trephining so as to expose the cortical substance and then stimulating it by a faradaic current before and after the administration of a drug either by inhalation or injection. Another method has been employed by Albertoni who first trephines on one side, and having estimated the strength of current sufficient to produce an epileptic convulsion when applied to a motor centre, he allows the wound to heal, and then gives for a length of time the drug on which he wishes to experiment. He then exposes the corresponding motor area on the other side and observes whether the strength of current required to produce an epileptic convulsion is greater or less than before.

The excitability of the motor centres is greatly lowered by anæsthetics, so that as anæsthesia becomes deeper, irritation of the motor centres has less and less effect, and when anæsthesia is very profound, such irritation has no action whatever.[1] The motor centres, however, are less affected than the sensory ones by anæsthetics, so that they will still re-act to faradic irritation when the sensation of pain has been completely abolished.

Alcohol also diminishes the excitability of the motor centres, so that the epileptic convulsions which usually follow the application of strong currents to the cortex are less readily produced after its administration, as well as after ether and chloroform.[2]

Bromide of potassium, according to Albertoni, when given for several weeks together, greatly diminishes the excitability of the motor centres so that when dogs are thoroughly under its influence it is almost impossible to produce epileptic convulsions by irritation of the cortical substance. Atropine in small doses increases the excitability of the brain in monkeys, but in large doses paralyses it. It greatly increases the tendency to epileptic convulsions in dogs, so that they can be produced by very much slighter stimuli than usual, and strychnine, absinthe, and cannabine have a similar action in this respect.[3] Physostigma appears to increase the excitability of motor centres in the brain; for when guinea-pigs have been rendered epileptic by section of a sciatic nerve, the administration of physostigma greatly increases the number of fits.

Irritant Action of Drugs on Motor Centres in the Brain.

Certain drugs when administered to animals or taken by man produce **convulsions**. The muscular actions which occur in these convulsive movements may be induced by (*a*) irritation of the motor centres in the spinal cord, (*b*) the motor centres in the

[1] This was observed in the case of ether by Hitzig, *Untersuchungen über das Gehirn*, Berlin, 1874. I have had several opportunities of observing the same thing in regard to chloroform when assisting my friend Dr. Ferrier in experiments on the brain.

[2] Franck and Pitres, *op. cit.*

[3] François Franck and Pitres, *Arch. de Physiol.*, July, 1883, p. 39.

medulla oblongata and pons varolii, or (*c*) cerebral cortex. These centres may be irritated directly by the action of the drug upon them, or they may be stimulated indirectly by the drug causing the blood in them to become venous through its action on the respiratory or circulatory organs. Convulsions of this sort, although caused by the administration of a poison, are really asphyxial, and are similar in character to those produced by suffocation.

Convulsions are usually ascertained to be of **spinal** origin by dividing the cord either at the occiput or lower down in its course and finding that they still persist in those parts of the body which derive their innervation from the spinal cord below the point of section. If they cease in parts of the body innervated by the spinal cord alone but continue in the parts which retain their nervous connection with the brain, they are regarded as of **cerebral** origin.

It has already been mentioned that irritation of the motor areas in the cortex of the brain will produce epileptic convulsions, but it is probable that such cortical irritation acts through lower ganglionic centres and especially through the medulla oblongata and pons varolii. Epileptic convulsions can be still more readily produced by irritation of this part of the brain than by irritation of the cerebral cortex, and may be induced by slight lesion of the pons and medulla by a needle. It is to irritation of this part of the brain by venous blood that asphyxial convulsions are due, for they can still be induced by suffocation or by ligature or compression of all the arteries leading to the brain after all the parts of the brain above the pons have been removed, and they cease when the spinal cord is divided just below the medulla, or the medulla itself divided at its lower end. It is evident that, if the spinal cord be paralysed the convulsions will not occur though the medulla and pons be irritated; and it has been found that, if its blood-supply is stopped at the same time as the circulation in the pons by ligaturing the aorta in place of the cerebral vessels alone, convulsions do not occur. Probably the absence of convulsions in slow asphyxia is due, at least in some degree, to gradual paralysis of the cord by the long-continued circulation of venous blood through it.

The centre for convulsions in the frog appears to be in the medulla oblongata.

Asphyxial convulsions are usually of an opisthotonic character, because, all the muscles being stimulated at once by the action of the venous blood on the motor centres, the stronger overpower the weaker, and the extensor muscles of the back being more powerful than the flexors bend the spine backwards. Asphyxial convulsions only occur in warm-blooded animals and not in frogs, where the respiratory processes are slow, and entire stoppage of the respiration for a length of time does not render the blood sufficiently venous to act as a powerful irritant. If any drug therefore

produces convulsions in the higher animals and not in frogs, the probability is that its convulsive action is indirect and the convulsions it produces are asphyxial. If on the other hand it produces convulsions in frogs as well as higher animals, its convulsive action is in all probability due to the direct effect of the drug upon the nerve centres. In order to ascertain this definitely, however, the usual plan is to see (1) whether the convulsions which occur after the drug has been injected disappear when artificial respiration is commenced, and (2) whether these convulsions are prevented by artificial respiration begun before the injection of the drug and kept up during its action. But even this does not entirely show whether the convulsive action of a drug is direct or indirect, for artificial respiration will not prevent asphyxial convulsions if these should depend upon the action of the drug in stopping the heart and thus arresting the circulation. If it is found that the convulsions occur very shortly after the heart stops, the usual plan is to paralyse the vagus in the heart by atropine, and ascertain whether the convulsive action then occurs. If the drug still produces convulsions when respiration is kept up and the heart is not stopped, it is almost certain that its action is direct upon the nerve centres.

Experiments to ascertain whether convulsions are asphyxial or not may be conveniently made upon fowls, for the venous or arterial condition of the blood is readily ascertained by the colour of the comb. Thus, in fowls killed by cobra poison, the convulsions come on at the moment the comb becomes livid, and when artificial respiration is begun the convulsions disappear as the comb again regains its normal colour. It is evident that the colour of the comb will indicate the condition of the blood supplying the brain, even though a venous condition of it should be due to stoppage of the heart and not to failure of the circulation.

Camphor has a curious exciting action both upon the brain and upon the medulla. It produces first rapid succession of ideas, great desire to move, hallucinations which are generally agreeable, and a wish to dance and laugh. In animals it has a similar action, causing wild excitement and constant motion, succeeded by clonic epileptiform convulsions during which death often occurs. Usually, if they survive the convulsions, they recover; but in man the convulsive stage may be succeeded by paralysis, coma, and death, the parts of the nervous system which are first excited being apparently finally paralysed. The action upon frogs is different from that in warm-blooded animals, for in them it produces such rapid paralysis both of the spinal and motor nerves that convulsions do not occur.

Among other drugs having a powerful convulsant action due to irritation either of the cortical centres or of the medulla and pons are picrotoxine (the active principle of *Anamirta cocculus* or *Cocculus indicus*), cicutoxine (the active principle of *Cicuta virosa*), and the active principle of the nearly-allied *Œnanthe crocata*,

coriamyrtine (from *Coriaria myrtifolia*), digitaliresin and toxiresin, which are products of the decomposition of the active principles of digitalis.

The **method of localising** the parts of the brain upon which certain drugs exert a **convulsant action**, consists in **extirpating** some of the **motor centres** and then giving these drugs, such as picrotoxine, cinchonidine, and quinine,[1] which produce epileptic convulsions.[2] The results of these experiments are that the epileptic convulsions produced by these poisons appear to have a twofold origin, (*a*) in the brain, and (*b*) in the medulla, the centre in the brain being the most sensitive to the action of the poison. In consequence of this, when the poison is given after the destruction of the motor centres on one side in such quantities as not to cause general convulsions, the weakness of the opposite side, due to the lesions, becomes still more evident, probably from the motor excitability of the sound side being increased. When convulsions are produced they are unsymmetrical. Those of the sound side are much stronger, are generally clonic, and apparently arise from irritation of the cerebral centres. Those of the paralysed side are much weaker, are more tonic, and apparently arise from irritation of the medulla.

ACTION OF DRUGS ON THE SENSORY AND PSYCHICAL CENTRES IN THE BRAIN.

The effect of drugs upon the higher mental functions can only be ascertained satisfactorily in man. These functions vary in complexity from simple choice to the highest efforts of genius.

The effect of drugs upon the **time required** for **mental processes** is observed by ascertaining, first, the time required for the performance before and after the administration of a drug, and comparing these two times with one another.

The processes generally investigated are, (*a*) the time required for simple reaction; (*b*) for discrimination; (*c*) for selection. The simple reaction is ascertained by marking on a chronograph the time when a signal is made, such as for example the exhibition of a coloured flag. As soon as this is seen by the individual experimented upon he marks the time upon the same chronograph by placing a finger upon a key which is connected with the registering electromagnet. The difference of time between the exhibition of the flag and the time registered by the electromagnet is equal to the time required for the transmission of the sensory impulse to the brain, for its transmission from the sensory to the motor

[1] I have seen a case in which an epileptic convulsion appeared to be caused by medicinal doses of quinine.

[2] Rovighi e Santini, *Publicazioni del R. Instit. di stud. superiori in Firenze Sizione di scienze fisiche natur*, 1882, s. 1.

tracts of the brain, for its passage down the motor nerves, and the latent period of the muscles.

The time required for selection is ascertained in the same way, but either a red or blue flag may be shown, and he has to discriminate between them, and only to press when the one previously agreed upon is shown. The difference between the time of this experiment and the former, gives the time required for discrimination.

The time required for decision is ascertained in the same way as the previous one, excepting that a different signal is to be made on the appearance of the red and of the blue.

Simple reaction has been found by Kraepelin[1] to be little affected by nitrite of amyl: sometimes it is a little quicker and sometimes a little slower than normal. It is rendered slower by ether and much slower by chloroform, although exceptionally it may be quickened by chloroform, probably when used in small doses.

The time required for discrimination is not definitely affected by nitrite of amyl, being sometimes increased and sometimes diminished. It is generally increased, though it may be diminished, by small doses of ether and also by chloroform.

The time for selection is sometimes increased and sometimes diminished by nitrite of amyl. It is increased by ether and also by chloroform: and if the quantity given be great, the increase may be very large.

The influence of alcohol upon psychical processes is curious; for, while it renders them much slower, the individual under its influence believes them to be much quicker than usual.

Drugs which increase the Functional Activity of the Brain.

Nerve Stimulants.

These are remedies which **increase** the **nervous activity** of the cerebro-spinal system. They are subdivided into those which act on the cerebrum, or cerebral stimulants, and those which affect the spinal cord, or spinal stimulants. Spinal stimulants have been already discussed (p. 151).

Cerebral Stimulants.

In popular language, the name of stimulant is generally applied to drugs which have the power to increase the activity of the brain. From their producing a feeling of comfort and mirth they are also

[1] Kraepelin, *Ueber die Einwirkung einiger medicamentose Stoffe auf die Dauer einfacher psychischer Vorgänge*, 1882. Abstract in *Revista Sperimentale di Freniatria*, anno ix. 1883, p. 124.

called **exhilarants.** The functional activity of the brain, like that of other organs, depends upon the tissue change which goes on in the cells and fibres which compose it, and the amount of tissue change is regulated to a great extent by the quantity and quality of the blood supplied to the organ. A free supply of blood to the brain may be obtained by general excitement of the circulation, *i.e.* more powerful and rapid action of the heart and contraction of the vessels in other parts of the body driving blood into the brain, or by local dilatation of the cerebral arteries allowing blood more ready access to the brain, or by a combination of these factors.

Free circulation through the cerebral arteries may be induced to some extent by **posture:** thus, some men can think best when the head is low, and almost every one naturally assumes the sitting posture with the head bowed down and held between the hands when suffering from the effects of mental depression. This posture is not, as is often supposed, merely consequent on the depressed condition of the nerve centres, it is voluntarily assumed because it affords an actual sense of relief. In eager conversation also the body generally stoops forward and the head is held low so as to allow of a free supply of blood to the brain.[1]



FIG. 47.—Tracing to show the increased rapidity of circulation in the carotid of a horse during mastication. (After Marey.)

Local dilatation of the arteries of the brain appears to be produced in animals by the movements of **mastication** and probably also by savoury food or irritating substances in the mouth. It is probably on this account that so many substances are **chewed** for their stimulant action, such as tobacco, betel nut, cola nut, and raisins. The effect of smoking is probably to a great extent due also to its action on the cerebral circulation through the stimulating effect of the smoke on the nerves of the mouth and nares, and so is the use of alcohol in sips by men such as journalists, who are engaged in writing. It is probable that tea and coffee also cause local dilatation of the arteries supplying the brain. Suction also causes an increased supply of blood to the brain.[2]

[1] This effect of posture on the human brain is admirably shown by a tracing taken from a patient with an aperture in the skull by François Franck and Brissaud. François Franck et Brissaud, Marey's *Travaux*, 1877, tom. iii. p. 147.

[2] François Franck, Marey's *Travaux*, 1876, p. 354.

The effect of local dilatation of the cerebral vessels is very greatly increased, if in addition to it the general circulation is increased and the blood-pressure raised by contraction of the arterioles in the body generally, or by more vigorous action of the heart.

General excitement of the circulation is induced by **exercise** short of fatigue, and a brisk walk will sometimes remove a condition of low spirits. Sometimes the supply of blood to the brain is but slightly increased during continuous exercise, as a large portion of the blood is then diverted to the muscles, but after the exertion is over, the excitement of the circulation continues for some time, and then the supply to the brain is increased. In some persons a cold wind acts as an exhilarant, causing contraction of the vessels with consequent increase in the general blood-pressure and increased circulation in the brain. In persons who are debilitated and feeble, on the contrary, the cold may have an opposite effect by depressing the action of the heart.

Some men can think best when walking about, on account of the excitement in the circulation which the exertion produces, but many such people, when they come to a very difficult point, will stand still or sit down, so as to allow the blood to flow more to the head and less to the muscles.

Where the circulation is feeble, so that the heart is not much stimulated by walking about, men often find that they can think better when lying down, or sitting with their head in their hands, so as to gain the advantage of the greater flow of blood to the head in these positions.

Stimulation of the mucous membrane of the nose by smelling the vapour of strong ammonia, carbonate of ammonia, or acetic acid, raises the blood-pressure generally throughout the body by reflexly stimulating the vaso-motor centre, and thus increases the circulation of blood in the brain. Smelling salts or aromatic vinegar are therefore frequently employed, not only to enable people to attend more readily to any subject in which they are engaged, and to prevent them from falling asleep, but also to arouse them from syncope.

The action of **sipping** is a powerful stimulant to the circulation, for, as Kronecker has shown, the inhibitory action of the vagus on the heart is abolished while the sipping continues, and the pulse rate is very greatly increased. A glass of cold water slowly sipped will produce greater acceleration of the pulse for a time than a glass of wine or spirits taken at a draught. Sipping cold water has been recommended to allay the craving for alcohol in drunkards endeavouring to reform, and probably its use is owing to this stimulant action on the heart. It is sometimes said that a single glass of ale sucked through a straw will intoxicate a man, although three times the quantity would not do so if taken in large draughts. If this be true, the more rapid intoxication caused by sucking is

probably due to the conjoined effects of the alcohol and of temporary paralysis of the vagus caused by the suction.

One of the most typical stimulants is **alcohol.** In small quantities it increases the arterial tension by locally stimulating, first the sensory nerves of the mouth, and afterwards those of the stomach, and thus causing reflex contraction of the vessels, and reflex acceleration of the beats of the heart. This effect occurs before its absorption, and is best marked when the alcohol is strong, and is but slightly marked when it is diluted. It is possible that by inducing local dilatation of the cerebral arteries while the heart still continues active, it may have a stimulant action on the cerebral functions, besides that which it induces by merely exciting the circulation generally.

Any stimulant action on the brain beyond what may be explained in this way is very slight, if indeed it exist at all. Its further actions are those of paralysis exerted on the nerve centres in the order of their development, the higher centres being paralysed first.

At or about this point its stimulating action ceases and its narcotic action commences. Its **exhilarating** effect, however, may be most marked just at this point, because it is just here, while the circulation of the brain remains increased, the restraining or inhibitory parts of it begin to be paralysed. Thus, imagination and emotion are more readily excited and expression is free and unrestrained; external circumstances are less attended to, and a boyish or childish hilarity occurs.

It is probable that some substances, such as strychnine, increase the mental powers by a direct action on the brain tissue itself, and possibly caffeine may do so also.

Drugs which lessen the Functional Activity of the Brain.

These drugs are soporifics or hypnotics ; narcotics; anodynes or analgesics; and anæsthetics.

Most of the substances belonging to those classes have a certain resemblance to one another in their action. Most of them stimulate the mental functions when given in very small doses. In larger doses they have also a stimulating action at first, *i.e.* while only a small quantity has been absorbed, but later on they diminish or abolish the mental faculties. The same drug, as, for example, opium or alcohol, in different doses may thus act as a stimulant, narcotic, soporific, and anæsthetic.

In a certain stage of their action opium and alcohol do not merely lessen the functional activity of the brain, but they **disturb** the normal **relations** of one part to another, so as to produce disorder of the mental functions. Bromide of potassium, on the other hand, appears simply to lessen the functional activity of the brain without disturbing the relation of one part to another. We do not

know what the causes of this difference in their action is, but with some degree of probability we may consider that such substances as bromide of potassium, or the normal products of tissue-waste, such as lactic acid, simply diminish the functional activity of the nerve-cells without disturbing the nervous paths by which they communicate with one another, so that we have merely a general and even diminution of the mental faculties, as in natural sleep. Such substances as alcohol, on the other hand, may be supposed not only to diminish the functional activity of the cells but to disturb the rate at which the impulses pass from one cell to another, or to alter the direction in which these impulses are sent, so that instead of the mental activity being lessened in degree but natural in kind as after the administration of bromide of potassium, we have a disturbance of the functions resembling that which we find in delirium or madness.

Hypnotics or Soporifics.

These are remedies which **induce sleep.** Although many of them are also narcotic, yet we may distinguish between hypnotics and narcotics. Pure hypnotics are substances which in the doses necessary to produce sleep do not disturb the normal relationship of the mental faculties to the external world.

In sleep the cerebro-spinal system, with the exception of the medulla oblongata, is to a great extent functionally inactive, and even the respiratory centre and the vaso-motor centre in the medulla, undergo a diminution in their functional activity, so that the respiration becomes slower, the vessels of the surface dilate, and the arterial tension falls.

Certain parts of the nervous system may still remain functionally active, so that, for example, when the nose is tickled with a hair, reflex movements of the face or hand may occur without awaking the sleeper; and certain parts of the brain may also be active so that dreams occur, which may be afterwards remembered as distinctly as real occurrences, or may produce at the time various movements of the body.

But while individual parts may be active, the **whole cerebro-spinal system** is **not active together,** and thus any co-ordination which may occur between either sensations or motions is incomplete; the dreams are incoherent, and the motions do not affect the whole body, as is seen in sleeping dogs, where the legs make a movement of running, but the animal continues to lie on its side. The functional inactivity of the whole or of the greater part of the cerebro-spinal system is associated with a condition of **anæmia,** and probably depends to a certain extent upon it. At the same time it is probable that sleep depends also on functional inactivity of the cerebral cells due to accumulation of the products of tissue waste in or around them.

The arteries of the brain during sleep are contracted, the brain is anæmic, and its bulk is small. On awaking, the arteries become dilated, the circulation becomes rapid, and the brain increases in bulk. Where parts of the brain are active, as in dreaming, increased circulation occurs, but probably this is local and not general.

In considering the **circulation** of the brain, however, a marked distinction must be drawn between the condition of the arteries and veins. So long as the blood is in the arteries it is available for the nutrition of the nervous structures, but once it is in the veins, it is no longer available, and its accumulation there will tend to impair nutrition, both by the pressure it exerts on the nervous structures, and by its interference with the supply of arterial blood.

In **normal sleep** the arteries and veins are both contracted, and the brain appears anæmic. In the very act of waking the brain may slightly contract, and this has been thought by Mosso, to whom we owe the observation, to show that sleep does not depend upon anæmia of the brain ; but this contraction may be due to the removal of venous blood, preparatory to further arterial supply.

Observations on the brain by trephining appear to show that during ordinary sleep, whether it has come on naturally, or has been induced by narcotics, such as a small dose of opium, the brain is anæmic. During functional activity, either of the whole or of its parts, there is arterial dilatation, with a free supply of blood. During **coma** the veins become dilated and the brain congested.[1] This congestion, however, is utterly different from the arterial congestion of functional activity, for in coma the blood, though abundant in quantity, is stagnating in the veins, and useless for the tissues.

In order to produce sleep, then, two things are necessary :—

1st. To lessen the circulation in the brain as much as possible by diverting blood from it or quieting cardiac action.

2nd. To lessen the functional activity of the organ.

Blood may be **diverted** from the brain by dilating the vessels elsewhere. In weak conditions of the body, with feeble vascular tone, this may occur simply from **position,** and such persons become drowsy when standing or walking about, or when sitting. As soon as they lie down, however, the cerebral vessels also having little or no tone, the blood floods the brain, and they are unable to sleep. In such persons, sleep may be sometimes obtained by raising the head with high pillows. In such cases, also, vascular tonics, such as **digitalis**, by increasing the contractile power of the arteries leading to the brain, may enable them to resist the increased pressure in the recumbent position and thus prevent the brain being flooded with blood and allow sleep to be obtained.

[1] Hammond, *On Wakefulness*, 1866, p. 20.

The largest vascular area into which the blood may be drawn away from the brain is that of the intestinal canal. When the vessels in the intestine are contracted, it is almost impossible to obtain sleep. Consequently both man and animals, when exposed to cold which, acting through the thin abdominal walls, would cause contraction of the intestinal vessels and drive the blood to the brain, instinctively keep the intestines warm by curling themselves up before going to sleep, and thus covering the abdomen with the thick muscles of the thighs.

Warmth to the abdomen also by means of a large poultice outside, will tend to produce sleep; or, in place of a poultice, a wet compress, consisting of linen or flannel wrung out of cold water, and covered with oil-silk, and with two thicknesses of dry flannel placed above it, tends greatly to induce sleep and is most useful for this purpose, especially in children.

Warmth to the interior of the stomach has a somewhat similar action, but it differs from warmth to the exterior in this, that it may, to a certain extent, stimulate the heart as well as dilate the abdominal vessels. Stimulation of the heart is of course objectionable, as it tends to maintain the activity of the brain.

On this account the food or drink should be tolerably warm, but not very hot. Warm milk, either alone, or with bread soaked in it, warm gruel, thin corn-flour, or ground rice, sago, or tapioca, warm beef-tea or soup, or a glass of hot wine and water or spirits and water at bed time, may all act as soporifics by withdrawing the blood from the brain to the stomach. In the sleeplessness of fever a **wet pack,** by restraining the movements and by diverting blood from the brain to the body generally, is often an efficient soporific.

Cold feet also tend to keep up the tension in the vessels and prevent sleep, and therefore they ought to be warmed either by the use of an india-rubber bag filled with hot water, and covered with flannel, or by rubbing them briskly in cold water and drying them thoroughly before going to bed, or by both means combined.

Cardiac excitement may be lessened by sedatives, one of the most useful of which is cold. After hours of weary tossing sleep may sometimes be induced by walking about in a night-dress until cool, or by sponging the surface either with cold or hot water.

The **chief hypnotics** or soporifics are—

Opium.	Bromide of potassium.
Morphine.	Bromide of sodium.
Chloral-hydrate.	Bromide of calcium.
Butyl-chloral-hydrate (croton-chloral).	Bromide of zinc.
Hyoscyamus,	Monobromo-camphor.
Cannabis.	Hop.
Paraldehyde.	Lettuce.
	Lactic acid.

The most powerful **hypnotics** that we possess are undoubtedly opium and morphia, and they seem to act by depressing the functional activity of the brain itself, although along with this depression an anæmic condition of the organ sets in. Besides their action in producing sleep, even in health opium and morphine have the power of lessening pain and thus removing the effect which painful stimuli have in maintaining a wakeful condition. Bromide of potassium and bromide of ammonium in large doses have also a hypnotic action, and even in smaller doses, when they would not of themselves produce sleep, they appear to lessen cerebral excitement and allow sleep to come on when other conditions are favourable. Chloral probably causes sleep both by acting on the brain itself and by causing dilatation of the vessels generally. It is therefore a useful hypnotic in persons suffering from Bright's disease, in which there is high tension of the vessels and consequently a tendency to sleeplessness.

A **combination** of hypnotics sometimes answers much better than any one singly. Thus morphine or opium alone sometimes simply cause excitement, but when chloral is given, either along with, or after them, the excitement is quieted and sleep occurs.

A combination also of small quantities, such as five or ten minims, of solution of opium or morphine with five grains of chloral and ten to thirty of bromide of potassium, is sometimes more useful than any one of the three used alone.

Indian hemp also is sometimes used to procure sleep, and lettuce and lactucarium are also said to have a hypnotic action. Lettuce certainly does seem to have such an action, but how much of it depends upon the juice and how much upon the mechanical effect of the indigestible fibres of the lettuce upon the stomach in drawing blood to it, it would be hard to say. Hops are said to be hypnotic, and their combination with lettuce in the form of a supper consisting chiefly of beer and salad has sometimes a very marked soporific action.

Narcotics.

Narcotics are substances which lessen our relationships with the external world. They are closely related, as I have already stated, to stimulants: and alcohol in the various stages of its action affords us a good example of both stimulant and narcotic action. Alcohol at first excites the cerebral circulation and then begins to paralyse various parts of the brain in the inverse order of their development.

But this order differs in different individuals, for in watching the growth of children we find that the order of development of the nerve centres in them is not always the same: some talking

before they can walk, and others walking before they can talk. In all, however, the powers of judgment and self-restraint are among the last to be completely developed.

While the circulation of the brain is still active, the restraining or depressing effect of present external circumstances, and the restraining effect of training, during previous life, which is stored up as it were in the inhibitory centres, are lessened. The fancy is thus allowed free play and a condition of joyousness and volubility like that of a child occurs. The imagination and memory fail next in some, while the emotions become prominent, and to this follows paralysis or paresis of the power of co-ordination. In others the power of co-ordination is impaired before the mental faculties are much affected, the speech becomes thick and the walking becomes staggering and uncertain. At this stage reflex action still persists, but afterwards it diminishes, and finally paralysis of the respiratory centre occurs. The effect of other drugs, such as ether and chloroform, is much the same as that of alcohol.

In the case of opium and Indian hemp, however, there is but little excitement of the circulation, and their effects appear to be due more to alterations in the relative functions of the different parts of the brain.

Belladonna, hyoscyamus, stramonium, and their allies, have a curious effect. They produce delirium of an active character, the patient having a constant desire to speak, move about, or be doing something, while at the same time he feels great languor. It is probable that this effect is due to the combined stimulant action of these drugs on the nerve centres in the brain and spinal cord and their paralysing action on the peripheral ends of motor nerves.

Anodynes or Analgesics.

Anodynes are remedies which **relieve pain** by lessening the excitability of nerves or of nerve centres. They are divided into local or general:—

Local Anodynes.	General Anodynes.
Cold—	Anæsthetics in small doses.
Cold water.	Atropine.
Ice bags.	Belladonna.
Warmth—	Butyl chloral.
Poultices.	Chloral.
Fomentations.	Conium.
Aconite.	Conine.
Acupuncture.	Gelsemium.
Atropine.	Hyoscyamus.
Belladonna.	Hyoscyamine.

Local Anodynes.	General Anodynes.
Blood letting—	Lupulus.
Leeches.	Lupuline.
Cupping.	Morphine.
Carbolic acid.	Opium.
Carbonic acid.	Stramonium.
Creasote.	
Conium.	
Gelsemium.	
Hydrocyanic acid.	
Morphine.	
Opium.	

Action.—The sensation of pain is due to a change in some part of the cerebrum, and is usually excited by injury to some part of the body.

According to Ferrier the hippocampal region is the seat of sensation. Pain may be of **central** origin, for if these convolutions should from any cause undergo changes similar to what usually take place in them on the application of a painful stimulus to a nerve, pain will be felt, even although no injury whatever has been done to the body. Something of this sort appears to occur in certain cases of hysteria.

Conversely, if the changes which ordinarily occur in these convolutions on severe irritation of a sensory nerve are prevented from taking place, pain will not be felt, however great the stimulus to the nerve may be.

The sensory nerves of the head pass directly to the brain, but all other sensory nerves have to pass for a greater or less distance along the spinal cord before they reach the brain.

The transmission of painful impressions along the spinal cord occurs in the grey matter, and the effect of anæsthetics in preventing the transmission of painful impressions while tactile stimuli are still conducted has been already discussed.

Pain may be occasioned by irritation applied to nerves anywhere between the brain and the periphery; and whatever its point of application may be, it is usually referred to the **peripheral** distribution of the nerve. Sometimes irritation of a nerve, instead of being referred by the brain to the proper spot, is referred to a branch of the same nerve going to a different point.

Pain may be **caused** by violent stimulation of the peripheral distribution of a nerve, of its trunk, of the spinal cord through which the fibres pass to the brain, or of the encephalic centres themselves.

Pain may be **relieved** by (*a*) removing the source of irritation, (*b*) by preventing the irritation from affecting the cerebrum. Thus, if necrosis of the jaw should give rise to intense pain, the pain will at once cease on dividing the sensory nerve by which

the impulses are transmitted to the brain. It may be relieved, also, while the source of irritation still remains, by lessening the excitability of the peripheral terminations of the sensory nerves which receive the painful impression; or of the nerve trunks; or of the spinal cord along which the impression travels; or of the cerebral centres in which it is perceived.

Opium probably acts on them all, diminishing the excitability of the cerebral centre, of the spinal cord, and of the sensory nerves; and bromide of potassium is also supposed to affect all these structures though to a much less degree than opium.

Chloral, butyl-chloral, lupulin, gelsemium, and cannabis indica probably act on the **cerebral centres.**

Belladonna and atropine lessen the excitability of the sensory nerves, and probably this is effected also by hyoscyamus, stramonium, aconite, aconitia, and veratrine.

Uses.—It is evident that if the nerve centre by which pain is perceived is deadened, the pain will cease wherever its seat may be; and therefore opium and morphia are used to relieve pain whatever may be its cause. Cannabis indica and bromide of potassium, having likewise a central action, may also be employed, but they are very much less efficient than opium. Chloral and butyl-chloral have an anæsthetic action when given in very large doses, but in moderate doses their power to relieve pain is not so marked as their hypnotic action. Butyl-chloral, however, seems to have a special sedative action on the fifth nerve, and so has gelsemium; consequently both of them are used in the treatment of facial neuralgia.

As belladonna, aconite, and veratrine have a **local** action on the peripheral ends of the sensory nerves, they are usually applied directly to the painful part in the form of ointment, liniment, or plaster. Local injections of morphine, atropine, and ether, in the neighbourhood of the painful part, are often of the greatest service.

Adjuncts to Anodynes.—As pain depends on the condition of the cerebral centre by which it is perceived as well as on irritation of sensory nerves, it is obvious that it may vary with the condition of these centres, although the irritation remains. Thus a decayed tooth does not always cause toothache, and when the toothache comes on, it may frequently be removed by means of a brisk **purgative,** even although the tooth be not extracted. It is possible that the purgative may act partly by lessening congestion around the tooth, but partly also by altering the condition of the cerebral centres. When the **attention** is fixed upon other things, also, the pain may be to a great extent, or even completely, abolished, as in mesmerism or hypnotism. The sensory stimuli, also, which would usually produce pain, may be diverted voluntarily or involuntarily into motor channels. Thus, during the heat of action, the pain of a wound is not felt; and the pain felt during the

extraction of a tooth is lessened by the employment of violent muscular effort, as in grasping the arms of the dentist's chair. Other most powerful adjuncts are **electricity** applied along the course of the nerves, and **counter-irritation,** especially by means of the actual cautery to the painful part, and, when other means fail, stretching the nerve may succeed.

Cold also, applied to the surface over a painful part, will relieve pain, and so may dry **heat,** applied by a sand-bag or hot cloth, or moist heat in the form of a poultice: for the mode of action of these *vide* "ACTION OF IRRITANTS."

Pain has been ascribed by Mortimer Granville to **vibrations** of **nerves** or of the sheaths; and, in order to lessen it, he proposes to produce vibrations of a different nature: this he does by percussing over the painful nerve with a small hammer, worked either with clockwork or electricity. For a dull heavy pain he uses quick and short vibrations of the hammer, and for a sharp lancinating pain he uses large and slow vibrations.

Anæsthetics.

Anæsthetics are remedies which **destroy sensation.**

It has already been mentioned that both sensation and pain require for their perception a certain condition of the cerebral centres and of the sensory nerves and spinal cord by which impressions are conveyed to these centres.

The difference between anæsthetics and anodynes is to a great extent one of degree. Anodynes affect more particularly the cerebral centres by which pain is perceived, or the conducting paths by which painful impressions are transmitted, and thus in moderate doses lessen pain without destroying reflex action. They only affect the ordinary centres for reflex action when the dose is considerably increased. Anæsthetics, on the other hand, affect the cerebral and spinal centres more equally, and so abolish pain, ordinary sensation, and reflex excitability more nearly at the same time, though their abolition is by no means completely simultaneous.

According to Eulenberg, in chloroform narcosis the patellar reflex is abolished first, then reflex from the skin, then from the conjunctivæ, and lastly from the nose. As the anæsthesia passes off they return in the inverse order, patellar reflex being the last to reappear. A stage of excitement generally precedes the disappearance of patellar reflex, both in man and animals.

Narcosis by ether differs from that of chloroform in the much greater increase of patellar and other tendon reflexes, both in extent and duration.

Chloral hydrate and potassium bromide have an action like chloroform, but much weaker. Like chloroform, they paralyse

patellar reflex before corneal reflex, but butyl-chloral (croton-chloral) paralyses the corneal reflex before the patellar.

In ordinary sleep reflexes disappear in the same order as in chloroform narcosis, but in mesmeric sleep the reflexes are increased as in narcosis from ether. In hysterical conditions diminution of the cerebral reflexes from nose and cornea with persistence of patellar reflexes has been observed.

The reflex power of the vaso-motor centre is very quickly paralysed by chloroform, so that irritation of a sensory nerve will no longer raise the blood-pressure. Its reflex power is much less affected by ether.[1]

Anæsthetics may be divided into local and general. The **local** are those which abolish the sensibility of the peripheral nerves of a particular area. The **general** are those which act on the central nervous system in the way already described, and abolish sensation throughout the whole body.

The chief **local anæsthetics** are cold and carbolic acid. Iodoform is also employed as a local anæsthetic.

For the purpose of producing local anæthesia, cold is generally applied by means of ether spray, until the part is all but frozen and is insensible, when slight operations may be made without the patient feeling any pain. The ether may perhaps have itself a certain amount of physiological effect in diminishing sensibility when applied in this manner. Carbolic acid painted over the surface also causes it to become white and to lose its sensibility, and may thus be used to lessen the pain of opening an abscess.

General anæsthetics are—

Nitrous oxide.	Trichlorhydrin.
Ether.	Bi-chloride of methylene.
Chloroform.	Paraldehyde.
Bromoform.	Bi-chloride of ethidene.
Tetrachloride of carbon.	Bromide of ethyl.

With the exception of nitrous oxide they all belong to the class of alcohols and ethers, and the substitution-compounds having an anæsthetic action are probably almost indefinite in number. Even alcohol itself produces general anæsthesia when volatilised and inhaled.

General anæsthetics may destroy the sensibility of the nerve centres indirectly or directly. Anæsthesia is induced indirectly by stopping the circulation in the brain, and thus arresting the process of oxidation and tissue change in the nerve cells which are necessary for their functional activity.

This result may be produced by draining the blood from the head into other parts of the body. Thus in some of the hospitals

[1] H. P. Bowditch and C. S. Minot, *Boston Med. and Surg. Journ.*, May 21, 1874.

at Paris, before anæsthetics were introduced, a plan was sometimes employed of rendering a patient insensible before an operation, by laying him flat on the ground, and then lifting him very suddenly to a standing posture by the united efforts of six or eight men.

Local arrest of the circulation to the brain by ligature or by compression of the arteries has a similar effect. Waller has recommended diminution of the cerebral circulation, by the combined effects of simultaneous pressure on the carotid arteries and vagi nerves, as an easy means of producing anæsthesia for short operations.

Slight anæsthesia, usually accompanied by some giddiness, may be produced by taking a number of deep breaths in rapid succession. This may be used in order to lessen the irritability of the pharynx in laryngoscopic examinations, and to lessen the pain of opening boils or abscesses. The anæsthesia thus produced may perhaps depend on anæmia of the brain, although this is not certain.

Anæsthesia may also be produced by **diminishing** the **internal respiration** of the nerve cells through a gradually increasing venous condition of the blood. Thus gradual suffocation by charcoal fumes or carbon monoxide causes complete insensibility, and the inhalation of nitrogen and of nitrous oxide has a similar action.

Anæsthesia may be caused by the direct action of **drugs** on the **nerve cells** themselves. Chloroform, ether, and other allied substances belonging to the alcohol series appear to act in this way. Although their action is generally exerted through the blood by which they are conveyed to the brain when inhaled, yet they will also produce a similar action if locally applied to the nerve centres. Thus Prevost[1] found that chloroform applied directly to the brain of a frog narcotises it when the aorta is tied. When the aorta is again unligatured, so that the current of blood can again wash the chloroform away, the narcosis disappears. Chloroform and ether when inhaled appear to act like alcohol, producing paralysis of the nerve centres, commencing with the highest and proceeding downwards. The rate of paralysis, though the same in order, is more rapid than that caused by alcohol.

These anæsthetics are, however, not nerve poisons only, they are **protoplasmic poisons** affecting simple organisms, such as amœbæ and leucocytes, and destroying also the irritability of muscular fibre. Their action upon muscular fibre is much more marked in lower than in higher animals, although it exists in both. In leeches they appear to destroy muscular irritability, and to coagulate the muscles, rendering them rigid before they affect the nervous system. This has been shown by some experiments of Krukenberg, in which he applied two ligatures to a leech, so as to divide it into three parts. The middle part, being immersed in a mixture of water with ether or chloroform, became perfectly rigid,

[1] Prevost, *Practitioner*, July, 1881.

and its muscular fibres no longer contracted when stimulated electrically. The conducting power of the nerves in this part appeared however, unimpaired, so that the two ends of the leech acted co-ordinately. When the middle part of a leech similarly ligatured, was rendered rigid by hot water, both muscles and nerves were destroyed, and the two ends of the leech then acted independently of each other, and not in accordance with one another, as they did when chloroform was used.

This action of chloroform and ether upon muscular fibre is one of considerable importance in reference to the occasional stoppage of the heart and consequent death during the administration of anæsthetics.

The **action** of **anæsthetics** may be divided into **four stages :—**

1st. The stimulant stage.
2nd. The narcotic and anodyne stage.
3rd. Anæsthetic stage.
4th. Paralytic stage.

Stimulant stage.—Chloroform and ether, as already mentioned, resemble alcohol in their actions, and like it in small doses will produce a condition of stimulation and acceleration of the circulation passing gradually into one of narcosis, in which the action of the higher nervous centre is more or less abolished, while that of the lower centres still remains.

In small quantities chloroform and ether are sometimes taken, either internally or by inhalation, for their stimulant effect. They are useful in lessening pain and spasm, as in neuralgia, and biliary, renal, or intestinal colic, when given till the stimulant is just passing into the narcotic stage.

Narcotic stage.—When pushed still further, sensibility becomes more impaired, reflex action still continues, and sometimes, just as in drunkenness, there is a form of wild delirium and great excitement. This is much less marked in feeble or debilitated persons than in strong men. In the latter, the struggles which occur in this condition are sometimes exceedingly violent, the patient raising himself forcibly from the couch, and his muscles being in a state of violent contraction, the face livid, the veins turgid, and eyeballs protruding. Usually this condition quickly subsides and passes into the third stage—that of complete anæsthesia.

In order to lessen the pains of labour, anæsthesia is usually carried to the commencement of the second stage.

Anæsthetic stage.—The third stage differs from the second, in the functions of the spinal cord being abolished, as well as those of the brain; ordinary reflex is consequently abolished, and the most common way of ascertaining whether this stage has set in or not is by drawing up the eyelid and touching the conjunctiva. If no reflex contraction of the eyelid occurs, the anæsthesia is

complete. By careful and judicious administration of the anæsthetic, this condition may be kept up for a length of time, even for hours, or days; but if the inhalation be carried too far, the anæsthetic passes into the fourth stage.

The third stage is the one employed for surgical operations.

Paralytic stage.—In the fourth the respiratory centre becomes paralysed, respiration ceases, and the beats of the heart become feebler and may cease altogether.

Uses of Anæsthetics.

Anæsthetics are used not only to lessen pain but to relax muscular action. They are chiefly employed to lessen pain in surgical operations, in labour, and in biliary and renal colic. They are used to lessen muscular action and spasm in tetanus, in poisoning by strychnine, in hydrophobia, and in the reduction of dislocations, fractures, and hernia. They are also of assistance in diagnosis, by allowing careful examination to be made of parts which are too tender or painful to be examined without it, and by causing the phantom tumours due to spasmodic contraction of the muscles to disappear.

Dangers of Anæsthetics.—(1) One danger is that just mentioned of **paralysis** of the **respiration** from an overdose. This however is one of the least of the dangers, and if the enfeeblement of the respiration be observed in time, it is generally possible to save the patient by stopping inhalation, and keeping up artificial respiration for a little while if necessary.

(2) Another danger is from **paralysis** of the **heart** by a too concentrated chloroform vapour. This is indicated by a sudden stoppage of the heart, paleness of the face, and dilatation of the pupil while the respiration may continue.

If this accident should occur, the body of the patient should be inclined so that the head should be lower than the feet, and artificial respiration should be kept up briskly, the expiratory movements being made by pressure on the thorax and especially over the cardiac region, so that the mechanical pressure should stimulate the heart if possible to renewed action. The vapour of nitrite of amyl may also be administered by holding a piece of blotting paper or cloth on which a few drops have been sprinkled before the nose, while artificial respiration is kept up. The inspiratory movements may be made by drawing the arms backwards over the head, as in Sylvester's plan.

(3) A third danger arises from stoppage of the heart by a combination of chloroform narcosis and **shock.** This is one of the most dangerous conditions. It may occur even during full chloroform narcosis in animals from operations on the stomach; but it is much more common in men from **imperfect anæsthesia.** In very many cases of so-called death from chloroform during

operations, we find it noted as a matter of surprise that death should have occurred as the quantity of chloroform given was so small. The reason that death occurred probably was because the quantity of chloroform given was so small. Had the patient been completely anæsthetized, the risk would have been very much less. The reason why imperfect anæsthesia is so dangerous is, that chloroform **does not paralyse all** the reflexes **at the same** time. A very large proportion of the deaths from chloroform occur during the extraction of teeth, and we may take this operation as a typical one in regard to the mode of action, both of the sensory irritation and of the chloroform. When a tooth is extracted in a waking person, the irritation of the sensory nerve produced by the operation has two effects:—1st, it may, acting reflexly through the vagus, cause stoppage of the heart and a consequent tendency to syncope. 2nd, it causes reflex contraction of the arterioles, which tends to raise the blood-pressure and counteract any tendency to syncope which the action of the vagus might have produced.

In complete anæsthesia all these reflexes are paralysed, and thus irritation of the sensory nerves by the extraction of the teeth has **no effect** either upon the vagus or upon the arterioles. In imperfect anæsthesia however, the reflex centre for the arterioles may be paralysed (*vide* p. 174), while the vagus centre is still unaffected. The irritation caused by the extraction of the tooth may then cause stoppage of the heart, and there being nothing to counteract the tendency to faint, syncope occurs and may prove fatal.

With nitrous oxide there is very much less danger, inasmuch as the nitrous oxide causes a venous condition of the blood, with consequent contraction of the arterioles and rise in the blood-pressure, so that any tendency to syncope through vagus irritation is efficiently counteracted.

With ether, also, the danger is very much less, probably because it has a more equal effect on the centres (*vide* p. 174).

(4) Another danger is that of **suffocation** from blood passing into the trachea in operations about the mouth or nose, or from the contents of the stomach being drawn into the larynx when vomiting has occurred during partial anæsthesia. In consequence of this, it is better, instead of giving chloroform or ether during the whole of an operation on the mouth or nose, to give it only at the commencement, and to administer along with it, or before it, a hypodermic injection of one-sixth to one-third of a grain of **morphine.** The chloroform anæsthesia thus passes into the morphine narcosis, and the operation can be finished without pain, and without danger.

To **prevent** the occurrence of **vomiting,** it is advisable not to give solid food for some hours before an operation, though if necessary a little beef-tea or stimulant may be given half an hour or so before the administration of the anæsthetic.

Mode of administering Anæsthetics.—In order to obtain the **first stages** of the action of anæsthetics, as in cases of intestinal, biliary, or renal colic, intense neuralgia, or parturition, the best means of administration consists of a tumbler, at the bottom of which is placed a piece of blotting-paper or linen thoroughly wetted with chloroform or ether. The patient holds the tumbler to the nose with his, or her, own hand. On account of the form of the tumbler, sufficient air always gets in at the sides, and the patient cannot inhale the vapour in too concentrated a condition. As soon as the anæsthetic begins to take effect, the hand drops, and the inhalation ceases. As the effect again passes off, the patient resumes the inhalation. In employing anæsthetics in this way, however, great care must be taken that the **bottle** containing the chloroform is never entrusted to the patient, but is always kept on a table at some little distance from the bed, and that the blotting-paper or lint in the tumbler is supplied with fresh chloroform by an attendant. If the bottle itself be entrusted to the patient, as the anæsthetic takes effect and produces stupidity, the stopper may fall out, the whole contents of the bottle may be sucked up by the pillow, bolster, bed, or bedclothes, and the vapour being inhaled, fatal suffocation may ensue.

Another method of administering chloroform, which is very convenient when complete anæsthesia is required for a length of time, and when the supply of chloroform is limited, was devised by Sir James Simpson: it consists of either a cup-shaped inhaler, consisting of a wire framework covered with flannel, or else simply of a single fold of a pocket-handkerchief thrown over the face: the chloroform is dropped upon the flannel or handkerchief just under the nostrils in single drops at a time. Another plan is to pour some chloroform on to a folded towel or pocket handkerchief, and then place it over the patient's face, taking care that it does not come so close over the nose as to interfere with a free admixture of air with the chloroform vapour. There is this difference between ether and chloroform, that whereas it is highly inadvisable to give chloroform vapour in a concentrated condition, it is requisite to give the ether vapour very strong, in order to produce an anæsthetic effect. A combined administration of nitrous oxide and ether is now used to a considerable extent: the nitrous oxide producing rapid anæsthesia which is kept up by the ether.

Anæsthesia in Animals.

In the course of many investigations into the action of drugs on animals it is necessary to perform experiments which would be painful unless the animals were anæsthetised. The easiest way of doing this with frogs or small animals, such as mice, rats, or rabbits,

is to put them under a bell-jar with an opening at the top. Into this opening a piece of cotton-wool or blotting-paper is put, and chloroform dropped on it. The vapour being heavier than air falls to the bottom, and the animal soon becomes insensible. The best way of anæsthetising cats, small dogs, or very large rabbits, is to put them into a wooden box or tin pail, and stretch a towel tightly over the top. An assistant then pours some chloroform on the towel and anæsthesia is quickly produced. Rats are most readily anæsthetised by completely covering the cage, in which they are, with a towel, and dropping chloroform upon it.

For very large or savage dogs an old packing-case without a lid may be simply placed over the animal and held firmly down, or one of the sides may be furnished with hinges so as to convert the case into a sort of kennel. After the dog is safely housed large pieces of blotting-paper or of cloth on which chloroform is poured are pushed through cracks in the top of the case or holes specially made for the purpose. The outer ends of the blotting-paper or cloth remaining outside, fresh quantities of chloroform can be introduced as required until complete anæsthesia is produced. Anæsthesia may be maintained for almost any length of time that is required, by putting a piece of cloth loosely round the animal's nose and dropping chloroform upon it. This requires careful attention, however, in order to prevent danger from an overdose on the one hand, or partial recovery on the other. I find the most convenient way of maintaining the anæsthesia induced by chloroform in the way already mentioned is to put a cannula in the trachea and connect it with a flask containing ether, so that the inspired air passes over the surface of the ether, and carries a quantity of the vapour with it into the lungs of the animal. By means of a peculiar stopcock,



FIG. 48.—Diagram of a stopcock by which air or vapour, or two kinds of gas, may be given alone, or mixed together in any proportion.

the construction of which is indicated in the diagram (Fig. 48), pure air or air loaded with ether vapour or a mixture of both may be given.

The advantages of employing this method and of using ether rather than chloroform are that complete anæsthesia may be kept up for hours together with little or no attention on the part of the operator, and without the respiration or blood-pressure being seriously affected by the anæsthetic.

Another plan of maintaining anæsthesia for a length of time is to inject some laudanum or liquid extract of opium into a vein after anæsthesia has been induced by chloroform. Before the effect of the chloroform has passed off, such complete narcosis is produced by the opium that no procedure, however painful it might otherwise be, will produce the slightest evidence of sensation. When the effect of the anæsthetic or of the opium would interfere with the investigation of the action of a drug on the circulation or reflex action, the animal may be anæsthetised by chloroform, and the crura cerebri divided. The channels by which painful impressions are conveyed to the brain being thus destroyed no pain can be felt, although the reflex action of the cord again returns after the effects of the chloroform have passed off.

History of the Discovery of Anæsthesia.

This is a subject of considerable interest, and has given rise to much discussion. The starting point of the discovery seems to have been Sir Humphrey Davy's observations on the properties of nitrous oxide, regarding which he said, "as nitrous oxide in its extensive operation seems capable of destroying physical pain, it may probably be used with advantage during surgical operations." The property of this gas and also of ether vapour to produce excitement when inhaled, caused these substances to be used in sport, and during their action bruises were frequently received, but not felt. This circumstance excited the attention of Dr. Crawford W. Long, of Athens, Georgia, and in 1842, he anæsthetised a patient with ether in order to remove a tumour. He was encouraged to do this by the fact that Dr. Wilhite in a frolic had rendered a negro boy completely insensible without any bad results. Mr. Horace Wells, without knowing what Dr. Long had done, used nitrous oxide as an anæsthetic in 1844. His pupil, Mr. Morton, wishing to use it also, asked him how to make it, and was referred to a scientific chemist, Dr. Jackson. Jackson advised Morton to use sulphuric ether, as it had similar properties to nitrous oxide and was easier to get. Acting on this suggestion Morton used ether in dentistry, and induced Drs. Warren, Haywood, and Bigelow to perform important surgical operations on patients whom he anæsthetised by it. From this time onwards anæsthesia has been regularly used in medical operations. Shortly afterwards, Sir J. Y. Simpson discovered the use of chloroform as an anæsthetic, and it has been chiefly employed in Great Britain, but in America ether has always retained its original place.

Antispasmodics.

These are remedies which **prevent** or **relieve spasm.**

Spasm is contraction of voluntary or involuntary muscles, in a way that is unnecessary or injurious to the organism generally. The spasmodic contraction of muscles may sometimes be excessive in degree, as in the calves of the legs in cramp, or in the fibres of the intestinal walls in colic. Sometimes they are not excessive in degree, but are merely out of place, as, for example, in the slight twitchings of the face or fingers which occur in mild cases of chorea.

Spasm may affect single muscles, or it may affect groups of muscles and the nerve centres by which they are set in action; these centres may sometimes be very limited in extent, but sometimes a great number, or indeed most of the motor centres in the body, may be involved, as in the convulsions of hysteria. Spasm is, indeed, a kind of insubordination in which the individual muscles or nerve centres act for themselves without reference to those higher centres which ought to co-ordinate their action for the general good of the organism. It may be due therefore, either to excess of action in the muscles or local centres, or diminished power of the higher co-ordinating centres. As a rule it is due to diminished action of the co-ordinating or inhibitory centres, rather than to excess of action in the motor centres; it is, therefore, a disease rather of **debility** and deficient co-ordination than of excessive strength.

Cramps in the muscles may come on from their exhaustion by excessive exertion, the waste products of their functional activity appearing to act as local irritants. This is relieved by the removal of these waste products; as, for example, by shampooing. In the intestine, cramp may be due to the presence of a local irritant, which ought in the normal condition to produce increased peristalsis, and thus insure the speedy removal of the offending substance. From some abnormal condition the muscular fibres around the irritant contract excessively, and do not pass on the stimulus to those adjoining. From this want of co-ordination painful and useless spasm occurs. In order to remove it we apply **warmth** to the abdomen so as to increase the functional activity, both of the muscular fibres and of the ganglia of the intestine. Peristalsis then occurring instead of cramp, the pain disappears, and the offending body is passed onwards and removed. Or we give internally aromatic oils, which will have a tendency to increase the regular peristalsis; or yet again, we may give opium for the purpose of lessening the sensibility of the irritated part, or the nerves connected with it, and thus again bringing it into relationship with other parts of the body.

General antispasmodics may **act** either—

(1) By increasing the power of the higher nervous centres to keep the lower ones and the muscles in proper subordination, or—

(2) By lessening the activity of over-excited muscles or lower nervous centres.

On this account we find stimulants and antispasmodics very much classed together. Those drugs which **stimulate** the circulation and increase the nutrition of the higher nerve centres and the **co-ordinating power,** tend to prevent spasm. Thus, small quantities of alcohol and ether, by acting in this way, tend to prevent general spasm, as in hysteria, nervous agitation, or trembling, or remove local spasm, as in colic.

Valerian, assafœtida, musk, castor, and other aromatic substances, have an antispasmodic action which we do not understand. It is possible that they affect some part of the brain particularly, so as to increase its regulating power.

Camphor, which is frequently used as an antispasmodic, has a stimulant action on the brain, spinal cord, circulation, and respiration. It is probable that such antispasmodic powers as it possesses are due to its exciting the higher centres, and increasing their inhibitory powers over the lower. Bromo-camphor has a somewhat similar action. It is possible that castor, musk, &c., act in much the same way as camphor.

Other antispasmodics, such as bromide of potassium, **lessen** the **irritability** of motor centres. Borneol and menthol have a depressing and finally paralysing effect upon motor, sensory, and reflex centres in the brain and spinal cord. In this respect they differ greatly from ordinary camphor, which has an exciting action upon these structures, though they may perhaps be still more useful as antispasmodics.

Other antispasmodics, instead of lessening the irritability of nerve centres, may paralyse the structures through which the nerves act. Thus, nitrite of amyl appears to arrest the spasm of the vessels in angina pectoris, by causing paralysis of the vessels themselves or of the peripheral ends of the vaso-motor nerves.

Adjuvants.—As spasm is usually an indication of deficient nervous power, tonics, as quinine, iron, cod-liver oil, arsenic, sulphur, cold baths, and moderate exercise, are useful as adjuvants.

It has already been mentioned, that a healthy condition of the various parts of the body depends on proper nutrition and proper removal of waste. Therefore, when there is a tendency to spasm, the diet should be plain, but nutritious. Those conditions which tend to cause excessive waste should be avoided, such as exciting emotions, excessive bodily or mental work, a close atmosphere, and late hours. Attention must be paid also to the proper removal of all waste by the use of purgatives, cholagogues, or diuretics if necessary.

Great irritability of the nervous system is usually observed in gouty subjects before an attack of gout comes on. It is uncertain to what this irritability is due, but it may not improbably be caused by the retention within the body of products of tissue-waste. Some years ago there was considerable discussion regarding the active ingredient of bromide of potassium, some attributing its antispasmodic action to the bromine, and others to the potassium. It occurred to me that possibly its action might be partly due simply to its action as a saline leading the patient to drink more water, and thus assisting the elimination of the products of tissue-waste. I accordingly tried 30-grain doses of chloride of sodium in cases of epilepsy. In some it did little or no good, but in a few it appeared to have nearly as powerful an action as bromide of potassium.

Uses.—Antispasmodics are used in convulsive diseases.

The drugs employed in hysteria are :—

Assafœtida.	Valerian.	Alkaline bromides.
Galbanum.	Musk.	Sumbul.
Ammoniacum.	Castor.	

In epilepsy, laryngismus, and infantile convulsions, bromides of potassium, sodium, ammonium and calcium, nitrite of soda, salts of silver, zinc, and copper.

In chorea, arsenic, conium, copper, zinc.

In spasmodic asthma, lobelia, stramonium.

In spasm of the blood-vessels, nitrite of amyl, and other nitrites.

Action of Drugs on the Cerebellum.

The chief function of the cerebellum appears to be the maintenance of equilibrium. Symmetrical lesions on both sides of the organ or division of it down the centre from before backwards, cause very little disturbance of the equilibrium, but when a lesion is unsymmetrical the equilibrium is disordered.

According to Ferrier if the lesion affects the whole of a lateral lobe, there is a tendency for the animal to roll over towards the affected side. In an animal standing on all fours or lying on the ground, we regard the centre of the back as the point of movement, but in a man standing upright we usually take the face, and therefore what we should regard in an animal as rolling towards the affected side, would be equivalent in man to a rotation towards the sound side. If the lesion is limited to one part of the lateral lobe, it may not cause rotation, but only falling towards the opposite side. When the anterior part of the middle lobe of the cerebellum is injured, the animal tends to fall forward, and in walking usually stumbles, or falls on its face. When the posterior part of the middle lobe of the cerebellum is injured, the

head is drawn backwards and there is a continual tendency to fall backwards when moving.[1]

Injuries of the cerebellum are frequently associated with a certain amount of nystagmus, and in all probability the complete or partial inability to walk or stand which alcohol produces, is due to its action on the cerebellum.

Different kinds of spirit appeared to have a tendency to affect different parts of the cerebellum, for good wine or beer is said to make a man fall on his side, whisky, and especially Irish whisky, on his face, and cider or perry on his back.[2] These disturbances of the equilibrium correspond exactly with those caused by injury to the lateral lobes, and to the anterior and posterior part of the middle lobe of the cerebellum respectively. Apomorphia in large doses appears also to have an action on the cerebellum or corpora quadrigemina, as the animal poisoned by it does not vomit, but moves round and round in a circle.

The action of alcohol on frogs is peculiar, and differs from that of other narcotics, inasmuch as it appears to affect unequally the two sides of the nervous apparatus by which the equilibrium is maintained, so that in a certain stage of alcoholic poisoning they excite similar *manège* movements to those which occur after division of the corpora quadrigemina on one side.[3]

[1] Ferrier, *Functions of the Brain*, p. 94.

[2] Shorthouse, Baily's *Magazine of Sports*, 1880, vol. xxxv. p. 396.

[3] "Untersuchungen zur Mechanik der Nerven und Nervencentren." Von Wilhelm Wundt. Zweite Abtheilung, 1876. Stuttgart.

CHAPTER IX.

ACTION OF DRUGS ON THE ORGANS OF SPECIAL SENSE.

Action of Drugs on the Eye.

Action on the Conjunctiva.—Before light can reach the retina, it has to pass through the cornea, and alterations in this part are therefore important. The chief drugs employed in the treatment of disease of the cornea are astringents and sedatives, especially nitrate of silver and belladonna. There are two astringents which ought to be avoided, these are solutions of lead and of alum. Lead salts are objectionable, because if there is any ulceration on the cornea they may form an insoluble albuminate and cause permanent opacity. Salts of alum are perhaps still more objectionable, because alum has the power of dissolving the cement by which the fibrillæ of the cornea are held together, and this is, according to Tweedy, very apt to give rise to perforation of the cornea whenever the epithelium is removed by injury or inflammation.

The chief effects which drugs produce on the eye, besides those just described, are alterations in the size of the pupil, in the power of accommodation, in the intra-ocular pressure, in the sensitiveness of the retina to impressions, and in the apparent colour of objects.

Action of Drugs on the Lachrymal Secretion.—The great power of certain volatile oils such as those of onion or mustard, to irritate the eyes and cause secretion of tears is well known. The prolonged action of atropine diminishes the secretion. Eserine abolishes the action of atropine, and quickly increases the secretion.[1]

Projection of the Eyeball.—The non-striated muscular fibres which are contained in the orbital membrane and in both eyelids push the eyeball forward and draw the eyelids back when they contract. Like the dilatator pupillæ they are innervated by the sympathetic, and consequently some degree of protrusion of the eyeball is frequently produced by such substances as dilate the pupil. Excessive pain, or an asphyxial condition of the blood,

[1] Maynard, *Virchow's Archiv*, vol. lxxxix. p. 258.

has a powerful action in producing this effect, so that in men subjected to torture in the Middle Ages protrusion of the eyeballs was noticed; and both in animals and men dying from rapid asphyxia the eyeballs may seem as if starting from the head.

Action on the Pupil.—The iris is usually said to consist of two muscles, the sphincter, which has circular fibres and contracts the pupil, and the dilator, which has radial fibres and dilates the pupil. All observers are agreed regarding the sphincter muscle of the eyes, but some deny the existence of the dilator muscle. In the following description, however, I shall take the view which is usually accepted.

The sphincter receives its motor nervous supply from the third nerve, and the dilator from the cervical sympathetic. The nervous centre for the contraction of the pupil probably lies in the corpora quadrigemina; the nerve centre for the dilatation of the pupil lies in the medulla oblongata. The contracting nerves are contained in the third nerve, and pass to the ciliary ganglion, and thence to the eye. Along with them motor fibres pass also to the ciliary muscle. This muscle when contracted lessens the tension of the suspensory ligament on the lens, allowing the latter to become more spherical, and thus accommodating the eye for near objects. Such accommodation and contraction of the pupil generally accompany one another. The arrangement of the nerves of the eye is very diagrammatically shown in Fig. 49. A few of the dilating



FIG. 49.—Diagram to show the nervous supply of the eye. *a*, nerves to the ciliary muscle regulating accommodation; *b*, nerves to the contracting fibres, and *c*, nerves to the dilating fibres of the iris; *d*, vaso-motor nerves to the vessels of the eye. The iris is put apparently behind instead of in front of the iris for convenience in showing the passage of nerves to it.

fibres are contained in the fifth nerve, but most of them pass down the spinal cord to the cilio-spinal region in the lower cervical and upper dorsal part of the cord, and thence through the inferior cervical and superior dorsal nerves into the cervical sympathetic, in which they again ascend to the eye. Along with the dilating fibres others pass to supply the orbital muscle at the back of the orbit, which causes protrusion of the eyeball, as already mentioned.

There are also other fibres from the sympathetic which supply the muscular coats of the arteries of the ciliary vessels.

The dilating centre may be stimulated directly by venous blood circulating in it. In consequence of this the pupils usually dilate much when the respiration is imperfect, as during dyspnœa; but when the asphyxia becomes complete the centre again becomes paralysed and the size of the pupil diminishes. It may be stimulated reflexly by irritation of sensory nerves, so that dilatation of the pupil has been used as an indication of sensation in animals paralysed by curare. It seems to be readily stimulated by irritation of the genital organs. This is probably the reason why dilatation of the pupil frequently occurs in persons suffering from irritation of the genital organs. It is probably also readily stimulated by irritation of the intestinal canal, and such irritation may be the cause of dilatation of the pupil in children suffering from worms, and in cases of poisoning by drugs which irritate the gastro-intestinal canal, like aconite.

The drugs which act upon the iris are divided into two classes: **Mydriatics** which dilate, and **Myotics** which contract the pupil. The most important of these are such drugs as have a local action on the eye, and they alone are used in ophthalmic medicine. They are indicated in the following list by an *.

Mydriatics.	**Myotics.**
Anæsthetics.	Anæsthetics.
*Atropine.	*Calabar bean.
*Belladonna.	
Belladonnine.	
Benzoyltropine.	
Daturine.	
*Duboisine.	
Gelsemine locally.	Gelsemine internally.
*Homatropine (oxytoluylic-acid-tropine).	Jaborandi.
	Lobeline internally.
	Morphine internally.
Muscarine locally (?)	Muscarine internally.
	,, locally.
Narcissine.	Nicotine locally.
Piturine.	Opium.
Stramonium.	*Physostigmine (eserine).
	Pilocarpin.

Anæsthetics occur in both classes, because they cause contraction towards the commencement of their action, while later on, they cause dilatation. The probable reason of this is that at first they lessen reflex action, so that the reflex dilatation of the pupil by stimulation of sensory nerves is abolished. Later on when they begin to paralyse the respiration, the accumulation of venous blood

causes irritation of the dilating centre and widens the pupil. Dilatation of the pupil during the administration of anæsthetics is therefore to be regarded as a sign of failing respiration.

The contraction caused by morphine is also central and probably due to a similar cause.

It is possible that the local application of drugs to the eyes may have an action on the pupil due merely to their effect as irritants, and independent of any special action on the iris, for E. H. Weber[1] found that local irritation at the margin of the cornea causes partial dilatation. Irritation in the middle of the cornea causes rather contraction of the pupil. Localised irritation at the margin of the iris may cause dilatation at that part.

The reason why muscarine has been found by Ringer and Morshead to dilate the pupil when applied locally is probably that the solution they used was very irritating, either from its strength or for some other reason, while Schmiedeberg and Harnack found it to contract the pupil both when given internally and applied locally.

The contraction of the pupil noticed by Rossbach in rabbits immediately after the application of atropine, may also have been due to local irritation. The occurrence of dilatation in one case and of contraction in the other may possibly have been due to the solution being dropped into the eye in a different way in the two cases.

The most important **local mydriatics** and **myotics** are atropine and physostigmine (eserine).

When a solution of atropine is dropped into the eye, the pupil dilates and the ciliary muscle becomes paralysed, so that the accommodation for near objects is no longer possible, and the eye remains focused for distant objects. When a solution of physostigmine is dropped into the eye, the pupil contracts and the ciliary muscle becomes spasmodically contracted, so that the eye is accommodated for near objects.

It is very difficult to explain their **mode of action** satisfactorily, and authorities are by no means agreed regarding it. That the action is local is shown by the fact that when either atropine or physostigmine is applied to one eye its action is limited to it and the other remains unaffected. If care be taken to limit the application of a solution of atropine to one side of the margin of the cornea, local dilatation of the corresponding part of the pupil may be produced.

Dilatation of the pupil may be due to paralysis of the sphincter or excessive action of the dilator.

Paralysis of the sphincter may be due to (1) imperfect action or paralysis of the oculo-motor centre in the corpora quadrigemina, (2) to paralysis of the ends of the third nerve in the sphincter iridis, or (3) to the action of the drug upon the muscular

[1] Quoted by Landois, *Physiologie*, 1880, p. 799.

fibres of the sphincter itself, or to one other or all of those together.

Along with the factors just mentioned might be associated excessive contraction of the dilator muscle, which may be due (1) to stimulation of the sympathetic centre in the medulla, (2) of the ends of the sympathetic in the dilator muscle, or (3) stimulation of the dilator muscle itself.

Excluding for the present the question of excessive action of the dilator muscle and confining ourselves to the causes of paralysis, we see that paralysis of the cerebral oculo-motor centre as a factor in dilatation of the pupil by atropine is excluded by the local action of the drug, and also by the experiments of Bernard and others, which show that dilatation occurs from the local action of atropine, when the ciliary ganglion is extirpated and all the nerves of the eye with the exception of the optic have been divided. We can now limit its action either to paralysis of the ends of the oculo-motor nerve, or paralysis of the muscular fibres of the sphincter.

That the ends of the oculo-motor nerve in the sphincter iridis are paralysed is shown by the experiment that when the pupil is under the full action of atropine, irritation of the third nerve will not produce any contraction in it, although the sphincter will still contract when stimulated directly.

Here also we find the same relation between the action of atropine on nerves supplying striated and non-striated muscle that we have already noticed in the case of the œsophagus, for in most animals the iris consists of unstriated muscular fibre, and atropine causes dilatation; but in birds the iris consists of striated muscular fibre, and atropine causes no dilatation. Paralysis of the ends of the oculo-motor nerve in the iris itself may be looked upon as one of the factors in dilatation by atropine, and similar paralysis of the fibres supplying the ciliary muscle may be regarded as the cause of loss of accommodation.

In addition to this, however, when the dose of atropine is large, the muscular fibres of the sphincter themselves become paralysed, and fail to contract even when directly irritated.

The question now arises whether in addition to paralysis of the oculo-motor nerve there is not also excessive action of the dilator. That such action of the dilator is actually present appears to be shown by the following fact, viz., that the dilatation caused by atropine does not appear to be merely passive, but occurs with such force as to tear the iris away from the lens, and break down adhesions which may have formed between them. This conclusion has been considered to be supported also by the facts:—(*a*) That when the oculo-motor nerve is divided the pupil does not dilate nearly to the same extent as it does from the application of atropine. This is shown both by a comparison of measurements of the eye under the two conditions and by the observation that after the nerves have been

divided and partial dilatation produced atropine causes the pupil to dilate still more. (*b*) When the pupil is dilated by atropine, section of the sympathetic in the neck lessens the dilatation.

We may consider, then, with tolerable certainty, that dilatation caused by atropine is due to increased action of the dilator as well as diminished action of the sphincter muscles of the iris.

Contraction of the pupil may be due to excessive action of the sphincter, or paralysis of the dilator. That the contraction caused by physostigmine is not due to paralysis of the dilator is shown by the pupil dilating somewhat when shaded, even when the drug is exerting a well-marked action. Excessive action of the sphincter must therefore be regarded as the cause of the myosis. Such action may be due to (1) stimulation of the oculo-motor cerebral centre, (2) of the ends of the oculo-motor nerve in the sphincter, or (3) to increased action of the muscular fibres in the sphincter from the direct effect of the drug upon them. The local action of physostigmine upon the eye excludes the cerebral centre, and leaves for our consideration stimulation of the ends of the nerves and of the muscular fibres themselves.

These two structures seem to be specially affected by different drugs—so that **local myotics** may be divided into two classes—

1st. Those which act upon the peripheral ends of the oculo-motor nerve.

2nd. Those which affect the muscular fibre of the iris.

The first class includes muscarine, pilocarpine, and nicotine. Physostigmine belongs to the second.

Muscarine, pilocarpine, and nicotine, when applied to the eye, cause contraction of the pupil and spasm of accommodation. Atropine, as we have already seen, not only paralyses the ends of the oculo-motor nerve, which these drugs stimulate, but has also an action on the muscular fibre itself. Its subsequent application will therefore remove the effect of these drugs, and they will not act after atropine has been applied first. As physostigmine stimulates the muscular fibre itself, it will cause contraction in an eye which is dilated by atropine.

The contraction produced by muscarine in the eye of the cat is so great as to reduce the pupil to a mere slit, and is much greater than that caused by physostigmine, for muscarine acting only on the ends of the oculo-motor produces spasm in the sphincter without affecting the dilator, while physostigmine acting on the muscular fibres stimulates those of the dilator as well as the sphincter, and thus renders the contraction less complete.[1]

It has already been pointed out, however, that the action of atropine is not confined to the ends of the oculo-motor nerve, but affects the muscular fibre itself, and thus it will counteract the effect of physostigmine, which it would not do if it acted only on the nerves.

[1] Schmiedeberg, *Arzneimittellehre*, p. 71.

Atropine consists of the combination of a base, tropine, with tropic acid. Tropine itself has no mydriatic action, but when an atom of hydrogen in it is displaced by an acid residue it acquires this action. A number of combinations of tropine with different acids have been artificially prepared by Ladenberg, who terms them tropeïnes. Amongst these are homatropine, in which the tropine is combined with oxytoluylic acid, and also benzoyl-tropine. Atropine appears to be identical with daturine. Hyoscyamine is also a combination of tropine with tropic acid, but it appears to be only isomeric with and not identical with atropine, though it appears to be identical with duboisine.

Action of Drugs on accommodation.—The accommodation of the eye depends upon the ciliary muscle. When the eye is at rest the lens is flattened by the elastic tension of the zonule of Zinn. During accommodation for near objects the ciliary muscle draws the zonule forward and allows the lens to become more convex. The ciliary muscle is innervated by the third nerve: the centre for it appears to be in the posterior part of the floor of the third ventricle. Those drugs which affect the iris, also affect the power of accommodation. Their action on the iris and on accommodation do not, however, always begin at the same time, nor have they the same duration. The action of physostigmine and atropine on accommodation usually begins after, and passes away long before, the affection of the pupil.

Action on intra-ocular pressure.—The intra-ocular pressure depends chiefly on the relation between the amount of fluid poured into the anterior chamber of the eye, and the amount which passes out in a given time. This fluid is chiefly secreted by the ciliary processes. It passes out from the anterior chamber of the eye by a number of small openings (*f*, Fig. 50) close to the junction of the cornea and iris into the canal of Schlemm (*c*, *s*, Fig. 50), thence into the perichoroidal space, and out through the lymphatics.

The intra-ocular pressure may be increased by (*a*) more rapid secretion from the ciliary processes, or (*b*) interference with its outward flow from the eye, or (*c*) by increased quantity of blood in the vessels of the iris. It may be diminished by the contrary conditions.

More rapid secretion from the ciliary process probably takes place under nervous conditions which are not at present well known. Interference with the flow of the aqueous humour out of the anterior chamber may occur in aquo capsulitis, in which the openings from the anterior chamber into the spaces of Fontana are probably blocked by a coating of inflammatory lymph; in glaucoma where these openings are blocked by the iris being pressed forward against them as in Fig. 50, and in iritis where the iris is much congested and the openings in it perhaps occluded by lymph. The secretion is probably diminished by the action of atropine. The

outward flow through the spaces of Fontana is increased by Calabar bean, which, causing contraction of the circular fibres, flattens the arch of the iris and draws it away from the cornea so as to widen



FIG. 50.—This diagram (which I owe to the kindness of Mr. J. Tweedy) represents a section through the corneo-scleral region, ciliary body and iris, of a healthy eye (left side), and of a glaucomatous eye (right side): *k*, cornea; *s*, sclerotica; *i*, iris; *f*, spaces of Fontana; *c s*, canal of Schlemm. In the glaucomatous eye the ciliary body is atrophied, and the iris lies against the cornea preventing the escape of fluids through the spaces of Fontana and canal of Schlemm.

the angle between the cornea and iris, and aid the passage of fluid into the space of Fontana.[1]

There are few or no experiments on the tension in the vitreous humour of the eye, and by the term intra-ocular tension is usually intended the pressure in the aqueous humour. This is usually ascertained by simply pressing the finger upon the eye and observing whether it is harder or softer than usual, or by pressing upon it with an ivory point attached to a registering spring, and noticing the pressure required to produce an indentation. These methods of experiment are very inaccurate, and it is much more exactly ascertained by passing a small trocar into the anterior chamber and connecting it with a manometer. The results of experiments even by this method are not entirely in accordance.

The most recent ones by Graser[2] appear to show that the tension depends to a great extent upon the height of the blood-pressure generally: contraction of the pupil diminishes, and dilatation increases the intra-ocular tension.

Atropine in doses sufficient to dilate the pupil increases the tension. This action of atropine and its allies in increasing the tension makes them dangerous in cases of glaucoma, and where this disease has been impending it has been at once brought on by the use of atropine or duboisine. Eserine causes temporary increase at first, but after contraction of the pupil comes on, the tension is diminished. Eserine is therefore useful in glaucoma.

Uses of Mydriatics and Myotics.—Belladonna is employed locally for its sedative action to relieve pain and irritation in the conjunctiva.

Mydriatics and myotics are used not only for their action upon the pupil but for their action upon accommodation and intra-ocular pressure.

[1] J. Tweedy, *Practitioner*, Nov. 1883, vol. xxxi. p. 321.
[2] Graser, *Archiv. f. exp. Path. u. Pharm.*, Bd. xvii. Heft 5.

Mydriatics are employed to dilate the pupil for the purpose of facilitating ophthalmic examination, assisting the detection of cataract commencing in the periphery of the lens, or allowing the patient to see round the margin of a cataract when this is central in position, and would obstruct the vision with a pupil of normal size. They are used to prevent prolapse of the iris, or to restore it to its normal position when already prolapsed in cases of perforating ulcer or mechanical lesion of the cornea. They are employed in iritis, to afford rest to the inflamed tissues of the eye, and to keep the iris as far as possible off the surface of the lens and prevent adhesions of its posterior surface to the anterior surface of the lens.

Myotics are used to contract the pupil in cases of photophobia, or to counteract the effect of mydriatics which have been previously employed. They are used also to counteract deficiency in tension of the ciliary muscles, as in paralysis of accommodation consequent on diphtheria, asthenopia, and hemeralopia.

Mydriatics and myotics may be employed alternately in order to ascertain the presence of any adhesions of the iris, and to break them up if present.

Mydriatics are employed to paralyse the ciliary muscle, and thus destroy the power of accommodation in order to test the condition of the refractive media of the eye in cases of astigmatism, or in cases where the patients either suffer from spasm of the ciliary muscle or are unable voluntarily to relax the accommodation.

Myotics are useful in cases of commencing glaucoma, from their power to lessen intra-ocular tension, and in such cases mydriatics on the other hand are injurious and may hasten the appearance of the disease.

In glaucoma the tension within the anterior chamber is greatly increased, and the increase, according to Tweedy, is due to the natural channel of escape for the aqueous humour through the spaces of Fontana and the canal of Schlemm being blocked by the iris lying against the cornea. This condition is relieved by myotics, which, by causing contraction of the pupil, draw the iris away from the cornea, and thus allow the fluid to escape through the spaces of Fontana. When the anterior chamber of the eye is shallow and the iris is lying close to the cornea, so as nearly, though not quite, to obstruct the spaces of Fontana, atropine may bring on an attack of glaucoma by dilating the pupil and thus packing the tissue of the iris into the angle between it and the cornea, so as to render the obstruction to the spaces of Fontana complete.

Action of Drugs on the Sensibility of the Eye.—The sensitiveness of the eye to impressions is increased by strychnine, the field of vision becoming larger, and the sight more acute, so that objects can be distinctly observed at a greater distance, and the field of colour is increased for blue. This action appears to be to a certain extent local, as it occurs more distinctly

on that side where the strychnine has been injected hypodermically. The sense of colour is affected in a remarkable way by santonin, which at first causes objects to appear somewhat violet and afterwards of a greenish yellow. The yellow colour has been ascribed to staining of the media of the eye by santonin, as it becomes yellow when exposed to the light; others again have supposed the alteration in the apparent colour of objects to be due, first to a stimulation, and then to a paralysis of those constituents of the retina by which the violet colour is perceived.

The sensibility of the eye for red and green appears to be sometimes diminished by physostigmine.

Action of Drugs in Producing Visions.—It may be well here to mention the effect of some drugs in causing subjective sensations of sight, although these probably depend rather upon the action of the drugs on the brain, than on the eye itself. The centres for sight, according to Ferrier, are the angular gyrus (14 and 15, Fig. 46, p. 154), and the occipital lobes. In delirium tremens arising from alcoholic excess the patients often complain much of visions of the most disagreeable character, which often take the form of demons or of animals.

Cannabis indica produces in some persons, though not in all, visions which may be pleasant or laughable. These chiefly occur just before sleep.[1]

Salicylate of soda in some persons tends to cause most disagreeable visions whenever the eyes are shut, and I have seen it have this effect even in such a small dose as five grains. Large doses of digitalis may cause subjective sensations of light, and after taking nearly one grain of digitalin in the course of forty-eight hours I suffered from the centre of the field of vision being occupied by a bright spot surrounded by rainbow colours. Digitalin when introduced into the eye locally causes at first smarting and lacrymation, which soon passes off, but after four or five hours, when a light is looked at, a halo is seen surrounding it, which is not improbably due to some opalescence in the cornea.[2]

Action of Drugs on Hearing.

The sense of hearing depends on the transmission of sonorous vibrations from the air to the auditory nerve by means of the membrana tympani and the ossicles of the ear, and upon the perception of those vibrations by the brain.

The centre for hearing, according to Ferrier, is in the superior temporo-sphenoidal convolution (16, Fig. 46, p. 154). It is probable that subjective sounds not depending on disturbance of

[1] Compare Schroff, *Pharmacologie*, 4th edition, p. 535, and Wood, *Materia Medica*, 3rd edition, p. 236.

[2] Lauder Brunton, *On Digitalis*, &c.

the auditory apparatus, such as the sounds of voices, &c., heard in delirium or mania, or as the prodromata of an epileptic fit in certain individuals, or during intoxication by cannabis indica, are due to irritation of these centres.

The sense of hearing may be dulled by any interference with the passage of the sound into the ear, as by wax in the auditory meatus, by disease of the auditory nerve or of the brain itself.

The hearing may be rendered more acute by the removal of any obstacle in the way of transmission of sound to the auditory nerve, or by drugs which increase the excitability of the auditory nerve or of the brain; thus the wax may be removed by simply syringing; thickness and catarrh of the Eustachian tube which interfere with vibrations in the middle ear may be lessened by the inhalation of camphor and ammonia, or by the application of a solution of ammonium chloride and sodium bi-carbonate to the posterior nares either by the spray or nasal douche. The excitability of the auditory nerve or of the brain is increased by strychnia which renders the hearing more acute.

Subjective noises in the ear, such as humming, buzzing, or ringing, are often very troublesome. Bubbling noises may be due to mucus in the Eustachian tube. Buzzing or humming are probably generally caused by vascular congestion either of the external meatus, of the middle ear, or of the Eustachian tube. Where the bubbling noises are due to the presence of mucus they may be to a considerable extent removed by washing out the mucus with a solution of carbonate of soda applied by a nasal douche. Noises in the ears due to hyperæmia may be lessened or removed by cholagogue purgatives and by hydrobromic acid. Where chronic thickening of the membrane is present, relief is usually afforded by iodide of potassium, or iodide of ammonium, both applied locally and taken internally. Subjective noises in the ears are caused by quinine in large doses, and also by salicylate of soda. Both of these drugs have their effect upon the ear to a great extent neutralised by hydrobromic acid, and ergot[1] is said to have a similar power to prevent or remove the unpleasant singing. It is uncertain whether the singing caused by quinine and salicylates is due to their action on the auditory apparatus, or the cerebral centres, but the fact that in larger doses they may cause delirium indicates that even the earlier symptom of buzzing in the ears may be due in part at least to their action on the cerebral centres.

Action of Drugs on Smell.

Many drugs, such as musk and ethereal oils, have a marked and characteristic smell due to their effect upon the terminal branches of the olfactory nerve. This nerve is soon exhausted, so that in a

[1] Schilling, *Aertzl. Intelligenzblatt.* 1883.

very short time, the smell is no longer perceived with anything like the intensity it was at first. Such smells as these just mentioned cannot be perceived by persons suffering from anosmia, but certain drugs, such as ammonia or acetic acid, can be recognised by them. The reason of this is that although such persons are incapable of perceiving any true smell, the nasal branches of the fifth nerve are irritated by pungent vapours, and thus produce a certain kind of sensation. The power of distinguishing smells seems to be increased by strychnine; which appears at the same time to render such disagreeable odours as those of assafœtida, garlic, and valerian agreeable. This effect may be due to the action of strychnine on the olfactory apparatus, but it is very probably due rather to the action of the drug on the cerebral centre for smell, which, according to Ferrier, is situated at the tip of the temporo-sphenoidal lobe. The power to distinguish smells is diminished by such drugs as lessen the sensibility of the brain, or by those which cause alterations in the nasal mucous membrane, as for example iodide of potassium given in such doses as to produce coryza.

Action of Drugs on Taste.

Most of the substances used in medicine have a strong taste and many a very unpleasant taste.

What is usually termed taste frequently depends on a mixture of taste and smell, and if the sense of smell is abolished for the time being, the characteristic taste of the substance cannot be distinguished. This is the reason why castor-oil, which owes its nauseous taste almost entirely to its odour, can be swallowed without being so readily distinguished if the nose is held during the act of swallowing. In addition to the taste they produce in the mouth, certain substances leave an impression termed "after-taste" on the tongue after they have been swallowed or ejected; and this is sometimes quite different from that of the taste of the substance itself: thus bitters leave a sweet after-taste in the mouth. If quinine is taken in a nearly neutral solution, it leaves a persistent bitter taste from the sparingly soluble alkaloid being precipitated on the tongue and remaining there for a length of time, but if the quinine be taken with excess of acid, so as to keep it entirely in solution, and washed out of the mouth immediately with a draught of water, it leaves a sweet after-taste.

Some substances after their entrance into the blood are excreted by the saliva and may cause a somewhat persistent taste in the mouth; this is observable in the case of iodide of potassium.

Iodine appears also to have the power of causing other substances to be excreted by the saliva, when they are combined with

it, and thus Bernard found that iodide of iron was secreted by the saliva, though lactate of iron was not; and I have sometimes thought that iodine has a similar effect upon quinine, because I have very frequently noticed patients complain of a persistent bitter taste in their mouth when I have given quinine combined with iodide of potassium, although they did not complain of this when either of the drugs has been given without the other.

CHAPTER X.

ACTION OF DRUGS ON RESPIRATION.

Respiratory Stimulants and Depressants.

It is usually supposed by naturalists that in the descent of man from some organism low in the scale of existence, he has passed at a remote period through a stage resembling the Ascidians or Tunicata. In these animals respiration is maintained by water being driven through a perforated sac in the meshes of which the nutritive fluids of the animal circulate. The contractile motions of the sac by which the circulation of fluid is maintained probably depend on a **nervous ganglion** situated between the oral and anal apertures as represented in the diagram (Fig. 51). We do not know whether or not this ganglion may influence the circulation which is maintained by the rhythmical contractions of the simple tube which serves as a heart. These drive the fluid first in one direction, and then after a while the action of the tube is reversed, and its contractions drive the fluid in the opposite direction. This ganglion in its functions would correspond with the **medulla oblongata** in the vertebrata, and thus the medulla oblongata may be looked upon as a lower and more **fundamental centre** than the brain or spinal cord.

We see this more distinctly perhaps by looking at the two diagrams (Figs. 52 and 53) representing an amphioxus and a fish. In the amphioxus respiration is kept up in much the same way as in the ascidian, the water passing from the pharyngeal to the atrial sac and through the atrial aperture or abdominal pore. There is no head and no organs of special sense, and so we have no brain whatever. But the body is elongated so as to remind us of an ascidian, having its ganglion and the part of the body wall containing it so much extended as to remove the anal considerably from the oral aperture. The muscles of this elongated body require innervation, and thus the ganglionic mass is elongated into a cord called the myelon, which represents the spinal cord as well as the medulla oblongata. In ascidians then we have a mass corresponding

to the medulla: in the amphioxus we have a mass corresponding to medulla and spinal cord.



FIG. 51.—Diagram of an Ascidian.



FIG. 52.—Diagram of Amphioxus. The water enters the oral aperture, passes through the openings in the pharyngeal sac into another cavity, whence it escapes by the abdominal pore.



FIG. 53.—Diagram of fish.

In a fish the pharyngeal or branchial sac, instead of opening into the atrial sac, opens directly into the surrounding water. We have a head and organs of special sense, and therefore we have a large nervous mass or brain.

In these three members of the animal kingdom, therefore, we have the medulla as the lowest or fundamental centre, next the spinal cord, and lastly the brain. We might therefore expect that notwithstanding the apparently higher position and greater nearness of the **medulla** to the brain than to the spinal cord, the medulla would be **less** readily **affected by** many **drugs than** the **cord** or the **brain,** and this is what we find in the case of such drugs as alcohol, ether, or morphia, which appear to paralyse

the nervous centres in the inverse order of their development, the brain first, spinal cord next, and medulla last.

There are some drugs, however, *e.g.* aconite, gelsemium and hydrocyanic acid, which seem to have a special paralysing action on the respiratory centre.

If we look at the ganglionic mass in an ascidian, represented in the diagram, we shall see that it sends some fibres to the pharyngeal sac and some to the anal sac. If these two sacs were to contract together they would oppose each other's action, and thus the passage of water through the branchial apertures would be stopped, and respiration consequently arrested. They must therefore act alternately, and this alternate action is regulated by the ganglion. This ganglion consists of numerous nerve cells and fibres. As some of these have a more special connection with the pharynx, the group which they form may be called the pharyngeal centre or inspiratory centre.

Similar arrangements occur in higher animals, and the terms used in regard to their nervous system may lead to some confusion of thought; thus we speak of the respiratory, of the inspiratory, of the expiratory, and of the vomiting centres.

By nerve centres we simply mean the **groups** of **cells** and fibres which are concerned in the **performance** of certain **acts.** They are not necessarily entirely distinct from one another, and the same group of ganglionic cells may form a part of several centres. Thus in the accompanying diagram, the **respiratory** centre includes both **inspiratory** and **expiratory** centres, and the vomiting centre includes some ganglionic groups which form part of the inspiratory, and others forming part of the expiratory centres, besides other ganglion groups which are concerned with the simultaneous dilatation of the cardiac orifice of the stomach. On analysing this subject still further also we find that the inspiratory centre affects many muscles, and that it does not always affect them to the same extent. Thus in men the diaphragm takes a more active share in inspiration during the day than the thoracic muscles. During sleep the diaphragm takes a much less active part, and may be entirely quiet, while the thoracic muscles are more active, and the chest rises and falls more than during waking.

The **inspiratory** centre might be thus still further divided into **thoracic** inspiratory centre, and **diaphragmatic** inspiratory centre.

Such subdivisions appear absurd if we imagine that each centre represents a distinct nervous mass, and we become puzzled to understand how the medulla oblongata can contain so many distinct centres in a small bulk. But if we remember that the word **"centre"** simply indicates a group of cells and fibres connected with the performance of a particular act, and that two centres may be formed by the same ganglionic groups, and differ from one another only by having a few ganglion cells more or

less which alter the function they perform, no harm is done by the use of the term.



FIG. 54.—Diagrammatic representation of various groups of ganglion cells, or "centres," in the medulla oblongata. The arrows indicate the directions in which the nerve-currents pass. Those pointing to the cells indicate sensory, those pointing from the cells indicate motor, nerves.

The act of **respiration** consists in the alternate enlargement and diminution of the thoracic cavity, so that the air is alternately inspired and expired.

The **muscles** by which this is effected in ordinary respiration are the diaphragm and intercostal and scaleni muscles. The diaphragm descends, and the intercostal and scaleni muscles raise the ribs during **inspiration**.

Expiration is normally a **passive** act[1] and is not performed by muscular action, but simply by the tendency of the diaphragm and thoracic walls to return to the position of equilibrium from which they had been removed during inspiration, and to the contraction of the elastic walls of the air-vesicles distended by inspiration.

When the supply of oxygen is deficient, other muscles are called in to aid the inspiration. Expiration appears to be a passive act not merely in ordinary respiration but even in dyspnœa caused by the absence of oxygen. In some experiments by Bernstein[2] the inspiration and expiration were equally increased in a rabbit, when the air which it had breathed was replaced by hydrogen. But expiratory efforts are required both for the production of voice, and for the removal of irritants from the air passages by coughing or sneezing; and forcible expiration is produced when an irritant is applied to the mucous membrane of

[1] Bernstein, *Archiv. f. Anat. u. Physiol.* 1882, p. 322.
[2] Bernstein, *Op. cit.*

the nose, of the larynx, trachea, or bronchi. As every one who has drunk a bottle of soda-water knows, carbonic acid is an irritant of considerable power to these mucous membranes, and when it is breathed instead of air or hydrogen the expiration becomes much more powerful, and is no longer a passive action, but an active one, performed by active muscular exertion.

The chief **respiratory centre** is situated in the medulla oblongata close to the end of the calamus scriptorius, at the point designated *noeud vital* by Flourens, because destruction of this point arrests the respiration and causes death.

It extends equally on both sides of the middle line in the medulla, each half regulating the breathing on the same side of the body. It has been supposed to be double, and to consist of inspiratory and expiratory centres which act alternately, but it would appear that in ordinary respiration the inspiratory centre only is active.

When the centre is injured by a puncture, as in Flourens' experiment, or when one half of it is destroyed, breathing usually stops entirely, but if the respiration be kept up artificially for several hours, the normal breathing again becomes established; and the prolonged continuance of artificial respiration has been recommended by Schiff in apoplexy.

When the connection between this centre and the respiratory muscles is cut off by dividing the spinal cord just below the medulla, respiration usually ceases entirely, so that at first sight it would seem that the respiratory centre is limited to the medulla.

The effects of strychnine show that this is not the case. This drug greatly increases the excitability of the respiratory centre, and when it is injected into the blood before division of the spinal cord, the respiratory movements still continue to some extent after the cord has been divided. When it is injected after section of the cord, the respiratory movements which had ceased again recommence to a slight degree.

The reason appears to be that the **respiratory centre** is not limited to the **medulla,** but extends to the upper part of the **spinal cord,** though the spinal portion is of itself too weak to keep up the respiratory movements, except when stimulated by strychnine.

The **amount of respiratory work** which this centre excites appears to **depend** to a great extent, though not entirely, upon the condition of the **centre** itself.

The **distribution** of the work is chiefly determined by the irritation of one or other of the afferent **nerves,** and these nerves also influence the amount of work.

The **centre** is stimulated, and the amount of work it does increased by a venous condition of the blood circulating in it. An arterial condition of its blood lessens or completely abolishes its activity, so that when the blood is highly aërated by forced

artificial respiration, a condition of **apnœa** is produced, in which no spontaneous respiratory movements occur.

This condition is much more readily induced when the excitability of the respiratory centre is lessened by drugs. In an animal poisoned by chloral, for example, it is very easy to induce it, and it lasts for a long time.

When the respiratory centre is excited, as by the injection of emetine or apomorphine into the circulation, it is difficult or impossible to produce this condition.

It is uncertain whether the stimulation which the venosity of the blood produces is due chiefly to the absence of oxygen or to the presence of carbonic acid. Possibly also it may be due to the products of imperfect combustion in the venous blood. Or all these three causes may share in the stimulation, though to what extent each does so is not known.

According to Bernstein, want of oxygen appears to stimulate the inspiratory and the presence of carbonic acid to stimulate the expiratory centre.[1]

As the blood becomes venous the activity of the respiratory centre increases, the respirations becoming quicker and deeper, and the accessory respiratory muscles are thrown into action. This condition is called **dyspnœa.** Finally the excitement extends to all the muscles of the body and we get general **convulsions,** which have usually an opisthotonic character. The eyeballs very often protrude during these convulsions, and the blood-pressure rises greatly from stimulation of sympathetic and vaso-motor centres in the medulla.

After the convulsions cease, the animal usually lies motionless, and the heart as a rule continues to beat for a short time after the respirations have ceased.

The excessive venosity of the blood in this condition has paralysed the nerve centres, but if artificial respiration be now commenced and the blood becomes gradually aërated, the conditions just described are again passed through in the reverse order: convulsions first reappearing, then dyspnœa, next normal breathing, and, if the respiration be pushed far enough, apnœa.

Asphyxial convulsions only occur in warm-blooded animals, and not in frogs, and when we find that any drug produces convulsions in mammals and not in frogs we usually assume that the convulsions are due to asphyxia produced by the action of the drug on the respiration or circulation, and not to a direct irritant action upon the motor centres. If on the other hand we find that the convulsions occur in frogs as well as in mammals, the presumption is in favour of their being due to the direct irritant action of the drug on motor centres.

Blood becomes venous when the external respiration or interchange of gases between it and the external air is arrested while internal respiration continues.

[1] Bernstein, *Op. cit.* p. 324.

Internal respiration or interchange of gases occurs between the blood and the tissues outside the vessels which are consuming oxygen and deriving it from the blood. But the blood although fluid is itself a tissue and likewise consumes oxygen, so that it will become venous if left to itself in a thoroughly-stoppered glass bottle.

External respiration may be arrested or diminished by—

(1) Interfering with the access of air to the blood; or
(2) „ „ „ „ „ blood to the air; or
(3) „ „ „ power of the blood to take up and give off oxygen.

The access of air to the blood may be prevented by obstruction to the air-passages or alteration in the structure of the lung; thus anæsthetics may obstruct respiration by allowing vomited matters to enter the trachea and plug it mechanically. Apomorphia may lead to obstruction of the bronchi by profuse secretion from the mucous membrane, and large doses of antimony may cause consolidation of the lung.

Air may be prevented from reaching the blood by any obstruction in the respiratory passages.

The respiratory passages may be obstructed by spasmodic closure of the glottis or of the nostrils in rabbits when an irritating vapour is inspired. This source of obstruction is easily avoided by putting a cannula into the trachea and allowing the vapour to be inspired through it. Another source of obstruction is the formation of plugs of mucus or clots of blood in the trachea or in the cannula, which has been introduced into it. Occasionally a plug of mucus, and sometimes a clot of blood, forms in the tracheal cannula and seriously impedes the respiration, whether natural or artificial, without being perceived by the experimenter. In order to be sure that such an occurrence has not taken place and vitiated the results, it is always advisable on removing the cannula from the trachea at the end of an experiment to blow through it and see that its lumen is perfectly unobstructed.

Access of air to the blood may be prevented also by paralysis of the muscles of respiration; thus curare will produce it by paralysing the ends of the motor nerves, hydrocyanic acid by paralysing the respiratory centre, and snake poison by paralysing both.

The blood may be prevented from reaching the lungs by arrest of the circulation either local or general, and may thus become venous either locally or generally.

The **venosity** of the blood circulating in the medulla may be altered **locally** without any change in the rest of the body. Thus if the carotid and vertebral arteries are tied, the blood stagnates in the vessels of the medulla, and there becoming venous causes dyspnœa and convulsions, which again disappear when the ligatures are loosed and the circulation re-established.

Dyspnœa and convulsions are likewise produced by alteration in the **general** circulation, *e.g.* by loss of blood, as is seen when an animal is bled to death, or when the supply of blood in the arteries is greatly diminished by ligature of the portal vein, which

causes the blood to accumulate and stagnate in the capacious veins of the intestine.

Stoppage of the **heart,** either by ligature directly applied to it or by the action of drugs upon it, causes asphyxia and convulsions.

Arrested circulation through the **pulmonary** vessels by emboli has a similar action. This sometimes leads to error in regard to the action of drugs when these are injected, as is often done, into the jugular veins.

If they contain solid particles, these may give rise to embolism in the pulmonary arteries and lead to the belief that the drug has a tetanising action, when, as a matter of fact, it has nothing of the kind. Thus, in making an experiment on condurango, I injected an infusion into the jugular vein of a rabbit, and it rapidly died with symptoms resembling those of strychnia poisoning. The cause of this, however, was simply embolism of the pulmonary vessels, due to undissolved particles in the infusion, and when this was avoided by injecting the drug into the peritoneal cavity, no symptom whatever was produced. Gianuzzi, in his experiments on this drug, appears to have fallen into the same error as I did at first.

Altered condition of the **blood** also gives rise to dyspnœa, as is seen in the breathlessness of anæmia, where the blood is unable to take up the quantity of oxygen necessary for any exertion, and the patient pants violently after any quick movement, such as going up stairs.

Dyspnœa and even convulsions are also caused by nitrites, *e.g.* nitrite of amyl or soda, which lessen the power of the blood to give off oxygen, and by carbonic oxide, which replaces the oxygen in the blood.

It must be remembered however, that, whatever may be the remote cause of dyspnœa, its direct cause is the condition of the nerve cells in the medulla, and if these are unable to take up oxygen, and give off carbonic acid to the blood, dyspnœa may occur, although the blood itself circulating in the medulla contains abundance of oxygen.

In the case of carbonic oxide poisoning the blood cannot take up oxygen from the lungs, although there is abundance of oxygen present; and in a similar way the nerve cells of the medulla may possibly be rendered by certain drugs unable to take up oxygen from the blood circulating through the medulla.

In simple suffocation the **internal respiration** of the nerve cells in the medulla is arrested by the general venous condition of the blood; in carbonic oxide poisoning by the oxygen being absent from the hæmoglobin; in nitrite poisoning by the oxygen being locked up in methæmoglobin. In all those cases the condition of the blood is betrayed to the eye by the appearance of the mucous membranes, which in suffocation and in nitrite poisoning become dark and livid, and in carbonic oxide poisoning of a cherry-red

colour. Perhaps the change is most conveniently seen in the comb of a cock poisoned by these substances, and in it the alteration in the colour of the blood produced by artificial respiration is readily seen. The dependence of convulsions upon the blood is also easily observed: the convulsions appearing as the comb becomes livid, and again disappearing when artificial respiration has been employed, and the colour of the comb becomes bright. In poisoning by hydrocyanic acid, however, I have observed that convulsions come on while the mucous membranes are still of a bright colour, so that we may conclude that they are not due to a venous condition of the blood as in ordinary suffocation. They might be due to the formation of a compound between the hydrocyanic acid and the blood as in poisoning by nitrites or carbonic oxide, but accurate analyses have shown that hydrocyanic acid does not displace the oxygen in hæmoglobin like carbonic acid, nor lock it up in the form of methæmoglobin like the nitrites. We are therefore obliged to consider the possibility that the dyspnœa and convulsions produced by hydrocyanic acid are not due so much to its effect upon the blood circulating in the medulla as by an action on the cells of the medulla itself, by which it prevents the ordinary internal respiration taking place in them.

Action of Drugs on the Respiratory Centre.

A useful method of testing the action of the drug itself on the respiratory centre is to perform artificial respiration vigorously so as to produce apnœa, to allow the respiration to become normal again, then to inject the drug and again try to produce apnœa. If the drug has excited the respiratory centre, apnœa will be much more difficult to produce after its injection than before, and will last a shorter time; if it has depressed it, apnœa will be more easily produced, and will last longer.

Apnœa lasting for a short time may be readily produced by taking five or six very deep breaths, and the effect of drugs on the respiratory centre may be readily tried by any one in the following way. Laying a watch before him, shutting his mouth and holding his nose, let him first ascertain how many seconds he can hold his breath after previous ordinary respiration. Next let him produce a certain amount of apnœa by six or more deep respirations, and again ascertain how long he can hold his breath. After repeating these observations several times, let him take the drug to be tested and repeat them again, taking care that all the circumstances should be the same as before.

The **activity** of the **respiratory centre** is augmented by heat, so that the respirations become both quicker and deeper, and more respiratory work is done. Strychnine, ammonia, atropine, duboisine, brucine, thebaine, apomorphine, emetine, members of the digitalis group, salts of zinc and copper, have a similar action.

It appears to be first excited and then depressed by caffeine, colchicine, nicotine, quinine, and saponine.

It is diminished by cold, so that the respirations become slow and shallow. Chloral, chloroform, ether, alcohol, opium,

physostigmine, muscarine, gelsemine, aconite, and veratrine in large doses, all have a similar action.

The action of drugs on the respiratory centre is one of great importance, not only as giving us a definite basis on which to found a plan of treatment in respiratory diseases, but as helping us to preserve life in cases of poisoning — drugs which stimulate being antagonised by those which depress the respiratory centre, and *vice versâ*.

The chief **afferent nerves,** by which the distribution of the respiratory movements is altered, may be divided into two classes —those having an inspiratory and those having an expiratory action.

The **expiratory** are the nasal branches of the fifth, the superior laryngeal, the inferior laryngeal, and the cutaneous nerves, especially of the breast and belly.

The chief **inspiratory** are the branches of the vagus going to the lung, but all sensory nerves when slightly stimulated appear also to have an inspiratory action.

The vagus appears, however, to contain both expiratory and inspiratory fibres, which are alternately stimulated by the condition of the lung. Expansion of the lung appears to stimulate mechanically the inhibitory or expiratory fibres; while its collapse stimulates the accelerating or inspiratory fibres.

When the **expiratory** nerves are stimulated, the respiratory movements become **slower** and deeper; and if the stimulation be strong they may stop altogether in expiration, with the diaphragm in complete relaxation.

Stimulation of the **inspiratory** nerves causes the respiration to become **quicker** and shallower, and at length to stop in inspiration, the diaphragm being in a state of tetanic contraction.

These are the general **results,** but they are **not** quite **constant.** The reason for this inconstancy may be either that all the nerves contain both inspiratory and expiratory fibres, or that the same fibres may stimulate either the inspiratory or expiratory centres, according to the strength of the stimulus and the condition of the animal. Thus, when the vagus is divided, the stimulus which is conveyed to the respiratory centre being removed, the respirations usually become very slow; when the central end of the divided nerve is irritated they become quick, and a very strong current may stop them in inspiration. But this is not always so: when the nerve is very much exhausted, irritation by a strong current may have an entirely **opposite** effect, and cause the respiration to stop in expiration instead of inspiration.

The probability that the same nervous fibres may, under different conditions, excite either inspiration, expiration, or the two alternately, is rendered still greater when we consider some other experiments; and the contradictory results which have been obtained by various observers in regard to the action of drugs may depend

to a great extent on the strength of the stimulus they have used and the state of exhaustion of the animal. Thus Langendorf has found that all sensory nerves in the body when slightly stimulated have an inspiratory, but when stimulated more strongly have an expiratory action. Rosenthal found that irritation of the crural nerves caused alternately deep inspiration and expiration in animals which were not narcotised. In narcotised animals, Langendorf, on slight irritation, observed an inspiratory effect, indicated by quickening of the respiration or slight inspiratory tetanus; but when the experiment was continued long, or the irritation was increased, the contrary or expiratory effect was observed, indicated by a slowing of the respiration.

On the hypothesis that the various actions of respiration depend upon individual centres, inspiratory, expiratory, and inhibitory, it is exceedingly difficult, or impossible, to understand the contradictory results of various experimenters, but the question seems much less intricate when we regard it as due to the interference of stimuli passing at different rates in different directions,


Inspiratory and Expiratory Fibres for voluntary alterations in Respiration
Cutaneous Nerves of Face
Chiefly expiratory and slowing.
Nasal Branch of Fifth Nerve
Superior Laryngeal Nerve
Inferior Laryngeal Nerve
Larynx
Cutaneous Nerves of the Chest
Expiratory Fibres of Vagus excited by distension of Lung
Inspiratory Fibres of Vagus excited by collapse of Lung
Respiratory Centre in Medulla and Cord.
Spinal cord.

FIG. 55.—Diagram showing the position of respiratory centre, and the afferent nerves which influence it. Inspiratory nerves are indicated by plain, and expiratory by dotted, lines.

or to different distances according to the strength of the stimulus and the irritability or exhaustion of the nervous system.

In regard then to inhibitory or slowing, and to stimulating or accelerating nerves or fibres, it must be carefully borne in mind that the same fibres may possibly have either the one or the other action, according to the conditions under which it is acting.

If we keep this carefully in view we may continue to use the terms accelerating and slowing or inspiratory and expiratory nerves as a convenient means of expression. These are shown in the accompanying diagram.

The movements of respiration are not only more easily counted than in any other way, but their depth and the relation of inspiration to expiration are best noted by causing them to register themselves on a revolving cylinder. Various means of doing this have been suggested by different authors. One of the simplest consists of a needle pushed into the diaphragm, and connected by a thread with one of Marey's levers. Marey's pneumograph consists of a cylinder of soft indiarubber, enclosing a spiral spring, whose extremities are connected with two pieces of metal which form the ends of the cylinder. A band is passed round the thorax of the animal, and attached to the ends of the cylinder. The interior of the cylinder is brought into communication with one of Marey's levers, and as each respiratory movement draws the ends of the cylinders wider apart, or allows them to approach, the air is rarefied or compressed, and a corresponding movement is transmitted to the lever. Bert has modified this, and made it more sensitive by making the cylinder itself of metal, and its ends of indiarubber. Another method—one more ordinarily employed—is to introduce one limb of a T-tube into the nostril or trachea of an animal, or connect it with a tracheal cannula. The respired air passes through the other end, and the third limb is connected with one of Marey's levers.

In the attempt to find out whether the alteration in respiration produced by any drug is due to its action on the respiratory centre, or on some of the nerves which influence it, we may find the following table useful by showing at a glance the chief ways in which the respirations may be rendered **quicker** or **slower**:—

The respiratory movements may be **quickened** by	Excitement of nerves.	Stimulation of the vagus.
		Stimulation of optic nerve.
		Stimulation of acoustic nerve.
	Greater excitement of respiratory centre.	Action of brain (voluntary).
		Increased temperature of blood.
		Increased venosity of blood.
		Action of drugs.
The respiratory movements may be rendered **slow** by	Diminished excitement of respiratory centre.	Diminished venosity of blood.
		Action of drugs.
		Action of brain (voluntary).
	Nervous influences.	Paralysis of vagi.
		Stimulation of superior laryngeal nerves.
		Stimulation of inferior laryngeal nerves.
		Stimulation of nasal nerves.
		Stimulation of cutaneous nerves.
		Stimulation of splanchic nerves.

If the drug to be experimented on be injected subcutaneously or into the veins, the actions on the respiratory centre and on the vagi are the chief points which require attention; but if we are experimenting with a vapour, its local action on the nasal, laryngeal, and possibly, also, on the pharyngeal nerves[1] must be carefully attended to, as it may greatly modify its general action on the

[1] Brown-Séquard, *Archives of Scientific and Practical Medicine*, p. 94.

respiratory centres. Thus Kratschmer has found that tobacco smoke inhaled by a rabbit through its nostrils, or blown upward into the nasal cavity from an aperture in the trachea, will cause arrest of breathing in a state of expiration from the irritating effect of the vapour on the nasal branches of the fifth, while it has no such effect when blown into the lungs. Ammonia, when inhaled, also arrests the respiratory movements in the same way; but Knoll[1] has observed that if it be blown into the lungs while the nostrils are carefully protected from its influence, it causes accelerated and shallow breathing, alternating with slow and deep respirations, and occasional stoppages in the position of expiration, obviously from its action on the different fibres of the vagi.

Action of Drugs on the Respiratory Nerves.

In experiments regarding the effect of drugs upon the respiration, the voluntary influence of the brain is excluded by the use of ether, chloroform, opium, or chloral, or by section of the crura cerebri. In the case of such poisons as cause sickness allowance must be made for the effect of gastric irritation. It will usually be found that before vomiting occurs the respiratory movements are very rapid, but they become slower after vomiting has taken place. As the chief afferent fibres from the stomach are contained in the vagus, the effect of irritation of the gastric, as well as of other fibres contained in these nerves, is prevented by their division. Sometimes the action of a drug on the peripheral ends of the vagus and upon its roots in the medulla may produce exactly opposite effects upon the respiration. Thus atropine appears to lessen the excitability of the respiratory fibres of the vagus, while it stimulates the respiratory centre. Such an action may be to a certain extent inferred from the respiration becoming slower almost immediately after the injection of the drug into the jugular vein, and while it is still passing through the lungs, and by this slowing being quickly succeeded by acceleration when the drug begins to circulate through the medulla.

There are two kinds of experiment by which such a conclusion may be tested. The one is to apply the drug first to the medulla by injecting it into the carotid artery, and seeing whether acceleration occurs at once and afterwards becomes less when the drug has had time to pass round again to the lungs. The other way is to divide the vagi before the injection and observe the effect. Any alteration in the respiration in the way of either quickening or slowing which the drug produced in the uninjured animal should remain the same after division of the vagi if its effect were due to its action on the medulla, but will be absent if it were due to an action upon the peripheral ends of the vagi.

This method was introduced into pharmacological research by

[1] *Sitzungsber. der Wien. Acad.*, vol. lxviii. Abt. 3, p. 255.

von Bezold in his admirable research on atropine, and it is the one usually employed.

There is one fallacy, however, which must not be entirely lost sight of, which is that after division of the vagi the nerves which remain in connection with the respiratory centre have chiefly a slowing action on the respiration; and thus a drug which really renders the respiratory centre more susceptible to reflex influences might seem to have a depressing action upon it.

While atropine injected into the jugular vein seems to produce first a slowing of the respiration, due to its paralysing action on the vagus ends, and afterwards a progressive quickening as more of it is carried out of the lungs into the medulla, physostigmine, muscarine, and veratrine have an opposite action, quickening the respiration at first by their stimulating action on the vagus ends, and afterwards slowing it by their action on the medulla.

In the action of veratrine upon the pulmonary branches of the vagus we may notice a resemblance to the stimulant action which, as already mentioned, it exerts upon the nerves of ordinary sensation. If the sensory branches of the vagus are affected by drugs in a somewhat similar way to those of ordinary sensation, as the action of veratrine might lead us to imagine, we should expect them to be much stimulated also by aconite, and, indeed, according to Boehm and Ewers, this is the case. The respiratory changes produced by aconite are regarded by them as due, in part, to irritation of the peripheral ends of the vagus, and disappear on section of the vagi or the administration of atropine.

Sternutatories or Errhines.

These are drugs which cause **sneezing** and increased secretion from the nose when locally applied to it. The drugs must be in a pulverised condition. The chief are:—

Tobacco (snuff).	Euphorbium.
Veratrum album.	Sassy bark.
Ipecacuanha.	Saponine.

Irritation applied to the nose is transmitted by the nasal branches of the fifth to the **respiratory** centre in the medulla oblongata, and excites the sudden and forcible expiratory movements of sneezing. At the same time, however, the stimulus is transmitted to the vaso motor centre, and the **blood-pressure** becomes considerably increased by the contraction of small vessels throughout the body, even when no sneezing occurs. When sneezing takes place, the pressure is still further increased by the muscular efforts which occur in the act. It is probable that there is not only general rise in blood-pressure but also that local dilatation of the **cerebral** vessels is reflexly produced by the nasal irritation, and thus a **stimulant** effect is produced on the brain. Snuff is there-

fore employed as a luxury giving a feeling of comfort and enabling the snuff-taker to think more clearly—"clearing the head" as it is often termed (*vide* p. 161).

Uses.—Though comparatively little used now, sternutatories were formerly employed in failure of memory, deafness, and severe persistent headache. From the violent expulsive efforts which they induce, they were given also to cause the expulsion of foreign bodies from the air-passages, and to hasten the expulsion of the child in cases of lingering labour where no obstruction was present, but where expulsive force was deficient. They were given also in order to try and check diseases at the commencement, by what was termed "shock to the system."

One curious thing is to be remarked, that stimulation of one part of the respiratory tract may arrest abnormal actions in another. Thus Marshall Hall has shown that actual sneezing may frequently be prevented, after the inspiration by which it is usually preceded has occurred, by forcibly rubbing the end of the nose or by tightly compressing the nostrils. In a similar way irritation of the interior of the nose by snuff will sometimes arrest obstinate hiccough.

Contraindications.—On account of the high blood-pressure which they produce their use is by no means free from danger in persons affected with atheroma or a tendency to pulmonary hæmorrhage or apoplexy, as they may cause rupture of a vessel, and in those who suffer from hernia or from prolapsus of the uterus, they may seriously increase the gravity of these affections.

Pulmonary Sedatives.

These are substances which **lessen** the irritability of the respiratory centre, or nerves connected with it, and thus diminish **cough** and spasmodic difficulty of breathing.

These may be divided into: (1) drugs which tend to **remove** the exciting **irritant** which acts as the cause of cough; (2) those which directly lessen the irritability of the respiratory **centre;** and (3) those which lessen directly the excitability of the afferent **nerves** in the lungs.

Cough consists in a deep inspiration followed by a forcible expiration with closed glottis, so that the air is driven rapidly through the larynx, carrying with it foreign substances, liquid or solid, which may be present in the air passages. As it is a modified respiratory act, the nerve centre by which the muscles employed in it are co-ordinated is situated in the medulla oblongata.

The afferent fibres by which cough may be excited are chiefly branches of the vagus. One of the most powerful is the superior laryngeal nerve distributed to the glosso-epiglottidean folds and to the whole of the interior of the larynx, and this being a special

expiratory nerve we find that irritation of the larynx and also of the trachea is usually characterised by a cough with very violent expulsive efforts. Irritation of the mucous membrane of the trachea



FIG. 56.—Diagram of the afferent nerves by which cough may be excited. These nerves are shown passing to the respiratory centre in the following order from above downwards—from the auditory meatus, pharynx, upper part of œsophagus, larynx and trachea, bronchi, lung, costal pleura, liver, and spleen.

especially at the bifurcation of the bronchi, and irritation of the substance of the lung, also give rise to cough; and irritation of the costal pleura and of the œsophagus does so also.[1] Irritation of the auditory meatus at the point to which the auricular branch of the vagus is distributed will also cause coughing; and cough appears to be also induced by irritation of certain parts of the interior of the nose. These are the surfaces of the inferior and middle turbinated bones, the most sensitive part being the posterior end of the inferior turbinated bone and the portion of the septum immediately opposite.[2] The sudden application of cold to the skin on various parts of the body will sometimes cause coughing. Probably the cough in this case is not due to the stimulus being conveyed directly to the respiratory centre by the cutaneous nerves, but to its causing congestion of the air passages as in Rossbach's experiments. The congestion then causes irritation of the sensory nerves of the bronchi, and occasions cough.

I have seen irritation of the liver and spleen, induced by percussion over them, in a man suffering from chronic enlargement

[1] Kohts, *Virchow's Archiv*, 66, 191.

[2] *On Nasal Cough*, by John N. Mackenzie, M.D., reprint from *The American Journal of the Medical Sciences*, July, 1883.

due to malaria, likewise cause coughing.[1] In addition to those nerves, however, it appears that irritation of the glosso-pharyngeal branches distributed to the **pharynx,** where the digestive and respiratory tracts coincide as they cross one another, may not only excite coughing, but may also act as an auxiliary to irritation of the branches of the vagus. The combined action of the two may thus induce cough, when irritation of the vagus alone would not do so. Thus we find that many persons begin to cough as soon as they lie down, but that sometimes by lying round partially on the face, the cough ceases. In these persons the uvula is often found to be long and much congested, and the tickling which it produces as it rests upon the pharynx or pillars of the fauces seems to aid the irritation in the respiratory passages, and produce cough.

Cough due to irritation of those parts of the respiratory tract where the nerves are chiefly expiratory, as the pharynx, larynx, trachea and large bronchi, is usually, as might be expected, loud, explosive, and prolonged; while cough due to irritation of those parts where the nerves are chiefly inspiratory is short and hacking.

Cough produced by irritation of the pharynx where the respiratory and digestive passages cross one another, is not only violent, noisy, and barking, but, as we would naturally expect, is not unfrequently accompanied by retching or vomiting.

Pharyngeal irritation may accompany dyspepsia, and it is probably the origin of the so-called **stomach-cough.** Irritation of the stomach itself, or of its nerves, causes vomiting, but does not produce cough.

Nevertheless there is a rationale for the common expression "stomach-cough." In some experiments on the reflex origin of cough, R. Meyer,[2] has noticed that when some part, from which cough can be reflexly induced, is already in a state of irritation, cough can be brought on with great ease by irritation of a neighbouring part which would not by itself cause cough. Something of this kind appears to occur with the stomach, for although irritation of the stomach alone will not cause coughing, yet it will do so if irritation of the larynx and trachea are already present. Thus I have observed violent spasms of coughing occur, along with acidity and heartburn, some time after a meal, in a person suffering from congestion of the pharynx, larynx, or trachea. The connection between the cough and the acidity was shown by the cough ceasing as soon as the acidity was relieved by a dose of alkali and the consequent removal of the irritation to the stomach, which the acidity had produced.

Soothing remedies applied to the pharynx greatly relieve cough, although they do not reach so far down as the epiglottis.

[1] These observations were made in January and April, 1879, but not published. Naunyn, in a paper published in the *Deutsch Archiv f. Klin. Med.* in 1880, recorded similar observations.

[2] R. Meyer, *Correspondenzblatt d. Schweizer, Aerzte,* No. 1, 1876.

Mucilaginous remedies are very useful for this purpose, and they may either be employed alone or as vehicles for the local application of sedatives such as morphia. Thus, a piece of extract of liquorice allowed to dissolve in the mouth, a marsh-mallow lozenge, a gum-jujube, or a sip of linseed-tea, by covering the back of the throat with a mucilaginous coating, will lessen cough to a great extent. Such remedies are especially useful where the cough depends on congestion of the pharynx and trachea. In such cases no abnormal sound at all may be heard in auscultation, and the cough being due to irritation of the parts supplied by the superior laryngeal nerve, has a peculiarly convulsive expiratory character often termed "barking."

Other remedies lessen cough by **diminishing congestion** of the respiratory passages, and thus lessening the irritation which causes the cough. Many of these also, however, come under the class of **expectorants** (p. 215), inasmuch as the diminished congestion is frequently associated with increase of the expectoration. Others, again, although they diminish cough, are included rather under the head of **"cardiac tonics,"** or sedatives. Digitalis is an example of this. In the congestion due to cardiac disease, and even in that due to bronchitis, the digitalis, by strengthening the heart and by contracting the vessels, may lessen the congestion in the lungs, and give the patient relief. Squill and a number of other drugs have an action on the blood-vessels similar to that of digitalis.

Other remedies, such as the vapour of hydrocyanic acid, conium, stramonium, and tobacco, have a **local sedative** action on the lung, and may lessen cough; they also are used in order to diminish local spasm of the bronchioles, and thus to relieve spasmodic asthma.

The chief drugs which diminish the excitability of the **respiratory centre** are opium and its principal alkaloid, morphia. Hydrocyanic acid has also a sedative action on it, but is by no means so powerful as the others.

Belladonna and stramonium have a rather peculiar action, stimulating the respiratory centre, and at the same time appearing to lessen the excitability of the ends of the vagi in the lungs. Morphine and opium have a double action in lessening cough: they not only **lessen** the excitablity of the respiratory centre, but they diminish the secretion of mucus in the bronchial tubes, and probably thus also lessen the irritation.

Atropine has but a very slight and uncertain action on the respiratory centre in preventing cough, if indeed it has any at all. It has, however, a powerful effect—much more powerful than that of opium,—in completely **arresting** the **secretion** from the bronchial tubes. The cases in which it is useful are therefore those where the cough depends upon excessive secretion. In cases where the mucous membrane is already too dry, it would be injurious rather than beneficial. When apomorphine and morphine are given together they do not destroy each other's

action, so that from the combination we get increased secretion from the mucous membrane, with diminished irritability of the respiratory centre, and consequently lessened cough. The cases in which this combination, then, is useful, are those where there is difficulty of breathing, continual cough, and thick tenacious mucus. When morphine and atropine are given together, also, they do not destroy each other's action; and thus dryness of the mucous membrane is produced along with diminished irritability of the centre for coughing. This combination is therefore useful in cases of catarrh, emphysema, and phthisis, where there is copious secretion of mucus. In phthisis it is especially indicated on account of the beneficial action of atropine in also lessening sweating. Where the copious expectoration depends upon the presence of a cavity, and not on excessive secretion from the bronchi, it will not be much affected by the use of these remedies.

Expectorants.

Expectorants are remedies which facilitate the **removal** of **secretions** from the **air passages.** The secretion may be rendered more easy of removal, either by an alteration in its character rendering it less adhesive and more easily detached from the air passages, or by increased activity of the expulsive mechanism.

Our knowledge of the use of expectorants is founded chiefly on empiricism. We are almost entirely indebted to the recent experiments of Rossbach for any precise information as to their mode of action.[1]

The secretion from the air passages, like other secretions, depends partly upon the condition of the circulation, and partly on the secreting cells themselves.

In healthy conditions the increased secretion and increased circulation of blood in the mucous membrane go together, but just as in the case of the sweat glands, these two factors may occur independently of each other, and secretion may take place rapidly when the circulation is diminished and the mucous membrane is anæmic, and, on the other hand, it may stop altogether when the vessels are dilated and the mucous membrane is congested. The latter happens both in cases of disease and in animals poisoned by atropine.

The **secretion** from the normal respiratory mucous membrane consists of a thin solution of mucin which dries very slowly, and is only secreted in sufficient quantity to keep the mucous membrane moist. It is slightly adhesive, and any particles of dust, &c., which may have found their way into the trachea, will stick to the walls of the air passages, and will be gradually moved up towards the mouth by the **cilia** with which the cells of the mucous membrane are furnished. Any excess of mucus secreted

[1] *Festschrift der Julius-Maximilian-Universität zu Würzburg*, Leipzig.

in consequence of irritation will also be moved upwards by the cilia in a similar manner. In the ciliated cells of the mucous membrane we recognise a structure which is frequently met with in animals lower down in the scale of existence, and the mucous membrane of the respiratory passages appears to resemble the parts of lower organisms, in being very slightly controlled by the central nervous system. When not irritated it secretes slowly and regularly; when irritated locally the secretion is increased, but irritation of the nerves passing to it, such as the vagus, the superior or inferior laryngeal, or the sympathetic, does not cause any increase as it does in the case of the submaxillary gland. These nerves, however, can influence it indirectly through the circulation, for when they are divided an increased dilatation of the vessels occurs in the mucous membrane of the trachea, a freer circulation of blood occurs, and increased secretion is thus indirectly produced. When they are irritated, however, and anæmia of the trachea produced, the secretion is not arrested but continues.

The **circulation** in the mucous membrane is readily affected reflexly by irritation of other parts of the body. When, for example, a warm poultice is laid for five or ten minutes on the belly of an animal, and then afterwards replaced by ice, the mucous membrane of the trachea and larynx becomes in half a minute deadly pale from contraction of its vessels. Though the ice is still allowed to remain on the belly, the tracheal mucous membrane quickly changes colour, and to the paleness succeeds first slight redness, then deep red congestion, and in five or ten minutes lividity. This lividity shows that the congestion is not arterial but venous, and that the circulation, instead of being quicker, is really slower. Along with the increase of congestion in the mucous membrane, the amount of **mucus** secreted increases. When the ice is removed for half an hour, and again replaced by a warm poultice, the bluish red colour of the mucous membrane almost immediately disappears and gives place to a rosy colour which is, however, redder than normal. Ice again applied will cause a second contraction of the vessels and paleness, though much less than before. These experiments show how sensitive is the mucous membrane of the trachea to reflex stimulation of other parts of the body by heat or cold, and enable us to understand more readily how a draught of cold air on some part of the body should cause inflammation of the respiratory organs.

Action of Drugs on the Secretion.—Alkalies, such as carbonate of soda, injected into the blood, lessen, or in large quantity completely arrest, the secretion of mucus from the trachea.

This experimental result is in contradiction to the teaching of clinical experience, which shows us that alkalies increase the amount of secretion, and render it more fluid. The results of clinical observation are quite as certain as those of Rossbach's

experiments, for we may not only remark the greater quantity of expectoration, and its greater fluidity in persons taking alkalies, but one may note the alteration which they occasion in the amount and nature of the moist *râles* heard within the lungs. This can be observed most readily in persons suffering from phthisis, especially round the margin of a cavity. After catching a slight cold an extension of consolidation may be remarked, in which moist *râles* readily occur on the administration of dilute alkalies. When these are continued until the expectoration has been free for a day or two and the *râles* diminish, acids may be given with advantage so as to dry up the expectoration still more. But if the acid is given too soon the expectoration diminishes, but the cough increases and becomes troublesome to the patient.

In all probability the difference between the results of clinical observation and Rossbach's experiments depends upon the difference of dose, the quantity usually given to a patient being proportionately much smaller than that which he employed. We are able to observe a similar difference between the effects of small and large doses in the case of iodide of potassium; a small dose of a grain and a half, taken by a healthy man three times a day, will almost certainly cause the nose to run freely, while if the dose be increased to ten, twenty, or thirty grains, the excessive secretion will almost certainly be arrested.

The local application of a one to two per cent. solution of sodium carbonate has very little action. The local application of strong liquor ammoniæ causes both congestion and increased secretion of mucus. Very strong solutions cause a croupous exudation from the surface of the mucous membrane. The local application of dilute acetic acid (three per cent. solution) has a similar action to weak solutions of ammonia: the mucous membrane becoming redder and secreting more mucus.

When acetic acid was given internally, Rossbach observed in one case that the mucus which was before watery and clear, became gelatinous and opalescent. This result agrees with what one finds clinically, that acids dry up the secretion and make it harder to expectorate.

Among **astringents** Rossbach tried tannin, alum, and nitrate of silver; the first two when locally applied made the mucous membrane appear paler by altering the epithelium of the mucous membrane and rendering it opaque, so that the vessels underneath could hardly be seen; at the same time they arrested the secretion of mucus almost entirely. A four per cent. solution of nitrate of silver also caused opacity of the epithelium, arrest of secretion, and dryness of the mucous membrane. There appears to be a difference in the action of nitrate of silver on the mucous membrane of the nose and on the trachea, as when the inside of the nose is touched by it, it causes a profuse secretion, whereas it causes dryness in the trachea.

The vapour of oil of turpentine mixed with air arrests the secretion of mucus, while a current of air alone, without admixture with oil of turpentine, will act as an irritant to the mucous membrane and increase secretion. Here again, however, a marked difference is to be seen in the effect of small and large doses, for when a watery solution containing from one to two per cent. of oil of turpentine was dropped directly on the mucous membrane, it became less vascular, but the secretion was at once increased, instead of being diminished as it was by the vapour.

This action of oil of turpentine is of great therapeutical importance, inasmuch as in many cases of bronchitis we have profuse secretion with vascular congestion, a condition likely to be removed by the vapour of oil of turpentine.

Apomorphine, emetine, and pilocarpine, when given internally, all cause a great increase of the secretion of mucus, but they do not alter the vascularity of the mucous membrane. The most powerful of all these is pilocarpine, and after it come apomorphine and emetine. One would therefore expect that pilocarpine would be the best remedy in catarrhal conditions, but this is not the case, for its other actions on the salivary and sweat glands and on the heart render its administration unpleasant for the patient. Sometimes also in children œdema of the lungs has followed its use. Apomorphine, on the contrary, has been found by Rossbach to be of the greatest service in catarrh of the larynx, trachea, and bronchia, both in adults and in children. Ipecacuanha has long been recognised as one of the most useful expectorants, but the dose given is often too small.

Rossbach's experiments have shown that the consequence of sudden changes of heat and cold applied to a part of the body is congestion of the respiratory mucous membrane with **diminished** circulation and stagnation of blood in the veins. A similar condition occurs in many cases of chronic bronchitis, and in them we not unfrequently find great benefit from **vascular tonics** such as digitalis, which, in addition to stimulating the vaso-motor centre, increase the activity of the heart, and thus tend to maintain the pulmonary circulation.

In what way cod-liver oil affects the bronchial mucous membrane it is perhaps hard to say, but there is no doubt whatever that it is one of the most efficient expectorants that we possess, and in cases of chronic bronchitis it affords more relief than any of the ordinary expectorants. It is possible that, being a form of fat which is readily assimilated, it is taken up by the young epithelial cells of the respiratory mucous membrane, and thus enables them to grow and maintain their attachment to the mucous membrane, instead of being at once shed in an undeveloped form as pus cells in the expectoration.

Action of Drugs on the Expulsive Mechanism.—The expectorants which act by increasing the activity of the expulsive apparatus may be divided into—

(1) Those which increase the rapidity of the **ciliary motion** in the tracheal mucous membrane.

(2) Those which increase the activity of the **respiratory centre.**

We have no direct experiments or observations on the rapidity of the ciliary motion in the bronchial mucous membrane of the higher animals, but ammonia has been found to increase its rapidity in the mucous membrane of the frog.

The remedies which increase the activity of the respiratory centre are : strychnine, ammonia, emetine, ipecacuanha, belladonna, atropine, senega, and saponine. They are used more especially in cases of bronchitis where the expectoration is imperfect.

The chief expectorants have been divided into depressant and stimulant. They are as follows :—

Depressant Expectorants.	Stimulating Expectorants.
Increasing secretion and generally tending to lessen blood-pressure.	Generally increasing blood-pressure and diminishing secretion.
Antimonial preparations.	Acids.
Tartar emetic.	Ammonium chloride.
Alkalies.	Ammonia.
Ipecacuanha.	Strychnine.
Emetine.	Nux vomica.
Lobelia.	Senega (saponine).
Lobeline.	Onion.
Jaborandi.	Garlic.
Pilocarpine.	Squill.
Apomorphine.	Tar.
Quebracho.	Benzoin.
Aspidospermine.	Benzoic acid.
Potassium iodide.	Balsam of Tolu.
	Balsam of Peru.
	Wood tar.
	Turpentine.
	Oleum Pini Sylvestris.
	Oleum Pini Pumilionis.
	Sulphur.
	Saccharine substances.
	Liquorice.

Adjuncts.—One of the most powerful adjuncts to expectorants is an **emetic,** which frequently will clear the lungs and save life in cases of chronic bronchitis with impending suffocation, when ordinary expectorants have completely failed.

One of the emetics most commonly employed in such cases is ipecacuanha either alone or combined with squill, *e.g.* half a fluid ounce each of ipecacuanha wine and oxymel of squills. When there is great depression, however, and the circulation is very feeble, carbonate of ammonia is to be preferred.

Another powerful adjunct is **warmth** and **moisture** in the room in which the patient is living, and this is best secured by means of steam brought well into the room from a kettle placed upon the hob. The kettle used should either be furnished with a very long spout, as in the case of the ordinary **bronchitis kettle,** or a long tube made of a piece of stout brown paper tied around with a string may be used to convey steam into the room from the nozzle of an ordinary kettle.

Respirators are also serviceable, by preventing the entrance of cold air into the trachea. Many persons, forgetting that the mouth is part of the digestive tract, and that the nose is the proper entrance to the respiratory tract, breathe through their mouth ; the consequence is, that the cold air passes down the trachea without being previously warmed. In the nose we have a special arrangement for warming the air. The turbinated bones present an enormous warming surface, like some recently-invented stoves, and moreover, a special arrangement is made for allowing a free flow of blood through this mucous membrane by its being loosely instead of firmly attached to the turbinated bones. Its vessels are therefore capable of great and rapid distension, so as to allow the air to be readily warmed in cold weather.

Most respirators are made simply to go over the mouth, and their advantage is that they force people to breathe through their nose, or warm the air if they cannot do so, and continue to breathe through the mouth. In many persons the same end may be gained by forcing them to wear an invisible respirator. An instrument is sold bearing this name, consisting of a thin plate of metal; but what is perhaps quite as good, or better, is a sovereign or half sovereign placed between the lips and teeth. Patients are thus forced to keep the mouth shut in order to prevent it from falling out, and its value makes them careful about losing it.

It is often forgotten too that passages and disused rooms are nearly as cold as the external air, and many delicate people who would never dream of going outside in cold weather will, without thinking, walk through cold passages and in rooms without fires. **Warm clothing,** especially over the shoulders, neck, and chest is very useful, and its utility is recognised by the common employment of so-called chest protectors made of chamois leather and red flannel.

Other adjuncts are **friction** to the chest with stimulating **liniments ;** mustard leaves, warm **poultices** and the application of **plasters ;** the emplastrum calefaciens (B.P.) or emplastrum picis cum cantharide (U.S.P.) is especially useful in chronic bronchitis.

CHAPTER XI.

ACTION OF DRUGS ON THE CIRCULATION.

It has already been mentioned that the cells of which higher organisms are composed live in the intercellular fluid or lymph which bathes them.

This nutritive fluid is continually being renewed by fresh supplies exuding from the blood-vessels into the lymph spaces which surround the cells, the excess being removed by absorption either by the veins or by the lymphatics. Besides this, an interchange of gases (internal respiration) and of solids takes place by diffusion between the lymph and the blood.

When the circulation stops, internal respiration is arrested, and the cells die. But they do not all die at the same time, for some are able to live longer without fresh supplies of oxygen than others. The order in which they die is (1) the cells of the initiative nerve-centres, as the brain; (2) those of the automatic and reflex centres; (3) nerve fibres (which are modified nerve-cells); (4) unstriated muscles; (5) striated muscles.

Arteries and Veins.—It is important in this respect to remember that it is only so long as blood is in the arteries that it is available for the nutrition of cells. Once in the veins it is useless for nutrition; and were it not that it readily passes from the veins into the arteries again, it might as well be outside the body for any purposes of nutrition.

The veins are very capacious, and when dilated to their utmost, they can alone hold all the blood the body contains, and more. During life they are constantly kept more or less in a state of contraction by the action of the nervous system, but when they become completely dilated, as after death, all the blood flows into them, leaving the arteries empty. It is therefore possible, as Ludwig has well expressed it, to bleed an animal into its own veins. Schiff has shown that when the blood-vessels relax as they do after section of the medulla oblongata, the whole of the blood of another animal as large as the one experimented upon must be

introduced in addition to its own, in order to raise the pressure within the vessels to the normal. Even this is insufficient to keep up the pressure, for the vessels go on still dilating, and the pressure falls, notwithstanding the large quantity of blood which is present in them. It is therefore evident that the normal action of the **vaso-motor centres** is more than equivalent, for the purposes of circulation, to as much blood again as the animal possesses. Weakened power of these centres is to a certain extent equivalent to bleeding, and increased power has a similar effect to an increase in the quantity of blood in the vessels.

Blood-Pressure.—The continuity of the circulation of blood through the capillaries is not maintained by the heart alone: the elastic pressure of the arteries on the blood within them plays a most important part, and indeed during the cardiac diastole the circulation is maintained entirely by this elastic pressure.

If the arterioles or capillaries through which the arterial system empties itself into the veins are much contracted, so that the blood can flow only slowly through them, the heart may stop, and yet the blood-pressure may remain for many seconds almost unchanged. But if the arterioles or capillaries are dilated, the arteries quickly empty themselves into the veins, arterial pressure rapidly falls, and circulation soon stops.

I use the words arterioles and capillaries as synonymous, because it is almost certain that the capillaries do contract. In most cases where contraction has occurred in the peripheral vessels, it is difficult or impossible to say whether its seat is in the capillaries or arterioles.



FIG. 57.—Diagram to illustrate the effects of the horizontal and vertical position on the circulation of the frog in shock. *a*, normal circulation in the upright position. *b*, circulation after dilatation of the veins has been produced by a blow on the intestines. The blood does not reach the heart, and it beats empty, so that the circulation stops. *c* shows the circulation in a horizontal position after the veins have been dilated, as in *b*. The veins are still dilated, but the blood reaches the heart, and the circulation is carried on. Fig. *c* is perhaps too diagrammatic, as it appears to show an empty space or air in the veins. In reality the veins, being very thin-walled, collapse. Fig. *b* is open to the same objection, but if we suppose ourselves to be looking at the vein from the front instead of in section, *b* represents almost exactly what I have myself seen in repeating Goltz's experiment.

The action of the heart is to pump the blood out of the veins into the arteries, and this it can only do when the blood reaches it. If the veins are much dilated and the animal is in an upright position, no blood, or so little blood may reach the heart, that its pulsations are practically useless. This is seen in the frog when dilatation of the large veins has been reflexly produced by striking the intestines (Fig. 57). When the animal is laid flat, the blood flows into the heart, and then it works normally. It is probable that a similar condition occurs in man, as one of the factors in

shock, and in this condition, as well as in fainting, or failure of the heart's action from the effect of drugs, as chloroform, or other causes, the person should be laid flat, with the limbs raised so that the blood may flow out of them into the heart, and with the head low (either perfectly level with the body or depressed below it), in order to permit of an increased supply of blood to the inter-cranial nerve-centres.

Fainting and Shock.—In **fainting** there is sudden unconsciousness, which appears to be caused by sudden arrest of the supply of blood to the brain. This arrest may be due to a rapid fall in blood-pressure, either from stoppage of the heart, rapid dilatation of the arterioles, or sudden removal of pressure from the larger vessels. It is possible that these conditions may be associated with spasmodic contraction not only of the vessels of the face and surface generally, but of those supplying the brain itself. The effect of sudden change from horizontal to an upright posture in producing syncope has already been mentioned, p. 173. Sudden removal of external pressure from the great vessels acts upon both arteries and veins. It removes external support from the arteries, and allows them to yield more readily to the influence of the blood-pressure, and by their dilatation to lessen it. It allows the large veins also to dilate and blood to stagnate in them. Its influence is readily seen when fluid is removed too suddenly from the abdomen, and external pressure by a bandage not supplied in its place, as in cases of ascites.

It is seen, perhaps, even more strikingly, where the bladder has been allowed to become distended and is suddenly emptied. The effect of this is shown in Fig. 58. In *a* the bladder is represented



FIG. 58.—Diagram to show the effects on the cerebral circulation of rapidly emptying the bladder.

as full, and, the pressure within the abdomen being considerable, the veins are prevented from dilating, the heart is well supplied with blood, and the circulation in the brain is active. In *b*, the bladder is represented as empty, and the abdominal contents being diminished, so that the intra-abdominal pressure is lessened, not only do

the aorta and other vessels become lax from loss of the external pressure but the veins dilate, the heart is imperfectly supplied with blood, the cerebral circulation fails, and syncope ensues. This occurs more readily just after waking, before the vaso-motor centre has recovered its usual tone, so that one of the most favourable conditions for its occurrence is when a man jumps suddenly into the upright position and empties his bladder immediately on waking. The consequence of this sometimes is that he falls down suddenly, quite insensible, during the act of micturition. I have seen one case in which the tendency appeared to be increased by the practice of opium-eating, probably from the diminished excitability of the vaso-motor centre produced by the drug. It is evident that the danger will be increased if the intervals between the systoles of the heart are prolonged, and it is the combination of the natural tendency to syncope, produced by large doses of digitalis, with that caused by the sudden assumption of the upright posture, and by the rapid emptying of the bladder, which renders micturition in the upright posture so excessively dangerous in persons under the action of digitalis, and leads so frequently to death.

It is evident that fainting may be prevented by increasing the blood-pressure in the brain locally, or throughout the body generally. To increase it locally the head of a fainting person should be allowed to lie level with the body, or a little below it, and on no account raised even by pillows. A fainting fit may indeed often be prevented by sitting with the head hanging between the knees. It may also be prevented or removed by such conditions as raise the general blood-pressure, *e.g.* a draught of cold water, which causes contraction of the gastric vessels, or a sniff of ammonia or acetic acid, which stimulates the nasal nerves, and causes reflex contraction of the vessels generally. In some parts of India the natives are accustomed to bring persons round from a faint by compressing the nostrils and holding the hand over the mouth, so as completely to stop respiration. The accumulation of carbonic acid in the blood irritates the vaso-motor centre, raises the blood-pressure, and thus probably tends to bring the person round.

In **shock** there is no unconsciousness, but the failure of the circulation is even more profound than in syncope. Its pathology is not perhaps exactly ascertained, but it probably depends to a great extent on a paralytic distension of the great veins, as in Goltz's experiments. I have found that in shock produced in a similar manner in a rabbit the blood-pressure could be raised from two inches up to two and a half by the inhalation of ammonia.

Schema of the Circulation.—In order to understand the action of drugs on the circulation it is absolutely necessary to have a clear idea regarding the effect of the heart and capillaries in maintaining the blood-pressure. This is best obtained by using a schema which can be easily made from a spray-apparatus. By removing the glass or metal tube from one of these, and

attaching a nozzle with a small stopcock to the India-rubber tube in its stead, we obtain a very good schema of the circulation ; and, by imitating on it the changes which occur in the heart and vessels, we may form a much clearer idea of them than we could otherwise do. The India-rubber ball will represent the heart ; the elastic bag, surrounded by netting, will represent the elastic aorta and larger arteries ; and the stopcock, which regulates the size of the aperture through which the air escapes, will represent the small arteries and capillaries, whose contraction or dilatation regulates the flow of blood from the arteries into the veins. We may judge of the tension in the arteries by the distension of the bag, or still better, we may connect the tube between it and the stopcock with a mercurial manometer, and estimate the tension by the height of the mercurial column which it sustains. If we turn the stopcock



FIG. 59.—Simple schema of the circulation, consisting of a spray-producer, bladder, and mercurial manometer. The elastic ball represents the heart, the elastic bag covered with netting to prevent too great distension represents the aorta and arterial system, and the bladder represents the venous system.

so as to present some resistance to the escape of air, and then compress the India-rubber ball, very little air will issue from the stopcock even while we are squeezing the ball ; the greater part of it goes to distend the bag ; and, when we cease to compress the ball, very little air passes through the stopcock. At the next squeeze, the bag becomes a little more distended ; and a little more air passes through the stopcock, not only while we are compressing the ball, but even when we relax our grasp. At each squeeze of the ball, the elastic bag becomes tighter, till it is so tense, and contracts so strongly on the air inside, that it can press all the extra amount of air, forced into it when the ball was compressed, through the stopcock during the time when the ball is relaxed. When this is the case, every time we squeeze the ball we see the bag become a little fuller, and air issue more quickly from the nozzle. At each relaxation, while the ball is refilling, the bag gets a little slacker, and the air passes out of the nozzle a little more slowly, but never stops entirely. During the time the ball is filling, the valves between it and the bag and nozzle are closed, and cut it off from any connection with them. All this time, then, the stream of air from the nozzle must be entirely independent of the ball; it is produced by the contraction of the elastic bag, and by it alone. The bag may be stretched, and the tension of its walls increased in consequence, in two ways : first, by working the ball more quickly or compressing it more completely ; second, by lessening the opening of the nozzle, and thus hindering the passage of air through it. One trial will, I think, be enough to show how much easier it is to alter the pressure by changing the size of the nozzle than by any alteration in the working of the ball, and to prove that alterations in blood-pressure probably

depend much more on alterations in the lumen of the small arteries than on changes in the action of the heart.

But our schema, as it at present exists, is not a perfect representation of the heart and vessels; for it draws its air from an inexhaustible reservoir, the atmosphere, and is not obliged each time to use that amount alone which it had previously driven through the nozzle; while the heart can only use the blood which has been forced by it through the capillaries and returned to it by the veins. In order to make our schema complete, we must connect its two ends by tying them into a bladder or large thin caoutchouc bag (such as is used, after inflation, as a toy for children), so that the air shall pass into it from the nozzle and be sucked out of it by the elastic ball. This will represent the veins. If we then repeat the experiment just described, we shall find that, when we begin to work the ball and stretch the elastic bag representing the arteries, the bladder representing the veins, becomes empty and collapsed; and just in proportion as we fill the bag do we empty the bladder. If we now stop, the air will gradually escape from the bag to the bladder, till the air in both is of equal tension as at first.

Circulation in the Living Body.—The phenomena of the circulation in the heart and vessels are very much the same as in the schema. When the heart stands still (as when the vagus is strongly galvanised), the blood flows from the arteries into the veins until the arteries are nearly empty and the pressure within them falls to zero. If the heart now begin to beat, it forces blood into the elastic aorta and arteries at each systole, and distends them, just like the elastic bag of the schema; while at the same time it takes blood from the veins, and they become empty in proportion as the arteries become full. During every diastole of the heart, the distended aorta and other arteries, in virtue of their elasticity, contract on the blood they contain, and keep it flowing on through the capillaries till another systole occurs; the heart, meanwhile, being completely shut off from the aorta by the sigmoid valves (just as the ball of the schema was shut off from the elastic bag). In general, the diastole is longer than the systole; so that for the greater part the circulation through the capillaries is carried on by the elasticity of the arteries, and not directly by the heart. The arteries, which we have supposed to be at first empty, gradually become distended by the heart, just as the elastic bag was by the ball, and exert more and more pressure on the blood in them (so that it would spout higher and higher, if one of them were cut), till they are able during the diastole to press the same amount of blood through the capillaries into the veins as had been pumped into them during the systole. The more tensely they are stretched, the greater is the pressure they exert on the blood they contain; and the amount of this is termed the **arterial tension** or **blood-pressure.** These two terms mean the same thing, and we use one or other just as the fancy strikes us. At each systole, the fresh supply of blood pumped in by the heart stretches them more; that is, the arterial tension rises. During each diastole, the blood escapes into the wide and dilatable veins, and the arteries become

less stretched; that is, the arterial tension falls. This alternation of rise and fall constitutes the **pulse.**

Besides the **oscillations** which take place in the blood-pressure at each beat of the **heart,** a rise and fall in the form of a long wave occurs at each **respiration.** The wave begins to rise just after inspiration has begun, reaches its maximum just after the beginning of expiration, and then begins to fall again till a new wave succeeds it. The heart-beats are generally quicker during inspiration, and slower during expiration.

The blood-pressure thus oscillates up and down at each heart-beat and rises and falls with each respiration, and the average between the highest and lowest points is called the mean arterial tension or **mean blood-pressure.**

Besides the oscillations in blood-pressure due to the pulse and to the respiration, there are slowly rising and falling waves to which the name of **Traube's curves** is given. These are due to alternate contraction and relaxation of the arterioles and capillaries. Rhythmical contraction of the arterioles has been observed in almost all parts of the body of rabbits, and probably occurs both in the lower animals and in man.

The blood-pressure is not equal throughout the whole arterial system. It is greater in the large and less in the smaller arteries in which it becomes diminished by the friction between the blood and the arterial walls. It is also modified by gravity, so that the position of a limb may alter the pressure in its arteries.

Method of ascertaining the Blood-Pressure.

The blood-pressure is usually estimated in animals by connecting a large artery, such as the carotid or femoral, with a bent tube containing mercury by means of a connecting tube, which is filled with a solution of carbonate of soda to prevent coagulation. The pressure is estimated by the height at which the mercury stands in the outer limb of the tube. The height may either be read off with the eye, or, what is much better, it may be registered on a revolving cylinder by means of a long float which rests upon the surface of the mercury, and bears on its upper end a brush or pen. This method, which is important both in itself and as being the introduction of the graphic method into physiology, we owe to C. Ludwig. The apparatus is known as the **kymograph.**

Tracings may be taken upon paper with a varying speed: it is usual to take them upon paper travelling rapidly, so that quick and small oscillations due to the cardiac beats may not be lost or obscured by fusion. The great disadvantage of this is that it is impossible to use the curves directly: they must be reduced, and this is a work requiring much time and labour. When taken on a slowly revolving cylinder we get the general results of the action of a drug on the blood-pressure shown us at a glance; and its effects on the form and rapidity of the pulse may by a little arrangement be recorded from time to time on another cylinder revolving more rapidly.

This method gives us both the blood-pressure and the oscillations which it undergoes on account of the cardiac pulsations and respiration. If we wish to get the mean blood-pressure unaffected by these oscillations, it is done by simply narrowing at one point the calibre of the tube containing the mercury, either by a stopcock, or by reducing the tube to a capillary bore.

Fallacies of Mercurial Manometers.—The oscillating mercurial column does not give the variations in blood-pressure quite truly, because the oscillations are compounded of these variations and of the oscillations due to the inertia of the mercury itself. In order to obtain the exact form of variation we employ Fick's kymograph, or Roy's tonometer, in which the apparatus is made very light, and all oscillations due to its own inertia are as far as possible avoided.


Writing-point
Piston to lessen oscillation of point
Tube filled with glycerine
Syringe for altering the pressure in the manometer.
Flat metal tube forming the manometer.
Tube to connect the manometer and artery.

FIG. 60.—Fick's kymograph. It consists of a flat metal tube, bent into a nearly circular form, filled with alcohol, and connected with the artery by means of a leaden tube, filled with a solution of sodium carbonate. When the pressure increases within it, the tube straightens, and when the pressure diminishes it bends. These changes are magnified and recorded on a cylinder by a light lever. The vibrations of the lever are lessened by a piston, which works in a tube filled with glycerine.

Fallacies from Anæsthetics.—Even if the instrument be free from fallacy, we still have difficulty in ascertaining the real action of the drug on the circulation, inasmuch as the blood-pressure is much affected by movements, and by anæsthetics. If the animal is not anæsthetised we may get untrustworthy results from the straining or movements it may make, and if it is anæsthetised, the anæsthetic may greatly alter the power of the heart, or the sensibility of the nerve centres, either to the direct action of the drugs upon them, or to its reflex action through the afferent nerves. In order to get rid of movement, and at the same time to prevent the vascular centres from being much depressed, curare is sometimes used instead of an anæsthetic. Perhaps, almost equally good results may be obtained by using ether as the anæsthetic, carefully regulating the supply so as to abolish sensation without greatly affecting the medulla. The reasons why this is possible are discussed at p. 171. In order to regulate the supply of ether, we use a stopcock, by which pure ether, or pure air, or an admixture of both in any desired proportion, can be passed into the lungs, Fig. 48, p. 178.

Other fallacies arise from the mode of injecting the drug, and this has sometimes led to false results: thus drugs are not unfrequently injected into the jugular vein, as it is very conveniently situated for the purpose. In this way, however, they are carried directly to the heart, and act much more strongly upon it, than they would do if absorbed from other parts of the body. In the case of irritant salts, for example, time is not afforded for their irritant properties becoming lessened by chemical combination with the constituents of the blood. If the solution injected contain particles which will

not pass through the pulmonary capillaries, or if it is likely to cause coagulation of the blood, it may plug up the pulmonary vessels and give rise to dyspnœa and convulsions.

Both these objections are avoided when the drug is injected under the skin, or into the peritoneal cavity. Absorption from the skin is slower than from the peritoneum. In some experiments this is a disadvantage: in others, however, it is an advantage.

Another fallacy sometimes arises from the solution of carbonate of soda used to prevent coagulation. In order to prevent the blood from passing too far into the tube connecting the artery with the kymograph, it is usual to introduce the solution of carbonate of soda into the tube by a syringe (*vide* Fig. 60) or otherwise, under a pressure very little less than the usual blood-pressure of the animal experimented on. If the blood-pressure be lowered much by stoppage of the heart or dilatation of the vessels, the solution of carbonate, or bicarbonate of soda, runs into the arteries, and may cause convulsions and death. Thus stoppage of the heart by irritation of the vagus, or by the action of a drug, may sometimes appear to be followed by results which are not really due to it, but only to the conditions under which the experiment has been made.

Alterations in Blood-Pressure.

In speaking of blood-pressure, arterial blood-pressure is always meant, unless otherwise stated.

As the blood-pressure depends on the difference between the quantity pumped into the arterial system by the heart at one end, and the quantity flowing out through the arterioles into the veins at the other in a given time, it is evident that—

The **blood-pressure** will remain **constant** when these quantities remain equal to each other.

It will **rise** when—

(*a*). More blood is pumped in by the heart.

(*b*). When less flows out through the arterioles in a given time.

It will **fall**—

(*a*). When less is pumped in by the heart, or:

(*b*). More flows out through the arterioles; or to look at it another way:—

Heart	more active.	Blood-pressure	rises.
	less „	„	falls.
Arterioles	contract	„	rises.
	dilate	„	falls.

The heart may throw more blood into the arteries, either by pulsating more rapidly, or by pulsating more vigorously and more completely, so that at each contraction a larger amount of blood is expelled. But increased activity can only affect the blood-pressure so long as there is a free supply of blood entering the heart. If there exist any obstruction to its entrance the increased cardiac action will have no effect. Hence obstruction of the pulmonary circulation will also lower the blood-pressure.

The causes of alteration in the blood-pressure may be tabulated as follows :—

Blood-Pressure.

May be raised—	May be lowered—
1. By the heart beating more quickly.	1. By the heart beating more slowly.
2. By the heart beating more vigorously and more completely, and sending more blood into the aorta at each beat.	2. By the heart beating less vigorously and completely, and sending less blood into the aorta at each beat.
3. By contraction of the arterioles, retaining the blood in the arterial system.	3. By dilatation of the arterioles, allowing the blood to flow more quickly into the veins.
	4. By deficient supply of blood to the left ventricle, as from contraction of the pulmonary vessels, or obstruction to the passage of blood through them, or from stagnation of blood in the large veins, *e.g.* in shock.

The influences on the pressure exerted by (*a*) the number of beats, and (*b*) by the amount of blood sent out by the heart at each beat, to a certain extent, though by no means completely, counteract each other; for, when the heart is beating quickly, it has not time to fill completely, and so sends out little blood at each beat; but, when beating slowly, it becomes quite full during each diastole, and sends out a larger quantity of blood at each contraction.

It is evident that the amount of blood which the heart can send into the arteries at each beat will depend also upon the completeness with which the ventricle relaxes during diastole. If the relaxation be incomplete very little blood will enter the ventricle, and thus a drug which increases the contractile power of the heart may, by unnecessarily prolonging the systole, lower the blood-pressure as much as a drug which paralyses the heart and prevents the ventricle from expelling its contents.

Relation of Pulse-Rate and Arterioles to Blood-Pressure.

Although we are unable, from the mere fact that the blood-pressure rises or falls after the administration of a drug, to say whether the result is due to the action of the drug on the heart or on the arterioles, yet we can come to some general conclusion regarding its mode of action by comparing the alterations which it has produced in the blood-pressure with those which occur in the pulse-rate. For in the normal condition of an animal, when all the nerves are intact, a rise in the blood-pressure renders the

pulse slow by increasing the normal tone of the vagus centre in the medulla, and a fall of blood-pressure quickens the pulse by diminishing the tone. This mechanism tends in the normal animal to keep the blood-pressure more or less constant.

We find, therefore, that when alterations in blood-pressure and pulse-rate are depicted graphically, so that a rise in one curve indicates a rise in blood-pressure, and a rise in the other indicates quickening of the pulse, the two **curves** run in **opposite** directions if the alteration in blood-pressure is due to the **arterioles,** but they run **parallel** when the alteration is due to the **heart.** Thus, if the vagi be cut, we find that the pulse-rate rises, and in consequence of this the blood-pressure also rises. Here the alteration in



FIG. 61.—Diagram of a pulse and blood-pressure curve, where the alterations are due at first to the action of a drug on the heart, as in the case of atropine. The unbroken line indicates the blood-pressure, and the dotted line the pulse. After the injection shown by the vertical line the vagus is paralysed, the pulse becomes very rapid, and the blood-pressure rises. At A the vaso-motor centre becomes paralysed, the arterioles dilate, and the pressure falls. From *a* to *b* the action of the heart continues nearly uniform, notwithstanding the fall in blood-pressure, but at *b* the heart begins to become paralysed, and the pulse-rate and blood-pressure both continue to fall steadily till death.

pressure is due to the heart, and the two curves are therefore parallel. If the vagi be irritated the pulse-rate falls, and in consequence of this the blood-pressure also falls. Here again the alteration is due to the heart, and the two curves are parallel.

If, on the other hand, the arterioles are made to contract the pressure rises, but the increased pressure stimulates the vagus roots in the medulla and the pulse-rate falls, so that the curves run in



FIG. 62.—Diagram of pulse and blood-pressure curves, where the alterations are due at first to the action of a drug on the arterioles. The unbroken line indicates the blood-pressure, the dotted line indicates the pulse. The upright line indicates the time of injection of the poison. This is followed by contraction of the arterioles and consequent rise of blood-pressure. This rise stimulates the vagus roots, and causes slowness of the pulse. At *b* the vagus becomes paralysed, the pulse becomes quick, and the pressure rises still higher between A and B. At B the vaso-motor centre becomes paralysed, the arterioles dilate, and the pressure falls, notwithstanding the rapidity of the pulse. At *c* the heart itself begins to be paralysed, its beats become slow, and both pulse and pressure fall steadily till death.

opposite directions. If the arterioles dilate the pressure falls, and the vagus tone being lessened the pulse-rate rises; so the curves are again in opposite directions.

An example of this is seen in the accompanying curve (Fig. 63), which illustrates the action of erythrophlœum—a substance similar in action to digitalis—on the circulation. After the injection of the drug the vessels contract, and the blood-pressure consequently rises and produces some slowness of the pulse. In a little while the vagus becomes paralysed, the pulse becomes quicker, and the pressure rises still further. At a later stage the heart becomes slow, apparently from the action of the drug upon it, and the



FIG. 63.—Curve of the pulse and blood-pressure in a cat after division of the spinal cord at the atlas and injection of erythrophlœum. From a paper by Brunton and Pye, *Phil. Trans.* vol 167.

blood-pressure then falls again. At first then, where the alteration of pressure depends upon the state of the vessels, we have the two curves running in opposite directions, but when the alterations depend upon the condition of the heart we have them running parallel.[1] It will be noticed that in the latter part of the curve, although the blood-pressure and the pulse sink together, they do not sink quite parallel; the pulse falling very rapidly and the

[1] Although the rise in blood-pressure which accompanies that of the pulse is partly due to the heart, it is very probable that the contraction of the arterioles which caused the rise at first is not only continuing but increasing.

blood-pressure very slowly. From this fact we may conclude that the arterioles are still contracted, and this affords an illustration of another way in which we judge of the effect of drugs upon the arterioles. This conclusion would not be warranted by the data contained in Fig. 63 alone. For the slow fall of blood-pressure in this experiment might possibly be due to the heart beating more perfectly, at the same time that it begins to beat more slowly. An examination of the original tracings of the blood-pressure shows that this is not the case and that the beats of the heart became feeble at the same time that they became slow.

The mutual regulating power of the pulse and blood-pressure only exists when the vagi are working normally. If they should be paralysed either by section or by the action of a drug, increased arterial pressure will no longer slow the pulse; it may even quicken it, and therefore the pulse-rate and blood-pressure may, in such a condition, run parallel even though the increased pressure should be dependent upon alterations in the arterioles.

But if the vagi are not paralysed, and we find on comparing the curves of blood-pressure and pulse-rate that they run parallel, a fall in the blood-pressure and slowness of pulse occurring together, or a rise in pressure and quickness of pulse accompanying each other, we may conclude that the alterations in such a case are due to changes in the action of the heart.

If, however, we find that the curves run in opposite directions, the pressure rising and the pulse falling, it is highly probable that the rise is due to contraction of the arterioles, and that the fall of the pulse is caused by the rise of pressure acting as a stimulus to the vagus roots. This is, however, not quite certain, as it might be due to the action of the drug upon the vagus, and the proper method of ascertaining this would be that employed by Ludwig, of allowing a quantity of blood to flow out into a bladder connected with a blood-vessel, so that the pressure should fall. If the pulse still continued slow in spite of the fall of pressure, it would be evident that the slowness was due to the action of the drug upon the vagus and not to indirect action through the blood-pressure. By employing a bladder in this manner the blood can be quickly introduced again into the vessels after the effect of its withdrawal has been ascertained.

We not unfrequently find that owing to the action of a drug the pulse, which has become slow during the rise of the blood-pressure, suddenly becomes very rapid notwithstanding that the pressure continues high. This is usually due to **paralysis** of the **vagus-ends** in the heart, and, when this occurs, the correctness of the conclusion which we draw from the occurrence may be ascertained by stimulating the vagus in the neck by a faradaic current, and seeing whether any slowing or stoppage of the heart occurs. Frequently we find that after the pulse has become

quick from paralysis of the vagus, the pressure which the quick pulse had raised begins to fall again from paralysis of the arterioles. The pulse may continue quick and weak almost till death and then cease suddenly, or it may become gradually slow as well as weak from paralysis of the heart itself.

Effect of the Arterioles on Pulse Curves.—The influence of the arterioles upon the blood-pressure in a living animal can be to a great extent ascertained from the rapidity or slowness of the fall of the blood-pressure during the diastole of the heart. When the heart is beating slowly the diastole may be long enough to show distinctly the curve which the blood-pressure describes during its descent; but if the heart is beating quickly the diastole may be so short that this curve cannot be exactly obtained. It is then necessary to prolong the diastole artificially by stimulation of the vagi.

The reason why the part which the arterioles play in maintaining the blood-pressure can be ascertained by the way in which it falls during cardiac diastole, natural or artificial, is that in the healthy heart the aortic valves close during the diastole so as to separate the aorta completely from the ventricle.

In considering the blood-pressure during the diastole, we may therefore disregard the heart entirely, and look upon the aorta and its branches as an elongated elastic bag closed at its cardiac end, but open at its capillary end. This bag is distended with blood, which in consequence of the elastic pressure exerted upon it by the arterial walls tends to flow out into the veins. The **rate** at which it does this will depend,

1st, on the elastic pressure or arterial tension, and,

2ndly, on the size or degree of contraction of the arterioles or capillaries.

If we connect a manometer with this elongated bag as in Fig. 64, and place on the mercurial column a float by which its



FIG 64.—Diagram of the circulation. *a*, the heart, completely shut off by the valves during diastole from *b*, the arteries. *c*, the capillaries. *d*, the veins. *e*, mercurial manometer. *f*, a float. *g*, a recording cylinder.

height can be recorded on a revolving cylinder, it is evident that the pressure curve will fall more quickly to zero when the capillaries are dilated, and more slowly when they are contracted.

With capillaries of the same size, the rate of flow will vary with the arterial pressure. If the pressure be high the curve will fall

more rapidly than when it is low, for the greater blood-pressure will drive the blood more rapidly through the open arterioles. If we find that with a normal pressure the pressure curve falls more slowly than usual during the diastole, we may conclude that the arterioles are contracted; and if we find that the fall is slower, notwithstanding that the pressure is higher than usual, the proof that the arterioles are contracted is so much the stronger.

This is what Meyer and I[1] observed in the case of digitalis, where we found as in the accompanying figure that the fall of the blood-pressure during the cardiac diastole in a dog is much slower after, than before the injection of digitalis into the circulation.



FIG. 65.—Tracing showing the blood-pressure and form of the pulse-wave before and after the injection of digitalis in the dog. The thin line shows the blood-pressure before, and the thick one after, the injection. The curve sinks more slowly after the injection, notwithstanding the greater pressure in the vessels.

In observations of this sort it must always be borne in mind that a great difference exists between the vessels of the intestines on the one hand, and those of the muscles on the other. The former are readily controlled by the vaso-motor centre, and when this is stimulated they contract greatly. Those of the muscles appear to be but slightly influenced by the vaso-motor centre, so that when it is stimulated they hardly contract at all, and indeed the flow of blood through them becomes accelerated on account of the contraction of the vessels elsewhere. When the vaso-motor centre is stimulated at the same time that the vagus is irritated, the blood-pressure appears to fall nearly as quickly as when the vagus alone is irritated. It seems possible, however, that this result may be really due to some extent to actual dilatation of the vessels in the muscles, for stimulation of the motor nerves of muscle appears to produce a vaso-dilating effect on their blood-vessels (Gaskell and others).

The want of power of the vaso-motor centre over the vessels of the muscles is probably of considerable pathological importance. John Hunter[2] noticed, when he was bleeding a lady from a vein in the arm, that the blood, which previously had been dark

[1] Brunton and Meyer, *Journal of Anatomy and Physiology*, vol. vii. 1872, p. 134. The experiments described in the paper were performed in 1868.

[2] John Hunter's works, edited by Palmer, 1837, vol. iii. p. 91.

and venous, became bright scarlet like arterial blood when she fainted, and remained so during the continuance of the faint. This seems to indicate that during syncope, although the superficial vessels are empty and contracted, the arterioles of the muscles are dilated like those of an actively secreting salivary gland.

If we find then that after the injection of a drug the blood-pressure remains constantly high, during stoppage of the heart, we may conclude that the vessels of the muscles are contracted as well as those of the intestine. Such a condition occurs after the injection both of digitalin and of erythrophlœum, in which the pressure sometimes remains high for many seconds, or even for a minute or more, after the heart has finally ceased to beat (Fig. 63).

Investigation of the Action of Drugs on the Arterioles.

The arterioles become contracted by the action of the involuntary muscular fibre contained in their walls; they dilate partly by their own elasticity and partly by the pressure of fluid within them.

The capillaries also appear to have the power of contraction. Both arterioles and capillaries are induced to contract by the effect upon them of the nerves which pass to them from vaso-motor centres. The blood-vessels may also dilate actively from irritation of vaso-inhibitory nerves. The exact mode of action of these nerves is not ascertained; they are generally looked upon as entirely separate from vaso-motor, but it seems not improbable that here also the difference between vaso-motor and vaso-inhibitory nerves is a mere question of relation, and some nerves produce contraction and dilatation according to the point where they are stimulated. Thus Dastre and Morat have found that the cervical sympathetic which produces contraction of the vessels in the rabbit's ear when irritated between the ear and the first thoracic ganglion, causes dilatation instead of constriction when it is irritated at a point below the ganglion, in which case the stimulus has to pass through the ganglion before it reaches the ear.

In considering the action of drugs on the vessels, we have, therefore, to examine.

1. Their direct effect upon—
   - A. The contractile walls of the vessels themselves with their
     - *a*, muscular fibres,
     - *b*, motor ganglia;
   - B. Nerve fibres
     - *a*, vaso-motor,
     - *b*, vaso-dilating;
   - C. Nerve centres
     - *a*, vaso-motor,
     - *b*, vaso-dilating.
2. Their reflex action on the nerve centres just mentioned.

There are two **modes of estimating the contraction** of the arterioles; 1st, by direct observation and measurement under the microscope; 2nd, by ascertaining the quantity of blood or other fluid which will pass through them in a given time.

Each of these methods may be used in several ways, according as we wish to ascertain the action of a drug; 1st, on the contractile walls of the vessels alone; 2nd, on the walls together with the vascular nerves but without the nerve-centres; and 3rd, on the vessels in connection with the nerve-centres.

The method of direct observation of the arterioles may be practised in either frogs or mammals.

The part of the **frog** usually selected is the web, the mesentery, the mylohyoid muscle, the tongue, or the lung. The parts usually observed in **mammals** are the wing of the bat and the ear of the rabbit.[1]

In observing the effect of various conditions on the lung, it is necessary to inflate it. This is easily done by means of a small cannula with a bulging end which is tied into the larynx. Over the other end is slipped a small piece of india-rubber tubing, and by clamping this after the lung has been inflated, the escape of air is prevented.

An apparatus for this purpose is described by Holmgren.[2] The accompanying engraving (Fig. 66) shows one which I used in 1870 for the purpose of investigating the action of heat and cold upon the lung.[3]

By means of the india-rubber ball I directed upon the lung a stream of air which was previously passed either through hot water or through iced water. The pulmonary capillaries, when treated in this way, contract under the influence of cold by one-third of their diameter. McKendrick, Coats, and Newman, in an investigation on the action of anæsthetics on the pulmonary circulation, found that chloroform, ethidene, and ether, all stop the pulmonary circulation, the action of chloroform being greatest and that of ether least.[4]

In observing the effects of drugs on the vessels alone, it is necessary to destroy the influence of the nerve-centres over them. This is usually done in a frog, by destroying the brain and spinal cord. In the rabbit's ear it is done by dividing as far as possible all the nerves going to one ear, then injecting the drug into the general circulation and comparing its effect upon the two ears. It is evident, however, that such experiments are not free from fallacy, because in them the circulation is dependent on the condition of the heart as well as that of the vessels; and both of these may be affected by the drug.

[1] For observing the vessels of the rabbit's ear one of Brücke's lenses is very convenient. It resembles a telescope in its construction, but has a very short focus.

[2] Ludwig's *Festgabe*.

[3] *British Medical Journal*, Feb. 13th, 1875, p. 204.

[4] *Ibid.* Dec. 18, 1880.

A better plan, therefore, is to obviate this fallacy by keeping up the circulation artificially, either in the body of the frog, or in the ear of the rabbit.



FIG. 66.—Apparatus for ascertaining the effect of heat and cold on the vessels of the frog's lung. A, a piece of cork to which the frog is fastened, is laid on B, the stage of a microscope, and attached by an india-rubber strap, C. D is a small ring of cork covered with a thin circle of glass. E is the inflated frog's lung. F is a tube by which a current of air can be directed on the frog's lung. It is held in position by a piece of wire, G, which can be bent to any position. I is a flask containing ice and water. H a flask containing hot water. K is a three-way stopcock, by which a current of air may be sent from the spray producer, L and M, through either I or H at will, and thus cold or hot air may be applied alternately to the lung.

A method for **maintaining artificial circulation** in the rabbit's ear while the calibre of the vessels is being measured was invented by Ludwig, and described by me in the *British Medical Journal*, 1871.

In the frog artificial circulation is kept up by putting a cannula into the aorta, and another into the vena cava or abdominal vein after destruction of the brain and spinal cord. The aortic cannula is connected with two funnels or bottles, such as are used for artificial circulation through the intestine (p. 333). These contain either a saline solution or a mixture of saline solution with blood. To one of them the drug is added. The circulation can be rendered quicker or slower at will, by increasing the pressure under which the fluid flows into the aorta. A suitable part of the frog is then put under the microscope, and the vessels measured while unpoisoned blood flows through them. The poisoned blood is then allowed to circulate under exactly the same conditions of pressure and the vessels are measured again. By this method of observation Gaskell ascertained that very dilute alkalies cause great contraction of the vessels, so as sometimes almost entirely to occlude them and arrest any flow of blood through them. Dilute acids counteract this effect and cause the vessels again to dilate.

Cash and I have observed that in addition to this action, dilute **acids** have a tendency to increase the exudation of fluid from the vessels and produce **œdema** of surrounding tissues.

In many experiments which have been made on the action of drugs on the blood-vessels by direct microscopic measurement of their size, before and after the application of the drug, no account has been taken of the effect which the application of the drug may produce by its local irritating action on the nerves or tissues of the part to which it is applied, and by its reflex action through the nerves, quite independently of any special action which it may have on the vessels. Thus, irritation by the application of alcohol, either alone or as a solvent in tinctures, or by a strong saline solution, has an effect similar to that of simple irritation by pressure or scratching, and usually causes temporary contraction, followed by dilatation of the capillaries. This contraction may be more or less prolonged, according to the strength of the irritant which is applied. Unless these conditions are taken into account, observations on the effect of drugs applied locally to the web, mesentery, or tongue, are very unsatisfactory and generally worthless.

Perhaps a somewhat better result may be obtained by injecting the drug into the lymph-sac of a frog, and then observing the web. But here also we have the same difficulty, because the sensory nerves of the lymph-sac being irritated, reflex stimulation of the vaso-motor centre and consequent contraction of the vessels may be induced.

Method of Measurement by Rate of Flow.—Another method of ascertaining the effect of drugs on the vessels is to measure the amount which flows out of them in a given time. This method may be employed either in the frog or in the higher animals. The method of employing it in the frog is to destroy the brain and spinal cord, and tie one cannula into

the heart or aortic bulb, and another into the inferior vena cava. The aortic cannula is connected with a reservoir containing saline solution, or defibrinated blood, which can be made to pass into the aorta and circulate through the vessels at any desired pressure by simply raising or lowering the reservoir; the fluid flows out through the cannula in the vena cava, and the quantity is registered upon a revolving cylinder.

By this method Cash and I have found that potassium chloride, contrary to our expectation, causes great contraction of the vessels; that barium and calcium and strontium do so also, but to a less extent. The instrument used for this purpose consists of a light lever, one end of which is depressed each time that a drop falls upon it. An electric circuit is thus broken, and the fall of each drop is readily recorded by means of an electro-magnetic marker, at the same time the pressure under which the circulation is going on is also recorded by means of a manometer. Slowing of the flow indicates of course contraction of the vessels, and acceleration indicates dilatation of the vessels.

The general results of our experiments with several metallic salts are shown in the accompanying table. Most of the drugs experimented on cause contraction of the blood-vessels, but we are unable at present to arrange them in the exact order of their strength of action.

Lithium causes slight contraction.	Iron causes slow contraction.
Potassium (very dilute solutions) causes dilatation.	Copper ,, powerful do.
Ditto (solutions of $\frac{1}{4000}$) causes contraction.	Zinc ,, powerful do.
Barium causes rapid contraction.	Tin ,, powerful do.
Calcium ,, gradual do.	Cadmium ,, slight do.
Strontium ,, gradual do.	Nickel ,, slight do.
Magnesium ,, slight do.	Cobalt ,, slight do.
Aluminium (much diluted), has no effect.	Platinum ,, powerful do., but none is produced by solutions weaker than $\frac{1}{8000}$.
1 per cent. needed to produce any effect.	

In experiments made by such methods as that just described we reduce the **problem** of the action of drugs on the blood-vessels to a very **simple form,** although we have still to distinguish whether the drug acts directly on the contractile walls of the blood-vessel or on the nervous elements contained in its wall. There is at present no means of absolutely separating those two factors, but it is probable that the nerves die sooner than the muscular fibres, and that if the experiments are carried on for some time the effect of the drug is chiefly, if not entirely, exerted upon the muscular fibres. This is probably the explanation of the different effects of chloral on the vessels of the kidney observed by Ludwig and Mosso (p. 241).

In experiments on the flow of blood through the vessels of

warm-blooded animals, the circulation is kept up in much the same way as in the frog. The blood may be used cold, or may be kept at the temperature of the body. The cannula is usually inserted either into the artery supplying an organ such as the kidney, or supplying a single muscle, or it may be put into the descending aorta, so that the blood passes through the whole of both lower extremities. The flow is measured by the rate at which the blood issues from the corresponding vein.

This method we owe to Ludwig, who, along with his pupil Mosso, made a number of experiments on the circulation through the kidney. The conclusions arrived at were :—that venous blood causes contraction, and oxygenated blood, dilatation of the vessels; but the dilatation which richly oxygenated blood, circulating after venous blood, causes in the vessels is only temporary, and they soon return to their normal calibre. Mosso's experiments have been repeated by Severini, who used the lung instead of the kidneys. He finds that the alternate circulation of oxygenated and of venous blood acts in the manner described by Mosso, but that when oxygenated blood is passed through steadily the vessels contract and the flow through them is diminished; venous blood on the contrary when circulated for a length of time causes the vessels to dilate and the flow through them to increase. The action of venous blood upon the arterioles appears indeed to be similar to its action upon other tissues. A small or moderate quantity of carbonic acid acts as a stimulus and causes contraction, but great interference with the natural process of oxidation produces paralysis.

Nicotine, in the proportion of 1 in 10,000, causes contraction of the vessels; but this is also temporary. One per cent., on the contrary, immediately causes dilatation.

Atropine has a very powerful action; but this differs completely according to the dose. One part in 100,000 causes temporary contraction of the vessels, which soon passes off. One in 10,000 causes contraction, which, instead of returning simply to the normal, passes into dilatation, and then returns to the normal. One in 5,000 has a similar action, but instead of the dilatation passing away, and the vessels returning to their normal size, the dilatation persists, and the kidney soon dies.

Chloral causes the vessels to contract and then to dilate; but besides this it has a peculiar action, either increasing rhythmical contraction and dilatation of the vessels, when such movements are already present, or inducing them when they are absent. It only acts upon the vessels when the blood contains oxygen; and when the blood is saturated with carbonic acid, it has no action on them at all. Its action is also altered by the condition of the kidney. When this organ has been kept for twenty-four hours in a cool place, its vessels still retain their irritability; but small doses of chloral, instead of causing contraction followed by dilatation,

only produce contraction, and a much larger dose is required to produce dilatation. This alteration is due to a change in the vessels—either in their muscular walls, or more probably in the ends of the vaso-motor nerves—and not to any change in the blood; for it occurs when serum instead of blood is passed through the kidneys. When the kidney is dead, chloral mixed with the blood, instead of increasing the rapidity of the current as in the living organ, or leaving it unaltered, as one would expect, greatly diminishes it. Chloral also alters the effect of artificial stimulation of the kidney. Faradaic currents or induction-shocks do not seem to affect the normal vessels, but constant currents cause dilatation, which continues while the currents are passing and diminishes after they cease. When chloral is added to the circulating blood, however, the vessels contract during the passage of the current instead of dilating, and dilate slightly after the current has ceased. When the chloral has acted so far upon the vessels as to dilate them greatly, the constant current causes no alteration while it is passing, but, after it ceases, dilatation increases still further.

Action of Drugs on Vaso-motor and Vaso-dilating Nerves.

The effect which irritation of the vascular nerves produces in the living body is also altered by the action of drugs. This effect is of two kinds—vaso-motor or vaso-contracting, and vaso-dilating. Fibres, having these two different actions on the vessels of a part, appear frequently to run together in the same nerve-trunk, so that sometimes we get dilatation, at other times contraction of the vessels on irritation of a nerve, and not unfrequently we get contraction followed by dilatation. Such fibres, however, are not contained in equal proportions in different nerve-trunks. The splanchnics, for example, chiefly contain vaso-motor fibres, so that irritation of these nerves causes great contraction of the vessels in the intestine, and a rise of blood-pressure. The motor nerves of muscles, on the contrary, appear to contain chiefly vaso-inhibitory fibres, so that stimulation of the nerve causes dilatation of the vessels in the muscle to which it is distributed. Similarly, irritation of nerves distributed to glands usually causes dilatation of the vessels in them. The chorda tympani affords a marked example of this, though the same thing is noticed also in the case of the sweat-glands in the foot on irritation of the sciatic nerve.

Most of these vaso-motor or vaso-inhibitory nerves can be stimulated reflexly by irritation of a sensory nerve, as well as directly by irritants applied to the nerves themselves.

We are not acquainted with many drugs which have the power of paralysing the ends of the vaso-motor nerves in the vessels apart from an action upon the contractile walls of the vessels, or the central nervous system. Arsenic, however, appears to

be a drug of this kind, and in acute poisoning by arsenic Böhm has observed that neither irritation of the splanchnic nerves nor of the medulla raises the pressure in the way it usually does. From this effect Böhm concludes that the vaso-motor nerves contained in the splanchnics are paralysed, but some other observers have not obtained similar results. Hay has found that potash has a similar action. The method is not free from fallacy, for it is obvious that if the vessels in the intestine should happen to be already contracted either from the effect of a drug upon them or from any other cause, neither stimulation of the splanchnics nor of the medulla can have any further effect upon them or on the blood-pressure through them. For when the vessels of the intestine are contracted the blood pours into the veins from the aortic system, through the arterioles and capillaries of the voluntary muscles, and these are only to a very slight extent under the control of the vaso-motor centre in the medulla. Irritation of it will therefore have little effect on the general blood-pressure when the arterioles of the intestine are already contracted, and irritation of the splanchnics is also prevented from having much effect.

It seems probable that curare and poisons which, like it, not only paralyse the ends of the motor nerves, but also the ends of the vagus in the heart, also paralyse vaso-motor nerves, though larger doses are required for this purpose.

Vaso-dilating fibres appear also to be paralysed by curare, for irritation of the motor nerve of a muscle does not cause dilatation [1] of the vessels in a muscle of an animal deeply poisoned by curare. Stimulation of the spinal cord produces contraction of the vessels of the penis instead of erection in an animal poisoned by curare,[2] and stimulation of the chorda tympani does not cause the same amount of dilatation in a poisoned as in a non-poisoned animal, even when the dose of curare is small.[3] Small doses of curare, however, and even large doses of opium, do not appear to paralyse the vaso-dilating nerves of muscles.

In some experiments which I made on the chorda tympani, I got a different result from the usual one in an animal thoroughly under the influence of opium. The vessels appeared to contract instead of dilating on irritation of the chorda tympani, so that instead of the blood gushing out of the vein, it flowed slowly, drop by drop.

Action of other parts on the Blood-Pressure.—It has already been mentioned that the blood-pressure rises during muscular exertion, as for example during the struggles of an animal. The cause of this has not been definitely ascertained, but it is probably, to a great extent, due to the flow of blood through the muscles being mechanically obstructed by the contraction of the muscular fibres and to a more rapid action of the heart.

[1] Gaskell, *Journ. of Physiol.* 1878-9, vol. i. p. 273.
[2] Eckhard, *Beiträge*, vol. vii. p. 67. [3] V. Frey, Ludwig's *Arbeiten*, 1876, p. 98.

The flow of blood through those organs which consist of involuntary muscles, *e.g.* the intestine, may also be obstructed.

When physostigma is given to an animal, the blood-pressure is sometimes noticed to rise considerably, and this rise of pressure was at first attributed to contraction of the arterioles. According to Von Bezold and Götz, however, this is due, to a great extent, not to the contraction of the arterioles themselves, but to mechanical obstruction of the intestinal vessels by the tetanic contraction of the muscular walls of the intestine.[1]

Reflex Contraction of Vessels.—Experiments on the outflow of blood from divided vessels, while the nervous system is intact, are sometimes made on frogs for the purpose of ascertaining the direct effect of drugs on the arterioles themselves, but this method is faulty, for the alterations consequent on the injection of the drug may be simply due to its local irritant action producing reflex contraction.

Such experiments are usually made by snipping off the toe of a frog, then injecting the drug into the lymph-sac and observing how many drops of blood exude in a given time from the toe before and after the injection.

It is obvious that if no change occur in the heart, and the openings of the divided vessels do not become obstructed by clots or otherwise, these experiments may give some indication regarding the contraction of the vessels: but the results are not trustworthy unless we can ascertain the condition of the heart. A modification of this experiment enables us to some extent to do this. The end of a toe on *each* foot having been snipped off, the nerve in *one* leg is divided and then the drug is injected into the lymph-sac. If it be then found that the flow of blood from the foot, whose vaso-motor supply has been destroyed by division of the nerve, continues unchanged or is even increased after the injection of the drug, while that from the other foot is diminished, we may conclude that the diminution is due to contraction of the vessels caused by the injection of the drug.

But it is incorrect to assume, as has sometimes been done, that this contraction is due to any specific action of the drug, either upon the muscular walls of the blood-vessels or upon the vaso-motor centre. There is here a fallacy similar to that already mentioned in respect to direct observation of the size of blood-vessels. Any irritation of a sensory nerve by pinching, scratching, heat, &c., may cause reflex stimulation of the vaso-motor centre and produce contraction of the vessels, and injection of strong saline solutions into the lymph-sac, having a local irritant action, will produce a similar effect.

As an example of this fallacy we may mention certain experiments with bromide of potassium. In such experiments it was found that injections into the lymph-sac were followed by contrac-

[1] *Centralblatt d. med. Wiss.* April 6, 1867, p. 234.

tion of the vessels of the toes, so that much less blood flowed after the injection. When the sciatic nerve was divided on one side the flow was not lessened but rather increased in the corresponding foot, at the same time that it was much diminished on the other side where the nerve was intact. This result clearly shows that after the injection the vessels in one foot contracted, and that this contraction was due to the effect of the injection on the vaso-motor centre, inasmuch as it did not occur in the foot whose vessels had been withdrawn from the influence of this centre by division of the nerves. From this fact the conclusion has been drawn that bromide of potassium has a special power of contracting blood-vessels generally, and on this conclusion theories of its action upon the nervous system have been based. Such theories, however, rest on a very untrustworthy foundation; for although contraction of the vessels no doubt followed the injection of a strong solution of bromide into the lymph-sac, this contraction was probably not at all due to any specific action of the bromide, but only to the reflex stimulation of the vaso-motor centre caused by its local irritant action at the place of application. If introduced in a dilute solution into the mouth instead of in a concentrated form into the lymph-sac, this local irritant action would be absent and probably no contraction of the blood-vessels would be produced.

Action of Drugs on Reflex Contraction of Vessels.—Irritation of a sensory nerve usually produces reflex stimulation of the vaso-motor centre and consequent contraction of the vessels and rise in the blood-pressure both in the frog and higher animals. The chief vaso-motor centre is situated in the medulla oblongata, but it is probable that there are many subsidiary centres throughout the body. It is probable also that these vary in strength and in the amount of independent action they possess in different animals. When the influence of the chief vaso-motor centre upon the body is destroyed by section of the spinal cord just below the medulla, the vessels dilate and the blood-pressure falls greatly. This is, however, not always the case, for in some dogs I have noticed that after section of the medulla, the blood-pressure remained so high that I was under the impression that the cord had been imperfectly divided, yet after death examination of the cord showed that section was complete.

The vaso-motor centre is paralysed by numerous drugs, especially in the final stages of their action, so that its ordinary tonic action is destroyed and the blood-pressure falls greatly. Its power of responding to a reflex stimulation is also abolished, and irritation of a sensory nerve no longer raises the pressure. The tonic and reflex action of the centre do not always appear to be effected *pari passu*,—chloral, for example, appearing to have a greater power to diminish its reflex action than its tone, so that stimulation of a sensory nerve has little or no effect even when the

blood-pressure has not as yet fallen very low. Sometimes indeed an opposite effect to the usual one may be produced and the blood-pressure be lowered still further instead of raised by the stimulation. Alcohol also paralyses very markedly both the reflex power and the direct excitability of the vaso-motor centre, so that neither stimulation of a sensory nerve, nor even stimulation of the centre by suffocation, will raise the blood-pressure.[1] Both the normal tone and the reflex excitability of the vaso-motor centre are greatly increased by strychnine. The general blood-pressure greatly rises after the injection of this drug, and the effect of irritation of a sensory nerve upon it is increased. It has already been mentioned that in ordinary circumstances the subsidiary vaso-motor centres in the cord when separated from the medulla cannot of themselves maintain the blood-pressure. After the injection of strychnine, however, their action is so much increased that they may keep the blood-pressure at a high average and may also cause it to rise on irritation of a sensory nerve.

Comparative effect of Heart and Vessels on Blood-Pressure in different Animals.—The influence of these two factors—the heart and the vessels—on the blood-pressure varies in different animals, and under different conditions; and a number of the discrepancies observed by various observers are probably due to this circumstance. Thus, in dogs the effect of the heart is very considerable, and when its beats are quickened by division of the vagi the pressure rises; in rabbits, on the other hand, the heart instead of working well under its power as in the dog, beats very rapidly in the normal condition, and when the vagi are divided the pressure does not rise much, although when they are stimulated the pressure falls both in the dog and in the rabbit. This different action of the vagus in the dog and rabbit is well seen when these animals are poisoned by atropia. This drug completely destroys the inhibitory action of the vagus on the heart; and when the inhibitory power is completely removed we find that only a slight increase in the number of beats takes place in the rabbit, the pulse-rate rising one quarter: for example, perhaps from 100 to 125. In the dog, on the contrary, the pulse-rate will rise to three times, or even four times, what it was before.

In man the effect of the vagus on the heart is intermediate between that of the rabbit and dog: so that if the normal pulse is between 70 and 80 in the minute, it rises to between 140 and 180 when the vagus is paralysed by atropia (Von Bezold).

This difference between the effect of the vagus on the heart alters the effect of drugs on the blood-pressure in different animals.

The difference in the action of drugs on the dog and rabbit is well shown in the case of nitrite of amyl. If this be given by inhalation to a rabbit, the blood-pressure falls immediately

[1] Dogiel, *Pflüger's Archiv*, 1874, Bd. viii.

and rapidly. If given to a dog, the fall may be very slight, at least if a small quantity only is used. On counting the pulse in the dog we discover at once the cause of the apparent difference in the action of the drug on the two animals. Before inhalation the pulse of the dog was slow, but after inhalation its pulse becomes almost as quick as that of the rabbit. In both animals the nitrite causes dilatation of the vessels, but in the dog the heart begins to beat so much more rapidly than usual that it maintains the blood-pressure nearly at the normal, notwithstanding this dilatation; while the heart of the rabbit beats so quickly, normally, that it cannot maintain the pressure by increased rate of pulsation. If the vagi be cut in the dog, so that the heart beats rapidly like that of the rabbit before inhalation, the nitrite causes as sudden a fall as in the rabbit.[1]

The numerous factors which have to be taken into consideration in regard to the blood-pressure, the action and the interaction of different parts of the body upon one another, render it by no means easy to understand the action of drugs on the circulation. The differences which we find in the action of drugs on different animals seem at first to make matters still worse: but it is through these differences of action that we learn the exact mode in which the various factors of the circulation are affected by the drug.

There are at least two other factors which must be borne in mind in relation to the difference between rabbits and dogs: these are (1) the much greater sensitiveness of the inhibitory nerves of the heart, to reflex stimulation from the nose as well as to stimulation by venous blood, in the rabbit than in the dog; and (2) the proportionately much greater length of the intestinal tube in the rabbit, which causes the vessels of the intestines, on account of their number, to exercise a greater action on the blood-pressure in it than in the dog. Thus, in the rabbit, a slightly irritating vapour will cause the animal to close its nostrils; and almost immediately the vagus will be excited and the heart will stop. This stoppage is probably chiefly due to reflex action on the heart through the nasal nerves, though it may be partly due to accumulation of carbonic acid in the blood. When the spinal cord is divided in the rabbit just below the medulla, the pressure sinks enormously: in the dog it also sinks, but not to the same extent; and in some cases it sinks so little that it is almost impossible to believe that the cord has been divided, until examination after death shows that the section has really been completed. This effect may be partially due to the less power which the dilatation of the intestinal vessels, consequent upon the section, has in the dog. It may also however, be partly due to greater development of extra-cranial vaso-motor centres in the spinal cord and elsewhere, than in the rabbit.

[1] Lauder Brunton, *Journ. of Anat. and Physiol.* Nov. 1870, p. 95.

Influence of Nerves on Blood-Pressure.—Both the quickness of the heart's beat and the contraction of the arteries are regulated by the **nervous system;** and it is generally by their action on it that drugs alter the blood-pressure, though it must be constantly borne in mind that they may also do so by acting directly on the **muscular walls** of the heart and arteries themselves. The parts of the nervous system chiefly concerned in regulating the circulation are:

I. The **motor cardiac ganglia** which lie in the walls of the heart, and are under ordinary circumstances the cause of its rhythmical action.

II. **Inhibitory nerves,** which render the heart's action slow, and, if irritated very strongly, may stop its beating altogether, and produce quiescence in **diastole.** The inhibitory fibres have their origin or roots in the medulla, and proceed in the vagi to the heart. In probably all the higher animals they are normally in more or less constant action. In men and dogs they maintain a well-marked action; and, after they are cut or paralysed, the heart beats in the dog three or four times as quickly, and in man twice as quickly, as before. In rabbits and cats they act less, and their division only makes the heart go one-half or one-fourth faster.

A drug may **irritate** them, and render the heart's action slow—

1. By acting **directly** on (*a*) their roots in the medulla, (*b*) their ends in the heart;

2. **Indirectly**, through its action on other parts, producing (*a*) increased blood-pressure, or (*b*) accumulation of carbonic acid in the blood, both of which act as irritants to the vagus roots;

3. **Reflexly**, through irritation of sensory nerves, *e.g.* irritation of the intestines; of the sympathetic nerve; of the depressor; or of certain afferent fibres in the vagus. Reflex irritation is only likely to be caused by drugs having a powerful local action.

Drugs may also paralyse the inhibitory or the ends of inhibitory nerves in the heart and thus quicken the heart.

Inhibitory ganglia have been supposed to exist in the heart, and certain drugs, such as muscarine, are supposed to slow its pulsations by their action on these ganglia. They have been supposed to be distinct from the ends of the vagus (p. 271), although generally when the ends of inhibitory nerves in the heart are spoken of, the inhibitory ganglia are included in the term.

III. **Quickening Nerves.**—These belong to the sympathetic system. They have their origin in the brain or medulla, pass down through the cervical part of the spinal cord to the last cervical and first dorsal ganglion (which in many animals are united), and thence through the third branch of the ganglion to the heart. Quickening fibres are said by some to run also in the cervical part of the sympathetic cord. Unlike the inhibitory nerves, the

quickening nerves are not normally in constant action. The accelerating centres may be stimulated—

1. By the **direct** action of drugs upon them.

2. **Indirectly** by the drugs producing a diminution in the blood-pressure. Such a diminution acts as a stimulus to them.

It is probable that accelerating fibres also pass to the cardiac ganglia from the endocardium, for irritation of the interior of the heart, either mechanically or by the injection of irritating drugs into it, causes acceleration. The supposed relationship of the various accelerating fibres to the cardiac ganglia is shown in the accompanying figure.



FIG. 67.—Diagram to show the supposed relation of motor ganglia in the heart to accelerating fibres. A, accelerating fibres proceeding from the cerebro-spinal or sympathetic nervous systems to the motor ganglia of the heart. G, motor ganglion. *a*, accelerating fibres passing from the endocardium to the motor ganglion. *m*, motor fibres to the cardiac muscle. H, the cardiac muscle. [For the sake of simplicity in this diagram all hypotheses regarding separate motor and accelerating ganglia have been disregarded.]

IV. **Vaso-motor Nerves,** which cause the smaller arteries, and probably also the capillaries, to contract. These belong to the sympathetic system; and the most important of them are contained in the splanchnics, which when stimulated produce contraction of the intestinal vessels. As these vessels can, under certain circumstances, hold all the blood in the body, the influence of the splanchnics over the blood-pressure is very great; and division of them can lower it, or stimulation of them increase it, very much. The intestine being much longer in herbivora than carnivora, the splanchnics have a greater influence over the blood-pressure in the former. The chief centre of the whole vaso-motor system seems to be in the medulla oblongata; and it is generally in constant action, keeping up a certain amount of contraction or tone in the vessels. There are also, however, subsidiary centres in the spinal cord, and possibly also in the ganglia of the sympathetic system.

The activity of the **vaso-motor centres** may be increased, and the vessels made to contract—

1. By **direct** irritation of these centres.

2. By **reflex** irritation through (*a*) the cervical sympathetic, (*b*) the vagus, when the brain is intact, and the animal not narcotised, (*c*) sensory nerves, including the splanchnics themselves. When

the medulla is separated from the rest of the body by dividing the spinal cord at the atlas, it can, of course, no longer exert any influence over the vessels; they consequently become dilated throughout the whole body, and the blood-pressure usually sinks very low. If the lower end of the divided cord be then irritated, the vaso-motor nerves which pass through it from the medulla to the body are stimulated, and the blood-pressure rises.

It is probable that the **peripheral ends** of the vaso-motor nerves in the vessels themselves may be either stimulated or paralysed by the action of drugs conveyed to them by the general circulation.

V. **Depressor nerves.**—Irritation of these nerves is conducted to the vaso-motor centres, and acts on them in such a way as to cause a reflex dilatation of the small vessels, either (1) **generally** throughout the whole body, or (2) **locally** in one particular part of it.

1. The chief nerve which causes dilatation, especially affecting the intestinal vessels, is one which runs from the heart to the medulla, and is called, from its power of diminishing blood-pressure, the depressor nerve. Its fibres seem to be included in the vagus in the dog; but in the rabbit it generally runs separate from the heart to the level of the thyroid cartilage; here it divides into two so-called roots, one root going to the superior laryngeal, and the other to the vagus nerve. These are generally called roots, though, as the nerve conveys impressions **from** the heart **to** the brain, they are, physiologically, really branches. There seem to be also depressor fibres in the vagus itself; but the vagus contains fibres of many kinds, and, among others, some which cause reflex contraction of the vessels and rise of blood-pressure—hence called pressor-fibres. The depressor-fibres of the vagus seem to act on the vaso-motor system through the medulla itself, while the pressor-fibres affect it through a centre in the brain, so that, when the brain is perfect, irritation of the central end of the vagus causes increased contraction of the vessels and raised blood-pressure; but, when the brain is removed or its functions abolished by opium, it causes dilatation of vessels and diminished pressure.

2. When a sensory nerve is irritated, the action of the vaso-motor centre is suspended in the part supplied by the nerve, and in those which immediately adjoin it, so that their vessels become dilated, while at the same time contraction of the vessels in other parts of the body is produced. The blood-pressure is thus increased generally, and produces in the **locally** dilated vessels a very rapid stream of blood. This fact was first discovered, and its therapeutics indicated, by Ludwig and Lovèn.

The causes of alteration in blood-pressure as well as in the pulse-rate, will perhaps be more easily seen from the following table:—

Causes of Alterations in Blood-pressure and Pulse-rate.

Blood-pressure may be diminished.

- **By slow action of the heart**
  - Irritation, or increased excitability of vagus roots
    - Directly, by the action of the drug on them.
    - Indirectly, by increased blood-pressure.
    - „ by accumulation of CO_2 in the blood.
  - Irritation, or increased excitability of vagus-ends in the heart.
    - Reflexly, by irritation of some afferent nerve.
  - Paralysis of sympathetic ends in the heart?
  - Weakness of the heart
    - Paralysis of the cardiac ganglia.
    - Paralysis of the cardiac muscular fibres.
- **By smallness in the amount of blood sent into the heart at each systole**
  - Imperfect systole of the heart.
  - Imperfect diastole of heart.
  - Contraction of the pulmonary vessels.
  - Great dilatation of the venous system.
- **By dilatation of the small arteries**
  - Paralysis of the vaso-motor centre
    - Directly, by the action of the drug.
    - Reflexly, through the depressor.
  - „ „ „ „ peripheral ends.
    - Reflexly, through vagus and sensory nerves, when brain is removed or animal poisoned by opium.
  - „ „ „ „ fibres
    - In operations by division of the cord or of the splanchnics.
  - Paralysis of the muscular coat of the arterial walls.

Blood-pressure may be increased.

- **By quick action of the heart**
  - Paralysis of vagus roots.
  - Paralysis of vagus ends in heart.
  - Stimulation of sympathetic roots
    - Directly by action of drug.
    - Indirectly, by lowered blood-pressure.
  - Stimulation of sympathetic ends in heart?
    - Directly.
  - Stimulation of the cardiac ganglia
    - Reflexly, by stimulation of the sensory nerves of the endocardium.
    - Indirectly, by causing increased temperature of [body.
- **By larger amount of blood at each beat**
  - More perfect diastole and systole.
- **By contraction of the small arteries**
  - Irritation of vaso-motor centre
    - Directly by action of drug on it.
    - Indirectly, by accumulation of CO_2 in the blood.
    - Reflexly, through the cervical sympathetic.
  - „ „ peripheral terminations.
    - Reflexly, through the vagus, when the brain is present, and the animal is not narcotised.
  - Direct irritation of muscular coat of vessels.
    - Reflexly, through sensory nerves.
  - „ „ „ vaso-motor fibres
    - In operations by irritation of the peripheral ends of the divided spinal cord or splanchnics.

Stimulation of nerve fibres of course frequently occurs in experiments from the application of a faradaic current to the trunk of a nerve, but it probably never occurs from the action of drugs introduced into the general circulation.

Action of the Heart on Blood-Pressure.—I have already mentioned that we can to a certain extent ascertain whether a rise or fall in blood-pressure is due to the heart or arterioles, by comparing the pressure curve with the pulse curve. If they run parallel the effect may be attributed in great measure to the heart.

But the effect of the heart on the blood-pressure is not so simple as that of the arterioles. In the case of the arterioles we have to consider only the rate at which the blood will flow through them when they are more or less contracted; but in the case of the heart we have to consider not only the rapidity of its pulsations, but the amount of blood which is sent into the arterial system at each beat. We judge of the amount of blood chiefly by the extent to which the blood-pressure oscillates with each pulsation. A large quantity of blood will as a rule cause an extensive, and a small quantity only a slight oscillation. When the heart is beating slowly, so that it has time to fill completely during each diastole, the oscillations are large, and when it is beating quickly the oscillations are small.

It is evident that although quick pulsations tend to raise the blood-pressure, they only do so up to a certain point, as beyond that, the heart does not get properly filled, and so sends but little blood into the aorta at each beat. But the heart may sometimes be imperfectly filled even when it is beating slowly; this has been shown to occur in the case of the frog, by Goltz. When a blow or two is struck on the intestines the veins dilate and the blood accumulates in them, so that the heart, which is also stopped at first, receives no blood when it does begin to beat again. It can therefore send none into the aorta, and the circulation remains completely arrested, although the heart is beating.



FIG. 68.—For description *vide* p. 222.

If the pulmonary capillaries also are contracted the left ventricle will receive little blood, and so will send little blood into the arteries although the right ventricle may be much distended. This appears to occur during poisoning with muscarine, which causes the lungs to become blanched,[1] the right ventricle distended, and the left ventricle and the arterial system empty: so that little blood flows from a wound.[2]

It is difficult, however, to estimate precisely the quantity of blood sent into the arteries at each beat, and its relation to the rapidity of the pulse, so as to ascertain directly how much the rise or fall of blood-pressure is due to the heart; and therefore this is sometimes estimated indirectly by ascertaining first how much of the effect of the drug on the blood-pressure is due to the arterioles, and then attributing to the heart what is not accounted for by their action.

Sometimes also we may get useful information by compressing the abdominal aorta as near the diaphragm as possible before and after injection. We

[1] Lauder Brunton, *Brit. Med. Journ.* Nov. 14th, 1874.
[2] Schmiedeberg and Koppe. *Das Muscarin*, p. 57.

thus diminish so greatly the number of capillary outlets by which the blood may flow from the arteries into the veins that we greatly lessen though we do not quite destroy the effect of the arterioles on the blood-pressure. We can thus estimate more precisely the action of the heart upon it.

Section of the spinal cord below the medulla oblongata by destroying the effect of the vaso-motor centre upon the vessels, also aids us in estimating the action of the heart.

Another method of ascertaining what share in alterations of the circulation locally is due to the heart and arterioles respectively, consists in the combined use of the manometer and Ludwig's stromuhr or Marey's hæmodromometer. The manometer shows the general blood-pressure while the hæmodromometer shows the rate of circulation in the particular artery experimented upon. If the rate of flow increases while the blood-pressure remains constant or sinks, it is evident that the arterioles of the particular vascular district to which the artery is distributed have become dilated. If on the other hand the rate of circulation diminishes while the pressure remains constant or rises, it is clear that the arterioles have become contracted.

This method is only capable of being applied to large arteries such as the carotid or femoral. By placing the stromuhr in the femoral artery, Dogiel and Kowalewsky found that during suffocation the rapidity of the blood-flow diminished while the pressure rose, showing that the peripheral vessels were contracted.[1]

By the use of the stromuhr, Dogiel[2] has found that the rapidity of the flow of blood in the carotid is first increased and then diminished by alcohol, the greatest diminution occurring during complete narcosis.

Effect of Drugs on the Pulse-Rate.—The pulse-rate, *i.e.* the rapidity of the heart's beats, is chiefly regulated by the inhibitory fibres of the vagus, although it is affected also by accelerating fibres. In the frog the latter, excepting those which pass to the motor ganglia of the heart from the endocardium, also run mainly in the vagus, which is really the vago-sympathetic (Gaskell). In the higher animals they run chiefly through sympathetic channels, though to a slight extent also in the vagus.

If we find that the administration of a drug quickens the pulse, we next try to discover the mode in which it has done so. A glance at the table will show that there are several ways in which acceleration may occur, though the most important is either paralysis of the vagus or, at least, cessation of its action. The usual stimulus to the vagus roots in the medulla which calls the nerve into action is the pressure of blood within the medulla; when this is high the vagus roots are stimulated, and the pulse becomes slow; when the pressure is low, the stimulus is removed, and the pulse again becomes quick. Alterations in the blood-pressure will therefore alter the pulse, and drugs which affect the arterioles may quicken or slow the pulse-rate without any marked action of their own on the heart or vagus. This has already been mentioned when speaking of nitrite of amyl, which, by lowering the blood-pressure, and thus lessening the normal stimulus to the vagus roots, greatly quickens the heart in the dog.

In order to ascertain whether irritation of the vagus has been

[1] *Pflüger's Archiv.* 1870, p. 489.
[2] *Ibid.* 1874, vol. viii. parts 11 and 12.

caused reflexly or not, we may divide the nerves through which we may expect the reflex to have occurred, or we may abolish their action on the medulla to a great extent by the use of large doses of chloral.

Action of Drugs on the Cardio-inhibitory Functions of the Vagus.

When speaking in the following pages of the inhibitory action of the vagus on the heart I mean its power to affect the rhythm of the heart so as to render its pulsations slow or stop them entirely, and I do not include under the term inhibition, the power which the vagus also possesses of enfeebling the cardiac contractions unless when this is expressly stated.

We distinguish between (*a*) stimulation of the vagus roots by any cause whatever, and (*b*) stimulation of its ends in the heart[1] by dividing both vagi. Sometimes we inject the drug first, and see whether any slowing of the heart which it has produced disappears on section, or we may divide them before injecting the drug, and see whether any change, either in the way of slowing or acceleration, occurs after the injection. If the effect of a drug in slowing the heart is removed by dividing the vagi, we conclude that its action has been exerted on the vagus roots; if it should still persist after their division, we conclude that it has acted on the vagus ends in the heart or on the heart itself.

Thus aconitine,[2] veratrine,[3] erythrophlœum,[4] and probably all members of the digitalis[5] group stimulate the vagus roots, so that the slowing of the pulse they produce is much lessened or completely abolished by section of the vagi, and takes place to a much less extent when the vagi are divided before the injection. That the slowing does not always completely disappear after section of the vagi, or is not always completely prevented by their previous section, is due to the fact that most of these drugs have also an action either on the ends of the vagus in the heart, or on the nervous mechanism or muscular fibre of the heart itself. Nicotine resembles the substances already mentioned in so far that the slowing which it would otherwise produce is somewhat lessened by section of the vagi, but only to a slight extent, its action being chiefly exerted on the peripheral cardio-inhibitory system.[6]

[1] We use the term vagus ends here for the sake of convenient distinction between the central cardio-inhibitory systems in the medulla oblongata and the peripheral one in the heart. A fuller explanation of the peripheral cardio-inhibitory apparatus will be given further on.

[2] Vide *Dissertation on Aconitine under Böhm's direction*, by C. Ewers, Dorpat, 1873.

[3] Von Bezold and Hirt, *Würzburger Physiol. Untersuch.* i. p. 103.

[4] Brunton and Pye, *Phil. Trans.* 1877, p. 627.

[5] Traube and others.

[6] Traube, *Med Centralztg.* 1862 and 1863, No. 9; *Centralblatt d. med. Wiss.* 1863, pp. 111 and 159; Rosenthal, *Centralblatt d. m. Wiss.* 1863, p. 737.

Physostigmine chiefly affects the heart itself, and so the slowing of the pulse it causes is not abolished by section of the vagi.[1]

Reflex Stimulation of the Vagus.—The vagus centre may be also stimulated reflexly, and slowing or stoppage of the heart produced by irritation of sensory nerves. This stimulation occurs most readily through the nasal, dental, or other branches of the fifth nerve, the nucleus of which is closely connected with that of the vagus or through the sensory branches of the vagus itself, but it may also be induced through almost any sensory, and some sympathetic nerves, if the stimulus be strong.

The vagus centre in rabbits appears to be very readily stimulated through the nasal nerves, for the application of any strong vapour such as ammonia or chloroform to the nose not only induces closure of the nostrils and stoppage of respiration, but also complete arrest of the heart's pulsations. It appears also to be very sensitive to venous blood. Stoppage of the heart may occur in man from irritation of a sensory nerve, even under chloroform anæsthesia, and indeed I believe that in excision of the eyeball the heart usually misses one beat at the moment the nerves are divided.

In dogs, stoppage of the heart and death may occur from irritation of the stomach, even when complete anæsthesia has been produced by chloroform. Some years ago, when making a gastric fistula in a dog, the animal, which was in a state of profound anæsthesia from chloroform, suddenly died when the stomach was laid hold of with forceps. This occurred in a second case just as the cannula was being introduced. On mentioning the subject to Professor Schiff, he informed me that he had had several cases of a similar sort when using chloroform as an anæsthetic, but had none after he began to use ether instead. I found also on using ether that no further death occurred.

Causes of Quickened Pulse.—If, instead of causing a slowness of the pulse, the drug produces **quickening,** it may be due to paralysis of the vagi, to stimulation of the accelerating nerves, or to direct action on the heart itself. We ascertain whether the drug has paralysed the ends of the vagus in the heart by injecting it, and then irritating the vagi in the neck by a faradaic current. If we find that we are no longer able to slow or stop the heart by stimulation of the vagi, we conclude that the drug has paralysed these nerves. This action is well marked in the case of atropine.

Action of Drugs on Vagus Roots.—We may wish to know, however, what the action of the drug has been on the vagus roots, and it is evident that if the ends in the heart are paralysed, no action on the vagus centre could alter the pulsations of the heart any more than nervous stimuli proceeding from the cord could move the legs of an animal poisoned by curare. Nor can we separate the vagus centre from the heart by ligature of the vessels so readily as one

[1] Fraser, *Trans. of Roy. Soc. of Edinburgh*, 1867, Reprint, p. 39; for other literature *vide* Harnack, *Arch. f. exp. Path. u. Pharm.* Bd. v. p. 446.

isolates the frog's leg. It can be done no doubt by tying the carotid and vertebral arteries and keeping up an artificial stream of blood through the head. Instead of this, however, the simpler method is generally adopted of injecting the drug to be tested into the carotid artery, so that it will reach the vagus centre before it gets to the heart instead of injecting it as usual into the subcutaneous tissue or veins, whence it will be carried to the heart before it can reach the vagus centre.

By experimenting in this way it is shown that atropine stimulates the vagus roots so that when injected into the carotid it causes slowing of the heart's action. When it has passed through the cerebral vessels, and returns with the blood to the heart it paralyses the ends of the vagus in the heart, and therefore the pulse again becomes very rapid, notwithstanding the continued stimulation of the vagus roots.

We cannot always conclude with certainty that a drug has excited the vagus roots merely because it has caused the pulse to become slower and has had no action after the vagi have been divided, for it is possible that the terminations of the vagus in the heart may be rendered more sensitive than usual by a drug, so that they may respond to a slighter stimulus than usual or with greater energy to a normal stimulus. Such an action appears to be exerted by physostigmine, which in a certain stage of poisoning renders the vagus more excitable, so that when irritated in the neck by a faradaic current a slighter stimulus suffices to stop the heart after the administration of the drug than before.

Action on Accelerating Nerves.—We ascertain whether a drug has a stimulating action on the accelerating nerves of the heart by cutting both vagi and then injecting the drug. If it quickens the heart still further, we assume that it does so by stimulation of the accelerating nerves. This experiment, however, does not enable us to decide whether the stimulation has affected the accelerating nerves passing to the cardiac ganglia from the central nervous system or those passing from the endocardium.

Stimulating Effect of Asphyxial Blood on the Medulla.—In order to prevent fallacies arising from stimulation of the vagus roots by an asphyxial condition of the blood due to the action of the drug upon respiration, it is usual to maintain artificial respiration through a cannula placed in the trachea. This acts perfectly well in some cases, but if the drug should cause violent convulsive actions it may prevent the movements of the thorax occurring regularly, and therefore it is sometimes necessary to paralyse them by means of curare.

Moreover, it must be remembered that prolonged stoppage of the heart itself will allow the blood in the medulla to become venous and will thus irritate the vagus roots. Prolonged arrest of the heart, therefore, tends by this action to prolong it still further, and functional inactivity tends to pass into death. This mechanism would render every intermission of the pulse very dangerous were it not that the same venous condition of the blood which stimulates the vagus roots stimulates also the vaso-motor centre and the respiratory centre. The vaso-motor centre by contracting the arterioles maintains the blood-pressure during the prolonged diastole, and excitation of the respiratory centre tends to restore the arterial character of the blood. The venous condition of the blood also stimulates accelerating centres in the medulla (Dastre and Morat).

Stimulation of the Heart by increased Blood-Pressure.—It has already been mentioned that increased blood-pressure usually renders the beats of the heart slower by the stimulating action it exerts on the vagus roots. When the vagi are divided, however, its effect is usually quite different, and a rise in blood-pressure after division of the vagi renders the pulse quicker instead of slower, at least generally. An opposite result has been found by Marey in the heart of the tortoise, where increased pressure

rendered the beats slower. The reason of the difference observed between the mammalian heart and that of the tortoise is probably due to the different development of the nervous and muscular structures. The tortoise heart acts more like a single simple muscle, and the more resistance it has to overcome the more slowly does it work.

In the mammalian heart the increased pressure appears to stimulate the nerves, so that the more resistance it has to overcome the more quickly does it work—that is, if the vagi have been cut. The sensibility of the nervous system in the heart to increased pressure appears to be diminished by atropine, for Schiff[1] has found that a quantity of this poison slightly larger than will dilate the pupil lessens the sensibility of the heart to changes in blood-pressure so much that the pressure may be first increased to three times the normal and then diminished to one-half, or even one-third, without any change in the pulse-rate being produced. Such an observation suggests that atropine would be useful in lessening pain or palpitation of the heart in persons with high blood-pressure or suffering from the effects of cardiac strain consequent on violent muscular exertion. I have tried it in such cases sometimes with apparently great benefit, at other times with little result. The cases of failure may, however, have been due to the remedy not being pushed far enough, as in them the pupil was not markedly dilated.

Palpitation.—In what I have just said regarding the effect of blood-pressure on the heart I have spoken of the total work, including in it both the rapidity of pulsation and the amount of work done by each beat. This is, perhaps, fair enough; but at the same time we must not forget that there is a distinction between the total amount of work done and the nature of the individual contraction, either in the heart of tortoises or mammals, or in voluntary muscles. Both voluntary muscles and the heart tend to contract rapidly if they have little resistance to overcome. In patients suffering from anæmia and debility where the blood-pressure is low and the resistance to the ventricular contractions is consequently small, they are apt to take place with great quickness, giving rise to a short flapping first sound and a sharp but unsustained apex beat, while the patient complains of much palpitation. In such cases increased blood-pressure will tend to lessen the palpitation, and digitalis, which contracts the vessels, will be useful; iron also is serviceable by increasing the nutrition of the circulatory apparatus of the body generally. The low blood-pressure, however, while it increases the tendency to palpitation, is not the only factor, and is usually accompanied by a tendency to disturbance of the cardiac innervation which is to be met by sedatives such as the bromides, or by remedies directed to the stomach or other organs from which the disturbing stimulus may proceed.

[1] *La Nazione*, 1872, No. 235.

The Heart of the Frog.

This is a very convenient object on which to study the action of drugs. Their effects upon it are somewhat, though not absolutely, the same as their effects on the mammalian heart; and the frog's heart being simpler in its construction it is easier to analyse the exact mode in which drugs act upon it. The frog's heart consists of three chambers, one ventricle and two auricles. But in addition to these, there is what might almost be called a fourth chamber, the venous sinus or sac into which the venæ cavæ open.

There are three venæ cavæ, two superior and one inferior, which open into the venous sinus.

The venous sinus itself opens into the right auricle, the opening being covered during the auricular systole by a small fold which acts as a valve.



FIG. 69.—Diagram of the frog's heart.

The left auricle receives the pulmonary veins and discharges into the single ventricle the arterial blood which enters it from them, while the right auricle does the same with the venous blood it receives from the sinus.

The septum between the auricles ends inferiorly in two triangular flaps which act as valves between the auricles and ventricle.

From the ventricle issues the common aorta, or aortic bulb, which has at its origin from the ventricle a spiral valve to prevent the return of the blood.



FIG. 70.—View of the auricular septum in the frog (seen from the left side). The nerves are stained with osmic acid. *n* is the posterior, and *n'* the anterior cardiac nerve; *t* is a horizontal portion of the latter nerve; *b* is the posterior, and *b'* the anterior auriculo-ventricular ganglion; *m* is a projecting muscular fold. [This figure is taken by the kind permission of my friend, M. Ranvier, from his *Leçons d'Anatomie Générale*, Année 1877–8, "Appareils nerveux terminaux," t. 6. p. 79.]

The two auricles beat together, and the aortic bulb and ventricle usually beat together, though the bulb is capable of independent pulsation.

The usual rhythm is the following: first the venous sinus, next the auricles, then the ventricle and bulb.

The pulsations of the venous sinus and ventricle alternate with those of the auricle. The heart continues to pulsate rhythmically after it has been completely removed from the body, so that the motor power of rhythmical contraction is evidently contained within itself. Its rhythm is, however, regulated by the vagi nerves. These pass along behind the two superior cavæ to the junction of the venous sinus with the auricle. At this spot, or just over the auricles, between the superior cavæ and the pulmonary veins, they anastomose to form a single or double ganglion, or a plexus containing ganglionic cells sometimes known as Remak's ganglion. From hence two nerves pass down in the auricular septum, to the base of the ventricle, where they end in two ganglia, known as Bidder's ganglia. These are situated at the junction of the wall of the ventricle with the two valvular flaps in which the septum ends. They are connected with one another by fibres which run transversely, nearly in a line with the auriculo-ventricular groove.

The posterior or dorsal nerve comes chiefly from the left vagus; and the anterior or ventral from the right vagus.

Both of these nerves grow thicker as they pass down towards Bidder's ganglia from the presence in them of numerous ganglionic cells; they also send off several branches to the auricle.

The ventricle itself has not been shown to contain either nerve fibres or ganglionic cells, excepting just at its base, where Bidder's ganglia already mentioned are situated, and where branches from them proceed to the ventricle.

Action of Drugs on the Heart of the Frog.

The effect of drugs may be observed by simply destroying the brain, exposing the heart, and either injecting the drug subcutaneously, or into the



FIG. 71.—Instrument for showing the action of heat and cold and of poisons on the frog's heart. It consists of a piece of tin plate or glass three or four inches long, and two or three wide, at one end of which an ordinary cork cut square is fastened with sealing-wax in such a manner that it projects half an inch or more beyond the edge of the plate. This serves as a support to a little wooden lever about three inches long, a quarter of an inch broad, and one-eighth of an inch thick. A pin is passed through a hole in the centre of this lever, and runs into the cork, so that the lever swings freely about upon it as on a pivot. The easiest way of making a hole of the proper size is simply to heat the pin red hot, and then to burn a hole in the lever with it. To prevent the lever from sliding along the pin, a minute piece of cardboard is put at each side of it, and oiled to prevent friction. A long fine bonnet straw, or section of one, is then fastened by sealing-wax to one end of the lever, and to the other end of the straw a round piece of white paper cut to the size of a shilling or half-crown, according to convenience, is also fixed by a drop of sealing-wax. The pin, which acts as a pivot, should be just sufficiently beyond the edge of the plate to allow the lever to move freely, and the lever itself should lie flat upon the plate. Its weight too, increased as it is by the straw and paper flag, would now be too great for the heart to lift, and so it must be counterpoised. This is readily done by clasping a pair of bulldog forceps on the other end. By altering the position of the forceps the weight of the lever can be regulated with great nicety. If the forceps are drawn back as at *c*. the flag is more than counterbalanced, and does not rest on the heart at all, while the position *a* brings the centre of gravity of the forceps in front of the pivot, and increases the pressure of the lever on the heart. The isolated frog's heart is laid under the lever near the pivot, and as it beats the lever oscillates upwards and downwards. When used for demonstrating the action of poisons the wooden lever should be covered with sealing-wax, so as to allow every particle of the poison to be washed off it, and thus prevent any portion from being left behind and interfering with a future experiment. By attaching a small point to the end of the straw in place of the paper flag tracings may be taken upon smoked paper fixed on a revolving cylinder.

dorsal lymph sac or even laying it upon the heart itself. Changes in the rate of the pulse and in the mode of contraction of the different cavities of the heart are thus readily observed. By exposure and irritation of the vagi the

effect of drugs upon their action can also be observed. Even when completely excised the heart of the frog continues to pulsate for a length of time, and the action of heat, cold, and poisons upon it can be readily demonstrated. A simple apparatus for this purpose is shown in Fig. 71.

The fact that heat accelerates and cold retards the pulsations of the heart is one of fundamental importance, both in regard to a right understanding of the quick pulse, which is one of the most prominent symptoms of **fever,** and to a correct knowledge of the proper treatment to apply when the heart's action is failing.

It may be shown with the apparatus just described by placing a piece of ice under the tin plate. The pulsations will become slower and slower, and if the room be not too warm the heart may stand completely still in diastole. On removing the plate from the ice the pulsations of the heart become quicker. If a spirit-lamp be now held at some distance below it the heart beats quicker and quicker as the heat increases, until at last it stands still in heat-tetanus. On again cooling it by the ice, its pulsations recommence. At first they are quick, but they gradually become slower and slower. On again applying the spirit-lamp they become quicker, and by raising the temperature sufficiently the heat-tetanus is converted into heat-rigor. In this condition no application of cold has the slightest effect in restoring pulsation.

Not only the effects of heat and cold, but the effect of separating the venous sinus or the auricles from the ventricle can readily be shown with this apparatus, as well as the action of various poisons. The best for the purpose of class demonstration is muscarine. A drop of saline solution containing a little of the alkaloid being placed on the heart, it ceases to beat entirely. If a drop of atropine solution be now added the beats recommence. I have seen them do so on one occasion after they had entirely ceased for four hours.

For the purpose of observing alterations in the strength of the cardiac pulsations as well as their rhythm, a convenient piece of apparatus is the one devised by Ludwig and used under his directions by Coats (Fig. 72).

One objection to this apparatus as shown in the engraving is, that the blood does not circulate freely through the heart, but this can be overcome by closing the tube at F only partially instead of completely, and according to the amount of closure the pressure under which the heart works may be regulated. Or the tube F may be lengthened and made to empty itself into the reservoir A. The pressure under which the heart works may be regulated by the height at which the tube is allowed to discharge.

Another apparatus is that used by Williams in his researches on digitalin.[1] It consists of a Y-shaped cannula whose stem is divided by a longitudinal septum into two halves, each of which is continuous with the fork on its own side. The stem is inserted through the aorta into the ventricle of the heart, which is kept moist by being dipped in a vessel containing serum or a dilute saline solution. One fork of the Y is connected with a flask containing blood serum or other nutritive fluid, and the other with a manometer. By means of valves these fluids are made to flow only in one direction. These valves consist

[1] *Arch. f. exp. Path. u. Pharm.* Bd. xiii. p. 1.

of a piece of glass tubing with a slit on one side ; over this slit is loosely tied a piece of thin membrane (gold-beater's skin) which covers about three



FIG. 72.—Ludwig and Coats' frog-heart apparatus. A. is a reservoir for serum. B. A stopcock to regulate the supply to the heart. C. A piece of caoutchouc tubing connecting A and D. D. A glass cannula in the vena cava inferior. D'. Another in the aorta. E. A manometer. F. A piece of tubing closed by a clip, to allow of the escape of serum. G. A fine pen, floating on the mercury in E. H. The frog's heart. J. A sealed glass tube passed through the œsophagus, K, and firmly held by a holder, L. N. A second holder to support A. P. A stand with upright rod. S. A flap of skin to cover the heart and prevent drying. The vagus nerve is seen passing to the heart.

quarters of the circumference of the tube. This membrane allows fluid to pass readily out of the tube from within outwards, but not from without inwards, any external pressure causing the membrane to become tightly applied to the slit and to close it.



FIG. 73.—Diagram of Williams' apparatus for investigating the action of drugs on the heart of the frog.

A very useful form of apparatus for investigating the action of drugs on the frog's heart and on the effect of the vagus upon it is made by combining the valves in Williams' apparatus with the apparatus of Ludwig and Coats.[1]

The **apex** (as the lower two-thirds of the ventricle is commonly called), contains, as has been mentioned, **no nerves,** and when separated from the rest, either by cutting or by a tight ligature, usually lies perfectly quiet without contracting. When irritated by a single induced shock, it answers by a single contraction, just like any other muscular fibre.

But though the muscular fibres contained in the apex cease to contract rhythmically, when the nervous stimulus usually supplied by Bidder's ganglia is removed, they still retain a tendency to rhythmical contraction; and when subjected to a constant stimulus of another kind they again commence to pulsate. This is seen when the apex is stimulated by supplying it with oxygenated blood through a cannula under pressure (the pressure supplying the necessary stimulus), or by passing through it a constant or interrupted current, or by adding a trace of delphinine to the nutritive fluid with which it is supplied. This phenomenon is similar to that which occurs in the bells of medusæ already described (p. 89), which cease to contract rhythmically when their marginal ganglia are removed, but recommence when an additional stimulus is applied to the bell itself, by putting it into acidulated water.

A curious point has been made out by Bowditch regarding the excitability of the heart-apex. It has already been mentioned that the amount of contraction of voluntary muscle varies with the intensity of the stimulus, and that this is also the case with the reflex contraction produced by irritation of sensory nerves. The apex when fed with serum usually stands still for a long time before it begins to beat, but when in this condition may be made

[1] Harnack and Hoffmann, *Arch. f. exp. Path. u. Pharm.* Bd. xvii. p. 159.

to contract by the application of an induction shock. The difference between the reaction of an ordinary striated muscle and of the apex to such a shock is, that the heart, instead of responding by a strong or weak contraction to a strong or weak stimulus, either does not contract at all or contracts with as much force as it can exert. The weakest stimulus which will act at all and the strongest have thus exactly the same action, or, in other words, a minimum is also a maximum stimulus. This condition does not correspond to that which obtains in the normal striated muscle when stimulated either directly or reflexly. We find, however, a corresponding condition in the reflex contraction of the muscle produced by stimulation of sensory nerves in an animal poisoned by strychnine (p. 150). We noted, however, in discussing the action of strychnine on the spinal cord, that, just after exhaustion had occurred from a spasm, strong and weak stimuli produced strong and weak contractions in the muscle. A somewhat similar condition appears to occur in the heart, for Mays has noticed that, when the apex is supplied with old blood which has stood three or four days instead of with fresh blood, strong and weak stimuli produce strong and weak contractions.[1]

It is obvious that, although the contractions of voluntary muscle on reflex stimulation may be analogous to the contractions of the apex, yet, in the former case, the alterations occur in the nervous centres, while in the apex the changes occur in the muscular substance.

Action of Drugs on the Muscular Substance of the Heart.

As the lower two-thirds of the ventricle or **apex,** as it is usually termed, contains no nerves, it forms a convenient object for ascertaining the action of drugs upon the muscular substance of the heart itself, and has been much used for this purpose.


Tube for allowing escape of fluid from the heart
Tube for the introduction of fluid
Tube for connecting with manometer.
End for introduction into the heart.

FIG. 74.—Perfusion cannula, with the anterior part removed so as to show the septum.

The apparatus usually employed consists of a small cannula introduced into the ventricle, which is attached to it by a ligature tightly tied round it at the junction of its upper with its lower two-thirds. The interior of the cannula is divided into two by a septum which runs longitudinally, and the one half is

[1] *Separat-Abdk a. d. Verhandl. d. physiol. gesellsch. zu Berlin,* Jan. 12, 1883.

connected with a flask containing the nutritive fluid with which it is to be supplied; and the other with a small mercurial manometer provided with a float to register its oscillations upon a revolving cylinder.



FIG. 75.—After Ringer. Tracings showing the effect of simple NaCl solution in weakening the pulsations of the apex of the frog's heart. The tracing *a* was taken soon after the blood was replaced by NaCl solution; *b*, after a longer period; and *c* after a still longer time.

At first the nutritive fluid is supplied pure to the apex, and after a normal tracing has been obtained the substance to be investigated is added to it.

When a ·65 per cent. solution of NaCl is employed, the apex usually stops in diastole for a period varying from a few minutes to an hour and a half. It then begins to pulsate (Fig. 75, *a*), getting gradually weaker and weaker (Fig. 75, *b* and *c*), and finally stops in diastole. When the heart is in this condition its pulsations may be restored by the addition to the chloride of sodium solution of 1 to 10 per cent. of blood, or of serum, or of a solution of the ashes of serum.

Minute quantities of several poisons such as delphinine or quinine, or a mixture of atropine and muscarine, also restore the rhythmical pulsations after they have ceased in a heart-apex supplied with NaCl solution. A minute quantity of Na_2CO_3 or ·005 per cent. of NaHO restores or increases the beats for a time; afterwards the pulsations become again weaker and the heart stops a second time, but it stops in systole and not in diastole.

Ringer has made the remarkable discovery that when the saline solution is made with ordinary tap-water the beats become prolonged, but the addition of a trace of potash causes them at once



FIG. 76.—After Ringer. Shows the effect produced upon the beat of the frog's heart fed with NaCl solution by the addition of a trace of calcium chloride. The beats in this case are induced by an induction shock.

to assume their normal character, and a frog's heart may be kept beating for hours together with saline solution made in this way and containing a trace of potash, although the saline solution never does this when made with distilled water. The addition of a minute trace of a calcium salt to distilled water produces the same effect as tap-water—the contractions become larger and longer (Fig. 76).

When potash is then added, the length of the contractions becomes diminished to the normal without their strength becoming affected, and thus a pure saline solution made with distilled water and with the addition of minute traces of calcium and potassium will keep the heart beating perfectly for hours together.

Dilute alkalies added to the saline solution have been shown by Gaskell to cause a tonic contraction of the muscular fibre of the apex, so that it may gradually cease to beat. This contraction may occur whether the apex is pulsating or not. If it remains at rest, a manometer connected with it simply shows a gradual rise in the mercury until the contraction of the apex is complete. If it is beating, the duration of full contraction at each systole becomes longer and relaxation during diastole less complete, until no diastolic relaxation occurs and the ventricle remains perfectly still in a condition of complete contraction.

Dilute acids have an opposite action to dilute alkalies, and when very dilute acid, *e.g.* lactic acid, is mixed with the saline solution, it produces a condition of complete relaxation.

Instead of increasing the duration of the systole like alkalies, acids first shorten it and then render it less and less powerful, until contractions cease altogether and the ventricle remains at rest in diastole.

Dilute acids and alkalies counteract each other's effects on the heart, so that after the beats have been very much lowered in force by acids, an alkali will first restore it to its original condition and then produce its own characteristic effect. The subsequent application of an acid will undo the effect of the alkali, again weakening the beats and again producing dilatation instead of contraction.[1]

The three alkalies, potash, soda, and ammonia, have all a somewhat similar tendency to increase the tonic contraction of the ventricle. When large doses are given they tend to paralyse the muscle, so that it again dilates after a period of tonic contraction. The paralysing action of potash is much more powerful, and manifests itself much sooner than that of the other two.

The excitability of the muscular fibre is also altered by alkalies. Soda and ammonia increase it, so that a faradaic stimulus applied to the ventricle has much more effect after the application of soda and ammonia than before. Potash has a different effect and diminishes the excitability of the ventricle, although sometimes the diminution may be preceded by a stage of increased excitability.[2]

A number of poisons act on the muscular fibre of the ventricle like alkalies, others act like acids.

Antiarine, digitaline, helleborine, veratrine, physostigmine, barium, and probably all the substances belonging to the digitalin group, act like alkalies.

[1] Gaskell, *Journ. of Physiol.* vol. iii. p. 48.
[2] Ringer, *Ibid.* vol. iii. p. 193.

Muscarine[1] acts like an acid, and so apparently do also pilocarpine,[2] saponine,[3] and apomorphine.

Neutral double salts of copper, chloral, iodal, and other members of the chloral group,[4] are probably to be classed along with salts of potash, first exciting and then paralysing the cardiac muscle.

In classifying cardiac poisons, when we say that some act like acids and others like alkalies, it must be borne in mind that the action though similar is not identical. Although the actions may be generally like one another, they may vary very considerably even in kind, and certainly vary enormously in degree. Thus the action of barium and veratrine may be very similar, but veratrine is much the more powerful. We find a similar condition in other structures. Thus iodide of ammonium and curarine both paralyse the ends of motor nerves, but an enormously larger amount of the former is required to produce the effect.

That there is considerable similarity in kind, however, between the action of the vegetable alkaloids and inorganic salts is shown by the fact that the action of veratrine may be neutralised by potassium chloride.[5]

The irritability of the heart is preserved for very different lengths of time in different gases. Thus Castell[6] found that the frog's heart continued to beat in oxygen for 12 hours, in nitrogen for 1 hour, in hydrogen for $1\frac{1}{4}$ hour, in CO_2 for 10 minutes, in nitrous oxide for 5 or 6 minutes, in carbonic oxide for 40 minutes, and in chlorine for 2 minutes.

Differences between the Heart Apex and the Heart.

When the heart is tied on to a cannula in the same way as the apex, by a ligature round the auricles or even the sinus, so that, instead of containing no ganglia at all, it contains either Bidder's



FIG. 77.—Diagram to show the difference in the mode of experimenting with the heart and with the apex alone. In *a* the apex alone is attached to the cannula. In *b* the heart, consisting of ventricle and auricles, or of the venous sinus, also is attached to the cannula.

or Bidder's and Remak's ganglia, it also remains motionless in the same way as the apex when supplied with chloride of sodium solution, but its rhythmical power is restored by the addition of blood

[1] Gaskell, *Journ. of Physiol.* vol. iii. p. 61.
[2] Gaskell, *op. cit.*
[3] Schmiedeberg, *Ludwig's Festgabe*, p. 127.
[4] Harnack, *Archiv. f. exp. Path. u. Pharm.* Bd. xvii. p. 185.
[5] Ringer, *Practitioner*, vol. xxx. p. 17.
[6] Hermann's *Handb. d. Phys.* iv. 1, p. 357.

of serum, of solution of the ashes of serum, by a trace of Na_2CO_3, or still better by the addition of ·0005 per cent. of NaHO and a trace of peptone or serum albumen.

When supplied with pure serum, it does not beat regularly, but its pulsations occur in groups separated by long intervals.[1] When



FIG. 78.—Periodic rhythm of the heart, the pulsations occurring in groups separated by intervals of complete quiescence.

a little hæmoglobin or blood is added to the serum, this grouping disappears, and the pulsations become regular.[2]

When the heart has been supplied with hæmoglobin or blood and is beating regularly, the addition of a little veratrine causes the groups to appear, and a similar effect is produced if the blood is not renewed, but allowed to remain in the heart till it becomes venous.[3]

This periodic stage does not occur immediately after the heart has been tied on the cannula and supplied with serum. It is preceded by an initial stage, in which the beats are at first very quick, then slow, and these are separated by long pauses. Next comes the periodic stage in which the groups occur. It is succeeded by the stage of crisis in which the groups are replaced by single pulsations slower and smaller than the normal.

Atropine and nicotine do not prevent the occurrence of groups. Both of them make the groups longer and the pauses shorter. Atropine, however, even in small doses, soon kills the heart before it even enters on the stage of crisis. Nicotine, on the other hand, shortens the pauses, and rapidly induces the stage of crisis without destroying the energy of the heart, which is quite as great after poisoning by nicotine as in the normal condition.

Moderate doses of muscarine make the pulsations smaller and slower, the groups shorter, and the pauses longer. Sometimes the heart becomes exhausted before the stage of crisis appears, at other times it does not. Large doses of muscarine arrest the movements of the heart.

The activity of the heart which has been stopped by muscarine is again restored by atropine, but muscarine can render the beats smaller and slower, even after the previous application of atropine.

The occurrence of groups appears to be most probably due to interference of rhythms—of the ganglionic rhythm with that of muscular fibre.

We find an indication of alternate interference and coincidence

[1] Luciani, *Ludwig's Arbeiten*, 1872, p. 120.
[2] Rossbach, *Ludwig's Arbeiten*, 1874, p. 92.
[3] Rossbach, *op. cit.* p. 93.

of two rhythms in the alterations which sometimes occur in the beats of a ventricle containing its ganglia but separated from the auricles. At first all the beats are of equal strength, but soon



FIG. 79.—After Ranvier, *Leçons*, 1877–78. Tracing of the pulsations of a ventricle separated from the auricles by section at the auriculo-ventricular groove.

each alternate beat gets longer and shorter, till some disappear and others get much stronger than before (Fig. 79; cf. Fig. 42, p. 138).

Action of Drugs on the Vagus in the Frog.—When the vagi are stimulated by an induced current, the heart usually stops in diastole.

The effect of stimulation may be observed either on the heart simply exposed or by means of Ludwig and Coats' apparatus. The action of both vagi is not always alike. The right vagus has usually a greater power to arrest the heart than the left. The action of the vagus varies also according to the condition of the heart, and may produce different effects. It may cause, 1st, stoppage of the heart's beats, followed after an interval by slow pulsations or by small rapid pulsations, gradually becoming larger and stronger; 2nd, it may cause them to become small and slow without actual stoppage—this is the usual effect of irritation of the vagus in the living body. 3rd, it may cause the pulsations to become simply small and rapid without any stoppage; 4th, it may cause them to become rapid; 5th, it may cause them to become more powerful (Figs. 86 to 89, p. 282).

It may also act differently on the auricles and ventricle, producing still-stand of the ventricle and rapid pulsation of the auricles. These differences are probably due to a great extent to the vagus of the frog being really the combined vagus and sympathetic. At present the chief point upon which I wish to insist is that irritation of the **vagus** usually causes **still-stand** of the heart.

When the **venous sinus** is stimulated, still-stand of the heart is produced, which is even more complete and permanent than that which follows irritation of the vagus.

Action of Drugs on Inhibition of the Heart.—The effect of certain drugs upon the still-stand produced by irritation of the vagus or of the venous sinus is very remarkable. A large number of drugs, more especially atropine, curare, conine, and nicotine, when injected into the circulation have the power of completely destroying the inhibitory power of the vagi as far as the rate of rhythm is concerned, so that when their fibres are stimulated

the heart is not arrested, nor are its beats rendered slower, but they are, on the contrary, quickened.

These poisons again may be divided into two classes:

Class I. containing atropine and its congeners.

Class II. containing curare, coniine, nicotine, &c.

These two classes agree in destroying the inhibitory power of the **vagus** nerve, so that irritation of its trunk will no longer produce still-stand or slowing of the heart. They differ in their action on the still-stand produced by irritation of the **venous sinus**. Atropine and its allies prevent any inhibition occurring when the venous sinus is stimulated, or when muscarine is applied to the heart directly.

This action affects chiefly the rhythm of the heart, for muscarine can still reduce the force of the cardiac contractions after the application of atropine. Poisons of the second class do not prevent still-stand of the heart occurring as usual on irritation of the sinus, nor do they prevent muscarine from arresting the beats of the heart. This antagonism of atropine and muscarine has hitherto been explained on the supposition that muscarine greatly stimulates inhibitory centres in the sinus or auricle, while atropine paralyses these.

These two classes also agree in leaving unaffected the **accelerating** nerves of the heart.[1]

These complicated effects are very hard to explain on the ordinary hypothesis.

It is still more strange that although atropine and muscarine have such apparently opposite effects, they both agree in ultimately paralysing the inhibitory function of the vagus.

Muscarine, as I have already mentioned, arrests the movements of the heart; but, if the circulation be carried on, this arrest is only temporary, and is succeeded by a period, first of slowness, then of irregularity, and then of return to the normal; the stage of irritation of the inhibitory centre by the muscarine gradually passing into that of complete paralysis. During the time when the pulse is still slow in consequence of the action of muscarine, irritation of the vagus itself has no power to arrest it, or even to increase the slowness, while at that very time irritation of the accelerating nerves quickens its pulsations just as it would those of a normal heart.[2] When the accelerating nerves are thus irritated, there is often not only an increase in the number but also

[1] In the frog the accelerating nerves appear to run along with the inhibitory fibres in the vagus trunk. In warm-blooded animals these fibres run in separate nerves which pass out from the spinal cord along the vertebral artery and reach the heart through the sympathetic system. Although the chief accelerating fibres pass in these nerves, some are also contained in the vagus trunk, both in warm-blooded animals and in frogs. In animals poisoned by atropine, irritation of the vagus usually produces acceleration of the pulse.

[2] Weinzweig. From experiments in von Basch's laboratory. *Archiv. f. Anat. u. Phys., Phys. Abt.* 1882, p. 527.

in the size of the pulsations, very much as Gaskell has observed under other conditions from irritation of the vagus in the frog. This action is only to be observed in moderate conditions of poisoning. When the poisoning is very profound, irritation of the accelerating nerves has a very peculiar effect, sometimes producing so-called staircases, and sometimes a prolonged condition of still-stand, half in systole and half in diastole.

A marked **difference** is seen **between** the action of the **accelerating** nerves **and** the **inhibitory fibres** of the vagus, as the inhibitory action follows very shortly after the irritation of the vagus, and usually ceases very shortly after the irritation is removed, whereas that of the accelerating nerves does not occur until some time after the irritation has been applied, and often lasts a good while after the irritation has been removed. The inhibitory fibres also appear to influence a different period of the heart's action, the inhibitory affecting the pause or relaxation, while the accelerating affect systole or contraction. This condition renders it not improbable that we may have to do here with an action of these nerves on two different parts of the heart—the ganglia and the cardiac muscle.

It is quite clear that, in order to get any satisfactory explanation of these phenomena, we must take into consideration not only the rhythmical actions going on in the cardiac ganglia and those in the cardiac muscle separately, but also the relation to one another of these rhythms both as regards their energy and rate.

Theories regarding the Mode of Action of Drugs upon the Heart.

In order to explain the effects of various poisons upon the heart, a hypothetical view of its nervous system has been proposed by Professor Schmiedeberg,[1] and I have endeavoured to represent this in the accompanying diagram.[2] It consists of a ganglion, M, which keeps up a rhythmical contraction of those muscular fibres of the heart to which it is connected by the fine nervous filaments, E. This ganglion is connected by an intermediate apparatus with an inhibitory ganglion, I, which can retard or stop the muscular contractions which M produces; and by another apparatus, C, with another ganglion, Q, which quickens the contractions. I is connected by an intermediate apparatus, A, with the retarding fibres, V, of the vagus, and D with the quickening nerve, S, of the heart. This schema has been adopted by Professor Harnack.[3]

[1] Schmiedeberg, *Ludwig's Arbeiten*, 1870, p. 41.

[2] "Experimental Investigations of the Action of Medicines," Lauder Brunton, *British Medical Journal*, December 16, 1871.

[3] *Pharmakologische Thatsachen für die Physiologie des Froschherzens*, Halle, 1881.

It has been supposed that **motor ganglia** are present because the apex of the heart of the frog, which contains no ganglia, will not contract rhythmically if left entirely to itself, whereas the ventricle containing ganglia will do so.[1]



FIG. 80.—Diagram of the hypothetical nervous apparatus in the heart. M, motor ganglion. I, inhibitory ganglion. Q, quickening ganglion. V, inhibitory fibres; and S, quickening fibres from the head. A, A', B, and C, intermediate apparatus. E, fibres passing from the motor ganglia, M, to the muscular substance, F. [For simplicity's sake only one set of motor ganglia has been represented, but other similar ones are supposed to be present in other parts of the heart, and so connected with this set that they all work in unison. It must be remembered that this diagram is purely hypothetical: but if this be carefully borne in mind, the sketch will be found of service in remembering and comparing the action of different poisons on the heart.]

It has been supposed that **inhibitory ganglia** are present, because when a little muscarine is applied to the heart it causes it to stop in diastole. This effect is not developed all at once, but goes on gradually increasing, and its action in this respect seems rather to point to its effect upon ganglia than upon nerve fibres.

It has been supposed that the vagus acts through this inhibitory ganglion or ganglia because irritation of the vagus arrests the heart in diastole, just as muscarine does; but it has been supposed to be connected by some **intermediate apparatus** with the inhibitory ganglia, because we find that when nicotine is applied to the heart irritation of the vagus will no longer arrest its beats, but that irritation of the venous sinus, in which the inhibitory ganglia have been supposed to be situated, will do so at once.

It has been supposed that the inhibitory apparatus, I, was connected by an intermediate structure with the motor ganglia, M, because physostigma does not produce the extraordinary still-stand which muscarine does, but it counteracts to a certain extent the effects of atropia which muscarine does not. Physostigma in small doses increases the excitability of the vagus, so that a slight stimulus applied to that nerve, so slight that it would under ordinary circumstances be insufficient to affect the heart, will stop it.[2] In large doses, it appears to paralyse the vagus. The difference of action between muscarine and physostigma seemed to show that they acted on different nerve structures;

[1] The recent researches of Gaskell have shown that the muscular fibre of the heart of the tortoise will contract, although it contains no ganglia. The question of muscular rhythm independent of ganglia will be considered further on.

[2] Arnstein and Sustschinsky, *Würzburger Physiol. Untersuch.* iii.

while the mutual power of atropia and physostigma to neutralise each other's effects within certain limits indicated that atropine acted on the same nerve structure as physostigma and consequently on a different one from muscarine. (*Brit. Med. Journ.*, Dec. 1871.)

When atropine is applied to the heart it completely removes the effect of muscarine and totally prevents any arrest being produced either by irritation of the vagus or the venous sinus. It has therefore been supposed that nicotine acts upon the intermediate apparatus, A, but that atropine acts either upon I or upon B.

The reason why it has been supposed that **quickening ganglia** exist is, that when irritation is applied to the vagus after its inhibitory power has been destroyed by the administration of nicotine or atropine it no longer produces slowness or still-stand of the heart, but, on the contrary, quickens its pulsations. But the **quickening** does **not** take place **immediately,** it only occurs some time after the application of the stimulus. If it is applied only for a short time, no quickening may take place until after its removal, but the quickening once induced remains for a considerable time. This seems to indicate that the stimulus does not act through nerve fibres, as these would conduct the stimulus directly to the muscle, but rather through some ganglionic apparatus. It has been supposed that this apparatus is not identical with the motor ganglia themselves, because, if the heart is irritated directly, its pulsations at once become quickened, and the quickening does not last long after the irritation is removed.

It is evident, however, that though this hypothetical schema allows us to explain in a fairly satisfactory manner the action of many drugs, yet it can only be looked upon in the same light as the hypothesis of cycles and epicycles in astronomy, which was useful for a time and enabled astronomers not only to recollect but to predict facts. Its use was only temporary, and the hypothesis just at the time of its greatest complication gave place to one of the greatest simplicity.

It is probable, indeed almost certain, that the same thing will occur in regard to the action of drugs upon the heart, and that the whole complication of motor ganglia, inhibitory ganglia, accelerating ganglia, vagus endings, and intermediate fibres may resolve themselves simply into a question of the mutual relationships between the rate of rhythm and rapidity of conduction in the muscular fibres, nervous ganglia, and nerve-fibres respectively. Schmiedeberg's hypothetical schema has been most useful for several years, but facts which it will not explain are beginning to accumulate, and we must look in another direction for their explanation. The whole question of the action of drugs upon the heart is far from being completely solved, but I shall try, if possible, to indicate the direction in which pharmacology is at present looking for an explanation.

For this purpose it will be necessary to go still more fully into the physiology of the heart than we have already done.

Before doing so, however, it may be advantageous to put in a



FIG. 81.—Diagram of the heart and vessels to illustrate the action of drugs on the various parts of the circulatory apparatus as given in the following tables. A, indicates accelerating ganglia.

tabular form the action of the most important drugs on the various parts of the circulatory apparatus, according to the prevalent opinions at present.[1]

[1] In drawing up this table [see pp. 274-277] I have been greatly aided by the admirable paper of Professor Boehm, read before the International Congress in London in 1881.

Vagus Centre.

STIMULATED BY.

[Stimulation is evidenced by slowing of the pulse, disappearing on section of the vagi.]

Increased blood-pressure.
Venous blood.
Ammonia (in frogs).
Carbonic oxide.
Chloroform.
Chloral hydrate.
Croton chloral.
Belladonna (atropine).
Hyoscyamus (hyoscyamine).
Stramonium (daturine).
Aconite (aconitine).
Veratrum viride (veratroidine).
Tobacco (nicotine).
Digitalis (digitalin).
Hydrocyanic acid.

DEPRESSED OR PARALYSED BY.

[Depression is evidenced by a quick pulse, which is not rendered slow by irritation of sensory nerves such as usually produce slowing of the pulse, *e.g.* the central end of one vagus.]

Diminished blood-pressure and substances which produce it, *e.g.* nitrite of amyl and other nitrites.

Large doses of such substances as stimulate it in small doses, *vide* adjoining list.

Accelerating Centre.

[Stimulation is evidenced by the injection of the drug after previous section of the vagi rendering the pulse still more rapid than before.]

Venous blood.
Ammonia.
Cicutoxine.
Caffeine.
Delphinine.
Picrotoxine.

[Little or nothing is known about the depression of the accelerating centres.]

Saponine paralyses accelerating nerves.

Vaso-motor Centre.

[Stimulation is evidenced by a rise of blood-pressure, which disappears on section of the spinal cord below the medulla, and does not occur if the cord has been divided before the injection of the drug. This rule is only partially true, because subsidiary vaso-motor centres occur in the spinal cord itself.]

Salts of ammonia.
Potassium (?).
Caffeine (?).
Cicutoxine.
Delphinine.
Picrotoxine.
Strychnine.
Digitalin (?)
Sanguinaria.
Thebaine.
Veratrine.
Ergot.
Belladonna (atropine.)
Hyoscyamus (hyoscyamine).
Stramonium (daturine).
Carbolic acid (?).
Salicylic acid.
Ether (?). Chloroform (?). Chloral (?). Croton chloral (?). — Stimulant action doubtful, slight, and transient.
Turpentine.
Camphor (rhythmically).
Oil of rosemary, and other ethereal oils.

[Depression is evidenced by fall in the blood-pressure not depending on failure of the heart's action. It is also shown by the absence of rise in blood-pressure, or irritation of sensory nerve.]

Carbolic acid.
Lobelia.
Large doses of most drugs, such as those in the adjoining column, which stimulate in small doses.
Depression usually occurs in the later stages of the action of such drugs even in moderate doses.

Vagus-ends in the Heart.

STIMULATED BY.	DEPRESSED OR PARALYSED BY.
[Stimulation either of the ends of the vagus in the heart or of the inhibitory ganglia is shown by the injection of a drug rendering the pulse slow after previous division of the trunks of the vagi.]	[Depression or paralysis is shown by irritation of the vagus trunk no longer producing slowness or stoppage of the pulsations of the heart, while the application of muscarine, or irritation of the venous sinus, will still cause stoppage.]
Physostigma (?).	Nicotine.
It is said to render the peripheral ends of the vagus more sensitive, so that a slighter stimulus will stop the heart applied to the trunk.	Curare, methyl-strychnine, and probably all other poisons which paralyse motor nerves.
	Saponin.
	Lobeline.
	And, probably, by large doses of all drugs which have the power of paralysing the ends of motor nerves.

Inhibitory Ganglia.

[Stimulation is shown by the direct application of the drug to the heart, stopping its spontaneous pulsations completely, while it still contracts on the application of a stimulus either mechanical or electrical.]	[Depression or paralysis is shown by stimulation, not only of the vagus trunk but of the venous sinus itself, having lost all power to slow or stop the heart; and by the direct application of muscarine, also having no action.]
Muscarine.	Atropine.
Pilocarpine.	Hyoscyamine.
	Daturine.
	Sparteine.
	Duboisine.
	Saponin.

Motor Ganglia.

[Stimulation is shown by increased rapidity and energy of contraction, which is observed, not only when the drug is given to an animal, but when it is applied directly to the heart.]	[Depression is evidenced by slower and less powerful pulsations, with final stoppage in diastole. This stoppage is shown to be due to the action of the drug on the ganglia, and not on the cardiac muscle by the heart contracting on stimulation, either mechanical or electrical, after spontaneous pulsation has ceased.]
Guanidine.	Ergot.
Alcohol.	Antimony (?). The stoppage in diastole caused by antimony is converted into stoppage in systole by helleboreine.
Ether.	
Chloroform.	Hydrocyanic acid.
Chloral.	
Anæsthetics generally.	
Cyanogen.	
Arsenic.	
Quinine.	

The same drugs that stimulate in small doses depress when used in larger quantity, or at a later stage of their action.

Cardiac Muscle.

STIMULATED BY.

[Stimulation is shown by increased energy of contraction, the rate of pulsation remaining the same or becoming slower.]

So-called cardiac poisons. With a larger dose the stage of stimulation is followed by one of peristaltic action, and final arrest in systole.

- Digitalin.
- Digitaleïn.
- Digitoxin.
- Erythrophleum.
- Helleboreïne.
- Nereïn (Oleander).
- Scillaïn.
- Antiarïn.
- Strophanthus hispidus.
- Thevetine.
- Theveresine.

- Veratrine.
- Barium salts.
- Caffeine (produces rigor).
- Potassium salts.
- Copper double salts.
- Zinc double salts.

These do not cause peristalsis, nor arrest in systole. They excite the heart to pulsate rhythmically, after it has been made to stand completely still in diastole by the application of muscarine.

- Guanidine.
- Physostigmine.
- Camphor.
- Monobromocamphor.
- Borneol.
- Arnica-camphor.
- Aniline sulphate.
- Cumarine.

This stoppage of the heart in systole occurs in frogs, but in higher animals the heart may stop in diastole.

DEPRESSED OR PARALYSED BY.

[Depression is shown by diminished energy of contraction with final stoppage in diastole. The cardiac muscle is shown to be paralysed by no longer contracting on stimulation, either mechanical or electrical.]

- Salicylic acid.
- Potassium salts.
- Copper double salts.
- Zinc double salts.
- Quinine (?).
- Saponin (removes the systolic still-stand produced by digitalin).
- Apomorphine.
- Emetine.
- Muscarine.
- Pilocarpine.
- Veratrum viride (veratroidine and jervine).

Vaso-motor Nerves.

[It is very doubtful whether they are stimulated by drugs, and at any rate it is very difficult to ascertain whether any stimulation which may occur in the arterioles or capillaries is in the terminations of the vaso-motor nerves or in the muscular walls.]

[Paralysis is shown by the vessels not contracting on stimulation of the vaso-motor nerves, while they still contract on direct stimulation. This has been chiefly observed in the vessels of the intestines after irritation of the splanchnic nerves. The effect of irritation is ascertained by the alterations in colour of the intestine, and also by the alterations in the general blood-pressure which occur after irritation.]

- Potassium salts.
- Arsenic.
- Antimony.
- Mercury.
- Iron.

Capillaries.

STIMULATED BY.	DEPRESSED OR PARALYSED BY.
[Stimulation is shown by a rise in blood-pressure which remains after section of the spinal cord at the occiput, and is produced by the injection of the drug after previous division of the cord. It is also ascertained by the rate of flow through the vessels being diminished by the drug when circulation is kept up artificially in a frog whose nerve-centres have been destroyed, or in a single limb of a warm-blooded animal.]	[Depression is shown by fall of blood-pressure to a slight extent, even after the spinal cord has been divided, and by increased rapidity of flow when artificial circulation is kept up.]
Alkalis.	Acids.
Digitalis and its allies.	Nitrites.
Barium salts.	Quinine (?).
Potassium salts.	
Copper.	
Zinc, &c.	

Stannius's Experiments.

Some of the most important experiments relating to the action of the various cavities of the frog's heart were first performed by Stannius, and bear his name.

When the venous sinus is separated from the rest of the heart by cutting it off with a sharp razor, or by a ligature tightly drawn round it at its junction with the auricle, it continues to pulsate, but the auricle and ventricle stand perfectly still (*a*, Fig. 82). If now the auricle is separated from the ventricle by another cut (*b*, Fig. 82), or another ligature be applied (*c*, Fig. 82), at the auriculo-ventricular groove, the auricles remain motionless, but the ventricle begins to



FIG. 82.—*a*, diagram of frog's heart ligatured at the junction of the venous sinus with the auricles. The venæ cavæ and sinus are represented with a crenated outline resembling the tracing which their beats might give if recorded on a revolving cylinder. The auricle and ventricle being motionless would only trace a straight line if connected with a recording apparatus. Their outline is therefore represented by a straight line. *b*, diagram of a frog's heart in which sections have been made at the junction of the sinus with the auricles, and at the auriculo-ventricular groove. The sinus and ventricles pulsate, whilst the auricles remain motionless. The beats of the ventricle should have been represented as slower than those of the auricle as in *f*, Fig. 83. *c*, the same as *b*, but with the parts of the heart separated by ligature instead of section.

beat, so that the venous sinus and ventricle are both pulsating, while the auricles are at rest. The venous sinus and the ventricle, however, no longer beat with the same rhythm, and the rate of the ventricular beats is usually much slower (*f*, Fig. 83). In this remarkable experiment the complete stoppage of the auricles and ventricle which follows the removal of the venous sinus has been supposed to show that the motor centres for the entire heart reside in the sinus, and that from them the motor impulses originate which keep up the rhythmical pulsations of the organ. But the fact that the ventricles begin to pulsate on their own account when separated by another cut from the auricle seems to show that they also contain motor centres. The hypothesis has therefore been advanced that both venous sinus and ventricles contain motor centres, while the auricles contain inhibitory centres.

So long as the auricles are in connection both with the venous sinus and the

ventricle, the motor centres in the latter two cavities are supposed to be sufficiently powerful to overcome the resistance offered by the inhibitory centres, and thus the cardiac rhythm is maintained. When the motor centres of the sinus are removed, the inhibitory centres of the auricle are supposed to be so powerful as to keep both it and the ventricle in a state of rest.

When the ventricle is separated from the auricles and their inhibitory influence removed, it again begins to pulsate rhythmically. In order to obtain a clearer idea of the mechanism of the heart, many variations of the above fundamental experiments have been made.

The chief results of these are the following :—

First, section or ligature of the venæ cavæ or of the venous sinus at any point before its junction with the ventricle does not affect the action of the heart (*d*, Fig. 83).

Second, section or ligature of the auricles at any point above the auriculo-ventricular groove arrests the movements of the part below them, while that connected with the venous sinus still continues to pulsate (*e*, Fig. 83).



FIG. 83.—*d*, diagram of a heart with ligature round the venous sinus. *e*, diagram of heart with ligature round middle of auricles. *f*, diagram of heart with ligature in the auriculo-ventricular groove. The pulsations of the ventricle are much slower than those of the auricle and venous sinus. This is indicated by the larger dentation of the outline of the ventricle.

Third, irritation of the vagus nerves usually produces stoppage of the heart-beats.

Fourth, ligature or section of the vagi before their entrance into the heart prevents their having any action upon it when they are stimulated.

Fifth, ligature or section of the venous sinus or auricles prevents any action of the vagi upon the part of the heart below the ligature or section.

It is evident that section or ligature of the heart at any point between the junction of the sinus and auricles and the auriculo-ventricular groove has the same action on the movements of the part below it as irritation of the vagus.

But more than this, although, as we have seen, the motor ganglia of the heart appear to be situated chiefly in the venous sinus, yet **irritation of the sinus** produces **complete still-stand** of the heart, even more perfect and prolonged than irritation of the vagus. Strong stimulation of the venous sinus has therefore the same effect as its removal. The parts whose motions have been arrested



FIG. 84.—*g*, diagram of heart stopped by a ligature at the junction of the sinus and auricles. The *outside* of the ventricle is irritated by a needle, and the even outline indicates that no contraction occurs. *h*, diagram similar to *g*, but with the *inside* of the ventricle irritated by a needle. The projections on the outline of the heart indicate that one contraction of the ventricle and three or four of the auricles occur. *k*, diagram similar to *g* and *h*, but with the outside of the auricle stimulated by a needle. The projections indicate that one contraction of the auricle and one of the ventricle occur.

by section or by irritation, in the experiment just described, are not paralysed: this is shown by the effect of stimulation upon them.

When the auricles and ventricle are standing still after section or ligature

of the venous sinus, **irritation** of the outside of the ventricle with a needle has no action (*g*, Fig. 84); but if its interior be irritated by a needle (*h*, Fig. 84), the auricle contracts first, then the ventricle, then the auricle again two or three times, but the ventricle does not respond. When the auricle is irritated by a needle applied to its outside, contraction both of the auricle and ventricle ensues (*k*, Fig. 84). When the auriculo-ventricular groove is irritated by a needle there are usually eight or ten contractions in response. When the outside of the auricle is irritated by an interrupted current, numerous and rhythmical contractions both of auricle and ventricle ensue.

To sum up these results shortly, we find that either **removal of** the normal **stimuli** which pass in the direction of the circulation from the venous sinus to the auricle and then to the ventricle, or abnormally **strong stimulation,** produces arrest of the rhythmical movements of the heart, or, as it is usually termed, **inhibition.**

Some exceedingly instructive experiments have been made by Gaskell, who, instead of separating the cavities of the frog's heart from each other by sections or by a ligature, compresses more or less completely the point of junction, so as to impede to a certain extent the transmission of stimuli from one cavity to another.



FIG. 85.—Diagram to illustrate Gaskell's experiment. At *a* the jaws of the clamp hold the heart without compressing it, and each beat of the auricle is succeeded by one of the ventricle as shown by the figure $\frac{I}{I}$. At *b* the heart is compressed, and its rhythm disturbed, so that one beat of the ventricle only occurs for several of the auricles.

He does this by a clamp the two limbs of which are placed one on each side of the heart. By means of a micrometer screw their edges can be approximated so as either simply to hold the heart without pressure or to compress it to any desired extent. When the clamp is placed in the auriculo-ventricular groove, the beats of the auricles and ventricle are registered separately by levers above and below the clamp with which the auricles and ventricle are connected by threads.

When the heart is simply held by the clamp without compression, each beat of the auricle is followed by one of the ventricle; but when the auriculo-ventricular groove is compressed the transmission of stimuli from the auricle to the ventricle appears to be blocked in somewhat the same way as it is by compression in the contractile tissue of medusæ, and one beat of the ventricle then occurs with every second, third, fourth, or more auricular beats, according to the degree of pressure, and if this be very great the ventricle will cease beating altogether.

The beats of the ventricle are shown in this experiment to be diminished or arrested by hindering or blocking the transmission of stimuli to it from the venous sinus and auricle. But, as one might expect, a diminution of the stimuli themselves has a similar effect as a block to their passage. Thus, if the auricle and sinus are heated, but not the ventricle, their rhythm is markedly quickened, but the ventricle now beats only once for every two or even more pulsations of the auricle, the heat appearing to render the impulses proceeding from the auricle and sinus more rapid but more weak. If the ventricle be heated as well, it will respond to each beat of the auricle, so that the whole heart beats more quickly, but if the ventricle alone be heated its rhythm remains unchanged.

Experiments which are likely to give useful information in regard to the action of various drugs on the cardiac muscle and nerves have been made by Gaskell by the aid of the clamp already described.

General Considerations regarding the Heart.

In ascidians the heart is a mere contractile sac open at both ends, and drives the fluid alternately in opposite directions. In snails it is a simple sac of protoplasm without differentiated nerves, but drives the nutritive fluid in one direction. In the amphioxus there is no special heart, but only numerous contractile dilatations in the chief blood-vessels. In fishes the heart may be said to consist of three parts—the auricle, ventricle, and arterial bulb. The heart of the frog has already been described, and that of mammals requires no description.

Even the complicated mammalian heart may be regarded as a special development of the simple contractile tube endued with the power of peristaltic contraction. The direction in which the contraction occurs is probably determined at first by slight differences in the stimuli to which the two ends of the tube are subjected, and the direction may be altered by altering the stimulus. Thus in the heart of a fish the contraction usually proceeds from the auricle to the ventricle and bulb, but by irritating the bulb the direction may be reversed so that the bulb contracts first and the auricle last, and this reversal of rhythm may persist for some time.[1] In the mammalian heart it is not perhaps so easy to reverse the rhythm by simple irritation, and probably some interference with the cardiac nervous system is also requisite, but by introducing tincture of opium into the mammalian ventricle the rhythm may be reversed so that the beats of the auricle follow instead of preceding those of the ventricle.[2]

The **cause of rhythmical pulsation** in the heart is usually supposed to be the motor ganglia which it contains. Of late years numerous researches have shown that, although these are very important indeed, yet they are not to be looked upon as the exclusive originators of the rhythm. The heart of the snail, although it consists of simple protoplasm without nerves, beats rhythmically, and when a ligature is tied across the venous sinus in the frog the venæ cavæ and upper part of the sinus continue to beat although they possess no special ganglia, while the rest of the heart remains motionless although it contains both Bidder's and Remak's ganglia. From this experiment one would be inclined at first to say that the **initiation of rhythm** in the heart is due to the **muscular tissue** of the venæ cavæ and sinus, and might be inclined to regard the **nervous system** of the heart as an apparatus for **merely conducting** stimuli from the sinus to the auricles and ventricle.

Other experiments would seem to deprive the nerves even of this function, for Engelmann[3] and Gaskell have shown that when Bidder's ganglia are excised, or the nerves cut through as they traverse the auricles, contractions still pass from the venous sinus to the ventricle, and continue to do so when the nerves have not only been divided but most of the muscular tissue of the auricle has been cut through and only a narrow bridge remains behind. This may seem to prove that the muscular tissue of the heart conducts the motor stimuli from the venous sinus to the auricle and ventricle, which cause them to contract, and may appear to show that the cardiac nerves are entirely superfluous. A similar mode of reasoning, however, would lead us to say that the ganglia in medusæ are also superfluous because the contractile tissue will pulsate rhythmically after they have been cut off, if it be placed in acidulated water.

In regard to the **conduction of stimuli**, the fact probably is that under favourable conditions they may be conveyed by the muscular tissue alone from the sinus to the ventricle, but under ordinary circumstances, they are conveyed in part, at least, by the nerves.

[1] Gaskell, *Journ. of Physiol.* vol. iv. p. 78.
[2] Ludwig, *Physiologie*, 1861, vol. ii. p. 88.
[3] Pflüger's *Archiv*, xi. p. 465.

Ganglionic tissue is more sensitive than contractile tissue, and the stimuli which act on the ganglia of the medusa, under the conditions in which it lives, are insufficient to excite contractile tissue. When the ganglia are paralysed by a poison, the effect is the same as if they were cut off, and pulsation is arrested. A similar condition appears to occur in the ventricle. The muscular tissue forming the apex of the frog's heart under ordinary circumstances will not beat when separated from the rest unless an extra stimulus be applied to it. The ventricle containing Bidder's ganglia will usually pulsate rhythmically, and if its apex be dipped in a solution of chloral no effect is produced, but if its base be dipped in the solution so that the drug acts upon the ganglia, the pulsations are arrested apparently by paralysis of the ganglia (Harnack).

We may consider then that ganglia are more susceptible to stimuli than muscular fibre, and have the function of making it pulsate rhythmically when it otherwise would not.

It is probable also that they serve to prevent the occurrence of blocks at the junction between the different cavities of the heart which might occur if the stimuli were transmitted from each cavity by muscular tissue alone.

When the **heart** is **dying,** and when we may fairly assume that its nerves are losing their functional activity, such blocks actually take place, and the ventricle may beat only once for every two or three or more beats of the auricle.

The cardiac muscle is also without doubt losing its functional activity, yet it still retains it to such an extent that each cavity can contract powerfully. The same thing occurs when the heart is poisoned with chloral, iodal, or other members of the same group, which, as already mentioned, paralyse the cardiac ganglia.[1]

In the present state of our knowledge it is difficult to make any absolute statement regarding the function of the **cardiac ganglia,** but I think we may fairly assume them to have two **functions,** (1) to originate rhythmical pulsations in the heart when the muscular fibre alone, although capable of independent rhythmical pulsation, would not pulsate under the conditions which may be present; (2) to transmit and receive stimuli from one cavity of the heart to the other, and thus prevent the occurrence of blocks at the junction of the cavities and consequent irregular action which might occur if the stimuli were transmitted only by the muscular fibre.

Regulating Action of the Nervous System.

The necessity of some means for regulating the action of the heart in accordance with the wants of the body is obvious, and in the heart we find that such an arrangement exists in relation both to the strength and rate of pulsation.

The **action of the vagus** upon the heart has long been a matter of great dispute, some physiologists holding it to be the motor nerve of the heart, while the majority regard it as inhibitory. The reason of this disagreement probably is that the right and left vagi have frequently different effects upon the heart, and that the effects even of the same vagus may vary according to the state of nutrition of the heart and other circumstances. We find for example in rabbits that both the right and left vagi can usually slow or stop the heart; but sometimes the right has much greater power in this respect than the left, and in some species of tortoise the left vagus has no inhibitory action upon the heart at all. A number of experiments made by Gaskell on the heart *in situ* and with the clamping apparatus already mentioned, by which the beats of the auricle and ventricle may be simultaneously recorded, have led him to divide the effects produced on the heart by irritation of the vagi into two types: (*a*) affections of the **rate** of rhythm; and (*b*) affections of the **strength** of the contractions.

The effects of vagus stimulation on the heart of the frog may thus be divided into five classes.

[1] Harnack and Witkowski, *Arch. f. exp. Path. und Pharm.* vol. xi. p. 15.

The 1st class is that which occurs with the heart of the tortoise or frog *in situ* or just after their removal from the body. The vagus here causes arrest by **slowing** the rate of **rhythm**; and, in consequence, the first beats which occur after the heart again begins to beat are slower than those preceding the stimulation.

In the next classes the vagus produces its effect by **weakening** the **strength** of the contractions so that they may become invisible and the heart remains still, but after it begins to beat their rate is as quick or quicker than before.

The 2nd class is an example of this. In it irritation of the nerve produces complete stoppage of both auricles and ventricles. This is followed by contractions, which are at first so small as to be hardly visible, but quickly grow larger until they are much greater than the normal; from this they gradually decrease to the normal size (Fig. 86).



FIG. 86.—After Gaskell. Tracing showing the action of the vagus on the heart. *Aur.* indicates the auricular, and *Vent.* the ventricular tracing. The part included between the upright lines indicates the time during which the vagus was stimulated. *C.* 8 indicates that the secondary coil used for stimulation was eight centimetres distant from the primary. The part of the tracing to the left hand shows the regular contractions of moderate height before stimulation. During stimulation, and for some time after, the movements of both auricle and ventricle are entirely arrested. After they again commence they are small at first, but soon acquire a much greate amplitude than before the application of the stimulus.

The two types of action may occur together, the rhythm becoming slower and the contractions smaller. This is seen in Fig. 87.



FIG. 87.—After Gaskell. Tracing showing diminished amplitude and slowing of the pulsations, without complete stoppage, during irritation of the vagus.

The 3rd class is where irritation produces no still-stand of either auricles or ventricles, but only great diminution in the size of the beats, followed by a gradual increase and subsequent fall similar to that just described. This curve is like the first, but differs from it in the absence of the complete arrest (Fig. 88).

The 4th is that where there is no primary diminution, but gradual increase in the size of the beats, which again sink to the normal (Fig. 89).

The 5th is where irritation of the vagus does not stop the beats of the venous sinus but causes both auricles and ventricle to stop.

The ordinary inhibitory effect of the vagus is the one which is noticed best in well nourished hearts, and as the heart becomes more exhausted and is dying, the motor power of the vagus becomes more and more pronounced. We

find a similar occurrence in the case of the splanchnics, which lose their inhibitory power as the intestine dies. Nervous structures as a rule die sooner



FIG. 88.—After Gaskell. Tracing showing diminished amplitude of contraction without slowing o stoppage during irritation of vagus.

than muscle, and the conclusion is not unwarranted that the disappearance of the inhibitory action of the vagus is due to a gradual death of the nervous



FIG. 89.—After Gaskell. Tracing showing increased cardiac contractions from irritation of the vagus. [In this figure the upper tracing shows the ventricular and the lower the auricular contractions.]

structures upon which it acts in the healthy heart, while its action on the muscular tissue, which has a more prolonged vitality, still remains. The actual increase, indeed, in its motor action we may attribute to the removal of nervous interference.

Hypothesis regarding the Action of the Vagus.—Nervous interference as a cause of inhibition was clearly pointed out by Bernard, and in the case of the heart has been discussed by Ranvier with his usual clearness.

In the grey matter of the spinal cord there is ample room for the slowing of nervous stimuli by transmission along paths of different lengths (p. 139), more especially as a small length of grey matter is equivalent to a great length of ordinary nerve fibre (p. 131).

In the heart we might suppose there was no such provision, but, as Ranvier points out, the ganglion cells in the auricle have one of their fibres wound spirally,



FIG. 90.—Part of the posterior cardiac nerve, more highly magnified, showing the ganglia (Ranvier, *op. cit.* p. 106.)



FIG. 91.—Spiral ganglion cell from the pneumogastric of the frog. This figure is not taken from the cells in the cardiac nerves, as in them the connection between the spiral and straight fibres has not been clearly made out, but it is probable that these cells have a structure similar to the one figured (Ranvier, *op. cit.* pp. 114–20). *a* is the cell-body, *n* the nucleus, *r* the nucleolus, *d* nucleus of the capsule. *f* the straight fibre, *g* Henle's sheath, *sf* spiral fibre, *g'* its gaine, *n* nucleus of Henle's sheath (Ranvier, *op. cit.* p. 114).

so as to give a great length in small space, and thus provide for retardation and interference of stimuli. If we suppose that some of the fibres of the vagus pass through these spiral ganglia while others pass on directly to these ganglia, we can understand that the different rates of transmission may lead to interference and stoppage of pulsation. Alterations in the rate of transmission along the spiral fibre may again convert interference into coincidence of waves and cause acceleration and increased action as in Gaskell's experiments just described. If these spiral fibres are affected by drugs so that the rate of transmission of stimuli along them is altered, we can understand that the interference may in some cases be increased, in others diminished, and that an increase of interference may readily pass into the opposite condition, so that irritation of the vagus no longer produces stoppage but acceleration of the heart, such as actually occurs on irritation of the vagus after its inhibitory power has been paralysed by atropine.

We can understand also how curare and the large class of drugs which paralyse the motor nerves may destroy the inhibitory power of the vagus.

Inhibition in the Heart.—But it is probable that interference between the nervous structures is not the sole cause of inhibition in the heart, we must look also to the relationship between nervous and muscular rhythms. Thus distension of the ventricle frequently diminishes or abolishes the action of the vagus, the stimulus which the pressure within the heart exerts on the muscular fibre appearing to more than counteract the inhibitory action of the nerve. The condition of the muscular fibre too is probably very important. Thus, feeding the frog's heart with a solution containing soda appears to paralyse the power of the vagus, which is again restored by potash.

It is indeed to an action on the muscle rather than on the nerve that we must probably look for the explanation of the action of atropine. For the heart in snails, though apparently destitute of both ganglia and nerves, is arrested by an interrupted current. This effect is prevented by atropine.

It is exceedingly difficult, or perhaps impossible, with the physiological data which we at present possess, to give a complete and satisfactory explanation of the action of drugs on the heart, but it is evident that while all new discoveries tended for a while to render our ideas regarding the cardiac mechanism more and more complicated, our increasing knowledge now tends to render our ideas more simple. Before long we may hope that systematic investigations into the action of drugs on the excitability, rhythm, and power to conduct stimuli of the cardiac muscle itself; on the action of drugs upon the rhythm of the ganglia, and on the rate of transmission by the nerves, as well as on the mutual relations of these various factors, will at last give us a clear understanding of this very difficult and complicated subject.

Therapeutic Uses of Drugs acting on the Circulation.

The drugs which act on the circulation have been divided according to their action into stimulants, tonics, and sedatives. Each of these classes has been further subdivided into cardiac and vascular, according as its members act on the heart and vessels. There are thus six subdivisions in all: cardiac stimulants, vascular stimulants, cardiac tonics, vascular tonics, cardiac sedatives, and vascular sedatives.

Cardiac Stimulants.

These are substances which rapidly increase the force and frequency of the pulse in conditions of depression. The most important are ammonia, and alcohol in its various forms, but there are also other substances which are sometimes useful :—

Heat.

Liquor ammoniæ. B.P. Aqua ammoniæ. U.S.P.
Ammonium carbonate.
Sal volatile (spiritus ammoniæ aromaticus).
Alcohol.
Brandy.
Whisky.
Eau de Cologne.
Gin.
Liqueurs.
Strong wines.
Atropine.
Ether.
Chloroform.
Spirit of chloroform.
Spirit of ether.
Camphor.
Aromatic volatile oils.
Oil of turpentine.
Heat and counter-irritants to the præcordium.

Cardiac stimulants are used to prevent or counteract sudden failure of the heart's action in syncope or shock due to mental emotion, physical injury, or poisoning by cardiac depressants, or by the bite of snakes, or when the action of the heart becomes much depressed in the course of fevers or other diseases.

Although alcohol after its absorption stimulates the heart, yet its effect on the heart is probably, to a considerable extent, due to a reflex action on it through the nerves of the mouth, gullet, and stomach. Its action is consequently very rapid, and begins before there has been time for much of it to be absorbed. On this account, however, it must be given in a somewhat concentrated form, and if much diluted, as in the form of weak wine or beer, which has little or no local action and can exert no reflex action, it has little or no power as an immediate stimulant. When given in disease it is best to administer it in small quantities frequently, and the rule by which to ascertain whether it is doing good or not is: Does it bring the circulation more nearly to the normal or not? If it does so it is beneficial; if it does not, it is harmful. Thus, if the pulse be too quick, alcohol should render it slower; if already abnormally slow, alcohol should make it quicker. If too small, soft, and compressible, alcohol should render it larger, fuller, and more resistant. There are other rules connected with the effect of alcohol on other organs which also regulate its use in disease, but these will be given further on.

Ether alone or mixed with alcohol has a stimulant action almost

more rapid than alcohol itself; and chloroform in small doses, and especially when mixed with alcohol, is also a powerful stimulant.

Ammonia has not only a reflex action on the heart like that of alcohol, but has powerful stimulating action on the vaso-motor centre. Its action when applied to the nose in syncope has already been discussed. In cases of snake-bite thirty minims of liquor ammoniæ have been injected directly into the veins. The immediate stimulating effect appears to be beneficial, although it is doubtful whether life can really be saved by this means.

Camphor is useful as a cardiac stimulant in febrile conditions with tendency to failure of the circulation, as in typhus and typhoid fevers; in exanthemata, when the rash does not appear; in asthenic pneumonia, and in the typhoid condition depending on other diseases.

Aromatic volatile oils and substances containing them have also been used in similar but less severe conditions.

One of the most powerful of all cardiac stimulants is heat, and when the heart's action threatens to fail it may be frequently restored by warm fluid taken into the stomach, or by the application of an indiarubber bag[1] or bottle filled with hot water, or of a bag filled with hot sand or salt, or of a hot poultice to the cardiac region.

Vascular Stimulants.

These are substances which cause dilatation of the peripheral vessels,[2] and thus render the flow of blood through them more rapid. The most important are:

Heat.

Alcohol in its various forms.
Ether.
Nitrous ether.
Dover's powder.
Acetate of ammonia.

Alcohol and ether, by stimulating the heart at the same time that they dilate the vessels, render the peripheral circulation very vigorous. From its stimulant action on the vaso-motor centre, ammonia is less useful than alcohol.

[1] An indiarubber bag for holding hot water is one of the most useful things an invalid can carry about with him. It should have a flannel case fastened by buttons so that it can easily be removed. This allows the heat to come gradually through without burning the skin. For a small gratuity the engine driver or stoker is usually willing to fill the bag with hot water, and the bag can be refilled if necessary at each station where there is a sufficiently long stoppage. This is sometimes a very great boon to invalids on long railway journeys such as they are often compelled to make on their way to winter health resorts.

[2] From this definition it will be observed that while cardiac stimulants increase the functional activity of the heart, vascular stimulants do not increase the contractile power of the vessels, nor the activity of the vaso-motor centre, but on the contrary diminish the contraction of the vessels.

Vascular stimulants are useful in equalising the circulation and preventing congestion of internal organs. Thus, from exposure to cold generally so that the whole surface of the body is chilled, or from a local chill due to a draught, or to the combined action of cold and moisture, as in wet feet, congestion of the respiratory tract, or of the stomach, intestines, or pelvic organs may occur. This frequently evidences itself immediately either by rigors or by localised pain. If the congestion be not relieved inflammation may occur, but if alcohol be taken either in a concentrated form or diluted with boiling water, the vessels of the surface dilate, a warm glow is felt throughout the body, the shivering and pains disappear, and frequently all injurious results of the chill are averted. If the external cold, however, is very excessive, and the exposure is to be prolonged, alcohol must be used with great care, as the blood becomes much more rapidly cooled when the cutaneous vessels are dilated than when they are contracted, and in arctic temperatures a person is much more readily frozen to death after the free use of alcohol. Dover's powder is also a useful vascular stimulant, though less powerful and rapid than alcohol. It is of use in similar cases to those just described, and may be given after the alcohol to supplement and continue its action.

Slighter cases of chill may be treated by Dover's powder alone, and ten grains of it taken at night will often cut short commencing coryza, and will frequently prevent slight increase of consolidation occurring round a cavity after a chill in persons suffering from phthisis. Patients suffering from this disease should not omit to take a Dover's powder or some other vascular stimulant at night whenever they feel as if they had caught cold, and before any local mischief can be detected.

All nitrites dilate the blood-vessels and thus act as vascular stimulants. The one most commonly employed is nitrite of ethyl in the form of spirits of nitrous ether. This remedy, taken in hot water or along with acetate of ammonia, is a useful vascular stimulant, and is often used for the same purposes as Dover's powder.

Camphor is frequently used as a popular remedy instead of alcohol or Dover's powder in order to cut short coryza or catarrh, about ten drops of the tincture being taken on a piece of sugar. Local vascular stimulation is useful in removing chronic inflammation or consolidation. For a more detailed account of its action and uses, *vide* Irritants and Counter-irritants, p. 298.

Cardiac Tonics.

These are drugs which have no perceptible immediate action on the heart, but when given for a little while render its beats much more powerful, although usually much slower. The most important of them are :—

Digitalis.
Digitalin.
Digitalein.
Digitoxin.
Erythrophlœum (Casca)
Erythrophlœin.
Strophanthus hispidus.
Strophanthine.
Convallaria majalis.
Convallamarin.
Adonis vernalis.
Adonidin.
Squills.
Scillaïn.
Helleboreïn.
Antiarin.
Caffeine.
Nux vomica.
Strychnine.

All these drugs, as already mentioned, stimulate the cardiac muscle and render its contractions slower and stronger. Although in large doses they tend themselves to produce irregular and peristaltic contraction of the heart, yet in moderate doses they tend to remove irregularity already present. The cases in which they are most useful are those in which the left ventricle is unable to drive the blood with sufficient force into the aorta. It is evident that this inability may depend on simple weakness of the ventricle without any valvular lesion, or upon irregular action of the various cavities, or upon valvular lesions, or on a combination of two or more of these conditions.

Weakness of the heart may occur in cases of general malnutrition, as anæmia and chlorosis, or in consequence of acute disease such as fevers. It is not necessarily accompanied by dilatation, but if it continues for some time the cavities are apt to dilate. A considerable amount of dilatation may sometimes occur without leading to valvular incompetence, but if it proceeds beyond a certain point the cusps of the tricuspid and mitral valves become insufficient to close the dilated orifices, and mitral or tricuspid regurgitation is the result. For it must be remembered that in the healthy heart the tricuspid and mitral orifices are much diminished in size by the contraction of the muscular tissue of the heart at the moment of systole.

In cases where the mitral valve is thus affected, a systolic murmur may be heard at the apex during life, but, should death occur, the valves may be found perfectly competent to close the mitral orifice in the heart, which is then in a state of more or less complete rigor. In all such cases of weakness of the heart, either with or without dilatation and functional incompetence of the valves, digitalis is of the greatest possible service. I have also found erythrophlœum give most satisfactory results in simple dilatation without incompetence.

The form of valvular disease in which cardiac tonics are especially useful is mitral regurgitation. In all forms of valvular disease there is a tendency to the occurrence of compensatory hypertrophy, which will enable the heart to do its work in spite of

the hindrance caused by the disease. Wherever this is sufficient so that the circulation is well carried on, notwithstanding the valvular defect, cardiac tonics are useless and likely to be injurious. Nor should they be given when the compensatory hypertrophy is just beginning to take place. But when compensation is insufficient, cardiac tonics are of the very highest value. In mitral regurgitation the blood, instead of being driven entirely onwards by the left ventricle into the aorta, is partially driven backwards into the left auricle at the very moment that the right ventricle is driving the blood into the pulmonary artery and lungs. Hence there is a tendency to pulmonary congestion, which may lead to hæmoptysis. The right ventricle having to work against greatly increased pressure tends to dilate, the blood accumulates in the venous system generally, and venous congestion of the stomach leads to loss of appetite, of the kidneys to albuminuria, and of the limbs to anasarca. While the venous system is gorged, the arterial is correspondingly empty, and it is not only the stomach, kidneys, and limbs which suffer by the stagnation of the circulation, for a similar condition exists in the heart itself. In consequence of this its action may become not only weak but irregular, and matters go on from bad to worse.

In such a condition cardiac tonics are of the greatest possible service. By increasing the strength of the cardiac muscle they not only enable the left ventricle to drive a larger proportion of blood into the aorta, but they actually tend to lessen the opening of the mitral orifice in the same way as in functional incompetence. By rendering the pulse less frequent they allow the ventricle to become more completely filled during each diastole. The pressure on the lungs, right side of the heart, and venous system, is diminished, the arterial system becomes correspondingly filled, the congestion of the various organs is diminished and their function correspondingly improved.

The consequence of this is, that in the stomach we have increased appetite, in the kidneys diminished albumen, and in the limbs removal of anasarca. The heart also benefits by the improved circulation in it, its pulsations are more regular and powerful, and it will often continue to act well and carry on the circulation satisfactorily even after the tonics which first enabled it to do so have been discontinued.

In mitral stenosis cardiac tonics probably are beneficial both by lengthening the diastole and thus allowing more time for the blood to run out of the auricle into the ventricle, and by strengthening the auricle itself. Besides this, mitral stenosis is usually accompanied by mitral regurgitation which will be benefited by cardiac tonics in the way just described.

In aortic stenosis digitalis is of little or no use when there is sufficient compensatory hypertrophy, but may be useful if the heart is becoming feeble.

There has been considerable difference of opinion regarding the use of digitalis in aortic regurgitation, some holding it to be useful and unattended with any risk, while others regard its administration as attended with considerable danger. In considering this question we must bear in mind that the risks which a patient runs from aortic regurgitation are not the same in all stages of the disease. While the aortic regurgitation is uncomplicated, and the ventricle strong enough to carry on the circulation, the risk to the patient is that of sudden death by syncope.

It is easy to understand how this should be the case. When the aortic valves are healthy the arterial system may be regarded as a large-branched tube open only at one end—the capillaries—and through these the blood flows so slowly that there is no risk of syncope from the blood-pressure falling too low (Fig. 92, *a*).



FIG. 92.—Diagram to illustrate the tendency to syncope in aortic regurgitation. In *a* the aortic valves are healthy and prevent regurgitation. The carotid and its branches are shown as full. In *b* there is aortic regurgitation, the blood flows out of the arterial system through the capillaries and into the heart. The carotid and its branches as shown are empty. In *c* the condition is the same as in *b*, but the patient is supposed to be in the recumbent posture, and the carotid and its branches remain full.

In a case of aortic regurgitation, on the contrary, the arterial system is open at both ends, and during the cardiac diastole the blood is not only running through the capillaries, but is running backwards into the left ventricle, so that the conditions are favourable for the blood-pressure falling so low as to induce syncope (fig. *b*). It is evident that anything which prolongs the diastole, and thus allows more time for the arterial system to empty itself through the capillaries at one end and into the ventricle at the other, will increase the risk of syncope, and for this reason digitalis cannot be regarded as free from danger in aortic regurgitation. The danger may, however, be very considerably diminished by keeping the patient in a recumbent posture with the head low. The column of blood above the aortic valves being lower, there will be somewhat less tendency to regurgitation; and even should the arterial

pressure fall much, the brain may still receive sufficient blood supply to prevent syncope.

In cases of aortic disease, where compensatory hypertrophy is insufficient, or where the hypertrophied heart is becoming enfeebled and dilated so that the mitral valves no longer close the orifice, the most urgent risk to the patient is no longer that of sudden syncope, but of pulmonary embarrassment, dropsy, and all the other consequences of mitral regurgitation. In such cases, as well as in those where organic disease of both mitral and aortic valves exist simultaneously, we must treat the urgent symptoms and give digitalis or other cardiac tonics.

In dilatation of the right heart due to bronchitis or emphysema, digitalis is frequently useful, though its benefit is less marked than in mitral disease.

Risks attending the Administration of Digitalis and other Cardiac Tonics.—The great risk attending the use of these drugs is sudden death from syncope. Whenever it is necessary to push them to any extent, the patient should be kept strictly in the recumbent posture, and not allowed to raise himself quickly even into a sitting position on any pretence whatever, even when there is no aortic complication. The effects of sudden change from the lying to the standing position in producing syncope have already been mentioned (p. 173), and when the patient is allowed to sit up he should be helped up slowly and with care. A change from the lying to the standing position by the patient getting out of bed is, of course, still more dangerous than simply sitting up in bed, and the most dangerous thing of all is for him to get up for the purpose of micturition. The reason of this has been already explained (p. 222).

Such strict precautions are, of course, not required excepting when the cardiac tonics have to be given in full doses. But when it is necessary to do this they should on no account be neglected.

As digitalis is cumulative in its action, it is often advisable after continuing it for several days to leave it off for a day or two, and then recommence, and this is a useful precaution when giving digitalis to out-patients who are seen at an interval of a week or more, even when the dose is comparatively small. Another difficulty in the administration of cardiac tonics is the gastric disturbance, loss of appetite, and vomiting, which they are apt to produce.

In cases where the arterial tension is already abnormally high, *e.g.* in cases of contracting kidney, and the heart seems unable to drive the blood into the aorta, the proper treatment of course is to reduce the abnormally high blood-pressure by purgatives, diuretics, and diaphoretics, and not to attempt to strengthen the heart by the use of cardiac tonics. If this be done the pressure may be raised still further and burst the vessels, giving rise to apoplexy.

Vascular Tonics.

Vascular tonics are substances which cause increased contraction of the arterioles or capillaries. They not only raise the blood-pressure, but influence to a considerable extent the quantity of lymph poured out into the tissues or absorbed from them, and thus modify tissue change. They are of special importance in the treatment of dropsy.

The most important vascular tonics are :—

Digitalis.
Iron.
Strychnine.

Pathology of Dropsy.—Dropsy consists in the accumulation of lymph, either in small lymph spaces in the tissues (œdema, anasarca), or large serous cavities (ascites, pleural or pericardial effusions). The accumulation is caused by more lymph being



FIG. 93.—Diagram of Ranvier's experiment on dropsy. The vena cava is ligatured, and in the left leg the trunk of the sciatic has been divided so that both the motor and vaso-motor nerves contained in it are paralysed. On the right side the motor roots of the sciatic alone are divided and the vaso-motor left uninjured. There is thus motor paralysis on both sides, but vaso-motor paralysis and dropsy only on the left side.

poured out from the capillaries than can be removed by the lymphatics and veins.

The chief causes of dropsy are—(1) Diminished removal of lymph from the lymph spaces or serous cavities. This may be due to (*a*)

obstruction of the veins, or (*b*) of the lymphatics. (2) Increased exudation of lymph from the capillaries. This increased exudation may be due to (*a*) changes in the walls of the capillaries themselves rendering them more permeable. This appears to be the only condition which by itself can produce œdema. There are two others, however, which, although by themselves incapable of producing œdema, yet, along with others, are of the utmost importance; these are (*b*) a watery condition of the blood, and (*c*) vaso-motor paralysis. In many, indeed in most cases of dropsy, two or three of these factors are combined.

Obstruction to the veins, or lymphatics alone, will rarely cause dropsy, unless at the same time there is increased transudation from the capillaries. Thus Ranvier found that ligaturing the vena cava of a dog did not produce dropsy in the legs, the lymph being removed either by the collateral venous circulation or by the lymphatics. On dividing the sciatic nerve on one side, however, after ligature of the vena cava, dropsy appeared in the corresponding leg, while it remained absent from the other. He showed that the dropsy was caused by paralysis of the vaso-motor, and not of the motor fibres contained in the sciatic, by dividing the motor roots of the sciatic on the other side, leaving the vaso-motor roots uninjured. When this was done motor paralysis occurred equally in both legs, but dropsy only appeared in the one where the vaso-motor nerves had been divided. This experiment shows what an important factor the loss of vascular tone is in the production of œdema, and we may legitimately infer from it that vascular tonics, by increasing the contractility of the vessels, will tend to prevent œdema, or remove it when it is already present.

A watery condition of the blood does not of itself increase the exudation of lymph, nor does it produce œdema, yet in cases of anæmia or chlorosis we very frequently find a tendency to œdema of the ankles, and experiments in Cohnheim's laboratory have shown that, although a watery condition of the blood alone causes no increased exudation of lymph so long as the vaso-motor nerves are intact, yet it does so to a very great extent when the vaso-motor nerves are paralysed.[1]

Alteration of the capillaries by inflammation causes increased exudation of lymph, and tends to produce a local œdema. This œdema is greatly increased if the vaso-motor nerves are paralysed, not only attaining a much greater extent, but appearing more quickly and lasting longer. I have already mentioned that, in experiments on artificial circulation, acids added to the circulating fluid not only caused dilatation of the vessels, but increased transudation through them, and tended to render the tissues œdematous. It is not improbable that some alterations of the blood-vessels of the living body which tend to render them more permeable may be

[1] Jankowski, *Virchow's Archiv*, xciii. p. 259.

connected with imperfect oxidation, and the formation of sarco-lactic instead of carbonic acid.

Arsenic has this power of lessening oxidation,[1] and it seems not improbable that the tendency to produce œdema of the eyelids which it possesses may be due to this peculiar action.

It is evident that whatever tends to increase oxidation will have an opposite effect, and will tend to prevent any excessive exudation from the capillaries. In cases of anæmia iron is therefore serviceable, and as the condition of the blood improves the tendency to œdema disappears.

What has just been said regarding the action of acids may seem to be in contradiction to the usually received opinion that the mineral acids act as vascular tonics. It is quite true that small doses of dilute acids, especially when given, as they usually are, along with bitters, frequently impart a feeling of strength and tone, whereas alkalies are frequently felt to be depressing, but in the case of both these classes of remedies this effect is probably not due to any direct action on the vessels themselves (*vide* Acids).

Cardiac Sedatives.

Cardiac sedatives are substances which lessen the force and frequency of the heart's action.

They are chiefly used, either for the purpose of lessening violent action or palpitation of the heart, or of rendering the pulse slower in febrile conditions, especially those consequent on local inflammation. It has already been mentioned that belladonna diminishes the sensibility of the heart to changes of pressure, and that sometimes it is useful in palpitation consequent on cardiac strain. Simple pressure over the cardiac region appears to have the power of lessening palpitation, so that when this occurs in consequence of any sudden emotion, there is a natural tendency to press the hand over the region of the heart. It is impossible to say whether the relief which such pressure certainly affords is simply mechanical, or is due to reflex action on the heart through the cutaneous nerves. Plasters applied to the cardiac region have a beneficial action upon palpitation similar to that of the hand, and one of the most commonly used and beneficial is belladonna plaster. In irritable heart of soldiers Dr. Da Costa found digitalis better than any other remedy.[2]

In palpitation depending on indigestion, hydrocyanic acid is useful. In palpitation due to aortic disease, senega has been recommended. It is probable that its efficacy depends upon the diminished action of the cardiac ganglia and muscle which its active principle, saponin, produces.

[1] Feitelberg, *Inaug. Diss.* Dorpat, 1883.
[2] *Amer. Journ. Med. Sci.* Jan. 1871.

An active circulation of blood is usually advantageous both for functional activity and for the repair of damage to an organ, but sometimes it may become excessive, and relief may be afforded by diminishing it (*vide* p. 299).

The chief cardiac sedatives employed for this purpose are :—

Aconite.
Veratrum viride.
Antimonial preparations.

It is questionable whether in extensive inflammation of internal organs cardiac sedatives are of much service or not. They seem, however, to give relief in the feverish condition which accompanies more limited inflammation, such as tonsilitis, otitis, &c. In such cases the tincture of aconite is best employed in very small doses (one drop) frequently repeated. The introduction of this method of using the drug in divided doses is due in great measure to Ringer, and it has the very great advantage that the desired effect can be produced with greater certainty and with less risk of an overdose being given.

Vascular Sedatives.

Vascular sedatives are substances which, by increasing the contraction of the vessels, lessen the flow of blood through them. They are chiefly used to lessen local inflammation or prevent hæmorrhage. One of the most powerful of all vascular sedatives is cold. For its use in local inflammation *vide* p. 298. It is not only a vascular but a cardiac sedative, and **ice** swallowed in considerable quantity will tend to lessen the action of the heart. It is therefore one of the means to which we chiefly trust in cases of hæmoptysis. In hæmatemesis it has the double action of lessening the activity of the heart, and of contracting the vessels in the stomach.

The remedies which are chiefly employed in addition to cold are :—

Digitalis.
Ergot.
Hamamelis.
Lead acetate.
Opium.

CHAPTER XII.

REMEDIES ACTING ON THE SURFACE OF THE BODY.

Irritants and Counter-irritants.

Irritants are substances which, when applied to the skin, cause a greater or less degree of vascular excitement or inflammation. They are employed for the sake of their **local action,** to produce increased circulation in the part to which they are applied, and thus to remove abnormal conditions already present in it.

When irritants are employed for the purpose of affecting reflexly a part **remote** from the seat of application they are named **Counter-irritants.**

Irritants are subdivided, according to the amount of effect produced, into rubefacients, vesicants, pustulants, and escharotics.

Rubefacients produce simply congestion and redness, which may be merely temporary, passing off in a few minutes, or may be more permanent, remaining for several days.

When more powerful, so as to cause exudation between the true skin and epidermis, giving rise to vesicles, they are called **vesicants,** or **epispastics.**

When they do not affect the whole skin alike, but do so unequally, and irritate isolated parts in it, such as the orifices of the sudoriferous glands, so powerfully as to give rise to pustules, they are called **pustulants.**

When they destroy the tissues altogether, forming a slough, they are called **caustics** or **escharotics.**

The difference between these sub-classes is chiefly one of degree, and not of kind. The weaker ones produce the higher degrees of action when applied for a long time, and the stronger ones produce the slighter kinds of action when applied for a short time.

It must be remembered that although inflammation is usually associated with increased circulation, the two things are essentially different.

Inflammation is the injury to the tissue, the increased circulation is the attempt to repair it.

Increased circulation occurs wherever we have increased functional activity, whether this be for the purpose of performing a normal function, as in glands during the process of secreting, and in muscles during contraction, or for the purpose of **repair.** When repair is going on slowly, the process may be frequently quickened by increasing the supply of blood to the part, and this is the reason for using friction, and liniments and blisters of various kinds, in cases of **chronic inflammation** in joints or in ulcers.

Sometimes irritation fails to cause absorption from being too weak. In a case of rheumatic gout which I saw some years ago, irritating liniments had been applied for some time in vain, until, by mistake on the patient's part, so much iodine liniment was put on at once as to cause vesication over the whole back of the hand, when recovery began immediately.

In **acute inflammation,** however, the greatly increased circulation, along with the heightened sensibility of the sensory nerves in the inflamed part, causes much pain, and this is relieved when the tension of the blood in the inflamed part is lessened. We notice this very clearly when the finger is inflamed in consequence of a thorn, bruise, or other injury. When it is allowed to hang by the side, the throbs of pain, coincident with every pulse-beat, become excruciating, while, if raised above the head, so that the pressure of blood in the vessels is less, the pain becomes greatly diminished. The tension in the vessels may be relieved likewise by causing contraction of the arteries leading to the part by a cold



FIG. 94.—Tracings from the radial artery at the wrist: *A* before and *B* after the application of a cloth dipped in cold water round the arm. After Winternitz.

compress around the arm, or by dipping the finger in cold water; but relief is also afforded by a warm poultice applied to the finger. At first sight it seems strange that **heat** and **cold** should both relieve the pain, but a little consideration will show that they both relieve the tension in the vessels of the inflamed part. Cold does so by causing a reflex contraction of the afferent arteries, and thus diminishing the quantity of blood going to the inflamed part. Warmth, on the other hand, dilates the capillaries of the collateral circulation, and thus diverts the current away from the inflamed vessels.

The use of **counter-irritation** as a remedial measure depends on the fact that similar alterations to those produced by heat and cold on the finger may be produced on the circulation in internal organs reflexly through the nervous system.

When an **irritant** is applied to any part of the skin, it causes a local dilatation of the vessels and redness of that part, but contraction of the vessels in other parts of the body. Probably this contraction takes place with the greatest force in certain



FIG. 95.—Diagram to show the effects of heat and cold in lessening the pain of inflammation. The diagrami s supposed to represent the end of the finger. The small star indicates the point of irritation, *e.g.* a prick by a thorn. The line in the centre of each figure is intended to represent the nerve going to the injured part; and at the side of each figure is an artery and vein connected by a capillary network. In *a* the capillary network around the seat of irritation is seen to be much congested: the nerve filaments are thus pressed upon and pain is occasioned. *b* represents the condition of the finger after the application of cold to the arm or hand. In consequence of the contraction of the afferent arteries the finger becomes anæmic; no pressure is exerted on the nervous filaments, and pain is alleviated. *c* represents the finger after it has been incased in a warm poultice: the capillary network at the surface of the finger is dilated, and the blood is thus drawn away from the seat of irritation and the pain therefore relieved.

organs having a definite nervous relation to that part of the surface which is irritated. Zülzer found that when cantharides-collodion was painted repeatedly over the back of a rabbit for fourteen days, he vessels underneath the skin, and the superficial layers of muscles, were congested. The deeper layers of the muscles, the thoracic wall, and even the lung itself, were much paler and more anæmic than those of the other side.


Vaso-dilating nerves to the cutaneous vessels.
Vessels of the skin and surface.
Blister applied to the chest-wall.
Thoracic wall.
Vaso-motor centre.
Afferent nerves.
Vaso-contracting nerves for the vessels of the lung.
Vessels of the lung.

FIG. 96.—Diagram to represent the mode of action of counter-irritants applied to the chest.

It is probable that a similar condition occurs in man, and that when we apply a blister to the side we, sometimes at least, cause contraction of the vessels in the pleura and lung below, and thus relieve pain in the chest in much the same way as when we apply cold to an inflamed finger. It has been supposed that the action of a poultice or blister was simply to draw away blood from the inflamed part. We have seen that the poultice does this in the case of an inflamed finger, but in an inflamed lung the quantity which comes to the skin is insufficient to explain the relief. It is quite possible, however, that the vessels in the lung and

pleura adjoining the inflamed district may be dilated by the application of a poultice or blister to the side, and thus relief is afforded in the same way as by the application of a poultice to the finger. It is not easy to say in which of these ways a poultice or blister acts in any particular case. Clinical experience seems to show that sometimes the blisters relieve acute inflammation by causing contraction of the afferent vessels (as represented in the accompanying diagram) and thus lessening the tension in the vessels of the inflamed part. If the blister is **too near** to the inflamed part, it may increase instead of diminishing the congestion, and thus do **harm** instead of good.

As a matter of practice, the rule is usually insisted upon that in a case of pericarditis, for instance, the blister should not be put immediately over the pericardium, but at some little distance from it.

Counter-irritation is not only used however as a means of lessening congestion and pain in acute inflammation, it is also employed with much advantage to cause the re-absorption of inflammatory products. The use of the increased circulation which a blister causes in a chronic ulcer is unquestionable, and the rapid absorption of the thickened margins of the ulcer is perceptible to the eye. A similar absorption appears to occur in deeper seated organs, such as the lung, on the application of counter-irritation to the chest, and painting with iodine liniment is useful in promoting absorption of liquid effused into the pleural cavity or of the product of chronic inflammation of the lung. The mode in which the irritation acts is probably the same both in the chronic ulcer and in the lung, *i.e.* by increasing the circulation through the part affected. Where the blister is applied, as in acute pericarditis, to lessen congestion, it is usually placed at a little distance from the inflamed part, but where we wish to increase absorption, as in consolidation of a part of the lung, we apply the counter-irritant directly over the consolidated part.

Rubefacients.

Mechanical as friction.

Ammonia.—Solution of ammonia, compound camphor liniment.

Alcohol (prevented from evaporating by oil-silk or watch-glass).

Arnica.

Cajeput oil.

Camphor.

Capsicum.

Chloroform (prevented from evaporating, like alcohol); chloroform liniment.

Ether (like chloroform).

Iodine and its preparations.—Iodide of cadmium, iodide of lead.

Menthol.

Mustard.

Oil of turpentine, of nutmeg, and many other volatile oils.

Vesicants.

Acetic acid (glacial).

Heat of:

Boiling water.

Corrigan's hammer.

Vesicants—*continued.*

Cantharides.—Solutions, plaster, cantharidine.
Euphorbium.
Mezereon.
Volatile oil of mustard.
Rhus toxicodendron.

Pustulants.

Croton oil.
Tartarated antimony.

Caustics.

Acids:—Acetic (glacial).
Carbolic.
Chromic.
Hydrochloric.
Nitric.
Osmic.
Sulphuric.
Alkalies:—Lime.
Potash.
Soda.
Alum (burnt).
Antimony (chloride).
Arsenious oxide.
Bromine.
Soluble compounds of the heavier metals; as:
Copper sulphate.
Mercuric chloride.
„ nitrate.
„ oxide.
Silver nitrate.
Zinc chloride.
Zinc sulphate.

Rubefacients.—One of the simplest rubefacients is mere **friction.** This may be made either with the hand, or more effectually still, with a rough cloth or a flesh-brush. Friction also greatly aids the action of many of the slighter rubefacients.

Rubefacients may be used for their action upon the skin itself to relieve itching. They may also be used for their effect on deeper-seated structures.

Friction, with firm pressure, is used in shampooing. Upward friction in the limbs will diminish their tension in dropsy, by removing part of the fluid from them. It also aids the circulation of the lymph, and by accelerating the passage of the products of muscular waste from the muscles themselves into the general circulation, it removes to a great extent the sense of fatigue after over-exertion. When applied along the back it soothes conditions of nervous excitement, and tends to produce sleep. Friction, along with stimulating liniments, applied to the joints after active inflammation has subsided in them, tends to remove the swelling and to restore their function.

Neuralgic pains are frequently relieved by the application of rubefacients such as ammonia, chloroform applied by a watch-glass, or a mustard plaster to the painful spot.

Conditions of nervous debility are sometimes benefited by the mustard liniment applied over the spine, and a mustard plaster to the nape of the neck is sometimes useful in nervous irritability with sleeplessness. In addition to the action which the mustard has on the vessels, it produces a sharp pain, so that it is employed also to rouse persons suffering from narcotic poisoning, or from coma.

Mustard leaves or iodine liniment applied over consolidated parts of the lung tend to cause absorption of inflammatory products and are used for this purpose in cases of effusion into the pleura or pericardium of chronic consolidation remaining after an attack of pleurisy or pneumonia, or in commencing phthisis.

Vesicants.—Vesicants are employed locally in **chronic ulcers** and to cause absorption of effusions into **joints,** or chronic thickening about them. When applied around the inflamed joints in acute rheumatism, they not only relieve the local affection, but appear to have a curative action on the general febrile condition.

In neuralgia, blisters over the painful point are useful, and sometimes, when neuralgia is in the side, or in the breast, it may be relieved by applying the blister over the corresponding part of the spine where there is usually a spot which is tender on pressure. In sciatica, the relief is often greater when the blister is applied to the heel, than over the nerve itself.

In neuralgia also it not unfrequently happens that a slight application of the actual cautery is more efficacious than a blister. The most convenient form of this is Paquelin's thermo-cautery.

In inflammation of the pericardium or pleura, a blister frequently relieves the pain, and it sometimes lessens or cuts short the inflammation. Applied over the epigastrium, blisters relieve vomiting arising from various causes.

In cerebral affections, such as obstinate headache, in meningitis and hydrocephalus, blisters to the nape of the neck or under the mastoid process are useful.

Hysterical paralysis of the limbs sometimes yields to blisters locally applied; and hysterical aphonia is sometimes removed by a blister over the larynx.

Pustulants.—Pustulants are employed for the purpose of keeping up a continuous moderate irritation in chronic inflammations: tartar emetic ointment, and croton-oil liniment seem sometimes to be of considerable advantage in chronic inflammation of joints or synovial membranes, in chronic bronchitis and in pleurisy; perhaps sometimes in phthisis. They have been used also as an application to the spine in paralysis and hysteria, and to the head in tubercular meningitis, and to the nape of the neck in chronic headache or giddiness. Though formerly these were much employed, iodine liniment of late years has to a great extent taken their place.

Caustics.—Caustics are used to destroy excrescences on the surface of the skin and mucous membranes: warts, condylomata, or polyp; to destroy exuberant and unhealthy granulations in ulcers and fungating sores: thus, a slight touch with nitrate of silver, sulphate of copper, or with nitric acid, will sometimes cause the

tissues in an unhealthy wound after an operation to become less exuberant, and take on a healthy healing action.

Caustics are only used to destroy malignant growths, more generally in the surgical operation performed for this purpose. Sometimes patients have such a horror of the knife that they will not submit to an operation, and in such cases caustics are sometimes employed. For this purpose Vienna paste may be employed, consisting of caustic lime and caustic potash. Sulphuric acid mixed with sawdust has sometimes also been used, but is exceedingly painful. Arsenious acid made with various inert substances into a paste is not unfrequently employed with considerable success by charlatans, who sometimes succeed in removing cancerous growths by its use in apparently hopeless cases, but the risk attending its use is considerable.

Caustics are sometimes employed also to open abscesses, especially abscesses of the liver, where it is advisable to cause adhesions between the viscus and the abdominal wall before the abscess is opened, so as to avoid any risk of pus finding its way into the abdominal cavity. The substance usually employed for this purpose is caustic potash.

Caustics are also used to keep up chronic irritation, as in chronic headache or epilepsy, a wound being first made by the use of the caustic, and prevented from healing by the introduction of a foreign body into it, or by the continued application of some irritating ointment, such as savine ointment.

Caustics are also used as an application to the bites of venomous serpents, or of rabid dogs, in order to destroy the virus and prevent its general action on the organism. The weaker caustics are of no use for this purpose. I have seen a boy die of hydrophobia six weeks after he was bitten by a mad dog, although the wound had been thoroughly cauterised by nitrate of silver five minutes after the bite. In all cases the parts around the bite should be, if possible, excised, and then cauterised with a red-hot iron, a ligature being, if possible, placed between the bitten part and the heart until the operation has been effected, so as to prevent any absorption of the virus.

Emollients and Demulcents.

Emollients are substances which soften and relax, while **Demulcents** are substances which protect and soothe the parts to which they are applied.

Many substances exercise both of these actions, and so no very sharp line of distinction is drawn between them. Emollients, however, are more generally spoken of in relation to their application to the skin, and demulcents to the mucous membranes.

Demulcents.	Emollients.
Bread.	Moist warmth—bathing with warm water, hot sponge, hot fomentations, steam.
Collodion.	Poultices made of substances which retain heat and moisture—bran, bread, figs, flour, linseed-meal, oat-meal, &c.
Cotton-wool (for external use only).	Gelatinous substances.
Figs.	Fats—almond-oil, glycerin, lard, linseed-oil, neat's-foot oil, olive-oil, spermaceti, suet.
Fuller's earth.	Paraffin—petrolatum, vaseline, and unguentum petrolei.
Gelatine.	Soap, and other liniments.
Iceland moss.	
Isinglass.	
Glycerine.	
Gum.	
Honey.	
Linseed.	
Linseed-tea.	
Marsh-mallows.	
Almond-oil.	
Olive-oil.	
Starch.	
White of egg.	

The action of Demulcents is chiefly mechanical. They form a smooth, soft coating to an inflamed mucous membrane, or to a skin deprived of its epidermis, and they thus protect the surface from external irritation, and allow the process of repair to go on. They are used externally in cases of irritating skin diseases, where the epidermis, from one cause or another, has been broken or removed, as by friction, exposure to cold, &c. Internally they are employed when the mucous membranes have been irritated, as, for example, in the after-treatment of cases of irritant poisoning.

Mucilaginous substances are also used to relieve pain and irritation in the throat, and to lessen the irritable cough which frequently depends on congestion of the pharynx and upper parts of the respiratory passages.

Such substances as figs, prunes, and even cabbage, are employed to protect the intestines from injury by hard and pointed substances which have been accidentally swallowed. They do this by leaving a bulky indigestible residue in which the pointed article becomes imbedded, and thus passes along the intestine without lacerating it.

The action of Emollients is to relieve the tension and pain in inflamed parts; **warmth** and **moisture** do this by dilating the collateral blood-vessels in the manner already described (p. 298). They also relax the tissues themselves and lessen the pressure upon the nerves of the part.

Fatty emollients soften the skin and thus render it softer and more flexible. These emollients also aid the immediate effect of friction upon the skin, enabling it to be applied with greater

advantage, and to act on the more deeply-seated tissues, as, for example, in cases of stiffness in joints.

Therapeutic Uses.—Warmth and moisture are almost invariably used to relieve spasm and the pain attending it, as well as to relieve pain in all cases of inflammation, whether superficial or deep-seated, and to relieve so much, that with many people the connection between pain and poultice has come to be a household word. When poultices are intended to act directly on the part to which they are applied, the linseed, bran, or bread should be applied to the skin with nothing between, or at most with only a thin piece of muslin, but when intended to act on deep-seated organs, a considerable thickness of flannel should be interposed, so that the heat may come gradually through, and allow an excessively hot poultice to be applied without burning the skin.

In cases of disease of the respiratory passages the warmth is usually applied by means of **inhalation.**

Fatty emollients, by softening the skin or mucous membranes, such as those of the lips, prevent them from cracking, and are used by persons with a delicate skin to prevent cracks forming on exposure to cold.

They are also used to prevent friction between surfaces of skin constantly in contact, as between the nates and inner joints in children, and to prevent bed sores.

Astringents.

These are substances which cause contraction of the tissues to which they are applied and lessen secretion from mucous membranes.

Acids.
Alcohol.
Alum.
Chalk and Lime.
Salts of the heavier metals, *e.g.*—
- Bismuth subnitrate, &c.
- Cadmium sulphate.
- Copper sulphate.
- Ferric chloride.
- Lead acetate.
- Silver nitrate.
- Zinc sulphate.

Gallic acid.
Tannic acid.
Vegetable substances containing these acids, *e.g.*—
- Catechu.
- Galls.
- Kino.
- Oak-bark.
- Uva-Ursi.
- Arbutine.

Astringents are usually divided into local and remote.

Local astringents are those which affect the part to which they are applied. **Remote** are those which act on internal organs after their absorption into the blood.

With the exception of gallic acid and ergot they all **coagulate** or precipitate **albumen.** Dilute mineral acids do not coagulate albumen, but precipitate albuminous substances from the alkaline fluids in which they are naturally dissolved in the body.

When applied to a surface from which the epidermis has been removed, the other astringents combine with the albuminous juices which moisten this surface, as well as with the tissues themselves, and form a pellicle more or less thick and dense, which in some measure protects the structures beneath it from external irritation at the same time that they cause the structures themselves to become smaller and more dense. On a mucous membrane they have a similar action, and they lessen its secretion. It was formerly supposed that their action was partly due to their causing the blood-vessels going to a part of the body to contract, thus lessening the supply of fluid to it, as well as to their effect on the tissues themselves. But experiment has shown that, while nitrate of silver and acetate of lead possess this power, perchloride of iron and alum do not, and that tannic and gallic acids actually dilate the vessels. The astringent action of these latter drugs must therefore be exerted upon the tissues. (Rossbach.)

Uses.—Astringents may be employed **locally** in various forms. In the solid form, as a powder, or in various preparations, such as lotions, ointments, plasters, glycerines, &c., they are applied, especially the metallic astringents, to wounds and ulcers for the purpose of reducing the size and increasing the firmness of exuberant granulations, as well as of protecting the surface by forming a pellicle over it. They are used to lessen congestion and diminish the secretion of the various mucous membranes—as a lotion to the eye and mouth; as a gargle or a spray to the throat; in the form of an injection to the nose, urethra and vagina; and of suppositories to the rectum. Administered internally, several astringents have a powerful effect in checking diarrhœa, and certain of them may have a local action upon the stomach and intestines.

The **remote** action of such astringents as acetate of lead and gallic acid, when absorbed into the blood, in lessening **hæmorrhage,** is made available in the treatment of hæmoptysis, hæmatemesis, hæmaturia, and loss of blood from other parts of the body.

Styptics.

Styptics are substances which arrest the flow of blood from broken or wounded surfaces or vessels. They may do this either by aiding the rapid formation of a coagulum which will plug up the wounded vessels, or by causing the vessels themselves to contract so much as to check the flow of blood out of them. They are closely connected with astringents, which, as we have already mentioned, nearly all coagulate albuminous substances.

Acids.
Actual cautery.
Alum.
Collodion.
Ferric chloride.
Matico.
Spider's-web.
Tannin.
Lead acetate.

Substances acting on the blood-vessels :—

Digitalis.
Ergot.

Action.—Matico and cobwebs act **mechanically** in aiding the formation of a clot around the fibres. Collodion also acts mechanically by exerting pressure over the surface, and thus preventing the blood from issuing.

Alum, lead acetate, and ferric chloride cause **coagulation** of the blood.

Pressure to the surface, cold sponges or ice, cause the vessels to **contract,** and thus prevent the blood from running out of them.

Lead acetate and gallic acid, when absorbed into the blood, not only tend to lessen secretion from the mucous membranes, but arrest hæmorrhage from internal organs. This is probably partly due to their effect in increasing the coagulability of the blood, and possibly partly also to their power of causing contraction of the anterioles. Ergot and digitalis also lessen or arrest hæmorrhage, although they have little or no action on coagulation, and their action probably depends on their power to cause contraction of the blood-vessels.

A dependent position increases the pressure of blood locally in the part, and thus tends to increase hæmorrhage. It is therefore advisable to keep the bleeding part as much raised as possible.

Powerful action of the heart tends to increase the blood pressure generally. In cases of severe hæmorrhage it is therefore of the greatest importance that the patient should keep **absolutely quiet,** and that all the food should be taken cold.

CHAPTER XIII.

ACTION OF DRUGS ON THE DIGESTIVE SYSTEM.

Action of Drugs on the Teeth.

ALTHOUGH the hurry and bustle of modern life is apt to make people forget it, mastication is a most important part of the digestive process. During early life the stomach and intestines may be able to digest imperfectly-masticated food, but as years advance they cease to do so, and imperfect mastication becomes a fruitful source of dyspepsia.

If the teeth are entirely or almost entirely gone, the person may chew with his gums, but if they are only partially gone it frequently happens that those which remain oppose one another only sufficiently to prevent the gums from closing, while they do not help mastication.

The decay of teeth is chiefly due to the dentine being attacked by the acid products of the decomposition of food in the mouth. This decomposition is to a great extent due to bacteria, and antiseptics are therefore useful in preventing decay.

By cleaning the teeth with a soft brush at night before going to bed, particles of food sticking between the teeth may be removed, and thus its decomposition and consequent injurious action on the teeth may be avoided. Chalk is employed as a basis of most dentifrices, as its mechanical action is sufficient to clean the teeth without injuring their polish, and at the same time it neutralises any acid which may be present. Charcoal has also a useful mechanical action greater than that of chalk, but it is more liable to scratch the enamel.

The antiseptics which are usually employed to cleanse the teeth are borax, quinine, and carbolic acid. Dilute solutions of permanganate of potash are also very useful, but have a very disagreeable taste. Where the gums are soft and spongy and are apt to leave the fang of the tooth more or less exposed, vegetable astringents such as areca nut, catechu, kino and rhatany are useful. Mineral acids when given medicinally cause an unpleasant feeling of the teeth being on edge, and are also injurious to the teeth; they are therefore usually sucked up by means of a glass tube or quill

instead of being simply swallowed. When used as gargles for the throat, their injurious action on the teeth may be to a considerable extent prevented by previously rubbing the teeth with oil, butter, or lard, and washing out the mouth or brushing the teeth with a weak solution of an alkaline bicarbonate or soap. Soluble preparations of iron, especially persalts, are apt to stain the teeth, and they are therefore also given by means of a tube; alum appears also to have a very injurious action on the teeth; alum gargles should therefore not be employed for a length of time together, and the same precautions should be used as with acid gargles.

When the gums have receded somewhat from the crown of the teeth, a pain or soreness is not unfrequently felt in the teeth although no definite caries is present. This soreness appears to be due to the irritant action of acid secretions in the mouth upon the exposed fang, and it may be often to a great extent removed by washing the mouth out with a weak solution of bicarbonate of soda, or rubbing finely-powdered chalk or magnesia along the gums. When toothache occurs in consequence of caries, it may sometimes also be relieved by a small pledget of cotton-wool dipped in tincture or liquid extract of opium with a little bicarbonate of soda and placed in the cavity of the tooth. A pledget of cotton-wool dipped in creasote is often used for a similar purpose, and one of the most effectual remedies is to dip a small pledget of cotton-wool in pure carbolic acid liquefied by heat, and place it in the cavity of the tooth, taking care to cover it well with clean cotton-wool so as to prevent the carbolic acid coming in contact with the tongue or cheeks. Chlorate of potash often lessens toothache if due to inflammation of a large open carious cavity.

Sialagogues.

These are remedies which **increase** the secretion of **saliva.**

Anything which is chewed, or even turned about in the mouth, such as a pebble, will increase the secretion of saliva; but the chief sialagogues have a stimulating action of their own.

Action.—In the secretion of saliva there are **two factors,** first the activity of the **secreting cells;** secondly, the supply of new material to them, from which they may manufacture the secretion. This depends on the **circulation.**

The secreting cells do not derive the new material from which they form the secretion directly from the blood. They obtain it from the lymph which fills the adjacent lymph spaces. Hence they may continue to secrete for a short while after the circulation has ceased, as in the sweat glands of an amputated limb, or in the salivary glands after the head of the animal has been separated from the body. But the supply of lymph soon becomes exhausted unless a supply of fresh lymph in the spaces is kept up by exudation from the blood-vessels. We therefore find that abundant

secretion is usually, though not invariably, associated with an abundant blood supply. If the flow of blood is not rapid the secretion must soon diminish or come to a stop, for, although it may occur rapidly at first, the lymph which has accumulated in the lymph spaces, supplying the cells, soon becomes exhausted.



FIG. 97.—Diagram representing the general relation of nerves to the secreting cells and vessels of a gland. For the sake of simplicity only one afferent nerve and one nerve centre and one set of secreting and vascular nerves are here represented.

In the salivary gland, when the secretion is going on, the arteries usually dilate, and the blood flows rapidly through them. The submaxillary gland, in which secretion has been best studied, appears to receive four kinds of nerves—two sets being contained in the chorda tympani and two in the sympathetic.

The chorda contains some fibres which act on the blood-vessels, causing them to dilate and allow the blood to flow freely through the gland, and others which stimulate the cells of the gland, to secrete a thin, watery saliva. These two kinds are spoken of as vaso-dilating and secreting, or secretory, fibres.

At present the usually accepted theory is that the secretory nerves have a direct influence upon the tissue change in the cells of the gland. During secretion the granules in the cell decrease in number and generally in size, the hyaline substance increases, and the network within the cell grows.[1] It is not at all improbable however, that in addition to their action upon secreting nerves some drugs influence the amount of fluid poured out from the vessels. For if we inject a solution of quinine into the duct of the gland and thus destroy its secreting power, and afterwards irritate the chorda tympani, the lymph poured out from the blood-vessels, will accumulate in the gland and render it œdematous; but if an animal be poisoned with atropine the gland does not become œdematous when the chorda tympani is stimulated—although the blood-vessels going to it are dilated and its power of secretion is completely destroyed. We might suppose that the gland did not become œdematous because the lymph, although not

[1] Langley, *Proceed. Camb. Phil. Soc.* Nov. 12, 1883.

used up by the gland, had been carried away by the cervical lymphatics. But this is not the case, for Heidenhain has found that the flow of cervical lymph is not increased under these circumstances.

It appears to me that this circumstance can hardly be explained otherwise than by supposing that atropine not only paralyses the secreting fibres of the chorda, but acts upon the vessels in such a manner as to greatly diminish or prevent the exudation which would usually take place from them into the lymph spaces on irritation of the chorda.

The sympathetic contains some fibres which cause the vessels of the gland to contract and the blood to flow slowly through it, and others which stimulate the cells to secrete a thick and viscid saliva.

Besides the ordinary secretion of saliva regulated by the action of the nerves, there is a secretion which is usually termed paralytic, because it occurs, not after irritation, but after paralysis of the nerves going to the salivary gland. It occurs in the submaxillary gland, when its nerves have either been paralysed by the injection of small doses of curare into the artery going to the heart, or by a section of the combined lingual nerve and chorda tympani, or extirpation of the submaxillary ganglion. It is not improbable that morphia also, like curare, produces it, because in moderate doses it causes dryness of the mouth, but in enormous doses causes excessive salivation.



FIG. 98.—Diagram to show the afferent nerves by which the secretion of saliva may be reflexly excited.

The **nerve-centre** which regulates the secretion of the thin chorda saliva is probably the nucleus of the seventh nerve situated in the medulla oblongata.

Efferent fibres pass out along the chorda tympani and reach the gland, some directly, and some after passing through the submaxillary ganglion.

The **afferent** fibres, which convey stimuli from the mouth to the

medulla are contained in the lingual branch of the fifth, and the glosso-pharyngeal nerves. Those which convey stimuli from the stomach, and excite the salivation which accompanies nausea, are contained in the vagus. The salivary centre may also be stimulated by impulses sent down from the brain, and the nerves of sight and smell may act as afferent nerves to the salivary centre indirectly through the brain.[1]

Besides the nerve-centre in the medulla oblongata there are **subsidiary** nerve-centres. These are the submaxillary ganglion and small ganglionic masses in the submaxillary gland itself.

The secretion of saliva may be stimulated by the **direct** action of drugs upon secreting nerves in the gland itself, or **reflexly** through the sensory nerves of the mouth, stomach, eye, or nose. The mere smell, or sight, of appetizing food, causes secretion of saliva, which is probably due to the nerves of smell and taste acting through the brain upon the medulla. The **brain,** when excited by mere recollection, may also stimulate the secretion of saliva.

Increased salivation is a common accompaniment of sickness or nausea. The afferent nerve here appears to be the gastric branches of the vagus.

Sialagogues have been divided into two **classes:** 1st, **topical,** or direct; and 2nd, specific, **remote,** or indirect. The names *direct* and *indirect* are complete misnomers, and ought not to be used; inasmuch as the so-called *direct* sialagogues are those which act *directly* on the *mouth,* but do *not* act *directly* on the substance of the *gland,* or on the nervous structures contained within it or immediately connected with it.

Topical Sialagogues.	**General Sialagogues.**
Acids, mineral and vegetable.	Jaborandi. (Pilocarpine.)
Acid salts.	Muscarine.
Alkalies.	Physostigma.
Ethereal bodies—	Compounds of Iodine.
Ether.	Mercury and its compounds.
Chloroform, &c.	
Pungent substances—	
Mustard.	
Horseradish.	
Ginger.	
Pyrethrum.	
Mezereon.	
Tobacco, &c.	
Rhubarb.	
Cubebs.	

[1] The nasal branches of the fifth nerve probably also act as afferent nerves for the salivary secretion, for I have noticed that on dipping the tip of the nose into hot water containing a little compound tincture of benzoin, salivation occurred, ceased when the nose was withdrawn, and again occurred regularly whenever the nose was again introduced into the mixture. The mere inhalation of the vapour had no effect.

The **topical** sialagogues, acids, ether, ginger, horseradish, mezereon, mustard, pyrethrum and rhubarb, all produce salivation by stimulating the salivary glands reflexly through the nerves of the mouth.

The effect produced by topical or reflex sialagogues is not the same for each. Ether and dilute acids produce a thin, watery saliva, but alkalies cause the secretion of a thicker and more viscid saliva: the former appearing to affect chiefly the chorda tympani, and the latter the sympathetic.

Mercury probably acts partly upon the gland structures and partly reflexly through the nerves of the mouth. **Jaborandi, physostigma**, and **tobacco**, probably stimulate the terminal branches of the secretory nerves in the glands. Nauseants, such as tartar emetic, stimulate the gland reflexly through the vagus.

The **peripheral ends** of the secreting nerves in the gland itself are stimulated by pilocarpine, muscarine, nicotine and physostigmine, so that secretion is induced by the injection of these substances into the blood even after all the nerves going to the gland have been cut.

In large doses these substances paralyse the ends of the secreting nerves, so that irritation of the chorda tympani will no longer cause secretion. Physostigmine and nicotine, besides acting on the peripheral terminations of the secretory nerves, stimulate the **central ends** of those nerves so that section of the chorda tympani greatly lessens the secretion which these substances cause, although it may still persist from the effect of the drug upon the peripheral terminations.

The peripheral action of physostigmine and nicotine is however much less marked than that of muscarine and pilocarpine, so that the secretion caused by the two former after the nerves have been divided is very much less than that produced by the latter.

Physostigmine acts also on the **sympathetic nerves**, producing contraction of the vessels at the same time that it is stimulating the secreting centre in the medulla. In consequence of this double action, secretion is rapid at first, but, however, diminishes very quickly or ceases entirely, the circulation being so much lessened by the contraction of the vessels that the glands do not get sufficient supply of new material to go on secreting.

Iodide of potassium may act partially as a reflex sialagogue, for it is secreted in the saliva, and it therefore comes to be present in the mouth more or less persistently. It is probable, however, that it acts also upon the gland structures, though it has not been determined whether the secreting cells or the nerves are chiefly affected.

Excretion by the Saliva.

Iodide of potassium is very quickly excreted by the kidneys, so that the great bulk of it passes out of the body in a short time

after it has been taken. But a little of it is retained very persistently for a length of time. There may be more than one reason for this. It is possible that it becomes combined with albuminous matters of the blood and tissues, and this combination



FIG. 99.—Diagram of the gastro-salivary circulation.

being only slowly broken up, the elimination of the drug continues for a length of time. Another reason appears to be that it is excreted even more readily by the salivary glands than by the urine. The saliva in which it is contained is swallowed, the iodide is again absorbed from the stomach and carried by the circulation to the salivary glands. It thus goes on in a continual round from mouth to stomach and from stomach to mouth. Iodide of iron, and probably other iodides, are eliminated by the saliva in the same way. Iodide of iron occurs in the saliva either when injected into the artery of the gland or when absorbed from the stomach. When lactate of iron and iodide of potassium are introduced simultaneously, or at a short interval after each other, into the stomach, so that iodide of iron is formed there by their combination, iodide of iron is found in the saliva.[1] But if they are injected separately into the blood, iodide of potassium alone without any iron appears in the saliva. Iodine probably causes other substances besides potassium and

[1] Bernard, *Physiologie Expérimentale*, tom. ii. p. 99.

iron to appear in the saliva when they are combined with it. It probably does so to quinine, for when iodide of potassium and quinine are given together in a mixture, patients frequently complain of a very persistent bitter taste in the mouth much more marked than when the quinine is given in simple solution with acid.

Uses.—Saliva is useful in keeping the mouth moist, and thus facilitating mastication, solution, deglutition, and the movement of the tongue in speaking. By moistening the fauces, it also prevents or lessens thirst. A pebble placed under the tongue or masticated, will keep up a slight flow of saliva, and may be useful for these purposes. Where this is insufficient, dilute acids are employed. As the flow of blood to the glands is greatly increased through secretion, sialagogues have been used as derivatives to lessen inflammation, congestion, and pain, in other parts of the head, as in tooth-ache, ear-ache, and inflammation of the ear, nose, or scalp.

Saliva has also a digestive action on starch, and increase of the flow may be advantageous in imperfect digestion of this substance. When swallowed the saliva stimulates the secretion of gastric juice, and increased salivary secretion therefore tends to aid the gastric digestion of proteids also. To obtain this object it is best to chew a piece of ginger, pellitory, or rhubarb.

Refrigerants.

Refrigerants are remedies which allay thirst, and give a feeling of coolness.

There appear to be two kinds of thirst: one of which is general, the other of which is local. **Local thirst** is occasioned by dryness of the mouth and fauces. It may be quenched by washing the mouth and gargling the throat with water, although none of it be swallowed, or by anything which will increase the flow of saliva, and thus keep the mouth and fauces moist. Thus, a pebble under the tongue, or chewed, will lessen thirst by increasing the secretion of saliva; and acids, both mineral and vegetable, as well as effervescing drinks containing carbonic acid and the juices of fruits, which contain either free vegetable acid or acid salts, acetates and tartrates, have a similar effect. When the secretion from the mouth and throat is very scanty, it is dried up by the passage of air to and fro in the process of respiration. The evaporation thus occasioned may be lessened, and the feeling of thirst diminished by the use of mucilaginous substances, which will form a thin coating over the mucous membrane of the mouth and pharynx. Thus, the addition of oatmeal to water will increase its power to quench thirst, and a very little milk added to water has a similar effect.

General thirst depends upon the condition of the organism

generally, which appears to be due either to deficiency of water or excess of soluble and especially saline substances in the circulation.

General thirst is very often accompanied by local thirst, and may be partially alleviated by the means already described, but cannot be removed excepting by the introduction of water into the organism, or removal from it of the saline or other substances which are present in excess, or by lessening the excitability of that part of the nervous system by which the sensation of thirst is perceived.

This part of the nervous system, or thirst centre as Nothnagel calls it, is probably situated according to him in the occipital lobes of the brain, and it is possible that it may be irritated directly by mechanical injury, or by the condition of the blood circulating in it, as well as reflexly from mucous membranes, such as that of the mouth and throat, and possibly also from the kidneys. Its excitability is lessened by opium, and this may be used to diminish thirst in cases where other remedies fail to relieve.

Anti-sialics.

Anti-sialics are substances which **lessen** the **salivary secretion.** They may do this:

First, by removing the stimulus to secretion.

Second, by lessening the excitability of the efferent nerves or reflex **centres.**

Third, by paralysing the efferent nerves, such as the chorda tympani.

Fourth, by acting on the circulation through the gland.

Fifth, by acting on the gland structures themselves.

Borax and chlorate of potash are useful in the first of these ways by inducing a healthy condition of the mucous membrane of the mouth, and thus lessening the irritation which gives rise to salivation; opium and morphia diminish the reflex excitability of the nerve-centre, and are thus powerful anti-sialics.

Physostigma in large doses greatly lessens the supply of blood to the gland, and thus diminishes its secretion, and quinine, hydrochloric acid, and alkalies injected directly into the duct of the gland arrest secretion by affecting the secretory cells themselves. These latter drugs however cannot be used as anti-sialics.

The most powerful of all anti-sialics is however atropine, which paralyses the peripheral terminations of secreting nerves. It does not affect the vaso-dilating nerves, so that in an animal poisoned by atropine electrical stimulation of the chorda tympani will cause dilatation of the vessels and a free flow of blood through the gland as usual, but not a drop of saliva will be secreted. That this absence of secretion is due to paralysis of secretory nerves and not of the secreting cells appears to be shown by the fact that

at the time when the power of the chorda to induce secretion is completely paralysed stimulation of the sympathetic will still induce secretion.

Very large doses of atropine however paralyse the secreting power of the sympathetic in the cat, although this has not been noticed in the dog.

The paralysing action of atropine can be counteracted by physostigmine. This is shown by poisoning an animal with atropine, and then injecting physostigmine into the gland of one side through the submental artery. It is then found that irritation of the chorda causes salivation in the gland which has received physostigmine, while it causes no secretion in the other.

Iodide of ethyl-strychnia and cicutine have an action on the secreting and not on the vaso-dilating[1] fibres of the chorda tympani like that of atropine.

Gastric Tonics.

These are substances which **increase** the **appetite** and **aid** gastric **digestion.**

From observations made on the stomach in persons or animals where a gastric fistula has been present, it has been found that in the normal condition, when the stomach is empty and quiet, the mucous membrane is of a pale rose colour. When stimulated mechanically, by rubbing it gently with a feather or glass rod, the mucous membrane becomes redder, and such abundant secretion of gastric juice occurs that it runs down in drops along the walls of the stomach.

When the irritation is greater, as, for example, when the mucous membrane is rubbed roughly instead of gently, an opposite effect is produced. The vessels then contract, the mucous membrane becomes pale, and the secretion of gastric juice stops, secretion of mucus commences, and if the irritation be carried still further, vomiting occurs.

Almost all substances which, when applied to the skin, act as irritants, as arsenic and salts of copper, silver, or zinc, and those also which, without irritating the skin, irritate the nerves of taste, as bitters, produce a feeling of appetite in the stomach, but they only do this in certain conditions of the stomach, and in certain quantities. The appetite appears to be associated with gentle stimulation of the gastric walls; stronger stimulation removes the appetite, still greater irritation causes nausea, and lastly vomiting.

In cases of atonic dyspepsia, where the stomach is below par, as, for instance, in anæmia and debility, slight stimulants or irritants produce appetite.

In such cases, where the tongue is usually smooth and flabby, bitters and metallic salts are useful. But when the stomach is

[1] Jolyet, *Gaz. Med. de Paris*, 1877.

already too irritable, and the tongue is red with enlarged papillæ, such substances are likely to irritate still more, and thus, instead of increasing the appetite, to diminish it, and produce nausea. The increased irritability of the stomach which precedes a bilious attack is often signalised by an unusually good appetite, which continues during the meal, so that food is eaten with relish. A still greater irritability is characterised by a great appetite before meals, which disappears, giving place to anorexia as soon as a few



FIG. 100.—Diagram to illustrate the supposed nervous connections of the stomach. A gentle stimulus applied to the walls of the stomach is transmitted by the afferent nerves, A, to a nerve-centre. B, and thence along the vaso-dilating nerves, C, and the secreting nerves, D, to the vessels of the mucous membrane and the cells of the gastric follicles. A stronger stimulus is transmitted up to the nerve-centre, E, and thence along the vaso-constricting fibres, F, and the secreting fibres, D, of the mucous follicles. A still stronger stimulus is transmitted to H, and thence along the motor nerves to the abdominal walls, K K, causing them to contract and produce retching or vomiting.

mouthfuls have been swallowed, and the gastric irritation increased by the increased circulation consequent on the introduction of the food. In such cases, bitters are likely to do harm, and gastric sedatives, such as bismuth, are required.

Bismuth is probably only a *milder* irritant than the others, because so slowly dissolved, and mild irritation allays inflammatory conditions.

But the stomach has not merely to receive food, it has to digest it, and in the process of digestion there are **three factors:** 1st, **secretion** of the gastric juice which is to render the food capable of absorption and of assimilation; 2ndly, **movements** of the stomach to break up the food and mix it thoroughly with the solvent juice; and 3rdly, **absorption** of the products of digestion.

Action of Drugs on Secretion in the Stomach.

The **secretion** of the gastric juice is stimulated by gentle mechanical and chemical irritation, as by dilute alkalies and alcohol.

The name of peptogens is given to substances which increase the gastric secretions. Schiff has examined these, and states the most important of them to be dextrine (toasted bread), soups, peptones, &c.[1]

In order to obtain gentle mechanical stimulation, it is often advisable to make patients who are suffering from atonic dyspepsia commence their meals, and especially their breakfast, with solids, instead of commencing with a large draught of liquid.

Dilute alkalies given before meals increase secretion of gastric juice; so much so, that the alkali is not only rapidly neutralised, but a large amount of acid gastric juice remains over.

The alkaline saliva has a powerful stimulant action on the secretion of gastric juice, and as its quantity is much increased both by savoury food and by the movements of mastication, it is important that the food should not only be well cooked, but slowly and perfectly masticated. Alcohol is one of the most powerful stimulants that we know, and is probably surpassed only by **ether.** In persons suffering from weak digestion, therefore, a little dilute alcohol with meals is sometimes very beneficial.

Thorough **mastication** is also of the greatest importance in ensuring perfect digestion, inasmuch as the gastric juice penetrates with difficulty, and only slowly dissolves the masses of albuminous matter, while it would digest them very quickly if they were thoroughly broken up.

In children and young people, the stomach may be able to do more than its fair share of work, but it cannot do this in persons above middle age, and in them, imperfect mastication, either from deficient or decayed teeth, or from the habit of eating quickly, is one of the most common causes of dyspepsia.

When the stomach is too much debilitated to secrete sufficiency of gastric juice, even when stimulated, as in the weakness consequent upon acute disease, general debility, or old age, we may supply **artificially** the **digestive substances** in the form of acids and of pepsin. Acids should be given for this purpose immediately after meals, or two hours after meals. Pepsin should be given either with, or immediately after, those meals which contain albuminous substances. As pepsin has no action on farinaceous food or salts, it is no use to give it after meals containing these only.

Pancreatin, given two hours after meals, along with a little bicarbonate of soda, appears, in some cases, to complete digestion, and to give great relief and comfort.

[1] Roberts, *Digestive Ferments.*

Action of Drugs on the Movements of the Stomach.

The digestion is greatly aided by the **movements** of the stomach, which assist it by breaking up the food and mixing it thoroughly with the gastric juice. When these are deficient, it is probable that they are stimulated by nux vomica, or strychnine, and also by bitters.

Absorption from the Stomach.—We know at present very little regarding the effect of drugs in stimulating **absorption** from the stomach, but it is probable that this is very greatly influenced by the condition of the liver. If there is any obstruction to the free flow of blood through the liver, the circulation in the stomach will necessarily be impeded and absorption probably diminished.

All the processes which go on in the stomach—secretion, peristaltic action and absorption—are much influenced by the condition of the circulation.

All the blood which circulates in the stomach has to pass through the liver before it gets into the general circulation, and thus the condition of the stomach is necessarily much modified by the condition of the liver. If there is any obstruction to the free flow of blood through the liver, the circulation in the stomach will necessarily be impeded, and absorption probably diminished.

Not only the blood from the stomach, but that from the intestines also, passess through the liver, and we may naturally expect that the liver itself will be influenced by the condition of the blood which passes to it from the intestinal canal.

In Dr. Beaumont's observations on Alexis St. Martin, in whom a gastric fistula existed, he found that after the stomach had been deranged by various articles of food, including fat pork, there was distress in the stomach, headache, costiveness, and a coated tongue. In the stomach there were numerous white and pustular-looking spots. Half a dozen calomel pills produced catharsis, removed the symptoms, and restored the mucous membrane of the stomach to its normal condition. Whether this effect was due to the action of the pills on the liver, or on the intestines, we cannot perhaps positively say, but at all events the improvement was readily evident to the observer's eye.

Purgatives and **Cholagogues** may thus act as **indirect gastric tonics.**[1]

Absorption from the stomach is probably also much influenced by the condition of the nervous system. Bouley found that when the vagi were divided in a horse, strychnine no longer produced poisoning, the reason being that the absorption took place so slowly after a division of the nerves that the poison was excreted as fast as it was absorbed. The retarded absorption, however, he considers to be due, not to any alteration in the absorptive power of the stomach itself, but to diminished movement in its walls, so that its

[1] Beaumont, *Physiology of Digestion*, Burlington, 1847, p. 118.

contents are not so quickly poured out into the intestine. Absorption normally goes on more slowly from the stomach than from the intestine, and so, while the poison remains in the stomach it is not absorbed quickly enough to cause poisoning.

Antacids.

Antacids are remedies employed to lessen or counteract acidity. The excessive acidity for which antacids are given may be present in the stomach, intestines, or urine.

Antacids are divided into direct and indirect, or remote. Direct antacids lessen the acidity in the stomach, to which they are directly applied. Remote antacids lessen the acidity of the urine. Some substances have both actions, such as potash and soda, or the carbonates and bi-carbonates. Other substances, such as the citrates, tartrates, and acetates of these bases, have no power to lessen acidity in the stomach, but, after absorption into the blood, they appear to undergo combustion, and become converted into carbonates — in this form they are excreted in the urine, and lessen its acidity.

Ammonia and its carbonates are direct antacids, but not remote antacids. They lessen acidity in the stomach or intestines, but after absorption they undergo change and are eliminated in the form of urea, and, according to some, of nitric acid, so that they do not lessen the acidity of the urine.

Direct Antacids.—Liquor potassæ, potassium carbonate, potassium bi-carbonate, liquor sodæ, sodium carbonate, sodium bi-carbonate, liquor lithiæ, lithium carbonate, lithium bi-carbonate, magnesia, magnesium carbonate, magnesium bi-carbonate, lime water, saccharine solution of lime, chalk.

Direct but not Remote Antacids.—Ammonium carbonate, aromatic spirit of ammonia.

Remote Antacids.—Potassium acetate, potassium citrate, potassium tartrate, potassium bi-tartrate, sodium acetate, sodium citrate, tartarated soda, lithium citrate.

Emetics.

These are remedies which **produce vomiting.**

Action.—The act of vomiting consists in compression of the stomach by the simultaneous spasmodic contraction of the diaphragm and abdominal muscles, while at the same time relaxation of its cardiac orifice is produced by contraction of the fibres which radiate out from the lower end of the œsophagus along the gastric walls. By their contraction these fibres draw the stomach up towards the diaphragm and pull the walls of the œsophagus apart at its lower end so as to open the cardia. When the cardiac orifice

dilates at the same moment that the stomach is compressed between the diaphragm and the abdominal muscles, its contents are expelled and **vomiting** occurs; but when the compression of the stomach and dilatation of the cardiac orifice do not take place simultaneously, the contents of the stomach are retained and the efforts are then termed **retching**.

The **nerve-centre** which regulates the movements of vomiting is situated in the medulla oblongata. The movements of vomiting are modified expiratory actions, and the respiratory centre appears to be closely connected with the vomiting centre. Indeed some groups of ganglion cells probably take part both in respiration and vomiting, or in other words form part of both the respiratory and vomiting centres (Fig. 53, p. 200).

The reason for this supposition is not merely that the movements of vomiting consist of modified respiratory movements, but that drugs which cause vomiting also increase the respiratory activity. Emetics usually quicken the respiration considerably before they produce vomiting, and if injected into the veins they not only quicken the respiration, but prevent the condition of apnœa being produced by vigorous artificial respiration.

On the other hand, the desire to vomit may be lessened to some extent by taking frequent and deep inspirations, and narcotics which diminish the excitability of the respiratory centre also lessen the tendency to vomit.

The **motor** impulses from the vomiting centre are sent to the abdominal muscles, diaphragm, stomach, and œsophagus by the intercostal, phrenic, and vagus nerves respectively. Section of the vagi generally, though not always, destroys the power to vomit, because it disturbs the co-ordination of the cardia and the abdominal muscles and diaphragm so that they no longer act simultaneously, and vomiting does not occur although retching may continue.

The vomiting centre is usually excited by stimulation of **afferent** nerves passing upwards to it from the body, or by impulses sent down to it from the brain.

The **brain** may be stimulated so as to act on the vomiting centre in the medulla through impressions on the nerves of special sense, such as a disgusting sight, stench, or taste, or by the recollection of such subjects. Irritation of the brain itself or of its membranes by inflammation, tubercle, hæmorrhage, softening, or cancer may also excite vomiting. The **afferent nerves** are shown in the accompanying diagram. Those chiefly concerned with the action of emetics are:—

1. Branches of the glosso-pharyngeal nerve to the soft palate, the root of the tongue, and the pharynx. Tickling these parts with the finger or with a feather is one of the readiest means of inducing vomiting. Vomiting also occurs when the soft palate, tonsils, or pharynx are inflamed, especially in children.

2. The nerves of the stomach. These are chiefly branches

of the pneumogastric, but they are contained also in the sympathetic system.

3. Mesenteric nerves causing vomiting in hernia.
4. Nerves of the liver and gall duct.
5. Nerves of the kidney and ureter.
6. Vesical nerves.
7. Uterine nerves.
8. Pulmonary branches of the vagus causing vomiting in phthisis.



FIG. 101.—Diagram showing the afferent nerves by which the vomiting centre may be excited to action.

There are also a number of other nerves which produce vomiting, but are more important in connection with pathological vomiting than with the action of emetics.

When less was known regarding the action of the nervous system in vomiting, **Emetics** were divided according to their relation to the stomach into direct and indirect. **Direct** emetics were those which acted only when introduced into the stomach. **Indirect** were those which acted when injected into the blood.

Their relation to the vomiting centre is of course the reverse. Drugs which are applied directly to the stomach act reflexly or indirectly on the vomiting centre, while those injected into the blood may be carried by the circulation to the medulla and act directly upon it.

It is to be noted however that drugs injected into the circulation

are carried not only to the nerve-centres but to the stomach, and may be **excreted** by the gastric mucous membrane. They may thus irritate the afferent nerves of the stomach and stimulate the vomiting centre reflexly just as they do when given by the mouth. Thus it has been shown by Brinton that tartar emetic injected into the veins of a dog is excreted in a few minutes into the stomach and may be found on testing its contents.

It is therefore evident that the action of drugs in causing vomiting may be complex, and that drugs injected into the **blood** or under the skin may cause vomiting, both by (1) **irritating** the vomiting **centre** in the medulla **directly** when conveyed to it by the circulation; and (2) by irritating it **reflexly** from the stomach, whither they have also been conveyed by the blood.

It is frequently very difficult to determine in which of these two ways a drug has acted, and sometimes almost impossible to decide with certainty.

The reasons for believing that any drug injected into the circulation has caused vomiting by irritating the medulla reflexly through the stomach, and not by acting directly upon it, are:

(*a*) when the vomiting does not take place immediately on injection, but only after sufficient time has elapsed to allow of excretion of the drug into the stomach.

(*b*) When the quantity of a drug required to produce vomiting by injection into the veins is greater than that which is sufficient to produce a similar effect if introduced into the stomach. It is probable that some drugs, as tartar emetic, act in both ways, because as has already been mentioned, it is excreted into the stomach and will there act as an irritant.

But it will also produce vomiting when the stomach has been excised and replaced by a bladder as in Magendie's celebrated experiment. Even this experiment however does not prove that tartar emetic acts directly on the vomiting centre, inasmuch as it is possible that it may be excreted by the œsophagus or intestines and irritate the vomiting centre reflexly through them. As tartar emetic however appears to act as an irritant chiefly in those parts of the body where there is an acid secretion, it seems doubtful whether it would produce irritation in the œsophagus and intestines such as it does in the stomach. It therefore seems not improbable that the vomiting which it occasions after excision of the stomach is due to its direct action on the medulla oblongata, but this cannot be regarded as quite proved. In order to avoid the confusion which the terms **direct** and **indirect** emetics are likely to produce with regard to their relations to the stomach and vomiting, it is better to describe them as, and to employ the terms, **topical** or **local** and **general** emetics.

Topical, or local, are such as produce vomiting by acting locally on the pharynx, œsophagus, or stomach; and **general,** such

as act through the medium of the circulation. The line between the two is not distinct, inasmuch as tartar emetic will produce vomiting in either way, and so will sulphate of zinc, or sulphate of copper. The *local* action of sulphate of zinc and sulphate of copper, however, on the stomach is so much greater than their general action that they may be classed among the *local* emetics.

Local Emetics.	**General Emetics.**
Alum.	Tartar emetic.
Ammonium carbonate.	Ipecacuanha and Emetine.
Copper sulphate.	Apomorphine.
Mustard.	Senega.
Salt.	Squill.
Subsulphate of Mercury.	Muscarine, Urechitine, Digitalis & its congeners, — not used medicinally as emetics.
Water (lukewarm and in copious draughts).	
Zinc sulphate.	
Strong infusions of vegetable bitters, as camomile, quassia, &c.	

The action of **local** emetics is confined to that of producing vomiting, which is generally not long continued, ceasing after the emetic has been evacuated, and is not accompanied by much general depression.

The vomiting occasioned by **general** emetics on the other hand is much longer continued, and is accompanied by much general depression, nausea, languor, muscular weakness, enfeeblement of the circulation, and increase of the secretions, especially those of saliva, sweat, and mucus in the œsophagus, stomach, and bronchial tubes.

Uses.—Emetics may be used for the purpose of simply **emptying** the **stomach,** or the violent expulsive efforts which they occasion may be utilised in order to remove foreign bodies or secretions from the œsophagus or from the biliary or respiratory passages.

1. Emetics may be used to cause the **expulsion** of **foreign bodies** such as pieces of gristle or meat which have become impacted in the upper part of the œsophagus, and, by pressing on the larynx, are giving rise to suffocation. In such cases apomorphine given subcutaneously, or injected into a vein in the dose of $\frac{1}{12}$th or $\frac{1}{10}$th of a grain, will be found of service.

2. They may be used to **remove** the **contents** of the **stomach**, when these, instead of undergoing digestion and absorption in the normal manner, have undergone fermentative changes and become acid, acrid, and irritating, giving rise to pain, either in the stomach itself, or in some other organ, as in the head. In gastralgia, or in headache either depending upon indigestion, or

associated like sick-headache with a tendency to vomiting, large draughts of warm water often give relief. Their emetic action may be aided if necessary by tickling the fauces with the finger, or by using strong camomile tea, or mustard and water in place of water alone. Simple draughts of warm water, however, may relieve the gastralgia or headache without causing vomiting. They appear to do so by simply diluting the acrid contents of the stomach so much that they no longer irritate the mucous membrane.

3. Emetics **remove** the **poison** from the stomach in cases where it has been swallowed. Here mustard and water is very useful, as it is the emetic which is most likely to be at hand; but sulphate of copper and sulphate of zinc if readily procured are to be preferred, as they empty the stomach most quickly and effectually. In cases of poisoning by laudanum, the nerve-centres are so much deadened by the narcotic that they may not respond to the stimulus even of large doses of these emetics, and then it may be necessary to employ the stomach-pump or gastric syphon.

4. To **expel bile** from the gall-bladder, to drive small **gall-stones** through the gall-duct. The bile is secreted under a very low pressure, and a very slight obstruction in front may prevent its flow through the gall-duct and occasion its accumulation in the gall-bladder and biliary capillaries. The compression of the liver between the diaphragm and abdomen muscles, even in ordinary respiration, tends greatly to dispel the bile from the liver, and this expulsive action is of course greatly increased during the violent efforts of vomiting. During these efforts the bile may be forced through the gall-duct, driving before it the obstruction which has been occasioned by the accumulation of mucus within it due to catarrh, or by the impaction of a small biliary calculus. In this manner emetics may remove jaundice due to obstruction.

5. To **remove bile** from the body in cases of **biliousness, fevers,** and **ague.** In biliousness the emetics have got the double action of expelling the bile from the liver in the way just mentioned, and of removing it from the body through the stomach. When bile passes along the intestines, not only is it reabsorbed, but poisonous matters from the intestine are absorbed with it. When it is ejected from the stomach by the efforts of vomiting, no time is allowed for its reabsorption, and so both the bile itself, and any poisonous matter which it contains, are more rapidly and certainly removed from the body. It is probable that the malarious poison circulates in the bile, and possibly also other poisons which give rise to fevers. There can be no doubt of the advantages to be derived from the use of emetics in ague before the administration of quinine; and indeed cases of ague may be sometimes cured by the use of emetics alone without quinine, while quinine without emetics is not unfrequently of very little use in bad cases. Emetics have also been recommended in the

early stages of continued fevers in order to remove the poison on which they are supposed to depend. For such purposes ipecacuanha or tartar emetic is best.

6. To **remove obstructions** from the **air-passages**, such as false membranes from the trachea and bronchia in croup or diphtheria, or the over-abundant secretion which is clogging the bronchia and interfering with respiration in bronchitis, and more rarely in phthisis. Ipecacuanha is the emetic most readily chosen in such cases, as it tends to increase the secretion from the air-passages, as well as to produce vomiting. When it does not act rapidly, sulphate of zinc or sulphate of copper may be used, and a teaspoonful of alum is a very efficient remedy in croup. When there is much depression of the circulation, carbonate of ammonia is to be preferred as an emetic, inasmuch as it stimulates the circulation, as well as causes vomiting.

Contra-indications.—Emetics must be avoided in persons suffering from **aneurism**, and used with care in persons suffering from **atheroma** or a tendency to **hæmorrhage** from the lungs or uterus, lest the high blood-pressure which occurs during the efforts of vomiting should lead to the rupture of a blood-vessel. They should be used with caution also in persons suffering from **hernia**, or who have a tendency to it, or from **prolapsus** of the uterus. In pregnancy we often find obstinate vomiting lasting for a length of time, and yet producing no abortion; but where a tendency to **abortion** exists, emetics should be avoided if possible.

Gastric Sedatives and Anti-emetics.

Gastric sedatives are substances which lessen the irritability of the stomach and thus diminish pain, nausea, and vomiting.

Their action may be either **local** on the stomach, or **general** on the nervous system, and especially on the vomiting centre in the medulla oblongata.

Local Sedatives.		General Sedatives.
Alcohol.	Ether.	Hydrocyanic acid.
Alum.	Hydrocyanic acid.	Morphine.
Arsenious acid in minute doses.	Ice.	Opium.
Atropine.	Morphine.	
Belladonna.	Opium.	
Bismuth salts.	Silver nitrate.	
Carbolic acid.		
Cerium oxalate.		
Chloroform.		
Creasote.		

The most powerful of all **local** sedatives is ice, and when vomiting is persistent, everything should be iced, and ice swallowed

in small lumps. Hydrocyanic acid and morphia probably act by lessening the irritability of both the nerves in the stomach itself and of the vomiting centre as well. The mode of action of creasote and carbolic acid is rather uncertain, because, although they have a local anæsthetic action, yet they are found useful also in cases of reflex vomiting, such as the vomiting of pregnancy.

As **adjuvants** to gastric sedatives, we may mention such substances as diminish or remove the irritation, although not lessening the sensibility, of the stomach itself. Thus, where the irritant consists of very acrid fluid in the stomach, a large draught of water, by diluting it, may lessen pain, or nausea, and alkalies have a similar action. When the irritation is due to congestion of the mucous membrane, **astringents** will also have a sedative action. Probably this is the explanation of the use of alum in vomiting of phthisis, and possibly, also, of the use of nitrate of silver in the vomiting of chronic alcoholism.

Uses.—Gastric sedatives are employed (1) to **relieve pain** in the stomach, as in gastrodynia. The most useful are small doses of morphia, hydrocyanic acid, belladonna, arsenic, and bismuth; (2) to **relieve vomiting.** This depends upon the cause of the vomit. When it is due to acrid substances in the stomach, the best sedative is often a large draught of warm water, which either dilutes or renders them less irritating, or causes their removal by vomiting.

Where it is due to acute irritation of the walls of the stomach itself, ice, hydrocyanic acid and morphia, and bismuth, are best.

When due to the acrid products of fermentation in the stomach, sulphurous acid and creasote are very useful.

When due to chronic irritation and congestion, alum, nitrate of silver, creasote, and carbolic acid are serviceable.

When the vomiting is due to strangulated hernia, the hernia must be reduced, and in cases of intussusception or obstruction these conditions must be removed. In the vomiting of pregnancy, the irritability of the vomiting centre must be reduced by bromide of potassium or morphia.

It is only in extreme cases that the source of irritation, viz. the pregnant condition, is to be removed, but certain local means are sometimes useful; such are separation of the membranes around the neck of the uterus, which may possibly act by lessening the irritation in the organ, and painting the os-uteri with stimulating applications which probably rather act by a kind of counter-irritation or inhibition.

Carminatives.

Carminatives are substances which aid the expulsion of gas from the stomach and intestines. They appear to do this by increasing the peristaltic movements of these organs, and in the

case of the stomach by causing the lower end of the œsophagus or cardiac sphincter, and perhaps sometimes the pyloric sphincter, to dilate so as to allow of the exit of gas. The stomach naturally contains a certain amount of gas, chiefly nitrogen and carbonic acid. The nitrogen is derived from air which has been swallowed, the oxygen with which it was mixed being absorbed by the walls of the stomach.

For respiration goes on in the stomach, as well as in the lungs, though to a much less extent in mammals, and oxygen is absorbed and carbonic acid excreted. The stomach, therefore, generally contains carbonic acid in addition to nitrogen; some of the carbonic acid also is derived from the food. In addition to these gases there is frequently hydrogen present: hydrogen and a quantity of carbonic acid being formed by processes of fermentation going on in the food. Sometimes instead of pure hydrogen marsh-gas is formed, which takes fire when expelled from the stomach, and not unfrequently the hydrogen unites with sulphur, forming sulphuretted hydrogen, causing to the patient an unpleasant taste of rotten eggs in the mouth, or giving their smell to the breath. It is probable that this last occurrence is due to the presence and decomposition in the stomach of bile, which contains sulphur as one of its constituents.

When digestion is rapid and complete, little or no fermentation occurs, very much less gas is formed, and therefore there is no uncomfortable distension.

There are several drugs which tend to prevent fermentation, while they hardly interfere at all with the action of the gastric juice. Among these may be mentioned creasote, sulphurous acid, and bitters. These substances may all be regarded as **adjuvants** to carminatives, and so indeed may pepsin, dilute alkalies, and all other remedies which stimulate the secretion of gastric juice and thus aid digestion.

Where there is any tendency to venous congestion in the stomach, there will be interference with the respiration in the stomach, and thus a greater tendency to the accumulation of gas. Any conditions interfering with the circulation, such as metral disease or hepatic congestion, will thus tend to cause flatulence, and in such cases digitalis and cholagogues will prove useful adjuvants to carminatives.

It is possible that much mucus covering the surface of the stomach may interfere both with absorption and with gastric respiration. Charcoal has been given to remove flatulence on the supposition that it absorbs the gases in the stomach. But it only absorbs gas when it is dry, and the beneficial action which it certainly possesses is probably a mechanical one in removing mucus and stimulating circulation. Possibly bismuth and magnesium act similarly, though less powerfully.

The chief Carminatives belong to the classes of aromatic oils, alcohols, or ethers. They are:—

Allspice and oil.	Cinnamon and oil.	Mace.
Anise and oil.	Cloves and oil.	Mustard.
Assafœtida.	Coriander and oil.	Nutmeg and oil.
Cajeput oil.	Dil and oil.	Pepper.
Capsicum.	Ether and acetic ether.	Peppermint and oil.
Caraway and oil.	Fennel.	Spearmint and oil.
Cardamoms.	Ginger.	Spirits.
Chilies.	Horseradish.	Valerian and oil.
Chloroform.		

Uses.—Carminatives are employed (1) to remove pain and distension of stomach and intestines caused by **flatulence**; (2) to render peristaltic action regular, and diminish local **spasm** and pain depending upon it. They are useful both in cases where the spasm is due to irritation of the stomach and intestines by irritant articles of food, irritant secretions, or irritant medicines. They are therefore commonly used not only in griping and colic pains due to indigestion, worms, or exposure to cold, but are commonly used as adjuvants to purgatives in order to lessen the griping pain, which they often cause when given alone. In addition to this, by rendering the peristaltic action of the bowel more regular, they assist the action of the purgatives.

ACTION OF DRUGS ON THE INTESTINES.

Intestinal Movements and Secretion. — The peristaltic movements of the intestine occur even when it is separated entirely from the body. Their rhythmical occurrence appears to be due to the action of the ganglia contained in Auerbach's plexus, which lies between the outer longitudinal and internal circular layer of the muscular coat. The **secretion** is probably influenced by Meissner's plexus, which lies in the sub-mucous coat.

Both the movements and the secretion of the intestine require to be regulated in accordance with the wants of the body, and this is done by the **nerves** which connect these plexuses with the cerebro-spinal centres. The chief of these nerves are the splanchnics and the vagi. Irritation of the vagi frequently causes movements of the intestine; irritation of the splanchnics, on the other hand, arrests them, so that the splanchnics have been regarded as the inhibitory nerves of the intestine, just as the vagi are the inhibitory nerves of the heart. But this arrest is by no means constant, sometimes the movements instead of being arrested are distinctly increased; so that it is evident that the splanchnics contain a mixture of stimulating and inhibitory fibres, or else that the same fibres are capable of exercising either function under different conditions.

Paralytic Secretion.—When all nervous connection between the intestine and the higher nerve-centres is cut off by completely dividing the intestinal nerves, a copious secretion, exactly resembling the rice-water stools of cholera, occurs in the intestine. This is best shown by isolating three loops of intestine, by means of ligatures, after they have been previously carefully emptied, as shown in Fig. 102. The nerve-fibres going to the middle loop are



FIG. 102.—Diagram showing the effect of section of nerves on secretion from the intestine. The nerves going to the middle loop have been divided, and it is distended with the fluid secreted.

then divided, and the intestine is returned to the abdominal cavity. After four or five hours the animal is killed, and the intestine examined; it is then found that the loop, the nerves of which have been divided, is filled with fluid, while the other loops which have been under precisely the same circumstances, but the nerves of which have not been cut, remain empty.

It is evident then, that certain **nerve-centres** possess the power of **restraining** the **secretion** from the intestine. These nerve-centres have been shown by Pye-Smith and myself to be the smaller or inferior ganglia of the solar plexus, with the superior mesenteric, off-set from them. When these ganglia are destroyed, the same abundant secretion occurs in the intestine as when all the nerves are cut, but if these ganglia be left intact the spinal cord may be removed, the vagi and splanchnics cut, and the semilunar ganglia excised without any excessive secretion occurring in the intestine.

The **vascular supply** of the intestines is regulated to a considerable extent by the splanchnics, irritation of which causes contraction of the vessels. There appears also however to be an important relation between the intestinal vessels and the lumbar portion of the spinal cord, because when this part of the cord is destroyed with extirpation of the solar plexus, **hæmorrhage** or hyperæmia of the intestinal mucous membrane occurs, so that the internal surface of the intestine has a somewhat dysenteric appearance. This does

not occur when the solar plexus and semilunar ganglia are destroyed, the splanchnics divided, or the mesenteric nerves cut.[1]

The nervous arrangements for regulating intestinal movement and secretion are evidently exceedingly complex, and until our knowledge of their physiological relations is more perfect, we cannot expect to understand completely the effect which drugs produce upon them. These are occasionally very complicated, and vary considerably according to the quantity of the drug used. **Drugs** may affect the intestine by their **local** action on the intestine itself, by their **direct** action on the **central nervous** system, or by their **indirect** action through the alterations in the quality or supply of the blood. The quality of the blood which circulates in the intestine alters its movements very considerably.

When the aorta is clamped, so that the blood which circulates in the intestine and in the lower part of the spinal cord becomes venous, the peristaltic movements are usually much increased; when the compression is removed and arterial blood is allowed to circulate again, the peristalsis instead of diminishing, as one might expect, becomes still more intense. Compression of the vena cava inferior, or of the portal vein, sometimes causes a slight increase in the peristaltic movements, but it is inconsiderable as compared with those produced by clamping the aorta. During **suffocation,** when the blood becomes venous throughout the whole body and exercises an irritating action, not only on the nerve-centres present in the intestine and in the lumbar portion of the spinal cord, but also on the brain and upper part of the cord, the effect on the movements of the intestine is variable. They are sometimes increased, but sometimes an inhibitory effect appears to be produced through the higher centres and their movements are arrested.

It is evident therefore that when an animal has been poisoned by any drug, and the intestines are examined after death, two **different conditions** may be found which do not depend upon any peculiar action of the drug on the intestine, but only upon its effects on the higher nerve-centres, thus, if the higher centres have been in such a condition as to cause inhibition, the intestines may be found in a state of perfect rest, whereas, if they happen not to be in this condition, brisk peristalsis may be observed. It very often occurs that when the intestines are first exposed after an animal's death, they are found to be at rest, but as the higher centres die from a stoppage of the circulation, the peristaltic movements become much accelerated.

In order to simplify the problem presented by the complicated nervous arrangement in the intestine, Ludwig and Salvioli have used the plan of keeping up the **circulation artificially** in a small piece of intestine, and then investigating its movements under various conditions. The intestine was laid on a piece of cork, in a

[1] T. Lauder Brunton and Pye-Smith on "Intestinal Secretion and Movement," *British Association Reports,* 1874, 1875, 1876.

warm chamber. It was supplied with blood by means of a cannula placed in the artery, and allowed to flow out through a cannula in the veins. Its movements were registered by a small lever placed upon it. When blood fully oxygenated passed through it, the lever traced only a straight line or gently oscillating curve, but when the flow of blood was stopped, so that the blood stagnated and became **venous,** contractions began which were indicated as a series of



FIG. 103.—Diagrammatic representation of apparatus for testing the action of drugs on the intestine by artificial circulation through it. For the sake of simplicity the means employed to keep up the temperature of the intestine and apparatus have been omitted. A, a board on which the intestine, B, is laid. C, a cannula tied into a branch of the mesenteric artery. D, D, two stop-cocks, by means of which pure blood or poisoned blood may be passed at will through the cannula. E and F, two flasks, containing pure and poisoned blood. G, a block on which they stand, and by which they can be raised to a greater or less height, so as to alter the pressure under which the blood flows. When the apparatus is kept warm the pressure is more easily regulated by passing air into the flasks from a pressure bottle. H, the lever for registering the movements of the intestine. One end is weighted and rests on the intestine. I is the axis on which the lever works. K is a revolving cylinder on which the movements are recorded.



FIG. 104.—Shows the effect of anæmia. The upper tracing shows the movements of the intestine supplied with normal blood; the lower shows the movements of an intestine rendered more vigorous by anæmia.



FIG. 105.—Shows the effect of peptones The first half of the tracing shows the movements of an intestine supplied with blood thoroughly oxygenated; the second half shows the effect of blood containing peptones.



FIG. 106.—Shows the effect of nicotine. The part of the tracing marked *A B* shows the intestinal movements during the circulation of blood saturated with oxygen (apnœic blood); the part *N B* of blood containing nicotine.



FIG. 107.—Shows the effect of opium. In the first part of the tracing the intestine was supplied with apnœic blood; in the latter with blood containing opium.

curves. A trace of **peptone** caused first strong contraction and then a number of irregular contractions, at the same time that the vessels become fuller of blood. **Nicotine** causes brisker movements of the intestine, and lessens the rapidity of the flow of blood. In large doses it causes tetanic contraction of the circular fibres.

Atropine causes irritation of the vessels, while the muscular fibres remain at rest. The action of **opium** is very remarkable when

a tincture is added in the proportion of ·04 to ·01 per cent. to the blood which is circulating through the intestine, the circulation becomes at once lessened, but almost immediately afterwards the diminution passes abruptly into great increase, so that five or seven times as much blood flows through in a given time as formerly; at the same time all the movements of the intestine are abolished, but the intestinal wall instead of being relaxed, as one would expect, is in a condition of considerable contraction. When the opium is washed out of the vessels by pure blood, the after-effects vary according to the quantity which is used. If it is small, the movements and circulation in the intestine soon become normal, but if a large dose has been used, the circulation returns to the normal condition but the movements remain abolished for a length of time. The peristaltic action induced by nicotin is arrested by opium. The local action of this drug therefore seems to be that it converts the peristaltic movement into a steady contraction.

A remarkable difference between the action of **soda** and **potash** on the intestine has been detected by Nothnagel. When the intestine is exposed, and a potash salt is applied to its external or peritoneal surfaces, it produces a contraction of the muscular walls, which remains localised to the point of contact, or simply causes a ring of contraction opposite the point. When a sodium salt is used instead, it produces a contraction which is not limited to the point of contact, but always spreads some little distance from it, and invariably does so in the direction towards the pylorus, and not towards the anus. This peculiar action appears to be due to the potassium salts acting as stronger muscular irritants than the sodium salts, while the progressive contractions caused by the sodium is due to the intestinal nerves, in their case more being involved. The effect of **morphine** is very remarkable. When the animal, in addition to being anæsthetised by ether only, as in the previous experiment, has a small dose of morphia injected also into the veins, it has a sedative effect, so that **sodium** salts applied to the intestine produce only a local contraction like potash-salts. But this is only when a certain dose of morphia is employed, about 0·01 to 0·03 of morphia for a rabbit. When the dose was increased from 0·05 to 0·1 gramme of morphia, an exactly **contrary effect** was produced, and the application of sodium salts, instead of being followed only by local contraction, caused a peristaltic contraction, which was usually very much more energetic than in the normal condition and not only spread upwards from the point of contact, but downwards towards the large intestine, which it never did under other circumstances. The quieting or inhibitory effect of moderate doses of morphia upon the intestine, irritated by soda salts, appears to be exercised through the splanchnic nerves, inasmuch as when the mesentery, going to one part of the intestine, is divided in an animal that has received a moderate dose of morphia, the application of soda salts to this part

is followed by a peristaltic wave; while, in the other parts of the intestine where the nerves are uninjured, the soda still produces only local contractions.

From these experiments it is evident that moderate doses of morphia produce a very different effect upon the intestine from large ones: and this effect has indeed been long recognised in practice.

Moderate doses of opium have a constipating action and are constantly used to check diarrhœa, but large doses, such as those taken by opium-eaters, really have no constipating effect. Indeed, large doses of opium injected directly into the jugular vein of a dog act as most energetic purgatives, being much more prompt in their action than almost any other drug that we know. Immediately after their injection the whole intestinal tract is thrown into violent action and its contents expelled, after which it again becomes quiet.

Very minute doses also seem to have a purgative action, as well as very large ones, and I have used them with considerable success in many cases of constipation.

Constipation may be due to diminished peristaltic action, or diminished secretion, or to both, and in some cases is associated with accelerated absorption. In all probability it is generally due to a diminution in the peristaltic action. In the normal condition this ought to go on regularly, so that the bowels should be evacuated, on an average, once a day, though in some persons evacuations normally occur two or three times a day, and in others only once in three or four days. In some apparently healthy persons I have observed an interval of as much as two or three weeks. In some persons the normal stimulus of ordinary easily digestible food does not seem to be sufficient to keep the bowels acting, but food which leaves much indigestible residue, such as brown or bran bread, salad, figs, prunes, or tamarinds, will do so. These latter fruits owe their laxative properties partly to the insoluble residue they leave and which acts as a mechanical irritant to the intestine, and partly to the salts and sugar and mild laxative principles they contain. Treacle and gingerbread also have a useful aperient action, and their pleasant taste makes them specially suitable for children. The effect of a somewhat stimulant article of food is greater when taken on an empty stomach, and thus a fig before breakfast will have a much greater laxative effect than one taken after dinner. A glass of cold water also, by stimulating peristalsis, will have a laxative action when taken on an empty stomach at bed-time or on rising in the morning. When these means are insufficient a slightly irritating substance, such as an aloetic pill taken on an empty stomach just before dinner, will aid the stimulating effect of the food which is taken afterwards, and will be sufficient to ensure perfectly regular and normal evacuations which do not in any way incommode the person. In consequence

of this many people continue to take such **dinner pills** regularly for many years together. Others, again, suffer from constipation, but with them small doses of purgative medicine if they act at all, act violently, and leave the person weak and uncomfortable, while the bowels again become constipated. This condition is found not unfrequently among women, and is accompanied, sometimes at least, with pain or tenderness in one or both ovaries. In such persons also, contrary to the general rule, walking exercise increases instead of diminishing constipation.

My friend Dr. Litteljohn noticed that in a case of ovarian tenderness, half a grain of opium given to relieve the pain acted as a purgative. On thinking over this, it occurred to me that the constipation in such cases might be due to reflex irritation of the



FIG. 108.—Diagram to show the way in which ovarian irritation probably causes constipation.

inhibitory intestinal nerves by the tender ovary. It seemed therefore probable that by using graduated doses of opium, one might be able to lessen the action of the inhibitory nerves, or even to divert the stimulus from them on to the stimulating fibres, and thus produce purgation instead of constipation. Not knowing what dose would be sufficient to produce this effect, I began with one drop of tincture of opium given in a teaspoonful of water every night. To my astonishment this dose was, not only in most cases sufficient, but in one case it proved excessive, doing no good, while half a drop acted as a brisk purgative. It is evident that opium used in this way will not act as a purgative in cases of constipation depending upon general insensibility of the intestinal nerves. The cases in which it is most useful are those of delicate women of a nervous temperament, suffering from ovarian pain, and in whom, ordinarily, purgatives produce excessive action followed by constipation. Small doses of belladonna have also been recommended in constipation, and it is probable that they act in a similar manner when given alone, and that belladonna, hyoscyamus, and essential oils assist the action of purgatives by tending to divert the stimulus, which the irritating constituent of a purgative produces, from the inhibitory to the accelerating intestinal nerves. We know at

present but little regarding diminished secretion as a cause of constipation.

Action of Drugs on Absorption from the Intestines.—Ether introduced into the intestine greatly increases its vascularity. It also quickens absorption very much, as is shown by the fact that poisons act more quickly, and such substances as ferro-cyanide of potassium appear sooner in the urine, when they are administered along with ether than when given alone. Carbonic acid has a somewhat similar though weaker action.

Coto bark has been used in diarrhœa, and as it has no proper astringent action, its utility has been ascribed to an antiseptic action by which it diminished the formation of irritant products in the intestines. Albertoni has investigated the action of the coto alkaloids, and finds that although cotoine somewhat lessens putrefaction and the development of bacteria, it does not stop them either in the organism or outside it. It has, however, a very peculiar action on the vessels of the intestine. By keeping up artificial circulation in a loop of intestine (*vide* p. 333), he finds that cotoine dilates the arteries, causes the blood to flow more readily into the veins, and preserves the vitality of the intestine. It also dilates the vessels of the kidney, and causes the blood to flow more rapidly through them, but does not alter the circulation in the submaxillary gland.

Opium and chloral also dilate the vessels of the intestine, but their action is a paralysing one, while that of cotoine is not. The action of paracotoine is similar to that of cotoine, but less marked.

Albertoni thinks that the benefit which cotoine produces in diarrhœa is due to dilatation of the intestinal vessels, and the increased power of absorption which it causes. He considers that in many cases of diarrhœa diminished absorption is a most important factor.[1]

It is possible that the beneficial action of bael fruit in dysentery may depend on some similar property, as this substance has the peculiarity of acting as a laxative in health, while it lessens the evacuations in dysentery.

Intestinal Astringents.—Diarrhœa may depend (1) upon excessive peristaltic action whereby the contents of the intestine are hurried along before time has been allowed for their absorption, (2) upon diminished absorption, (3) upon excessive secretion. In one form of diarrhœa, where the introduction of food into the stomach seems to excite peristaltic action throughout the intestine so that the person is frequently forced to rise from the table in order to evacuate the bowels, small doses of one half to two minims of liquor arsenicalis given immediately before meals, as recommended by Ringer, frequently act like a charm. In ordinary cases of

[1] *Archiv. für exper. Path. und Pharm.* p. 291, vol. xvii.

diarrhœa, opium, by lessening the irritability of the intestine, is most serviceable. Some medicines lessen peristaltic action, not by affecting the bowel, but simply by removing the stimuli which were exciting it. Thus small doses of soda are useful in the diarrhœa of children by neutralising the acid which was acting as an irritant. Creasote has a similar action by lessening putrefaction or fermentation, and thus preventing the formation of irritant products. It is probable that lime acts also to a certain extent by its antacid properties, but there is little doubt that there are other factors in its astringent action which we do not yet understand. The effect of cotoine on intestinal absorption has just been mentioned. With the view of ascertaining whether we could find any drug which would arrest the copious secretion from the intestine which takes place in cholera, Pye-Smith and I made a large number of experiments. For this purpose we isolated loops of intestine, and into one injected sulphate of magnesia mixed with the drug to be tested. In some experiments we injected the sulphate of magnesia into the intestine, and the drug which we wished to test into the veins.

Sulphate of atropine, iodide of methyl-atropine, chloral-hydrate, emetine, morphine, sulphate of quinine, tannin, and sulphate of zinc, were all tried locally with negative results. Chloral and morphine injected subcutaneously also gave negative results.[1]

In many cases the best way of checking diarrhœa at its commencement is to give a purgative such as castor-oil, either alone or



FIG. 109. – Diagram illustrating diarrhœa depending on the presence of scybala in the intestine. *a* is a scybalous mass ; *b* is the fluid which it causes the intestine to secrete.

with a few drops of tincture of opium in it. The irritant substances which cause the diarrhœa are swept out of the intestine by the action of the purgative, and any irritation which remains is soothed by the opium. Chronic watery diarrhœa, alternating with constipation, is often best treated in the same way. We may

[1] *Report to Brit. Assoc.* 1874.

suppose that here the presence of scybalous masses in the intestine gives rise to a watery discharge, which does not, however, wash away the scybala themselves. When a purgative is given which causes secretion from the intestine above the scybala, the fluid in its downward flow, assisted also by the increased peristalsis, washes away the scybala, and thus removes the source of irritation.

Purgatives.

Purgatives are substances which **cause intestinal evacuations.** They are divided according to their nature into **laxatives, simple, drastic,** and **saline purgatives, hydragogues,** and **cholagogues.**

Laxatives are those which increase only **slightly** the action of the bowels and render the motions slightly more frequent and softer, without causing any irritation. Most articles of food which leave a large indigestible residue in the stomach act as laxatives: such are oatmeal, brown bread, and bran biscuits. Articles of food also which contain salts of vegetable acids and sugar in considerable quantity also act as laxatives. The chief laxatives are :—

Honey.	Cassia.	Stewed apples.
Treacle.	Tamarinds.	Sulphur.
Gingerbread.	Figs.	Magnesia.
Manna.	Prunes.	Castor-oil (in small doses).

Figs, raspberries, and strawberries, in addition to containing sugar and vegetable acids, have a number of small seeds which are absolutely indigestible, and these have probably a mechanical action in stimulating the bowel.

Simple purgatives also, when given in small doses, act as laxatives: such are carbonate of magnesia, magnesia, olive-oil, and sulphur.

Simple purgatives are more active than laxatives, and their administration is usually followed by one or more copious and somewhat liquid stools. Their action is sometimes accompanied by some irritation and griping. These are :—

Aloes.	Rhamnus (various species).
Rhubarb.	Castor-oil.
Senna.	

Drastic purgatives are those which cause violent action of the bowels, usually accompanied by evidences of greatly increased peristaltic action, such as borborygmi. They cause irritation of the

intestine, and when taken in large doses produce inflammation and symptoms of poisoning. These are :—

Elaterium.	Gamboge.
Colocynth.	Podophyllin.
Jalap.	Croton oil.
Scammony.	

Saline purgatives consist of neutral salts of metals of the alkalies or alkaline earths. The more commonly employed are :—

Sulphate of potassium.	Bi-tartrate of potassium.
„ sodium.	Tartrate of potassium and sodium.
„ magnesium.	Citrate of magnesium.
Phosphate of sodium.	Sulpho-vinate of sodium.
Tartrate of potassium.	

Hydragogues are purgatives which excite a copious secretion from the intestinal mucous membrane and thus remove much water from the body; some of them belong also to the drastic group and others to the saline.

Bi-tartrate of potassium.
Elaterium.
Gamboge.

Cholagogues are purgatives which remove bile from the body. Some of them probably do this by stimulating the secretion of the liver, others by quickening peristaltic action of the duodenum and small intestine and thus preventing the absorption of the secreted bile.

Aloes.	Euonymin.
Rhubarb.	Iridin.
Mercurial preparations (blue pill, calomel, grey-powder).	Podophyllin.

Action of Purgatives.—Purgatives may act in three ways; 1st, by quickening the peristaltic action of the bowels; 2nd, by increasing secretion of the intestinal membrane, and thus to some extent washing out its interior; 3rd, by hindering absorption of the fluids of the intestines.

Simple purgatives act chiefly by stimulating **peristaltic** movements and have little effect on the secretion.

Hydragogue and **cholagogue** purgatives increase the secretion more than the peristaltic action, and **drastics** increase both. It has been held by several eminent German pharmacologists that the more watery stools produced by many purgatives are due only to more rapid peristaltic action, which hurries along the intestinal contents before there has been time for the absorption of their fluid constituents.

This opinion is chiefly based on the observations of Thiry and Radziejewski.

Thiry isolated a small piece of intestine, one end of which he attached to the abdomen and the other he sewed up. The part of the intestine from which this piece had been removed was again united by sutures, so that the intestine was perfect as before, though rather shorter. The small bag of intestine retains its vascular nerves supply uninjured and secreted readily when tickled with a feather, but purgative medicines, such as croton oil, senna, sulphate of magnesia, aloes, jalap, and sulphate of soda, when applied to it, produced no increased secretion. These experiments led pharmacologists to believe that the ordinary idea that purgatives produced increased secretion from the intestine was erroneous; and the necessity for any such supposition seemed to be removed by an experiment of Radziejewski, who made an intestinal fistula in the ascending colon of a dog, and found that the intestinal contents as poured into the large from the small intestine exactly resembled the stools which ordinarily follow the administration of a purgative.

The ordinary phenomena produced by purgative medicines would therefore seem to be readily explained by increased peristalsis alone, but some other experiments by Colin and by Moreau have shown that the method employed by Thiry did not afford trustworthy results as to the action of purgatives on the intestines. Moreau isolated three loops of intestine by means of ligatures, carefully emptying the loops beforehand. He then injected a purgative medicine into the middle loop and returned the intestine to the abdomen. On examination some hours afterwards, it was found that although all three loops had been under similar conditions, the one into which the purgative had been injected was distended with fluid while the others remained perfectly empty. These experiments were repeated by Vulpian, and afterwards by myself, with similar results. There can be no doubt whatever, then, that purgatives act both by increasing peristaltic action and intestinal secretion. Some purgatives act chiefly by the one, and some chiefly by the other.

In the case of some of the salines, the secretion is greatly increased, while the peristaltic movement is so little affected that the secretion may lie so long in the intestine as to be again reabsorbed, and the drug therefore fails to produce purgation at all. For this reason it is usual to **combine** such salines with simple purgatives, which will accelerate the peristalsis.

Laxatives have little action on the system beyond that which is due to the removal of waste and irritating substances from the bowels, but simple **purgatives,** and still more drastic purgatives, in addition to the direct action upon the bowels, exert an indirect effect upon the blood, removing from it a not inconsiderable portion of its fluid, and therefore causing a form of partial depletion.

The action of cholagogues will be more particularly considered in another paragraph (p. 353).

The action of purgatives generally and especially of saline cathartics has been a subject of very great dispute, and it is a matter of extreme difficulty to determine exactly. The question seems to be, however, settled by the masterly researches of Dr. Matthew Hay, and I cannot, I think, do better than give his conclusions in his own words.

1. A saline purgative always excites more or less secretion from the alimentary canal, depending on the amount of the salt and the strength of its solution, and varying with the nature of the salt.

2. The excito-secretory action of the salt is probably due to the bitterness as well as to the irritant and specific properties of the salt, and not to osmosis.

3. The low diffusibility of the salt impedes the absorption of the secreted fluid.

4. Between stimulated secretion on the one hand, and impeded absorption on the other, there is an accumulation of fluid in the canal.

5. The accumulated fluid, partly from ordinary dynamical laws, partly from a gentle stimulation of the peristaltic movements excited by distension, reaches the rectum and produces purgation.

6. Purgation will not ensue if water be withheld from the diet for one or two days previous to the administration of the salt in a concentrated form.

7. The absence of purgation is not due to the want of water in the alimentary canal, but to its deficiency in the blood.

8. Under ordinary conditions, with an unrestricted supply of water, the maximal amount of fluid accumulated within the canal corresponds very nearly to the quantity of water required to form a 5 or 6 per cent. solution of the amount of salt administered.

9. If, therefore, a solution of this strength be given, it does not increase in bulk.

10. If a solution of greater strength be administered, it rapidly increases in volume until the maximum is attained. This it accomplishes in the case of a 20 per cent. solution in from one to one and a half hours.

11. After the maximum has been reached, the fluid begins gradually and slowly to diminish in quantity.

12. *Cæteris paribus*, the weaker, or in other words, the more voluminous the solution of the salt administered is, the more quickly is the maximum within the canal reached; and accordingly purgation follows with greater rapidity.

13. Unless the solution of the salt is more concentrated than 10 per cent. it excites little or no secretion in the stomach.

14. The salt is absorbed with extreme slowness by the stomach of the cat.

15. The salt excites an active secretion in the intestines, and probably for the most part in the small intestine, all portions of this viscus being capable of yielding the secretion in almost equal quantities.

16. The bile and pancreatic juice participate but very little in the secretion.

17. The secretion is probably a true *succus entericus*, resembling the secretion obtained by Moreau after division of the mesenteric nerves.

18. The secretion is promoted by local irritation of the intestine, as by ligatures, but only in the immediate vicinity of the irritation.

19. Absorption by the intestine generally is reflexly stimulated by such irritation (the effect of numerous ligatures applied at points remote from the seat of the injected salt being to diminish the amount of purgative fluid by accelerated absorption).

20. If the salt solution be injected directly into the small intestine, the stronger within certain limits the solution is, the greater will be the accumulation of fluid within the intestine.

21. This difference is not observed when the salt is administered *per os*, as the strong solution becomes diluted in the stomach and duodenum before passing into the intestine generally.

22. The difference is due to the local action of the salt on the mucous membrane, and probably more to an impeded absorption than to a stimulated secretion.

23. When the salt is administered in the usual manner, it appears, in the case of the sulphate of magnesia and sulphate of soda, to become split up in the small intestine, the acid being more rapidly absorbed than the base.

24. A portion of the absorbed acid shortly afterwards returns to the intestines.

25. After the maximum of excretion of the acid has been reached, the salt begins very slowly and gradually to disappear by absorption, which is checked only by the occurrence of purgation.

26. During the alternations of absorption and secretion of the acid, it is the salt left within the intestine which excites secretion, the absorbed and excreted acid exerting no such action whilst in the blood, or during the process of its excretion, as Headland believed.

27. The salt does not purge when injected into the blood, and excites no intestinal secretion.

28. Nor does it purge, when injected subcutaneously, unless in virtue of its causing local irritation of the abdominal subcutaneous tissue, which acts reflexly on the intestines, dilating their blood-vessels, and perhaps stimulating their muscular movements.

29. The sulphate of soda exhibits no poisonous action when injected into the circulation.

30. The sulphate of magnesia is, on the other hand, powerfully toxic when so injected, paralysing first the respiration and afterwards the heart, and abolishing sensation or paralysing the sensory-motor reflex centres.

31. Both salts, when administered in the usual manner, produce a gradual but well-marked increase in the tension of the pulse.

32. According as the salt-solution within the intestine increases in amount, there occurs a corresponding diminution of the fluids of the blood.

33. The blood recoups itself in a short time by absorbing from the tissues a nearly equal quantity of their fluids.

34. The salt, after some hours, causes diuresis, and with it a second concentration of the blood, which continues so long as the diuresis is active.

35. As the intestinal secretion excited by the salt contains a very small proportion of organic matter as compared with the inorganic matter, the purgative removes more of the latter than the former from the blood. In certain cases a large quantity of the salts of the blood is thus evacuated.

36. The amount of the normal constituents of the urine is not affected by the salt.

37. After the administration of sulphate of magnesia much more of the acid than of the base is excreted in the urine.

38. The salt has no specific action in lowering the internal temperature of the body, or has it only to a very small extent.

39. It reduces, however, the absolute amount of heat in the body.

Uses.—Purgatives are used, firstly, to **remove** from the intestinal tube **fæcal** matters. They thus not only prevent the accumulation of such matters, but remove the irritation which their presence produces, and which may evidence itself in disturbances of other organs, producing, for example, headache and malaise. These disagreeable symptoms produced by constipation are perhaps partly due to the irritation of the intestinal nerves producing reflex disturbance of the circulation, but it is probable also that they may be due in part to the toxic action of poisonous gases, liquids, or solids, generated in the intestine by imperfect digestion or decomposition of the food. For such purposes as this we may employ, as we find them necessary, laxatives or simple purgatives.

The second use of purgatives is to **remove liquid** from the body in cases of dropsy, due either to heart or kidney disease. For such purposes we use saline hydragogue cathartics.

From his researches on the action of saline cathartics Dr. Hay had found that if a salt be given in a concentrated solution when the alimentary canal contains little or no fluid, it produces an almost immediate and very decided concentration of the blood by the removal of a large quantity of its water in the form of intestinal

secretion. But if the salt be given in sufficient water, or if the alimentary canal contain sufficient fluid at the time of administration, no such concentration occurs. The concentration reaches its maximum in half an hour, but does not last more than half an hour or an hour, when it begins to decline, and continues to do so until it reaches the normal at the end of about four hours. This return of the blood to its normal concentration is not due to re-absorption from the intestine, but to the absorption of lymph and fluids from the tissues. Some hours after the administration, either of a concentrated or dilute saline solution, the blood undergoes another concentration, less than the first but continuing longer. Saline cathartics as often used in **dilute** saline solution owe their use in dropsy to a great extent to their **diuretic** action. When given in **concentrated** solution under proper conditions, the benefit they produce by **purgation** is exceedingly great. These conditions are that the alimentary canal should be freed from food and especially from liquids by previous abstinence for some hours, and that the salt should be given along with the smallest possible quantity of water. Sulphate of magnesia being soluble in less than its own weight of water is most suitable. Alkaline tartrates and Rochelle salt may also be useful; sulphate of soda is more insoluble, and therefore less suitable; phosphate of soda and sulphate of potash are too insoluble to be of any service.[1]

The third use is to **lower** the **temperature** in fever, and for this we chiefly use salines. The *modus operandi* here is not yet well understood, as they have no such action in health (p. 344).

The fourth use is to **lower** the **blood-pressure,** and thus to prevent the rupture of a blood-vessel, and consequent apoplexy, or to prevent further extravasation in a case where the vessel has already burst.

The regular use of aperients is especially necessary in gouty persons with contracting kidney and high blood-pressure. How far their utility is to be ascribed to their direct effect in lowering the blood-pressure and how far to the removal of waste products which might raise the pressure it is impossible at present to say. The utility of purgatives after apoplexy has occurred may be doubtful, but they are usually administered, and probably they do no good. Even if they do no good, they do no harm. A drop of croton-oil or a few grains of calomel on the tongue is the usual form of administration.

A fifth use is to prevent straining at stool where violent efforts are dangerous, as in aneurism, hernia, &c.

Action of Irritant Poisons.

A great number of drugs which are employed in medicine, and are most useful when given in small doses, act as irritant poisons in large ones. Their action is then not restricted to the stomach,

[1] *Lancet*, April 21, 1883.

nor even to the whole of the intestinal canal, but they exercise, in addition, a marked effect upon other functions of the body, such as respiration and circulation.

In considering the physiological action of many drugs it is necessary to describe the effect they will produce when given in large quantities, as, for example, in an overdose, as well as in moderate or small ones.

It will save both time and space to consider here the action of irritant poisons generally, and to refer to this description when discussing the effect of individual drugs.

The symptoms of irritant poisoning are to a great extent the same, whatever be the irritants swallowed; it is therefore convenient to give an account of these symptoms, and then to mention the special peculiarities which occur in the case of different poisons.

A poison is most usually swallowed, and it then comes successively in contact with the lips, **mouth** and tongue, **gullet** and **stomach.** It may sometimes reach no further, being either evacuated by vomiting or absorbed. It frequently, however, also passes into the intestine. On all those parts which it reaches it exerts a local action; besides this, however, it exerts a reflex action on the respiration and circulation. Corrosive poisons produce a feeling of burning in the lips, mouth, gullet, and stomach; the **pain** in the stomach, extending more or less over the abdomen, is accompanied by tenderness, and is increased by pressure. It is thus distinguished from the pain of colic, which is usually relieved by pressure.



FIG. 110. – Diagram to show the nervous mechanism by which the action of the heart may be depressed by irritation of the stomach. The reflex irritation of the vagus may render the heart's action simply weak, or slow and weak (*vide* p. 232).

The irritation of the stomach gives rise to **vomiting;** the vomited matters usually consisting, first of the contents of the stomach, next of bile or mucus, and lastly of mucus stained with blood. These matters may sometimes be more or less acted

upon by the poison where this is a strong acid or alkali. The intense irritation in the stomach produces effects on the respiration and circulation very much like those caused by a severe blow in the epigastrium. The heart's action is greatly weakened at first, and it may be rendered slow from reflex irritation of the vagus, but in the later stages it is generally rapid, very small, weak, or almost imperceptible; sometimes it may be intermittent. On account of the weakness of the circulation the face and the general **surface** of the body are pale, the cheeks sunken, and the extremities cold. The frequency of the **respiration** may vary—may be either slower or quicker than normal, but it is almost always laboured and shallow, as the intense irritation in the stomach renders the descent of the diaphragm in deep inspiration painful, and the sufferer therefore tries to avoid it.

Although the **pulse** at the beginning of the poisoning may be slow, when advanced it is usually, as already mentioned, very rapid. Exceptions to this rule may occur chiefly in the case of poisons which, after their absorption, have an action on the heart itself; these are potassium nitrate and salts of barium. In consequence of the weakness of the circulation the face is usually very pale, but an exception to this may occur in poisoning by corrosive sublimate, where the face may be flushed. In arsenical poisoning the face is not only pale, but assumes a bluish hue, and the pinching may be extreme, so that the condition resembles that of a person suffering from Asiatic cholera.

Where the poison is exceedingly corrosive, as in the case of acids and alkalies, its local action on the stomach in causing swelling of the mucous membrane may tend partially to occlude the pylorus, and the greater part of the poison may either remain in the stomach itself or be ejected by vomiting without passing into the intestine. In such cases vomiting will occur alone without being accompanied by purging, and the pain in the abdomen may be less diffused. Most irritant poisons, however, pass from the stomach into the **intestines,** and thus violent purging is induced in addition to the vomiting. The inflammation of the intestines also causes the pain to be diffused over the whole abdomen.

Peculiarities in the Action of different Irritant Poisons.—Acids throw down albumen as a white precipitate, and in consequence, when brought in contact with the lips or tongue in a concentrated condition, they cause white stains. The white stain is most marked in the case of hydrochloric acid; it may occur also from sulphuric; but as the further action of the sulphuric is to char albumen or other organic substances, the stain may acquire a brown or black colour. Nitric acid produces a yellow stain, rendered brighter by the application of ammonia. Perchloride of iron produces a yellowish-brown stain; the caustic alkalies remove the epidermis and give a soapy feeling to the surface, but do not

leave any stain. After a short time the mucous membrane becomes injected and swollen from the irritation.

In the mouth the taste peculiar to the poison often leads to its detection, so that very little of it may be swallowed in cases where a person was about to take it unwittingly and not intentionally. Arsenic, although a powerful irritant in the stomach, is almost tasteless. As the poison passes down the gullet, it may have an important influence on the respiratory tract; this is especially the case where it gives off fumes like nitric acid, hydrochloric acid, and ammonia; the fumes, passing into the larynx and trachea, excite irritation, spasm, and inflammation, and may cause death by suffocation. Death by suffocation may, however, sometimes occur from the action of poisons which do not fume, *e.g.* sulphuric acid; the local irritation about the epiglottis being so great as to cause obstruction to the respiratory passages. Sometimes, also, such poisons as sulphuric acid may pass directly into the trachea instead of the œsophagus, and thus cause very rapid death from suffocation.

Purging is usually absent and the bowels constipated in poisoning by strong alkalies or acids, and by salts of lead; the former probably act by corroding the stomach, and partially occluding the pylorus; the latter by lessening the peristaltic movements of the intestine. In the case of lead salts, the abdominal pain differs from that of ordinary irritant poisons, being of a colicky nature, and to a certain extent relieved by pressure.

Secondary Effects of Irritant Poisoning.—After the immediate condition of collapse caused by the powerful action of the irritant has passed off, the local inflammation which it has produced may give rise to a general febrile condition, with hot skin, flushed face, and quick bounding pulse. This condition may be accompanied by other symptoms due to the physiological action of the poison after its absorption; thus, in the case of corrosive sublimate, there may be the metallic taste, sore gums, and profuse salivation.

One of the most important instances of the secondary effects of irritant poisons is phosphorus; after the primary symptoms of gastric irritation have passed off the patient may appear perfectly well, and then vomiting and purging may set in a second time. These are due, not to the local action of the phosphorus which has been swallowed on the stomach and intestines, but to changes in the liver, blood, and other organs, which the phosphorus has produced after its absorption. A similar condition has been observed in poisoning by arsenic, but usually the symptoms of arsenical poisoning are continuous, and do not exhibit a distinct intermission of this kind.

Death may occur from the secondary action of some poisons a good while after the primary symptoms have disappeared; thus strong acids and alkalies may produce death, weeks or even

months after they have been swallowed, from the effects of their local action on the œsophagus or the stomach. During the passage down the œsophagus they may destroy the mucous membrane to such an extent that when it heals and the cicatrix begins to contract, the lumen of the tube may be completely obstructed, so that no food can reach the stomach, and the patient dies of starvation, or the mucous membrane of the stomach may be destroyed to such an extent that what remains is insufficient to digest the food, and the patient dies from non-assimilation.

Action of Drugs on the Liver.

The liver is by far the largest organ in the body, and it is placed in a very peculiar situation. It acts as a porter or doorkeeper to the circulation, all the substances which are absorbed from the intestinal canal having to pass through the portal vein and the capillaries of the liver before they can enter the general circulation.

Since the discovery by Ludwig and Schmidt-Mülheim that peptones are poisonous when injected directly into the circulation, the liver has acquired a new importance. Schiff and Lautenbach indeed had previously made some experiments which they thought showed that a subtle poison existed in the blood even of healthy animals, but was destroyed by the liver. They based this idea on the observation that ligature of the portal vein causes death in animals with very much the same symptoms as when they are bled to death. Ludwig had formerly explained this phenomenon by supposing that the ligature caused the blood to accumulate in the large and dilatable portal radicals and prevented it from getting into the general circulation again. The animal was thus, as Ludwig expressed it, bled to death into its own veins. Schiff and Lautenbach, however, thought the symptoms were due rather to poison than to this mechanical alteration in the circulation, because they found that when the blood of an animal whose portal vein had been ligatured was injected into a frog, it produced death within three hours, whereas blood from a similar animal whose portal vein had not been ligatured produced no effect.

The **liver** therefore seems to have a most important function in **destroying** the **poisonous properties** of **peptones,** and perhaps **other substances** produced during digestion, and possibly also of poisonous products of tissue waste. The peptones are converted by it into sugar and glycogenic substance.[1]

Drugs which act on the liver are usually divided into hepatic stimulants and cholagogues and into hepatic depressants.

It has been for a very long time a matter of clinical experience that the administration of mercurial purgatives was frequently followed by the discharge of greenish bilious-looking evacuations

[1] Seegen, Pflüger's *Archiv.* xxviii. p. 990.

and a great improvement in the general condition of the patient. These two results were classed together as cause and effect, and the improvement was considered to be due to the removal of bile. It was then supposed that the bile was formed in the blood and simply excreted by the liver, and, therefore, the bilious-looking stools were ascribed to stimulation of the secreting function of the liver by the mercurials. Hepatic stimulants and cholagogues were therefore considered to be identical. We now know that the bile is formed in the liver and not simply excreted by it from the blood, and that bile formed in the liver may again be absorbed into the blood. Increased functional activity of the liver might thus lead to the presence of a greater instead of a less quantity of bile in the blood. Recent experiments have also shown that one of the most marked cholagogues which we know, viz. calomel, appears rather to diminish than to increase the actual secretion of bile, so that we are now obliged to distinguish between hepatic stimulants and cholagogues. **Hepatic stimulants** are drugs which increase the functional activity of the liver, and the amount of bile which it forms. **Cholagogues** are substances which remove bile from the body, possibly by acting rather on the intestines; they do not necessarily increase the secretion of bile, they may only prevent its re-absorption and thus diminish the quantity in the circulation. Hepatic depressants are drugs which lessen the quantity of bile secreted by the liver.

In relation to tissue waste it is not to be forgotten that the products of the functional activity of one organ are not only poisonous to itself, but may be poisonous to other organs. Thus the waste products of muscular activity gradually poison the muscle and prevent its contraction, although as soon as they are washed out with salt solution the muscle recovers its power.

Lactic acid also, which is a product of muscular waste, is poisonous not only to muscle but to some extent to nerves, and lessens the functional activity of the brain and produces sleep. At the same time it is possible that these waste products, poisonous in themselves, may through slight changes be rendered available for nutrition, just as peptones which are themselves poisonous are most important foods.

Besides acting on peptones, the liver seems to have the power of destroying the poisonous properties of some **vegetable alkaloids.** For example, $\frac{1}{20}$th of a drop of nicotin given to a frog does not produce death, but $\frac{1}{40}$th is sufficient, when the liver has been previously removed. Conia, cobra poison and hyoscyamin, all exert much less poisonous action after they pass through the liver, before they reach the general circulation, than they do when injected directly into the blood. Curare, prussic acid and atropia, on the other hand, do not have their action modified.[1]

[1] Lautenbach, *Philadelphia Medical Times*, May 26, 1877.

The result of these experiments, may be partly explained on the supposition that a good deal of the **poison** has been **excreted** along with the bile, and has thus been prevented from reaching the general circulation. But it is probable that in addition to the function of excreting poisons, the liver has also got the power of destroying poisons, and, it may be, the power of removing poisons from the circulation by merely storing them for a time.

In relation to this subject it is interesting to bear in mind that alkaloids to which the name of ptomaïnes has been given, are formed in dead bodies during the process of decomposition, and that when a solution of peptone is treated with potash and ether it yields a body which appears to be a volatile alkaloid. If putrid peptone is treated in the same way, a solid non-volatile alkaloid is obtained.[1]

Ptomaïnes are not only formed in dead bodies, they are also formed in the intestine by the decomposition of parts of its contents. They have been found in large quantities by Bouchard both in the stools of persons suffering from diarrhœa or typhoid fever, and in normal fæces. They appear to be absorbed from the intestine into the blood and excreted by the urine. They have been found by Bouchard in the urine both in health and disease, and Bocci has shown that the human urine has a paralysing action on frogs like that of curare, or of the ptomaïnes which Mosso and Guareschi have obtained from putrefied fibrin or brain.

Some time ago I pointed out[2] the resemblance between the languor and weakness which occur in many cases of indigestion and the symptoms of poisoning by curare, and drew attention to the probability that the languor was due to the effect of poisonous substances absorbed from the intestine. These I considered to be probably peptones, but it is possible that they may be ptomaïnes. But whether the poisonous substances be peptones or ptomaïnes, the function of the liver is equally important in preventing them from reaching the general circulation.

Bearing in mind, then, the office of the liver as a porter to prevent the passage of injurious substances from the intestinal canal into the blood, and the great effect that any alteration in the circulation through it may produce upon the circulation, and consequently on the functions of all the intestinal organs, we will much more readily understand the importance of this gland, the largest in the body, than if we look upon it simply as an instrument for secreting the bile which plays a useful, but still subordinate part in the process of digestion.

We are still but imperfectly acquainted with its functions, but we may say that they are at least five :—

[1] Tanret, *Comptes Rendus*, xcii. 1163.

[2] Lauder Brunton, "Indigestion as a Cause of Nervous Depression," *Practitioner*, vol. xxv. October and November, 1880.

1st, to **form** and **store up glycogen,** a material which will afterwards be used in evolving heat and muscular energy: it will thus, as it were, perform the office of a kind of coal-bunker to the body;

2ndly, to **secrete bile** for use in digestion;

3rdly, to **excrete bile**;

4thly, to **destroy peptones** which are poisonous when they are directly introduced into the general circulation, and to convert them into glycogen, &c.;

5thly, to **destroy** or store up and **excrete** other organic **poisons** which may have been formed in the alimentary canal during the process of digestion, or may have been introduced into it from without.

The **glycogenic function** of the liver is influenced by a number of drugs, especially phosphorus, and substances belonging to the same chemical group. Phosphorus, arsenic, and antimony, all destroy the glycogenic function, and at the same time tend to cause fatty degeneration of the organ. It is possible that these effects of the poisons are closely connected, but the exact connection between them has not yet been ascertained.

In consequence of the disappearance of glycogen from the liver which is caused by these drugs, puncture of the fourth ventricle will no longer cause glycosuria in animals which have been poisoned by them. Attempts have been made to utilise this fact in the treatment of diabetes, but as yet the results have not been very satisfactory.

Hepatic Stimulants.—The action of drugs on the **secretion** of the liver has been very carefully studied by some observers, especially by Röhrig, Rutherford, and Vignal. The mode of experimenting was to curarise a dog, ligature the common bile duct and insert a cannula into it. The bile was thus entirely prevented from reaching the intestine, and the whole of it flowed through the cannula into a vessel in which it was collected, so that the amount secreted in a given time was readily estimated. The drug was then administered, usually by injection into the duodenum, and the increase or diminution which this caused in the bile was noticed

The ingestion of **food** greatly **increases** the secretion of bile, and in order to get rid of this disturbing factor, the experiments were all made on fasting animals.

A great number of drugs were experimented upon, some of which were found to stimulate the liver, and increase the quantity of bile without altering its quality, so that their action upon the liver would be nearly analogous to that of laxatives upon the intestine; others increase the quantity of bile, and render it more watery; others again had little effect upon the liver, but stimulated the intestinal secretion and movements.

The following are hepatic stimulants :—

Acid, dilute nitro-hydro-chloric.[1]	Ammonium benzo-ate.[2]	Podophyllin.[1]
Aloes.[1]	Baptisin.[2]	Sanguinarin.[1]
Rochelle salt.[3]	Euonymin.[1]	Colchicin.[1]
Sodium sulphate.[2]	Hydrastin.[2]	Colocynth.[1]
Sodium phosphate.[1]	Juglandin.[2]	Jalap.[2]
Potassium sulphate.[2]	Iridin.[1]	Rhubarb.[2]
Mercuric chloride.[1]	Leptandrin.[2]	Ipecacuanha.[1]
Sodium salicylate.[1]	Phylolaccin.[1]	Physostigma[3] (extract).
Sodium benzoate.[1]		

The most powerful stimulants in the preceding list are indicated by ([1]), the less powerful by ([2]) and ([3]).

Those drugs which stimulate the intestine much, as a rule increase only slightly the secretion of bile by the liver, and podophyllin, which in certain doses acts as a powerful hepatic stimulant, ceases to have this effect when it produces marked purgation. These effects occur independently of the action of the drugs on the re-absorption and re-secretion of bile, inasmuch as in the experiments quoted the whole of the bile was collected directly from the liver and not allowed to pass at all into the intestine.

Cholagogues.—In making similar experiments, however, Schiff observed that the secretion of bile was very much greater


Liver with bile duct leading into the duodenum.
Portal vein with entero-hepatic circulation showing absorption and re-excretion of bile.....
Mesenteric veins .....
Stomach.
Small Intestine.
Colon.

FIG. 111.

for a short time immediately after the bile duct was tied, than it was later on; and on further investigation he found that this was due to the fact that the liver has a double function: it not only **forms new bile,** but **re-excretes** the **old bile** which has been re-absorbed from the intestine. A certain quantity of bile is lost

in the fæces, but a considerable portion of it seems to be utilised again and again; being formed by the liver, poured out into the intestine, re-absorbed and again excreted. This circulation of bile between the intestine and the liver has been called by Lussana the entero-hepatic circulation. It has been shown that the bile which is absorbed from the duodenum does not merely act as a stimulus to the liver to cause a greater formation of new bile, but is actually re-excreted by injecting ox-bile, which gives Pettenkofer's reaction, into the duodenum of a guinea-pig, and finding that shortly afterwards the bile which issued from the gall duct gave this reaction while the bile normally secreted by the guinea-pig does not.

Not only is bile re-excreted in this manner by the liver, but other substances also, such as **medicines** and **poisons,** are likewise **excreted.** The absorption and re-excretion takes place with great rapidity, for Laffter, in some experiments made under Heidenhain's direction, found that rhubarb injected into the duodenum appeared in the bile in less than five minutes. Substances injected into the blood were also excreted by the bile with great rapidity, so that sulphindigotate of soda introduced directly into the circulation in some experiments, began to colour the bile blue one minute after its injection. Other substances are also absorbed from the intestine and excreted by the liver and passed round in the entero-hepatic circulation, just like the bile. Curare is one of those, and to this probably is due in a great measure the absence of fatal effect from its introduction into the stomach. **Iron** also circulates with the bile, and it is probable that the beneficial effect of large doses may be due in part to the action of the iron upon the liver. The objection has been raised to the use of large doses that they are useless, inasmuch as the whole of the iron which is taken into the mouth is again expelled in the fæces, but there can be no doubt that clinically large doses of iron are sometimes beneficial. Copper and manganese also appear in the bile, and it is probable that lead and all the heavy metals pass chiefly out of the body by this channel.

It has been suggested by Lussana that the **malarial poison** also circulates in the entero-hepatic circulation.

From the fact that bile is re-absorbed from the intestine, it is obvious that a **hepatic stimulant** which simply increases the secretion of the bile by the liver, **will not of itself act as a cholagogue** and remove the bile from the body. In order to do this, this action must be combined with increased peristaltic action of the bowels which will hurry the bile out and prevent its re-absorption. If in addition to increased peristalsis, we have increased secretion from the intestinal mucous membrane, so as to wash out the intestine, we shall get the bile still more effectually removed from the body. The necessity for such a combination has indeed been long ago shown by clinical experience, and the

advantages of following a mercurial pill by a saline purgative in order to clear it away have long been recognised. Some hepatic stimulants increase also the peristaltic movements and secretions from the intestine, for example those substances which have been already enumerated as cholagogue purgatives.

Aloes.	Colocynth.	Sulphate of potash.
Baptisin.	Jalap.	Sulphate of soda.
Colchicum in large doses.	Podophyllin.	Phosphate of soda.
	Rhubarb.	Mercury salts.

In most cases, however, it is advisable to **combine hepatic** and **intestinal stimulants** in order to insure a more complete **cholagogue effect.** Thus calomel as employed in Rutherford's experiments has no stimulant action on the liver, but stimulates the intestinal glands; corrosive sublimate, on the contrary, stimulates the liver powerfully but has a very feeble stimulant action on the intestine; a combination of the two stimulates both the liver and the intestinal glands. When used in medicine, calomel is recognised to be a powerful cholagogue, one of the most powerful indeed that we possess, and it is by no means impossible that a small portion of it may be converted into a corrosive sublimate in the intestine, so that we thus get from the calomel, when given alone, the combined effects of both the mercurial preparations just mentioned. It is perhaps more probable, however, that the cholagogue action of calomel may be due to its having a peculiar stimulant action on the duodenum and ileum, so as to hurry the bile along the intestine and prevent its re-absorption. The reason for supposing that this is the case rather than that part of it is converted into corrosive sublimate and stimulates the liver, is that when given to dogs with a permanent fistula it does not increase the flow of bile, which it would probably do if any corrosive sublimate were formed. Another is that after the administration of calomel, leucine and tyrosine, which are products of pancreatic digestion, are found in the stools, and it seems not improbable that their appearance under such circumstances is due to their having been hurried along the intestine from the duodenum to the anus, and evacuated without time being allowed for their absorption or decomposition in the intestine.

Adjuncts to Cholagogues.—The pressure under which bile is secreted is very low, so that a very slight obstruction to its flow through the common bile duct is sufficient to cause its accumulation in the gall bladder and gall ducts, and thus to lead to its re-absorption. This is readily observed in cases of catarrh, either of the duodenum or of the gall ducts. In such cases the use of ipecacuanha is indicated. It has been found clinically to be of great service, and it probably acts by lessening the tenacity of the mucus in the gall duct, and thus tends to remove the obstruction in front, while at the same time it increases the pressure behind, by stimu-

lating the hepatic secretion. The movements of the **diaphragm** have a powerful action in aiding the **expulsion** of **bile** from the liver; they do this to a certain extent in ordinary respiration, but their effect is much greater in forced inspiration. Exercise therefore tends to expel bile from the liver, and prevent its accumulation in the biliary capillaries, but a little **brisk exercise** as in riding, rowing, climbing, tennis, &c., will have in a few minutes a more beneficial action than a lazy constitutional walk of a couple of hours.

The secretion of bile is not only increased, but the **pressure** under which it is secreted is **raised** by **sipping fluids.** This is in all probability due to nervous influence, for it has been shown by Kronecker that taking a liquid in numerous small sips will for the time completely abolish the inhibitory action of the vagus on the heart. It is probable in consequence of this fact, that Carlsbad water when taken in numerous sips for an hour or more, as at Carlsbad itself, is so exceedingly efficacious in hepatic diseases, while sodium sulphate, which is the main constituent of the water, was found by Rutherford to have only a very slight action as a stimulant to the liver.

Uses of Hepatic Stimulants and Cholagogues.—The pressure under which the bile is secreted is very small, but the blood-pressure also in the portal vein is very low. In consequence of this a very slight increase in the tension of the bile within the gall ducts, or diminution of the pressure of blood in the vein, causes the bile to be absorbed. It is then carried by the circulation to various parts of the body and disturbs their functions. It lessens the power of the heart and appears to diminish the activity of the brain, so that persons suffering from biliousness and presenting a slight icteric tinge of the conjunctiva, are apt to feel irritable, stupid, and out of sorts generally. Cholagogues are useful by removing bile from the body, and thus relieving the symptoms above mentioned. It is probable, however, that they also in some way improve the portal circulation, and thus lessen congestion of the stomach and intestines as in Beaumont's experiments on Alexis St. Martin (p. 320).

Hepatic Depressants.

Purgatives will act as hepatic depressants and lessen the secretion of the liver by removing from the intestine the bile which would otherwise be re-absorbed, and by hurrying out also the food which might yield materials for the secretion of new bile, but some substances, such as calomel, castor-oil, gamboge, and magnesium sulphate, were found by Rutherford to depress the secretion in cases where the bile duct was ligatured and the animals fasting, so that in all probability the effect of the drugs in diminishing the secretion was due to their lowering the blood-pressure in the liver.

Action of Drugs on the Pancreas.

The pancreatic juice is important in the process of digestion, as it has the threefold power of converting starch into sugar, of digesting proteids with the formation of peptones, and of splitting up fats.

The process of secretion in the pancreas is associated with increased blood supply as in other glands. Its nerves arise from the hepatic, splenic, and superior mesentery plexures, with branches from the vagi and splanchnics. Electrical stimulation of the gland itself will cause secretion, and so will stimulation of the medulla oblongata. It is arrested by powerful irritation of sensory nerves, such as the central end of the vagus, the crural or sciatic, and by the production of nausea or vomiting.

The secretion is stimulated by the injection of ether into the stomach, and appears to be paralysed by atropine in the same way as the secretion of the salivary gland.

When fibrin is digested with pancreatic juice the solution soon begins to swarm with bacteria and products of decomposition occur, among which is indol with a peculiarly disagreeable odour.

When calomel is added to pancreatic juice it does not impair its digestive action upon starch, proteids, or fats, but it arrests decomposition, and thus prevents the formation of indol and scatol, although leucin and tyrosin, which are the normal products of pancreatic digestion, are still formed. Salicylic acid has a similar action.[1]

After the administration of calomel the stools are often of a green colour, and this is due to unaltered bile. From the experiments on biliary fistulæ already mentioned it is probable that this bile in the motions is not due to increased secretion by the liver but to occurrence of diminished absorption, caused by its more rapid passage through the intestine, and possibly also to lessened transformation from the effect of the calomel in preventing its decomposition.

Anthelmintics.

These are remedies which kill or expel intestinal worms.

They have been divided into **vermicides,** which kill the worm, and **vermifuges,** which expel the worm without necessarily killing it, *e.g.* purgatives.

The chief worms which infest the intestine are tape worms, round worms, and thread worms.

The chief Vermicides are :—

For THREAD WORMS.—Local injections of alum, iron, lime-water, quassia, eucalyptol, sodium chloride, and tannin or substances containing it, as catechu, hamatoxylon, kino, rhatany.

For ROUND WORMS.—Santonin, santonica.

For TAPE WORMS.—Areca nut, filix mas, kamala, kousso, pomegranate, turpentine.

[1] *Zeitschr. f. physiol. Chem.* vi. 2.

As VERMIFUGES.—Castor oil, scammony.

Adjuncts.—Ammonium chloride, common salt and iron, and bitter tonics, are useful internally in preventing excessive secretion of intestinal mucus which affords a **nidus** for intestinal worms.

Uses.—They are used to destroy and remove worms present in the intestine. In order that the remedies can come into more intimate contact with the worms, and thus destroy them more easily, it is usual to clear out the intestine by a purgative some hours before the administration of the remedy, which is usually given on an empty stomach, or with a small quantity of milk. After some hours another purgative is given in order to bring the worms away. As much mucus in the intestine forms a nidus for the worms, remedies which diminish it tend to prevent their occurrence. For this purpose preparations of iron and bitter tonics are useful.

CHAPTER XIV.

DRUGS ACTING ON TISSUE CHANGE.

Tonics.

THESE are remedies which impart permanent strength to the body, or its parts. When an individual is loose and limp, and feels unfit for work, like a relaxed bowstring, tonics **restore** his **energy** and strength, and again fit him for work. As their action in this respect resembles the effect of tightening a bowstring, they have received their name, which is derived from τόνος, tension. The feeling of **debility** may depend on many different causes. It may be due to weakness of the muscles, or weakness of the nervous system. Again, the nerves and muscles may suffer because the circulation is languid and feeble, or because the blood which supplies them is deficient in oxygen, or in nutritive matter. These deficiencies again may depend on **deficient nutrition**, due to want of appetite, so that too little food is consumed, or to an improper or insufficient diet, or to imperfect digestion, so that it is not assimilated. But weakness may be also induced by the **accumulation** of **waste products** in the body, which interfere with the functional activity of the muscular and nervous systems; and these products may accumulate, because they are formed in excess in the tissues themselves by overwork, or in the intestinal canal from imperfect digestion; or because they may be allowed to pass too readily from the intestinal canal into the blood by deficient action of the liver.

Or their excretion may be defective from the kidneys being insufficiently active, or the bowels constipated.

The mode of action of tonics is so manifold that they have been divided into blood tonics or hæmatinics, vascular tonics, gastric tonics, intestinal tonics, and nervine tonics.

Uses.—In order to ascertain what form of tonic is required, it is necessary to determine carefully what part of the organism is in fault. In very many cases the imperfect functional activity in the body generally, which exhibits itself in languor and weakness, is due to accumulation of waste products, and not to deficient nutriment. In such cases the plan of loading the stomach with food,

and giving iron, wine, and beef-tea, simply increases the mischief. If it is found on examination of the urine that the kidneys are not excreting a sufficient quantity of solids, and especially of urea, it is necessary to diminish the quantity of food, and especially of animal food, as all, or nearly all, the nitrogen taken into the body must be excreted by the kidneys.

In order that no unnecessary work be thrown on the kidneys, we must as far as possible prevent products of imperfect digestion from being absorbed from the intestinal canal, and therefore the state of the liver must be carefully attended to, and the bowels themselves carefully regulated.

In cases where the debility does not depend upon excessive waste products in the blood and tissues, but upon defective oxidation due to deficiency of hæmoglobin, the patient must be treated by **hæmatinics** such as iron, cod-liver oil, and phosphate of lime. When the digestion is imperfect, gastric or **intestinal** tonics must be used as the case requires.

Where enfeeblement of the stomach appears to be present, as shown by loss of appetite, and such signs of imperfect digestion as flatulence or weight and pain after eating, **gastric** tonics are used. Should its muscular coat be feeble or inactive, as shown by tendency to dilatation and splashing of the contents on movement, strychnine is especially indicated, and galvanism or systematic kneading may be also employed. Where the stomach is too debilitated to respond sufficiently to this form of treatment, as after long-continued gastric catarrh, or in old age, its work must be partly done for it, and then such **digestives** as hydrochloric acid and pepsin are useful. When the muscular movements of the intestine are sluggish, as indicated by constipation and by a tendency to the distension of the bowel with gas, nux vomica and belladonna may be given; and when its mucous membrane appears to be relaxed and flabby, and secreting too profusely, the mineral acids, astringents and metallic salts may be of much service. When the pulse is soft and feeble, and there is a tendency to vascular dilatation, either general or local, as shown by local congestion and œdema of the dependent parts, or by drowsiness in the upright position and sleeplessness in the recumbent posture, **vascular** tonics are serviceable. **Nerve** tonics are used where the nervous functions are imperfectly performed, as shown by dulness, loss of memory, incapacity for work, languor, paralysis, or tendency to spasm, as in chorea. As the functions of this system depend very greatly upon the quality of the blood with which the nervous system is supplied, and on the rapidity of the circulation, the other tonics frequently require to be given in addition to nervine tonics.

Hæmatinics.

Blood tonics, blood restoratives, analeptic tonics.—These are generally remedies which improve the quality of the blood; but the name blood tonics or hæmatinics is generally applied specially to such remedies as **increase** the quantity of red blood-corpuscles and **hæmoglobin** in the blood. The quality of the blood depends upon a number of conditions: upon the amount and nature of the food ingested, on the digestion, on the formation and excretion of the various products of tissue change, and more especially on the formation and destruction of the red blood-corpuscles themselves.

The red **blood-corpuscles** are probably **formed** in the spleen, the medulla of bones, the liver, and possibly other parts of the body, from leucocytes which lose their nucleus, take up hæmoglobin, and alter their form to that of the red corpuscles.

The red corpuscles are probably **destroyed,** at least to a great extent, in the liver, and probably also in the spleen. The colouring matter of bile contains a quantity of iron, and appears to be formed from hæmoglobin.

An abnormal condition of the liver, by leading to excessive destruction of blood-corpuscles, may therefore be an important cause of anæmia. The corpuscles contain albuminous matters as well as hæmoglobin, and deficiency of albumen in the blood will lead to anæmia. Thus, in cases of Bright's disease, the loss of albumen through the kidneys tends to produce anæmia, and this must be combated by lessening the loss, if possible, as well as by supplying albumen.

The blood-corpuscles also contain fat, and deficiency of fatty food will tend to produce anæmia. Cod-liver oil, on the other hand, which is an easily assimilated form of fat, is a powerful hæmatinic. In anæmia there is a deficiency of iron in the blood, and chalybeate preparations are among the most powerful of all hæmatinics.

One well-marked disease due to imperfect nutrition is scurvy. In it there is not only a deficiency of red blood-corpuscles, but a tendency to extravasation. Its pathology is not definitely made out, and it has been supposed to be due to a deficiency of potash in the blood, but it is much more likely that it is due to increase in the chlorides, and especially chloride of sodium, either absolutely or relatively to the carbonates.

Excess of chloride of sodium causes the blood-corpuscles to pass out of the vessels (page 49), and potash salts alone, or beef-tea, which contains them, do not cure scurvy; but it is removed by fresh vegetables or by lime juice.

Alteratives.

These are remedies which **improve** the **nutrition** of the body **without** exerting any very **perceptible action** on individual organs. The chief alteratives are:—

Arsenic.	Colchicum.
Mercury.	Guaiacum.
Iodine. Iodides.	Stillingia.
Cod-liver oil.	Sanguinaria.
Sarsaparilla.	Xanthoxylum.
Gold.	Mezereum.

Action.—Healthy nutrition depends (1) upon a proper supply of oxygen and nutriment to each tissue and organ in the body, (2) on the proper amount and kind of tissue change in the various cells; (3) on the proper removal of waste.

The proper supply of oxygen and of nutriment to the body generally will depend upon the state of the respiratory and digestive organs; their proper supply to the tissues, as well as the removal of waste from them, will depend upon the circulation; and the removal of waste from the body generally will depend upon the bowels, skin, and kidneys.

The drugs which act upon the different organs just mentioned are considered under other headings, but the changes which take place in the tissues themselves appear to be effected by drugs which produce no marked corresponding changes in assimilation, circulation, or excretion. It is uncertain how they act: it is possible that they may alter in some way the action of enzymes in the body, but it is also possible that they act by replacing the normal constituents of the tissues and forming compounds which tend to break up in a different way from those which are ordinarily present.

Thus chloride of sodium and nitrogenous bodies such as albumen are amongst the most important constituents of the body; and we find that among the chief alteratives are substances which will replace chlorine, soda, or nitrogen in many compounds. Thus we have iodine and iodides, and nitric or nitrohydrochloric acids, which will displace or replace chlorine. We have chlorine itself, and chlorides which may alter the proportion of chlorides to other salts in the blood and tissues and thus modify the solubility of various constituents of the tissues. We have salts of potash and lime which may replace those of soda; sulphur, and sulphides which may replace oxygen; phosphorus, hypophosphites, antimony and arsenic, which may replace nitrogen: mercury and its salts which may replace calcium.

Besides these we have organic alteratives, regarding the action of which we can at present form no hypothesis unless they influence the processes of digestion. Nitrohydrochloric acids, taraxacum, and

small doses of mercurials, probably act either by modifying the digestion of food in the duodenum and jejunum, or by modifying the changes which it undergoes in the liver after absorption.

The action of drugs upon tissue change has usually been investigated by ascertaining the amount of urea excreted before, during, and after the administration of a drug. Most of the older experiments on this subject are of little or no value, as sufficient care was not taken to ensure that the amount of nitrogenous food consumed each day during the experiment was exactly the same. As all the nitrogen taken in the food reappears in the urine, any irregularity in the quantity introduced into the body will cause a corresponding irregularity in the quantity excreted. After this fact was ascertained the plan adopted by some experimenters was to deprive an animal of food for several days until the excretion of urea due to the gradual destruction of its nitrogenous tissues became nearly constant The plan now adopted is to give to a dog or a man a quantity of food of an uniform quality and the amount of nitrogen in which is exactly known. The quantity given each day is exactly weighed. The same amount of nitrogen is thus introduced into the organism every day, and therefore any variations in the amount of nitrogen excreted must be due to changes in the organism itself.

Observations on the excretions of urea only give us a very partial and imperfect knowledge of the process of tissue change, and they ought to be combined as in the experiments of Pettenkofer and Voit with observations on the amount of oxygen absorbed and of carbonic acid given off. Such experiments as these, although very valuable, are very laborious, and comparatively few have hitherto been made.[1]

From experiments made with those necessary precautions just described it has been found that free consumption of water increases tissue change very considerably, as is shown by the increased excretion of urea.

Common salt, sulphate of soda, phosphate of soda, acetate of soda, borax, nitrate of potash, chloride of ammonium, carbonate of ammonium and probably all salts which pass out in the urine carrying water with them, somewhat increase tissue change and the amount of urea excreted. Fats and fatty acids apparently lessen the decomposition of albuminous tissues and the excretion of urea, but glycerine has no action of this sort. Alcohol in small or moderate doses lessens, in large doses increases, tissue change. Benzoic acid, salicylic acid and benzamide, all increase tissue change and the excretion of urea. Contrary to what perhaps might have been expected, tea, coffee and cocoa, have no action whatever on the excretion of urea.[2] The experiments which seemed to show that they diminished it, appear to have been made without the necessary precautions. Morphine slightly diminishes the excretion of urea but its action is much more marked on the consumption of oxygen and excretion of carbonic acid. These are greatly increased in the stage of excitement and greatly diminished in the stage of

[1] A complete account of the whole subject is given by Voit in Hermann's *Handb. d. physiol.* Band. VI. Theil. i. This contains also complete references to the literature.

[2] Voit, *op. cit.*

quiescence. It would appear that these changes are not due to the direct action of the morphine but only to the alterations of muscular activity which follow its administration.

Quinine lessens tissue change, iron appears to increase it, mercury also slightly increases it,[1] while iodine appears to have little influence upon the quantity of urea excreted. This fact is of itself I think sufficient to show that the mere estimation of the quantity of urea excreted before and after the administration of a drug is quite insufficient to give us any precise information regarding their action on tissue metamorphosis.

Antimony, arsenic, and phosphorus have a special action on tissue change, and powerfully affect the glandular, nervous, respiratory and cutaneous systems. In large quantities they affect the liver very markedly, producing fatty degeneration: and this also occurs in other tissues.

This **fatty degeneration** is due to a twofold action:—1st, increased tissue metamorphosis; and 2nd, diminished oxidation. In the normal condition albuminous tissues split up as indicated below:—

Albuminous Tissues. Split up into: Non-nitrogenous substances ..... *e.g.* Fat, &c. — Converted in health into: Carbonic acid, excreted by lungs.

Albuminous Tissues. Split up into: Nitrogenous substances, *e.g.* Leucine, Tyrosine, &c. — Converted in health into: Urea, excreted by kidneys.

In poisoning by antimony, arsenic, and phosphorus, the nitrogenous products of tissue waste appear in much larger quantity in the urine than normally, owing to the increased decomposition which is going on. They may appear in the urine in the form of an excessive quantity of urea, as in cases of phosphorus poisoning in the dog, but in man they may appear in the form of leucine and tyrosine. Owing to the diminished oxidation the non-nitrogenous substances remain in the body as fat instead of being oxidised and passing out of the body as carbonic acid.

The exact nature of their effect on the nervous system has not been made out. Their action on the skin and epithelial cells of the lungs seems to be that of causing fatty degeneration.

Fatty degeneration of the liver occurs also in poisoning by salts of silver.

Mercury has a peculiar power of breaking up newly deposited fibrin and of causing disorganisation of syphilitic deposits. Iodine, iodides, and probably also chlorides, appear to act on the lymphatic system and promote absorption: their action is specially well marked in cases of glandular enlargement.

Uses.—In general mal-nutrition without definite symptoms, mercurials, taraxacum, and nitrohydrochloric acid are used and are especially indicated where the liver is suspected to be in fault, as where there are symptoms of biliousness, and also where oxalates and urates are found abundantly in the urine.

[1] Boeck, quoted by Voit, *op. cit.*

In gout, potash and colchicum are used. Phosphorus and arsenic are employed in nervous debility: and they as well as antimony are serviceable in neuralgia, chorea, and other nervous diseases.

In diseases of the skin, arsenic is chiefly employed.

In diseases of the respiratory organs, antimony is very serviceable when the attack is acute; and arsenic is most valuable in some chronic conditions, especially in chronic consolidation, where it probably acts by producing fatty degeneration and softening of the effusion, so that it is either absorbed or expectorated.

Mercury is employed specially to break up deposits of lymph and to prevent adhesions, as in iritis and pericarditis; and is also used and is most serviceable in the treatment of syphilis. It is most generally employed in the secondary stage of this disease: in the third stage it is either given along with, or entirely replaced by the use of, iodides.

Antipyretics, Febrifuges.

These are remedies which **reduce** the **temperature** of the body in fever. They act much more powerfully when the temperature is abnormally high than when it is normal.

The constant temperature of warm-blooded animals depends upon the maintenance of a proper balance between the amount of heat generated in the body, chiefly by oxidation, and on the amount given off to the surrounding medium—air or water. The heat is chiefly generated in the muscles and glands. It is chiefly given off by the skin, although some is also lost by the lungs, etc.

A little heat, but not much, may be given off by radiation alone. The power of dry air to take up heat is very slight, and so the skin is not much cooled, and very little sensation of cold is felt at temperatures much below 0° if the air is both still and dry. If the air be moist its capacity for heat is much greater, and the loss of heat from the skin being much more rapid, a person may actually feel the weather colder at 4° F. than at −40° F., the air being still in both cases. If air, either dry or moist, is in motion, so that fresh portions of it come successively into contact with the skin, the loss of heat is much more rapid, and a little wind will render even dry air unbearably cold at a temperature which would be quite supportable if the air were still.

It is to be observed that during sleep the action of the vasomotor centre is less, the vessels of the surface dilate, and loss of heat, with danger of consequent chill, takes place more rapidly. For the effects of local chill to the surface, *vide* Rossbach's experiments (p. 216).

Antipyretics may be divided into two great classes: those which **lessen** the **production** of heat, and those which **increase** the

loss of heat; and these again may be subdivided as shown in the following table :—



The mode of action of those which affect the blood and tissues themselves has already been considered tolerably fully under the head of "Oxidation of Protoplasm" (p. 53). They appear simply to diminish the temperature by lessening oxidation. The mode of action of antipyretics which produce their effect through the circulation, has not been investigated in detail with satisfactory exactitude, but it is supposed that by lessening the rapidity of the circulation through those parts of the body in which the increased tissue change is taking place, the temperature is reduced.

Blisters will have this effect locally by causing contraction of the vessels in the inflamed part, as already described under the head of Counter-Irritants (p. 299).

Antipyretics, which increase the **loss** of **heat,** may do so (1) by causing greater dilatation of the vessels of the skin, and thus allowing a quicker radiation of heat from the body; (2) by

augmenting the secretion of **sweat:** and thus carrying off heat by means of evaporation; or (3) they may actually **remove warmth** from the body, as cold baths, cold affusion, cold sponging, wet packing, cold enemata, or ice to the surface.

Uses.—Antipyretics are used to **lower** the **temperature** when it has risen above the normal, whatever be the cause. A high temperature may be produced simply by prolonged exposure to heat. This exposure, and the rise in temperature it occasions, seems to induce increased tissue change, and this increase of the tissue change will keep up a febrile temperature, even after the external temperature has fallen. Such thermal fever is found in warm climates, and in it quinine injected subcutaneously seems to be very efficient.

A high temperature may also occur from specific fevers, as typhus, typhoid, scarlet fever, measles, and acute rheumatism. The most rapid and powerful antipyretic in such cases is the application of cold by bathing, or sponging; and probably next come large doses of quinine or salicylate of soda. In typhoid fever, salicylate of soda does not seem to act so rapidly as it does in acute rheumatism.

Venesection, though formerly the antipyretic which was chiefly relied upon, has now fallen to a great extent out of use—this is probably from its having been very much abused.

In persons suffering from acute inflammation of the lungs or bronchi, where the amount of lung tissue which remains sound is insufficient to aërate the whole mass of blood, and the patient is becoming livid, small bleedings are serviceable, not only relieving the breathing, but lessening delirium which may be present.

Venesection lowers the temperature for a short time, but it soon rises again in many cases, so that bleeding alone is by no means a powerful antipyretic,[1] unless the quantity of blood abstracted be so great as probably to injure the patient seriously; yet in combination with other antipyretics it may sometimes be of very great service.

Local bleeding by **leeches** or by **wet cupping** sometimes gives very great relief, lessening both local inflammation and the general symptomatic fever consequent upon it, in pneumonia, pleurisy, pericarditis, peritonitis, etc. In such cases blisters may be used to diminish the local inflammation, and thus aid the action of other antipyretics.

Vascular antipyretics, such as aconite and digitalis, also seem to be of more service in symptomatic fever than they are in specific fevers.

Purgatives take an intermediate place between antipyretics which lessen the production of heat by acting on the tissues, and those which act on the circulation. They diminish the force of

[1] Wunderlich's *Medical Thermometry*, pp. 118, 134, 378, New Sydenham Society's edition.

the circulation, and may in this way lessen the production of heat. It is not impossible also, however, although this is a point on which we have not sufficient information, that they may do so by removing from the body substances whose effect when present in the circulation or tissues would be to maintain the high temperature.

Amongst antipyretics which increase the loss of heat we have: first, alcohol, which is included also in the former list of those which lessen the production of heat, for it appears to act in both ways, both diminishing oxidation and also increasing the loss of heat. It does this by dilating the vessels of the skin and allowing free radiation from the surface, and also by the cooling effect of evaporation of the sweat, although its action as a sudorific is not very marked.

We have also the whole class of **sudorifics** (p. 383). One of the most useful of these in checking a febrile condition just at its onset is a dose of compound ipecacuanha powder, or Dover's powder, which has now, to a great extent, taken the place of the older remedy, having a somewhat similar action, viz. antimonial powder, or James's powder.

Another mixture in great favour is acetate of ammonia and spirit of nitrous ether. The most powerful, however, of all remedies which increase the loss of heat are the application of **cold** water or ice. The mode of applying these is discussed at page 407.

CHAPTER XV.

ACTION OF DRUGS ON EXCRETION.

Action of Drugs on the Kidneys.

THE kidney has a twofold office. It has (1) to regulate the amount of water in the body under various conditions; (2) to remove the products of tissue waste. These products must be removed in a state of solution from the part of the kidney where they are excreted, and yet sometimes provision must be made for the water, by which they are washed out, being retained in the body. The urine in mammals and amphibia is liquid; in birds and reptiles it is semi-fluid or solid, yet the solid constituents are removed in solution from the urinary tubules, and the water in which they are dissolved is afterwards absorbed. We may say then that the kidney has not only a twofold, but a **threefold action**:—1st, the **excretion** of **waste** products; 2ndly, a provision for the **removal** of excessive **water**; and 3rdly, an arrangement for the **retention** of **water** in the body by its re-absorption, after it has washed out the waste products. On looking at the kidney we find three structures which seem to be connected with these three functions, viz.: (1) **convoluted tubules** with epithelial cells, which in all probability are the chief structures for excreting waste products; (2) the **Malpighian corpuscles** for excreting water along with some solids, and (3) usually one or more **constrictions** in the tubule which may serve the purpose of preventing too rapid exit of the water, and thus allow time for its re-absorption in cases where its retention is desirable, as for example on a hot day and when the supply of drinking-water is very limited.

The process of **secretion** in the kidney was regarded by Bowman as consisting of the filtration of water from the vessels of the glomeruli into the tubules, and the excretion of waste products by the epithelium lining the tubules. Ludwig, however, came to look upon it rather as a process of filtration and re-absorption; a dilute solution of urea and salt being according to him poured out from the Malpighian corpuscles and gradually concentrated by the absorption of water in its passage along the

tubules. This theory had so many facts in its favour that it was for a good while exclusively adopted, but latterly Heidenhain in an admirable series of experiments has shown that such substances as indigo are certainly excreted by the epithelium of the tubules. At the same time Hüfner has shown by a comparison of the structure of the kidney in fishes, frogs, tortoises, birds and mammals, that the form of the tubules closely agrees with that required for the re-absorption of water in each case. Fishes have a low blood-pressure, and so the resistance in the kidney requires to



FIG. 112.—Diagram showing the form of the urinary tubules in different classes of animals, after Hüfner. 1. Fish. 2. Frog. 3. Tortoise. 4. Bird. 5. Mammal. The letters have the same signification in each. *a*. Capsule of the glomerulus. *b*. Convoluted tubule. *c*. Loop. *d*. Collecting tubule. *u* in 2 indicates the transverse section of the ureter.

be small in order to allow of the secretion of urine. Living as they do in water, they do not require any apparatus for its retention in the body. In them therefore the tubule is short and wide, and destitute of any constriction which would retard the outflow of fluid. In frogs there must be ample provision for the retention of water in the body, as evaporation takes place freely from their skin. In them we find, as we might expect, that the tubule, and especially the contracted part of it, is very long. In tortoises no evaporation from the skin can take place, and in them the contracted part of the tubule is short. This renders it probable that, while the ideas advanced by Bowman and supported by Heidenhain are in the main true, the **re-absorption** of water on which Ludwig lays so much stress is also an important factor in the secretion of urine under different circumstances.

But it is not only rendered probable by the facts of comparative anatomy; it appears to be proved by **direct experiment.** Ribbert has extirpated the medullary substance of the kidney in the rabbit while leaving the cortical substance. He has thus succeeded in collecting the urine as it is excreted by the Malpighian corpuscles before it has passed through Henle's loops, and has found that the urine secreted by the cortical substance alone is much more watery than that which is secreted by the entire kidney, a fact which appears conclusively to prove that water is actually re-absorbed, and the urine rendered more concentrated, during its passage through the tubules of the medullary substance.

In the frog and triton the arrangement of the kidney is such as to allow of a much more complete investigation of the different factors in secretion, than in mammals, because in amphibia, the glomeruli which separate the water and the tubules which excrete the solids, receive their blood supply to a great extent independently. The glomeruli are supplied by branches of the renal artery. The tubules are supplied by a vein which proceeds from the posterior extremities and, entering the kidney, breaks up into a capillary plexus bearing a somewhat similar relation to the renal tubules as that which the portal vein does to the lobules of the liver. It is therefore called the portal vein of the kidney.

The arterial circulation in the glomeruli and the venous portal circulation round the tubules are not entirely distinct, for the efferent arteries of the glomeruli unite with the portal capillaries, and, moreover, arterial twigs also pass directly from the renal artery into the capillary venous plexus. The two systems are, however, so far distinct that Nussbaum has been able to ascertain with considerable exactitude the part played by each in secretion. By ligaturing the renal artery he destroyed the functional activity of the glomeruli, and by ligaturing the portal vein of the kidney he destroyed that of the tubules. By injecting a substance into the circulation after ligature either of the artery or the vein, and observing whether it is excreted or not, he determines whether it is excreted by the glomeruli or by the tubules. In this way he finds that sugar, peptones, and albumen pass out through the glomeruli exclusively, for they are not excreted when the renal arteries are tied. Albumen, however, only passes out through the glomeruli when an abnormal change has already occurred in the vascular wall; as, for example, after the circulation has been arrested for a while by ligature of the renal artery. Indigo-carmine, when injected after ligature of the renal arteries, passes into the epithelium of the tubules, but it does not give rise to any secretion of water, so that the bladder is found empty. Urea, on the contrary, is not only excreted by the tubules after ligature of the renal artery, but carries with it,

[1] Ribbert, *Virchow's Archiv*, July 1883, p. 189.

in the process of secretion, from the venous plexus, a considerable quantity of water, so that the bladder becomes partially filled.


Branch of renal artery.
Afferent artery to the glomerulus.
Connecting branch
Artery passing directly to the plexus (corresponding to one of the arteriæ rectæ).
Glomerulus with efferent artery.
Union of arterial and venous branches to form the plexus.
Portal vein of the kidney.
Urinary tubule.
Abdominal vein.
Small branch connecting the efferent artery from the glomerulus directly with the abdominal vein.

FIG. 113.—Diagram of the circulation in the kidney of the newt. Modified from Nussbaum.

The **excretion** of **water,** therefore, takes place in a **double** manner: it passes out through the glomeruli when the renal arteries are free, and it passes out from the venous plexus along with urea, even although the renal arteries are tied.



FIG. 114.—Diagrammatic sketch of the blood-vessels in a mammalian kidney; from Schweigger-Seidel, *Die Nieren,* Halle, 1865. *O* is an artery ascending into the cortical substance of the kidney; *p* is a branch from it which divides into two branches, *q* and *P*. *q* breaks up at once into a number of twigs. *P* is the afferent artery to a glomerulus, *S*, of the lowest row. *t* is the efferent vessel of the glomerulus. It divides into two branches, one of which, *u*, ascends towards the cortex, whilst the other, *v*, descends towards the medulla.

In the kidneys of the higher animals and of man the glomeruli and the tubules do not receive blood from two entirely different sources; but there is an arrangement somewhat similar, for the plexus surrounding the tubules does not receive blood only from the efferent vessels of the Malpighian corpuscles, but gets it also directly from the renal arteries. There are three channels by which the blood may pass from the renal arteries into the venous plexus without going through the glomeruli. The first is the inosculation which takes place between the terminal twigs of the renal artery and

the venous plexus on the surface of the kidney directly under the capsule.[1] The second channel is formed by small branches given off directly by the interlobular arteries or by the afferent arteries before they reach the glomeruli. The former of these may be regarded as corresponding to the artery which passes directly to the plexus in the newt, and the latter to the branch connecting it with the afferent artery (Fig. 113). These arterial twigs are



FIG. 115.—Diagram of the tubules and vascular supply of the kidney. On the left is a tubule alone; in the middle is a tubule along with the blood-vessels; on the right are blood-vessels only.

found not only near the surface of the kidney, but also in the deeper layers of the cortical substance.[2] The third and most important channel is afforded by the arteriæ rectæ, which spring from the branches of the renal artery at the boundary between the cortical and medullary substance and pass into the medulla, where they form a plexus with elongated meshes surrounding

[1] Ludwig, *Handwörterbuch d. Physiol.* v. R. Wagner, Bd. 2.

[2] Schweigger-Seidel, *Die Nieren*, p. 67; Heidenhain, Hermann's *Handbuch d. Physiologie*, vol. v. Th. 1, p. 293.

Henle's loops and the collecting tubules. Near their origin the arteriæ rectæ inosculate with the venous plexus surrounding the convoluted tubules.

Through these three channels it is possible for blood to reach the secreting structures of the kidney and there get rid of urea, salts, &c., without losing water by its passage through the glomeruli. On the other hand, if these vessels contract, while the size of the renal artery and the pressure of the blood within it remain unaltered, more blood will be forced into the Malpighian corpuscles, and thus the quantity of water excreted will be increased. At the same time the contraction of the arteriæ rectæ will probably diminish absorption from the tubules, and thus the quantity of water excreted will be increased in a twofold manner.

Circumstances Modifying the Secretion of Urine.—The experiments of Ludwig and his pupils have shown that the amount of urine secreted depends very closely upon the pressure of blood in the Malpighian corpuscles, or, to put it more exactly, on the **difference** of **pressure** between the blood in these corpuscles and the pressure within the tubules. For if the ureter be tied so that the pressure of urine in the tubules is increased, the secretion is greatly diminished, and even arrested, even though the pressure of blood in the renal artery be high.

A somewhat similar effect to that of ligature of the ureter is produced by ligature of the renal vein, for the blood accumulating in the venous plexus surrounding the tubules compresses them so as to prevent the flow of urine through them. A similar condition may occur from cardiac or pulmonary disease obstructing the venous circulation.

But unless under exceptional circumstances which alter the pressure within the tubules, such as compression of the tubules by congestion of the venous plexus, as in cardiac disease, impaction of a calculus in the ureter, or pressure on the ureters by dropsical accumulations or tumours, the rapidity of the **secretion** of urine depends on two factors :—(1) **arterial pressure** in the glomeruli ; and (2) the **composition** of the **blood.**

The **pressure** of blood in the glomeruli may be **raised :**

(1) By increase of the arterial tension generally.

(2) By increased tension locally.

Such a **general** increase may be brought about by greater action of the heart, or by contraction of the blood-vessels in other vascular areas, such as the intestines, muscles or skin, by nervous stimulation, exposure to cold, or the action of drugs.

The pressure may be increased **locally** by dilatation of the renal arteries, *e.g.* from section of the vaso-motor nerves, or possibly stimulation of vaso-dilating nerves.

In addition to such increase of pressure in the glomeruli by increase of blood supply to them, we must not, however, forget the possibility of increased pressure in them by contraction of

the efferent vessels leading from them, as well as of those arterial twigs (arteriæ rectæ) which pass directly to the venous plexus surrounding the tubules, and which form no inconsiderable part of the vascular supply of the kidney.

Alterations in the size of the renal vessels were formerly ascertained simply by exposing the kidney and observing its colour, contraction of the arteries being associated with paleness, and dilatation with redness of the organ. A much more exact method has been introduced by Roy, who incloses the kidney in a capsule filled with oil and connected with a registering apparatus. When the vessels dilate, the kidney increases in size, and diminishes when it contracts, so that the alterations can be readily recorded on the same revolving cylinder on which the general blood-pressure is registered by the manometer.

The **pressure** of blood in the glomeruli may be **diminished** generally:

(1) By failure of the heart's action, or

(2) By dilatation of the vessels of large areas, as the intestines, muscles, or skin.

The pressure of blood in the glomeruli may be **diminished locally** by contraction of the renal arteries, or of the afferent branches to the glomeruli.

The heart's action may fail from many causes, which have already been discussed more particularly.

Dilatation of the vessels in the skin, intestines, &c., may be caused by exposure to warmth, by the action of drugs, or by paralysis due to nervous injury.

Section of the splanchnics or of the spinal cord causes paralysis of the renal arteries, and ought, therefore, to increase the secretion of urine. This does occur, though not invariably, when the splanchnics are divided; but section of the spinal cord, by paralysing the intestinal and other vessels, lowers the blood-pressure so much that the supply of blood to the kidney is not only much below the normal, but is so small that the secretion of urine is generally almost completely arrested.

The **nerves** of the kidney consist of a number of small branches running along the renal artery and containing a number of ganglia. When these nerves are **cut** the vessels of the kidney dilate; when they are stimulated the vessels contract. A number of those fibres pass to the kidney from the spinal cord through the **splanchnics,** so that when the splanchnics are cut the vessels of the kidney usually dilate, and when they are irritated they contract.

The whole of the nerves, however, do not pass through the splanchnics, for stimulation of a sensory nerve, of the medulla oblongata, or of the spinal cord in the neck, will cause contraction of the renal vessels after both splanchnics have been cut, and section of the splanchnics does not always cause the renal vessels to dilate.

The **nervous centre** for the renal arteries is probably, like the chief vaso-motor centre for the body generally, in the medulla oblongata; but in all probability there are also subsidiary centres in the spinal cord and in the solar and mesenteric plexuses.

The reason for supposing these latter centres to exist is, that stimulation of the peripheral end of the splanchnic, divided at its passage through the diaphragm, causes contraction of both kidneys, and the vessels of the kidney of the side opposite to the stimulated nerve commence to contract later than that on the same side. A delay like this in the action of the stimulus indicates that it has not acted directly, but through the medium of ganglia.

When the splanchnics are divided the vessels of the kidney sometimes dilate and the kidney increases in size; a profuse secretion of urine may take place, which quickly increases to a maximum and remains for a considerable time. This, however, is not a constant effect, and not unfrequently the vessels do not dilate, and the kidney instead of increasing, diminishes in size. This is what to a certain extent might be expected, inasmuch as a section of the splanchnics causes dilatation of the intestinal vessels and lowers the blood-pressure, and thus diminishes the supply of blood to the kidney.

When a puncture is made in the medulla oblongata in the fourth floor of the ventricle, profuse secretion also occurs, but this differs from that caused by section of the splanchnics, in being preceded by a slight diminution, by rising rapidly to a maximum and then rapidly falling. These characters seem to show that it is due to irritation of some vaso-dilating mechanism,[1] rather than to any paralysis.

Stimulation of the vaso-motor centre in the medulla oblongata by venous blood, or by drugs such as strychnine or digitalis, has a twofold action on the kidney, for it tends to cause contraction not only in the vessels of the kidney, but in those of other parts of the body. The effect upon the kidney is thus a complicated one, for the contraction of the intestinal and other vessels by raising the blood-pressure tends to drive blood into the kidneys, at the same time that the contraction of the renal arteries tends to keep it out. When the renal nerves are cut, the renal vessels no longer oppose the entrance of blood, and therefore the renal vessels dilate very greatly when the vaso-motor centre is stimulated; but when the renal nerves are intact the result is a varying one, for sometimes contraction of the renal vessels may be so great as to prevent the entrance of blood into the kidney, however high the general blood-pressure may rise; at other times the general high blood-pressure may be able to dilate the renal arteries in spite of any resistance they may offer. These different conditions may occur subsequently to one another; and this stimulation of the

[1] Heidenhain, Hermann's *Handbuch et Physiologie*, vol. v. Th. 1, p. 366.

vaso-motor centre may cause contraction of the renal vessels succeeded by dilatation, or *vice versâ*. Thus Mr. Power and I found that on injecting digitalis into the circulation of a dog, the blood-pressure rose, but the secretion of urine was either greatly diminished or ceased altogether. Here it is evident that the renal vessels had contracted so much as to prevent the circulation through the kidney, notwithstanding the rise which had taken place in the blood-pressure. After a while the blood-pressure began to fall, and then the secretion of urine rose much above its normal, showing that the general blood-pressure was then able again to drive the blood into the kidneys.[1]

Similar observations were made by Mr. Pye and myself with regard to erythrophlœum; and the accompanying curves show



FIG. 116.—Curves showing the effect of erythrophlœum upon the blood-pressure and secretion of urine. From *Phil. Trans.* vol. clxvii.

well the result upon the urine of the mutual action of the rise in blood-pressure and the contraction of the renal arteries upon the secretion of urine. It will be noticed that at first the blood-pressure rises more quickly than the secretion of urine, the circulation through the kidney appearing to be opposed by the renal arteries. This opposition is then overcome, and the secretion of the urine rises more quickly than the general blood-pressure. The renal vessels again appear to contract, so that the urine diminishes while the blood-pressure rises still further. We have then oscillations due first to one factor and then to the other being predominant; and then, when the blood-pressure rises to its maximum, we find that the urine is at its minimum, the secretion of urine again rising as the blood-pressure falls.

A good deal of discussion has arisen regarding the mode of

[1] *Royal Society's Proceedings*, No. 153, 1874.

action of digitalis, and it has been stated by many to act as a diuretic only in cases of heart disease, and to have no diuretic action in health. In my own experiments, however, I found that it acted as a very marked diuretic even in health, and the explanation of this discrepancy may possibly be that, in my own case, the blood-pressure was low, whereas, in the others, it was probably much higher; but I am uncertain regarding the true explanation, though I am certain of the fact.

By causing increased secretion of water through the kidneys diuretics may increase the concentration of the blood and thus produce thirst, or cause absorption of water from the intercellular tissue or serous cavities in dropsies. In my own experiments on digitalis I weighed all my food and measured all my drink for nearly six months, taking exactly the same quantity every day. After producing profuse diuresis by a large dose of digitaline (sixty milligrammes in two days), such thirst ensued that I was forced to take a quantity of water to allay it.[1]

Mode of Action of Diuretics.—From what has already been said, it is evident that diuretics may act in several ways. They


Afferent vessels. (?) Dilated by nitrous ether, potassium nitrite
Efferent vessels. (?) Contracted by digitalis, strychnine, erythrophlœum, squill
Tubules. (?) Stimulated by urea and potassium nitrite, acetate, &c. Caffeine, turpentine, cantharidine (?) Paralysed by curare (?)

FIG. 117.—Diagram to show the parts of the secreting apparatus of the kidney which are probably affected by different diuretics.

may act: *A*, on the **circulation** in the kidney, raising the pressure in the glomeruli, (1) locally, (*a*) by contracting the efferent vessels, or the arterial twigs which pass directly to the capillary plexus; (*b*) by causing dilatation of the renal arteries, and thus increasing the supply of blood to the kidney. This they may do also, in more ways than one, for they may either paralyse the vaso-motor nerves of the kidney, or act on vaso-dilating mechanisms. (2) they may raise the blood-pressure generally by causing the contraction of vessels in other parts of the body.

B. Other diuretics may act on the **secreting cells** of the tubules, and may increase both the amount of water and the amount of solids excreted by them.

[1] The experiments were made in 1855 and published in part in my thesis on *Digitalis, with some Observations on Urine*. London: Churchill and Co. 1868.

Diuretics have already been classified as stimulating and sedative; and the sedative class agrees very closely with the one which we have just indicated as acting on the kidney through the circulation.

From what has been said of the action of diuretics it is evident that we may hope to do much more by combining them than by using them singly. Thus we see that digitalis instead of acting as a diuretic may completely arrest the renal circulation and stop the secretion altogether. If, however, we can combine it with something which will produce dilatation of the renal vessels, while the general blood-pressure remains high, we shall greatly increase the circulation through the kidney, and obtain the desired result. Experiments in regard to this were made by Grützner with nitrite of soda. He found that this substance increased the secretion of urine when the blood-pressure was reduced to a minimum by curare; and he found that it also had this effect when the blood pressure was raised by imperfect respiration. When the vaso-motor centre was greatly stimulated however, by allowing the blood to become very venous, the nitrite of soda no longer produced any increase of secretion.

Diuretics.

Refrigerant Diuretics.	Stimulant Diuretics.
Water in large quantities.	Alcohol.
Carbonic acid (aërated waters).	Gin.
Potassium salts, especially the	Hock.
Acetate.	Cantharides.
Citrate.	Blatta Orientalis.
Bitartrate.	Oleo-resins, resins and volatile oils—
Chlorate.	Turpentine.
Nitrate.	Juniper.
Sodium salts, *e.g.* common salt.	Savine.
Hydragogue diuretics—	Copaiba.
Adonis Vernalis.	Cubebs.
Broom.	Black pepper.
Caffeine.	Matico.
Colchicum.	Kava.
Digitalis.	Guaiac.
Erythrophlœum.	Umbelliferous plants chiefly containing volatile oils—
Nitrous ether.	Parsley.
Squill.	Carrot.
Strophanthus.	Dill.
	Fennel.
	Cruciferous plants—
	Mustard.

Stimulant Diuretics—*continued.*

Cruciferous plants—
Horseradish.
Asparagus.
Uva ursi.
Sarsaparilla.
Buchu.
Pareira.
Chimaphila.
Taraxacum.
Ononis spinosum.
Santonica.

The following tabular view of the probable mode of action of the various diuretics may help to show it more distinctly:—



* When a current of blood is passed artificially through an excised kidney, the stream is much accelerated by the addition of urea. Abeles, *Sitz-Ber. d. k. k. Wiener Akad.* Bd. 87, Abt. 3, April, 1883.

Uses.—Diuretics may be employed for the purpose of **removing** either **water** or **solids** from the body. They are used:

1st, to remove the excess of fluid met with in the tissues and serous cavities in cases of dropsy.

2nd, to hasten the removal of injurious waste products and poisonous substances from the blood.

3rd, to dilute the urine.

In cases where the accumulation of fluid depends on venous congestion, as for example in **cardiac** dropsy, those diuretics which act on the general vascular system, like digitalis, strophanthus, squill, or erythrophlœum, are most efficient because they tend to remove the cause of the dropsy (p. 290), as well as to assist the absorption and excretion of the fluid already effused.

When the dropsy depends on the disease of the **kidneys** or **liver,** other diuretics should either be given instead of, or along with, digitalis or squill. Even in cases of cardiac disease where

digitalis or squill are not proving efficacious, the addition of a little blue pill greatly assists their action, though it would be hard to say in what way it does so.

In dropsy depending on kidney disease, decoction of broom, oil of juniper, and nitrous ether, are amongst the most reliable diuretics, and copaiba in hepatic dropsy.

Diuretics are used to increase the secretion of **solids** in febrile conditions, and in cases of kidney disease where the excretion of waste products is deficient, and their retention threatens to prove injurious. In such cases, nitrate and bi-tartrate of potash, turpentine, juniper, and caffeine are useful.

Diuretics are also used to **increase** the proportion of **water** in the urine, and thus to prevent the solids being deposited from it and forming calculi in the kidney or bladder; or even to dissolve again such concretions as have been already formed.

Adjuvants to Diuretics.—As the amount of urine secreted depends upon the difference in pressure between the blood in the glomeruli and the urine in the tubules, it is evident that any pressure on the tubules, whether caused by obstruction of the ureter by a calculus, by the mechanical pressure of dropsical accumulations in the abdomen, or by distension of the venous plexus in the kidney itself, will tend to lessen the secretion of urine. Consequently we sometimes find that in such cases diuretics fail to act until the pressure has been relieved by **paracentesis** in cases of dropsy, or the venous congestion lessened by the use of a brisk **purgative,** or by **cupping** over the loins.

If the venous congestion is very great, as in cases of mitral disease or of chronic bronchitis with emphysema and dilated heart, bleeding from the arm may be advantageous or even imperatively necessary. In dilated heart and in mitral incompetence, the action of digitalis on the heart itself, strengthening its action and enabling it more effectually to pump the blood out of the venous into the arterial system and thus reduce venous congestion, will aid its action upon the kidneys.

Action of Drugs on Albuminuria.—In the normal kidney no albumen passes from the vessels or lymphatics into the urinary tubules, but under abnormal conditions it may do so and the urine become albuminous.

Albuminuria may be produced by ligature or compression of the renal artery; by ligature of the renal vein; and, though to a less extent, by ligature of the ureter. A similar effect to that of ligature of the renal artery may be produced by causing it to contract temporarily by means of drugs such as digitalis. In the experiments made by Mr. Power and myself we noticed that the urine which was secreted after the secretion had been completely stopped by digitalis was albuminous.

Albuminuria is also noticed after poisoning by strychnine, which, as Grützner has shown, has a similar action to digitalis,

and in cases of suffocation or of epilepsy, where the vaso-motor centre is stimulated by venous blood.

Other drugs appear to cause albuminuria by a direct action on the kidney itself. A marked example of this is cantharides, which produces both albuminuria and hæmaturia. Shortly after its injection the kidney appears congested and swollen, and on microscopic examination it is found that the alterations begin first in the glomeruli and convoluted tubules, and gradually extend to the straight tubules. These changes consist in intense congestion, especially of the glomeruli, with increased tension of blood in the vessels. Then the liquid constituents of the blood pass through the vascular walls carrying along with them granules, red corpuscles, and white corpuscles. This exudation then passes from the glomerulus along the whole length of the tubules, the epithelium of which next becomes changed, the cells which line them swelling up, multiplying, and becoming modified in form, migration of leucocytes also occurring. In short, we have the signs of inflammation beginning in the glomeruli and passing along the tubules.

Lead produces also disease of the kidney, but of a different kind. The kidney in animals poisoned by it is pale and granular with an adherent capsule and with atrophy of the cortical substance, in which crystals are often present. These appearances are due to chronic interstitial nephritis caused by calcareous deposits in Henle's loops. These block up the tubuli, produce subacute inflammation of the glomeruli and tubules, with atrophy and cirrhosis. A similar result is produced also by mercury. Chlorate of potash has a very peculiar action on the kidney. In large doses it produces a peculiar kind of hæmaturia, the urine being dark brown and containing large quantities of broken-up blood corpuscles. The drug arrests the secretion of the urine by blocking up the tubules with plugs of broken-up blood corpuscles.

Tannin and tannate of soda appear to have a certain power to lessen the exudation of albumen through the Malpighian tufts, as Ribbert found that when albuminuria was produced artificially in rabbits by temporary ligature of the renal artery, both tannin and tannate of soda either lessened or prevented the exudation of albumen. Arbutine, the active principle of uva ursi, appears to be still more efficacious, but requires to be given in somewhat large doses.

Lithontriptics.

These are remedies employed for the purpose of preventing the solids of the urine from being deposited, or of causing re-solution.

One of the most important is the abundant use of water, and sometimes it is advisable to use distilled water in place of ordinary water, as distilled water is free from salts of all kinds. Distilled

water has a disagreeable, flat taste, but it may be made quite agreeable by charging it with carbonic acid in a gasogen.

The substances which most generally are deposited from the urine are uric acid, acid urates, oxalate of lime and phosphates; the two former are liable to be deposited when the urine is too acid, and the two latter when it is alkaline or neutral. Oxalate of lime also may be deposited from faintly acid urine. These substances may be deposited either in the kidney or bladder, and thus give rise to renal or vesical calculi.

The lithontriptics generally employed when uric acid, or acid urates, are present, are salts of lithia and potash, as the urate of potash is more soluble than the urate of soda, and the urate of lithia more soluble than even that of potash. On account of the low atomic weight of lithium its salts have the further advantage of combining with a much larger relative proportion of uric acid than the salts of potash or soda. When phosphates are present, mineral acids, such as phosphoric, are sometimes employed, but it is difficult to render the urine acid by the internal administration of mineral acids, although it is easy to render it alkaline by the administration of alkalies. Benzoic and cinnamic acids, however, in passing through the body, are converted into hippuric acid, and they render the urine acid. They may either be given alone, or in combination with ammonia as benzoate of ammonia, because although ammonia is alkaline yet it appears to undergo conversion into urea in the body, and does not render the urine alkaline.

The deposition of oxalate of lime is usually connected with disturbances in the digestive system, and I have observed in a hospital ward, that a deposit of it is very commonly found in the urine after the patients have had cabbage for dinner. The administration of nitro-muriatic acid frequently tends to prevent the deposition of oxalates, and this is perhaps, on the whole, the best remedy for the form of dyspepsia to which the name of oxalic diathesis is sometimes given. Sometimes, however, carbonate of soda, by aiding the digestion, seems to be more beneficial.

Action of Drugs on the Skin.

Diaphoretics and Sudorifics.

The difference between these classes of remedies is simply one of degree. When the drugs **increase** the secretion of **sweat** only slightly, so that it can still evaporate from the skin, without running down in drops, they are called **diaphoretics;** but when they increase it so greatly that it can no longer evaporate, and streams down the skin, they are called **sudorifics.**

The **secretion** of sweat, like that of saliva, consists in the formation of the secretion by the cells of the gland from the material which is yielded by the fluid in the lymph spaces around the gland.

New material is constantly supplied to this fluid by the blood which circulates in the vessels. We therefore find that increased **circulation** of blood through the cutaneous vessels and increased secretion of sweat usually accompany one another, but this is not always the case. In the sweat glands, as in the salivary glands, the **secreting nerves** which regulate the activity of the **cells** are independent of the vascular nerves which regulate the capacity of the vessels. In fever or in poisoning by atropine the vessels may be widely dilated and the current of blood through them **rapid,** while the **secretion** of sweat is arrested. On the other hand, in dying persons we see a copious secretion of sweat occur, while the circulation through the skin has become very feeble or almost stagnant. A certain amount of sweat, indeed, may even be secreted by amputated limbs, the material for it being afforded by the lymph around the glands. But profuse secretion of sweat cannot go on long unless the gland is freely supplied with blood, for otherwise the supply of new material would cease. Dilatation of the vessels therefore aids the **secretion** of sweat. Dilatation may be induced by section of vaso-motor nerves or stimulation of vaso-dilating nerves. Thus, when the sympathetic is cut in the neck of a horse, dilatation of the vessels is produced by the section, and sweating occurs on that side.

The vaso-dilating and secreting nerves of the sweat glands usually run together, and by irritation of a nerve trunk, such as that of the sciatic, the vessels of the foot may be dilated, and sweating excited.

Warmth usually increases both the circulation of blood in the skin and the secretion of sweat; while **cold** has the contrary effect.

The **nerve centres** which excite the secretion of sweat appear to be situated in the **spinal cord;** the centre for the posterior extremities being situated in the upper lumbar and lower thoracic part of the cord in the cat; while that for the upper extremities in the same animal is situated in the under part of the cervical part of the cord.

The sweat glands may be excited to secrete:

(1) By the action of drugs upon the terminations of nerves in the glands.
(2) By the action of drugs on the sweat centres themselves.
(3) Reflexly by stimulation of sensory nerves.
(4) By mental stimuli.

An example of the stimulation of sweating by the action of drugs on the **nervous terminations** in the glands themselves is afforded by pilocarpin, which will cause secretion even when the nerves which connect the centres with the glands have been cut.

Secretion may be also arrested by the paralysing action of

drugs upon the terminal fibres; thus, atropine locally injected, prevents the secretion of sweat, however much the nerves going to the gland or the nerve centres be stimulated; and atropine also antagonises the effect of pilocarpine on the nervous terminations, and arrests the secretion which the latter causes.

The **nerve-centres** may be stimulated directly by the condition of the blood which is passing through them, or reflexly by irritation of sensory nerves. Stimulants of these nerve-centres are: (1) a venous condition of the blood; (2) high temperature of the blood; and (3) poisons, especially nicotine.

A venous condition of the blood is one of the most powerful stimulants, and it is to this that the sweats which precede death are in all probability due, for I have watched a patient dying, and observed that drops of sweat appeared on the brow just at the time that the blood became venous, as was evidenced by the commencing lividity of the finger-nails and lobes of the ears. Under such conditions, while the secreting cells are strongly stimulated, the circulation is very feeble.

A high temperature is also a powerful stimulant. In considering its action we must take into account the effect of the warm blood upon the sweat centres in the cord, as it circulates through them, and its local action also on the sweat glands themselves. Up to a certain point it appears to have the effect of dilating vessels and of increasing the activity of the glands by acting both on the sweat centres and on the periphery.

Local warmth to one foot increases the secretion of sweat, and local cold diminishes it in that foot, when the glands in all four feet of an animal are stimulated equally either by excitement of the sweat centres or by the action of pilocarpine on the peripheral ends of the sweat nerves.[1]

The sweat centres appear to be directly stimulated by nicotine, but the action of this drug may be partly due also to a reflex effect on those centres through the nerves of the stomach.

The sweat centres appear to be **reflexly** excited by severe irritation of any sensory nerve passing from the surface of the body, and the point at which the irritation is applied does not seem to be of much importance. They are probably stimulated reflexly from the stomach, as in the sweating which accompanies nausea.

The power of the **brain** to stimulate the sweat centres is shown in the effect of mental emotion, and direct irritation of the medulla oblongata will cause sweating in cats even some time after death.

Excretion by the Sweat Glands.—A number of substances taken into the body pass out in small quantities through the skin. Aromatic and volatile substances appear to pass readily, so also benzoic acid, hippuric and cinnamic acid, tartaric acid, succinic acid, iodide of potassium, quinine, corrosive sublimate, arseniates of soda

[1] Luchsinger, *Pflüger's Archiv*, 1876, vol. xviii. p. 480.

and potash. When arseniate of iron has been taken, curiously enough, arsenious acid has been found in the sweat, and iron in the urine. Some **colouring matters** are excreted especially by the skin of the armpits, and the underclothing may sometimes be found stained of a brick-red colour at these parts. I have observed this in some cases after drinking claret or port, but it only occurs exceptionally after the employment of these wines, and it is possible that it is due to adulteration with foreign colouring matters, for I have also noticed it in cases where no wine has been drunk, but where pickled red cabbage or beet-root has been eaten.

Relation between Sweat Glands and Kidneys.—The sweat glands and the kidneys both remove **water** and small quantities of salts from the blood, and thus tend to keep it at its normal concentration. Their functions are complementary, so that when much water is excreted by the skin less is excreted by the kidneys, and *vice versâ*.

The amount of sweat and of urine is in inverse ratio—when the skin acts more, the kidneys act less. This is to a great extent due to the different distribution of blood under varying conditions, because when both are stimulated, as, for example, by salts of ammonia, diuresis will occur, if the blood be driven towards the kidneys by external cold; and diaphoresis if it be attracted to the skin by external warmth.

The quantity of solids contained in the sweat is very small, only a little over one per cent.—three-fourths of these being organic, and one-fourth inorganic. The organic are chiefly fats, fatty acids, and small quantities of urea—about one-tenth per cent. When the kidneys are insufficient, however, to excrete urea, the quantity in the sweat becomes greatly increased, and it has even been found crystallised upon the skin.

Action of the Skin in Regulating Temperature.—As I have already mentioned, the skin has an excreting function complementary to that of the kidneys, and it may to some extent relieve them when they are doing their work imperfectly. But its chief function is that of regulating the bodily temperature. The quantity of heat which is changed into potential energy, in converting liquid water into gaseous steam, is very great. Five and a half times as much heat is required to convert boiling water into steam, as to raise the same amount of water from the freezing to the boiling point. The immense loss of heat thus occasioned, converts the healthy skin under the influence of great heat into an actual cooling apparatus. In negroes on the west coast of Africa it has been noticed that while the skin is perspiring profusely, it is as cold as marble, and Sir Charles Blagdon observed that in a room with a temperature of 198° Fahr. his side felt quite cold to the touch.

Uses.—Diaphoretics are used in cases of threatened catarrh or inflammation of mucous or serous surfaces, or internal organs

after exposure to cold. Their beneficial action in such cases may be partly due to the withdrawal of blood from internal organs to the surface of the body by the use of diaphoretics, but it is not improbable that in addition to this the condition of the skin which they induce exercises a favourable action reflexly on internal parts. There seems to be a sort of complementary action between the skin and the internal mucous membranes, as well as between the skin and kidneys. This is sometimes well marked in gouty patients where the disappearance of an eruption from the skin is followed by asthma, and *vice versâ*. It is also shown by the experiments of Rossbach (p. 216); and the effect of irritation of the stomach and nausea on the secretion of the skin has already been noticed.

One of the best diaphoretics to cut short commencing catarrh is compound ipecacuanha powder. In fevers, with the exception of rheumatic fever, the skin is generally dry although the temperature is high, and diaphoretics are employed to increase the cutaneous secretion, and thus to lower the temperature.

In exanthemata, after the eruption disappears from the skin, there is a tendency to inflammation of internal organs, and in order to prevent this diaphoretics are used, those which act markedly on the vessels, or stimulating diaphoretics, being especially indicated.

The advantage of a free supply of blood in chronic morbid conditions, such as chronic ulcers has already been mentioned when speaking of irritants (p. 298); and in chronic morbid conditions of the skin diaphoretics are sometimes employed to promote the cutaneous circulation. In diseases of the kidneys, when it is advantageous to lessen their functional activity, diaphoretics are employed in order to make the skin act vigorously; and they are used also to assist the kidneys in removing the fluid which has already accumulated in the body in cases of dropsy. When the kidneys, though not diseased, are called upon to do excessive work —as in diabetes mellitus, or polyuria—diaphoretics are employed to aid them. Where an unnatural secretion of fluid is taking place from the intestine, as in cases of chronic diarrhœa, diaphoretics are also employed to divert secretion from the intestine to the skin and thus lessen the diarrhœa.

Antihydrotics or Anhydrotics.

These are substances which **lessen** the secretion of **sweat**:—

Acids.
Belladonna and Atropine.
Hyoscyamus.
Amarita muscaria and muscarine.
Agaricus albus.
Jaborandi and Pilocarpine.
Nux vomica and Strychnine.
Quinine.
Picrotoxine.
Ipecacuanha (compound powder).
Zinc salts.

These remedies may act (1) on the **sweat glands** themselves by lessening the excitability either of the secreting **cells** or of the secreting **nerves**; (2) on the **sweat centres,** by lessening their excitability or removing the excitant; and (3) on the **circulation.** Belladonna in large doses paralyses the ends of the secreting nerves, just as it does in the salivary glands, so that the sweat glands will not secrete even when a strong stimulation is applied to their nerves. As belladonna acts thus when locally applied, it may be used for local sweating in the form of extract or of solution of atropine painted on, or rubbed over, the surface. It is thus useful in cases of local sweating of the palms of the hands and soles of the feet. It may also be given internally to paralyse the ends of the secreting nerves, and thus to arrest the night sweats in phthisis. But in all probability its beneficial effect in the night sweats of phthisis is not dependent on its paralysing action on the secreting nerves, for it is useful in doses which appear to be too small to produce this effect, and which also do not act immediately, but rather after some time. Its utility in such cases, therefore, is probably due to an effect on the nerve-centres, and especially to a stimulating action on the respiratory centre.

The **night sweats** of **phthisis** are usually followed by great weakness and prostration, which has sometimes been attributed


Respiratory centre — more readily stimulated by venous blood than the sweat centres in the spinal cord.
Carotid artery and vertebral arteries supplying the respiratory centre with blood.
Motor nerves of thorax...
Motor nerves of diaphragm...
Sweat centres in spinal cord with arteries carrying blood to them, and with nerves passing to sweat glands.
Diaphragm
Nerves to sweat glands.....

FIG. 118.—Diagram to illustrate the action of antihydrotics. The secretory nerves passing to the sweat glands from the sweat centres in the spinal cord have been represented as a single nerve for the sake of simplicity.

to the loss of salts and organic matter contained in the sweat. But the quantity of these is very small, and the same depression is not noticed when there is an increase of two or three ounces in the daily secretion of urine, although it will carry off quite as large

a quantity of both salts and organic matter. Nor is the same depression produced by the profuse sweating due to active exertion, nor even by the sweating in ague. The depression is not the consequence of the profuse sweat; both are probably the consequence of one common cause. This cause I believe to be partial failure of the respiration and consequent accumulation of carbonic acid in the system, which leads at the same time to stimulation of the sweat centres and impairment of tissue change throughout the body generally.

In healthy persons the respiratory centre is more sensitive to the stimulus of carbonic acid than other parts of the nervous system. Thus any increase in the venosity of the blood at once stimulates this centre, and through it the diaphragm and respiratory muscles of the thoracic wall, rendering the respiration more active, and increasing arterialisation. Consequently, the blood does not become venous enough to stimulate the sweat centres. But when the respiratory centre is depressed by excessive reflex stimulation during the day in the process of coughing, and by the natural depression which occurs during sleep, it may respond less readily to the stimulus of venous blood. The amount of carbonic acid in the blood may thus accumulate to such an extent that the sweat centres are stimulated before the respiratory centre responds, and thus the profuse sweats which are so depressing to the patient may occur.

It is probable that this is only part of the truth, and that there are other factors in the production of abnormally profuse sweats; for in children suffering from rickets, the head perspires profusely during sleep, yet the mucous membranes are of a bright rosy colour. Nevertheless, acting on this idea, I have given at night such substances as are powerful stimulants to the respiratory centre, like nux vomica and strychnine, and I have found that the sweating is usually arrested by them. A small dose is sometimes sufficient, but occasionally it must be steadily increased until as much as half a drachm of the tincture of nux vomica is given at once. The only disadvantage that I have noticed from this treatment is that the excitability of the respiratory centre sometimes persists during the day, and renders the cough more troublesome. I have tried to remedy this by combining strychnia with opium, and partially succeeded. If we now review the **remedies** used in the night **sweating** of phthisis, we shall see that almost every one of them has a **stimulant** action on the **respiratory centre.** It is possessed in a marked degree by atropine and hyoscyamus. Ipecacuanha has this action also, and its combination with opium, in the form of Dover's powder, although it causes sweating in healthy persons, tends to restrain it in phthisical patients. Picrotoxine, salts of zinc, and pilocarpine, all stimulate the respiratory centre also, and we find that the last is useful in the night sweats of phthisis, although we would expect from its physiological action that it would be injurious, stimulating, as

it does, the terminations of the secreting nerves in the sweat glands themselves. It is possible, however, that in addition to the stimulation of the sweat centres by venous blood, the night sweats of phthisis may be sometimes increased by the **high temperature** of the patient, and in such cases **quinine**, as Murrell has pointed out, is likely to be most serviceable.

Action of Drugs on the Bladder.

The walls of the bladder consist of involuntary muscular fibre which expels the urine by its contraction. Around the neck of the bladder is a band of involuntary muscular fibre, the sphincter vesicæ, which by its contraction closes the orifice and prevents the escape of urine. The sphincter vesicæ receives its motor supply through the third, fourth, and fifth sacra nerves.

The **nerve-centre** for the movements of the bladder is situated in the **spinal** cord opposite the fifth lumbar vertebra in dogs, and the seventh in rabbits. This centre is able to regulate the retention and discharge of the urine by the bladder even when the spinal cord is divided between it and the brain, but the activity of the centre under normal conditions is modified by the brain, so that we may consider that there is a cerebral as well as a spinal centre for the bladder. The spinal centre may be set in action either reflexly, or by stimuli passing down from it to the brain. The cerebral centre may be set in action either reflexly or voluntarily.

Usually when the pressure of the urine within the bladder is increased beyond a certain limit depending not only on the quantity of the water, but on the state of the contraction of the bladder itself, the neck of the bladder becomes slightly dilated, and a drop of urine exuding acts as a stimulus to the sensory nerves of the urethra, and thus calls reflexly into action the centre in the spinal cord by which at the same time the sphincter vesicæ is inhibited, and the detrusor urinæ stimulated. Reflex action may also be induced by stimulation of other nerves, as for example by the application of a wet sponge to the anus or perinæum. The **cerebral centre** is usually called into action by the sensation of the bladder being full. It may be called into action voluntarily although there is little urine in the bladder; and also may be excited by emotion, such as fear.

It may be also excited reflexly through the sense of hearing. Boerhaave was accustomed when patients found difficulty in passing water, to make an attendant pour water from a height into a basin in the patient's hearing. The splashing thus occasioned induced the patient to pass water, and a similar effect, as is well known, is produced on horses by whistling. Nervous agitation has often the contrary effect of producing retention of water. When it is desirable for a person to pass water—*e.g.* when a

specimen of urine is wanted for examination—it is advisable to put him in a room by himself and turn on a tap within his hearing. The removal of the restraint exercised by the presence of another person, along with the stimulant action of the sound of falling water, rarely fails to produce the desired effect. Even the recollection of the sound of falling water will tend to cause evacuation of the bladder, and when there is difficulty in passing water the patient may sometimes obtain relief by thinking of a waterfall. Washing the hands in cold water also tends reflexly to cause evacuation of urine, and the effect of a wet sponge to the perinæum has already been mentioned.

Vesical sedatives are substances which lessen the irritability of the bladder, and thus remove pain, and lessen the desire to urinate. This desire may be excited not only by the presence of urine in the bladder, but by the irritation of calculi, or inflammation of the mucous membrane of the bladder itself. When calculi are a source of irritation, carbonate of lime taken internally seems to lessen the irritability. In cystitis the irritation is diminished by the use of very hot water externally, in a bidet or hip-bath. The irritability of the nerves may be diminished by opium, belladonna, and hyoscyamus, and by drinking freely of warm water, either alone, or in the form of an infusion or decoction of some mucilaginous substance, *e.g.* linseed-tea or barley-water.

In chronic inflammation the irritation may be diminished by astringents such as buchu, uva ursi, pareira brava, and alchemilla.

Vesical tonics are substances which increase the contractile power of the muscular fibres in the bladder. They are therefore useful in two different conditions, for by strengthening the detrusor urinæ they prevent retention, and by strengthening the sphincter vesicæ they prevent incontinence.

Some of these remedies appear to act by increasing the stimulating power of the urine, so that the sphincter vesicæ is consequently more firmly contracted—of this class is cantharides. Others appear to alter the direction of reflex action—such are the passing of a bougie through the urethra once or twice a day, or the application of an injection of nitrate of silver, ten to thirty grains to the ounce, to the neck of the bladder. Others act on the nerve-centres and apparently are useful sometimes by lessening the reflex susceptibility from the bladder, so that the detrusor urinæ is less called into action; at other times by increasing the susceptibility of the nerve-centre so that the sphincter vesicæ is more firmly contracted—of the latter class is strychnia; to the former belongs bromide of potassium, given at night. Belladonna, which is one of the most useful remedies in incontinence of urine, acts upon the nerve-centres, but whether it acts in the same way as strychnine or as bromide of potassium, it is difficult to say. It is quite possible that it lessens the sensibility of the bladder to

changes in pressure within it in somewhat the same way as it lessens the sensibility of the heart to changes in blood-pressure (p. 257).

Urinary Sedatives and Astringents.

When the urinary passages are healthy, the secretion of mucus from them is very slight, and the presence of urine in the bladder or its passage along the urethra usually gives rise to no pain. Pain and scalding are sometimes caused by an abnormally acid urine, or by the presence of crystals of uric acid in it, even though the mucous membrane itself be healthy. In such cases the use of potash or lithia is indicated to restore the healthy character of the urine.

When the bladder itself is irritable or inflamed, the secretion of mucus is increased and there is constant desire to micturate. There are here two indications to be fulfilled; one is to lessen the irritability, and the other is to remove the inflammation. In lessening the irritability, belladonna seems to be especially useful, and to diminish the inflammation, astringents are employed.

In inflammation of the urethra the same indications exist, and here also cubebs, copaiba, and sandal-wood oil are employed. It is, however, easier to apply astringents locally to the urethra than to the bladder, and consequently astringent injections are more frequently used: these are usually solutions of alum, sulphate or acetate of zinc, and acetate of lead.

Finely-divided powders act also beneficially by keeping the inflamed walls of the urethra apart, and on this account a mixture of sulphate of zinc and acetate of lead, which gives a fine, white, insoluble precipitate of sulphate of lead, is more efficacious than either of the solutions employed alone. Kaolin or china clay, which is a completely inert powder, as well as bismuth and calomel, have also been used for a similar purpose. As it is found that the secretion in gonorrhœa frequently, if not always, contains microscopic organisms, the injection of antiseptics has been used: among these may be mentioned permanganate of potash, boracic acid, carbolic acid, sulpho-carbolates, sulphurous acid, as well as drugs having both an astringent and antiseptic action, like chloralum, perchloride and pernitrate of mercury, and chloride of zinc.

The beneficial effects of copaiba in inflammation of the bladder and urethra are probably due to its antiseptic action. It is excreted in considerable quantities by the kidneys and renders the urine antiseptic, so that its decomposition and the appearance of bacteria in it are greatly retarded or completely prevented. The whole urinary passages from the glomeruli of the kidney to the orifice of the urethra are thus washed out by antiseptic urine, which does not decompose, and which tends to destroy or remove any germs that may be present. Cubebs and terpenes have probably a similar action.[1]

[1] Schmiedeberg, *Arzneimittellehre*, p. 121.

CHAPTER XVI.

ACTION OF DRUGS ON THE GENERATIVE SYSTEM.

Aphrodisiacs and Anaphrodisiacs.

THE sexual function is regulated by two nerve-centres, one of which is cerebral and the other spinal. The **cerebral centre** is the seat of the feelings and appetite which prompt the individual to seek sexual congress.

The **spinal centre** regulates the condition of erection in the sexual organs which is necessary for coitus. These two centres may act independently of each other, *e.g.* when the spinal cord is cut, but in the normal condition they naturally influence each other, excitement of the spinal centre re-acting on the cerebral centre so as to awaken sexual feelings, and excitement of the cerebral centre re-acting on the spinal so as to produce erection of the genital organs.

Erection is due partly to dilatation of the arteries in the erectile tissues of the genital organs, and partly to compression of the efferent veins. The blood being thus allowed to flow freely into the organs, and prevented from flowing out, distends them so as to render them turgid and more or less rigid. During the orgasm the turgidity is increased by partial stoppage of respiration, which, by rendering the blood venous and thus stimulating the vaso-motor centre, tends to raise the blood-pressure in the body generally, and in the erectile tissues particularly.

Dilatation of the arteries in the genital organs and consequent erection occurs on stimulation, either of the genital centre in the lumbar spinal cord or of the vaso-dilating nerves (*nervi erigentes*) which pass from it to the genital organs and end in a ganglionic plexus surrounding the arteries.

The **lumbar** genital centre may be excited either reflexly by stimulation of the sensory nerves of the genital organs and adjoining parts, or by psychical stimuli transmitted to it from the brain.

The exact seat of the cerebral genital centre has not been determined, but Eckhard has found that irritation of the crura

cerebri can produce similar effects to stimulation of the nervi erigentes.

The **cerebral** genital centre may be stimulated and sexual feelings aroused by impressions made on the nerves of special


Optic nerves
Auditory nerves
Olfactory nerves
Nerves of mammæ and general surface
Nervi erigentes passing to the genital arteries
Sensory nerves of the genital organs
,, ,, ,, prostate and bladder
,, ,, ,, perineum and rectum
Sensory nerves of nates, and rectum.

FIG. 119.—Diagram to illustrate the action of aphrodisiacs and anaphrodisiacs. The darkly-shaded spot indicates the genital centre in the brain, and the lighter spot the spinal centre in the lumbar portion of the cord. The direction in which impulses are conveyed along the nerves are indicated by the arrows. The nerves from the general surface have been represented as going to the cerebral centre, and acting through it on the spinal centre. It is probable, however, that several of them pass directly to the spinal centre, as represented in the case of the nerves of the nates.

or general sense, *e.g.* on the eye, ear, nose, on the mammæ, and general surface of the body, the genital organs and parts adjoining, as the bladder, prostate, and nates. Thus, sexual excitement may occur in consequence of the sight of persons or pictures, the reading or hearing licentious stories, or of irritation of the surface of the body either by gentle friction or by prurigenous irritation due to irritating articles of clothing, parasites, or skin diseases. Distension of the bladder has a somewhat similar effect, and the irritation consequent on an enlarged prostate is probably, in part at least, the cause of the great sexual excitement which sometimes occurs in elderly men. A very acid condition of the urine, such as is found in some gouty patients, may possibly have a similar action. Chlorate and nitrate of potash administered internally are said by Jacobi[1] to render the urine so irritating and to produce such sexual excitement as to lead to onanism. Ascarides in the rectum may cause excitement of the cerebral genital centre and give rise to nocturnal emissions as well as possibly to diurnal excitement, and in females they may cause even greater irritation by passing into the vagina. Irritation of the rectum from the presence of piles or fissure may also give rise to such great sexual excitement as to induce onanism or nymphomania. Fæces in the rectum, and

[1] *Medical Times and Gazette*, 1876, vol. i. p. 177.

perhaps in the colon, may also cause sexual excitement in some persons or increase it when present.

Such sources of local irritation may sometimes be insufficient to affect the cerebral centre during waking hours, when the attention is otherwise engaged, but may do so powerfully during sleep, or when the cerebral functions are disturbed by cannabis indica, and they may then produce erotic dreams or seminal emissions.

The lumbar centre is most readily excited by mechanical stimulation of the genital organs, but it may be also powerfully stimulated from the mucous membranes of the urinary passages, as is seen in the painful priapism which occurs in poisoning by cantharides.

Stimulation of the lumbar centre without stimulation of the cerebral centre may occur from the presence of fæces in the rectum and perhaps in the colon, so as to give rise to seminal emissions during sleep unaccompanied by any dreams of a sexual character.

Aphrodisiacs.

These are medicines which increase the sexual appetite.

Irritation of the nates either mechanically alone by flogging or mechanically and chemically combined by urtication or flogging with nettles has been used as an aphrodisiac.[1]

The sexual function requires, however, for its proper performance a healthy state of the body, and good, or at least fair, nutrition; without these, mere reflex excitement of the genital centres is likely to prove inefficient for the propagation of the race. Tonics generally, such as iron, are therefore to be regarded as **indirect aphrodisiacs.**

Strychnia has probably a double action, both increasing the general nutrition and rendering the genital nervous centres, both lumbar and cerebral, more susceptible to the action of stimuli. Its aphrodisiac action is sometimes an objection to its use as a tonic, for both it and nux vomica may cause seminal emissions which more than counter-balance its tonic action and weaken the patient.

Cannabis indica has been regarded as an aphrodisiac, but the trials of it made in this country seem to show that it does not itself at least have any such action, and merely induces a condition of partial delirium in which Easterns may possibly have visions of a sexual nature, and indeed, they try to give a sexual direction to the mental disturbance which the cannabis produces, by mixing with it musk, ambergris or cantharides.

Cantharides act as an aphrodisiac, but their action is probably due to their irritating effect on the mucous membrane of the urethra, and its use in such doses as to have any aphrodisiac action is attended with danger. Blatta orientalis when used as a diuretic may have an aphrodisiac action like cantharides.[2]

[1] Trousseau et Pidoux, *Traité de Thérapeutique.*

[2] Buttenwieser, *Der practische Arzt*, Feb. 1882.

Alcohol appears to excite the cerebral centre and increase the sexual appetite, while it partially paralyses either the lumbar centre or the nervi erigentes, through which this centre acts on the genital organs and thus interferes with the proper performance of the generative act.[1]

Anaphrodisiacs.

These are medicines which diminish the sexual passion.

The agents employed as anaphrodisiacs are:—

Ice.	Conium.
Cold baths, local and general.	Camphor.
Bromides of potassium and ammonium.	Digitalis.
Iodide of potassium.	Purgatives.
	Nauseants, and
	Bleeding.

Anaphrodisiacs may act locally on the genital organs, or may act upon the genital nerve-centres.

The effect on the nervous system may be directly exerted on the nervous structures themselves, on the circulation, nutrition, and general surroundings. Amongst the most powerful **local** anaphrodisiacs is the continuous application of cold by means of ice. Bromide of potassium possibly has also a local as well as a general action.

When the lumbar portion of the cord is abnormally stimulated reflexly, the **stimulus** ought to be removed: thus, in warm countries, where smegma may accumulate around and irritate the glans penis, very careful washing is requisite and circumcision is an advantage. Both in warm and cold countries circumcision, either general or partial, is useful if the prepuce be very long and its orifice much contracted.

When the irritation appears to arise from the presence of very acid urine, or of crystals of uric acid, irritating the bladder or urethra, as in gouty persons, potash or lithia should be employed to lessen the acidity of the urine, or to render it neutral. Where abnormal irritation of the genitals is present the urine should be examined for sugar as well as for uric acid, as the sugar may cause local irritation of the prepuce or vulva.

Distension of the bladder ought also to be avoided, and in persons who suffer from seminal emissions, occurring in the morning, it is occasionally advisable that they should be awakened and empty the bladder an hour or more before their usual time of rising.

If stone in the bladder is acting as an irritant, surgical treatment should be employed, but in cases where this is inadvisable, or where the irritation is dependent on enlarged prostate, general anaphrodisiacs must be used, such as bromide of potassium in large doses,

[1] Shakespeare, *Macbeth*, act ii. scene iii.

care also being taken that the condition of the urine is not abnormally acid or alkaline. Ascarides in the rectum must be treated with anthelmintics. When irritation arises from piles the use of sulphur internally is often beneficial, though surgical interference may be necessary both for them and for fissure.

When irritation arises from fæcal accumulations in the rectum or colon, they should be removed and their return prevented by the careful use of aperients.

As anything which tends to increase the flow of blood to the genital organs or the lumbar portion of the spinal cord heightens their excitability, care should be taken not only to avoid this, but also to direct as much as possible the current of blood to other parts of the body. Thus, warm and heavy clothing or pads about the hips or loins should be avoided, and a hard mattress should be used in the place of a feather bed. Sometimes patients suffer from emissions in consequence of lying on their back. This is probably due to the effect of warmth on the spinal cord, and in order to avoid it, a towel or girdle should be put around the loins with a knot tied in it, or some hard substance fastened on it opposite the spine, so that the person would, even during sleep, be prevented from lying on his back. Walking exercise is not so useful as exercise of the arms, as in rowing, gymnastics, or mechanical occupations, such as those of a carpenter or blacksmith, because, in walking, the current of blood passes towards the lower extremities and part of it may become directed to the pelvis. In the other occupations just mentioned, the current of blood is, on the contrary, directed to the upper extremities. Working a treadle, as in turning a lathe or sewing-machine, is objectionable, both because the blood is directed towards the lower extremities generally and because it may become specially directed to the genitals by occasional friction of the clothes.

Hard mental work has also a similar effect to that of bodily exercise. In addition to these measures, a meagre diet, and especially a vegetable diet, with the avoidance of stimulants, is of considerable service.

Emmenagogues and Ecbolics.

Emmenagogues are remedies which **restore** and regulate the normal **menstrual flow** when it is absent or deficient or irregular.

Ecbolics are remedies which cause the **expulsion** of the **contents** of the **uterus.**

In menstruation both ovaries and uterus become congested. An ovum is discharged, and a flow of blood occurs from the uterus. Diminution or absence of the menstrual flow may be occasioned either by general or local conditions : thus great debility or anæmia may cause it, and it is very frequent indeed in the anæmia and

debility which are consequent on the occurrence of slight consolidation in the lungs.

A local cause may be deficient determination of blood to the ovaries and uterus, although no general anæmia exists.

The remedies employed for these two conditions are termed **indirect emmenagogues.** To correct anæmia, iron, manganese, and cod-liver oil, may be employed.

In order to determine more blood to the uterus, warm foot-baths, warm hip-baths, mustard hip-baths, mustard stupes or poultices to the thighs and lower part of the abdomen, and leeches to the inside of the thighs or to the genitals, and aloetic purgatives, may be employed.

It might at first seem from theoretical considerations that foot-baths could hardly have any action on the uterus, but warm foot-baths cause great dilatation of the arteries in the legs, and it is probable that this dilation extends up the iliacs, so that more blood may be sent to the genitals as well. But in addition to this, it is not at all improbable that a close nervous connection exists between the vascular supply of the uterus and of the feet, for not only does the warm foot-bath tend greatly to restore, but cold and wet feet are amongst the most powerful agents in checking, menstruation.

Other substances, which seem to have a direct stimulating action on the womb itself, are called **direct emmenagogues.** It is not easy to see at present how they act; we know, however, that when given in large doses they cause contraction of the womb, and then act as ecbolics. The chief emmenagogues are :—

Indirect Emmenagogues.	**Direct Emmenagogues.**
Baths: Hot foot.	Ergot.
Baths: Hot hip.	Digitalis.
Baths: Mustard.	Savine.
Leeches: To genitals.	Quinine.
Leeches: To thighs.	Assafœtida.
Mustard: Baths.	Myrrh.
Mustard: Poultices.	Guaiacum.
Mustard: Stupes.	Cantharides.
Purgatives, as aloes.	Borax.
Iron.	Rue.
Manganese.	
Cod-liver oil.	
Strychnine.	

Ecbolics.

The involuntary muscular fibres of the uterus appear, like those of the ureter or of the frog's heart, to possess the power of rhythmical contraction, and may contract when entirely separated from the general nervous system. They are, however, controlled

by the higher **nerve-centres.** There appears to be one centre, situated in the **lumbar** portion of the spinal cord, which is of itself sufficient to regulate all the movements, for they go on normally, even when the spinal cord has been completely divided above it. This **centre** may be reflexly stimulated and contractions of the uterus induced by irritation of the ovarian, crural, or sciatic nerves. It may be also stimulated by the action upon it of drugs circulating in the blood, as ergotine, picrotoxine, or strychnine, or by great venosity of the blood, due to asphyxia.

There appears, however, also to be a second centre for the uterus, as for the male genital organs, in the **brain** (*vide* p. 394), by which the lumbar centre may be excited, and in consequence of this, stimulation of the cerebellum, crura cerebri, corpora striata, and optic thalami, also give rise to uterine contractions.

V. Basch and Hofmann consider that the impulses pass to the uterus from the central nervous system, along two sets of nerves. One is composed of nerves passing from the inferior mesenteric ganglion to the hypogastric plexus. Stimulation of these causes circular contraction of the uterus, descent of the cervix and dilatation of the os. The other consists of branches passing from the sacral nerves across the pelvis to the hypogastric plexus, and representing the nervi erigentes. On stimulation of these the uterus contracts longitudinally; the cervix ascends and the os closes.

The mode of action of ecbolics has not been satisfactorily ascertained. Ammonia injected into the circulation appears to cause contraction of the muscular fibres, for it causes contraction of the uterus even when all nervous connections have been divided. Ergot possibly acts in the same way, but it is possible also that it acts on the spinal centre.

The chief ecbolics are :—

Ergot.
Savine.
Quinine.

Uses.—Ecbolics are used to **accelerate** the **expulsion** of the child when the passages are free but expulsive power is deficient, and to cause firm contraction of the uterus and so **prevent hæmorrhage** after delivery.

Adjuncts.—Compression of the uterus by kneading, pressure over it by a pad, the hand dipped in cold water laid over the uterus, or a cold pad. Sternutatories have been used to supplement the expulsive power of the uterus, and when necessary, operative interference must be had recourse to.

Action of Drugs upon Milk.

The milk glands somewhat resemble the salivary glands in the way in which they are affected by the central nervous system, and by the action of drugs upon them. The action of the central nervous

system on the milk glands, however, has not been made out with anything like the same clearness as in the case of the salivary glands, experiments on animals having given not very definite results. It is chiefly inferred from the effect of mental emotions in checking or altering the secretion of the milk; and from the effect of belladonna locally applied in checking the secretion. The amount of secretion appears to depend on the amount of blood-pressure in the gland, and gentle stimulation of the nipple increases both the flow of blood to the gland and the secretion of milk. It is uncertain whether there are definite secreting nerves affecting the gland cells apart from the vaso-motor nerves.

The character of the milk depends to a great extent upon the feeding and exercise of the mother, and diet is the most important agent in regulating both the quality and the quantity of the milk. As Dolan points out, it not unfrequently happens that a wet nurse, when first she arrives, yields such milk that the child she is nursing thrives well, but the quality soon falls off. In place of much outdoor exercise and plain, nutritious diet, she is fed luxuriously and gets little exercise. In order to restore the quality of the milk in such a case, the woman must be restored as far as possible to her previous conditions of diet and exercise.

Many substances are excreted in the milk, such as ammonia and the aromatic oils to which vegetable substances belonging to umbellifera and crucifera owe their flavour, probably also all volatile oils are thus excreted. Amongst those which have actually been found to pass into the milk are the oils of anise, cummin, dill, wormwood, and garlic, as well as turpentine and copaiba. The purgative principles of rhubarb, senna, scammony, and castor-oil, pass into the milk. Opium, iodine, and indigo do so also, and metals, such as antimony, arsenic, bismuth, iron, lead, mercury, and zinc. Volatile oils, having an agreeable taste, do not appear to affect the secretion of milk directly, but appear to render it pleasant to children, so that they take the breast eagerly. When lactation is defective they may increase the reflex stimulus to the nipple by making the child suck more vigorously and thus increase the quantity of milk. For this reason such volatile oils as anise and dill may be useful as galactagogues. Garlic, on the contrary, renders the milk disagreeable to children, so that they will not take it. Copaiba also renders the milk disagreeable. The nearest approach to a true galactagogue is jaborandi, but it affects the gland only temporarily. Beer and porter stimulate the secretion for a short time, but they produce no proportionate benefit in the child, and nursing mothers are, as a rule, much better without alcohol, and should rather take milk instead. When the milk of the mother is deficient in saline constituents they may be supplied by giving the appropriate salts to the mother.

Various physiological actions may be produced in the child by administering drugs to the mother. The administration of acids

to nursing mothers is generally to be avoided, as they are apt to cause griping in the child. Neutral salts as a rule pass into the milk and cause looseness of the bowels in the child. Senna, castor-oil, rhubarb, scammony, sulphur, and probably jalap, act as purgatives to the child. Salts of potash administered to the mother will act as diuretics to the child. Turpentine administered to the mother also can be detected in the urine of the child; and this is also the case with copaiba and iodide of potassium. Opium administered to the mother may act as a narcotic to the child, and mercury, arsenic, and iodide of potassium, may all be given to nursing children by administration to the mother.

CHAPTER XVII.

METHODS OF ADMINISTERING DRUGS.

Drugs may be used either for their local or general action, and sometimes for a combination of the two. Thus a solution of opium may be applied to the eye for its local effect in relieving irritation of the conjunctiva. It may be given by the mouth or injected under the skin to relieve pain and induce sleep, though the seat of the pain may be far removed, both from the point of injection and from the alimentary canal; or the opium may be applied in the form of a pessary in uterine disease to relieve pain, both by its local action on the part, and its general action on the system after absorption.

In order to produce their general action drugs may be introduced into the system through the skin, subcutaneous cellular tissue, lungs, mucous membranes, especially that of the alimentary canal, serous membranes and veins. The same drug applied in the same quantity through different channels may have different effects; for not only may slower absorption give rise to difference in the amount present at any time in the blood as already explained (p. 29), but a reflex effect upon the organism may be produced by the local action of the drug at the place of introduction.

Application of Drugs by the Skin.

There are three different methods of applying drugs to the skin which are well recognised, these are :—

1. Epidermic, to the skin covered by epidermis.
2. Endermic, to the skin denuded of epidermis.
3. Hypodermic, to the subcutaneous cellular tissue.

Epidermic Application. — Remedies are applied to the unbroken skin chiefly for their local action on the part to which they are applied, or their reflex action through the nervous system on more distant parts. The epidermic applications are comparatively rarely used as a means of introducing drugs into the system, for the epidermis opposes such an obstacle to absorption, that it takes place slowly and with great difficulty.

In some of the lower animals, such as frogs, respiration takes place to such an extent through the skin, that the animal will live

for a long time after respiratory movements have ceased. Respiration also takes place through the skin in man, but to a very slight extent, the absorption of oxygen and the excretion of carbonic acid being only about $\frac{1}{200}$th part of that in the lungs.

The skin is able to absorb other gases as well as oxygen, such as sulphuretted hydrogen, carbonic acid, carbonic oxide, and the vapours of hydrocyanic acid, ether, and chloroform.

From the relief which persons who have been shipwrecked and have suffered from extreme thirst have received by bathing in sea-water, or putting on shirts wet with sea-water, it seems probable that the skin is able to absorb water, but this fact also shows that solids dissolved in the water are not absorbed by the skin. A good deal of discussion has taken place regarding the absorption by the skin of substances applied to it in a state of solution. Experiments on this point have usually been made with iodide of potassium, on account of the ease with which this salt can be detected in the urine. The results have generally been negative, but sometimes they have been positive. The general result is that the salt is never absorbed by the skin from the solution, and that in the cases where absorption has taken place, it has been due to the skin not having been washed after the bath, so that the iodide has crystallised on the surface, and has afterwards by friction of the clothes been rubbed into the sebaceous glands. It would appear that the fat in the skin as well as the epidermis presents an obstacle to the absorption of substances in solution, but when they are applied in such a form that they can readily mix with the sebaceous matter of the skin, they are tolerably readily absorbed, as for example when they are used in the form of ointment and well rubbed into the skin, so as to penetrate into the sebaceous follicles and also the sweat glands. They are also absorbed when dissolved in ether, and especially in chloroform, even when simply painted over the surface. Alcoholic solutions are not absorbed when painted on in this way, although they may be absorbed if rubbed well in. It has been supposed that the absorption of chloroform solutions is due to the chloroform mixing with the sebaceous matter. But if true at all, this is certainly not the complete explanation of the fact, for as has just been mentioned, alcoholic solutions are not absorbed although alcohol as well as chloroform will dissolve sebaceous matter. Waller has also shown that chloroform passes rapidly through the dead skin, carrying with it alkaloids dissolved in it. Its action is therefore to a great extent due to its peculiar endosmotic power.

The vascularity of the skin greatly alters its absorptive power. In the frog, absorption usually occurs rapidly through the skin, so that if the hind legs be immersed for a few minutes in a solution of cyanide of potassium, the salt is rapidly absorbed and can be detected in the mouth of the animal in a few minutes. But if the circulation be depressed by the previous administration of ether,

curare, or any cardiac depressant, this absorption into the system does not take place; for although the cyanide of potassium passes through the skin, yet, the subcutaneous circulation being feeble, it is not conveyed away from the point of local application into the system generally.

The absorption of drugs may therefore be diminished by depression of the circulation either locally at the point of application or in the system generally. It may be rendered more rapid by increased circulation at the point of application. A general increase in the circulation usually accelerates the circulation in the different parts of the body, but does not necessarily do so, for the vessels of a part may remain contracted while the general circulation is more rapid than usual.

A local increase in the circulation occurs from inflammation of a part, or from temporary irritation such as that produced by rubbing, or by the application of irritant substances. The use of friction, therefore, increases absorption not only by pressing the substances employed into the sweat glands and hair follicles but also by increasing the circulation, and this effect will take place to a still greater extent if the substances used have a tendency to cause dilatation of the vessels.

The most common methods of applying drugs epidermically are baths, poultices, inunction, and friction.

Baths.

These may be either **local** or **general.** In **general** baths, the whole of the body excepting the head is exposed to the action of various agents. According to the nature of the agent, baths may be divided as follows—

- I. WATER.
  - A. Simple.
    - Cold.
      - (1) Ordinary full bath.
      - (2) Affusions.
      - (3) Spray.
      - (4) Sitz-bath.
      - (5) Foot-bath.
      - (6) Cold pack.
      - (7) Compresses.
      - (8) Douches.
    - Hot.
      - (1) Tepid bath.
      - (2) Warm bath.
      - (3) Hot bath.
      - (4) Hot foot-bath.
      - (5) Hot sitz-bath.
  - B. Medicated.
    - (1) Sea bathing.
    - (2) Common saline bath. Artificial sea-water made by dissolving bay-salt in water (1 lb. of salt in 30 gal. of water).
    - (3) Acid bath.
    - (4) Alkaline bath.
    - (5) Sulphurous bath.
    - (6) Mustard bath.
    - (7) Pine bath (Fichtennadelbad).

II. VAPOUR.	A. Aqueous.	(1) Simple	Russian. Simple vapour.
		(2) Medicated.	Vinegar.
	B. Volatilised drugs, *e.g.* Calomel.		
III. AIR.	Turkish bath.		

Cold Bath.—The effect of a bath depends very much upon its temperature.

In a cold bath, the temperature of the water is at or below 70° F.

The **first** effect of immersion in a cold bath is contraction of the vessels of the skin, accompanied by a feeling of chilliness and perhaps even of shivering. When the water reaches the level of the chest, the respiratory centre becomes reflexly affected, and the respiration becomes gasping.

After a few minutes the cutaneous vessels begin to relax, and the blood returning to the surface warms it. If the person now comes out of the bath, dries quickly and rubs vigorously, the brisk circulation in the skin gives rise to a pleasant feeling of warmth.

The feeling of warmth, or at least of lessened coldness, will occur even if the bath be continued, but the increased circulation in the skin allows the blood to be much more rapidly cooled, and thus the temperature of the body is much more quickly reduced. When the blood which has been thus cooled in the skin returns to the nerve-centres, it appears to stimulate the vaso-motor centre and produce a second contraction of the cutaneous vessels, accompanied by a greater and more persistent chilliness than before.

The **object** of cold baths is usually:—1st, either to have a **tonic** and bracing influence on the body; or 2ndly, to **abstract heat** from the body in cases of fever.

As a **tonic** the cold bath is often very efficacious, and not only gives a feeling of strength and comfort, but tends to prevent those who take it from catching cold so readily as they might otherwise do. The vessels of the skin are, as has already been mentioned, the regulators of temperature, and contract when they are exposed to cold: thus protecting the internal organs from its chilling influence. But Rosenthal has found that when animals are kept for a long time in a warm chamber, their vessels lose to a great extent their contractile power, and thus the animal becomes much more readily chilled when exposed to cold. Cold baths, by training as it were the cutaneous vessels to contract, tend to protect the organism from the injurious effects of accidental exposure. Besides this, however, the stimulation to the circulation which comes as an after-effect, tends to increase both the tissue change in the body, and the excretion of waste substances from it. In consequence of this cold bathing is usually followed by an increased appetite, so

that the most favourable conditions for the nutrition of the body are supplied by cold baths, viz. increased supply of food, increased tissue change, increased excretion of waste.

Cold baths may therefore be looked upon as a most powerful tonic.

But while cold baths are of great use to those with whom they agree, they **may be productive of great harm,** when they are indiscreetly used. As a general rule it may be said that when they cause much discomfort during the bath, and especially if they cause chilliness afterwards, they do harm rather than good. This is more especially the case with children and with persons of feeble circulation.

Rosenthal's experiments, already quoted, show us that there is a scientific basis for the popular notion of "**hardening**" by exposure. But this process may be carried much too far, and instead of getting excitement of the circulation with all its attendant advantages, the effect of the bath may be to lower the temperature, depress the circulation, and greatly injure the nutrition. The **risk** of such injury may be much **diminished** by proper attention to the mode of giving the bath. In children or delicate persons it is better as a rule to avoid immersing the whole body, and especially to avoid putting the feet in cold water at the same time as the body. The best way is to let the person sit down in a sitz-bath with the feet out and quickly to dash the water over the face, chest, back, and arms. Then a large bath sheet is to be thrown around the body so as completely to envelope it, and to prevent its being chilled during the process of drying. For during the exposure of the body while the surface is still wet, the chilling process is going on by evaporation during summer, and by conduction by the cold air in winter. This may be seen markedly in persons of a feeble circulation who rise from the bath with a feeling of slight glow, but lose it completely and begin to feel chilly, if the process of drying is delayed. Instead of a bath sheet, a dressing-gown made of towelling may be used. For very delicate persons the water of the bath should be rendered tepid by the addition of a little hot water, and the face may not be sponged until after the rest of the body has been dried and the clothes put on.

Sometimes the vigorous use of a flesh-brush over the chest tends to assist the reaction, and if practicable, a short though brisk walk is advisable just after the bath. It must not, however, be long, as otherwise exhaustion might set in, and the appetite instead of being increased would be diminished.

Besides the tonic action which cold baths exert on the circulation and on the body generally, they appear to have a beneficial action in certain disturbances of the respiration.

The respiratory centre (p. 201), may be strongly affected reflexly by cold applied to the surface of the chest, as is shown by the gasping

breathing, or inspiratory tetanus, observed when the cold water reaches the chest on walking slowly into it.

Cold sponging as recommended by Ringer in his excellent work on Therapeutics is exceedingly useful in laryngismus stridulus. It should be used two or three times a day whatever be the weather. If the child be hoarse, it should not be allowed to go out, but if there is no hoarseness, the fresh air, even if cold, will be advantageous. To arrest a paroxysm cold water should be dashed over the child.

Ringer also recommends it for a catch in the breath occurring in young children during the night, awaking them from sleep.

By abstracting heat, cold baths are useful in **fever** in several ways. By reducing the temperature they tend to lessen the amount of **tissue change** which is already excessive, and they thus tend to husband the patient's strength, as well as to reduce the alterations of the tissues, such as fatty degeneration of the heart, which occur in consequence of a high temperature. By lessening the temperature also, they diminish the rapidity of the pulse, and by thus prolonging the cardiac diastole give more opportunity for the nutrition of the muscular wall of the heart.

A high temperature, if it is remittent is better supported than a lower temperature which is continuous, and therefore Liebermeister, to whom we in a great measure owe the recent introduction of cold baths as a therapeutic measure, uses them with the object of increasing and prolonging the remissions in temperature which usually occur spontaneously in febrile diseases.

There are several ways of employing cold baths to reduce temperature. One is that of **cold affusion,** in which the patient is put into a tub and four or five gallons of cold water thrown over him. Another is to place the patient in a **bath** at about 90° F. and **gradually reduce** the **temperature,** by the addition of cold water, to 80°, 70°, or even 60° F. The patient is kept in this from ten to twenty minutes, according to his strength and the height of the temperature. As the temperature continues to fall for some time after the removal of the patient from the water, the bath should not be continued so long as to lower it to the full extent required while he is in the bath, lest collapse occur afterwards.

Instead of the bath being gradually cooled down, it may be **used at once** at a temperature between 60° and 90° according to the condition of the patient, and if the temperature be very high, the water must be cooled still more by means of **ice,** and its action aided by ice given by the mouth and rubbed or laid upon the surface of the body. This treatment may be adopted even although pneumonia be present, if the patient's life is threatened by an excessive rise in temperature. When the temperature rises again the bath should be repeated.

Cold Pack.—The pack is a less efficient means of abstracting heat from the body, but it is useful in causing a different distribution of blood in the body. It is therefore sometimes very useful

in lessening delirium and producing quietness and sleep. In employing it a wet sheet is wrung well out of cold water and wrapped tightly around the patient; over this are wrapped one to three blankets. A little heat is abstracted at first by the cold of the sheet, but this is very little, and indeed it is asserted by some that cold packs instead of abstracting heat, prevent its escape. The skin soon becomes warm and frequently profuse perspiration is produced. A certain amount of heat is lost, though perhaps not very great, by the evaporation through the blankets. It is probable however that the production of heat is to a certain extent lessened, at least in restless patients, by their movements being mechanically restrained by the sheet, and also by the blood being withdrawn from the internal organs and muscles to the skin. As the pack restrains the movements in a most complete way and with a force against which it is in vain to struggle, while at the same time it is comfortable and soothing, it frequently induces sleep when narcotics have been useless.

Cold sponging is sometimes a very useful means of abstracting heat in cases of fever, where the patient is weak and the temperature, though perhaps not going above 104° or 105° F., tends rapidly to regain its former height after cooling, and where it seems inadvisable to subject the patient to the frequent movement in and out of bed required in cold baths. The loss of heat consequent on cold sponging is due partly to the application of the cold water, but it is due chiefly to the evaporation which takes place from the surface of the body. Consequently sponging with tepid or even with hot water will also reduce temperature.

Cold Douches.[1]—In this form of bath a stream of water having considerable force is directed against a part of the body. The stream may either be unbroken, and to this the name douche is usually restricted, or it may be broken up by delivery through a rose into a number of minute streams so as to form a shower or rain bath. If the douche is large (one to two inches in diameter) it causes a great amount of shock and sometimes does much harm. Usually a stream of a quarter of an inch in diameter is quite sufficient for all purposes. Douches are chiefly applied to the spine, spleen, liver, joints, anus, and vagina. The **spinal douche** usually consists of a single stream, and may either be allowed to fall vertically upon the spine, the body being more or less inclined, or it may be delivered from a horizontal pipe with the body in an upright position. It is useful as a stimulant in melancholia, cerebral anæmia, and general debility. To avoid too great depression it is better to apply hot and cold water alternately, unless it is used immediately after a hot application such as a spinal pack. Douches to the **liver and spleen** have been found useful in

[1] For a short and concise account of the various appliances used in hydro-therapeutics, *vide* Paper on "Rational Hydro-therapeutics" by G. L. Pardington, M.D., *Practitioner*, Jan. 1884.

chronic congestion and enlargement of these organs. The douche applied to stiffened **joints** appears sometimes to be of considerable service.

The **ascending douche** is usually delivered through a rose, so as to form a shower, and it is directed against the perinæum while the patient is in a sitting position. It is useful in hæmorrhoids and pruritus ani, and when used at a regular hour daily, first tepid and then cold, it is useful in constipation.

The vaginal douche is used by the patient lying on her back with her knees drawn up and with the pipe in the vagina. It is useful in vaginal leucorrhœa and cervical catarrh, and in chronic subinvolution and hyperplasia the hot douche at 105° F. to 110° F. twice a day for several minutes is of much service.[1]

Local Application of Cold.

Sitz-Bath.—When a person sits down in a cold sitz-bath, or when he sits down in an empty bath and cold water is poured into it, until it covers the hips, the vessels of the parts exposed to the cold contract, and the blood is consequently driven into other parts of the body. It would appear however that not only do the vessels of the skin contract, but that also contraction of the intestinal vessels occurs reflexly through the splanchnic nerves: so that in consequence there is a feeling of warmth and fulness in the head, an increase in the volume of the arm as measured by the plethysmograph, and a rise of temperature in the axilla.

A cold sitz-bath, when applied only from one to five minutes and followed by a brisk rubbing afterwards, tends to increase the amount of blood in the abdominal organs, to quicken the circulation in the liver and spleen, and to augment the activity of the movements of the intestine and bladder. It may therefore be used with advantage in constipation and in disorders of the bladder depending upon weakness, such as either difficulty in expelling the urine or difficulty in retaining it.

In pregnancy, cold sitz-baths are sometimes useful, giving a feeling of comfort and strength, and lessening the sensations of dragging in the abdomen.

Where any tendency to premature expulsion of the fœtus exists they should be avoided, as the increased circulation which they cause in the pelvic organs might lead to abortion.

When cold sitz-baths are continued for a long time, as from ten to thirty minutes, at a temperature from 8° to 15° C. the contraction of the abdominal vessels appears to be more permanent, and thus they may be employed for the purpose of lessening congestion in the intestine; and may be used with advantage in cases of obstinate diarrhœa and congestive enlargement of the liver and spleen.

[1] Pardington, *op. cit.*

The effect of a prolonged sitz-bath in lessening congestion of the abdominal organs is greatly increased if it be preceded by a wash-down with brisk friction, so that the blood may be attracted to the other parts of the surface as well as driven out of the abdomen by contraction of the intestinal vessels.

Cold Foot-Bath.—Coldness of the feet not only causes discomfort to the person, but if it occurs at night, it may prevent sleep. Putting them in hot water may warm them temporarily, but will not do so permanently, and a much better way is to put them in cold water, rub them briskly while in it, and then dry them thoroughly with a soft towel, giving them a rub afterwards with a rough bath-towel.

Cold foot-baths are to be avoided during the menstrual period, as they have a very great power indeed to check menstruation and frequently bring on amenorrhœa. Their power to check the menstrual flow is popularly known, and sometimes great harm is occasioned by young women using them to check menstruation in order that they may be able to attend some party of pleasure.

Cold Compresses.—By the application of cold over the course of an artery, it can be made to contract, and the amount of blood to the district which it supplies may consequently be diminished. This is shown by the accompanying curve taken by Winternitz from the radial artery.



FIG. 120.—Tracings from the radial artery at the wrist: *A* before and *B* after the application of a cloth dipped in cold water round the arm. After Winternitz.

The first half of the curve (*A*) was taken before anything had been applied to the arm, the instrument being allowed to remain. Ice was next applied to the arm, and the second half of the curve (*B*) shows the contraction which it had produced in the artery.

When the cold application is allowed to remain for a while, it gradually acquires the temperature of the body, and if evaporation be prevented, it comes to have the same effect as warmth, but if constantly renewed, the contraction of the artery may be kept up. A similar contraction to that just noticed in the vessels of the arm may be produced in the vessels of the head by cold applications around the neck This is shown by the fall of temperature in the auditory meatus. Cold may be applied to the neck either by a bag containing ice, or by an india-rubber bag, or coils of tubing, through which cold water may be kept constantly flowing.

It may be applied to the neck in cases of tonsillitis. Cold to the head is frequently applied in delirium, meningitis, and severe cephalalgia. It may be applied either by a bag containing cold

water or ice, or still more conveniently by a cap consisting of india-rubber tubing through which water constantly flows.

Warm Baths.

Tepid Baths.—These baths range from 85° F. to 65° F. or 29°·4 C. to 18°·3 C. They are chiefly used for cleansing purposes, and at the lower margin of about 65° F. they may be used for a somewhat tonic action in persons of feeble circulation.

Warm Baths.—These range from 97° F. to 85° F., or 36°·1 C. to 29°·4 C. When the water is above these temperatures it forms a hot bath. The warm water softens the epidermis, and is thus of much use in chronic skin diseases. It dilates the vessels of the surface of the body, and thus tends to lessen any internal congestion. At the same time it tends to induce perspiration. On this account the warm bath is useful in lessening pain depending on congestion of internal organs and in preventing congestion from going on to inflammation. It is therefore very serviceable when there is a threatening of bronchitis, or gastro-intestinal catarrh, colic, etc. It tends to reduce the temperature both by dilating the peripheral vessels and inducing perspiration, and is therefore useful in febrile conditions. By withdrawing blood from the brain it tends to induce sleep.

Hot Baths.—These range from 97° F., or 36°·1 C., upwards. A much higher temperature than can be endured at first can be borne if the temperature be gradually raised by the gradual addition of hot water to the bath while the body is immersed, and the bath may thus be raised as high as 110° F. Hot baths not only prevent loss of heat from the surface, but if above the temperature of the blood, actually impart heat to the body. The consequence of this is that the temperature of the body rises very rapidly, and therefore the respiration and pulse both become very quick. The peripheral vessels become still more dilated than in the warm bath, and the blood pours so rapidly through them that, in spite of the quick and powerful action of the heart, there may be a tendency to syncope when the head is raised. After remaining in such a bath from ten to twenty minutes, the patient must be carefully lifted out so as to avoid any risk of syncope, and should be wrapped in warm, dry blankets. The hot bath is a still more powerful agent than the warm bath in producing sweating, and is employed in cases of dropsy.

Hot Foot-Bath.—A hot foot bath has a general effect that can hardly be explained by the simple dilatation of the vessels in the feet and consequent derivation of blood to them. It seems, indeed, to exert some reflex action on other parts of the body and causes a general feeling of warmth. It is very useful as an adjunct to vascular stimulants in relieving congestion and preventing inflammation, as in threatened catarrh, bronchitis, etc. When the feet are put into a hot bath, we find that the femoral arteries

become much dilated and pulsate much more vigorously than they did before. It is not improbable that this dilatation extends beyond the femoral to the iliac arteries, and that the supply of blood is increased in the pelvic organs as well as in the feet. In cases of amenorrhœa, especially where it has been brought on by exposure to cold, hot foot-baths tend to restore the menstrual flow. They should be begun four or five nights before the period is expected, and continued during the time it ought to last. Their efficacy may be increased by the addition of a little mustard.

Hot Sitz-Baths.—These have a still greater tendency than hot foot-baths to increase the circulation in the pelvic organs, and they may be used either alone or with mustard in the manner just described in cases of amenorrhœa.

Poultices.—Poultices are simply a means of applying heat and moisture to a limited portion of the surface of the body, and they consist essentially of some farinaceous substance made into a paste with hot water. The most common substances used are linseed meal, crushed linseed, bread, bran, oatmeal, and starch. The most common basis of a poultice is either linseed meal or crushed linseed. The difference between the two is that the crushed linseed still retains the oil naturally present in the seed, whereas it has been expressed from the linseed meal. Crushed linseed, if fresh, forms an excellent basis for a poultice, but if kept long is apt to become rancid. In order to avoid this disadvantage, the British Pharmacopœia directs that linseed meal should be used, and that olive oil should be added to the poultice. Oil is only wanted when the poultice is to be applied directly to a wound or sore. It is unnecessary when the poultice is to be used for the relief of internal pain. In all cases, not only should the water with which the poultice is made be **perfectly** boiling, but the bowl in which it is to be mixed, the spoon with which it is to be stirred, and the tow or flannel in which it is to be laid, should all be as hot as possible. By adding the linseed meal to the water and constantly stirring, there is less chance of the poultice being knotty than if the water were added to the meal. If the poultice is intended to be applied to a wound, sore, boil, or carbuncle, it should be spread upon a piece of flannel or tow and applied directly to the skin, because the softening action of the water and oil it contains on the dermal tissues is required as well as the warmth. But where the poultice is used to relieve pain or congestion of the internal organs it ought not to be applied directly to the skin, but should be separated from it by something which conducts heat badly, such as flannel. The reason for this is that it is impossible to apply a very hot poultice directly to the skin on account of the pain it causes, whereas if a substance which conducts heat badly be interposed, the poultice can be applied boiling hot, the heat gradually passes through without becoming inconveniently great, and is retained for a much longer time.

Medicated Baths.

The addition of stimulating substances, such as **salt,** to the water increases the stimulation to the skin, and the amount of after-reaction.

In **sea-bathing** the stimulating effect of the salt is further increased by the mechanical shock of the waves, and sometimes also by the friction of the fine sand of the beach. Sea-bathing also differs from baths in the fact that muscular exertion is combined with it either in simply moving about and retaining one's footing, or still more in swimming.

Acid Bath.—This bath is made by mixing eight ounces of nitrohydrochloric acid with a gallon of water at blood heat (98° F.). This is sometimes used as a foot-bath, but it is better applied as a compress. A flannel roller about a foot wide, and long enough to go twice round the body, should be soaked in the acidulated water, wrung thoroughly out, and rolled round the region of the liver; a piece of oil-silk, large enough to cover it completely and leave a little margin over, should then be put over it. It may be worn for several days, being renewed every night, and it is chiefly useful in chronic disease of the liver.[1]

Alkaline Bath.—This is made by adding crystallised carbonate of soda to water in the proportion of about one drachm to each gallon. It is chiefly used in chronic skin diseases.

Sulphurous Bath.—This may be made by dissolving sulphurated potash in water, about half a drachm to the gallon, or in imitation of Barège waters may be made by mixing sodium sulphide, sodium carbonate, and sodium chloride in the proportion of twenty grains of each to the gallon. These are chiefly useful in chronic scaly skin diseases, and in rheumatism. Much more benefit is usually obtained by a visit to sulphur springs, such as those of Aix-les-Bains, Aix-la-Chapelle, Barège, Harrogate, or Strathpeffer, than from the use of sulphur baths at home.

Mustard Bath.—This is made by adding mustard to water in the proportion of about half a drachm to a drachm and a quarter per gallon. It is a powerful stimulant, but must not be applied too long. It must be remembered that, while slight stimuli to the skin increase the frequency and energy of the cardiac contractions and the rapidity of the circulation, and raise the temperature, severe irritation of the skin lessens the frequency of the pulse and the rapidity of the circulation, dilates the vessels and lowers the temperature.[2] The patient should never be allowed to remain more than ten minutes in the bath, and should be at once removed as

[1] Squire's *Companion to the British Pharmacopœia*, 13th Ed.

[2] Naumann, *Prager, Med. Jahrsch.* 1863, i. p. 1, and 1867, i. p. 133; Heidenhain, *Pflüger's Archiv*, Bd. iii. p. 504, and Bd. v. p. 77; Riegel, *Pflüger's Archiv*, Bd. iv. p. 350.

soon as he feels either burning of the skin or icy coldness. Mustard baths are generally used in order to quicken the appearance of the eruption in exanthemata.

Pine Bath.—This is made by adding a decoction of the shoots of pines to water, but it is more convenient to use the oleum pini sylvestris in the proportion of one minim to the gallon. These baths are used in rheumatism, gout, paralysis, scrofula, and skin diseases.

Vapour Baths.

In these the body is exposed to steam instead of being immersed in hot water. The effect is much the same as that of the hot bath. The so-called Russian bath consists of a room filled with steam and provided with benches at various levels. The higher the level the greater is the heat, and usually, excepting on the lower benches, it is only possible to breathe with any comfort by holding a sponge dipped in cold water before the nose. From this room the bather goes to another where he is drenched with cold water by a douche, and is then quickly dried, and allowed to rest for some time before dressing. These baths are chiefly used in chronic rheumatism. They are liable to the same objections as the hot bath, and to a still greater extent, for the inhalation of the hot steam produces greater difficulty of breathing, greater acceleration of the pulse, and greater tendency to syncope. Vapour baths, in which the body only is exposed to the action of the steam, and the head is left out, are much better. They are usually applied either by means of a kind of box in which the body of the bather is inclosed while the head remains outside, or else by introducing steam under the bedclothes, which are supported by a kind of cradle, while the bedclothes are tucked tightly round the patient's neck to prevent the escape of the vapour. The latter plan is very useful in cases of dropsy and uræmia, as it induces a copious perspiration and does not exhaust the patient nearly so much as a hot bath. In cases of acute rheumatism a vapour bath of vinegar has been recommended.

Calomel Fumigation.—This is used as a means of inducing the general action of mercury. The patient is seated naked on a wickerwork chair, underneath which is put a stand holding a shallow cup containing calomel. The calomel is volatilised by means of a spirit-lamp, and a blanket or waterproof sheet being thrown round the patient so as completely to envelope himself, his chair, and the fumigating apparatus, the calomel fumes become condensed upon his skin in a fine state of division. It is absorbed with considerable rapidity, probably from becoming mixed with the sebaceous secretion from the skin, and the general action of mercury is quickly induced.

Air Baths.

Turkish Bath.—The Turkish bath usually consists of three rooms, although frequently there are more. The temperature of the first, or dressing-room, is moderate, that of the second is higher, and that of the third is higher still. In the first room, the bather, after undressing, winds one towel round his loins, and a second round his head in the form of a turban. If he has any tendency to cerebral congestion, the second one may be wet. He then passes into the second room, where he usually waits a short time before passing into the third room. Some people, however, go directly into the third room. In both the second and third rooms the bathers partake freely of cold water. A few minutes' stay in the warmest room is usually sufficient to make the bather perspire freely, and he then returns to the second or cooler room, where he may remain half an hour or more, according to circumstances. He may then be shampooed, the surface of the body being rubbed, the muscles kneaded, and the smaller joints extended. He is next washed with a lather of soap, and sluiced with basins of tepid or warm water. For some people it is most agreeable after this to be simply wrapped in warm towels and allowed to repose in the dressing-room. Others prefer to finish up with a cold douche before proceeding to the dressing-room. Here they remain resting for a considerable time before they again dress. Turkish baths are exceedingly useful in chronic rheumatism and gout, and in persons suffering from the effects of malaria. The chief objection to the Turkish bath is the length of time that it takes. In some persons it has a weakening effect, but in many others it has none. The chief precautions are not to stay too long in the hot room, and to leave it at once if giddiness or a feeling of tightness in the head comes on. If the skin perspires with difficulty, the necessity for caution in entering the hot room becomes still greater, and it is advisable rather to spend a longer time in the second room, and drink freely of water before entering the hotter room, if, indeed, this be entered at all on the first few times of taking the bath. Persons who suffer from a feeling of exhaustion after a Turkish bath should not take a cold douche nor a plunge into water after perspiring, but should simply allow themselves to cool very gradually, and should take some stimulant such as coffee or beef-tea while doing so. Persons who suffer from malaria also should spend a good while in the second room before attempting to enter the third, as the sudden application of heat to the skin and lungs seems to irritate the vaso-motor centres and cause chilliness, or even shivering.

Friction and Inunction.

Friction of the skin causes first a temporary contraction of the vessels, followed by a more or less permanent dilatation, so that the

skin continues red for a length of time after the irritation has ceased. This redness is accompanied by a warm glow from the **increased circulation** in the skin, and friction is therefore useful as an adjunct to cold baths. Besides this, friction along the extremities in an upward direction tends to aid the flow of lymph, and thus to **remove** the products of **waste** from the muscles.



FIG. 121.—Injected lymph spaces from the fascia lata of a dog, after Ludwig and Schweigger-Seidel. The injected lymph spaces are black in the figure.

The fascia covering a muscle forms a pumping apparatus for removing waste products from the muscles. It consists of two layers, *a b* and *e f*, and between these are lymph spaces, some of which, *x*, are seen in transverse, and others, which appear black from the injection with which they are filled, are seen in longitudinal section. Each time the muscle contracts, it becomes thicker, presses the two layers of fascia together, and drives the lymph from the spaces onwards into the lymphatics. Each time the muscle relaxes the layers of fascia tend to separate, and lymph from the muscle, carrying with it the waste products, fills the spaces between the layers. The action of the muscle itself thus tends to remove the waste products which give rise to fatigue (*vide* Massage, p. 107), but after over-exertion their removal may be greatly aided by gentle but firm upward friction which will have a similar action on the fascia to the alternate compression and separation of its two layers, caused by the action of the muscle itself.

Gentle firm friction thus lessens or may even remove entirely the feeling of **fatigue** and weight in the extremities after exertion. When applied to the nape of the neck, or along the spine—it is sometimes useful in headache, in nervous irritability and in sleeplessness.

When applied between the shoulders in persons suffering from flatulence, it appears to aid the expulsion of gas from the stomach.

The effect of friction as a **counter-irritant** is greatly increased by the use of stimulating liniments. These are applied by pouring a little into the hollow of the hand and then rubbing it over the surface of the body, or else by soaking a piece of flannel in the liniment and rubbing the skin with it. Linimentum ammoniæ applied thus to the chest is useful in the bronchitis of children;

and linimentum camphoræ compositum, B.P., or linimentum terebinthinæ may be used in a similar way for adults.

In chronic inflammation of joints, liniments may be applied in a similar way. Sometimes it may be advisable also in such cases to swathe the joint in a piece of flannel or lint, soaked in the liniment so as to procure more continuous application.

Inunction.—Metallic salts are very slightly, if at all, absorbed from the skin when applied to it in watery solution, and wiped off without being allowed to dry. But when applied in the form of ointments a considerable absorption takes place. Advantage is taken of this, in order to obtain the *general* action of mercury without its *local* effect on the intestinal canal. For this purpose mercurial ointment is rubbed on the skin, and especially on those parts where the epidermis is thin, as under the axillæ and on the inside of the thighs.

Absorption also takes place, however, through the skin of the hands, and if the ointment is not rubbed on by the patient himself, but by another person, in whom the action of mercury is undesirable, it has been recommended that the latter should cover his hands with a piece of bladder thoroughly well oiled in order to prevent absorption.

In children, instead of applying the mercurial ointment by inunction, it is customary to smear the ointment on a piece of flannel, and to keep it applied to the abdomen of the child by means of a bandage.

Endermic Application of Drugs.

This method consists in applying the drug to the skin previously denuded of its epidermis or epithelial layer by blistering. The drug may be applied in the form of powder, solution, ointment, liniment, or plaster, but most frequently in the form of powder. The drug is more readily absorbed when applied in this manner than when applied over the epidermis. Cantharides may be used for the purpose of raising a blister, but a more convenient method is to fill a thimble with cotton-wool or lint soaked in the strongest liquor ammoniæ, apply it to the spot and keep it on for five minutes. If the cuticle has not then risen in a blister apply a poultice until it rises. Cut off the cuticle, place the powder on the denuded surface, and cover it with a piece of oil-silk fixed in position by two pieces of strapping crossed over it. This method was chiefly employed for the local application of morphine. It has now been almost entirely superseded by the hypodermic method, but may still be occasionally employed in cases where it is advisable to combine the counter-irritant action of the blister with the local sedative effect of the morphine.

Hypodermic Administration of Drugs.

This method, the introduction of which we owe to Dr. Alexander Wood of Edinburgh, possesses great advantages.

It consists in the **injection** of a solution of a remedy under the skin. Absorption takes place from the subcutaneous cellular tissue rapidly, and it is much less likely to be modified by altered conditions of the organism than absorption from the stomach and intestine. For in the intestinal canal there is not only the condition of the circulation to be taken into consideration, but the fulness or emptiness of the stomach and intestine, the condition of their epithelial covering and of their nervous supply, and the state of the liver. These conditions may not only delay but entirely prevent absorption.

The advantages of the hypodermic method, therefore, are 1st, **certainty** of effect, and 2nd, **rapidity** of action.

As absorption of a drug takes place so much more rapidly from the subcutaneous cellular tissue than from the stomach, a less quantity is excreted during the process of absorption, and consequently a smaller quantity of the drug is required (p. 29).

But absorption does not take place with equal rapidity from all parts of the intercellular tissue. The vascularity of this tissue, and the rate of absorption from it, are greater on the temples and breast than on the back, and greater on the inner than on the outer surfaces of the arms and legs.

As the liquids used for hypodermic injection are usually concentrated solutions of powerful poisons, it is important that neither more nor less than the quantity previously determined upon should be administered. The syringe consists of two parts:



FIG. 122.—Syringe for hypodermic injection.

a glass barrel in which a piston plays air-tight, and a hollow needle which fits tightly on to the end of the syringe either with or without a screw. The bore of the needle being very fine it is apt to get choked by rust, or by crystals of the substance last employed for injection forming within it, and rendering it impermeable and useless. In order to avoid this it should be carefully washed with water each time it is used, and a small piece of thin wire kept constantly in it during the intervals of use. When the syringe has not been used for some time, the packing of the piston is apt to shrink, so that it will no longer either suck in or drive fluid out of the barrel efficiently. This may often be remedied to a great extent by soaking the syringe for a short time in warm water and driving the piston up and down in it. If this

is insufficient the piston may be taken out, and sufficient thread wound round it to make it work. Care must be taken also that the needle fits tightly on the syringe, and that no leakage takes place at the junction. The liquid to be injected should contain no solid particles which may obstruct the needle, and if any such should be present, the fluid may be filtered through clean blotting paper.

The exact quantity required, and no more, should then be drawn up into the syringe and injected. Some syringes have a small screw upon the piston, so as to stop its movement at any required point. With such a syringe, the barrel may be filled quite full of the solution, and the required quantity injected by forcing the piston down until it is stopped by the screw. The advantage of this arrangement is that if any leakage should occur, the screw may be moved further up, and an additional quantity of solution injected without the necessity of withdrawing and reintroducing the needle under the skin. If all proper precautions be taken, however, the necessity for such a procedure will rarely arise.

Convenient places for injection are the outside of the arm near the deltoid, the fore-arms, or the thighs. In order to avoid the risk of introducing the needle into a vein, the injection should not be made over a vein visible through the skin. The skin should be pinched up between the finger and thumb, the needle pushed directly through it, and then passed onwards a little way obliquely in the subcutaneous cellular tissue.

Objections to Hypodermic Injections.—The chief objections are, (1) the pain caused at the time by the introduction of the needle, or by the drug itself after its injection, (2) the inflammation which either the needle or the drug may give rise to subsequently, (3) the scars which may be left by the frequent repetition of the injection, (4) the danger of communicating a specific or contagious disease, (5) the danger of injecting the drug directly into a vein, and thus producing a dangerous or fatal effect from the too rapid entrance of the drug into the circulation. With a little care these untoward results may be almost entirely avoided. If the needle is well sharpened the pain of introducing it is very slight, and may be still further lessened by making the patient take several deep breaths in rapid succession before the injection is made. If the patient is excessively sensitive, partial or complete anæsthesia of the part may be produced by cold or by carbolic acid (p. 172).

The solutions should always be perfectly free from solid particles and should be as neutral and bland as possible. Metallic salts have their irritating properties diminished or removed when combined with albumen or with an alkaline citrate or tartrate so as to form double salts.

By washing the syringe and needle thoroughly out with carbolic acid, the danger of conveying any specific or contagious disease is

rendered very slight, and it may be completely avoided by heating all parts of the syringe in a spirit-lamp before using them. The syringe employed by Koch in his experiments on the effects of micro-organisms in producing disease (Fig. 122) is admirably adapted for this purpose, as all parts of it can be readily heated, and the padding upon the piston which is more likely to retain infective matter than any other part of the syringe can be renewed each time that the instrument is employed. In order to prevent pain or inflammation being caused by the solution injected, care should be taken that its reaction is as nearly as possible neutral, and that the quantity should not be great. The smart which follows the injection is lessened by rubbing the finger gently over the part so as to distribute the fluid in the subcutaneous tissue. If it is necessary to employ such large quantities as half a drachm or a drachm, as may be the case with ergot, it is better not to inject the solution under the skin but into the substance of a muscle, such as the gluteus maximus.

Cicatrices are not apt to follow injection if the precautions already mentioned have been taken, and if the injections are not made too frequently at the same point.

Application of Drugs to the Eye.

For inflammation of the lids, ointment is smeared between the edges.

Cold water is applied to the conjunctiva for its tonic action, by keeping the eyes open and then dipping the face into a basin of water.

Strong solutions like that of atropine are applied to the conjunctiva by dropping them into the outer canthus of the eye and allowing them to flow over the surface. If such a solution is to be applied frequently, it may be dropped into the inner canthus, and the head held so as to allow it to drop out of the outer canthus; for when the reverse procedure is employed the atropine may pass down the lachrymal duct, and being absorbed may produce its general effect upon the system and cause symptoms of poisoning.

Application of Drugs to the Ear.

Astringent solutions are usually applied to the auditory meatus, by injecting them in a gentle stream by means of a small syringe (Fig. 123).



FIG. 123.—Vulcanite syringe for injecting solutions into the ear.

For the mode of injecting into the middle ear, special treatises on aural surgery must be consulted.

Application of Drugs to the Nose.

Drugs are applied to the nose in the form of powder, which may be taken in the same way as **snuff** by putting a little on the top of the thumb, holding it in front of the nose and strongly inspiring; or the powder may be put on a small piece of cardboard in which a pin-hole has been made just under the powder, or with a small perforated spoon like that used in Scotland for snuff. Sternutatories may be used in this way, and so may Ferrier's powder for soothing the mucous membrane in cases of commencing catarrh.

Fluids may be applied by **insufflation,** the nose being simply immersed in them and strong inspiration being made.

They may also be applied by the **nasal douche.** This consists simply of a long india-rubber tube to act as a syphon (Fig. 124),



FIG. 124.—Nasal douche.

The upper end of it is placed in a vessel filled with the solution to be applied, and it is prevented from falling out by a hollow lead weight attached to its upper end. At the lower end is a conical nozzle, which completely plugs the nostril. The tube being filled with the fluid by suction so that it commences to act as a syphon, the nozzle is placed in one nostril, and the head is held with the mouth open over a basin. In this position the posterior nares are cut off by the soft palate from the pharynx, and the solution passes up one nostril and out through the other, so that the nasal cavity is washed out and its mucous membrane acted

upon by the solution which is employed. By altering the position of the head, both in insufflation and in washing with the douche, the part of the nose reached by the fluid will be changed. Thus when the head is held much forward, the anterior and upper part of the nose will be chiefly cleansed, when the head is held upright, the posterior and lower, and when the position is intermediate, the middle part of the nose will be most affected.

Pure water is irritating to sensitive mucous membranes like that of the nose, and so instead of employing pure water it is much better to use a ·5 to 1 per cent. solution of common salt, which is a bland non-irritating fluid. Such a solution may be made by adding a drachm of common salt to a pint of water.

Fluids may also be applied to the nose in the form of spray, either directed simply into the nostrils, or by means of a catheter perforated with a number of minute holes, and introduced along the floor of the nasal fossæ. The former may be used for applying astringent and deodorising solutions, and the latter for the purpose of washing out the nose and removing hardened secretions.

Application of Drugs to the Larynx.

Solid powders may be applied to the larynx by **insufflation.** The insufflator used for this purpose consists of a tube curved at one end, and having at the other a piece of india-rubber tubing or an india-rubber ball, by which a powder may be blown through the tube near this end of the tube. There is a small opening in



FIG. 125.—Insufflator for applying powders to the larynx. A, piece of india-rubber covering the opening in the insufflator, by which the powder is placed in it. B, india-rubber tube, by which the powder is blown out of the insufflator into the larynx. C, curved end of insufflator for introduction into the pharynx.

its side through which the powder may be introduced, and this is afterwards covered by a sliding ring or a piece of india-rubber tubing so as to prevent the powder from escaping. The bent part of the tube is carefully introduced into the mouth so as not to cause retching by touching the tongue or soft palate, and, when the end of it points down over the larynx, the patient is told

to take a deep breath. At the moment of inspiration the operator forces the powder out of the tube into the larynx, either by blowing through the india-rubber mouth-piece or by compressing the india-rubber ball. Morphine applied by this method gives more relief than almost anything else in laryngeal phthisis. About one-sixth of a grain is sufficient, and in order to give it sufficient bulk it may be mixed with either starch or bismuth.

Solutions may be simply applied by means of a sponge firmly tied to a piece of whalebone having the proper curve; as the patient inspires this is pushed down the larynx. Doubts have been expressed as to whether the sponge does get through the larynx, but I have seen the cricothyroid membrane projected forwards by the sponge applied in this manner.

Nitrate of silver applied in this way gives relief in cases of phthisis, but it is a very rough method, and the application of the solution by means of a brush with the aid of the laryngoscope is much to be preferred. When the sponge has not been firmly fixed it has been known to come off and fall into the trachea.

Fluids may be applied by a brush to the larynx, the operator using the brush with one hand and holding the laryngoscopic mirror with the other, while the patient holds his tongue out himself. If the patient is made to take several deep breaths in succession a slight anæsthetic condition is produced which renders the operation much more easy.

Caustics are best applied to the larynx by means of a caustic holder in which the caustic is concealed until it reaches the point of application, when it can be projected by a touch of the finger, and again withdrawn at the wish of the operator.

Liquid may be applied to the larynx in the form of spray, produced either by means of Richardson's apparatus or by a current of steam. The nozzle of the spray producer may be simply directed towards the pharynx, or the tongue and the cheeks may be protected from the spray by a cylindrical glass speculum.

Application of Drugs to the Lungs.

Inhalations.—Vapours employed as inhalations act not only on the bronchial tubes but upon the larynx, pharynx, and nostrils. One of the commonest is that of simple hot water. A jug is filled about half full of boiling water and the head held over it, the steam being kept in by means of a napkin or towel thrown over the head and around the mouth of the jug. This application often gives great, though temporary, relief in nasal, laryngeal, and bronchial catarrh.

Vapour may be **medicated** by the addition of various substances to it such as carbolic acid, tincture of benzoin, creasote, or pine oil. But in order to gain the full advantage of the

admixture of these substances it is better that the inspired air should not merely play over the surface of the hot water, but be drawn through it, and for this purpose **inhalers** are employed. In these the air is inspired by means of a mouth-piece fitted with a valve. This valve prevents the air from passing into the mouth-piece, so that during inhalation it is sucked through a tube which dips under the water and passes into the mouth laden with the vapour. During expiration it passes readily through the valve just mentioned.

In cases of bronchitis, the patient breathes much more easily when the air of the room is kept warm and moist, and this is effected by means of a **bronchitis kettle.** This is simply a tin kettle with a spout about three feet long which projects into the room, so that when the kettle is kept boiling briskly a constant current of steam is driven well out into the room. When this cannot be obtained a substitute may be extemporized by rolling a piece of brown paper into a tube, tying a piece of string around it at intervals so as to keep it in shape, and putting it over the spout of an ordinary kettle. In cases of tracheotomy it is usual to keep the air still warmer and moister by hanging sheets around the bed so as to convert it into a kind of tent, and then conveying the steam from a bronchitis kettle into it by means of an india-rubber tube, or keeping up a constant spray by one of Lister's steam spray producers.

Smoke.—The attacks of difficulty of breathing which come on in cases of pure spasmodic asthma, in advanced kidney disease, or in emphysema, are frequently much relieved by inhaling the smoke which issues from burning touch-paper or from powdered stramonium. The touch-paper or stramonium may be simply laid on a plate, or may be placed at the bottom of a cup or jug, and the fumes inhaled. Datura is often used in the form of cigarettes made either from the leaves of the datura stramonium or datura tatula.

Application of Drugs to the Digestive Tract.

Mouth and Pharynx.—Weak solutions are applied to the mouth in the form of **washes** with which the mouth is rinsed out. Stronger ones may be **painted** with a camel's hair brush inside the cheek, lips, gums, tongue or pharynx. Solutions may be applied to the pharynx by painting with a brush; solid substances, as caustics, by **rubbing.** In using caustic, care must be taken that it is firmly attached to the caustic holder and, in the case of nitrate of silver, that only a short point is used, as otherwise the caustic may fall off, or the stick of nitrate of silver may break and be swallowed. This is especially necessary in touching the throat in children. In cases of post-nasal or pharyngeal catarrh solutions

such as glycerin or tannin, &c. may be applied to the back of the soft palate and the **posterior** part of the **nares** by means of a camel's hair brush fixed on a wire which may be bent to any desired angle.

Masticatories.—We sometimes give the patients solid pieces of a drug to chew. These are called masticatories. We use them for their action upon the mouth itself, *e.g.* pellitory, where we wish to increase the secretion of saliva; or where we not only wish to produce the effect upon the mouth, but the effect of the drug mixed with the saliva upon the stomach and intestines, as in the case of rhubarb.

Gargles.—In gargling, a full breath is taken, the mouth is filled with the liquid which is to be applied to the pharynx, and the head being then thrown back the fluid runs against the pharynx and is partly thrown up against the soft palate by the air which gradually escapes from the lungs. In cases where it is advisable for the fluid to reach the posterior nares, the patient should lie down flat, take a mouthful of the liquid, draw out the tongue as far as possible with a handkerchief, and gargle while in that position. By throwing the head suddenly forward the liquid may be brought through the nose. This method is useful both as a method of applying the liquid more thoroughly to the pharynx and as a training preparatory to rhinoscopic examination.

Stomach.—Drugs are applied to the stomach in the form of solutions or draughts, pills, powders, or boluses, &c. which are swallowed.

Powders may be very conveniently given in wafers. A thin wafer is moistened with water, and the powder being introduced, is folded up in it and swallowed. Another most convenient vehicle is oatmeal porridge, a little of which is put upon a spoon, and, a depression being made in it with the finger, the powder is put into it and covered over with porridge. The porridge should fill the front half of the spoon, and the back part should be filled with milk, which helps the child to swallow more easily. Powders are sometimes given to children in jelly, but this is too soft, and so also is the paste made of bread and milk, although this may be used when porridge cannot be readily obtained. Pills may be simply swallowed with water, or taken in jelly, but some people are unable to take them without choking, and children especially have much difficulty in swallowing them. This difficulty is readily got over by dividing the pill into four or more parts, and taking each part in a little oatmeal porridge. Custard puddings, or puddings made of corn flour or arrowroot, may be used instead of porridge, but are hardly so good.

Stomach-pump.—In cases where the patient is unable to swallow from paralysis of the pharynx, constriction of the œsophagus, or narcotic poisoning, the stomach-pump may be used. This consists of a large, double-acting syringe with a flexible tube attached. In

using it care must be taken[1] (1) to have the tube well softened in hot water; (2) to keep its end directed towards the pharynx, and not bent too much forward, lest it enter the larynx; (3) not to use violence in introducing the tube, lest it should be driven into the mediastinum, or even through the walls of the stomach itself, into the peritoneal cavity; (4) not to use violence in working the syringe, lest the mucous membrane of the stomach should be drawn into the lower orifice of the tube and injured.

In place of the stomach-pump the **gastric syphon** may sometimes be advantageously employed, especially for feeding. It consists of a piece of thick-walled, soft, and flexible india-rubber tubing. It is so soft and flexible that it can hardly by any possibility injure the œsophagus or stomach, and yet it is sufficiently firm to pass down without much difficulty. After it is in, an ordinary funnel is attached to the projecting end, and water, beef tea, or whatever substance one wishes to introduce into the stomach, is simply poured in, the funnel being kept at, or above, the level of the patient's mouth. When it is desired to empty the stomach water is poured in, in the manner just described, and then the outer end of the funnel is held down as low as possible—the syphon action is thus reversed, and the fluid which has just been poured into the stomach again flows out of it.

Intestine.—Drugs are applied to the intestine by means of enemata or suppositories. **Enemata** are liquid injections into the rectum for the purpose of emptying the lower parts of the bowels when we do not wish to excite the whole bowel, or when we wish to cause as little movement as possible to the patient. They are also used for the purpose of administering nutriment when the patient is unable to swallow or to retain food given by the mouth. In using enemata for the purpose of inducing action of the bowels the quantity should be considerable—sixteen fluid ounces, or even more. When they are intended to be retained, the quantity is usually small—not more than two to four fluid ounces at most. In using the enema syringe care should be taken that it is first emptied of air and that it is not pushed forcibly into the bowel. The nozzle should not be directed too much backward, as if this be done, and especially if force be employed, ulceration of the posterior wall of the rectum may be induced. Where enemata are given for the purpose of nutrition, a much larger quantity than four ounces may be retained by using the proper method. A flexible, soft rubber tube should be passed for eight or ten inches up the intestine and the nutrient enema may then be slowly and gently introduced either by using a syringe or by simply pouring it into the tube by a funnel. By this method

[1] In cases of poisoning it may be absolutely necessary to use the stomach-pump, but in ordinary cases a tube should never be passed down the œsophagus until the absence of aortic aneurism has been ascertained by a careful examination of the patient's chest.

the fluid is introduced into the sigmoid flexure or descending colon, and if the patient can be propped somewhat so as to lie on his left side, none of it may descend into the rectum. In this case there will be little or no tendency to evacuate it and the whole may be readily absorbed.

Suppositories are drugs made up into a conical shape by means of cacao-butter. When introduced into the rectum the cacao-butter melts, the drugs become spread over the surface of the mucous membrane of the rectum, and gradually absorbed. They are employed when we wish to get the local action of a drug upon the rectum, or the parts surrounding it, or when we wish to get the general action of a drug after its absorption without producing any local effect upon the stomach.

Application of Drugs to the Urethra.—They are usually employed as lotions. The syringe used to inject them should not have a small thin nozzle, but should have a conical point such as that shown in Fig. 126, which fills up the opening of the urethra and allows the injection to be forced up to the neck of the bladder without any escaping.



FIG. 126.—Vulcanite syringe for injecting solutions into the urethra.

Application of Drugs to the Vagina and Uterus.—Lotions are usually either injected into the vagina with a syringe, or allowed to flow into it from a reservoir at some height above the patient. In either case, if it is desirable that the lotion should remain in contact with the vaginal walls or cervix uteri, the patient should lie on her back with the hips raised by a pillow. The syringe employed for the vagina is usually furnished with a shield to prevent it from being introduced too far, and it ought to have no central opening, but only openings at the side, as occasionally, when astringent and irritating fluids have been used with syringes having a central aperture, they have been forced into the cavity of the uterus, and have there produced uterine contraction and consequent pain. Sedative and astringent substances are often introduced in the form of **pessaries** or vaginal suppositories, in which the active substance is mixed with either cacao-butter or with gelatine and glycerine. Solids such as **caustics** are applied either to the vaginal walls or cervix directly through a speculum, and powders are applied on pledgets of cotton-wool. **Tents,** consisting of thin sticks of a porous substance, are introduced into the cervix itself for the purpose of dilating it, and solutions may be injected into the uterine cavity itself by means of a syringe provided with a long nozzle.

CHAPTER XVIII.

ANTIDOTES.

ANTIDOTES are remedies which **counteract** the effect of **poisons.**

Action.—Antidotes may act in two ways: they may either **prevent** the action of the poison on the body, or they may **counteract** its effects. Many of them, especially those which are employed in the case of mineral poisons, form chemical compounds with the poisons which are almost insoluble and therefore inert.

Some of these compounds though nearly insoluble will nevertheless be gradually dissolved and absorbed if left too long in the stomach, and therefore it is advisable to remove them by means of **emetics** or by the **stomach-pump** or stomach-syphon as soon as possible. Indeed, it is advisable **in all cases of poisoning,** when the substance has been taken into the stomach, to **empty the stomach** at once before proceeding to administer the antidote. The only possible **exception** is when a highly corrosive substance has been taken which may have partially dissolved the wall of the stomach and rendered it extremely liable to rupture during emesis, or on the introduction of a stomach tube. If the poison has been absorbed, we must try to counteract its poisonous action on the respiration, circulation, or temperature, by giving substances which will tend to produce an opposite effect.

The more common poisons with their antidotes are given in the following table:—

Poisonous Gases.

Sulphuretted hydrogen	Chlorine cautiously inhaled.
Chlorine	Steam inhalations.
Bromine	
Iodine vapour	
Vapour of ammonia .	Vapour of vinegar.
Carbon monoxide.	Fresh air and artificial respiration. Transfusion.

Poisonous Gases—*continued.*

Nitrous oxide	Artificial respiration, with the tongue drawn forward, and with intermittent pressure over the cardiac region if the heart is failing.
Coal gas	Artificial respiration.
Charcoal fumes . . .	Alternate warm and cold douche to the head and chest.
Carbonic acid (choke damp)	Friction.
Marsh gas	Mustard plasters over surface.
Fire damp	

Acids.

Acids—	Alkalies—
Sulphuric	Bicarbonate of soda or potash.
Hydrochloric . . .	Magnesia.
Nitric	Chalk or whiting.
Phosphoric	Plaster from the wall.
	Soap.
	Milk.
	Eggs beaten up.
	Olive or almond oil.
Oxalic acid	Chalk or whiting, or plaster from the wall, with water.
Bin-Oxalate of potash (salts of lemon or salts of sorrel)	
Tartaric acid	
Acetic acid	
Hydrocyanic acid . .	Alternate cold and warm affusions.
	Artificial respiration.
	Injection of atropine (2 to 4 min. liquor atropiæ), repeated every half hour.
	Per- and proto- salts of iron, with magnesia, are recommended to render the acid insoluble, but it acts so quickly that there is usually no time for their application.

Alkalies.

Caustic potash or soda	Vinegar.
Caustic lime	Lemon juice.
Caustic ammonia . . .	Other dilute acids.
Carbonate of soda or potash	Milk.
	Oil.

Alkalies—*continued.*

Aconite	Spirits. Ammonia. Warmth. Digitalis. Atropine.
Alcohol	Coffee. Cold douche to head.
Anæsthetics Chloroform, ether, etc.	Artificial respiration, inversion, etc.
Antimony	If vomiting does not occur wash out the stomach with water first; then with tannic or gallic acid; then give milk and white of egg as demulcent to stomach.
Arsenic	Wash out the stomach with large draughts of warm water, either by stomach-pump, or if the arsenic itself does not cause vomiting, by using sulphate of zinc. Give magnesia, or still better, freshly precipitated oxide of iron made by precipitating a solution of perchloride of iron with carbonate of soda. Dialysed iron is also very useful.
Atropine	Give stimulants and coffee; inject caffeine subcutaneously; arouse from stupor, as in opium poisoning, and if necessary, artifical respiration. Give cautiously physostigma.
Baryta salts	Give Epsom or Glauber salts or dilute sulphuric acid.
Belladonna, *vide* Atropine.	
Burnett's Disinfecting Fluid, *vide* Metallic Salts.	
Calabar bean	Stimulants. Atropine. Artificial respiration if necessary.
Cannabis Indica	*Vide* Morphine.
Cantharides	Large quantity of demulcent drinks. Barley water. Gruel. Linseed tea. Avoid oils and fats.

Alkalies—*continued.*

Carbolic acid	Saccharated lime. Stimulants.
Cherry laurel water	*Vide* Hydrocyanic Acid.
Chloral	Keep patient warm. Arouse him. Give him coffee per rectum. Liquor strychniæ, 4 minims, subcutaneously, repeated every 10 to 20 minutes, if necessary.
Bichromate of potash	Same as Acids.
Colchicum	Tannic or Gallic acids. Stimulants.
Conium	Tannic acid. Stimulants. Coffee.
Quinia	Tannic or Gallic acids. Strong tea or coffee. Stimulants warmed. Artificial respiration.
Copper	*Vide* Metallic Salts.
Corrosive sublimate	*Vide* Metallic Salts.
Creasote	*Vide* Carbolic Acid.
Croton oil	Demulcents. Stimulants.
Curare	Artificial respiration. If there is a wound, ligature above it if possible, and incise and suck strongly. The ligature should be loosened from time to time, and again tightened, so as not to let too much poison into the blood at once.
Cyanide of potassium	*Vide* Hydrocyanic Acid.
Digitalis	Strong tea. Tannin. Stimulants. Aconite, 5 mins. of the tincture subcutaneously. Keep perfectly quiet, lying in bed.

Alkalies—*continued.*

Ergot	Tannin. Stimulants.
Insect powder	*Vide* Arsenic.
Gelsemium	Atropine. Stimulants. Artificial respiration.
Hyoscyamus	*Vide* Atropine.
Laburnum	Stimulants. Coffee. Alternate hot and cold douches to chest.
Lead	*Vide* Metallic Salts.
Lobelia	Tannin. Stimulants. Strychnia hypodermically (5 mins. liq. strychniæ).
Metallic salts	White of egg freely to form insoluble compound: then wash out stomach to remove it: afterwards demulcents. Poultices to surface, and morphia if necessary.
Morphia	Warm coffee after the stomach is emptied. Ammonia. Arouse by flicking with a towel, or by galvanic battery, and keep awake by walking about and renewal of stimulation if necessary. 2 to 4 mins. liq. atropiæ subcutaneously. Artificial respiration, if necessary.
Mushrooms	2 to 4 mins. liq. atropiæ, subcutaneously: repeat if necessary. Castor oil. Stimulants.
Nitro-benzol Nitrite of Amyl	Stimulants. Alternate douche. Artificial respiration.
Nitro-glycerin	Cold to head. Ergotin. Atropine, subcutaneously.

Oil of Bitter Almonds	*Vide* Hydrocyanic acid.
Opium	*Vide* Morphine.
Phosphorus	Sulphate of copper. Oil of turpentine, old and oxidised. Avoid oils and fats.
Physostigma	Stimulants. Atropine. Chloral. Strychnine. Artificial respiration.
Picrotoxine	Chloral. Bromide of potassium.
Pilocarpine	Atropine.
Rat paste	*Vide* Phosphorus.
Savin	Epsom salts. Demulcents.
Snake-bite	Ligature limb, cut out part with penknife and sear with hot iron. Alcoholic stimulants. Ammonia. Artificial respiration.
Stramonium	*Vide* Atropine.
Strychnia	Chloroform. Tannin. Bromide of potassium. Chloral.
Tobacco	Tannin. Stimulants, warm. Strychnine.
Turpentine (oil of)	Demulcents. Sulphate of magnesia.
Veratrine	Stimulants. Coffee, warm. Recumbent posture

CHAPTER XIX.

ANTAGONISTIC ACTION OF DRUGS.

THE idea that one drug might be made to counteract the deadly effects of another is a very old one, and in the middle ages alexipharmics and mithridates were used as antidotes. Of late years, however, the subject has been investigated experimentally, and a more accurate knowledge of it obtained. Amongst the first of these experimental researches were those of Preyer, on the antagonism of atropine and hydrocyanic acid; of Schmiedeberg and Koppe on the antagonism of muscarine and atropine; and of Fraser on the antagonism between physostigma and atropine.

Although the fact is undisputed that we are occasionally able by the administration of one drug, to prevent the appearance of certain symptoms which would otherwise have certainly been produced by another previously administered, it is by no means certain that the one simply counteracts the effect of the other.

Some regard the effect of one drug in counteracting another as a case of chemical combination or substitution, the second drug either becoming added on to a compound of the first with some of the tissues, or else displacing it from such a compound with the tissues. Others, again, think that no chemical action of this sort takes place, but that each drug acts upon the tissue or tissues by itself, one, for example, exciting and the other paralysing.

In favour of the first view may be mentioned the analogy between the action of poisons and the formation of acid-albumen and alkali-albumen, either of which can be changed into the other by excess of alkali or of acid respectively.

The objection is a very natural one that the doses of alkaloids required to produce marked physiological action are so extremely small that one can hardly fancy any chemical action being the cause of their physiological action. I have, however, on one occasion, by the addition of a single drop of liquor potassæ, converted a milky-looking fluid, consisting of the nuclei of fowl's blood corpuscles suspended in water and measuring 90 cc., into a solid jelly-like mass, a result more striking than if a similar quantity injected into a frog had induced rigor in every muscle. Even such a result is infinitely less delicate than the colour reactions by which alkaloids are detected.

Some of the best-marked examples of antagonism in regard

to involuntary muscular fibre are those observed by Ringer in the frog's heart, and they strongly support the view which he advocates of chemical substitution. As already mentioned, calcium salts and veratrine greatly prolong the cardiac systole; but this prolongation is at once removed, and the systole rendered normal by a small quantity of a potash salt. The salts of potash alone render the systole short and weaker, and then normal, but this action again is neutralised by calcium.

A similar condition has been observed by Cash and myself in the voluntary muscles of the frog. The contraction of the gastrocnemius is prolonged to a slight extent by calcium, and to a great extent by veratrine, and also by barium salts. This contraction is quickly reduced to the normal by the addition of a small quantity of potash.

There is no very well-marked case of antagonism, in which one drug is able to restore power to motor nerves which have been paralysed by another drug; such antagonism, however, has been observed in regard to the vagus. By small doses of atropine this may be paralysed; by a dose of physostigma administered afterwards the inhibitory power may again be restored; and by a further dose of atropine it may be again paralysed. This action has been denied by Rossbach, but in experiments on the subject by myself, I have obtained this effect in such a marked degree that I have no doubt regarding it. It is possible that the different results obtained may be due partly to the animal employed, partly to the dose, partly to the preparations of the drug, and partly to the temperature at which the experiments are made.[1] In my experiments the vagus was irritated, and I ascertained that the stimulation was strong enough to stop the heart. A very small quantity of atropine was then injected, and the same stimulus was repeated. After enough atropine had been gradually injected to abolish the inhibitory action of the vagus completely, some physostigma was then injected into the jugular vein, and the irritation again repeated with the effect of stopping the heart as at first.

The antagonism of certain drugs upon the frog's heart has received much attention. In considering this subject care must be taken to distinguish between experiments made with the ventricle alone, containing involuntary muscular fibres but no ganglia, and the whole heart, in which both muscle and ganglia are contained. The experiments on veratrine, calcium, and potassium, already alluded to, were made with the ventricle alone; those which are now to be considered have reference to the whole heart. Atropine appears to have the power not only of destroying the inhibitory action of the vagus upon the heart, but of antagonising those drugs which inhibit the heart and render its beats slower, or stop them altogether, such as muscarine, physostigma,

[1] My experiments were made on rabbits during the summer. The preparation of physostigma employed was a glycerin extract of the bean, and the preparation of atropine used was the Liquor Atropiæ, B.P.

pilocarpine, and phytolacca. Digitalin and saponin have a mutually antagonistic power, so that when the frog's heart has been stopped by either of them, the other will restore its pulsations. A limited antagonism also exists between muscarine, aconitine, and digitalin; when the heart has been stopped by digitalis, muscarine and aconite will restore its movements. Digitalin will also restore the pulsations in a heart which has been arrested by aconite. Physostigmine, camphor, and other drugs which stimulate the muscular fibre of the heart will remove the still-stand caused by muscarine.

Another very important antagonism is that between drugs acting on the respiratory centre and spinal cord. The mode of action of these drugs is difficult to explain on account of our imperfect knowledge of the physiology of the structures on which they act. Chloral lessens the excitability of these structures, strychnine increases it. These drugs have to a certain extent an antagonistic action, so that a fatal dose of strychnine may be so antagonised by chloral as to prevent death; and a small quantity of strychnine may prevent death from chloral. Atropine has an exciting action on the respiratory centre, somewhat like strychnine though very much less marked; and atropine also will antagonise chloral. It has also an antagonistic action to aconite, which has a peculiar depressing influence on the respiratory centre.

The sedative action of chloral enables it to antagonise picrotoxine which has a stimulant action on the brain causing convulsions. Opium and belladonna have to a certain extent an antagonistic action to one another. The first point which appeared to indicate an antagonistic action was their different effect on the pupil; but probably the point in which they chiefly antagonise one another is their action on respiration, atropine acting as a stimulant and morphine as a depressant to the respiratory centre.

The alkaloids of tea, coffee, and allied substances, viz. theine, or caffeine, cocaine and guaranine, are antagonistic to morphine. These alkaloids in small and moderate doses increase the irritability of the brain, spinal cord, heart, and vaso-motor system, and in large doses paralyse them. Morphine and these alkaloids to a certain extent counteract one another, so that a lethal dose of one may be prevented from causing death by administering the other.

The antagonism of drugs is also marked in regard to their action on the glandular system; thus the excessive salivation produced by physostigma, pilocarpine, and bromal may be arrested by atropine, which also arrests the excessive secretion from the skin caused by pilocarpine, and the secretion from the mucous membrane of the lungs produced by bromal.

The following table shows the most important examples of antagonism. The lethal and antagonistic doses have only been ascertained for a few. When the remark "not antagonistic" occurs in the table, it means that the second drug mentioned will not prevent death from a lethal dose of the first, although the first will prevent death from a lethal dose of the second.

TABLE SHOWING THE ANTAGONISM OF DRUGS.

		Lethal dose.—I.	Lethal dose.—II.	Antidotal doses.
Aconitine . . .	Atropine	$\frac{1}{900}$th	7	$\frac{1}{750}$th.
,,	Digitalin	$\frac{1}{900}$th.	1	$\frac{1}{600}$th.
,,	Strychnine	$\frac{1}{900}$th.	$\frac{1}{288}$th	$\frac{1}{750}$
Alcohol	Strychnine	—	$\frac{1}{288}$th.	
Ammonium chloride . .	Chloral	—		
Atropine . . .	Aconitine	7	$\frac{1}{900}$th.	not antagonistic
,,	Bromal-hydrate . .	7	$1\frac{1}{4}$	not antagonistic
,,	Chloral-hydrate . .	7	7	
,,	Hydrocyanic acid . .	7		
,,	Jaborandi	7		
,,	Muscarine	7		
,,	Morphine	7	3	not antagonistic
,,	Physostigmine . . .	7	$\frac{1}{25}$	
,,	Phytolacca	7		
,,	Pilocarpine	7		
,,	Quinine	7		
Barium	Sodium sulphate . .			
,,	Potash salts			
Bromal-hydrate	Atropine	$1\frac{1}{4}$	7	
Brucine	Chloral			
Calabarine . . .	Chloral			
Carbolic acid . .	Chloral			
Chloral . . .	Ammonium chloride.			
,,	Atropine			
,,	Brucine			
,,	Calabarine			
,,	Carbolic acid			
,,	Codeine			
,,	Physostigma			
,,	Picrotoxine			
,,	Strychnine			
,,	Thebaine			
Chloroform . .	Amyl nitrite			
Cocaine	Morphine			
Codeine	Chloral			
Digitalin . . .	Aconitine			
,,	Muscarine			
,,	Saponin			
Gelsemium . .	Opium			
,,	Atropine			
Morphine . . .	Atropine			
,,	Caffeine			
,,	Chloroform			
,,	Cocaine			
,,	Daturine			
,,	Hyoscyamine . . .			
,,	Nicotine			
,,	Physostigma			
Muscarine . . .	Atropine			
Opium . . .	Atropine			
,,	Gelsemium			
,,	Veratrum viride . .			
Physostigma . .	Atropine			
,,	Chloral			
,,	Morphine			
Saponin	Digitalin			
Strychnin . . .	Alcohol			
,,	Chloral			
,,	Hydrocyanic acid . .			
,,	Nicotine			
,,	Nitrite of amyl . .			
Thebaine . . .	Chloral			

CHAPTER XX.

DOSAGE.

THE circumstances which affect dosage have already been discussed (p. 28). In practice we reckon the dose according to age, making allowances, however, for the size and sex of the patient. Various tables have been drawn up for this purpose. One in common use is Dr. Young's. It is to convert the age into a fraction by adding twelve to it and using the number thus obtained as the denominator, the age itself being the numerator. Thus, if a child's age be three years, the denominator will be $3 + 12 = 15$, and the numerator will be 3. The dose for the child will therefore be $\frac{3}{3+12} = \frac{3}{15} = \frac{1}{5}$ of that for an adult. For a child five years old it will be $\frac{5}{5+12} = \frac{5}{17}$, which is between one-third and one-fourth of that for an adult. If the child is large for its years, we would give one-third; if small, we would rather give one-fourth.

Another rule, proposed by Dr. Cowling, is to divide the number of the patient's *next* birthday by twenty-four. Thus, for a child three years old, the fraction representing the dose would be $\frac{4}{24} = \frac{1}{6}$; for a child five years old, $\frac{6}{24} = \frac{1}{4}$.

The rule which I should propose as being more convenient for the metric system is a modification of Dr. Cowling's. If we assume that the body has attained its full growth at twenty-five years of age instead of twenty-four, we get the proportion by dividing the number of the next birthday by twenty-five. Thus, for a child three years of age, the proportion would be $\frac{4}{25}$ = nearly $\frac{1}{6}$; for a child five years of age, $\frac{6}{25}$ = between $\frac{1}{5}$ and $\frac{1}{4}$. This number does not lend itself readily to fractions such as the preceding, but it is very easy to divide by twenty-five by simply multiplying by four and dividing by 100. When the metrical system is used, all that is necessary is to multiply the full dose by the number of the child's next birthday, then by four, and remove the decimal point two places to the left. Thus, if the full dose for an adult be 1 gramme, the dose for a child of three will be $\frac{1 \times 4 \times 4}{100} = \cdot 160$ gramme or 16 centigrammes. If the full dose for an adult be ·3 gramme, the dose for a child of three will be $\frac{\cdot 3 \times 4 \times 4}{100} = \cdot 048$, or 48 milligrammes. If the full dose be 1 gramme, the dose for a child of five will be $\frac{1 \times 6 \times 4}{100} = \cdot 240$ gramme or 24 centigrammes. If the full dose be ·3 gramme, the dose for a child of five will be $\frac{\cdot 3 \times \text{grm.} \times 6 \times 4}{100} = \cdot 072$ gramme or 72 milligrammes. To put it more shortly, the number of grammes in the full dose multiplied by the child's next birthday and by four, gives the result in centigrammes. The number of decigrammes multiplied in the same way gives the result in milligrammes.

SECTION II.

GENERAL PHARMACY.

CHAPTER XXI.

PHARMACEUTICAL PREPARATIONS.

PHARMACY includes both the general preparation of drugs from crude natural products and their combinations with other substances, so as to render them either more effectual or more easily administered.

The great rule for the administration of medicines is (1) *curare*, (2) *cito*, (3) *tute, et* (4) *jucunde*—that they shall not only (1) cure, but that they shall do so (2) quickly, (3) safely, and (4) pleasantly. According to this rule many prescriptions contain four ingredients, viz.: (1) the substance which is to cure, or the *basis*; (2) the *adjuvant* to help it; (3) the *corrective* to prevent any bad effects; and (4) the *vehicle* to make it pleasant to take. This rule, however, is carried out not only in written prescriptions, but in those also which have been adopted by the profession at large, as a means of saving labour and time in the routine of practice, and embodied in the Pharmacopœia as useful preparations.

Formerly we were dependent for our medicines chiefly on the crude products of the animal, vegetable, and mineral kingdoms. As chemistry advanced various inorganic compounds were discovered and added to the Materia Medica, and as our knowledge of this science becomes greater and our power of preparing various organic bodies increases, we find that such bodies are becoming more and more introduced into medicine. As examples of these, we may take carbolic acid, chloral, chloroform, ether, hydrocyanic acid, iodoform, nitrite of amyl, salicylic acid, and kairin.

We seem now on the verge of discovering the mode of preparation of many organic alkaloids, and when this has been done, the vegetable Materia Medica will be less important than it is now, inasmuch as it is probable that, by using artificial alkaloids, prepared always under similar conditions, we may obtain purer products and greater constancy of action than we can at present from the natural active principles.

Recent discoveries have shown that plants generally contain active principles so closely associated, that the mixture was

regarded as a pure alkaloid, and yet these drugs have very different and sometimes opposite physiological actions. Thus ordinary conïne usually contains pure conïne and methyl-conïne, the former of which paralyses the motor nerves, while the latter paralyses the spinal cord. Extract of physostigma, and supposed pure physostigmine, or eserine, have been found to contain two active principles, viz. physostigmine having a paralysing action, and calabarine having a tetanising action on the spinal cord.

The power which chemistry now gives us also of modifying the chemical constitution of organic bodies and therewith their physiological action, will almost certainly enable us to treat disease much more perfectly than we can at present. For such modified drugs, however, we must be indebted to the chemist. He will prefer to operate on substances which have been already prepared by himself rather than on crude drugs obtained from plants. But at present we are still dependent on the vegetable kingdom for a large number of our most useful remedies. In plants they are associated as a rule with quantities of woody tissue which is quite inert and indigestible, and which would interfere very much both with their easy administration and with their action.

Sometimes the crude drug is given in the form of a simple **powder,** without any admixture, as in the case of guaiac given in tonsillitis, where it is advisable to have the local action of the drug on the throat, as well as its general action on the system. Sometimes the powder may be readily given, by enveloping it in a **wafer,** and swallowing it with a little water, and at other times it is made up with saccharine, and more or less adhesive substances, into the form of a **confection** or **bolus;** or suspended in water by means of mucilage in the form of a **mixture.** Usually however the active parts of the drug are extracted by means of solvents, and either given in solution, or in the solid form, after the solvents have been evaporated. There are a number of preparations according to the solvents used, and the mode in which they are applied. Probably the most convenient arrangement is not to take the groups of preparations according to the solvents or mode of preparation, but alphabetically for the sake of reference.

The letters B.P. stand for the British Pharmacopœia of 1874, and U.S.P. for the United States Pharmacopœia of 1883. When the letters B.P. or U.S.P. *precede* the name of a class or of a substance, they indicate that it is contained in the corresponding pharmacopœia only, but not in the other. They succeed the name or are omitted when the class or substance occurs in both pharmacopœias. When there are differences between things bearing the same name in the British and United States Pharmacopœias, the letters B.P. are placed after the descriptions of that contained in the British, and U.S.P. after that of the United States Pharmacopœia.

U.S.P. Abstracta. ABSTRACTS.—These are dry powdered extracts. They are twice the strength of the crude drug, and about twice the strength of the corresponding fluid extracts. They are prepared by extracting the active principles from 200 parts of the crude drug by percolation with the strong or diluted alcohol, mixing the percolate with some sugar of milk, letting it dry, and then adding sufficient sugar of milk to make up the product to 100 parts. They are eleven in number.

	Dose.		Dose
Abstractum Aconiti	¼-1 gr.	Abstractum Ignatiæ	½-1½ gr.
,, Belladonnæ ...	½-1 gr.	,, Jalapæ	5-15 grs.
,, Conii	1-3 grs.	,, Nucis Vomicæ.	½-2 grs.
,, Digitalis	½-1 gr.	,, Podophylli ...	5-10 grs.
,, Hyoscyami ...	2-3 grs.	,, Senegæ	1-3 grs.
		,, Valerianæ	10-20 grs.

Aceta. VINEGARS. — These are solutions of medicines in vinegar or acetic acid. In the B.P. there are three, in the U.S.P. there are four.

B.P.	Dose.	U.S.P.	Dose.
Acetum		Acetum Lobeliæ	30-60 min.
,, Cantharidis		,, Opii	10-15 min.
,, Scillæ	15-60 min.	,, Sanguinariæ	3-4 fluid dr.
		,, Scillæ	15-60 min.

Alkaloidea. ALKALOIDS.—These are organic bases which may be regarded as compound ammonias.

Like ammonia they all contain nitrogen, and form salts with acids. Most of them contain oxygen in addition to nitrogen, carbon, and hydrogen, and occur as crystalline solids. Some, *e.g.* coniine, nicotine, sparteine, contain no oxygen, and occur as oily liquids. They generally have a powerful physiological action. They occur in many exogenous plants, but only veratrine and substances nearly allied to it have been obtained from the class of endogens and muscarine from thallogens. They occur in the plants in combination with acids. The alkaloids themselves are generally soluble in alcohol, but sparingly soluble in water. Their salts are more soluble in water. The general plan of preparing them is to precipitate them by ammonia from an aqueous solution either of the salt originally present in the plant, or of one formed by treatment with an acid. In the B.P. the names of alkaloid all terminate in "ia," like ammonia, *e.g.* quinia, strychnia. Neutral principles have the termination "in," *e.g.* santonin, digitalin. Chemists have now generally returned to the older nomenclature, and assign the termination "ine" to alkaloids, *e.g.* strychnine, quinine. To neutral principles they give the termination "in," *e.g.* santonin, digitalin. This terminology has been followed in the U.S.P.

B.P.	U.S.P.
Aconitia (Aconitia).	Apomorphina (Apomorphine).
Atropia (Atropia).	Atropina (Atropine).
Beberiæ Sulphas (Sulphate of Beberia).	Caffeina (Caffeine).
Morphiæ Hydrochloras (Hydrochlorate of Morphia).	Cinchonidinæ Sulphas (Sulphate of Cinchonidine).
Quiniæ Sulphas (Sulphate of Quinia).	Cinchonina (Cinchonine).
Strychnia (Strychnia).	Codeina (Codeine).
Veratria (Veratria).	Hyoscyaminæ Sulphas (Sulphate of Hyoscyamine).
	Morphina (Morphine).
	Physostigminæ Salicylas (Salicylate of Physostigmine).
	Pilocarpinæ Hydrochloras (Hydrochlorate of Pilocarpine).
	Peperina (Peperine).
	Quinidinæ Sulphas (Sulphate of Quinidine).
	Quinina (Quinine).
	Strychnina (Strychnine).
	Veratrina (Veratrine).

Chinoidinum (Chinoidin or Quinoidin), U.S.P., is a mixture of bases.

Along with the alkaloids may be mentioned several **neutral principles** which resemble alkaloids in having a powerful physiological action,

B.P.	U.S.P.
Digitalinum (Digitalin).	Chrysarobinum (Chrysarobin).
Santoninum (Santonin).	Picrotoxinum (Picrotoxin).
	Salicinum (Salicin).
	Santoninum (Santonin).

Aquæ. WATERS. (15 in B.P. and U.S.P.).—One is simply water, another distilled water. The others in the B.P. are water containing small quantities of volatile oils in solution, with the exception of two, aquæ chloroformi and aquæ laurocerasi, which contain chloroform and prussic acid respectively instead of a volatile oil. Two waters are prepared by simply dissolving the substances in them in the cold; these are aqua camphoræ and aqua chloroformi. All the rest are prepared by distillation. Two are prepared by distilling the volatile oils with water; these are peppermint and spearmint waters. All the rest are prepared by distilling the plant in a retort with water and continuing the process until a certain quantity is distilled over.

In the U.S.P. aqua ammoniæ, aqua ammoniæ fortior, and aqua chlori consist of solutions of ammoniacal and chlorine gases in water. One, the aqua creasoti, consists of a solution of one part of creasote in 100 of water.

The others consist of volatile oils in water. Only two, aqua aurantii florum and aqua rosæ, are prepared by distilling the flowers with water. The others are prepared by thoroughly distributing the requisite quantity of volatile oil through a quantity of cotton,

and dissolving it in water, by allowing the latter to percolate through. Camphor is dissolved in alcohol before adding it to the cotton.

Waters are chiefly **used** as vehicles.

The **dose** of all those in the B.P. with one exception is from half an ounce to two ounces. This exception is aquæ laurocerasi, which is not used as a vehicle, but is on the contrary a powerful drug containing hydrocyanic acid, and the dose of it is very small, 5—30 minims.

Aqua anethi is a favourite remedy for flatulence in children, and in them it is given in a dose of a teaspoonful or more.

B.P. (15).	DOSE.
Aqua	
,, Destillata	
,, Anethi	½–2 oz.
,, Aurantii Floris	,,
,, Camphoræ	,,
,, Carui	,,
,, Chloroformi	,,
,, Cinnamomi	,,
,, Fœniculi	,,
,, Laurocerasi	5-30 minims.
,, Menthæ Piperitæ	½–2 oz.
,, Menthæ Viridis	,,
,, Pimentæ	,,
,, Rosæ	,,
,, Sambuci	,,

U.S.P. (15).	DOSE.
Aqua	
,, Destillata	
,, Ammoniæ	10–30 minims.
,, Ammoniæ Fortior	
,, Amygdalæ Amaræ	2 drachms.
,, Anisi	½–2 oz.
,, Aurantii Florum	,,
,, Camphoræ	,,
,, Chlori	,,
,, Cinnamonii	½–2 fluid oz.
,, Creasoti	1–4 drachms.
,, Fœniculi	1–2 fluid oz.
,, Menthæ Piperitæ	,,
,, Menthæ Viridis	,,
,, Rosæ	,,

B.P. Cataplasmata. CATAPLASMS OR POULTICES. (6.)—These are used as a means of applying externally moisture and warmth, and in certain cases medicaments, to parts of the body. They consist of linseed meal or of bread crumb, made into a paste with hot water. In one, cataplasma conii, hemlock leaf is added to relieve pain; in another, cataplasma sinapis, mustard is used to stimulate the skin; and in the cataplasma carbonis, cataplasma fermenti, and cataplasma sodæ chloratæ, wood charcoal, yeast, and chlorinated soda respectively, are added for the purpose of removing fœtor or acting as disinfectants.

Cataplasma Carbonis.
,, Conii.
,, Fermenti.
,, Lini.
,, Sinapis.
,, Sodæ Chloratae.

U.S.P. Cerata. CERATES.—These are ointments containing wax. The admixture of wax with oil or lard in cerates renders them harder than ointments, though they are softer than plasters. They can be spread on linen or leather, at ordinary temperatures without requiring heat like plasters, and they can be applied to the skin without melting and running like ointments.

U.S.P.

Ceratum.
,, Camphoræ.
,, Cantharidis.
,, Cetacei.
,, Extracti Cantharidis.
,, Plumbi Subacetatis.
,, Resinæ.
,, Sabinæ.

Chartæ. PAPERS.—Charta epispastica or cantharidis, and charta sinapis consist of irritating substances spread upon paper, and used for the purpose of producing rubefaction or vesication. Charta potassii nitratis consists of bibulous paper soaked in a solution of nitrate of potash and dried, and is used for burning to give relief in asthma by inhalation of the fumes.

B.P. (2).

Charta Epispastica.
,, Sinapis.

U.S.P. (3).

Charta Cantharidis.
,, Potassii Nitratis.
,, Sinapis.

Collodia. COLLODIONS.—In these collodion is used as a solvent and means of application.

B.P.

Collodium.
,, Flexile.

U.S.P.

Collodium.
,, cum Cantharide.
,, Flexile.
,, Stypticum.

Confectiones. CONFECTIONS, ELECTUARIES OR CONSERVES.—These are soft pastes which contain the drug mixed with sugar or honey, and are convenient forms of administering drugs, which would be unpleasant to take alone, and would be too bulky for pills. In two of them, the confection of dog roses, and of red roses, the drug is of itself inert, and the confection is used only as a vehicle; in the others, the drug is active, and the confection is used as a mode of administering it. The dose of all is 1 to 2 drachms, with the exception of the confection of opium (B.P.) and of scammony (B.P.).

B.P. (8).	DOSE.	U.S.P. (2).	DOSE.
Confectio Opii	5–20 grs.	Confectio Rosæ.	
,, Piperis		,, Sennæ	1-2 dr.
,, Rosæ Caninæ			
,, Rosæ Gallicæ			
,, Scammonii	10–30 grs.		
,, Sennæ			
,, Sulphuris			
,, Terebenthinæ			

Decocta. DECOCTIONS.—These are made by boiling the drug with water, and then straining while hot. Usually the boiling is continued from ten to twenty minutes, in order to dissolve out the active part of the drug; prolonged boiling, frequently alters it, and may render it inert.

B.P. (14).	DOSE.
Decoctum Aloes Compositum.	½-1 fl. oz.
,, Cetrariæ	ad lib.
,, Cinchonæ Flavæ	1-2 fl. oz.
,, Granati Radicis	,,
,, Hæmatoxyli	,,
,, Hordei	ad lib.
,, Papaveris	for external use.
,, Pareiræ	1-2 fl. oz.
,, Quercus	,,
,, Sarsæ	2-10 fl. oz
,, Sarsæ Compositum	,,
,, Scoparii	2-4 fl. oz.
,, Taraxaci	,,
,, Ulmi	,,

U.S.P. (2).	DOSE.
Decoctum Cetrariæ	ad lib.
,, Sarsaparillæ Compositum	4-6 fl. oz.

U.S.P. Elixiria. ELIXIRS.—These are diluted tinctures rendered agreeable by aromatics and sugar. The only one in the U.S.P. is used as a vehicle.

U.S.P. (1).

Elixir Aurantii (Simple Elixir).

Emplastra. PLASTERS.—These consist of adhesive substances spread upon leather or cloth, so as to stick to the part of the body to which they are applied.

Lead plaster is one of the most important, as it forms a basis for other plasters. It is also used for covering slight wounds and excoriations. Resin plaster is more adhesive, and is used to hold the edges of wounds together and to apply pressure. Two others, emplastrum belladonnæ and emplastrum opii, contain narcotic substances with the intention of lessening pain locally. The others are used for the purpose of affording mechanical support or gentle stimulation, and emplastrum cantharidis (B.P.) is used as a vesicant.

B.P. (14).
Emplastrum Ammoniaci cum Hydrargyro.
,, Belladonnæ.
,, Calefaciens (warming).
,, Cantharidis.
,, Cerati Saponis.
,, Ferri.
,, Galbani.
,, Hydrargyri.
,, Opii
,, Picis.
,, Plumbi.
,, ,, Iodidi.
,, Resinæ.
,, Saponis.

U.S.P. (17).
Emplastrum Ammoniaci (Ammoniac).
,, ,, c. Hydrargyro (ammoniac with mercury).
,, Arnicæ (Arnica).
,, Asafœtidæ (Asafœtida).
,, Belladonnæ (Belladonna).
,, Capsici (Capsicum).
,, Ferri (Iron).
,, Galbani (Galbanum).
,, Hydrargyri (Mercurial).
,, Icthyocollæ (Court).
,, Opii (Opium).
,, Picis Burgundicæ (Burgundy pitch).
,, Picis Canadensis (Hemlock pitch).
,, Picis cum Cantharide (warming).
,, Plumbi (Diachylon).
,, Resinæ (adhesive).
,, Saponis (soap).

B.P. Enemata. INJECTIONS, ENEMAS, OR CLYSTERS.—These are preparations for injection into the rectum. When the quantity injected is large, and especially if cold, it is usually returned almost immediately; therefore, when we wish to get it retained, a small quantity only, and warm, must be employed. The vehicle in most injections is starch mucilage. In the enema of aloes 10 ounces, and in those of Epsom salts and of turpentine, 15 ounces of the vehicle are used, and these enemata are employed for the purpose of evacuating the bowel. In the case of the enema opii which we wish to be retained the quantity is only 2 ounces. This is used both as a local and general sedative, in order to relieve pain in or about the pelvis, or to produce the general action of opium after its absorption, in cases where medicines cannot be retained by the stomach, or when it is inadvisable to administer them by the mouth. The enema asafœtidæ is perhaps the most powerful remedy we possess in cases of tympanitic distension of the bowels. As it is used for the purpose of exciting the contraction of the bowels and the expulsion of flatulence, but not of simply evacuating the rectum, an intermediate quantity is used, viz. 4 ounces. Asafœtida contains a gum as well as a resin, and therefore no mucilage is required to suspend it, and water only is required in preparing it.

The enema of tobacco is now rarely used on account of the danger from collapse; but formerly, before the introduction of chloroform, it was frequently employed in order to cause muscular relaxation and aid in the reduction of hernia.

B.P. (6).	NONE IN U.S.P.
Enema Aloes (aloes 40 grains, carbonate of potash 15 grains).	
,, Magnesiæ Sulphatis (sulphate of magnesia 1 oz., olive oil 1 fl. oz.).	
,, Opii (tincture of opium ½ fl. dr.).	
,, Terebinthinæ (oil of turpentine 1 fl. oz.).	
,, Asafœtidæ (asafœtida 30 gr., water 4 fl. oz.).	
,, Tabaci (leaf tobacco 20 gr., water 8 fl. oz.).	

B.P. Essentiæ. ESSENCES.—These are strong solutions of 1 part volatile oil in 4 of rectified spirit. They are used as carminatives, and are usually given in the form of a few drops on a piece of lump sugar, or with a little hot sugar and water, in order to remove flatulence.

B.P. (2).	DOSE.
Essentia Anisi.....	10-20 m.
,, Menthæ Piperitæ	10-20 m.

Extracta. EXTRACTS.—Extracts consist of the soluble parts of plants reduced to the consistence of a thick paste by extraction and evaporation. The plan of treatment adopted in order to extract the soluble parts, and leave behind the woody fibre and other inert constituents varies, according as the plant is fresh or dry.

From fresh plants, green extracts (B.P.) are obtained by evaporation of the fresh juice after removal of the coaguiable

albumen. From dried plants the active principles are removed by treatment with cold or boiling water, with spirit, ether, or acetic acid, and the solutions thus obtained are evaporated to a consistence suitable for making pills, or else to dryness.

Where the active principles are of a resinous or alkaloidal nature, and are more soluble in pure, than in dilute spirit, alcohol or rectified spirit is used; in other cases dilute alcohol or proof spirit is employed. Where the drug contains more than one active substance and one is more soluble in spirit, and the other in water, both spirit and water are used. In order to prevent extracts which, when freshly prepared are of a proper consistence for making pills, from becoming too dry and hard by keeping, the U.S.P. in several instances directs them to be mixed with 5 per cent. of glycerine.

B.P. (29).	DOSE.
Extractum Aconiti	1-2 gr.
,, Aloes Barbadensis	2-6 gr.
,, ,, Socotrinæ	,,
,, Anthemidis	2-10 gr.
,, Belladonnæ	$\frac{1}{4}$-1 gr.
,, Calumbæ	2-10 gr.
,, Cannabis Indicæ	$\frac{1}{4}$-1 gr.
,, Colchici	$\frac{1}{2}$-2 gr.
,, ,, Aceticum	,,
,, Colocynthidis Compositum	3-10 gr.
,, Conii	2-6 gr.
,, Gentianæ	2-10 gr.
,, Glycyrrhizæ	10-30 gr.
,, Hæmatoxyli	,,
,, Hyoscyami	5-10 gr.
,, Jalapæ	5-15 gr.
,, Krameriæ	5-20 gr.
,, Lactucæ	5-15 gr.
,, Lupuli	,,
,, Mezerei Æthereum	
,, Nucis Vomicæ	$\frac{1}{2}$-2 gr.
,, Opii	,,
,, Papaveris	2-5 gr.
,, Pareiræ	10-20 gr.
,, Physostigmatis	$\frac{1}{16}$-$\frac{1}{4}$ gr.
,, Quassiæ	3-5 gr.
,, Rhei	5-15 gr.
,, Stramonii	$\frac{1}{4}$-$\frac{1}{2}$ gr.
,, Taraxaci	5-30 gr.

U.S.P. (31).	DOSE.
Extractum Aconiti	$\frac{1}{6}$-$\frac{1}{4}$ gr.
,, Aloes Aquosum	2-10 gr.
,, Arnicæ Radicis	3-5 gr.
,, Belladonnæ Alcoholicum	$\frac{1}{4}$ gr.
,, Cannabis Indicæ	,,
,, Cinchonæ	10-30 gr.
,, Colchici Radicis	1-2 gr.
,, Colocynthidis	$\frac{1}{2}$-1 gr.
,, ,, Compositum	5-30 gr.
,, Conii Alcoholicum	$\frac{1}{2}$-1 gr.
,, Digitalis	$\frac{1}{4}$ gr.
,, Ergotæ	5-15 gr.
,, Euonymi	1-3 gr.
,, Gentianæ	10-30 gr.
,, Glycyrrhizæ Purum	
,, Hæmatoxyli	10-30 gr.
,, Hyoscyami Alcoholicum	1-2 gr.
,, Iridis	1-2 gr.
,, Juglandis	5-10 gr.
,, Krameriæ	10-20 gr.
,, Leptandræ	20-30 gr.
,, Malti	1-4 dr.
,, Mezerei	
,, Nucis Vomicæ	$\frac{1}{2}$-2 gr.
,, Opii	$\frac{1}{2}$-1 gr.
,, Podophylli	1-3 gr.
,, Physostigmatis	$\frac{1}{16}$-$\frac{1}{8}$ gr.
,, Quassiæ	1-2 gr.
,, Rhei	5-10 gr.
,, Stramonii	$\frac{1}{4}$-$\frac{1}{2}$ gr.
,, Taraxaci	20-60 gr.

Fluid U.S.P. OR **Liquid B.P. Extracts.**—These are made like watery extracts, excepting that instead of evaporating the infusion, decoction, or alcoholic solution (U.S.P.) to a solid paste, it is only reduced to a small bulk, and in the B.P. some spirit is added to it in order to prevent decomposition.

B.P. (8).		DOSE.
Extractum Belæ Liquidum		1-2 fluid drachms.
,, Cinchonæ Flavæ Liquidum		10-30 minims.
,, Ergotæ	,,	10-30 minims.
,, Filicis	,,	15-60 minims.
,, Glycyrrhizæ	,,	60-120 minims.
,, Opii	,,	10-40 minims.
,, Pareiræ	,,	½-2 fluid drachms.
,, Sarsæ	,,	2-4 fluid drachms.

U.S.P. (79).		DOSE.
Extractum Aconiti Fluidum		½-1 m. (0·03-0·06 c.c.)
,, Arnicæ Radicis Fluidum		5-10 m. (0·3-0·6 c.c.)
,, Aromaticum	,,	10-20 m. (0·6-1·25 c.c.)
,, Aurantii Amari	,,	15-30 m. (0·9-1·9 c.c.)
,, Belladonnæ	,,	1-2 m. (0·06-0·12 c.c.)
,, Brayeræ	,,	½-1 fl. oz. (15-30 c.c.)
,, Buchu	,,	30-60 m. (1·9-3·8 c.c.)
,, Calami	,,	5-15 m. (0·3-0·9 c.c.)
,, Calumbæ	,,	15-30 m. (0·9-1·9 c.c.)
,, Cannabis Indicæ	,,	½-1 m. (0·03-0·06 c.c.)
,, Capsici	,,	½-1 m. (0·03-0·06 c.c.)
,, Castaneæ	,,	1-2 fl. dr. (3·75-7·5 c.c.)
,, Chimaphilæ	,,	1 fl. dr. (3·75 c.c.)
,, Chiratæ	,,	½ fl. dr. (1·9 c.c.)
,, Cimicifugæ	,,	½-1 fl. dr. (1·9-3·75 c.c.)
,, Cinchonæ	,,	¼-2 fl. oz. (7·5-60 c.c.)
,, Colchici Radicis	,,	2-8 m. (0·12-0·5 c.c.)
,, Colchici Seminis	,,	2-8 m. (0·12-0·5 c.c.)
,, Conii	,,	5 m. (0·3 c.c.)
,, Cornus	,,	30 m. (1·9 c.c.)
,, Cubebæ	,,	10-40 m. (0·6-2·5 c.c.)
,, Cypripedii	,,	15 m. (0·9 c.c.)
,, Digitalis	,,	1-2 m. (0·06-0·12 c.c.)
,, Dulcamaræ	,,	30-60 m. (1·9-3·75 c.c.)
,, Ergotæ	,,	½-4 fl. dr. (1·9-15 c.c.)
,, Erythroxyli	,,	20-60 m. (1·25-3·75 c.c.)
,, Eucalypti	,,	5-10 m. (0·3-0·6 c.c.)
,, Eupatorii	,,	20-60 m. (1·25-3·75 c.c.)
,, Frangulæ	,,	10-20 m. (0·6-1·25 c.c.)
,, Gelsemii	,,	2-3 m. (0·12-0·18 c.c.)
,, Gentianæ	,,	10-30 m. (0·6-1·9 c.c.)
,, Geranii	,,	30-60 m. 1·9-3·75 c.c.
,, Glycyrrhizæ	,,	30-120 m. (1·9-7·5 c.c.)
,, Gossypii Radicis	,,	30-60 m. (1·9-3·75 c.c.)
,, Grindeliæ	,,	30-60 m. (1·9-3·75 c.c.)
,, Guaranæ	,,	1-2 fl. dr. (3·75-7·5 c.c)
,, Hamamelidis	,,	30 m. (1·9 c.c.)
,, Hydrastis	,,	1-2 fl. dr. (3·75-7·5 c.c.)
,, Hyoscyami	,,	5 m. (0·3 c.c.)
,, Ipecacuanhæ	,,	15-30 m. (0·9-1·9 c.c.)
,, Iridis	,,	5-10 m. (0·3-0·6 c.c.)
,, Krameriæ	,,	10-60 m. (0·6-3·75 c.c)
,, Lactucarii	,,	5-30 m. (0·3-1·9 c.c.)
,, Leptandræ	,,	20-60 m. (1·25-3·75 c.c.)
,, Lobeliæ	,,	10-20 m. (0·6-1·25 c.c.)
,, Lupulini	,,	10-15 m. (0·6-0·9 c.c.)
,, Maticæ	,,	30-60 m. (1·9-3·75 c.c.)
,, Mezerei	,,	for external use.
,, Nucis Vomicæ	,,	3-5 m. (0·18-0·3 c.c.)
,, Pareiræ	,,	1-2 fl. dr. (3·75-7·5 c.c.)

U.S.P.			DOSE.
Extractum	Pilocarpi	Fluidum	15-30 m. (0·9-1·9 c.c.)
,,	Podophylli	,,	5-15 m. (0·3-0·9 c.c.)
,,	Pruni Virginianæ	,,	30-60 m. (1·9-3·75 c.c.)
,,	Quassiæ	,,	5 10 m. (0·3-0·6 c.c.)
,,	Rhei	,,	5-30 m. (0·3-1·9 c.c.)
,,	Rhois Glabræ	,,	for external use.
,,	Rosæ	,,	1-2 fl. dr. (3·75-7·5 c.c.)
,,	Rubi	,,	½-1 fl. dr. (1·9-3·75 c.c.)
,,	Rumicis	,,	1 fl. dr. (3·75 c.c.)
,,	Sabinæ	,,	3-8 m. (0·18-0·5 c.c.)
,,	Sanguinariæ	,,	3-5 m. (0·18-0·3 c.c.)
,,	Sarsaparillæ	,,	2-4 fl. dr. (7·5-15 c.c.)
,,	Sarsaparillæ Compositum	Fluidum	30-60 (1·9-3·75 c.c.)
,,	Scillæ	,,	1-3 m. (0·12-0·18 c.c.)
,,	Scutellariæ	,,	30-60 m. (1·9-3·75 c.c.)
,,	Senegæ	,,	1-5 m. (0·06-0·3 c.c.)
,,	Sennæ	,,	1-4 fl. dr. (3·75-15 c.c.)
,,	Serpentariæ	,,	20-30 m. (1·25-1·9 c.c.)
,,	Spigeliæ	,,	1-2 fl. dr. (3·75-7·5 c.c.)
,,	Stillingiæ	,,	15-45 m. (0·9-2·8 c.c.)
,,	Stramonii	,,	1-2 m. (0·06-0·12 c.c.)
,,	Taraxaci	,,	1-3 fl. dr. (3·75-11·25 c.c.)
,,	Tritici	,,	3-6 fl. dr. (11·25-22·5 c.c.)
,,	Uvæ Ursi	,,	30-60 m. (1·9-3.75 c.c.)
,,	Valerianæ	,,	1 fl. dr. (3·75 c.c.)
,,	Veratri Viridis	,,	1-2 m. (0·06-0·12 c.c.)
,,	Viburni	,,	30-60 m. (1·9-3·75 c.c.)
,,	Xanthoxyli	,,	30-60 m. (1·9-3·75 c.c.)
,,	Zingiberis	,,	10-20 m. (0·6-1·25 c.c.)

B.P. Fresh or Green Extracts.—These extracts have already been enumerated among the others. In preparing them, the juice obtained from the fresh leaves, flowering tops or fruits, of the plant, by pressure, is heated to 130° F. to coagulate the green colouring matter. This is then filtered off and laid aside. The filtrate is next heated to 200° so as to coagulate the albumen; this is filtered out and thrown away. The filtrate is then evaporated at a temperature not exceeding 140° to a thin syrup. The colouring matter is then added to it, and the whole evaporated to a proper consistence. In the case of extracts of colchicum and taraxacum there is no chlorophyll to separate, as the juices are obtained by expression from the colchicum corm and the taraxacum root, and not from flowering tops. Consequently the juice is at once heated to the boiling point to coagulate the albumen, and after this has been filtered out the filtrate is evaporated at a temperature of 160°. In the case of green extracts, the preservation of the green colour is usually regarded as a sign that they are good. It certainly indicates that the first and the last parts of the process have been conducted with care, as too high a temperature destroys the green colour. It is therefore probable that the whole process may have been carefully done; but this is not certain, for the juice may have been exposed to a high temperature, and thus injured during its evaporation after the chlorophyll has been removed and before it has been again added.

The green extracts of the B.P. are (8) :—

Extractum Aconiti.	Extractum Colchici Aceticum.	Extractum Lactucæ.
,, Belladonnæ.	,, Conii.	,, Taraxaci.
,, Colchici.	,, Hyoscyami.	

Glycerina, B.P. ; Glycerita, U.S.P. GLYCERINES.—These are solutions of soothing, astringent, or antiseptic substances in glycerine. Glycerine being thick and adhesive, they form most useful local applications, either to the skin or mucous membranes.

Those in the B.P. contain one part of the drug by weight to four of glycerine by measure, excepting in the case of starch, which being very light and bulky, is used in only half this proportion, *i.e.* one ounce of starch to eight ounces of glycerine. In the U.S.P. the starch is in the proportion of 1 to 9, *i.e.* 10 per cent. The glyceritum vitelli contains 45 parts fresh yolk of egg to 55 of glycerine.

B.P. (6).	U.S.P. (3).
Glycerinum.	Glycerinum.
,, Acidi Carbolici.	Glyceritum Amyli.
,, ,, Gallici.	,, Vitelli.
,, ,, Tannici.	
,, Amyli.	
,, Boracis.	

Infusa. INFUSIONS.—These are prepared by simply pouring boiling water on the drug and allowing it to stand for a short time and then straining.

There are two exceptions to this rule, calumba and quassia, which are prepared with cold water. The reason for using cold water in the case of calumba is that the root contains a quantity of starch, and if hot water be used, this is extracted and renders the infusion liable to decompose, especially in hot weather.

I have been unable to find any definite reason assigned for using cold water in the preparation of infusion of quassia, excepting that cold water is sufficient to dissolve the active principle.

In the only instance in which I have seen an infusion made with hot water used, it caused vomiting, so that perhaps an infusion made with hot water has a more irritating action than that made with cold.

Infusions of chiretta and cusparia are made with water at 120° instead of boiling water, as they are more agreeable when prepared in this way.

The infusions of substances not specified in the U.S.P. are directed by it to be prepared by taking ten parts of the substance in coarse powder and 100 of boiling water. These are to be put into a vessel with a tight cover, and allowed to stand for two hours. The infusion is then strained, and enough water passed through the strainer to make the product weigh 100 parts.

All the infusions both of the B.P. and U.S.P. are strained, with the exception of the infusion of cusso or brayera.

B.P. (28).	DOSE	U.S.P. (5).	
Of all not specified	1-2 fl. oz.		
Infusum Anthemidis	1-4 fl. oz.	Infusum Brayeræ (Cusso)	10 oz.
,, Aurantii		,, Cinchonæ	2 oz.
,, ,, Compositum		,, Digitalis	½ oz.*
,, Buchu	1-4 fl. oz.	,, Pruni Virginianæ	2-3 oz.
,, Calumbæ		,, Sennæ Compositum	4 fl. oz.
,, Caryophylli			
,, Cascarillæ			
,, Catechu			
,, Chiratæ			
,, Cinchonæ Fluidum			
,, Cuspariæ			
,, Cusso (Brayera anthelmintica)	4-8 fl. oz.		
,, Digitalis	1-4 fl. dr.		
,, Dulcamaræ			
,, Ergotæ			
,, Gentianæ Compositum			
,, Krameriæ			
,, Lini			
,, Lupuli			
,, Maticæ			
,, Quassiæ			
,, Rhei			
,, Rosæ Acidum			
,, Senegæ			
,, Sennæ			
,, Serpentariæ			
,, Uvæ Ursi			
,, Valerianæ			

* This infusion is about twice the strength of the B.P. The dose is usually stated at ½ oz. twice a day, but in many cases this dose would probably prove too large, and it is safer to begin with a smaller dose, and gradually push it as the patient will stand it.

B.P. Injectio Hypodermica. HYPODERMIC INJECTION.—There is only one, that of acetate of morphia, used simply for injecting under the skin. It is 10 times stronger than the liquor morphiæ acetatis, and contains 40 grains to the fluid ounce or 1 grain in twelve minims.

B.P.	DOSE.
Injectio Morphiæ Hypodermica	2-3 minims.

Linimenta. LINIMENTS OR EMBROCATIONS.—These are preparations for rubbing or painting on a part of the body in order to produce local stimulation or relieve pain. The basis of most of those in the British Pharmacopœia is olive oil, and of those in the United States Pharmacopœia cotton-seed oil.[1] Camphor is added to most of the liniments in the B.P. for its local stimulant action, and also that its strong smell may lessen the risk of the liniment being used internally. There are four exceptions in the B.P., the liniments of ammonia, lime, croton oil, and iodide of potassium with soap. With the exception of the liniment of lime all these contain very strong smelling substances, namely, ammonia in the

[1] I have been told that a great deal of what is sold as olive oil in Great Britain is really cotton-seed oil.

corresponding liniment, cajuput oil in the croton oil liniment, and oil of lemon in the iodide of potassium and soap liniment.

Camphor is not contained in the liniments of the U.S.P., with the exceptions of the liniments of belladonna, camphor, chloroform and soap.

Soap is used to give a lubricating quality to four liniments in the B.P., viz. opium, iodide of potassium with soap, soap and turpentine, and to two in the U.S.P., viz. chloroform and soap. In the compound mustard liniment, whose composition is nearly the same in the B.P. and the U.S.P., castor oil is used as a lubricant along with alcohol. In one, the turpentine liniment of the U.S.P., the lubricating substances are lard and yellow wax.

Three liniments in the B.P., aconite, belladonna, and iodine, and one in the U.S.P., belladonna, are really exceedingly strong solutions of active principles in spirit with camphor added for the purposes already mentioned.

The liniments last mentioned contain no fatty substances as lubricants, nor does the croton oil liniment of the B.P., compound camphor liniment (B.P.), nor the linimentum cantharidis (U.S P.). Croton oil liniment (B.P.) is a solution of croton oil with cajuput oil in spirit. The compound camphor liniment is a mixture of strong solution of ammonia with rectified spirit, camphor, and oil of lavender.

The linimentum cantharidis (U.S.P.) is a solution of the active principles of cantharides in turpentine. The difference in composition between the ordinary camphor liniment (B.P.) which is simply a mixture of camphor and olive oil, and the compound camphor liniment should be carefully borne in mind. The linimentum terebinthinæ aceticum (B.P.) consists of oil of turpentine and acetic acid mixed with ordinary camphor liniment. But if any one thinking to increase its efficacy should add to it compound camphor liniment, the acetic acid and ammonia would neutralise one another more or less completely, and the activity of both liniments would be to a great extent destroyed.

B.P.	U.S.P.
Linimentum Aconiti.	Linimentum Ammoniæ.
,, Ammoniæ.	,, Belladonnæ.
,, Belladonnæ.	,, Calcis.
,, Calcis.	,, Camphoræ.
,, Camphoræ.	,, Cantharidis.
,, Camphoræ Compositum.	,, Chloroformi.
,, Chloroformi.	,, Plumbi Subacetatis.
,, Crotonis.	,, Saponis.
,, Hydrargyri.	,, Sinapis Compositum.
,, Iodi.	,, Terebinthinæ.
,, Opii.	
,, Potassii Iodidi cum Sapone.	
,, Saponis.	
,, Sinapis Compositum.	
,, Terebinthinæ.	
,, Terebinthinæ Aceticum.	

Liquores. SOLUTIONS.—These are solutions of active substances in water, either alone or with the aid of other solvents.

B.P. (39).	DOSE.
Liquor Ammoniæ	10-30 m.
,, ,, Acetatis	2-6 fl. dr.
,, ,, Citratis	,,
,, ,, Fortior	3-10 m.
,, Antimonii Chloridi	
,, Arsenicalis	2-8 m.
,, Arsenici Hydrochloricus	,,
,, Atropiæ	1-2 m.
,, Atropiæ Sulphatis	,,
,, Bismuthi et Ammoniæ Citratis	½-1 fl. dr.
,, Calcis	1-4 fl. oz.
,, Calcis Chloratæ	
,, ,, Saccharatus	15-60 m.
,, Chlori	10-20 m.
,, Epispasticus	
,, Ferri Perchloridi	10-30 m.
,, ,, ,, Fortior	
,, ,, Pernitratis	,,
,, ,, Persulphatis	
,, Gutta-Percha	
,, Hydrargyri Nitratis Acidus	
,, Hydrargyri Perchloridi	½-2 fl. dr.
,, Iodi	
,, Lithiæ Effervescens	5-10 fl. oz.
,, Magnesiæ Carbonatis	1-2 fl. oz.
,, ,, Citratis	5-10 fl. oz.
,, Morphiæ Acetatis	10-60 m.
,, ,, Hydrochloratis	,,
,, Plumbi Subacetatis	
,, ,, ,, Dilutus	
,, Potassæ	,,
,, ,, Effervescens	5-10 fl. oz.
,, ,, Permanganatis	1-4 fl. dr.
,, Sodæ	10-60 m.
,, ,, Arseniatis	5-10 m.
,, ,, Chloratæ	10-20 m.
,, ,, Effervescens	5-10 fl. oz.
,, Strychniæ	5-10 m.
,, Zinci Chloridi	

U.S.P.	DOSE.
Liquor Acidi Arseniosi	2-8 m.
,, Ammonii Acetatis	½-1½ oz.
,, Arsenici et Hydrargyri Iodidi	5-10 m.
,, Calcis	2-4 fl. oz.
,, Ferri Acetatis	2-10 m.
,, ,, Chloridi	,,
,, ,, Citratis	10 m.
,, ,, et Quininæ Citratis	10-20 m.
,, ,, Nitratis	5-20 m.
,, ,, Subsulphatis	3-6 m.
,, ,, Tersulphatis	
,, Gutta-Perchæ	
,, Hydrargyri Nitratis	
,, Iodi Compositus	5 m.
,, Magnesii Citratis	6-12 fl. oz.
,, Pepsini	½-2 fl. oz.
,, Plumbi Subacetatis	
,, ,, Subacetatis Dilutus	
,, Potassii	10-60 m.
,, ,, Arsenitis	5 m.
,, ,, Citratis	½-2 fl. oz.
,, Sodæ	10-60 m.
,, Sodæ Chloratæ	30-60 m.
,, Sodii Arseniatis	3-8 m.
,, ,, Silicatis	
,, Zinci Chloridi	

U.S.P. Massæ. MASSES.—These simply consist of substances mixed together to a consistence suitable for making pills.

Massa Copaibæ.
,, Ferri Carbonatis.
,, Hydrargyri.

Mellita. HONEYS.—In these preparations honey is used as a vehicle. Oxymel and oxymel scillæ of the B.P., which contain acetic acid, may be regarded as belonging to this class.

B.P.	U.S.P.
Mel Boracis.	Mel Despumatum.
,, Depuratum.	,, Rosæ.
Oxymel.	
,, Scillæ.	

Misturæ. MIXTURES.—These usually consist of insoluble substances simply mixed with water or suspended in it by the aid of gum or other viscid substances. In almond (B.P. and U.S.P.), chalk (B.P. and U.S.P.) guaiac (B.P.) and compound glycyrrhiza (U.S.P.) mixtures, gum is added. In the ammoniacum (B.P. and U.S.P.) asafœtida (U.S.P.) and compound iron (B.P. and U.S.P.) mixtures, gum is contained in the ammoniacum, asafœtida, and myrrh used in their preparation respectively.

In scammony mixture (B.P.) the scammony resin is simply suspended in milk. In egg flip or brandy mixture (mistura spiritus vini gallici) (B.P.) and chloroform mixture (U.S.P.) yolk of egg forms the basis of the mixture.

The magnesia and asafœtida,[1] and rhubarb and soda mixtures of the U.S.P. contain insoluble substances mixed with water without the addition of any viscid substance; in the creasote mixture (B P.) the syrup may be looked upon as viscid and tending to keep the ingredients mixed, but the aromatic iron, compound gentian, and compound senna mixtures of the B.P. and the acetate of iron and ammonia (U.S P.) mixture are simply solutions and not mixtures in the usual sense.

B.P. (11).	DOSE.	U.S.P. (11).	DOSE.
Mistura Ammoniaci	½-1 fl. oz.	Mistura Ammoniaci	½-1 fl. oz.
,, Amygdalæ	1-2 fl. oz.	,, Amygdalæ	1-2 fl. oz.
,, Creasoti	,,	,, Asafœtidæ	½-1 fl. oz.
,, Cretæ	,,	,, Chloroformi	,,
,, Ferri Aromatica	,,	,, Cretæ	1-2 fl. oz.
,, ,, Composita	,,	,, Ferri Compositæ	,,
,, Gentianæ	½-1 fl. oz.	,, ,, et Ammonii Acetatis	½-1 fl. oz.
,, Guaiaci	½-2 fl. oz.	,, Glycyrrhizæ Composita	½ oz.
,, Scammonii	,,	,, Magnesiæ et Asafœtidæ	20 m.
,, Sennæ Composita	1-2 fl. oz.	,, Potassii Citratis	½ fl. oz.
,, Spiritus Vini Gallici.		,, Rhei et Sodæ	½-1 dr.

Mucilagines. MUCILAGES.—These are thick solutions, partial or complete, of gum or starch, which are convenient for suspending heavy powders in mixtures.

B.P. (3).	U.S.P. (5).
Mucilago Acaciæ.	Mucilago Acaciæ.
,, Amyli.	,, Cydonii.
,, Tragacanthæ.	,, Sassafras Medullæ.
	,, Tragacanthæ.
	,, Ulmi.

[1] In this mixture there is no gum, for although it is contained in crude asafœtida, it is not contained in the tincture of asafœtida used in this preparation.

Olea. OILS.—These are divided into fixed and volatile. The fixed are obtained by simple expression; the volatile by distillation excepting in the case of oil of lemons, which being contained in distinct vittæ in the rind, may be expressed instead of being distilled.

Fixed Oils.

B.P. (9).	DOSE.	U.S.P. (11).	DOSE.
Oleum Amygdalæ	1-4 fl. dr.	Oleum Adipis	
,, Crotonis (croton oil)	⅓-1 min.	,, Amygdalæ Expressum	1-8 fl. dr.
,, Lini		,, Gossypii Seminis	
,, Morrhuæ	1-8 fl. dr.	,, Lini	
,, Myristicæ Expressum.		,, Morrhuæ	½-4 fl. oz.
,, Olivæ	,,	,, Olivæ	
,, Phosphoratum	5-10 min.	,, Phosphoratum	1-5 min.
,, Ricini	1-8 fl. dr.	,, Ricini	1-8 fl. dr.
,, Theobromæ		,, Sesami	
		,, Theobromæ	
		,, Tiglii (croton oil)	¼-1 min.

Volatile Oils.

B.P. (22).	DOSE OF EACH.
Oleum Anethi	1-5 m. unless otherwise mentioned.
,, Anisi	
,, Anthemidis	
,, Cajuputi	
,, Carui	
,, Caryophylli	
,, Cinnamomi	
,, Copaibæ	5-20 min.
,, Coriandri	
,, Cubebæ	5-20 min.
,, Juniperi	1-10 min.
,, Lavandulæ	
,, Limonis	
,, Menthæ Piperitæ	
,, ,, Viridis	
,, Myristicæ	
,, Pimenti	
,, Rosmarini	
,, Rutæ	
,, Sabinæ	
,, Sinapis	For external use only.
,, Terebinthinæ	10-20 m. as diuretic, 2-6 fl. dr. as anthelmintic.

Volatile Oils.

U.S.P.	
Oleum Æthereum	
,, Amygdalæ Amaræ	¼-1 min. (0·016-0·06 c.c)
,, Anisi	5-15 min. (0·3-0·9 c.c.)
,, Aurantii Corticis	
,, ,, Florum	
,, Bergamii	

U.S.P.	DOSE.
Oleum Cajuputi	5-20 min. (0·3-1·25 c.c.)
,, Cari	1-10 min. (0·06-0·6 c.c.)
,, Caryophylli	2-6 min. (0·12-0·36 c.c.)
,, Chenopodii	4-8 min. for a child (0·25-0·5 c.c.)
,, Cinnamomi	1-3 min. (0·06-0·18 c.c.)
,, Copaibæ	10-15 min. (0·6-0·9 c.c.)
,, Coriandri	
,, Cubebæ	10-12 min. at first (0·6 or 0·72 c.c.) gradually increased.
,, Erigerontis	10 min. ½ fluid drachm (0·6-0·18 c.c.)
,, Eucalypti	10-15 min. (0·6-0·9 c.c.)
,, Fœniculi	5-15 min. (0·3-0·9 c.c.)
,, Gaultheriæ	
,, Hedeomæ (penny royal)	2-10 min. (0·12-0·6 c.c.)
,, Juniperi	5-15 min. (0·3-0·9 c.c.)
,, Lavandulæ	1-5 min. (0·06-0·3 c.c.)
,, ,, Florum	
,, Limonis	
,, Menthæ Piperitæ	2-6 min. (0·12-0·36 c.c.)
,, ,, Viridis	2-6 min. (0·06-0·36 c.c.)
,, Myrciæ	
,, Myristicæ	2-3 min. (0·12-0·18 c.c.)
,, Picis Liquidæ	
,, Pimentæ	3-6 min. (0·18-0·35 c.c.)
,, Rosæ	
,, Rosmarini	5-6 min. (0·18-0·36 c.c.)
,, Rutæ	2-5 min. (0·12-0·3 c.c.)
,, Sabinæ	2-5 min. (0·12-0·3 c.c.)
,, Santali	20-30 min. (1·25-1·9 c.c.)
,, Sassafras	3-5 min. (0·18-0·3 c.c.)
,, Sinapis Volatile	
,, Succini	5-15 min. (0·3-0·9 c.c.)
,, Terebinthinæ	5-30 min. (0·3-1·9 c.c.)
,, Thymi	
,, Valerianæ	4-5 min. (0·24-0·3 c.c.)

U.S.P. Oleata. OLEATES.—Solutions of bases in oleic acid. They are more readily absorbed by the skin than ointments.

U.S.P.
Oleatum Hydrargyri.
,, Veratrinæ.

U.S.P. Oleoresinæ. OLEORESINS.—These are, as their name implies, mixtures of volatile oil and resin. They are extracted by treating the crude substance with stronger ether, and removing the ether partly by distillation and partly by evaporation. Their advantage is that they remain in a liquid or semi-liquid state, and are stable, not requiring alcohol to prevent decomposition.

U.S.P.	DOSE.
Oleoresina Aspidii	½-1 fl. dr.) 1·9-3·75 c.c.)
,, Capsici	¼-1 min. (0·015-0·06 c.c.)
,, Cubebæ	5-30 min. (0·3-1·9 c.c.)
,, Lupulini	2-5 gr. (0·13-0·33 gm.)
,, Piperis	¼-1 min. (0·015-0·06 c.c.)
,, Zingiberis	$\frac{1}{10}$-1 min. (0·006-0·06 c.c.)

Oxymel, *vide* MELLITA.

Pilulæ. PILLS.—Pills are small round masses which can be conveniently swallowed. They are rarely made of a greater weight than five grains, as they then become too bulky to be swallowed easily. Those of the U.S.P. are four grains each. In their composition the old rule of **curare, cito, tute et jucunde,** has been pretty strictly followed, and most of them in addition to the basis contain an adjuvant, corrective, and vehicle. To prevent them sticking together they are generally shaken with some dry powder, such as lycopodium, carbonate of magnesia, flour, starch, or liquorice powder. Sometimes they are gilt or silvered by shaking them while freshly prepared, and without the addition of any dusting powder, along with gold or silver leaf in a hollow spherical wooden box. Recently a coating of firm gelatine has been used, and sometimes pills are coated with sugar.

B.P.	DOSE.
Dose, 5-10 grs. with the exception of those mentioned.	
Pilula Aloes Barbadensis	
,, Aloes et Asafœtidæ	
,, ,, et Ferri	
,, ,, et Myrrhæ	
,, ,, Socotrinæ	
,, Asafœtidæ Composita	
,, Cambogiæ Composita	
,, Colocynthidis Composita	
,, ,, et Hyoscyami	
,, Conii Composita	
,, Ferri Carbonatis	
,, ,, Iodidi	3-8 grs.
,, Hydrargyri	3-8 grs.
,, Hydrargyri Subchloridi Composita	
,, Ipecacuanhæ cum Scillâ	
,, Phosphori	2-5 grs.
,, Plumbi cum Opio	2-5 grs.
,, Quiniæ	2-10 grs.
,, Rhei Composita	
,, Saponis Composita	2-5 grs.
,, Scammonii Composita	5-15 grs.
,, Scillæ Composita	

U.S.P.	DOSE.
Pilulæ Aloes	1-5 pills.
,, Aloes et Asafœtidæ	2-5 pills.
,, ,, et Ferri	1-3 pills.
,, ,, et Mastiches	1 pill.
,, ,, et Myrrhæ	3-6 pills.
,, Antimonii Compositæ	1-2 pills.
,, Asafœtidæ	1 pill.
,, Catharticæ Compositæ	1-3 pills.
,, Ferri Compositæ	2-6 pills.
,, ,, Iodidi	1 pill.
,, Galbani Compositæ	2-4 pills.
,, Opii	1 pill.
,, Phosphori	1-2 pills.
,, Rhei	1-6 pills.
,, ,, Compositæ	2-4 pills.

Pulveres. POWDERS.—The officinal powders contain two or more substances triturated and mixed together. The fineness of powders is ascertained by the size of the meshes of the sieve through which they pass.

B.P. (15).	DOSE.
Pulvis Amygdalæ Compositus	60-120 grs.
,, Antimonialis	3-10 grs.
,, Catechu Compositus	20-40 grs.
,, Cinnamomi Compositus	3-10 grs.
,, Cretæ Aromaticus	10-60 grs.
,, ,, Aromaticus Cum Opio	10-40 grs.
,, Elaterii Compositus	½-5 grs.
,, Glycyrrhizæ Compositus	30-60 grs.
,, Ipecacuanhæ Compositus	5-15 grs.
,, Jalapæ Compositus	20-60 grs.
,, Kino Compositus	5-20 grs.
,, Opii Compositus	2-5 grs.
,, Rhei Compositus	20-60 grs.
,, Scammonii Compositus	10-20 grs.
,, Tragacanthæ Compositus	20-60 grs.

U.S.P. (9).	DOSE.
Pulvis Antimonialis	3-8 grs. (0·2-0·52 gm.)
,, Aromaticus	10-30 grs. (0·65-1·95 gm.)
,, Cretæ Compositus	10-30 grs. (0·65-1·95 gm.)
,, Effervescens Compositus	One powder.
,, Glycyrrhizæ Compositus	30-60 grs. (1·95-3·9 gm.)
,, Ipecacuanhæ et Opii	5 15 grs. (0·33-1 gm.)
,, Jalapæ Compositus	30-60 grs. (1·95-3·9 gm.)
,, Morphinæ Compositus	10 grs. (0·65 gm.)
,, Rhei Compositus	30-60 grs. (1·95-3·9 gm.)

Resina. RESINS.—These are brittle, amorphous solids, consisting of an acid or mixtures of acids formed by the oxidation of terpenes which are volatile hydrocarbons having the formula $C_{10}H_{16}$. Resins are insoluble in water but soluble in spirit. They melt when heated, and solidify again on cooling. They dissolve in alkalies, forming a kind of soap. They frequently occur in plants along with unoxidised volatile oils as oleo-resins. Resins may be obtained from oleo-resins, *e.g.* turpentine, by simple distillation, when the volatile oil distils over and resin remains. They may be got by heating the part of the plant in which they are contained, *e.g.* guaiac resin. They may be prepared by dissolving them out of the plants by means of alcohol and removing the alcohol by distillation, or precipitating them by throwing the strong tincture into water. Resins are of an acid nature, and the addition of a little mineral acid to water causes them to be precipitated more readily.

B.P.	U.S.P.
Resina.	Resina Copaibæ.
,, Guiaci.	,, Jalapæ.
,, Jalapæ.	,, Podophylli.
,, Podophylli.	,, Scammonii.
,, Scammoniæ.	Guaiaci Resina.

Spiritus. SPIRITS.—With the exception of rectified and proof spirit, these are alcoholic solutions of volatile oils or ethers. The dose is ½ to 1 fluid drachm, except where otherwise mentioned, and except in the case of brandy, rum, and whisky, the doses of which vary very much, according to the purpose for which they are used.

B.P. (16).	DOSE.
Spiritus Ætheris	
,, ,, Nitrosi	½-2 fluid drachms.
,, Ammoniæ Aromaticus	
,, ,, Fœtidus	
,, Armoraciæ Compositus	1-2 fluid drachms.
,, Cajuputi	
,, Camphoræ	10-30 min.
,, Chloroformi	10-60 min.
,, Juniperi	½-1½ fluid drachms.
,, Lavandulæ	
,, Menthæ Piperitæ	
,, Myristicæ	
,, Rectificatus	
,, Rosmarini	10-60 min.
,, Tenuior	
,, Vini Gallici	

U.S.P. (22).	DOSE.
Spiritus Ætheris	1-3 fluid drachms (3·75-11·25 c.c.)
,, ,, Compositus	½-2 fluid drachms (1·0-7·5 c.c.)
,, ,, Nitrosi	30-60 min. (1·9-3·75 c.c.)
,, Ammoniæ	10-30 min. (0·6-1·9 c.c.)
,, ,, Aromaticus	30-60 min. (1·9-3·75 c.c.)
,, Anisi	1-2 fluid drachms (3·75-7·5 c.c.)
,, Aurantii	1-2 fl. dr. (3·75-7·5 c.c.)
,, Camphoræ	5-60 min. (0·3-3·75 c.c.)
,, Chloroformi	10-60 min. (0·6-3·75 c.c.)
,, Cinnamonii	10-20 min. (0·6-1·25 c.c.)
,, Frumenti (Whisky)	
,, Gaultheriæ	10-20 min. (0·6-1·25 c.c.)
,, Juniperi	30-60 min. (1·9-3·75 c.c.)
,, ,, Compositus	2-4 fluid drachms (7·5-15 c.c.)
,, Lavandulæ	30-60 min. (1·9-3·75 cc.)
,, Limonis	
,, Menthæ Piperitæ	10-20 min. (0·6-1·25 c.c.)
,, ,, Viridis	30-40 min. (1·9-2·5 c.c.)
,, Myrciæ (Bay Rum)	
,, Myristicæ	1 fluid drachm (3·75 c.c.)
,, Odoratus (Cologne-Water)	
,, Vini Gallici	

Suppositoria. SUPPOSITORIES.—These are small conical masses for introducing drugs into the rectum. They are used either to produce a local action on the rectum itself, or on the adjoining pelvic organs, such as the uterus or the bladder; or to introduce certain drugs into the body when we wish to avoid any local action on the stomach.

Thus the morphia suppositories may be used for their general action in inducing sleep, or for their local action in soothing pain or irritation in the rectum or pelvic organs, or to check diarrhœa. The compound lead suppository may be used in diarrhœa for its local action on the rectum, and likewise for its general action in

checking bleeding from the lungs, etc. The same may be said of the mercurial suppository. The others are more intended for local action.

B.P. (7).

Suppositoria Acidi Carbolici cum Sapone.
,, ,, Tannici.
,, ,, ,, cum Sapone.
,, Hydrargyri.
,, Morphiæ.
,, ,, cum Sapone.
,, Plumbi Composita.

In the U.S.P. no special suppositories are named, but a formula is given for their preparation. The quantity of the medicine required, brought to a proper consistency if necessary, is to be mixed with a small quantity of oil of theobroma by rubbing together, and then sufficient oil of theobroma previously melted and cooled to the temperature of 35° C. (95° F.) is to be mixed thoroughly with it, and immediately poured into suitable moulds cooled by ice. In the absence of moulds the mass is to be divided into parts of a definite weight, which are to be made into a convenient form for a suppository. Unless otherwise specified, they should weigh fifteen grains or one gramme.

B.P. Succi. JUICES (8).—These consist of the fresh juices of the plant which are mixed with a sufficient quantity of spirit to prevent them from decomposing, except in the case of lemon, mulberry, and buckthorn juice, to which no alcohol is added.

B.P. (8).

Succus Belladonnæ.
,, Conii.
,, Hyoscyami.
,, Scoparii.
,, Taraxaci.
Limonis Succus.
Mori ,,
Rhamni. ,,

Syrupi. SYRUPS.—These are strong solutions of sugar; many of them contain flavouring or colouring matters, and are used to make medicines more agreeable to the eye or palate.

In the case of iodide of iron and phosphate of iron the sugar prevents oxidation, and thus preserves the preparation from decomposition.

B.P. (18).	DOSE.
	All 1 fluid drachm except those specially marked.
Syrupus	
,, Aurantii	
,, Aurantii Floris	
,, Chloral	½-2 fluid drachms.
,, Ferri Iodidi	½-1 fluid drachm.
,, ,, Phosphatis	
,, Hemidesmi	
,, Limonis	
,, Mori	
,, Papaveris	
,, Rhamni	

	B.P. (18).	DOSE.
Syrupus	Rhei	1-4 fluid drachms.
,,	Rhœados	
,,	Rosæ Gallicæ	
,,	Scillæ	½-1 fluid drachm.
,,	Sennæ	1-4 fluid drachms.
,,	Tolutanus	
,,	Zingiberis	½-1 fluid drachm.

	U.S.P.	DOSE.
Syrupus	Acaciæ	
,,	Acidi Citrici	
,,	,, Hydriodici	1-4 fl. dr. (3·75-15 c.c.)
,,	Allii	1 fl. dr. (3·75 c.c.)
,,	Althææ	1-4 fl. dr. (3·75-15 c.c.)
,,	Amygdalæ	
,,	Aurantii	
,,	,, Florum	1 fl. dr. (3·75 c.c.)
,,	Calcii Lactophosphatis	2-4 fl. dr. (7·5-15 c.c.)
,,	Calcis	1 fl. dr. (3·75 c.c.)
,,	Ferri Bromidi	⅓ 1 fl. dr. (1·9-3·15 c.c.)
,,	,, Iodidi	15-30 m. (0·9-1·9 c.c.)
,,	,, Quininæ et Strychninæ Phosphatum	1 fl. dr. (3·75 c.c.)
,,		1-2 fl. dr. (3·75-7·5 c.c.)
,,	Hypophosphitum	1-2 fl. dr. (3·75-7·5 c.c.)
,,	,, cum Ferro	1-2 fl. dr. (3·75-7·5 c.c.)
,,	Ipecacuanhæ	(Emetic) ½-1 oz. 15-30 c.c.) (Expectorant) 30-60 m. (1·9-3·75 c.c.)
,,	Krameriæ	½ fl. oz. (15 c.c.)
,,	Lactucarii	2-3 fl. dr. (7·5-11·25 c.c.)
,,	Limonis	
,,	Picis Liquidæ	1-2 fl. dr. (3·75-7·5 c.c.)
,,	Pruni Virginianæ	½ fl. oz. (15 c.c.)
,,	Rhei	1 fl. dr. (3·75 c.c.)
,,	,, Aromaticus	1 fl. dr. (3·75 c.c.)
,,	Rosæ	1 fl. dr. (3·75 c.c.)
,,	Rubi	1-2 fl. dr. (3·75-7·5 c.c.)
,,	,, Idæi	
,,	Sarsaparillæ Compositus	½ fl. oz. (15 c.c.)
,,	Scillæ	1 fl. dr. (3·75.)
,,	,, Compositus	(Expectorant) 20-30 m. (1·25-1·9 c.c.)
,,	Senegæ	1-2 fl. dr. (3·75-7·5 c.c.)
,,	Sennæ	1-4 fl. dr. (3·75-15 c.c.)
,,	Tolutanus	
,,	Zingiberis	1 fl. dr. (3·75 c.c.)

Tincturæ. TINCTURES. — These are solutions of active principles in spirit. Rectified spirit, or alcohol, is used whenever the active principle is more soluble in strong than in dilute alcohol, as in the case of alkaloids, such as veratrum viride; resins, such as asafœtida, benzoin, and Indian hemp; oils, such as cubebs, lavender, tolu, orange peel, larch bark, and ginger; and other substances, such as chloroform, acetate of iron, perchloride of iron, iodine, kino.

Aromatic spirit of ammonia is used in the ammoniated tincture of guaiac, of valerian, and of opium (B.P. and U.S.P.). In the case of guaiac and valerian the active principles have an acid character, and so ammonia tends to dissolve them more completely. In both

of them, however, as well as in ammoniated tincture of opium, the ammonia has got a stimulating action of its own, which tends to aid the effect of the other substances.

Tinctures of fresh herbs (Tincturæ Herbarum recentium) when not otherwise directed, are, according to the U.S.P., to be prepared by macerating fifty parts of the fresh herb bruised or crushed in a hundred parts of alcohol for fourteen days, then expressing the liquid, and filtering.

B.P. (68).	DOSE.
	The usual dose is ½-2 fl. dr. unless otherwise mentioned.
Tinctura Aconiti	1-10 min.
,, Aloes	
,, Arnicæ	
,, Asafœtidæ	½-1 fluid drachm.
,, Aurantii	
,, ,, Recentis	
,, Belladonnæ	5-20 min.
,, Benzoini Composita	½-1 fluid drachm.
,, Buchu	
,, Calumbæ	
,, Camphoræ Composita	15 min.-1 fluid drachm.
,, Cannabis Indicæ	5-20 min.
,, Cantharidis	5-20 min.
,, Capsici	5-20 min.
,, Cardamomi Composita	
,, Cascarillæ	
,, Castorei	½-1 fluid drachm.
,, Catechu	
,, Chiratæ	
,, Chloroformi Composita	10-60 min.
,, Cinchonæ Composita	
,, Cinchonæ Flavæ	
,, Cinnamomi	
,, Cocci	
,, Colchici Seminum	10-30 min.
,, Conii	10-60 min.
,, Croci	
,, Cubebæ	
,, Digitalis	5-30 min.
,, Ergotæ	10-60 min.
,, Ferri Acetatis	5-30 min.
,, ,, Perchloridi	5-30 min.
,, Gallæ	
,, Gentianæ Composita	
,, Guaiaci Ammoniata	½-1 fluid drachm.
,, Hyoscyami	½-1 fluid drachm.
,, Iodi	5-20 min.
,, Jalapæ	
,, Kino	
,, Krameriæ	
,, Laricis	15-30 min.
,, Lavandulæ Composita	
,, Limonis	
,, Lobeliæ	10-30 min.
,, ,, Ætherea	10-30 min.
,, Lupuli	
,, Myrrhæ	30-60 min.
,, Nucis Vomicæ	10-30 min.
,, Opii	5-40 min.
,, ,, Ammoniata	30-60 min.

B.P. (68).	DOSE.
Tinctura Pyrethri	
,, Quassiæ	
,, Quiniæ	
,, ,, Ammoniata	
,, Rhei	(Stomachic) ½-2 fluid drachms.
,, ,,	(Purgative) 4-8 fluid drachms.
,, Sabinæ	10-60 min.
,, Scillæ	10-30 min.
,, Senegæ	
,, Sennæ	1 fluid drachm to 4 fluid oz.
,, Serpentariæ	
,, Stramonii	10-30 min.
,, Sumbul	10-30 min.
,, Tolutana	10-30 min. or more.
,, Valerianæ	
,, ,, Ammoniata	½-1 drachm.
,, Veratri Viridis	5-20 min.
,, Zingiberis	10-60 min.
,, ,, Fortior	5-20 min.

U.S.P.	DOSE.
Tinctura Aconiti	1-3 m. (0·06-0·18 c.c.)
,, Aloes	(As laxative) ½-1 fl. dr.
,, ,,	(As purgative) 2-4 fl. dr.
,, ,, et Myrrhæ	1-2 fl. dr. (3·75-7·5 c.c.)
,, Arnicæ Florum	10-30 m. (0·6-1·9 c.c.)
,, ,, Radicis	20-30 m. (1·25-1·9 c.c.)
,, Asafœtidæ	30-60 m. (1·9-3·75 c.c.)
,, Aurantii Amari	1-2 fl. dr. (3·75-7·5 c.c.)
,, ,, Dulcis	
,, Belladonnæ	15-30 m. (0·9-1·9 c.c.)
,, Benzoini	20-30 m. (1·25-1·9 c.c.)
,, ,, Composita	½-2 fl. dr. (1·9-7·5 c.c.)
,, Bryoniæ	1-2 fl. dr. (3·75-7·5 c.c.)
,, Calendulæ	
,, Calumbæ	1-4 fl. dr. (3·75-15. c.c.)
,, Cannabis Indicæ	30 m. (1·9 c.c.)
,, Cantharidis	3-10 m. (0·07-0·30 c.c.)
,, Capsici	30-60 m. (1·9-3·7 c.c.)
,, Cardamomi	1 fl. dr. (3·75 c.c.)
,, ,, Composita	1-2 fl. dr. (3·75-7·5 c.c.)
,, Catechu Composita	½-3 fl. dr. (1·9-11·25 c.c.)
,, Chiratæ	1-2 fl. dr. (3·75-7·5 c.c.)
,, Cimicifugæ	1-4 fl. dr. (3·75-15 c.c.)
,, Cinchonæ	1-4 fl. dr. (3·75-15 c.c.)
,, ,, Composita	1-4 fl. dr. (3·75-15 c.c.)
,, Cinnamomi	1-4 fl. dr. (3·75-15 c.c.)
,, Colchici	½-2 fl. dr. (1·9-7·5 c.c.)
,, Conii	30 m. (1·9 c.c.) to be increased.
,, Croci	1-3 fl. dr. (3·75-11·25 c.c.)
,, Cubebæ	1-2 fl. dr. (3·75-7·5 c.c.)
,, Digitalis	10-20 m. (0·6-1·25 c.c.)
,, Ferri Acetatis	20-60 m. (1·25-3·75 c.c.)
,, ,, Chloridi	10-30 m. (0·6-1·9 c.c.)
,, Gallæ	1-3 fl. dr. (3·75-11·25 c.c.)
,, Gelsemii	10-20 m. (0·6-1·25 c.c.)
,, Gentianæ Composita	1-2 fl. dr. (3·75-7·5 c.c.)
,, Guaiaci	1 fl. dr. (3·75 c.c.)
,, ,, Ammoniata	1-2 fl. dr. (3·75-7·5 c.c.)
,, Herbarum recentium	
,, Humuli	1-3 fl. dr. (3·75-11·25 c.c.)
,, Hydrastis	30-60 m. (1·9-3·75 c.c.)
,, Hyoscyami	60 m. (3·75 c.c.)

	U.S.P. DOSE.
Tinctura	Ignatiæ ..... 15-20 m. (0·9-1·25 c.c.)
,,	Iodi ..... 5-15 m. (0·3-0·9 c.c.)
,,	Ipecacuanhæ et Opii ..... 10 m. (0·6 c.c.)
,,	Kino ..... 1-2 fl. dr. (3·75-7·5 c.c.)
,,	Krameriæ ..... 1-2 fl. dr. (3·75-7·5 c.c.)
,,	Lavandulæ Composita ..... 30-60 m. (1·9-3·75 c.c.)
,,	Lobeliæ ..... 30-60 m. (1·9-3·75 c.c.)
,,	Matiçæ ..... 1 fl. dr. (3·75 c.c.)
,,	Moschi ..... ½-2 fl. dr. (1·9-7·5 c.c.)
,,	Myrrhæ ..... 15-30 m. (0·9-1·9 c.c.)
,,	Nucis Vomicæ ..... 20 m. (1·25 c.c.)
,,	Opii ..... 11 m. (0·65 c.c.) or 22 drops.
,,	,, Camphorata ..... 1-4 fl. dr. (3·75-15 c.c.)
,,	,, Deodorata ..... 11 m. (0·65 c.c.)
,,	Physostigmatis ..... 20-40 m. (1·25-2·5 c.c.)
,,	Pyrethri .....
,,	Quassiæ ..... 1 fl. dr. (3·75 c.c.)
,,	Rhei ..... 1-2 fl. dr. (3·75-7·5 c.c.)
,,	,, Aromatica ..... ½-1 fl. dr. (1·9-3·75 c.c.)
,,	,, Dulcis ..... 2-3 fl. dr. (7·5-11·25 c.c.)
,,	Sanguinariæ ..... 30-60 m. (1·9-3·75 c.c.)
,,	Saponis Viridis .....
,,	Scillæ ..... 10-20 m. (0·6-1·25 c.c.)
,,	Serpentariæ ..... 1-4 fl. dr. (3·75-15 c.c.)
,,	Stramonii ..... 20-30 m. (1·25-1·9 c.c.)
,,	Sumbul ..... 20-60 m. (1·2-3·7 c.c.)
,,	Tolutana ..... 1-2 fl. dr. (3·75-7·5 c.c.)
,,	Valerianæ ..... 1-4 fl. dr. (3·75-15 c.c.)
,,	,, Ammoniata ..... 30-60 m. (1·9-3·75 c.c.)
,,	Vanillæ .....
,,	Veratri Viridis ..... 3-8 min. (0·18-0·5 c.c.)
,,	Zingiberis ..... 8-40 m. (0·5-2·5 c.c.)

U.S.P. Triturationes. TRITURATIONS.—These are intimate mixtures of substances with sugar of milk. Each contains 10 per cent. of the active substances. A general formula for their preparation is given in the U.S.P., although only one is named. According to this formula 10 parts of the substance and 90 parts of sugar of milk are to be weighed out separately. The substance, reduced to a moderately fine powder if necessary, is mixed in a mortar with about its own bulk of sugar of milk and they are triturated together. Fresh portions of the sugar of milk are added from time to time until the whole has been added, and the trituration is continued until the substance is intimately mixed with the sugar of milk and finely comminuted.

U.S.P.
Trituratio Elaterini.

Trochisci. LOZENGES.—These are small, flat, and hard, so that they can be readily carried about and melt slowly in the mouth. They are thus convenient for giving drugs which are intended to act upon the mouth or throat locally, or to be readily carried about and taken at times and in places where more bulky preparations would be inconvenient. Thus we have lozenges of chlorate of potash which are useful for soreness of the mouth and

tongue; tannic acid and catechu which are useful in relaxed sore throat and hoarseness; ipecacuanha with morphia, and with opium, which are useful in coughs; bicarbonate of soda useful before meals in dyspepsia or after meals in acidity; bismuth for irritability of the stomach; and reduced iron for debility. Bismuth, morphia and opium, are also useful in diarrhœa. In many cases it happens that although patients can take potions before, after, or with their morning and evening meals, they are unable to do so in the middle of the day when they are absent from home and engaged in various avocations. For such cases lozenges form a useful means of administering medicine.

B.P. (10).	U.S.P. (16).
Trochisci Acidi Tannici.	Trochisci Acidi Tannici.
,, Bismuthi.	,, Ammonii Chloridi.
,, Catechu.	,, Catechu.
,, Ferri Redacti.	,, Cretæ.
,, Ipecacuanhæ.	,, Cubebæ.
,, Morphiæ.	,, Ferri.
,, Morphiæ et Ipecacuanhæ.	,, Glycyrrhizæ et Opii.
,, Opii.	,, Ipecacuanhæ.
,, Potassæ Chloratis.	,, Krameriæ.
,, Sodæ Bicarbonatis.	,, Magnesiæ.
	,, Menthæ Piperitæ
	,, Morphinæ et Ipecacuanhæ.
	,, Potassii Chloratis.
	,, Sodii Bicarbonatis.
	,, ,, Santoninatis.
	,, Zingiberis.

Unguenta. OINTMENTS. — These are soft admixtures of medicines with fatty substances for external application. The basis of many of them is lard, either alone or mixed with benzoin in order to preserve it from rancidity, or mixed with white wax in the form of ointment (unguentum U.S.P.). In the B.P. simple ointment, which consists of white wax and almond oil, forms the basis of several ointments.

The semi-solid substances, obtained from American petroleum, form a useful basis for ointments as they do not become rancid. They consist of hydrocarbons chiefly of the marsh-gas series. There are two chief varieties, one softer, having a melting point about 40° C. (104° F.), the other 51° C. (or 121° F.). They are obtained by distilling off the lighter and more volatile portions from American petroleum. They are known under different names. Petrolatum (U.S.P.) cosmoline, unguentum petrolei, and vaseline.

B.P. (34).	U.S.P. (25).
Unguentum Aconitiæ.	Unguentum Acidi Carbolici.
,, Antimonii Tartarati.	,, Acidi Gallici.
,, Atropiæ.	,, ,, Tannici.
,, Belladonnæ.	,, Aquæ Rosæ (cold cream).
,, Cadmii Iodidi.	,, Belladonnæ.
,, Cantharidis.	,, Chrysarobini.
,, Cetacei.	,, Diachylon.
,, Creasoti.	,, Gallæ.

B.P. (34).

Unguentum Elemi.
,, Gallæ.
,, ,, cum Opio.
,, Hydrargyri (blue ointment).
,, ,, Ammoniati.
,, ,, Compositum.
,, ,, Iodidi Rubri.
,, ,, Nitratis.
,, ,, Oxidi Rubri.
,, ,, Subchloridi.
,, Iodi.
,, Picis Liquidæ.
,, Plumbi Acetatis.
,, ,, Carbonatis.
,, ,, Iodidi.
,, ,, Subacetatis Compositum.
,, Potassæ Sulphuratæ.
,, Potassii Iodidi.
,, Resinæ.
,, Sabinæ.
,, Simplex.
,, Sulphuris.
,, ,, Iodidi.
,, Terebinthinæ.
,, Veratriæ.
,, Zinci.

U.S.P. (25).

Unguentum Hydrargyri.
,, ,, Ammoniati.
,, ,, Nitratis.
,, ,, Oxidi Flavi.
,, ,, ,, Rubri.
,, Iodi.
,, Iodoformi.
,, Mezerei.
,, Picis Liquidæ.
,, Plumbi Carbonatis.
,, ,, Iodidi.
,, Potassii Iodidi.
,, Stramonii.
,, Sulphuris.
,, ,, Alkalinum.
,, Veratrinæ.
,, Zinci Oxidi.

B.P. Vapores. VAPOURS, INHALATIONS.—These are preparations for applying volatile drugs to the air-passages for the purpose of deodorising, disinfecting, stimulating or soothing. The drug is mixed with water and the vapour inhaled. If the drug is not readily volatile, warm water is used as in the vapor creasoti, or the water is warmed during inhalation, as in the vapor iodi.

B.P. (5).

Vapor Acidi Hydrocyanici.
,, Chlori.
,, Coniæ.
,, Creasoti.
,, Iodi.

The vapours of chlorine, creasote, and iodine may be used for deodorising in cases of ozœna or in cases of chronic bronchitis with offensive sputa.

Antiseptic inhalations, such as those of creasote and iodine, as well as non-officinal inhalations of iodoform and oil of pine, have been recently used in the treatment of phthisis with the object of destroying the tubercle bacillus. For this purpose a special form of inhaler is used, which fits over the mouth and nose. It contains a sponge which is soaked with the drug to be inhaled either pure or dissolved in spirit or water.

They are probably also useful even in simple catarrh by destroying organisms which may have found their way into the air-passages and occasion or keep up inflammation. The vapours of hydrocyanic acid and conium are useful for the purpose of

allaying irritability, as in spasm of the glottis, violent coughing or spasmodic asthma.

Vina. WINES.—These are made in the same way as tinctures, sherry or orange wine (B.P.) or stronger white wine (U.S.P.) being employed instead of spirit.

B.P. (10).	DOSE.
Vinum Aloes	1-2 fluid drachms.
,, Antimoniale	5-30 min. as expectorant.
,, ,,	½-1 fluid oz. as emetic.
,, Colchici	10-30 min.
,, Ferri	1-4 fluid drachms.
,, ,, Citratis	1-4 fluid drachms.
,, Ipecacuanhæ	5-40 min. as expectorant.
,, ,,	1-8 drachms as emetic.
,, Opii	10-40 min.
,, Quiniæ	½-1 fluid oz.
,, Rhei	1-2 drachms.
,, Xericum	

U.S.P. (14).	
Vinum Album	
,, Album Fortius	
,, Aloes	Stomachic, 1-2 drachms. Purgative, ½-1 fluid oz.
,, Antimonii	Expectorant, 10-30 min.
,, Aromaticum	
,, Colchici Radicis	10 min.-1 fluid drachm.
,, ,, Seminis	30 min.-2 fluid drachms.
,, Ergotæ	1-4 fluid drachms.
,, Ferri Amarum	2-4 fluid drachms.
,, ,, Citratis	1-4 fluid drachms.
,, Ipecacuanhæ	Expectorant, 10-30 min. Emetic, 1-8 drachms.
,, Opii	15-20 min.
,, Rhei	1-4 fluid drachms.
,, Rubrum	

SECTION III.

INORGANIC MATERIA MEDICA.

CHAPTER XXII.

HYDROGEN, OXYGEN, OZONE, CARBON, SULPHUR, AND THE HALOGENS.

ALTHOUGH the officinal substances included in this chapter differ widely from each other in many respects, yet their relations to oxygen form a connecting link between them. Sulphur belongs to the same chemical group as oxygen. The chief action of charcoal is its power of oxidising organic substances by means of oxygen which it has condensed in its pores. The halogens probably owe their disinfecting properties in great measure to their power of liberating oxygen from water in the presence of organic matter which they thus oxidise and destroy.

HYDROGEN (H ; 1). Not officinal.

PREPARATION.—By adding diluted hydrochloric or sulphuric acid to granulated zinc—

$$Zn + 2HCl = ZnCl_2 + H_2.$$

USES.—It is of little or no use as a remedy, and is only used as a test.

It is very frequently employed in testing for arsenic, antimony, or sulphur. When in its nascent condition it has active chemical affinities, and readily unites with these substances, forming sulphuretted, arseniuretted, or antimoniuretted hydrogen.

OXYGEN (O ; 16). Not officinal.

PREPARATION.—By heating chlorate of potash with peroxide of manganese—

$$2KClO_3 = 2KCl + 3O_2.$$

Peroxide of manganese merely aids the decomposition of the chlorate of potash, and takes no part in the reaction.

PROPERTIES.—Oxygen is a colourless gas without smell, slightly heavier than common air. It forms rather more than a fifth by volume of the atmosphere.

PHYSIOLOGICAL ACTION.—Oxygen applied to the unbroken skin has but little action, but when applied to a wound it increases the circulation in it, and acts as a stimulant. When inhaled by healthy persons it causes a slight feeling of warmth in the mouth, extending downwards over the front of the body. In some people it appears to cause nervous symptoms somewhat like those produced by nitrous oxide.

In animals, excess of oxygen produces tetanic symptoms almost like those of strychnine, and death. This effect is produced by a pressure of three atmospheres, and it is evident that it is due to the oxygen and not to the simple increase in atmospheric pressure only, because when ordinary air is used a pressure of three atmospheres has no such action, and a pressure of twenty-five atmospheres is requisite to produce this effect (Bert).

It has been thought by some that when oxygen has been once breathed it loses something which enables it to support life. The reason of this belief is that animals soon die which are kept in a confined space, from which the carbonic acid formed during respiration is absorbed by lime or baryta, and its place supplied by fresh oxygen. Professor Seegen, however, has found that the death in such cases is not due to the removal of anything from the oxygen, but to actual poisoning by products of tissue waste. In some experiments he noticed that the air in which the animal had been confined for a while, although its chemical composition was correct, had a disagreeable smell, and the animal after its removal soon died of pneumonia. When the air which the animal was breathing was extracted from one end of the compartment, made to pass through a red-hot tube, and introduced at the other end so that any organic matter formed during respiration was consumed, the animal could be kept for almost any length of time without injury to its health.

USES.—Oxygen has been applied to the surface in atonic, scrofulous, and syphilitic ulcers, and in cases of senile or other gangrene. It has more especially been employed in cases of respiratory disease such as emphysema, bronchial dilatation, phthisis, and gangrene of the lung, in asphyxia from noxious vapours or anæsthetics, and in spasmodic asthma. It seems to be chiefly of use in the latter disease. It has been employed also in cases of difficulty of breathing, of cardiac disease, and of anæmia from loss of blood or suppuration. It has been employed also in conditions where oxidation seems to be deficient, as in gout and diabetes, where sometimes the sugar disappears from the urine during its inhalation. Oxygen has also been used in the treatment of epilepsy and spasm.

It has been strongly recommended by Bert in paralysis occurring

in divers, due to their sudden ascension from a great depth to the surface. When submerged at a considerable depth the pressure of the air causes both nitrogen and oxygen to be absorbed by the blood; when they return to the surface the oxygen enters into combination, but the nitrogen is set free in the blood-vessels, forming minute bubbles, which act as emboli, obstructing the circulation in the nerve-centres and in the lungs, thus producing paralysis and dyspnœa. The nitrogen diffuses as readily into an atmosphere of oxygen as into an absolute vacuum; and therefore when animals, in which such a state has been artificially induced, have been made to breathe pure oxygen, bubbles of nitrogen disappear from the blood, the circulation is speedily restored to its normal condition, and the paralysis and dyspnœa disappear.

Its inhalation has been recommended in cases of cholera.

OZONE. Not officinal.

When an electric spark is passed through air a peculiar smell is noticed; this is due to the formation of ozone. The electricity in passing through the air appears to break up the molecules of ordinary oxygen (Fig. 127), and the atoms which are thus dissociated



a *b*

FIG. 127.—Diagram to illustrate the formation of ozone by electricity. *a* represents oxygen, through which a spark is passing; *b* after it has passed. The double rings are intended to represent molecules of oxygen, each containing two atoms. As the electric spark passes through the oxygen it breaks up the first molecule, carrying one atom on to join the second molecule of oxygen, and form one of ozone. The atom which is left joins another molecule of oxygen, and also forms ozone. (After Lockyer)

join together so as to form ozone. It is also formed by the slow oxidation of phosphorus (Fig. 128), and is formed also by protoplasm (p. 54). Two atoms are present in a molecule of oxygen and three in that of ozone. When electricity is passed through a quantity of oxygen, contained in a tube over mercury, so as to convert a portion of it into ozone, it becomes condensed in bulk and acquires much greater chemical activity. On warming it again to about 300° C. the molecules of ozone become again dissociated, ordinary oxygen is formed, the gas then returns to its

original bulk, and it loses its active properties. Ozone has a most powerful oxidising property, attacking metals and forming oxides,



a *b*

FIG. 123.—Diagram to represent the formation of ozone by the oxidation of phosphorus. *a*, during oxidation; *b*, after oxidation. The phosphorus in uniting with oxygen splits up the molecules. Some of the atoms combine with the phosphorus to form phosphoric acid. Others reunite to form oxygen, and others form ozone ($3P + 15O_2 = 3PO_5 + 6O_2 + O_3$).

and destroying organic substances, such as paper and caoutchouc. It has a curious action upon albumen, already described (p. 44), and decomposes blood. As might be expected, it is exceedingly poisonous to low organisms, and is fatal also to the higher animals.

Its effect appears to be due in a great measure to its having such a powerful irritant and even destructive effect on the albuminous tissues of the respiratory passages, that it causes reflex depression of the heart and interferes with the ordinary respiration in the lungs. It thus diminishes instead of increasing oxidation. In animals it causes sometimes quickness, and sometimes slowness of the respiration (*vide* p. 206), and produces excitement followed by exhaustion and sometimes convulsions.

When it is present only in small quantity in air, it may be inhaled without any disagreeable effects, and is, according to Binz, a decided soporific.

USES.—It has been recommended in cases similar to those already mentioned under oxygen; and also in infectious diseases, and in diphtheria, where it is likely to be useful by destroying low organisms, which produce the disease.

PEROXIDE OF HYDROGEN (H_2O_2; 34). Not officinal.

PREPARATION.—It is generally prepared by treating barium di-oxide with dilute sulphuric acid ($BaO_2 + H_2SO_4 = H_2O_2 + BaSO_4$) and filtering off the aqueous solution from the sulphate of barium which is precipitated.

PROPERTIES.—When the watery solution thus obtained is evaporated it forms a transparent oily liquid, but it is generally employed in the form of a 10 to 15 per cent. solution in water or in ether. The ethereal solution is commonly known by the name

of ozonic ether. The ethereal solution is generally more stable than the aqueous solution, which, especially if kept in a badly-stoppered bottle, soon decomposes into water and oxygen.

ACTION AND USES.—Peroxide of hydrogen has a powerful oxidising effect upon organic substances, readily giving off an atom of oxygen in much the same way as ozone. It has therefore been used for similar purposes to ozone. It destroys bacteria, and is a powerful antiseptic.[1] When mixed with the secretion from chancre it destroys its infective power; and it has been employed as a local dressing for chancres, and also as an application for diphtheritic sore throat. Curiously enough, although when mixed with blood or with albumen it becomes decomposed almost immediately, it appears to be tolerably stable in the body, and is said to have been found in the urine after it has been taken by the mouth. Its internal administration has been recommended in rheumatism, scrofula, diabetes, and cardiac disease.

CARBON (C; 12).

This element is employed in medicine in the form of animal and vegetable charcoal.

Carbo Ligni, B.P. and U.S.P. WOOD CHARCOAL.—Wood charred by exposure to a red heat without access of air, B.P. Charcoal prepared from soft wood, U.S.P.

PREPARATION.—It is prepared either by burning the wood under turf, or in retorts, so that the hydrogen and oxygen are driven off and charcoal alone remains. If too much air be allowed to have access, the charcoal itself becomes burnt, and too large a proportion of ash comes to be present.

CHARACTERS.—In black, brittle, porous masses, without taste or smell, very light, and retaining the shape and texture of the wood from which it was obtained. When pulverized it forms a fine black powder.

IMPURITIES.—Too much ash.

TESTS.—When burned at a high temperature with free access of air it leaves not more than two per cent. of ash.

DOSE.—20–60 grains.

OFFICINAL PREPARATION.

B.P.	U.S.P.
Cataplasma Carbonis.	None.

B.P. Cataplasma Carbonis. CHARCOAL POULTICE.—Powdered charcoal 1; bread 4; linseed-meal 3; boiling water 20. Mix the water, bread, and linseed-meal, then add half the charcoal and sprinkle the remainder on the surface. By simply sprinkling a part of the charcoal on the surface of the poultice it is not wetted, and its disinfectant power not destroyed.

[1] Professor Dewar, Cambridge, unpublished experiments.

ACTION.—Charcoal has the power of absorbing gases and of condensing them within its pores. Amongst others it absorbs oxygen readily. The oxygen thus condensed has an oxidising action akin to that of ozone, and the charcoal parts with it readily when brought into contact with oxidisable substances, whether these substances be in solution or in the form of gas, but especially the latter. Thus it oxidises and decomposes sulphuretted hydrogen very readily, and also quickly oxidises and destroys decomposing organic substances. It thus acts as a deodoriser and disinfectant. It only possesses this power, however, when it is dry, and loses it when it is wet. For this reason the whole of it is not mixed with the poultice in the cataplasma carbonis, a part of it being merely sprinkled on the surface. Its oxidising power is destroyed completely only when the charcoal is thoroughly saturated with water, and this occurs with difficulty even when it is thrown into water. Consequently its oxidising power may still be exerted in fluids to which it has been freshly added.

USES.—It is employed as a deodoriser and disinfectant in traps through which sewer gases may pass, and in a respirator for persons exposed to sewer gas or other noxious emanations. As a poultice it is employed for fœtid and phagedenic ulcers and gangrene. It forms a useful tooth-powder, cleaning the teeth rapidly, but it is much more apt to scratch the enamel than a tooth-powder of chalk. When taken into the stomach it relieves flatulent distension and acidity in the stomach and intestines. It has thus been used in acute and chronic dyspepsia, gastrodynia, and even cancer of the stomach; in constipation, flatulent distension of the colon, diarrhœa, dysentery, cancer of the rectum. It has been supposed to relieve flatulence by absorbing the gases in the stomach and intestines, but as it will become wet by the juices of the intestinal canal after it is swallowed, it is much more probable that it acts mechanically, by removing mucus, or by stimulating the circulation and peristaltic movements in the walls of the stomach and intestine. This is rendered all the more probable by the fact that in some cases where it is useful the patient is likewise benefited by beginning each meal with solid food, and abstaining from liquids until the meal is well over, so that the stomach may receive a mechanical stimulus from the food, which would be prevented by the ingestion of much liquid at the beginning of the meal. In large doses it acts as a mild purgative. It has also been used in diabetes and in intermittent fevers.

ADMINISTRATION.—It is either used in the form of powder, or made up into biscuits or lozenges.

Carbo Animalis, B.P. and U.S.P. ANIMAL CHARCOAL.—Bone black. Animal charcoal prepared from bone, U.S.P. The residue of bones, which have been exposed to a red heat without the access of air. Consists principally of charcoal and phosphate and carbonate of lime, B.P.

Carbo Animalis Purificatus, B.P. and U.S.P. PURIFIED ANIMAL CHARCOAL.

PREPARATION.—By dissolving out the earthy matter by hydrochloric acid, washing and drying.

CHARACTERS.—It is a black powder without taste or smell. It absorbs colouring matters, and tincture of litmus diluted with 20 times its bulk of water agitated with it and thrown upon a filter passes through colourless. It is insoluble in all reagents.

IMPURITIES.—Too much ash.

TEST.—When burnt at a high temperature with a little red oxide of mercury and free access of air, it leaves only a slight residue.

DOSE.—20-60 grains.

USES.—From its power of absorbing colouring matters, animal charcoal is used in the preparation of organic alkaloids, for the purpose of decolorising them. It not only carries down colouring matters with it, but alkaloids as well, and therefore a considerable loss is occasioned in the process of bleaching. Advantage has been taken of this power to use animal charcoal as an antidote in poisoning by opium, aconite, nux vomica, etc. The alkaloid is removed from solution by the animal charcoal and retained by it with considerable pertinacity. It would, however, be gradually dissolved out if allowed to remain too long in the stomach, and therefore the stomach-pump, or emetics, must be used in addition. As an antidote it is used in doses of a tablespoonful frequently repeated.

SULPHUR (S : 32).

Sulphur is found native in volcanic districts, and occurs in combination with metals as sulphides in various ores, especially in iron and copper pyrites.

Sulphur Sublimatum, B.P. and U.S.P. SUBLIMED SULPHUR, FLOWERS OF SULPHUR.

PREPARATION.—Native sulphur is usually mixed with earthy impurities. When heated the sulphur volatilises. If the vapour is condensed in a large room it falls in a fine powder. If condensed in water it forms masses, which, when melted and run into moulds, form roll sulphur, but this is not officinal. Ores containing sulphur are decomposed by heat, and part of the sulphur they contain sublimes, and may be condensed in the same way as native sulphur.

CHARACTERS.—A fine, citron-yellow powder, of a slight characteristic odour and generally of a faintly-acid taste and an acid reaction from slight oxidation occurring with the formation of small quantities of sulphurous acid. It is insoluble in water or

alcohol, slightly soluble in oils and fats, and completely soluble in carbon disulphide. When ignited it burns with a blue flame, forming sulphurous acid gas and leaving no residue, or only a trace.

IMPURITIES.—Ores are apt to contain arsenic, and when this is the case, sulphide of arsenic, being volatile, sublimes along with the sulphur and renders it impure. During sublimation the sulphur may undergo oxidation, and thus sulphurous or sulphuric acids may be present in it as impurities.

TESTS.—*Vide* SULPHUR LOTUM.

OFFICINAL PREPARATIONS.

B.P.	DOSE.	U.S.P.
Confectio Sulphuris, as laxative	60-120 grs.	Sulphur Lotum.
,, ,, as alterative	5-20 grs.	,, Præcipitatum.
Unguentum Sulphuris.		Unguentum Sulphuris.

B.P. Confectio Sulphuris. CONFECTION OF SULPHUR.—Sulphur 4 ; acid tartrate of potash 1 ; syrup of orange peel 4. The acid tartrate of potash is added for the purpose of increasing the secretion from the intestine, while the sulphur stimulates peristaltic action.

Unguentum Sulphuris. SULPHUR OINTMENT.—Sulphur mixed with benzoated lard, 1 part to 4, B.P. ; 30 to 70, U.S.P. The U.S.P. ointment is nearly twice as strong as the B.P.

U.S.P. Sulphur Lotum. WASHED SULPHUR.

PREPARATION.—By digesting sulphur with dilute ammonia, thoroughly washing, drying at a gentle heat and passing through a No. 30 sieve. In this process the ammonia not only neutralises the sulphurous or sulphuric acid, but dissolves out and removes sulphide of arsenic, which is soluble in it.

CHARACTERS AND IMPURITIES.—Those of sulphur sublimatum.

TESTS.—Water agitated with it should not redden blue litmus paper (absence of free acid). If washed sulphur be digested with two parts of water of ammonia, and the mixture filtered, the filtrate, on being supersaturated with hydrochloric acid, should remain unaltered (absence of arsenious sulphide), nor should a precipitate make its appearance on passing hydrosulphuric acid through the filtrate (absence of arsenious acid).

OFFICINAL PREPARATIONS.

U.S.P.

Pulvis Glycyrrhizæ Compositus.
Sulphuris Iodidum.
Unguentum Sulphuris Alkalinum.

U.S.P. Unguentum Sulphuris Alkalinum. ALKALINE SULPHUR OINTMENT. Sulphur 20 ; carbonate of potassium 10 ; water 5 ; benzoated lard 65.

Sulphur Precipitatum, B.P. and U.S.P. PRECIPITATED SULPHUR, LAC SULPHURIS, MILK OF SULPHUR.

PREPARATION.—By boiling sulphur with slaked lime and water. Calcium sulphide and calcium hyposulphite are thus formed.

Hydrochloric acid is then added, which decomposes these substances and throws down sulphur in the form of an exceedingly fine powder which is washed until the washings are tasteless (U.S.P.), and have no acid reaction and cease to give a precipitate with oxalic acid (B.P.), showing that both acid and lime have been removed.

CHARACTERS.—Being in a finer state of division than sublimed sulphur, it looks almost white with only a slight tinge of yellow. Otherwise its characters are the same.

IMPURITIES.—There is a great temptation to fraudulent manufacturers to use sulphuric acid instead of hydrochloric acid. It is not only cheaper but it yields a large product consisting to a great extent of sulphate of lime which is precipitated along with the sulphur instead of remaining in solution like the calcium chloride which is formed when hydrochloric acid is employed.

With Hydrochloric Acid, $2CaS_5 + CaS_2O_3 + 6HCl = (S_2)_6 + 3H_2O + 3CaCl_2$
,, Sulphuric ,, $2CaS_5 + CaS_2O_3 + 3H_2SO_4 = (S_2)_6 + 3H_2O + 3CaSO_4$

Besides this there are the other impurities which may be present in the sublimed sulphur employed in the process.

TESTS.—It should be completely volatilised by heat and leave no residue of sulphate behind. Under the microscope it should exhibit only minute globules of sulphur and no crystals of sulphate. The absence of the impurities contained in sublimed sulphur is ascertained by the tests already given.

DOSE.—Of precipitated sulphur, as alterative 10 grs., as laxative 30—60 grs.

Sulphuretted Hydrogen or HYDROGEN SULPHIDE (H_2S; 34). A colourless gas, with a smell of rotten eggs. Used only as a test.

PREPARATION.—By pouring diluted sulphuric acid on sulphide of iron. By passing the gas into cold water a solution is obtained.

PROPERTIES.—It precipitates most metals as sulphides from acid solutions, the precipitate with arsenic being yellow; antimony, orange; cadmium, yellow; copper, lead, mercury, and silver, black; bismuth, brown; gold and platinum, brownish black.

General Action of Sulphuretted Hydrogen.—As sulphuretted hydrogen is formed in small quantities from sulphur when the latter is used in various ways, it may be more convenient to take its action before that of sulphur. It is very destructive to plant life even in very minute quantities. There is a curious difference between the action of sulphuretted hydrogen and that of sulphurous acid on plants. The latter seems to act as an irritant, causing the leaves to crumple up and fall off, but even when the leaves are destroyed by sulphurous acid the plant may again recover. Sulphuretted hydrogen causes the leaves simply to become flaccid and droop, but when this has once taken place the plant does not recover.

In animals it destroys the functions of all tissues, and in consequence has two actions which are well marked, (1) decomposing the **blood** and thus producing symptoms of asphyxia, and (2) paralysing the **nervous system** and **muscles.** It is **absorbed** by the skin, by the lungs, mucous membrane of the alimentary canal, and subcutaneous cellular tissue, and may produce symptoms of poisoning through any of these channels. In **frogs,** which are less affected than mammals by interference with the respiration, the symptoms produced by sulphuretted hydrogen are those of paralysis of voluntary motion and reflex action, preceded by a stage of restlessness. In **mammals** the symptoms are those of asphyxia; muscular tremors occur, and are succeeded by asphyxial convulsions and death. Most cases of poisoning by sulphuretted hydrogen in man occur from inhalation of the gas which is often found in large quantities in cesspools.

One case has been recorded where symptoms of poisoning occurred from excessive formation of the gas in the intestinal canal and subsequent absorption into the blood. Cases of poisoning are best treated by artificial respiration.

Special Action.—Even in minute quantities it destroys the catalytic action of many substances on peroxide of hydrogen. In this respect as well as in many of the symptoms it produces, it resembles hydrocyanic acid.

On the **blood.** It first reduces and then decomposes hæmoglobin. Both the blood and the muscles of frogs poisoned by it exhibit a greenish colour. As death occurs in mammals before the blood has become so extensively changed, it simply exhibits the characters of asphyxial blood. It induces rigor mortis rapidly in the **muscular substance** both of the voluntary muscles and of the frog's heart.

ACTION OF SULPHUR.—Sulphur, when brought into contact with living **protoplasm,** enters into combination and forms sulphuretted hydrogen or sulphurous acid. When sulphur is sprinkled over actively-growing fungi, like those which cause the vine disease, these gases are formed and the fungi destroyed.

Sulphur has little or no action on the **skin,** excepting a mechanical one. When taken into the **intestinal canal,** a considerable part of it again passes out unchanged; a little of it, however, appears to be converted into sulphides and into sulphuretted hydrogen. The latter is **excreted** by the breath, and may give to it the peculiar disagreeable smell of rotten eggs. It is also excreted by the skin, so as to blacken any silver articles which may be worn about the person. The sulphides give rise to increased peristaltic action of the bowels so that the motions become more frequent and softer; colicky pains are sometimes produced. The sulphides, after absorption into the blood, are excreted in the urine, chiefly as sulphates.

USES.—It has been applied by insufflation to the throat in diphtheria, in order to destroy the organisms present in the pharynx, in the same way as in the vine disease. I have seen one case do very

well under this treatment; but its general efficacy is by no means certain. In the form of ointment it is used in scabies to kill the acarus which is the cause of the disease. Internally it is employed as a mild laxative in cases of constipation where active purgatives are inadmissible, as in pregnancy, in hæmorrhoids, fissure of the anus, and stricture or prolapsus of the rectum. It has been used also in cases of lead-poisoning, to prevent the reabsorption of the lead from the intestine.

It has been found useful in cases of sexual irritation arising from hæmorrhoidal congestion (pp. 394 and 397), and also in the nervous excitement and other disturbances accompanying the menopause.

It exerts a beneficial action on the tissues in chronic rheumatism and gout, and is especially useful in the form of sulphurous waters. During its elimination by the lungs it is supposed to have a beneficial action on them, and it is consequently used in chronic bronchitis.

HALOGEN ELEMENTS.

Fluorine, Fl.; 19 or 19·1. **Chlorine,** Cl.; 35·5 or 35·4. **Bromine,** Br.; 80 or 79·75. **Iodine,** I.; 127 or 126·53.

These substances form a series in which the atomic weights are nearly in the relation of 1, 2, 4, and 7 (*vide* also p. 15). They are distinguished by the activity of their chemical affinities and the number of compounds they form.

General Source.—The name halogen (from ἅλς the sea) has been given to the group, because its most important members, chlorine, bromine, and iodine, are derived from the sea; chlorine being obtained from sea-salt, bromine from sea-water, iodine from sea-weed.

General Characters.—They are all very volatile. At ordinary temperatures, chlorine is a gas, bromine a liquid, and iodine a solid, but both bromine and iodine give off vapour freely. On account of their active chemical affinities they unite directly with metals, as is seen in the officinal processes for the preparation of iodide of iron and green iodide of mercury. They have all a great affinity for hydrogen, and are therefore powerful decomposers of organic matter, destroying organic colours and disagreeable emanations of organic origin, as well as decomposing sulphuretted hydrogen ($H_2S+Cl_2=2HCl+S_2$) and ammonia which occur amongst the products of decomposition of organic matter. They are therefore used as deodorisers and disinfectants. Chlorine is used for bleaching, but bromine and iodine form coloured compounds with many organic substances, and so are not used for this purpose.

Probably the bleaching power of chlorine is not due to its decomposing organic colours by removing hydrogen from them, but rather to its decomposing water by removing the hydrogen from

it, and thus setting free nascent oxygen, which is the direct destroyer of organic matters. The reason for this supposition is that chlorine does not act upon colouring matters when they are dry, but only when moist.

MODE OF PREPARATION.—Chlorine, bromine, and iodine are all prepared by expelling them from their compounds with the alkaline metals by means of sulphuric acid and manganese dioxide.

Chlorine is prepared by putting sodium chloride, sulphuric acid and manganese dioxide into a retort, applying heat and collecting the chlorine gas in a receiver, by displacement or over warm water, or passing it into cold water which dissolves it freely, forming liquor chlori B.P. or aqua chlori U.S.P.

Bromine is prepared in a similar manner from the bromides of sodium and magnesium contained in the bittern or mother-liquor left after the salt has crystallised out of sea-water, or out of the brine obtained in salt mines. In order to obtain the bromine pure, the bittern is often not treated directly with sulphuric acid and manganese dioxide. Instead of this the bromine is first separated by passing chlorine through the liquid which is then shaken up with ether. The chlorine decomposes the magnesium bromide and the ether dissolves the bromine thus set free. The bromine is then converted again by potash into bromide, from which bromine is obtained by means of manganese dioxide and acid.

Iodine is prepared in a similar manner to chlorine from the iodides of sodium and magnesium contained in sea-weed. The iodides are obtained from the weed by calcining it in a retort, or by burning it, when the ashes in which they are contained form a hard mass called kelp. This is treated with successive portions of water until the soluble salts are all dissolved out (lixiviation). The solution is filtered, and evaporated to a small bulk, when the less soluble salts, as the sulphates, &c. crystallise out. The mother-liquor containing the iodides of sodium and magnesium is then treated with manganese dioxide and sulphuric acid, and the iodine distils over.

The reactions which occur in the preparations just described are—

Chlorine $2NaCl + 2H_2SO_4 + MnO_2 = Cl_2 + Na_2SO_4 + MnSO_4 + 2H_2O.$

Bromine
$$\begin{cases} 2NaBr + 2H_2SO_4 + MnO_2 = Br_2 + Na_2SO_4 + MnSO_4 + 2H_2O. \\ MgBr_2 + 2H_2SO_4 + MnO_2 = Br_2 + MgSO_4 + MnSO_4 + 2H_2O. \end{cases}$$

Iodine
$$\begin{cases} 2NaI + 2H_2SO_4 + MnO_2 = I_2 + Na_2SO_4 + MnSO_4 + 2H_2O. \\ MgI_2 + 2H_2SO_4 + MnO_2 = I_2 + MgSO_4 + MnSO_4 + 2H_2O. \end{cases}$$

GENERAL ACTION.—As chlorine, bromine, and iodine decompose organic compounds having a disagreeable odour, they have been supposed to have a similar action upon the germs of infectious diseases. Chlorine, and sometimes iodine, are therefore used as **deodorisers** and **disinfectants** in sick rooms. Bromine cannot well be used on account of its abominable smell.

The objections to chlorine or the vapour of iodine as disinfectants are that we do not at all know that they have any disinfecting power in the dilute state, in which only they can be used in a sick room. When applied to the **skin** or mucous membranes they cause a greater or less amount of irritation or inflammation, according to the length of time during which they act, and the greater or less degree of concentration in which they are applied. They probably do not enter the blood in the free state, but combine with bases or with albuminous substances at the place of application, and are **absorbed** as chlorides, bromides, or iodides, or else as albuminous compounds. According to Binz, free chlorine, bromine, and iodine, and all their readily decomposable compounds, have a narcotic action, and paralyse nervous centres in the brain by a direct action on the nervous structures themselves. He considers that they cause death by paralysis of the respiratory centre, and not by paralysis of the heart.

CHLORINE. Cl. 35·5.

A greenish yellow gas with a suffocating odour. Its preparation and general action have already been described (p. 484).

ACTION.—When applied for a long time to the **skin,** as in persons who have to work in an atmosphere containing it, it causes itching, reddening, and inflammation. When applied to the more sensitive **mucous membranes** of the respiratory passages, it acts as a stimulant or irritant. In a concentrated form it may cause death from spasm of the glottis, or intense bronchitis. In a more dilute form it is used as a stimulant, deodorsier, and **disinfectant**. The manner of employing it, is to put a saucer containing salt, binoxide of manganese, and sulphuric acid on a shelf or high piece of furniture in the sick room, and thus allow the chlorine vapour, which is heavier than air, to diffuse itself through the apartment. When placed on the floor it is of little use.

Liquor Chlori, B.P.; Aqua Chlori, U.S.P. CHLORINE WATER.—An aqueous solution of chlorine containing at least 0·4 per cent. of the gas U.S.P., or 2·66 grains in 1 fluid ounce = about 0·6 per cent. B.P.

PREPARATION.—By passing washed chlorine into water, p. 484. The chlorine is directed by the B. and U.S.P. to be prepared from hydrochloric acid and manganese dioxide, instead of from sodium chloride. $4HCl + MnO_2 = Cl_2 + MnCl_2 + 2H_2O$.

CHARACTERS.—A greenish-yellow clear liquid with a strong smell and taste of chlorine. It instantly decolorises dilute solutions of litmus and indigo.

IMPURITIES.—The chief is too little chlorine. When exposed to light it is apt to be decomposed, the chlorine combining with the hydrogen of the water and forming hydrochloric acid. The chlorine water thus loses strength, and it also becomes weaker by the

chlorine escaping when the bottle is imperfectly stopped or frequently opened. A solution of chlorinated soda or lime may be sometimes substituted for chlorine water.

TESTS.—The amount of chlorine is not tested directly but indirectly, by estimating the amount of iodine which a definite quantity of chlorine water liberates from iodide of potassium. In this process chlorine water (439 grains or 1 fluid ounce B.P., or 35·4 gm. U.S.P.,) is mixed with iodide of potassium (20 grains B.P., 0·9 gm. U.S.P.) and water (1 fluid ounce B.P., 20 gm. U.S.P.). The amount of iodine which is set free by the chlorine ($2KI + Cl_2 = 2KCl + I_2$) gives a red colour to the solution, and corresponds in quantity to the chlorine contained in the water. The red solution requires for its decolorisation 750 grain-measures B.P., or 40 cc. U.S.P. of the volumetric solution of hyposulphite of soda. The reaction which occurs is:—

Iodine. Sodium Hyposulphite. Sodium Iodide. Sodium Tetrathionate. Water.

$$I_2 + 2NaH_2S_2O_4 = 2NaI + Na_2S_2O_4 + H_2O.$$

USES.—Chlorine is used in solution as a lotion to foul-smelling ulcers or cancer; as an application to relieve itching in chronic skin diseases; and as a gargle or wash to the mouth in affections of the mouth, throat, and tonsils, especially where they are accompanied by fœtor, as in mercurial ptyalism and ulceration of the tonsils. It is sometimes given internally in cases of blood-poisoning. As an inhalation it has been used in cases of phthisis, it is said with good effect. It is also employed as a stimulant and deodoriser in cases of chronic bronchitis with fœtid sputa. (*Vide* Vapor Chlori, p. 487.)

The aqueous solution is so unstable and liable to lose its strength, that compounds of chlorine from which it can be easily evolved are more convenient for general use. The chief of these are the following compounds with lime and with soda.

Calx Chlorata, B. and U.S.P. CHLORINATED LIME.—A product obtained by exposing slaked lime to the action of chlorine gas so long as the latter is absorbed, B.P. A compound resulting from the action of chlorine upon hydrate of calcium, and containing at least 25 per cent. of available chlorine, U.S.P.

CHARACTERS.—A greyish-white powder having the odour of chlorine and an acrid taste; absorbs carbonic acid and water when exposed to the air, and at the same time gives off chlorine; it is only partly soluble in water. The solution is alkaline and possesses bleaching properties (*e.g.* it bleaches sulphate of indigo).

It is readily decomposed by acids, even by carbonic acid, and thus when exposed to the air chlorine is given off slowly. The addition of a stronger acid causes it to be evolved rapidly. Its probable constitution is $Ca\begin{cases} Cl. \\ OCl. \end{cases}$ This is decomposed by water

into a mixture of calcium chloride and hypochlorite, and as it is usually moist it may be regarded as usually consisting of a mixture of these substances. On the addition of sulphuric acid, hypochlorous and hydrochloric acids are set free, which reacting on one another yield free chlorine. $HClO + HCl = Cl_2 + H_2O$.

REACTION.—The addition of oxalic acid causes the rapid and copious evolution of chlorine and the deposition of oxalate of lime.

IMPURITIES.—Imperfect saturation with chlorine. It is tested volumetrically in a similar way to liquor chlori, the chlorine being set free from it by the addition of hydrochloric acid. The chlorine thus liberated should amount to 30 per cent. B.P., 25 per cent. U.S.P.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
Liquor Calcis Chloratæ.	Liquor Calcis Chloratæ.
Vapor Chlori.	

Liquor Calcis Chloratæ. SOLUTION OF CHLORINATED LIME.—It is a solution of 1 lb. to the gallon of water, and when tested volumetrically it should contain 13 grains of available chlorine in 1 fl. oz.

B.P. Vapor Chlori. INHALATION OF CHLORINE.—Put 2 ounces of chlorinated lime into an inhaler or jug, moisten it with water and let the vapour be inhaled.

Liquor Sodæ Chloratæ, B. and U.S.P. SOLUTION OF CHLORINATED SODA. (Labarraque's disinfecting fluid.)

PREPARATION.—By passing chlorine into a solution of sodium carbonate B.P., or by decomposing chlorinated lime by sodium carbonate U.S.P.

CHARACTERS AND TESTS.—A colourless alkaline liquid, with astringent taste and feeble odour of chlorine. It behaves like a solution of chlorinated lime, but is not precipitated by oxalic acid nor oxalate of ammonia. (Distinction from and absence of solution of chlorinated lime).

DOSE.—10 to 20 minims.

OFFICINAL PREPARATION, B.P.

Cataplasma Sodæ Chloratæ.

Cataplasma Sodæ Chloratæ.—Linseed meal 4; solution of chlorinated soda 2; boiling water 8.

USES.—Chlorinated lime is chiefly employed as a disinfectant and a deodoriser. In sick rooms some of it is put in saucers, and either simply moistened and exposed to the air, when it is gradually decomposed by the carbonic acid, or acid is added to it according to the amount of chlorine which it is wished to evolve. It is employed also for disinfecting typhoid stools, water-closets and sewers. For this purpose it is used either in powder or solution. A solution is used to disinfect the sheets and bedding of patients suffering from infectious diseases.

Solutions of chlorinated lime or of chlorinated soda may be employed instead of chlorine water or permanganate of potash for washing the hands after dissecting or performing post-mortem examinations. They are applied externally to wounds and ulcers of all sorts which have a fœtid discharge and a tendency to slough.

Not only do they remove the fœtor, but they often induce a healthy action in the tissues themselves; and instead of the ulceration or sloughing extending farther and farther, the slough is thrown off and leaves behind it a healthy healing surface. As the removal of sloughs is aided by heat, we have in the B.P. the poultice of chlorinated soda.

Like chlorine they are destructive to plant life, and they are therefore useful in skin diseases depending on the presence of parasitic fungi, such as ringworm of the scalp, and in scabies which is due to the presence of a parasitic acarus. As they have a stimulant action on the skin, they are sometimes useful in eczema and prurigo.

They are employed as gargles, or washes to the mouth when fœtid ulcers occur in these parts, as in ptyalism or in scarlatina; as an injection into the nose they have been used to lessen the discharge and to remove the fœtor in ozæna, a disease in which the discharge from the nostrils is sometimes so disgusting as to be almost unendurable to the patient himself as well as to those around him. They are likewise useful in fœtid discharges from the vagina, such as occur when the uterus is the seat of malignant disease.

Internally they have been employed in so-called putrid fevers, when it was imagined there was a special tendency to decomposition in the blood, such as typhus and malignant scarlatina. They have been given more especially in these diseases when there was great prostration of strength, with fœtid evacuations and a dry and furred tongue.

BROMUM. Br. 80.

Bromine, B. and U.S.P. A liquid non-metallic element obtained from sea-water and from some saline springs.

PREPARATION.—*Vide* p. 484.

CHARACTERS.—A dark brownish-red, very volatile liquid, with a strong, disagreeable odour. The solution renders cold starch-water yellow.

IMPURITIES.—Iodine.

TEST.—When agitated with sufficient soda to render the fluid very slightly alkaline, it forms a colourless liquid, which, if coloured by a further addition of a little bromine, does not become blue on the subsequent addition of a cold solution of starch. B.P. (absence of iodine).

If an aqueous solution of bromine be poured upon reduced iron and shaken with the latter until it has become nearly colourless, then filtered, mixed with gelatinised starch, and a few drops of bromine solution be now carefully poured on the top, not more than a very faint blue zone should appear at the line of contact of the two liquids (limit of iodine), U.S.P.

USES.—Bromine, although a powerful disinfectant, is not much used on account of its exceedingly fœtid and disagreeable smell. It is a powerful irritant, and when inhaled without sufficient

dilution with air will produce pneumonia. Taken in small doses, for a length of time, it has produced mental depression, drowsiness, and stupidity. It is only used in the form of its potassium, sodium, ammonium, calcium, and zinc salts, and of hydrobromic acid, which have not its powerfully irritant local action. It is introduced into the pharmacopœias for their preparation.

IODUM. I. 127 or 126·6, U.S.P.

Iodine.—A non-metallic element obtained principally from the ashes of sea-weed.

PREPARATION.—*Vide* p. 484.

CHARACTERS.—Heavy bluish-black rhombic plates of a peculiar odour and metallic lustre, which, when heated, yield a beautiful violet-coloured vapour; very sparingly soluble in water, but freely dissolved by alcohol, by ether, and by a solution of iodide of potassium. The aqueous solution strikes a deep blue colour with starch.

IMPURITIES.—Moisture, metallic impurities fraudulently added, cyanide of iodine (the nitrogen in this is yielded by marine animals amongst the sea-weed), chloride of iodine, chlorine and bromine.

TESTS.—It should not adhere to the sides of the bottle and its solution in chloroform should be clear and limpid (absence of moisture). It sublimes as a purple vapour without leaving any residue (absence of fixed impurities), and the portion that first comes over does not include any slender colourless prisms emitting a pungent odour (absence of cyanide of iodine); 12·7 grains dissolved in an ounce of water containing fifteen grains of iodide of potassium require for complete discoloration 1,000 grain-measures of the volumetric solution of hyposulphite of soda.

PREPARATIONS. B.P.

Cadmii Iodidum.
Ferri Iodidum.
Hydrargyri Iodidum Rubrum.
,, ,, Viride.
***Linimentum Iodi,** alcoholic solution (1 in 9).
Linimentum Potassii Iodidi cum Sapone, aqueous solution.
***Liquor Iodi** (1 in 24).
Pilula Ferri Iodidi.
Potassii Iodidum.
Sulphuris Iodidum.
Syrupus Ferri Iodidi.
***Tinctura Iodi,** alcoholic solution (1 in 40).
Unguentum Cadmii Iodidi.
* ,, ,, **Iodi** (1 in 31).
,, ,, Plumbi Iodidi.
,, ,, Sulphuris Iodidi.
***Vapor Iodi** (Tincture of Iodine, 1 fl. dr. mixed with 1 fl. oz. of water, gently warmed, and the vapour inhaled.

U.S.P.

Ammonii Iodidum.
Argenti Iodidum.
Arsenici Iodidum.
***Liquor Iodi Compositus** (5 in 100).
Plumbi Iodidum.
Potassii Iodidum.
Sodii Iodidum.
Sulphuris Iodidum.
***Tinctura Iodi** (8 in 100).
***Unguentum Iodi** (4 in 100).
,, Plumbi Iodidi.
,, Potassii Iodi.
Zinci Iodidum.

The preparations marked with * in the preceding list contain iodine in a free state. The others contain it in a state of combination.

Sulphuris Iodidum. IODIDE OF SULPHUR, B.P. and U.S.P.

PREPARATION.—By fusing iodine and sublimed sulphur together.

CHARACTERS.—Greyish black crystalline lumps. It smells like iodine and stains the skin. When boiled with water it is decomposed, iodine passing off and sulphur remaining.

OFFICINAL PREPARATION, B.P.

Unguentum Sulphuris Iodidi.—Ointment of iodide of sulphur (30 grains to an ounce of prepared lead).

U.S.P.

None.

USES.—It has been given internally in scrofula, skin diseases, and glanders. It is used externally as ointment in lupus and parasitic skin diseases.

Iodine is rendered much more soluble either in water or spirit by the addition of iodide of potassium, hence this substance is used in the liniment, liquor, tincture, and ointment of the B.P., and in the compound solution and ointment of the U.S.P. It is not contained in the tincture of the U.S.P., which is a simple solution of iodine in alcohol.

DOSE.—The only preparations of iodine used for internal administration are the tincture B.P. and U.S.P., the liquor B.P. and compound solution U.S.P., of all of which the dose is 5 to 20 minims.

PHYSIOLOGICAL ACTION.—Like chlorine and bromine, iodine is a powerful antiseptic and oxidising agent. When applied to the unbroken **skin,** iodine stains it of a dark yellowish-brown colour, causes slight warmth, and afterwards a little itching. In stronger solutions it will cause a painful burning sensation, and desquamation of the epidermis. In still stronger solution it may produce vesication. When taken internally, in small doses, it acts as an irritant to the **intestinal canal,** causing catarrh of the mucous membrane. When absorbed into the blood it somewhat increases the rapidity of the **pulse.** It has little action upon blood-pressure. Its influence upon the **temperature** is very slight, but seems rather to raise it. Iodine appears to have a tendency to cause **absorption** of enlarged glands and thickenings caused by chronic inflammation. It seems to combine with such metals as lead and mercury, which have become deposited in the tissues in cases of chronic poisoning, forming with these soluble iodides, which are eliminated in the same way as iodine itself. It is **eliminated** by the urine, nasal mucous membrane, saliva, intestinal mucus and milk, in all of which it may be readily detected. It appears to be eliminated even more readily by the saliva than by the urine (p. 313), and on this account it may remain a considerable time in the body. During the

process of elimination it may irritate those parts where it is set free from its compounds, as the nose or skin. Even in small doses it may cause symptoms of **iodism.** These consist in irritation, either of the nose or intestinal tract; the most prominent are great running at the nose, lacrymation, and sometimes frontal headache. Similar symptoms are produced by exposure to the fumes of iodine for a length of time. The nasal symptoms may be accompanied or replaced by symptoms of gastric irritation, loss of appetite, slight nausea, and tendency to looseness of the bowels. The **symptoms of poisoning**, such as have occurred from the injection of large quantities of iodine solution into the ovarian cyst, were first, collapse, followed after a little while by an appearance of fever, with rapid pulse and flushed face, but without any rise of temperature. This condition passed off in several days, but during apparent convalescence the patient suddenly died. Small doses of iodine, by improving the health of patients, may increase the menstrual flow, and may act as aphrodisiacs. Larger doses generally have a very marked **anaphrodisiac** action, and it has been stated that long continued use has produced atrophy of the mammæ, ovaries, and testes. It has been stated that very large doses affect the **nervous system,** causing delirium, and twitching or paralysis of the muscles (p. 485).

USES.—Iodine applied to the epidermis acts as a parasiticide, and may be used, in cases of tinea, either alone or combined with tar to destroy parasitic fungi. Its solution, painted on the surface, is useful in removing muscular pains, and in causing absorption of thickening around joints, or of enlarged strumous glands. When painted on the surface it sometimes causes absorption of the enlarged thyroid gland in goitre, and, when outward application is insufficient, success is sometimes obtained by injecting from ten to thirty minims of tincture of iodine into the substance of the tumour by means of a hypodermic syringe, care being taken to avoid injection into a vein. Its solution, painted on the surface, is also useful in causing absorption of fluid from serous cavities, as pleurisy. Sometimes, after the fluid has been evacuated from a serous sac, such as the pleura, or the tunica vaginalis in hydrocele, or from ovarian cysts, a dilute tincture of iodine is injected into the sac to prevent the fluid from again accumluating.

In removing slight consolidation of the lung, remaining after pneumonia or pleurisy, or in cases of commencing phthisis, the external application of liniment of iodine is very useful. It should be painted on the surface, every second or third day, so as always to keep one part a little tender. By mixing the liniment with the tincture in varying proportions any degree of strength can be obtained. Cases of ozœna are sometimes much benefited by washing out the nose with a solution of common salt to which a few drops of tincture of iodine have been added. The vapour of iodine is employed in chronic bronchitis and phthisis.

On account of its irritating action on the intestinal mucous membrane, iodine is rarely given internally, its place being supplied by iodide of potassium, but some consider that iodine is sometimes more effectual.

The liquor iodi B.P., or compound solution of iodine U.S.P., is useful in arresting vomiting when administered internally in doses of 3 to 5 minims.

CHAPTER XXIII.

ACIDS.

General Characters.—It is somewhat difficult to get a correct definition of an acid. Most of them have a sour taste and redden blue litmus: they combine with alkalies and destroy the power which these have of turning red litmus-paper blue.

They may be regarded as compounds of hydrogen with certain radicals, hydrogen being readily displaced by other bases. Some acids, as boric and carbolic, have no sour taste. Carbolic acid does not redden litmus-paper, but it is in reality an alcohol, although in chemical combinations it behaves like an acid.

General Preparation of Acids.—Most acids are prepared by liberating them from their alkaline salts by means of sulphuric acid. When they are volatile they are separated by distillation, and when non-volatile by crystallisation.

Sulphuric acid, which is of such importance in the preparation of other acids, is itself prepared by oxidising the fumes of sulphur by means of nitric acid. Sulphur is burnt, and the sulphurous oxide thus produced is conducted along with the vapour of nitric acid into a large leaden chamber where it is mixed with steam. Sulphurous oxide is oxidised by the nitric acid and sulphuric oxide is formed, which uniting with the watery vapour forms sulphuric acid. The nitric acid is deoxidised in this process into nitric oxide, this unites with the oxygen of the air to form nitric peroxide, and this again supplies fresh oxygen to the sulphurous acid, $NO_2+SO_2+H_2O=NO+H_2SO_4$. In this way a small quantity of nitric acid is sufficient to oxidise a large quantity of sulphuric acid; reduction and reoxidation going on alternately in the nitrous fumes. The sulphuric acid formed in the leaden chamber is drawn off and evaporated to the proper strength.

The acids which are prepared by liberation from their salts by sulphuric acid are given in the following tables:—

Volatile Acid.	Prepared from	By addition of Sulphuric Acid and
Carbonic Acid.	Any carbonate, generally carbonate of lime.	Conducting into water or alkaline solution, according to the purpose required.
Hydrochloric Acid, B. and U.S.P.	Sodium chloride.	Distilling into water, which dissolves the acid.
Nitric Acid, B. and U.S.P.	Sodium Nitrate, or Potassium Nitrate.	Distilling.
Acetic Acid, B. and U.S.P.	Crystallised Sodium Acetate.	Do.
Glacial Acetic Acid, B. and U.S.P.	Dried Sodium Acetate.	Do.
Dilute Hydrocyanic Acid, B. and U.S.P.	Potassium Ferrocyanide.	Distilling into water.
Dilute Hydrobromic Acid, U.S.P.	Potassium Bromide.	Crystallising out potassium sulphate, distilling the mother-liquor, and diluting the distillate.

Sodium chloride and sodium nitrate are found native: the sodium acetate is prepared from gas liquor by saturating with sodium carbonate.

In preparing hydrocyanic acid the cyanide is not employed, but the ferrocyanide which is prepared by heating together animal refuse and iron filings and potassium carbonate.

Non-Volatile Acid.	Prepared from	By addition of Sulphuric Acid and
Tartaric Acid, B. and U.S.P.	Tartrate of lime made from acid tartrate of potash.	Subsequent decantation from calcium sulphate, evaporation and crystallisation.
Citric Acid, B. and U.S.P.	Citrate of lime prepared from lemon juice.	Subsequent decantation from calcium sulphate, evaporation and crystallisation.
Boracic Acid B.P., or Boric acid U.S.P.	Sodium borate.	Precipitation; the boracic acid, sparingly soluble in water, falls as a precipitate, and the sodium sulphate is removed by decantation or filtration.

If sulphuric acid were added to citrate or tartrate of potassium or sodium, it would be difficult to separate the acid from the

sulphate. To avoid this, the citrates and tartrates of lime are first prepared, and to these sulphuric acid is added. There results an insoluble calcium sulphate which falls as a precipitate, and the solution of citric or tartaric acid is readily separated by decantation or filtration, and evaporated to crystallisation.

Citrate of lime is prepared by adding chalk to boiling lemon-juice, and washing the colouring matter from the precipitate by hot water. Hot, is employed in preference to cold water because citrate of lime is less soluble in it. Tartrate of lime is prepared from the crude acid tartrate of potash or argol, which is deposited from wine during the process of fermentation. Chalk is first added to a solution of it, whereby a neutral tartrate is formed, $2(KHC_4H_4O_6) + CaCO_3 = CaC_4H_4O_6 + K_2C_4H_4O_6 + CO_2 + H_2O$. This is then decomposed by the addition of calcium chloride or sulphate, $K_2C_4H_4O_6 + CaCl_2 = CaC_4H_4O_6 + 2KCl$.

Hydrobromic acid, although volatile, is not unfrequently prepared without distillation. Hamilton's plan is to dissolve 84¼ grs. potassium bromide in a fluid ounce of water, and add 99 grs. of tartaric acid to it. After standing at a low temperature for twelve hours, acid tartrate of potassium crystallises out, and leaves a solution containing about 10 per cent. of real hydrobromic acid.

Exceptions to the rule that acids are prepared from salts by the addition of sulphuric acid :—

Acid.	Prepared by
Sulphuric Acid.	Oxidising sulphur by means of nitrous fumes.
Phosphoric Acid Dilute	Oxidising phosphorus by heating it with diluted nitric acid until nitrous fumes have ceased to form, and then diluting it to the proper strength.
Oxalic Acid.	Oxidising sugar by heating with nitric acid.
Sulphurous Acid.	Deoxidising sulphuric acid by means of charcoal and passing the fumes into water.
Arsenious Acid.	Roasting arsenical ores, collecting the acid which sublimes, and purifying it by resublimation.
Benzoic Acid.	Heating gum benzoin when the acid sublimes.
Carbolic Acid.	Fractional distillation of tar.
Oleic Acid.	Decomposing lead oleate by hydrochloric acid.
Salicylic Acid.	By passing carbonic acid gas over sodium carbolate which is made by evaporating caustic soda and carbolic acid together to dryness.
Tannic Acid.	Dissolving out from the fresh nut-galls in which it is contained by ether and water.
Gallic Acid.	Dissolving it out from fermented nut-galls by hot water.

GENERAL ACTION OF ACIDS.—They have an affinity for electro-positive or basic substances, and combine with them when they

come in contact. Stronger acids drive out weaker ones from their combination with bases, setting them free; but are themselves sometimes driven out by weaker ones if these form an insoluble combination.

When they come in contact with the tissues they produce changes in a twofold manner; (1) by forming new compounds, (2) by destroying others previously existing. The different acids possess different affinities, and the actions they exert vary with the acid and with the degree of its concentration, weak acids having their affinities easily satisfied. All the tissues of the body are alkaline, and the first effect of acids will be to neutralise the alkali, and if albumen be dissolved in it to precipitate it. If sufficient acid be present, they all, with the exception of nitric acid, again redissolve it. Acids unite with albumen in different proportions, forming acid albumins. When mixed with blood they not only precipitate albuminous substances, but decompose hæmoglobin, forming a substance which holds oxygen with more tenacity than hæmoglobin. They coagulate myosin and produce instantaneous rigidity in muscles. Sulphuric and phosphoric acids have, besides their chemical affinities, a strong attraction for water, and completely decompose the tissues to which they are applied, so that they are most powerful **escharotics.** Nitric acid does not readily redissolve the albumen precipitated by it, and thus forms a barrier to its own action, so that it does not penetrate so deeply as sulphuric acid.

Round the tissue killed by the acids inflammation ensues, and an eschar is separated. When their action is less intense they cause inflammation of the surface of the dermis, and produce **vesication.** Still less concentrated, they precipitate albumen from its solutions in the tissues, act as irritants, and cause contraction of the blood-vessels. This effect is removed by the alkalinity of the blood, and the irritation may be only sufficient to cause a temporary congestion subsequent to the contraction. Then the acids act only as **rubefacients.** As such they are used in the form of baths.

In the **mouth** they cause a peculiar taste, and a feeling of roughness in the teeth. They cause an increased flow of saliva from the parotid, and of the thin saliva which the submaxillary secretes when the chorda tympani is irritated, but have no effect on the sympathetic saliva. They are therefore given to allay thirst in fever, the increased secretion of saliva which they provoke keeping the fauces moist (p. 315).

Acids stimulate the secretion of the alkaline saliva and intestinal juice, and excite the expulsion of bile from the gall-bladder. They are supposed generally to stimulate those glands whose secretions are alkaline. On the other hand alkalies stimulate the secretion of gastric juice, which is acid; and they are supposed to stimulate in general those glands whose secretion is acid. Professor Ringer supposes that the converse is also the case, and that acids and alkalies severally hinder the secretions of a like character. This

supposition may be correct, and no doubt when an acid is present, *e.g.* in the stomach, it will neutralise any alkali which may be taken and either retard its stimulant action on the gland or prevent it altogether, according to the relative quantities of acid present and of alkali employed. The presence of much alkali will also hinder the action of an acid stimulus in the same manner, but whether acids and alkalis have any farther effect in hindering secretion than that just mentioned is uncertain.

Acids are partly neutralised by the saliva, and partly act as astringents on the mouth and fauces. They are thus used in congestion of the throat. As they corrode the teeth, they are generally given through a glass tube or quill, and the teeth should be rubbed with chalk afterwards.

Digestion in the **stomach** is accomplished by the action of pepsin along with dilute hydrochloric acid. This ferment only acts in presence of free acid; but the amount of acid necessary is different in different animals, being greatest in the carnivora and least in the herbivora. Pepsin seems able to go on dissolving fibrin almost without a limit, but fresh acid must always be added. If the secretion is deficient, digestion goes on slowly and fermentation of the food takes place, causing the formation of other acids and liberation of gases.

The secretion of gastric juice may be stimulated by alkalis given just before meals, but if the stomach is so much out of order as not to respond to the stimulus, hydrochloric or phosphoric acid may be given after meals, alone, or with pepsin. In febrile conditions there is a deficiency of acid in the stomach, although pepsin is present in plenty. In chronic gastric catarrh, especially when accompanied by dilatation, the acid is greatly diminished, and in carcinoma of the stomach it would seem to be wanting in the great majority of cases. In such conditions, therefore, the administration of diluted hydrochloric acid is indicated.

For acid eructations and heartburn depending on excessive acidity of the gastric juice, acids should be given before meals (Ringer).

Some persons are troubled by eructations of sulphuretted hydrogen with a taste of rotten eggs. These persons have generally oxalic acid in the urine, and frequently suffer from depression of spirits. Such patients are benefited by acids, especially nitro-hydrochloric acid. Persons who suffer from dyspepsia and depression of spirits with oxaluria are also benefited by mineral acids, even when no sulphuretted hydrogen is present in the intestines.

When the use of acids is long continued they lessen the secretion of gastric juice, and produce a catarrhal condition of the mucous membrane of the stomach. They should therefore not be given for more than a week or two at a time. They should then be left off for a short time, or alternated with alkalis. Constant use of acid wines has a similar tendency to produce catarrh. Vinegar is sometimes drunk in order to lessen obesity or even

plumpness. It has this effect by inducing gastro-intestinal catarrh, but sometimes the derangement of the digestion occasioned by it has been so great as to cause death.

Acids stimulate the expulsion of bile from the gall bladder, and the secretion of **intestinal** juice. As they will be rapidly neutralised by the bile and pancreatic juice, and absorbed in the duodenum, they can hardly reach the lower and middle parts of the alimentary canal as acids. Their action in relieving diarrhœa is difficult to explain.

When absorbed from the intestine they must pass through the **liver** before they can reach the general circulation. It is probable that during their passage through the portal system they alter the processes of tissue change which go on in the liver, and check the formation of urea. The reason for this supposition is that acids are excreted in the urine, chiefly in the form of ammoniacal salts. In the normal condition ammonia is readily converted into urea in the organism, and when given internally it appears in the urine in the form of urea and not of ammoniacal salts. The appearance of these salts in the urine after the administration of acids shows that the normal process of conversion into urea has been diminished. Possibly it is to such alterations in the **tissue change** in the liver that the so-called tonic action of acids is due (p. 359), as well as the marked benefit obtained in hepatic disorders from the administration of nitric and nitro-hydrochloric acids. Although acids appear in the **urine** in combination with ammonia and other bases, yet their free administration increases the acidity of the urine. They are therefore used to prevent the deposits of phosphatic calculi which are apt to occur in alkaline urine.

POISONING BY ACIDS.—The symptoms of poisoning by acids, and the antidotes to be employed, have already been described (p. 346, 348, and 429). In cases of acute poisoning where death has not occurred too quickly, much albumen, hæmatin, and indican have appeared in the urine, and fatty degeneration of the liver, muscles, and kidneys has been found. In the kidneys the cloudy swelling and fatty degeneration of the cells was accompanied by evidences of inflammation in the connective tissue also, as it exhibited proliferation of nuclei, especially along the course of the vessels.

Acidum Sulphuricum, B. and U.S.P. SULPHURIC ACID.—It contains 96·8 per cent. of H_2SO_4 (98) and corresponds to 79 per cent. of anhydrous sulphuric acid, SO_3 (80).

PREPARATION.—*Vide* p. 495.

PROPERTIES.—A colourless, oily-looking heavy liquid. Sp. gr. 1·843; no smell; but intensely acid taste. It blackens and corrodes most organic substances. It has a great affinity for water, and when mixed with it evolves much heat. When diluted it gives a copious white precipitate of barium sulphate ($BaSO_4$) with chloride of barium, insoluble in nitric or in hydrochloric acid.

IMPURITIES.—Lead derived from the leaden chambers in which it is prepared; nitric acid from the nitrous fumes; arsenic from impure sulphur being used and the arsenious fumes passing over with the sulphurous acid; and water from imperfect concentration or fraudulent addition.

TESTS.—Not unfrequently it contains so much lead in the form of sulphate, that when diluted with water it deposits a white precipitate, the sulphate being soluble in the strong but not in the weak acid. It should not do this, and when evaporated in a platinum dish it should leave little or no residue (no lead, arsenic, or saline impurities). When a solution of sulphate of iron is carefully poured over its surface, there is no purple colour developed where the two liquids unite (no nitric acid). Diluted with six times its volume of distilled water, it gives no precipitate with sulphuretted hydrogen (no arsenic or lead). The absence of water is ascertained by the sp. gr. not being below 1·840, and by the volumetric estimation of its neutralising power with solution of soda.

OFFICINAL PREPARATIONS.

Acidum Sulphuricum Aromaticum, B. and U.S.P. AROMATIC SULPHURIC ACID. Is sulphuric acid diluted with alcohol and flavoured with cinnamon and ginger. About 1 in 13 B.P., and 1 in 10 U.S.P. by measure.

Acidum Sulphuricum Dilutum B. and U.S.P. DILUTE SULPHURIC ACID. Is the strong acid diluted with 11 parts B.P., 16½ parts U.S.P., of water by measure; 1 in 10 by weight U.S.P.

DOSES.—Of either aromatic or dilute sulphuric acid 5-30 min. freely diluted.

INCOMPATIBLES.—Preparations of lead.

ACTION.—It is a most powerful caustic and quickly chars and destroys the parts it touches. When mixed with charcoal paste it is used as a caustic in cancer, and with lard in obstinate skin diseases. When swallowed, as it not unfrequently is in manufacturing districts, it produces symptoms of irritant poisoning (p. 345). The antidotes are alkalis, soap, oil, whiting, milk, plaster from the wall, or magnesia.

USES.—Internally it is used after free dilution to quench thirst in fever, to prevent absorption of lead from the stomach in painters and colour-grinders, to check diarrhœa especially in phthisis, to arrest hæmoptysis and other hæmorrhages, and to lessen night sweats and mucous discharges.

Acidum Sulphurosum, B. and U.S.P. SULPHUROUS ACID.—Sulphurous acid gas (SO_2; 64) dissolved in water and constituting 9·2 per cent. of the solution.

PREPARATION.—*Vide* p. 495, $2H_2SO_4 + C = CO_2 + 2SO_2 + 2H_2O$.

PROPERTIES.—A colourless liquid with a strong sulphurous odour. Unlike sulphuric acid, it gives no precipitate with chloride of barium, but if chlorine be added to it, it becomes converted into sulphuric acid, and then gives a precipitate, $SO_2 + 2H_2O + Cl_2 = H_2SO_4 + 2HCl$.

IMPURITIES.—Sulphuric acid, solid impurities, too little sulphurous acid.

TEST.—It should give no precipitate, or only a slight one, with chloride of barium (little or no sulphuric acid); but very few specimens answer either to this test or to the officinal volumetric test on account of the liability of the acid to decompose. It should leave no residue on evaporation. Its strength is determined by its sp. gr. 1·04, and the volumetric test.

DOSE.—$\frac{1}{2}$-1 fluid drachm diluted with water.

ACTION.—It is a powerful deoxidising agent. It is extremely destructive to plant life, and so may destroy disease germs.

USES.—Gaseous sulphurous acid is used to disinfect rooms. The room should be closely shut up, and a brazier with charcoal placed in it. On this sulphur is thrown, and the fumes are allowed to permeate the room for several hours. Care must be taken that the brazier is so placed that there is no danger of anything in the room catching fire. A solution mixed with glycerine may be applied in skin diseases depending on parasitic fungi. It is very useful in cases of vomiting, especially when the vomited matters have a frothy or yeasty appearance due to the presence of sarcinæ and to the occurrence of fermentation in the stomach. Applied as spray it sometimes gives relief in laryngeal phthisis.

Acidum Hydrochloricum, B. and U.S.P. HYDROCHLORIC or MURIATIC ACID.—Hydrochloric acid gas (HCl; 36·4) dissolved in water, and forming 31·8 B.P., 31·9 U.S.P., per cent. by weight of the solution.

PREPARATION.—By warming chloride of sodium with sulphuric acid, washing the evolved HCl, and conducting it into cold water by which it is absorbed. Excess of sulphuric acid is employed if glass vessels are used in the preparation either of this or of nitric acid, as the bisulphate of potash left behind is more soluble than the neutral sulphate, and thus the vessels are more easily cleaned. $NaCl + H_2SO_4 = NaHSO_4 + HCl$.

PROPERTIES.—A nearly colourless liquid, sp. gr. 1·16. It emits white vapours having a pungent odour, and has a strongly acid taste.

REACTION.—It gives with nitrate of silver a curdy white precipitate soluble in excess of ammonia, insoluble in nitric acid.

IMPURITIES.—Salts; sulphuric acid, with its impurities lead and arsenic; chloride of sodium or chlorine; sulphurous acid formed from sulphuric by organic substances; iron from the apparatus in which it is made commercially.

Arsenic is of importance as an impurity because hydrochloric acid is sometimes used in testing for arsenic by the formation of arseniuretted hydrogen. When testing for arsenic in cases of suspected poisoning both the acid and the zinc must be tested first, in order to ascertain their purity before the suspected substance is added

TESTS.—When diluted with four times its volume of distilled water it gives no precipitate with solution of chloride of barium (absence of sulphuric acid), or with sulphuretted hydrogen (absence of lead or arsenic), and does not tarnish or alter the colour of bright copper foil when boiled with it (absence of arsenic). When diluted with five volumes of water it should not liberate iodine from iodide of potassium (absence of chlorine); and when 1 c.c. is diluted to 10 c.c. with water, and supersaturated with ammonia, the addition of two drops of ammonium sulphide causes no black colour (absence of iron). If a fluid drachm of it mixed with half an ounce of distilled water be put into a small flask with a few pieces of granulated zinc, and while the effervescence continues a slip of bibulous paper wetted with solution of subacetate of lead, B.P., or nitrate of silver, U.S.P., be suspended in the upper part of the flask above the liquid for about five minutes, the paper will not become discoloured (absence of sulphurous or arsenious acid, $SO_2 + 6H = H_2S + 2H_2O$). When evaporated it leaves no residue (no sodium chloride or other fixed impurity).

PREPARATIONS CONTAINING FREE HYDROCHLORIC ACID.

B.P.	DOSE.
Acidum Hydrochloricum Dilutum (acid 8, diluted with water up to 26½ by measure)	10-30 m.
Acidum Nitro-hydrochloricum Dilutum	10-30 m.
Liquor Antimonii Chloridi	
,, Arsenici Hydrochloricus	
,, Morphiæ Hydrochloratis	

U.S.P.	
Acidum Hydrochloricum Dilutum (acid 6, water 13 by weight; 5½ and 14 by measure)	10-30 m.
Acidum Nitro-hydrochloricum	
,, ,, ,, Dilutum	10-30 m.

ACTION AND USES.—It produces symptoms of poisoning like those of sulphuric acid. The stains which it leaves upon the mucous membrane are white. It is rarely used externally. It may be employed to quench thirst in fevers, and to lessen phosphatic deposits in the urine. As it is the acid of the gastric juice, it may be given after meals in cases of indigestion, where we suspect deficiency of acid (p. 496) and to aid the digestion of food, as well as to relieve thirst in febrile conditions (pp. 496 and 315).

Acidum Nitricum, B. and U.S.P. NITRIC ACID, (HNO_3; 63.)—An acid prepared from nitrate of potash or nitrate of soda by distillation with sulphuric acid and water, and containing 70 per cent. B.P., or 69·4 U.S.P. by weight of nitric acid, HNO_3, corresponding to 60 per cent. of anhydrous nitric acid, N_2O_5.

CHARACTERS.—A colourless liquid, having a specific gravity of 1·42. When exposed to the air it emits an acrid, corrosive vapour.

If it be poured over copper filings dense red vapours are immediately formed, but if the acid be mixed with an equal volume of water, and then added to the copper, it gives off a colourless gas, which acquires an orange-red colour as it mixes with the air, and which, if it be introduced into a solution of sulphate of iron, communicates to it a dark purple or brown colour, due either to solution of N_2O_2 in the sulphate or combination with it. The boiling-point of the acid is 250°. If submitted to distillation the product continues uniform throughout the process.

IMPURITIES.—Weaker or stronger acid, sulphuric or hydrochloric acids, fixed impurities.

TESTS.—It leaves no residue when evaporated to dryness (no fixed impurities, as iron, lead, &c.). Diluted with six times its volume of distilled water it gives no precipitate with chloride of barium or nitrate of silver (absence of sulphuric or hydrochloric acids).

PREPARATIONS CONTAINING FREE NITRIC ACID.

B.P.	DOSE.	U.S.P.
Acidum Nitricum Dilutum (1 with about 4 of water by measure)	10-30 m.	**Acidum Nitricum Dilutum** (acid 1, water 6 by weight; 1½, and 12½ by measure)
Acidum Nitro-hydrochloricum Dilutum		Acidum Nitro-hydrochloricum ,, ,, ,, Dilutum.
Liquor Ferri Pernitratis		
,, Hydrargyri Nitratis Acidus		
Unguentum Hydrargyri Nitratis		

ACTION.—It is an exceedingly powerful caustic, and destroys the tissues, but, unlike sulphuric acid, it forms, to some extent, a barrier to its own action by coagulating the albumen with which it meets. When swallowed, it may not only produce the symptoms of irritant poisoning already described, but the vapour getting into the larynx, may cause spasm of the glottis, and death from suffocation, or may produce intense bronchitis.

USES.—Nitric acid is applied externally to destroy chancres, warty growths, and hæmorrhoids; to the surface of phagedenic ulcers; and to bites of snakes or rabid dogs in order to destroy the virus and prevent its absorption. Internally the dilute acid is used to quench thirst in febrile conditions, like other dilute acids, and it is useful in cases of dyspepsia. It is supposed to have an action upon the liver, and certainly appears to be of use in cases of so-called biliousness. When absorbed it has an astringent action, and is exceedingly serviceable in diminishing the secretion from the lungs in bronchitis and in the sub-acute exacerbations of phthisis. It is also employed in cases of syphilis occurring in debilitated subjects, where mercurials are not well borne. It diminishes phosphatic deposits in the urine, and, in a dilute condition, has been injected into the bladder in order to dissolve calculi already formed.

U.S.P. Acidum Nitrohydrochloricum. NITROHYDROCHLORIC ACID.

PREPARATION.—By mixing nitric acid (4) with hydrochloric acid (15 parts) and when effervescence has ceased, preserving it in glass-stoppered bottles which should not be more than half filled and kept in a cool place.

CHARACTERS.—A golden yellow, fuming and very corrosive liquid, having a strong odour of chlorine and a strongly acid reaction. By heat it is wholly volatilised. It readily dissolves gold leaf, and a drop added to test solution of iodide of potassium liberates iodine abundantly.

Acidum Nitrohydrochloricum Dilutum, B. and U.S.P. DILUTE NITROHYDROCHLORIC ACID.

PREPARATION.—By diluting nitrohydrochloric acid (1) with water (26 parts by weight U.S.P.). The proportions in the B.P. are nitric 3, hydrochloric 4, water 25, by measure. In the U.S.P. by measure, nitric 3, hydrochloric acid $13\frac{1}{2}$, water 80.

DOSE.—5—20 min.

USE.—This, like nitric acid, is supposed to have a special action upon the liver. It is sometimes used in the form of baths or compresses in hepatic disorders, and is frequently given in cases of dyspepsia, biliousness, and jaundice. When given before meals it seems to check acidity in the stomach, and it is very useful in removing headache situated in the forehead, just above the eyebrows, and unaccompanied by constipation.

Acidum Aceticum, B. and U.S.P. ACETIC ACID—$HC_2H_3O_2$; 60. An acid liquid prepared from wood by destructive distillation and subsequent purification. 100 parts by weight contain 33 B.P., 36 U.S.P. parts of acetic acid $HC_2H_3O_2$; 60 corresponding to 28 parts of anhydrous acetic acid, $C_4H_6O_3$.

CHARACTERS AND TESTS.—A colourless liquid having a strong acid reaction and a pungent odour. Specific gravity 1·044 B.P., 1·048 U.S.P., at 15° C.

IMPURITIES.—Lime, lead, copper, tin, sulphuric and hydrochloric acids, and sulphurous acid due to the action of organic matter on the sulphuric acid.

TESTS.—It leaves no residue when evaporated (no lime, &c.), and gives no precipitate with sulphuretted hydrogen (no metals), chloride of barium (absence of sulphuricacid), or nitrate of silver (absence of hydrochloric acid. If a fluid drachm of it mixed with half an ounce of distilled water and half a drachm of pure hydrochloric acid be put into a small flask with a few pieces of granulated zinc, and while the effervescence continues a slip of bibulous paper wetted with solution of subacetate of lead be suspended in the upper part of the flask above the liquid for about five minutes, the paper will not become discoloured (absence of sulphurous acid $SO_2 + 6H = H_2S + 2H_2O$).

PREPARATIONS CONTAINING FREE ACETIC ACID.

Acetum.....4·6 per cent. anhydrous acetic acid.
,, Cantharidis.....
,, Scillæ .....
Acidum Aceticum Glaciale .....84 per cent. anhydrous acid.
,, **Aceticum** .....28 per cent. ,,
,, ,, **Dilutum** .....3·6 per cent. ,,
Extractum Colchici Aceticum .....
Linimentum Terebinthinæ Aceticum...1 volume acetic acid in 3.
Liquor Epispasticus.....1 volume acetic acid in 5.
Mistura Creasoti .....
Oxymel ....
,, Scillæ .....
Syrupus Scillæ .....

Acidum Aceticum Dilutum, B. and U.S.P. DILUTED ACETIC ACID.—Acetic acid, 1 part diluted with water 7 parts, B.P., or acid 17, water 83, U.S.P.

PROPERTIES, IMPURITIES.—The same as of acetic acid, except so far as they are affected by its dilution.

DOSE.—1 to 2 fluid drachms.

PREPARATIONS IN WHICH DILUTED ACETIC ACID IS USED.

B.P.

Acetum Scillæ. Liquor Morphiæ Acetatis.

Acidum Aceticum Glaciale, B. and U.S.P.—GLACIAL ACETIC ACID, $HC_2H_3O_2$; 60. Concentrated acetic acid, corresponding to at least 84 per cent. of anhydrous acid, $C_4H_6O_3$, B.P. Nearly or quite absolute acetic acid, U.S.P.

CHARACTERS AND TESTS.—It crystallises when cooled to 34°, and remains crystalline until the temperature rises to above 48°. Specific gravity 1·065 to 1·066, and this is increased by adding ten per cent. of water. At the mean temperature of the air it is a colourless liquid, with a pungent acetous odour. B.P.

At or below 15° C. (59° F.) a crystalline solid; at higher temperature, a colourless liquid. When liquefied and as near as possible to 15° C. (59° F.) it has the sp. gr. 1·056—1·058. Its properties are similar to those of acetic acid, and it is similarly affected by reagents. U.S.P.

PREPARATIONS IN WHICH GLACIAL ACETIC ACID IS USED.

B.P.

Acetum Cantharidis. Mistura Creasoti.

B.P. Acetum. VINEGAR.—An acid liquid, prepared from malt and unmalted grain by the acetous fermentation.

CHARACTERS.—A liquid of a brown colour and peculiar odour.

IMPURITIES.—A little sulphuric acid added to it is said to make it keep better. Too much may be fraudulently added in order to increase its acidity. Lead from the vessels in which it is kept.

TESTS.—If ten minims of solution of chloride of barium be added to a fluid ounce of the vinegar, and the precipitate, if any, be separated by filtration, a further addition of the test will give no precipitate (limit of sulphuric acid). Sulphuretted hydrogen causes no change of colour (absence of lead).

DOSE.—1 to 2 fluid drachms.

PREPARATION IN WHICH VINEGAR IS USED.

Emplastrum Cerati Saponis.

ACTION AND USES.—When applied externally to the skin, glacial acetic acid causes the formation of a large bleb. It is used to destroy warts, and is sometimes employed as a vesicant in cases of kidney disease, where danger is apprehended from the use of cantharides. When the vapour of it is sniffed up the nose, it causes reflex contraction of the blood-vessels, and raises the blood pressure. It is therefore useful in lessening drowsiness and preventing syncope, or arousing patients from it (pp. 162 and 224).

Dilute acetic acid is applied to the skin in cases of headache, and is used to sponge the surface and check perspiration when too profuse. It checks bleeding, and may be used to stop oozing from leech bites, or to wash out the mouth after the extraction of a tooth; and, when sniffed up the nose, sometimes arrests epistaxis. It is occasionally employed in the form of an enema to destroy ascarides.

U.S.P. Acidum Phosphoricum. PHOSPHORIC ACID.—A liquid composed of 50 per cent. of orthophosphoric acid (H_3PO_4; 98) and 50 per cent. of water.

PREPARATION. — Oxidising phosphorus by nitric acid. *Vide* p. 495.

CHARACTERS.—A strongly acid liquid, without odour, and of a strongly acid taste and reaction, sp. gr. 1·347. When heated it loses water, and when a temperature of about 200° C. (392° F.) has been reached, the acid is gradually converted into pyrophosphoric and metaphosphoric acids, which may be volatilised at a red heat. When diluted, and supersaturated with ammonia, the test-solution of magnesium gives a white precipitate. *Vide* also the reactions and tests of acidum phosphoricum dilutum.

OFFICINAL PREPARATION.

U.S.P.

Acidum Phosphoricum Dilutum.

Acidum Phosphoricum Dilutum, B. and U.S.P. DILUTED PHOSPHORIC ACID.—Phosphoric acid, H_3PO_4, dissolved in water and corresponding to 10 per cent. by weight of anhydrous phosphoric acid, P_2O_5, B.P., Phosphoric acid 20 parts with 80 of water, U.S.P.

CHARACTERS AND TESTS.—A colourless liquid, with a sour taste and strongly acid reaction. Specific gravity, 1·08. With ammonio-nitrate of silver it gives a canary-yellow precipitate, soluble in ammonia and in diluted nitric acid. Evaporated, it leaves a residue which melts at a low red heat, and upon cooling exhibits a glassy appearance.

IMPURITIES.—Phosphorous acid, meta-, and pyro-phosphoric acids, nitric, sulphuric and hydrochloric acids, arsenic.

TESTS.—It is not precipitated by sulphuretted hydrogen (no metals), chloride of barium (no sulphuric acid), nitrate of silver acidulated with nitric acid (no hydrochloric acid), nor by the solution of albumen (absence of metaphosphoric acid which coagulates albumen). When mixed with an equal volume of pure sulphuric acid, and then introduced into solution of sulphate of iron, it does not communicate to it a dark colour (absence of nitric acid). Mixed with an equal volume of solution of perchloride of mercury and heated, no precipitate is formed (no pyrophosphates). Its strength is estimated gravimetrically by ascertaining the increase in weight which occurs in oxide of lead when phosphoric acid is poured on it, evaporated and ignited.

DOSE.—10 to 30 minims.

B.P. PREPARATION CONTAINING FREE PHOSPHORIC ACID.

Syrupus Ferri Phosphatis.

USES.—Phosphoric acid may be used to allay thirst, like other dilute acids, in febrile states, and in diabetes. It may be given in larger doses than other mineral acids without deranging digestion, and is therefore to be preferred to them in cases where it requires to be given for a length of time, as in diabetes and alkalinity of the urine. It is said to be useful in scrofula, and to diminish the growth of bony tumours.

Acidum Tartaricum, B. and U.S.P. TARTARIC ACID. $H_2C_4H_4O_6$; 150.—A crystalline acid prepared from the acid tartrate of potash.

PREPARATION.—*Vide* p. 494.

CHARACTERS.—In colourless crystals, the primary form of which is the oblique rhombic prism. It has a strongly acid taste, and is readily soluble in water and in rectified spirit. When to either solution, not too much diluted, a little acetate of potash is added, a white crystalline precipitate is formed.

20 grains neutralise { 27 grains bicarbonate of potash.
22 ,, ,, soda.
15½ ,, carbonate of ammonia.

DOSE.—10 to 30 grains.

IMPURITIES.—Lead, copper, and iron from the vessels in which it is prepared; lime, or acid tartrate of potash, from the substances used in its preparation; racemic and oxalic acids.

TESTS.—An aqueous solution of the acid is not affected by sulphuretted hydrogen (absence of metals), and gives no precipitate with the solution of sulphate of lime (no racemic or oxalic acids) or of oxalate of ammonia (no lime). It leaves no residue, or only a mere trace, when burned with free access of air (no acid tartrate of potash).

ACTION AND USES.—Used for cooling drinks.

Acidum Citricum, B. and U.S.P. CITRIC ACID. $H_3C_6H_5O_7.H_2O$; 210.—A crystalline acid prepared from lemon-juice, or from the juice of the fruit of the Lime, *Citrus Limetta*.

PREPARATION.—*Vide* p. 494.

CHARACTERS.—In colourless crystals, of which the right rhombic prism is the primary form; very soluble in water, less soluble in rectified spirit, and insoluble in pure ether. The crystals dissolve in three-fourths of their weight of cold, and in half their weight of boiling water. The diluted aqueous solution has an agreeable acid taste. When the solution is made by dissolving thirty-four grains of the acid in one ounce of water, it resembles lemon-juice in strength and in the nature of its acid properties, and, like lemon-juice, it undergoes decomposition and becomes mouldy by keeping.

The quantity contained in $\frac{1}{2}$ fl. oz. of this solution; viz.:—

17 grains neutralise { 25 grains bicarbonate of potash. / 20 ,, ,, soda. / 15 ,, carbonate of ammonia.

IMPURITIES.—Lead and copper from the vessels in which it is prepared, lime used in its preparation, tartaric acid, which is cheaper, and is apt to be mixed with or substituted for it, sulphuric acid or sulphates, oxalic acid.

TESTS.—The aqueous solution is not darkened by sulphuretted hydrogen (absence of metals), gives no precipitate when added in excess to solution of acetate of potash (no tartaric acid), or of chloride of barium (no sulphates), and if sparingly added to cold lime-water it does not render it turbid (no oxalic acid). The crystals leave no ash when burned with free access of air (no lime).

DOSE.—10 to 30 grains.

PREPARATIONS CONTAINING FREE CITRIC ACID.

B.P.	U.S.P.
Succus Limonis.	Syrupus Acidi Citrici.
Syrupus Limonis.	
Vinum Quiniæ.	

U.S.P. Syrupus Acidi Citrici. SYRUP OF CITRIC ACID.—Citric acid 8, water 8, spirit of lemon 4, syrup 980.

ACTION AND USES.—Citric acid, from the agreeable taste of its solution in water, is used for drinking in fever to allay thirst, either alone or with alkaline bicarbonates as effervescing drinks. It is also used in scurvy, as it is supposed by some to be the ingredient to which lemon juice owes its properties.

B.P. Oxalic Acid, Purified. $H_2C_2O_4.2H_2O.$; 126.

Dissolve 1 pound of commercial oxalic acid in 30 fluid ounces of boiling distilled water, filter the solution, and set it aside to crystallise. Pour off the liquor, and dry the crystals by exposure to the air on filtering paper placed on porous bricks.

TEST.—It is entirely dissipated by a heat below 350°.

USES.—As a test.

Standard Solution of Oxalic Acid, B.P. and U.S.P.—63 grammes dissolve in water to 1000 cc.

Acidum Gallicum, *vide* p. 941.

Acidum Tannicum, *vide* p. 943.

U.S.P. Acidum Boricum. BORIC OR BORACIC ACID, H_3BO_3; 62.

PREPARATION.—*Vide* p. 494.

CHARACTERS.—Transparent, colourless, six-sided plates, slightly unctuous to the touch, permanent in the air, odourless, having a cooling bitterish taste and a feebly acid reaction; in solution turning blue litmus paper red and turmeric paper brown, the tint in the latter case remaining unaltered in presence of free hydrochloric acid. The alcoholic solution burns with a flame tinged with green.

IMPURITIES.—Sulphates, chlorides, lead, copper, iron, &c., calcium and sodium salts.

TESTS.—An aqueous solution of boric acid should not be precipitated by test solutions of chloride of barium, nitrate of silver with nitric acid, sulphide of ammonium, or oxalate of ammonium. A fragment heated on a clean platinum wire in a non-luminous flame should not impart to the latter a persistent yellow colour.

ACTION.—It has the power of destroying low organisms, and has therefore been used as an **antiseptic** application to wounds either in the form of a solution (1 part in 20 of hot water) or of an ointment. The antiseptic ointment originally recommended by Lister consisted of a mixture of the acid (1) with white wax (1), paraffin (2), almond oil (2). This is rather hard, and a better ointment consists of the powdered acid (3), paraffin (5) and vaseline (10). The relative proportions of these may be varied according to the temperature, more or less paraffin being added according as the temperature is high or low. The powdered acid, mixed with starch, forms a useful dusting powder for infants, and lessens the fœtor of perspiration. When given internally it is said to be occasionally useful in cases of vomiting in somewhat the same way as sulphurous acid, and it has also been given along with ether in septic diseases. **Boro-glyceride,** discovered and patented by Barff, is made by heating 92 parts of glycerine with 62 of boric acid. A solution of 1 in 40 of water is recommended as a powerful antiseptic. It is used to preserve food, and as a lotion for the treatment of wounds and in purulent ophthalmia.[1]

U.S.P. Acidum Chromicum. CHROMIC ACID, CrO_3; 100.4.

CHARACTERS.—Small, crimson, needle-shaped or columnar

[1] *Extra Pharmacopœia,* Martindale and Westcott.

crystals, deliquescent, odourless, having a caustic effect upon the skin and other animal tissues, and an acid reaction. Very soluble in water, forming an orange-red solution. Brought in contact with alcohol, mutual decomposition takes place. When heated to about 190° C. (374° F.) chromic acid melts and at 250° C. (482° F.) it is mostly decomposed with the formation of dark green chromic oxide and the evolution of oxygen. On contact, trituration, or warming with strong alcohol, glycerine, spirit of nitrous ether, or other easily oxidisable substances, it is liable to cause sudden combustion or explosion.

TESTS.—If 1 grain of chromic acid be dissolved in 100 cc. of cold water and mixed with 10 cc. of hydrochloric acid, the further addition of 1 cc. of test solution of chloride of barium should cause not more than a white turbidity (limit of sulphuric acid.)

ACTIONS.—It has a great power of coagulating albumen, and destroying low organisms, and as it parts very readily with oxygen it oxidises organic matter and decomposes ammonia and sulphuretted hydrogen. It is thus a powerful deodoriser and **disinfectant.** It is chiefly used as a **caustic** to destroy condylomata, and morbid growths in the mouth, larynx, or uterus, and to phagedenic ulcers, poisoned wounds, &c. As a solution of 1 in 40 it has been especially recommended in syphilitic affections of the tongue, mouth, and throat. As a lotion it has been employed to lessen fœtid discharges, and as an injection in ozœna, leucorrhœa and gonorrhœa. Care must be taken not to prescribe it with any substance to which it readily yields oxygen, such as glycerine, as the mixture may explode spontaneously.

Acidum Carbonicum. CARBONIC ACID, CO_2; 44. Not Officinal. It is very extensively used dissolved in water, as aërated water, effervescing soda, potash or lithia waters, or in wine as champagne.

PROPERTIES.—Colourless gas, heavier than air, causes a pungent feeling in the nostrils. Soluble in its own volume of water. Its solubility is increased by the presence of carbonates, or by pressure, and when this is removed the gas escapes and causes the fluid to effervesce. The solution has an acid reaction. Carbonates of magnesia, lime, iron, &c., which are only sparingly soluble in water, are dissolved with comparative ease by water holding the gas in solution.

ACTION AND USES.—Like other acids, when applied to the **skin** it acts as an irritant, but only slightly. After a prolonged application it causes a slight reddening of the skin and a feeling of warmth, which changes on the continuance of the application into burning or prickling, most felt where the skin is thin and richly supplied with nerves, as the external genitals, and this is not unfrequently accompanied by sweat. Carbonic acid baths are therefore sometimes used in catarrh and rheumatism as a slight rubefacient to the whole skin, and to cause sweat, especially where it can be obtained with ease, as in places where there are springs

containing much CO_2. It has been used as a stimulant to ulcers, either by directing a stream of gas directly upon them or by applying a poultice of yeast (Cataplasma Fermenti. B.P.) which in the process of fermentation causes a constant production of this gas.

Streams of CO_2 have been applied to the eyes, ears, nose, vagina, and rectum in catarrhal inflammation or ulceration of these parts, in order to cause a slight hyperæmia of the parts and healing of the inflammation and to diminish pain, as CO_2 is supposed to act locally by diminishing the sensibility of the nerves of the part.

In the **mouth** CO_2, like other acids, acts as a stimulant to the secretion of saliva, and so water containing CO_2 quenches thirst better than pure water, and it is therefore often used in feverish states (p. 315).

In the **stomach** it causes that slight pain which we confound with hunger, and a pleasant feeling of warmth just as on the skin. Here too it most probably causes a slight hyperæmia, and increased secretion. The greatest part leaves the stomach as gaseous eructations, but a portion is absorbed and enters the blood. Its action is thus transient, and it produces no material change in the chemical composition either of the contents or walls of the stomach. It increases the rapidity of the absorption of water in the **intestinal canal,** as is shown by the fact that water containing carbonic acid is excreted by the kidneys much sooner after it has been drunk, than water without it. It relieves irritation in the stomach, and allays or stops vomiting or nausea and slight derangements of digestion. Carbonic acid is naturally present in the intestines, in greater quantities in the large than the small. The CO_2 is partly that which passes from the blood into the intestine in interchange for the O contained in the air we swallow, and is partly formed by processes of fermentation which take place in the chymus.

That part of the CO_2 which, after introduction into the stomach, passes into the blood is excreted by the lungs. CO_2 injected into the blood through a vein is likewise excreted in the same way without causing any injury, unless it is injected in such a quantity that some remains as gas undissolved in the blood, and then it causes death mechanically, just like air, by hindering the passage of blood through the lungs.

POISONING BY CARBONIC ACID.—When CO_2 is inhaled, the ordinary interchange between the CO_2 in the blood and the O of the air is prevented, the CO_2 in the blood accumulates, and the processes of oxidation in tissues being interfered with, their functions are lessened or destroyed (p. 221).

The nervous system is first affected, and there is headache, beating or singing in the ears, giddiness, flushing of the face. Then there is a feeling of want of breath, tightness of the breast, palpitation of the heart and great anxiety. If the CO_2 be still inhaled, the pulse becomes slower, consciousness is lost, delirium or coma ensues, and death occurs with convulsions.

In poisoning by carbonic acid three stages may be distinguished, (1) dyspnœa; (2) convulsions; (3) paralysis.

During the first stage the carbonic acid appears to act as a stimulus to the nerve-centres in the medulla, and especially to the respiratory and vaso-motor centres. In the second stage it stimulates other motor centres (p. 202). In the third it paralyses them. In the first stage, that of **dyspnœa,** the respirations are both rapid and deep, the inspiratory as well as the expiratory movements being increased. Both the inhibitory and the accelerating centres for the heart are stimulated, but the irritation of the vagus roots preponderates, and the heart is generally slow. The vaso-motor centre in the medulla is also stimulated, and the blood-pressure rises. Besides this the carbonic acid also stimulates either subsidiary centres in the spinal cord (pp. 245 and 246), or acts directly on the walls of the vessels themselves, causing them to contract (p. 241), for the blood-pressure rises during inhalation of carbonic acid even when the spinal cord has been divided below the medulla. The vessels of the surface become dilated. This is ascribed by Fränkel to stimulation of a dilating centre. During the second stage, that of **convulsions,** the respiration becomes more and more laboured, and the expiratory movements greater, until general convulsions occur. The blood-pressure rises still more, the heart becomes still slower, and the right ventricle more distended. In the third stage, that of **paralysis,** the inspiratory movements become more and more feeble, the intervals between them longer and longer, and finally they cease. The vaso-motor centre becoming exhausted the blood-pressure falls, and this fall is probably aided by the action of the carbonic acid on the muscular walls of the blood-vessels themselves (p. 241), as well as by weakness of the heart. The heart generally continues to beat for some minutes after respiration has completely ceased, and if artificial respiration be commenced before pulsation is entirely arrested, life may generally be saved. Indeed, this is the case even when the cardiac pulsations are quite imperceptible, and therefore in cases of death from asphyxia it is well to keep up artificial respiration if possible for an hour or even longer, notwithstanding the apparent hopelessness of the case. It should only be discontinued when a ligature tied moderately tightly, causes no trace of congestion in the finger-tip after being on for ten minutes, and it ought to be supplemented by intermittent pressure on the cardiac region in order to stimulate the heart. These observations apply not only to poisoning by carbonic acid, but to poisoning by all drugs which produce death by asphyxia.

Post-mortem examination shows great venous congestion everywhere, the right side of the heart being distended with blood, the brain much congested, with exudation and even extravasation, and the blood extraordinarily dark.

TREATMENT.—In cases of poisoning by CO_2, as in miners or

men who have been suffocated in wells or brewers' vats, the great object is to get the blood oxygenated as quickly as possible. Get the person into the fresh air, and if the respiratory movements have ceased, dash cold water on the face and chest to awaken them reflexly. If this does not do, have recourse to artificial respiration. The next thing is to see that the heart is beating. When the right ventricle is distended with blood it becomes paralysed, and if it does not begin to beat shortly after artificial respiration has been begun the jugular vein should be opened in order to relieve the dilatation. There are no valves between the heart and the jugular vein (at least of any importance), so the blood flows directly out and the distended ventricle is relieved. One must of course be careful to prevent the access of air into the vein.

Acidum Hydrocyanicum Dilutum, B. and U.S.P. DILUTED HYDROCYANIC ACID. PRUSSIC ACID.—Hydrocyanic acid, HCN, dissolved in water, and constituting 2 per cent. by weight of the solution, B.P. A liquid consisting of 2 per cent. of absolute hydrocyanic acid (HCN ; 27) and 98 per cent. of water, U.S.P.

PREPARATION.—By distilling yellow prussiate of potash with H_2SO_4.

Potassium Ferrocyanide. Everett's yellow salt.

$$2K_4FeCy_6 + 6H_2SO_4 = 6HCy + K_2Fe_2Cy_6 + 6KHSO_4.$$

Half the cyanogen of the ferrocyanide passes over as hydrocyanic acid, while a ferrocyanide of potassium and iron, often called Everett's yellow salt, remains behind along with potassium sulphate.

CHARACTERS AND TESTS.—A colourless liquid, with a peculiar odour. Specific gravity, 0·997. It only slightly and transiently reddens litmus paper. Treated with a minute quantity of a mixed solution of sulphate and persulphate of iron, afterwards with potash, and finally acidulated with hydrochloric acid, it forms Prussian blue.

IMPURITIES.—The most important is want of strength, so that when prescribed it has not the desired effect. It loses strength when kept, and therefore the volumetric test is more important than in the case of other acids.

TESTS.—A fluid drachm of it evaporated in a platinum dish leaves no fixed residue (no fixed impurities). It gives no precipitate with chloride of barium (no sulphuric acid), but with nitrate of silver it gives a white precipitate entirely soluble in boiling concentrated nitric acid (no hydrochloric acid). 270 grains of it rendered alkaline by the addition of solution of soda, require 1000 grain-measures of the volumetric solution of nitrate of silver to be added before a permanent precipitate begins to form, which corresponds to 2 per cent. of the real acid. Silver nitrate forms a soluble double cyanide of silver and sodium, and till all the hydro-

cyanic acid is used up no silver oxide is precipitated. $AgNO_3 + 2NaCy = NaNO_3 + NaAgCy_2$.

Standard silver test-solution contains $\frac{1}{10}$ of an equivalent of $AgNO_3$ and 1,000 grains therefore combine with $\frac{1}{10}$ of 2 Na Cy.

DOSE.—2 to 8 minims. As a lotion, 5-10 min. to 1 fl. oz. of water, rose water, elderflower water, or almond mixture. The addition of 1 fl. dr. of glycerine tends to prevent evaporation.

PREPARATIONS. B.P.

Vapor Acidi Hydrocyanici.

B.P. Vapor Acidi Hydrocyanici. VAPOR OF HYDROCYANIC ACID.—Mix 10 to 15 minims of diluted hydrocyanic acid with 1 fluid drachm of cold water in a suitable apparatus, and let the vapour that arises be inhaled.

ACTION.—Hydrocyanic acid differs from all the other acids in having upon the organism an action peculiarly its own. It is one of the most powerful and most rapid poisons known. It destroys protoplasmic movement, kills infusoria, checks oxidation and arrests fermentation. When applied to the **skin** it passes through the epidermis and paralyses the ends of the sensory nerves below, so that the part becomes numb, and tactile sensation is diminished or destroyed. It is rapidly absorbed from the mucous membranes, and its action is the same when applied to any of them. A single drop of pure hydrocyanic acid injected into the eye, nose, or mouth of a small animal, causes it to fall down dead as if struck by lightning, and the same dose is sufficient to cause the death even of a large animal. In these cases the pupils are usually widely dilated, and the animal generally utters a characteristic cry. When a smaller, but still fatal dose is given, the **poisoning** may be divided into three stages. In the first stage the brain is chiefly affected. There is giddiness, uncertain gait, a few slow breaths, and then rapid respiration, and irregular action of the heart. These are succeeded in the second stage by violent convulsions, tonic and clonic. The head is bent backwards, the limbs are stiffly extended, and sensibility is generally lost, although reflex action may still persist. In the third stage there is coma, complete loss of sensibility, paralysis of the voluntary muscles, almost imperceptible pulse, slow and weak respiration—the expiratory movements predominating, and death.

It is evident that these are the symptoms of rapid asphyxia. They are very like those produced by carbonic acid, but much more rapid, and resemble those of poisoning by sulphuretted hydrogen. The convulsions occur only in warm-blooded animals, and not in frogs. In this point they resemble those of simple asphyxia (p. 202). They differ from those of ordinary asphyxia, however, in the fact that whereas the blood is venous when asphyxial convulsions occur, the blood is arterial in colour when the hydrocyanic acid convulsions occur. They differ also in not being arrested by artificial respiration.

Death, in animals poisoned by hydrocyanic acid, is due to

sudden arrest of the heart in the more rapid cases, and to paralysis of the respiration in those which occur more slowly. In consequence of this, the blood in the left side of the heart is found to be arterial in cases of instantaneous death, but venous in those instances where some minutes have been required. It is stated that in the first stage of poisoning the blood is more arterial than usual, though it afterwards becomes more venous. This has been said to depend upon diminution of the oxidising power of the **blood** by the action of the acid. Hydrocyanic acid is said to form a compound with hæmoglobin (cyan-hæmoglobin) which does not readily give up its oxygen (p. 56). But this compound is often not to be found in the blood of animals poisoned by the acid, and the arterial appearance is more probably due to dilatation of the peripheral vessels allowing the blood to pass through them rapidly, without undergoing the usual changes, just as it does in the sub-maxillary gland on irritation of the chorda tympani nerve. This is rendered all the more probable by the fact, that at the exact moment in which the blood becomes of an arterial colour in the veins, the blood-pressure suddenly falls in the arteries (Rossbach).

The **respiratory changes,** however, do seem to be also interfered with, for in the first stage of poisoning the exhalation of carbonic acid is diminished. As the diminution in the power of the blood to give oxygen off is hardly sufficient to explain this, and as the convulsions, apparently asphyxial in character, come on while the blood is still arterial, we may, with some probability, suppose that the respiratory changes are due to the effect of the hydrocyanic acid in lessening internal respiration in the nervous tissues themselves (p. 205).

The stoppage of the **heart** in mammals is partly due to irritation of the vagus roots in the medulla, and partly to paralysis of the motor ganglia in the heart.

When placed upon the heart of a frog, it arrests its beats, but the heart, at first, still contracts when irritated, although after a short time its muscular irritability is also lost.

That its action in stopping the mammalian heart is partly due to irritation of the vagus roots is shown by the fact that, in some animals, section of the vagi prevents the stoppage. The effect of hydrocyanic acid is, first to raise, and afterwards greatly to depress the **arterial pressure,** and at the same time to slow the **pulse.** The slowing and paralysis of respiratory movements which this acid produces are chiefly due to its action on the **respiratory centre** in the medulla oblongata. When directly applied to the medulla in the alligator it causes continuous powerful expiration and death, whereas when given in other ways considerable time is required for its action to be produced. It appears to paralyse the **brain,** peripheral **afferent nerves,** then **spinal cord, motor nerves** and **muscles.** That the afferent nerves are

paralysed before the cord, is proved by the fact that when frogs are poisoned with prussic acid, and afterwards with strychnine, slight irritation of the sensory nerve roots will cause tetanus, after irritation of the periphery has ceased to produce any effect.

This fact was observed by von Kiedrowski, working under Reichert's direction. The same author observed the effect of the local application of hydrocyanic acid in paralysing muscle and nerve, by removing the soft parts and bone from the lower part of the thigh of a frog, leaving the leg attached to the body only by nerves. The gastrocnemius and crural muscles were then separated, and the gastrocnemius with its nerve was immersed in aqueous humour diluted with water, and the crural muscles with their nerves in a similar liquid to which hydrocyanic acid had been added. After four hours the crural muscles did not contract on direct irritation, but the gastrocnemius did so readily. This showed that the acid had paralysed the **muscles**. Irritation of the gastrocnemius, of its nerve *f g*, or of the sciatic nerve *a b*, caused reflex movements in the body of the frog, but irritation of the crural muscles caused no such reflex movements, showing that the ends of the sensory nerves within them had been paralysed. When the sciatic *a b* was irritated the crural muscles did not contract, but the gastrocnemius did. This poison probably paralyses motor nerves as well as muscles, for it is found that the muscles contract, though feebly, on direct irritation, after they have ceased to respond to the strongest irritation of the motor nerves.



FIG. 129.—After Kiedrowski. Diagram to show the effect of hydrocyanic acid when applied locally. *a* the sciatic nerve; *b* thigh of a frog; *d* and *e* branches of sciatic going to the crural muscles; *f g* branch going to the gastrocnemius.

USES. Hydrocyanic acid is used externally in order to lessen itching in skin diseases, and is best applied in combination with glycerine. It is chiefly employed internally to diminish irritability of the stomach, and to relieve vomiting, also pain in the stomach or intestines, and functional palpitation of the heart dependent on dyspepsia. It is also used to relieve cough in cases of bronchitis, phthisis, asthma, and whooping cough. It has sometimes been

employed, though with doubtful effect, in chorea, epilepsy, and hysteria. Its vapour is sometimes used to lessen irritability of the respiratory passages and cough.

Acidum Arseniosum.—*Vide* p. 646.

Acidum Benzoicum.—*Vide* p. 879.

Acidum Chrysophanicum.—*Vide* p. 823.

U.S.P. Acidum Lacticum. LACTIC ACID. $HC_3H_5O_3$; 90. A liquor composed of 75 per cent. of absolute lactic acid and 25 per cent. of water.

PREPARATION.—By adding chalk to sour milk and decomposing the lactate of lime with sulphuric acid.

CHARACTERS.—A nearly colourless syrupy liquid, odourless, having a very acid taste, and an acid reaction. Sp. gr., 1·212. It is freely miscible with water, alcohol and ether, but nearly insoluble in chloroform. It is not vaporised by a heat below 160° C. (320° F.); at higher temperatures it emits inflammable vapours, then chars, and is finally entirely volatilised, or leaves but a trace of residue.

IMPURITIES.—Hydrochloric acid, sulphuric acid, sarcolactic acid, lead, iron, sugars, glycerin, organic impurities.

TESTS.—When diluted with water, lactic acid should afford no precipitate with test solutions of nitrate of silver, chloride of barium, sulphate of copper, nor with sulphide of ammonium after addition of excess of water of ammonia. It should not reduce warm test-solution of potassio-cupric tartrate. When mixed and heated with excess of hydrated zinc oxide and extracted with absolute alcohol, the latter should not leave a sweet residue on evaporation. Cold concentrated sulphuric acid shaken with an equal volume of lactic acid should assume at most only a pale yellow colour.

DOSE.—1 to 3 fl. dr. per diem, diluted or sweetened, like lemonade.

ACTION.—It has been employed in solution of 1 part to 5, to dissolve the false membrane in croup and diphtheria. In cases of dyspepsia it is used to aid digestion in somewhat the same way as hydrochloric acid, and it has been given also to lessen the alkalinity of the urine and prevent phosphatic deposits. In diabetes it has been employed with considerable success along with an exclusively meat diet in doses of ½ oz. in 1 pint of water daily. Buttermilk has been recommended in place of it, but the difficulty of obtaining this in towns is very great.

U.S.P. Acidum Hydrobromicum Dilutum. DILUTED HYDROBROMIC ACID.—A liquid composed of 10 per cent. of absolute hydrobromic acid (HBr; 80·8) and 90 per cent of water.

CHARACTERS.—A clear, colourless liquid, odourless, having a strongly acid taste and an acid reaction. Sp. gr., 1·077. By heat it is completely volatilised. On adding chlorine or nitric acid to diluted hydrobromic acid, bromine is liberated, which is soluble in chloroform or in disulphide of carbon, imparting to these liquids a yellow colour. Test-solution of nitrate of silver causes a white

precipitate, insoluble in nitric acid and in water of ammonia, and sparingly soluble in stronger water of ammonia.

On being kept for some time, the acid should not become coloured; test-solution of chloride of barium should not produce a turbidity or precipitate (sulphuric acid).

DOSE.—Two fluid drachms, which are equal to about 18 grains of bromide of potassium. It may be given in syrup.

ACTION AND USES.—It appears to act as a sedative to the nervous system, diminishing reflex action and lessening tendency to spasm, in the same way as bromide of potassium, but differing from it in not producing the feeling of depression frequently caused by potassium bromide.

It has been employed in epilepsy, and to relieve nervousness.

It is useful in headache and singing in the ears, either idiopathic or due to the administration of quinine or of iron. It is used also to remove the bad effects of excess in tea or alcohol, and to quiet palpitation

U.S.P. Acidum Oleicum. OLEIC ACID.—$HC_{18}H_{33}O_2$; 282.

PREPARATION.—It is obtained from almond oil by adding lead oxide, which forms an oleate of lead, and decomposing this by hydrochloric acid. Or by decomposing palm oil by superheated steam.

CHARACTERS.—A yellowish, oily liquid, gradually becoming brown, rancid and acid, when exposed to the air; odourless, or nearly so, tasteless, and, when pure, of a neutral reaction. Sp. gr., 0·800 to 0·810. Oleic acid is insoluble in water, but completely soluble in alcohol, chloroform, benzol, benzin, oil of turpentine, and the fixed oils. At 14° C. (57·2° F.) it becomes semi-solid, and remains so until cooled to 4° C. (39·2° F.), at which temperature it becomes a whitish mass of crystals. At a gentle heat the acid is completely saponified by carbonate of potassium. If the resulting soap be dissolved in water and exactly neutralised with acetic acid, the liquid will form a white precipitate with test-solution of acetate of lead. This precipitate, after being twice washed with boiling water, should be almost entirely soluble in ether (abs. of more than traces of palmitic and stearic acids). Equal volumes of the acid and of alcohol, heated to 25° C. (77° F.) should give a clear solution, without separating oily drops upon the surface (fixed oils).

USES.—Oleic acid is employed only for the preparation of oleates, which are not only elegant preparations, but appear to be more readily absorbed than other ointments.

U.S.P.	PREPARATIONS.	DOSE.
Oleatum Hydrargyri.	OLEATE OF MERCURY (Hydrargyri Oxidum Flavum, 1 part; Acidum Oleicum, 9 parts)	10 min., externally.
Oleatum Veratrinæ.	(Veratrinum, 2 parts; Acidum Oleicum, 98 parts)	6-25 gr., externally.

Acidum Carbolicum.—*Vide* p. 734.

Acidum Salicylicum.—*Vide* p. 740.

CHAPTER XXIV.

METALS.

GENERAL CLASSIFICATION OF THE METALS.

It has already been mentioned (p. 19) that Mendelejeff's classification of the elements, although it gives us the outlines of a true natural classification, is not at present perfect, inasmuch as it separates members of natural groups such as those of the earthy metals. In regard to this classification it must be borne in mind that by it the elements are arranged in groups according to their atomicity, and this is not in all cases determined. A glance at the table (p. 17) will show this, for copper, silver, and gold are there included both in Group I., containing monad metals, and in Group VIII. But the commonest and most stable compounds of copper, such as cupric oxide or cupric sulphide, appear to show that it is a dyad rather than a monad. Silver also, though it appears like copper in Groups I., and VIII., may also be a dyad,[1] while gold forms two series of compounds, in one of which it is monad and in the other triad. In the classification which I have adopted I have followed Mendelejeff's tables, as modified by Watts, but I have modified them somewhat in order not to separate metals having a similar physiological action.

Class I.—MONAD METALS.[2]

Group I.—Alkalis—Potassium, Sodium, Lithium, *Cæsium*, *Rubidium*.

II.—Ammonium.

[1] The formula of argentous oxide is Ag_4O, and if this formula be correct, and silver be a monad, oxygen must be a tetrad ; but if silver be a diad, argentous oxide may be represented as $\begin{matrix} Ag-Ag \\ Ag-O-Ag. \end{matrix}$ owne's *Ch emistry*, by Watts, 12th ed. vol. i. p. 369.)

[2] The metals whose names are printed in italics are not officinal.

CLASS II.—DYAD METALS.

GROUP I.—Metals of the alkaline earths—Calcium, *Strontium*, Barium.

(Appendix.) Metals of the earths—Aluminium, Cerium, *Beryllium, Zirconium, Thorium, Lanthanum, Didymium, Yttrum, Erbium.*

II.—Magnesium.

III.—Copper, Zinc, Silver, Cadmium.

IV.—Mercury.

CLASS III.—TRIAD METALS.

Thallium, Iridium, Gallium.

CLASS IV.—TETRAD METALS.

Tin, Lead, *Titanium.*

CLASS V.—PENTAD ELEMENTS.

Nitrogen, Phosphorus, Arsenic, Antimony, Bismuth, *Vanadium, Tantalum, Niobium or Columbium.*

CLASS VI.—HEXAD METALS.

Chromium, *Uranium, Tungsten, Molybdenum.*

CLASS VII.—HEPTAD METALS.

MANGANESE, *vide* next group.

CLASS VIII.

GROUP I.—Iron metals. Iron, Nickel, Cobalt, Manganese.

II.—Platinum, Gold.

GENERAL TESTS FOR THE ACID RADICALS IN METALLIC SALTS.—As the same acids occur in the salts of different metals, the tests for their presence are described again and again in the Pharmacopœias. In order to save repetition, it may be advisable to give here in a tabular form the tests for the different acids. It is to be remembered that the same tests apply to the simple recognition of a metallic salt and to its detection as an impurity in other substances. The tests are generally applied to solutions of the salt in water.

Salt.	Reagent.	Reaction.
Acetate.*	Sulphuric acid.	Vapour of acetic acid given off and recognised by its smell.
,,	Ferric chloride.	Deep red colour.
Borate.	Sulphuric acid.	The saturated solution causes deposit of shining scales, which give a green colour to the flame of alcohol.
Benzoate.*	Dilute solution of ferrous sulphate.	Flesh-coloured precipitate.
Bromide.	Disulphide of carbon and chlorine water.	If disulphide of carbon be poured into a solution of the salt, the chlorine water added drop by drop, and the whole agitated, the disulphide will acquire a yellow or yellowish-brown colour. (If iodine be present there will be a violet tint.)
Carbonate.	Acid.	Causes effervescence.
Bicarbonate.	,,	Causes effervescence more abundant than in the case of the carbonate. With solution of mercuric chloride bicarbonates give a white, and carbonates a yellow, precipitate.
Citrate.*	Calcium chloride.	The solution remains clear, but deposits white precipitate on boiling (calcium citrate being less soluble in hot than in cold water).
,,	Sulphuric acid and heat.	Is charred and evolves the odour of acetic acid.
Chloride.	Nitrate of silver.	White precipitate, soluble in ammonia, insoluble in hydrochloric or nitric acid.
Hypophosphite.	Heat.	Heated in a dry test-tube it evolves phosphoretted hydrogen, which takes fire spontaneously, and burns with a bright flame.
,,	Nitrate of silver.	White precipitate, which rapidly turns brown and black.
,,	Hydrochloric acid and mercuric chloride.	White precipitate of calomel, and on further addition separation of metallic mercury.
Hyposulphite.	Sulphuric acid.	Gives rise to the smell of burning sulphur, and causes white precipitate of sulphur (bisulphite and sulphite give no precipitate).
Iodide.	Disulphide of carbon and chlorine water.	If disulphide of carbon be poured into a solution of the salt, then chlorine water added drop by drop, and the whole agitated, the disulphide of carbon will acquire a violet colour.

Salt.	Reagent.	Reaction.
Iodide.	Starch water, starch paste, or gelatinised starch, with chlorine water.	Blue colour in the cold, discharged by boiling.
Nitrate.	Sulphuric acid and copper.	Nitrous fumes.
,,	Sulphuric acid and solution of ferrous sulphate.	When sulphuric acid is added to a solution containing a nitrate, and a solution of ferrous sulphate is carefully poured over it, a dark colour appears at the junction of the two liquids.
Oxalate.*	Calcium chloride.	White precipitate. In applying the test to cerium and iron, their salts must be decomposed by boiling with potash or soda. The oxide of cerium or iron is removed by filtration, and the reagent applied to the filtrate, which contains oxalate of potash or soda.
Phosphate.	Chloride of ammonium, ammonia, and sulphate of magnesia.	White precipitate.
Phosphide.	Sulphuric or hydrochloric acid.	Evolves phosphoretted hydrogen.
Salicylate.*	Ferric salts.	Intense violet colour.
Sulpho-carbolate.	Ferric chloride.	Violet colour. This salt can be distinguished from the salicylate by heat, when it gives off inflammable vapours having the odour of carbolic acid.
Sulphate.	Barium chloride.	White precipitate, almost insoluble in nitric acid.
Sulphide.	Mineral acids, *e.g.* sulphuric or hydrochloric.	Gives off sulphuretted hydrogen.
Sulphite.	Ditto.	Gives off sulphurous acid (has neutral or feebly alkaline reaction).
Bisulphite.	Ditto.	Ditto (has acid reaction).
Tartrate.*	Acetic acid in presence of potash.	White crystalline precipitate of bitartrate.
,,	Sulphuric acid and heat.	Is charred and evolves the odour of burnt sugar.
,,	Nitrate of silver.	White precipitate, becoming black on boiling.
Bitartrate.*	Nitrate of silver.	Solution rendered neutral by potash, gives with the reagent a white precipitate becoming black on boiling (very sparingly soluble in water: is thus distinguished from neutral tartrate, which is readily soluble).
,,	Sulphuric acid and heat.	Same reaction as tartrate.

* In the preceding table the salts of organic acids marked * when ignited in a crucible, or on a piece of platinum foil, become charred and oxidised, leaving a residue which consists of carbonate. This is black from the presence of carbon, if ignition has not been carried sufficiently far to convert all the carbon into carbonic acid. This residue gives the reaction of a carbonate, effervescing with acids, and it is frequently convenient to convert the carbonate into chloride, before applying tests for the base.

Class I.—MONAD METALS.

GROUP I.—METALS OF THE ALKALIS.

Lithium, Sodium, Potassium, *Rubidium, Cæsium.*

GROUP II.—AMMONIUM.

I have omitted silver and gold from this class, because both their physiological actions and physical properties appear to show that they do not belong to it. I have put ammonia into a group by itself and separated it from the other members of this class, because it differs from them in being a compound and not an element; in being volatile; and in having an entirely different physiological action.

GENERAL CHARACTERS.—They are all powerful bases and have a great affinity for oxygen. The oxides of the first group are non-volatile and are sometimes termed fixed alkalis, while ammonia is volatile. They all have a strong alkaline reaction, neutralising acids readily, turning red litmus paper blue and turmeric paper brown.

GENERAL REACTIONS.—They are not precipitated from solutions by the successive addition of (1) hydrochloric acid, (2) hydrogen sulphide, (3) ammonium sulphide, (4) ammonium carbonate, and (5) sodium phosphate.

GENERAL PHYSIOLOGICAL ACTION.—The alkalis are of great physiological importance, and salts of potash and soda form a large proportion of the saline constituents of the body. These two bases are differently distributed, potash being chiefly found in solid tissues, while soda is more abundant in the fluids. They are found as carbonates, bicarbonates, chlorides, phosphates, and sulphates. The proportion of these salts in the body is, however, very different, as are also their uses in the economy. The chlorides are by far the most abundant, and sodium chloride may be looked upon as the most important constituent of the nutritive fluids in which all the tissues of the body are bathed. But while sodium chloride forms the saline basis of these fluids, the other constituents are indispensable for the continued life of the tissues. All the fluids of the body are alkaline, and death occurs whenever the alkalinity is diminished below a certain point, even though the fluids and tissues are far from having an acid reaction. Such a reaction is only observed in the tissues after death. The importance of the different saline constituents in nutrition has been most fully worked out in the case of the frog's heart (p. 264).

In the case of the **heavy metals,** which are not normal constituents of the body, the action of their **salts** depends almost entirely on the **base** and only slightly on the **acid** with which it

is combined. In the case of the **alkalis,** however, this is not so, the action of their salts depending much on the **acid.**

In consequence of this it is necessary in considering the physiological action of salts of the alkaline metals to divide them into at least three groups :—

1. Alkaline salts, hydrates, carbonates, and bicarbonates.
   (Sub-groups—Salts of organic acids, acetates, citrates, tartrates.)
2. Chlorides.
3. Sulphates and other salts which are slowly absorbed.

General Action of the Alkaline Group.—Alkaline salts have their activity diminished by combination with carbonic, or organic acids. The hydrates have an intense **local action** on the tissues; and the carbonates have an action, the same in kind, but much less in degree. In the case of the bicarbonates it is still further diminished, and in the acetates, citrates, and tartrates it is absent. The hydrates of potash and soda dissolve **horny tissues** such as the epidermis. They combine with **albumin** and form a soluble alkali-albuminate.

When applied to the **skin** the hydrated alkalis, which have a great affinity for water, withdraw it from the tissues and form a solution which softens and partly dissolves the epidermis and then acts on the softer textures below, combining with and dissolving them. Round the part thus killed, inflammation sets in, and a slough separates. The rapidity with which they absorb water and form a solution which flows readily over adjacent parts, where its action is injurious, is an objection to their application, and the part actually cauterised by them should always be less than the part we wish to destroy. From this very property of widely destroying the tissues over which they flow, or through which they soak, they are admirably adapted for application in cases where we desire this effect, as in cauterising poisoned wounds.

When applied as **caustics** to unhealthy sores, cancer, &c., their action is sometimes limited by adding lime and forming the so-called Vienna paste. The water which they withdraw from the tissues is sucked up by the lime, forming a solid hydrate and preventing the caustic from becoming too fluid and running over other parts. When less concentrated they may only irritate the surface sufficiently to produce exudation, but they generally soften or dissolve the epidermis so much that vesicles do not form well. When still more diluted they may cause only congestion or redness of the skin. They are then said to act as **rubefacients.** This rubefacient action may be used for the purpose of relieving troublesome itching in skin diseases, or to produce derivation from other parts.

Ammonia does not dissolve the epidermis and so, unlike potash or soda, it does not act as an immediate caustic, but only

passes through the epidermis and irritates the skin below, causing lymph to be effused between it and the epidermis, and thus acting as a **vesicant.** It may, however, act as a caustic if its evaporation is prevented and it is applied too long, the irritation then becoming so great as to lead to suppuration or even to sloughing of the part.

From their great solvent power, and especially their power of dissolving greasy substances, alkalis are used for **cleansing** the skin, but when used alone they very frequently produce irritation, and we therefore generally employ them in the form of soap, or in the form of those salts which have only a very slight alkaline character, such as borax.

In the **mouth** they neutralise any acid present. They may thus relieve toothache due to irritation of the exposed nerve in a carious tooth or of the roots of the teeth close to the gums by acid secretions. A dilute solution of sodium bi-carbonate as a wash to the mouth frequently relieves soreness of the teeth, or headache depending on dental irritation and prevents injury from acid tonics. Alkalis are used in the shape of borax to heal aphthæ in the mouth and as soap for cleaning the teeth.

In the **stomach** they increase the amount of gastric juice secreted; and where this is deficient and the food lies heavy and is digested slowly and with difficulty, they should be given before a meal or just at its commencement, either in the form of a medicinal mixture or as aërated potash or soda water. The amount of acid secreted by the stomach after their introduction is sufficient to neutralise them pretty rapidly, and probably only the caustic alkalies which act very rapidly have time to produce any local action before they are neutralised, unless large quantities have been ingested. Where there is a large amount of mucus on the surface of the stomach it will both hinder the exit of the gastric juice from the follicles and the entrance of the peptones from the stomach into the blood. Caustic alkalies have a great power of dissolving mucus. They probably do this to some extent before they are neutralised, and this may be the reason why we occasionally find that they are of great service when a corresponding amount of their carbonates does little or no good. From the effect they produce on the secretion of gastric juice, alkalis in small doses are said to act as **gastric stimulants** (p. 319).

When the amount of acid in the stomach is too great, either because too great a proportion of it has been present in the gastric juice, or because it has been generated by the decomposition of food, digestion goes on slowly, and acid, burning eructations take place after meals. In such cases we give alkalies to neutralise the excess and to restore the proportion of acid in the stomach to its normal. They are then said to act as **antacids** (p. 321).

Alkalies are serviceable as **antidotes** in poisoning by acids, metals, and alkaloids. They neutralise the acids, they precipitate the metals as insoluble oxides, and they render alkaloids less

soluble by taking away the acid with which they are generally combined. They thus retard their absorption and afford time for the use of other means.

The chyme from the stomach is normally acid, and will therefore act as a stimulus to the expulsion of bile from the gall bladder. It is partly neutralised by the bile and pancreatic juice, but generally remains acid throughout the small **intestines** and will act as a stimulus to the secretion of intestinal juice. If it be neutralised by alkalies in the stomach, this stimulus will be removed and digestion consequently impaired. Many substances will thus pass through the intestinal canal undigested, which amounts to the same thing as if less food had been taken.

Through this derangement of the digestion the blood will become poorer in solids, the person will become emaciated, the fat will naturally be first absorbed, and, along with this, perhaps pathological formations may also disappear.

The excessive use of alkalis or their carbonates is thus injurious and their employment to reduce obesity may, unless carefully watched, be followed by serious consequences like the use of acids for a similar purpose (pp. 497 and 498).

Caustic alkalies injected directly into the blood cause death in a few minutes, probably from formation of alkaline albuminate in the blood and its consequent coagulation. Shortly after death the blood is found coagulated. Smaller amounts taken in from the stomach will to some extent increase the alkalinity of the blood, but are rapidly separated by the **kidneys.** They cause thirst, and probably the larger amount of water drunk in consequence is one cause of the diuresis they produce. From their power of dissolving fibrin outside the body, they have been given in acute rheumatism to prevent fibrinous deposits on the heart. It is not certain that the amount we can introduce into the blood without injury to the patient has this effect.

After small doses of liquor potassii the urea and sulphuric acid in the urine are increased, and Parkes therefore thinks that the tissue change of the albuminous substances is increased. Alkalis are therefore classed as **alteratives** (p. 362).

They are used both to increase the amount of water passed and to diminish its acidity if this be excessive. They are therefore classed amongst **diuretics** (p. 379), and **remote antacids** (p. 321).

GENERAL ACTION OF THE GROUP OF CHLORIDES.—Chloride of sodium is not only one of the most abundant saline constituents of the animal body, but it is one of the most important **solvents** of albuminous substances. Water will dissolve albumins proper, but globulins are insoluble in it, and are precipitated by it from solutions. Dilute solutions of chloride of sodium on the contrary dissolve both albumins and globulins. From this action of water on albuminous substances it is very irritating when applied to a cut surface, or to the delicate mucous membrane of the nose,

while muscles dipped in it swell up, and pass into a state of rigor. Weak solutions of chloride of sodium, on the other hand, have no irritating action, and may be applied to cut surfaces or mucous membranes without causing pain, and to muscle and nerve without producing any injurious effect. A solution of the strength of 0·65 per cent. is the one usually employed in physiological experiments as a basis for the nutritive fluid in artificial circulation through the frog's heart or vessels, and as a solvent for alkaloids which are to be injected into the lymph sac of the frog, in order to avoid the local irritation which the injection of a watery solution would produce. A solution of this strength is often called "normal salt solution" in physiological treatises.

While dilute solutions of chloride of sodium are ready solvents of albuminous substances and are non-irritating, sodium chloride, in substance or in concentrated solutions, precipitates globulins, withdraws water from the tissues, and acts as an exceedingly powerful irritant to cut surfaces, mucous membranes, muscle, and nerve. Common salt taken in a large quantity at once will irritate the **stomach** and cause vomiting. It is **absorbed** with great rapidity, but is also excreted so rapidly that it produces no definite symptoms of irritation in any part of the body, excepting that part of the **nervous system** by which the sensation of thirst is perceived. This sensation becomes so urgent when much salt has been taken that any risk will be encountered in order to gratify it. Should it be impossible to obtain fresh water, other parts of the nervous system become involved, and travellers whose supply of water has failed in the desert, or shipwrecked sailors who have drunk sea water, have become delirious. It is difficult to say, however, how far the delirium is due to the direct irritant action of sodium chloride on the brain, as many other factors may concur in its production. Under ordinary circumstances, the thirst occasioned by sodium chloride, after its absorption, causes as much water to be drunk as will allow the salt to be excreted by the **kidneys,** leaving the proportion both of salt and water in the body nearly the same as before. During its stay in the body the salt does not appear to alter the composition of the **tissues,** and the chief alterations produced by it are probably due to its action on the solubility of albuminous substances and on the processes of osmosis between the intercellular fluid and blood, and the circulation of lymph in the tissues. In consequence of this, sodium chloride increases tissue change as is shown by an increase in the amount of urea excreted. A similar increase, however, occurs when the quantity usually taken is diminished, the amount of water daily consumed remaining the same. The alteration here is probably also due to increased rapidity of the circulation of fluid through the tissues (Voit), but it may also be due in part to the different solubilities of albuminous substances in solutions of sodium chloride of different strengths. Certain albuminous tissues may thus be

affected by one proportion of salt in the blood, others by another, so that increase and diminution of the normal proportion of sodium chloride may increase tissue change in the body as a whole, though not in the same tissues. The **proportion** of chloride of sodium in the body is not always the same. It depends on the quantity taken daily, and may be increased or diminished within certain limits. If a definite quantity be taken daily for some time, the same quantity will be found in the urine, so that the amount present in the body is constant. If the quantity consumed be now increased, no increase takes place in the excretion for about three days, a **storage** of salt taking place in the body. After about three days the quantity excreted daily in the urine will again be found equal to the quantity daily taken, the amount present in the body remaining constantly at the higher level. If the quantity daily taken be now diminished, no diminution takes place in the quantity excreted for about three days, and then the quantities daily taken and excreted again correspond. The amount stored up at first is now gone, and the proportion of salt in the body is now again reduced to its lower level.[1]

Increased consumption of sodium chloride not only increases the quantity of it and of urea in the urine but increases also the **excretion** of potash salts.

On the other hand, potash salts also increase the excretion of sodium. Between salts containing no chlorine, such as carbonate or phosphate, and the sodium chloride in the blood, a double decomposition takes place, potassium chloride, and sodium carbonate or phosphate, being formed. These newly-formed salts are unnecessary for the organism, and are excreted in the urine along with the unaltered remainder of the phosphate or carbonate administered. Considerable quantities both of chlorine and sodium may thus be removed from the organism. In consequence of this, herbivorous animals and people living chiefly on a vegetable diet, and who thus consume considerable quantities of potash salts, feel the need of sodium chloride greatly, and on the American prairies the herds of buffaloes travel hundreds of miles to visit the salt licks. Beyond a certain point, however, the excretion of sodium chloride is not increased by potash salts, and when the quantity of sodium salts in the body is low, excretion is not increased at all.

When an abnormal quantity of fluid is present in the tissues, as in dropsies, an increase in the saline constituents of the blood may cause its absorption, especially if the quantity of water drunk by the patient be limited. It is probable that in addition to their diuretic action the alkaline salts affect the nutrition of the tissues themselves, and that salts of potash are better than those of soda in cases of dropsy, because of their action on the tissues.

General Action of the Sub-Group of Sulphates, &c.—This group contains salts which are sparingly absorbed, such as

[1] Ludwig, *Manuscript Notes of Lectures*, 1869–1870.

sulphates, phosphates, and bitartrates. That they are sparingly absorbed is shown by the fact that when administered internally they only appear to a small extent in the urine. They usually act as **purgatives**, but if from any cause their purgative action should be prevented, and they remain long in the intestine, absorption will occur, though slowly. In herbivorous animals, which have a much longer intestinal canal than carnivora, larger doses of these salts are required to produce a purgative action. The mode of action has already been discussed (p. 342).

COMPARATIVE ACTION OF THE ALKALINE METALS.—As the action of the base appears to be less modified by the acid radical in the case of the chlorides than of other salts of the alkaline metals, they are better adapted for experiments on the comparative action of the members of this class.

Group I.—The chlorides of lithium, sodium, potassium, rubidium, and cæsium produce in **frogs** gradually increasing torpor, paralysis, and death. The chief action appears to be on the **spinal cord,** which is **paralysed,** a slight primary excitement occurring in the case of potassium and rubidium. Lithium and potassium paralyse also the ends of the **motor nerves.** Sodium does so also, though to a much less extent. Cæsium and rubidium do not do so, excepting when given in very large doses.

The contractile power of **muscle** is almost always diminished by lithium, unaffected by sodium, and increased by the other members of this group in small or moderate doses. Large quantities of potassium diminish both the irritability and contractile power of muscle voluntary and involuntary.

In frogs the heart becomes weaker and finally stops in diastole.

Group II.—Ammonium differs entirely from the members of the first group in the symptoms it produces. While they paralyse the spinal cord with little or no previous excitement, causing torpor and death, ammonia at first **stimulates** the cord, producing tetanic convulsions. The action of ammonium is considerably modified by the acid radical with which it is combined. All the ammonium salts have an action on the **spinal cord, motor nerves,** and **muscles,** and, in advanced poisoning, **paralyse** these structures.

They do not, however, affect all these structures with equal readiness. The organ first affected, and consequently (p. 20) the symptoms of poisoning, vary with the salt employed. Some salts affect the spinal cord first, others the motor nerves. Ammonia and ammonium chloride produce tetanus. The bromide produces hyperæsthesia with some clonic spasm, passing into tetanus, which, however, comes on very late.

The sulphate also produces hyperæsthesia and clonic spasms, but rarely tetanus. The phosphate produces paralysis without convulsions, either clonic or tonic, the only indication of any convulsant action being slight twitches accompanying movements in the hind limbs before reflex action has ceased. The iodide

produces progressive paralysis and no tetanus. The brain appears to be affected before the spinal cord. This is shown by the frog croaking when stroked, as it does after removal of the cerebral hemispheres, and by the reflex from the conjunctiva failing before that from the limbs.

Ammonium salts appear to form a **series,** at one end of which the members **stimulate** the spinal **cord** and have no marked paralysing action on the motor nerves, while those at the other end have no marked stimulating action on the cord, but, on the contrary, have a marked **paralysing** action both on the **cord** and on **motor nerves.** At the stimulating end of this series are ammonia and ammonium chloride, and at the paralysing end ammonium iodide; whilst the bromide, phosphate, and sulphate lie between.

GROUP I.—METALS OF THE ALKALIES.

POTASSIUM. K; 39.

GENERAL SOURCES OF POTASH SALTS.—The chief source of potash salts is the ash left by the combustion of plants or trees; but there are two subsidiary sources, viz., nitrate of potash, which is found native, and bitartrate of potash, which is deposited from wine in the process of fermentation.

GENERAL REACTIONS OF POTASH SALTS.—In analysis, potassium is distinguished from all other bases, excepting magnesium, sodium, and ammonium, by not being precipitated by ammonium sulphide nor carbonate of ammonia. The positive reactions by which its presence is ascertained are—(1) its precipitation when converted into an acid tartrate; (2) its precipitation by perchloride of platinum; (3) the violet colour it imparts to flame.

The sparing solubility of the **acid tartrate** is the test which is used in the U.S.P. to distinguish all salts of potash. The reagent employed is tartaric acid in the case of potassium hydrate, carbonate, and bicarbonate; in the case of the tartrate of potassium and sodium, acetic acid is used. In the case of most other salts a saturated solution of bitartrate of sodium is added to their aqueous solution. Potassium chlorate is calcined and the reagent added to a solution of the residue. Potassa sulphurata is decomposed by boiling with hydrochloric acid, the sulphur removed by filtration, and the filtrate neutralised by soda before the reagent is applied. No test for potassium is given in the case of potassium bitartrate or permanganate.

This test is only employed in the British Pharmacopœia in four instances, viz., neutral tartrate, acetate, bromide, and iodide. In the case of the neutral tartrate the test is applied by adding a small quantity of acetic acid, and thus producing acid tartrate. In the case of the acetate, bromide, and iodide, it is applied by adding tartaric acid. On the addition of **perchloride of platinum**

to chloride of potassium a double chloride of potassium and platinum is formed, and falls as a sparingly soluble pale-yellow precipitate. If the potassium salt be other than a chloride, part of the chlorine in the platinum salt is used up to convert the potassium into a chloride, and thus loss of the expensive reagent takes place. To avoid this loss hydrochloric acid is always to be added before the addition of the platinum salt. This reaction is not used for the bromides and iodides, because bromide and iodide of platinum would be formed and a loss of the reagent would occur. In testing some potassium salts, **modifications** are observed in the mode of applying the test. Before applying it to the chlorate the salt is calcined, oxygen is thus driven off, and the residue, consisting of chloride of potassium, does not require the addition of hydrochloric acid. The permanganate is also calcined, but the potash contained in the residue, after being dissolved out by water from its admixture with manganese dioxide requires to be treated with acid as usual. In the case of the sulphide the hydrochloric acid causes the evolution of hydrogen sulphide, which must be removed by boiling, and causes also the precipitation of sulphur, which must be removed by filtration before the addition of platinum chloride.

PREPARATION OF POTASH SALTS.

	Prepared from	By
Potassium carbonate, B. and U.S.P.	Wood ashes.	Lixiviating, evaporating, and crystallising.
Liquor potassæ, B.P. ,, potassii, U.S.P.	Carbonate of potash.	Treating solution with slaked lime and partially evaporating.
Caustic potash, B. and U.S.P.	Do.	Ditto, and evaporating to dryness.
Potassium bicarbonate, B. and U.S.P.	Do.	Passing carbonic acid gas into solution.
Potassium sulphite, U.S.P.	Do.	Passing sulphurous acid gas into strong solution until acid, adding equal weight of potassium carbonate, and crystallising.
Potassium acetate, B. and U.S.P.	Do	Dissolving in acetic acid.
Potassium citrate, B. and U.S.P.	Do.	Neutralising with citric acid.
Potassium hypophosphite, U.S.P.	Do.	Decomposing by hypophosphite of lime.
Potassium chlorate, B. and U.S.P.	Do.	Treating with lime and chlorine.

PREPARATION OF POTASH SALTS—(*continued*).

	Prepared from	By
Potassium ferrocyanide, U.S.P.	Carbonate of potash.	Heating animal matter and iron together.
Potassium cyanide, U.S.P.	Potassium ferrocyanide.	Igniting either alone, or with carbonate of potash. The former process gives a purer, the latter a more abundant, product.
Potassa sulphurata, B. and U.S.P.	Carbonate of potash and sulphur.	Heating together.
Potassium acid tartrate, B. and U.S.P.	Crude tartar or argol.	Treating with charcoal or clay.
Potassium tartrate, B. and U.S.P.	Acid tartrate of potash.	Neutralising with carbonate of potash.
Potassium nitrate, B. and U.S.P.	Native.	——
Potassium sulphate, B. and U.S.P.	Acid sulphate left from admixture of sulphuric acid and potassium nitrate in the preparation of nitric acid.	Neutralising with carbonate of potash or lime.
Potassium permanganate, B. and U.S.P.	Chlorate of potash, caustic potash, and oxide of manganese.	Ignition together, boiling and neutralising.
Potassium iodide, B. and U.S.P.	Potash and iodine.	Mixing and heating with charcoal.
Potassium bromide, B. and U.S.P.	Potash and bromine.	As in the iodide.

GENERAL ACTION OF POTASH SALTS.—According to Ringer, potash is a **protoplasmic poison** destroying muscle, nerves and nerve-centres when applied to them sufficiently long and in a sufficiently concentrated form. But this action is not peculiar to potassium, for sodium, ammonium, hydrocyanic acid, and probably many other substances possess it. Potash salts differ from soda salts in **diffusing** more readily through membranes. They are more easily absorbed and more easily excreted than soda salts. In the living organism they **occur** chiefly in the solid structures, such as blood-corpuscles and muscles, while soda salts occur chiefly in the fluids of the body.

When applied to **muscle,** potash salts in minute doses may increase its contractile power (p. 106); but in larger doses, or when continued for a longer time, they diminish its power and finally paralyse it altogether. They remove the excessive prolongation

of muscular contraction produced by veratrine, barium, calcium, strontium, and by large doses of sodium or lithium (p. 106).

They have a somewhat paralysing action on **motor nerves.** They paralyse also the **nerve-centres,** generally after a primary, transitory, excitement.

A peculiar difference in the action of sodium and potassium salts locally applied to the intestine has been already noticed (p. 334). Large doses paralyse the muscular fibre of the intestines, and it is possible that this paralysing action is the cause of the digestive disturbances which the prolonged use of potash salts causes (Rossbach).

When administered by the mouth they may produce, like other salts in large doses, irritation of the **gastro-intestinal** canal. They are, however, so quickly **excreted** that they can hardly produce poisoning by their action on the heart while circulating in the blood; they probably modify the nutrition of the tissues and act as alteratives. It is probable that potash salts may accumulate to a certain extent in the body in the same way as sodium chloride (p. 527). By feeding animals with potash salts the poisonous action of barium may be lessened. Cash and I have now found that when injected simultaneously with salts of barium (cf. p. 112), they will antagonise the action of the latter, and prevent death from an otherwise lethal dose of barium. Similar experiments with veratrine have given negative results. The prolonged use of potash salts is apt to cause some depression, and larger doses continued for some time may diminish the force of the circulation. They do not paralyse the **heart** when given by the mouth, but when injected directly into the veins they produce transitory excitement, clonic spasms, paralysis, and death.

Death is preceded by convulsions, and is caused by stoppage of the heart while respiration still continues. Even after both heart and respiration have ceased and the animal is apparently dead, life may be restored by the patient use of artificial respiration, and mechanical irritation of the heart by compressing the cardiac region. After the heart has thus been induced to beat spontaneously, respiration still remains in abeyance for some time. The **nerve-centres** are also paralysed, and neither voluntary movement nor reflex action occur for some time. When **reflex excitability** returns it is often much exaggerated, so that a slight shake or gentle touch on the surface may cause spasms. In this respect potassium somewhat resembles atropine, and the possible explanation of this action has already been discussed (p. 141).

The effect of potash salts on the **circulation** somewhat resembles that of digitalis. In large doses they cause a rapid fall of the blood-pressure and pulse-rate. Smaller doses cause a slight fall of both pulse-rate and pressure, followed by a rise of both. During the rise of pressure, however, the pulse becomes again slow, and continues so even when the pressure again begins to fall to the

normal. The rise of pressure occurs even when the spinal cord is divided, and probably depends on contraction of the arterioles (p. 240).

Potassæ Carbonas, B.P.; Potassii Carbonas, (K_2CO_3) $3H_2O$, 330, **U.S.P.** CARBONATE OF POTASH. K_2CO_3, with about 16 per cent. of water of crystallisation, B.P.

CHARACTERS AND TESTS.—A white crystalline powder, alkaline, and caustic to the taste, very deliquescent, readily soluble in water but insoluble in spirit, and giving the reactions of a carbonate and of potassium.

20 grains Carbonate of Potash } neutralise { 17 grains Citric Acid, or 18 grains Tartaric Acid.

DOSE.—10 to 30 grains.

ACTION.—When taken internally it acts as an **irritant** poison. It is rarely used internally, but may be given instead of liquor potassæ, or of bicarbonate, or in an effervescent form with citric or tartaric acid. It is chiefly employed in the preparation of other potash salts. A dilute solution of it may be used as an application to the skin to relieve itching, and for this purpose may be alternated with dilute acid.

Liquor Potassæ, B. and U.S.P. SOLUTION OF POTASH, B.P.; OF POTASSA, U.S.P.—An aqueous solution of hydrate of potassium (KHO; 56) containing about 5 per cent. of the hydrate, U.S.P.

USES.—Dilute liquor potassæ is used **externally** as a lotion in freckles, and, when diluted with water in the proportion of 1 to 6, is employed in order to soften in-growing toe-nails. It is also administered **internally** in scaly skin diseases, in eczema and acne, especially when these occur in gouty subjects, or are accompanied by acidity of the stomach. In cases of dyspepsia, with irritability, liquor potassæ is said to have a **sedative** action upon the stomach, and thus to be preferable to the bicarbonate. It is believed to be useful in jaundice, and enlargement or cancer of the liver. For its action upon the system it has been administered in rheumatism, both acute and chronic. It is given to cause the **absorption** of fat in obese persons but may destroy the general health (cf. p. 525). It has been used to cause the absorption of scrofulous glands and of bronchocele. It increases the bronchial secretion, and renders it more liquid and easier to cough up. It is therefore useful in bronchitis where the secretion is scanty and difficult to expectorate, and is equally serviceable in the intercurrent bronchitic attacks to which phthisical patients are liable (p. 217).

Potassa Caustica, B.P.; Potassa, U.S.P. KHO; 56. CAUSTIC POTASH.—Hydrate of potash, KHO, containing some impurities.

CHARACTERS AND TESTS.—In hard white pencils, very deliquescent, powerfully alkaline and corrosive. A watery solution gives

the reactions of potassium and those showing the absence of impurities.

PREPARATION CONTAINING CAUSTIC POTASH.

Liquor Potassæ ..... 27 grains in 1 fluid ounce.

PREPARATION IN WHICH CAUSTIC POTASH IS USED.

Potassæ Permanganas.

USES.—It is used as a **caustic** where we wish to burn deeply and widely, as in snake-bites, the bites of rabid animals, or in poisoned wounds. It is sometimes employed to open abscesses, more especially abscess of the liver, in which it is preferred to the knife, as by its use we secure adhesion of the liver to the abdominal wall before the abscess is opened, and thus prevent any pus from finding its way into the peritoneal cavity. Ringer says that the best way to apply it is to cut a hole in a thick piece of plaster, smaller than the size of the slough which we wish to make, and rub on the caustic potash, slightly wetted until the tissues assume a greyish colour, then to wash the part with vinegar, and apply a poultice.

U.S.P. Potassa cum Calce. Potassa with Lime; Vienna Paste.

PREPARATION.—Equal parts of caustic potash and lime made into a paste with alcohol.

CHARACTERS.—It is a greyish white, deliquescent powder with a strongly alkaline reaction. It gives the tests of potassium and calcium.

USES.—It is used for the same purposes and in the same manner as caustic potash, but being less deliquescent its action is slower and more limited; it is thus more easily restricted to the part which it is wished to destroy, and is less liable to spread.

Potassæ Bicarbonas, B. and U.S.P. BICARBONATE OF POTASH. $KHCO_3$; 100.

CHARACTERS AND TESTS.—Colourless right rhombic prisms, not deliquescent, of a saline feebly alkaline taste, not corrosive. Diluted hydrochloric acid causes strong effervescence, forming a solution which gives the reactions of potassium and those showing the absence of impurities.

20 grains Bicarbonate of Potash } neutralise { 14 grains Citric Acid, or 15 grains Tartaric Acid

DOSE.—10 to 40 grains.

PREPARATION.

B.P.

Liquor Potassæ Effervescens (Potash water)..... 30 grs. in 1 pint.

USES.—Solutions of bicarbonate of potash may be used **externally** to relieve itching. **Internally** it is given in dyspepsia, rheumatism, gout, and scalding depending upon excessive acidity of the urine with presence of uric acid, or in cases of deposit of this acid in the urinary passages.

Potassæ Acetas, B. and U.S.P. ACETATE OF POTASH. $KC_2H_3O_2$; 98.

CHARACTERS AND TESTS.—White foliaceous satiny masses, very deliquescent, with a watery solution of which tartaric acid causes a crystalline precipitate (potash), sulphuric acid the disengagement of acetic acid, and a dilute solution of perchloride of iron strikes a deep red colour (acetate).

IMPURITIES.—Acid, carbonate, lead.

TESTS.—Neutral to test paper (no acid); entirely soluble in rectified spirit (no carbonate). Its solution is unaffected by sulphide of ammonium (no metals).

DOSE.—10 to 60 grains.

PREPARATION IN WHICH ACETATE OF POTASH IS USED.

Tinctura Ferri Acetatis.

USES.—From its slight local action and its great solubility it produces little effect directly on the stomach and is easily absorbed into the blood. Here it is converted into carbonate and renders the blood and the secretions which come from it more **alkaline.** This salt of potash is one which is very frequently used for the purpose of rendering the urine alkaline. It is one of the most powerful saline **diuretics** we possess, and is much used in dropsies, alone or combined with other diuretics, or with tonics and stimulants, *e.g.* acetate of iron and acetic ether.

When given in large doses (120 grains and upwards) and in a concentrated form it acts as a **purgative.**

It is employed like other potash salts as an **alterative** in acute rheumatism, skin diseases, and enlarged glands.

Potassæ Citras, B. and U.S.P. CITRATE OF POTASH. $K_3C_5H_5O_7H_2O$; 324.

CHARACTERS AND TESTS.—A white powder, of saline feebly acid taste, deliquescent, and very soluble in water. Heated with sulphuric acid it forms a brown fluid, gives off an inflammable gas, and evolves the odour of acetic acid (citrate). Its solution gives the reactions of potassium and, mixed with a solution of chloride of calcium, remains clear till it is boiled, when a white precipitate separates which is readily soluble in acetic acid. This precipitate is citrate of lime, which is less soluble in hot than in cold water.

DOSE.—20 to 60 grains.

USES.—Is very pleasant to the taste, produces no local action and is very soluble. It is thus easily absorbed into the blood, and there becomes carbonate. It is less liable to purge than other potash salts, and can thus be given in larger doses. After absorption it acts like the carbonate, causes **diuresis** and **lessened acidity** or even alkalinity of the urine, and probably influences tissue change as well. It is **antiscorbutic.**

Potassæ Tartras Acida, B.P.; Potasii Bitartras, U.S.P. ACID TARTRATE OF POTASH, B.P.; BITARTRATE OF POTASSIUM, U.S.P. CREAM OF TARTAR. $KHC_4H_4O_6$; 188.

An acid salt obtained from the crude tartar which is deposited during the fermentation of grape juice, B.P.

CHARACTERS AND TESTS.—A gritty white powder, or fragments of cakes crystallised on one surface; of a pleasant acid taste, sparingly soluble in water, insoluble in spirit. Heated in a crucible it evolves inflammable gas and the odour of burned sugar, and leaves a black residue (tartrate). The calcined residue consists of potassium carbonate and gives its reactions.

DOSE.—20 to 60 grains as a diuretic; $\frac{1}{4}$-$\frac{1}{2}$ oz. as purgative.

PREPARATIONS IN WHICH ACID TARTRATE OF POTASH IS USED.

B.P.	U.S.P.
Acidum Tartaricum.	Pulvis Jalapæ Compositus.
Antimonium Tartaratum.	
Confectio Sulphuris.	
Ferrum Tartaratum.	
Potassæ Tartras.	
Pulvis Jalapæ Compositus.	
Soda Tartarata.	

USES.—From there being two equivalents of tartaric acid to one of potash it has a somewhat acid taste, and is used instead of tartaric or other acids for making **cooling** drinks in fevers, &c. A refreshing drink called Potus Imperialis, or Imperial, is made by dissolving 1 to $1\frac{1}{2}$ drachm of acid tartrate and a little sugar in a pint of boiling water and infusing with half the fresh peel of a lemon.

In small doses it is absorbed, oxidised in the blood to carbonate, and acts like the acetate as a **diuretic.**

In larger doses it retains water with great avidity, and prevents its absorption into the blood for a long time. It therefore causes the stools to be very watery, by detaining water in the intestine, but it has no irritating action on the intestine, and produces no increased peristalsis. If no other medicine be given to cause peristalsis, the salt and the water it has been retaining will be absorbed. Its action is thus very much like that of a simple enema of water going along the whole intestine, and like a simple enema it produces no depressing effect.

It is much used in dropsies as a **purgative,** generally in combination with jalap or scammony to produce peristalsis, whether the dropsy be due to affections of the heart or kidneys, and also in Bright's disease, even when unaccompanied by dropsy. It has also been employed as a laxative in dysentery, piles and prolapsus ani.

Potassæ Tartras, B.P.; Potassii Tartras, U.S.P. TARTRATE OF POTASH, B.P.; TARTRATE OF POTASSIUM, U.S.P. $2KO,C_8H_4O_{10}$ or $(K_2C_4H_4O_6)_2H_2O$; 470.

CHARACTERS AND TESTS.—In small, colourless, four or six-sided prisms. It gives the reactions showing the presence of tartaric acid and potassium like the bitartrate, but it is readily distinguishable by its greater solubility in water.

IMPURITY.—Bitartrate.

TEST.—Entirely dissolved by its own weight of water.

DOSE.—As a diuretic, 20—60 grains. As a purgative, $\frac{1}{4}$—$\frac{1}{2}$ ounce.

USES.—In small doses it is absorbed, converted into carbonate in the blood and acts as a **diuretic, antilithic,** &c., like the acetate and citrate. In larger doses it acts as a **purgative** like other saline cathartics.

Potassæ Sulphas, B.P.; Potassii Sulphas, U.S.P. SULPHATE OF POTASH, B.P.; OF POTASSIUM, U.S.P. K_2SO_4.

CHARACTERS AND TESTS.—Colourless hard six-sided prisms terminated by six-sided pyramids; decrepitates strongly when heated; sparingly soluble in water; insoluble in alcohol. Its solution in water gives the reactions showing the presence of potassium and a sulphate.

IMPURITIES.—Lime, chlorides, iron and lead.

TEST.—The solution should give no precipitate with oxalate of ammonia (no lime), nitrate of silver (no chloride), nor ammonium sulphide (no metals).

DOSE.—15 to 60 grains.

PREPARATIONS.

B.P.	
Pilula Colocynthidis Composita	1 part in 24.
,, ,, et Hyoscyami	1 ,, 36.
,, Ipecacuanhæ cum Scilla	1 ,, 3.
Pulvis Ipecacuanhæ Compositus	4 ,, 5.

USES.—Sulphate of potash is employed as a saline **purgative** in cases of dyspepsia, biliousness, and albuminuria. It is generally combined with some other aperient, such as rhubarb. From its hardness it is used to aid in pulverising tough vegetable substances, like ipecacuanha in the preparation of Pulv. Ipecacuanhæ Co. B.P. It was once supposed to have the power of arresting the secretion of milk, and was therefore given to women who wished to stop suckling.

Potassæ Nitras, B.P.; Potassii Nitras, U.S.P. NITRATE OF POTASH, B.P.; NITRATE OF POTASSIUM, U.S.P. KNO_3; 101.

Nitrate of potash of commerce, purified, if necessary, by crystallisation from solution in distilled water.

CHARACTERS AND TESTS.—In white crystalline masses or fragments of striated six-sided prisms, colourless, of a peculiar cool saline taste. Thrown on the fire it deflagrates; warmed in a test tube with sulphuric acid and copper wire it evolves ruddy fumes (nitrate). Its solution gives the reactions of potassium.

IMPURITIES.—Sulphates and chlorides, which are detected by the usual tests.

DOSE.—10 to 30 grains.

PREPARATIONS.

U.S.P.

Charta Potassii Nitratis. Nitrate of Potassium Paper. Unsized paper dipped in a 20 per cent. solution of nitrate of potash and dried.
Argenti Nitras Dilutus.

ACTION.—In large doses, nitrate of potash will produce death by **gastro-enteritis,** with vomiting, weakness, and arrest of the circulation, due partly to the reflex action of the drug, and partly to its direct action on the **heart** after absorption. When injected into the blood, it slows the pulse by lessening the irritability of the cardiac ganglia, lowers the **temperature,** and causes dyspnœa and death with convulsions. The convulsions are due to arrest of the heart, and consequent irritation of the brain by venous blood.

USES.—Nitrate of potash gives up its oxygen readily, and paper dipped in a strong solution of it (Charta potassii nitratis, U.S.P.) and then dried, may be burnt in a plate, and the fumes inhaled, in asthma. It has been suggested that among the products of combustion the nitrite of potassium is the most efficacious. A ball of nitre, kept in the mouth and allowed to melt slowly away, gives relief in cases of relaxed sore-throat. It has been used internally in acute bronchitis, spasmodic asthma (either internally or by inhaling its fumes), and in dyspepsia with congestion of the mucous membranes. Generally it is avoided in inflammation of the stomach, intestine, kidneys and bladder, on account of its local irritant action. On account of its action on the heart it has been given in hæmoptysis and other hæmorrhages. On account of its supposed action on the blood it was, and is, used in inflammation, fevers, and exanthemata. As an alterative it is used in scurvy, purpura, rheumatism and gout. Twenty grains of nitre with thirty of potassium bicarbonate taken in the morning in a large soda-water tumbler full of water will sometimes prevent the onset of a gouty paroxysm, and will also remove the headache consequent upon a debauch. Nitrate of potash is also used as a **diuretic** in cases of dropsy and gonorrhœa, and as a stimulant to the bladder in cases of incontinence of urine.

Potassæ Chloras, B.P.; Potassii Chloras, U.S.P. CHLORATE OF POTASH, B.P.; CHLORATE OF POTASSIUM, U.S.P. $KClO_3$; 122·4

PREPARATION.—By passing chlorine through a mixture of potassium carbonate and slaked lime. If potassium carbonate alone were used part of it would be converted into KCl and lost. $3K_2CO_3 + 3Cl_2 = 5KCl + KClO_3 + 3CO_2$. To save this, lime is

used which is much cheaper. After the mixture has been saturated with chlorine it is boiled, filtered, evaporated, and the chlorate crystallised out. $K_2CO_3 + 6CaH_2O_2 + 6Cl_2 = 2KClO_3 + 5CaCl_2 + CaCO_3 + 6H_2O$.

CHARACTERS AND TESTS.—In colourless rhomboidal crystalline plates, with a cool saline taste, sparingly soluble in cold water. It explodes when triturated with sulphur. By heat it fuses, gives off oxygen gas, and leaves a white residue, which dissolves in water and gives the reactions of potassium and of a chloride.

IMPURITIES.—Chloride and lime.

TEST.—Its solution is not affected by nitrate of silver (no chloride) nor oxalate of ammonia (no lime).

DOSE.—10 to 30 grains.

OFFICINAL PREPARATIONS.

B.P. AND U.S.P.	DOSE.
Trochisci Potassæ Chloratis	.....5 grains in each lozenge.—1 to 6.

Used also in preparing Potassæ Permanganas.

ACTION.—Chlorate of potash, when injected into the circulation, has not the same action as other salts of potash. Small doses generally at first depress, and afterwards raise the **blood pressure** and accelerate the **pulse.** Large doses cause sudden stoppage of respiration, and sinking of the blood-pressure down to zero, while the exposed heart continues to beat at nearly its normal rate, or a little over it, for half or three quarters of an hour.

Large doses administered medicinally have caused poisoning, especially in children. The symptoms are due to the hæmoglobin of the **blood** being converted in methæmoglobin by the action of the chlorate. They consist in hæmaturia with blood-casts and diminished secretion of urine, many of the renal tubules being filled with plugs of blood. The skin becomes discoloured or jaundiced, and death occurs with coma or convulsions.

USES.—Chlorate of potash is chiefly used as a **local** application to the mouth, to bring about a more healthy condition of the mucous membrane, and to cause ulceration present there to heal up. It is used in stomatitis occurring during nursing, on whatever this depends, in aphthæ, in cancrum oris. As a gargle it is used in follicular pharyngitis, and has been employed internally and as a local application in cases of croup, diphtheria, and spasm of the larynx. It may be used **internally** as a lotion to relieve the dryness of the throat after diphtheria and scarlatina. When taken early, it is said to lessen or arrest catarrhal conditions of the nose, throat, and larynx. It has been recommended in chronic mucous diarrhœa with whitish or mucilaginous-looking stools. It has also been used as an enema in cases of dysentery. **After absorption** into the blood it has been supposed to give off its oxygen,

and thus to have a disinfectant action in cases of blood-poisoning and malignant fevers. A great part of it is excreted unchanged by the kidneys, but in large doses it decomposes the blood and converts it into methæmoglobin. It has been employed in acute and chronic bronchitis, in order to thin the secretion and promote expectoration, and as a diuretic in cases of dropsy. It was recommended by the late Sir James Simpson in 20-grain doses three times a day, to pregnant women where abortion was liable to occur from fatty degeneration of the placenta.

Potassæ Permanganas, B.P.; Potassii Permanganas, U.S.P. PERMANGANATE OF POTASH, B.P.; PERMANGANATE OF POTASSIUM, U.S.P. $KMnO_4$. B.P. $K_2Mn_2O_8$; 314, U.S.P.

PREPARATION.—By heating caustic potash, and manganese dioxide together in a crucible with chlorate of potash which yields up its oxygen to the manganese and forms manganate of potash. $3MnO_2 + 6KHO + KClO_3 = 3K_2MnO_4 + KCl + 3HO$. On boiling this with water it is decomposed, permanganate being formed, and manganese dioxide being deposited. $3K_2MnO_4 + 2H_2O = 2KMnO_4 + MnO_2 + 4KHO$. On decanting from the manganese dioxide, neutralising with sulphuric acid, evaporating, filtering through asbestos, and evaporating further, the salt crystallises out.

CHARACTERS AND TESTS.—Dark purple, slender, prismatic crystals, inodorous, with a sweet astringent taste, entirely soluble in cold water. A single small crystal suffices to form with an ounce of water a rich purple solution. It gives off oxygen readily to organic substances and is decomposed, manganese dioxide being precipitated, so that the solution when mixed with a little rectified spirit and heated, becomes yellowish-brown. The crystals heated to redness decrepitate, evolve oxygen gas, and leave a black residue from which water extracts potash, recognised by its alkaline reaction and by the appropriate tests.

PREPARATION.

B.P. Solution of Liquor Potassæ Permanganatis (Permanganate of Potash 4 grs. in 1 fl. oz. of water).

Condy's Fluid is a solution of 2 grains to the ounce.

ADMINISTRATION.—The solution has a disagreeable taste, and the solid permanganate of potash gives off oxygen so readily that, if mixed with easily-oxidisable substances, such as sugar, syrup, or glycerine, the mixture may explode or take fire spontaneously. Martindale recommends that the necessary quantity of permanganate should be made into a pill with kaolin ointment consisting of equal parts of vaseline, paraffin, and kaolin.

ACTION.—Permanganate of potash very readily parts with its oxygen, and thus **destroys organic matter;** when mixed with **cobra poison** it completely destroys the deadly power of the latter, and the mixture may be injected subcutaneously without

any bad effects. When injected after the poison, however, it does not appear to come into such immediate contact with it in the tissues as to destroy it, and it therefore does not act as an antidote.

USES.—It is used to **disinfect** the stools in typhoid fever, and to disinfect the hands after making post-mortem examination, or after coming in contact with matters likely to convey contagion or infection (p. 85). It is applied as a lotion to wounds and sores, especially those having a foul-smelling discharge, and may be injected into the cavity of abscesses after evacuation of pus, or used to wash out the cavity of the pleura after the fluid has been removed in cases of pleurisy. In cases of ozæna it is employed to wash the nose, and as a lotion or gargle to the mouth in ulceration with fœtor, such as mercurial stomatitis, and also in diphtheria. It has been recommended internally in cases of diabetes. It is said by Ringer and Murrell to be of very great use in **amenorrhœa,** two or three grains being given in pill three or four times a day for some days before the period.

Potassa Sulphurata, B. and U.S.P. SULPHURATED POTASH, B.P.; SULPHURATED POTASSA, U.S.P.

CHARACTERS AND TESTS.—Solid, greenish fragments, liver-brown when recently broken, alkaline, and acrid to the taste, readily forming with water a yellow solution, which has the odour of sulphuretted hydrogen, and evolves it freely when excess of hydrochloric acid is dropped into it, sulphur being at the same time deposited. The acid fluid when boiled and filtered is precipitated yellow by perchloride of platinum, and white by chloride of barium.

IMPURITY.—Carbonate left in the preparation, or sulphate formed by decomposition.

TEST.—About three-fourths of its weight are dissolved by rectified spirit, in which both carbonate and sulphate are insoluble.

DOSE.—2 to 10 grains.

PREPARATION.

B.P.

Unguentum Potassæ Sulphuratæ (30 grs. to 1 oz. of lard).

ACTION.—When applied to the skin, the ointment may be used instead of simple sulphur ointment. In the intestine sulphurated potash seems to stimulate peristaltic action, and to act as a laxative. Apparently also, like sulphur it has a somewhat stimulating action upon the **respiratory** mucous membrane, and upon the **sweat** glands.

USES.—The ointment is used externally in cases of scabies and acne. Sulphurated potash is used as a bath in rheumatism (p. 413), and as a diaphoretic in albuminuria. It has been given internally in chronic bronchitis, croup, and whooping-cough, and used as an injection into the rectum to destroy ascarides, in solutions of half a grain to a grain in the ounce of water.

Potassæ Bichromas, B.P.; Potassii Bichromas, U.S.P. BICHROMATE OF POTASH, B.P.; BICHROMATE OF POTASSIUM, U.S.P. $K_2Cr_2O_7$; 294·8.

CHARACTERS AND TESTS.—In large red, transparent, four-sided tables; anhydrous; fuses below redness; at a higher temperature is decomposed, yielding green oxide of chromium and yellow chromate of potash, which may be separated by dissolving the latter in water. The bichromate dissolved in water gives a yellowish-white precipitate with chloride of barium, and a purplish red precipitate with nitrate of silver, and both these precipitates are soluble in diluted nitric acid. The solution also when digested with sulphuric acid and rectified spirit acquires an emerald green colour.

PREPARATION IN WHICH BICHROMATE OF POTASH IS USED.

Sodæ Valerianas.

Test Solution of Bichromate of Potassium, U.S.P. 1 in 10 of water.

ACTION.—In **frogs** it causes general feebleness of motion, respiration, and circulation, and sometimes convulsions. The nerve-centres are first excited and then depressed. The nerve-centres are affected before the nerves or muscles. The heart stops in diastole. In **mammals** it causes vomiting, diarrhœa, and bloody stools, great feebleness, and general clonic movements. In rabbits and guinea-pigs **convulsions** and **paralysis** occur, chiefly affecting the posterior limbs. Post-mortem a red coloration of the muscles is observed, and the gastric and intestinal mucous membranes are congested.

USES.—It has been used by Vulpian alternately with iodide of potassium and nitrate of silver in tabes dorsalis; and in doses of $\frac{1}{2}$-$1\frac{1}{2}$ grs. it is said to be useful in dyspepsia simulating cancer of the stomach.

Potassæ Prussias Flava, B.P.; Potassii Ferrocyanidum, U.S.P. YELLOW PRUSSIATE OF POTASH, B.P.; FERROCYANIDE OF POTASSIUM, U.S.P. $K_4Fe(CN)_6 3H_2O$; 421·9.—A salt obtained by fusing animal substances, such as the cuttings of horns, hoofs, and skins, with carbonate of potash, in an iron pot, lixiviating the crude product with water, and purifying the salt by crystallisation.

CHARACTERS AND TESTS.—In large yellow four-sided tablets or prisms, permanent in the air, soluble in water, insoluble in alcohol. The aqueous solution precipitates deep blue with persulphate of iron, brick-red with sulphate of copper, and white with acetate of lead. Heated with diluted sulphuric acid, hydrocyanic acid vapours are evolved.

USES.—As a test and in the preparation of hydrocyanic acid.

Test Solution of Yellow Prussiate of Potash. Dissolve $\frac{1}{4}$ ounce of yellow prussiate of potash in crystals in 5 fluid ounces of distilled water and filter, B.P., 1 in 10 of water, U.S.P.

Test Solution of Red Prussiate of Potash. Dissolve $\frac{1}{4}$ oz. of red prussiate of potash in crystals in 5 fluid ounces of distilled water and filter, B.P., 1 in 10 of water, U.S.P.

Potassii Iodidum, B. and U.S.P. IODIDE OF POTASSIUM. KI; 165·6.

PREPARATION.—By mixing iodine and solution of potash, when iodide and iodate of potassium are formed, $6KHO+6I = KIO_3+5KI+3H_2O$. The iodate is then reduced to iodide by roasting with charcoal, $5KI+KIO_3+3C = 6K3+4CO$.

CHARACTERS.—In colourless, generally opaque, cubic crystals, readily soluble in water, and in a less degree in spirit. It commonly has a feeble alkaline reaction; its solution gives the reactions of potassium and an iodide.

IMPURITIES.—Iodate from imperfect reduction, chlorides, sulphates, carbonates. Iodate is the most important impurity, since the dilute acid of the gastric juice will liberate free iodine from it in the stomach, and thus give rise to such gastric irritation that the iodide cannot be borne in doses where pure iodide would be readily tolerated.

TESTS.—The addition of tartaric acid, B.P., or dilute sulphuric acid, U.S.P., and mucilage of starch, B.P., or gelatinized starch, U.S.P., to its watery solution does not develop a blue colour. (Absence of iodate.) If iodate be present the acid liberates hydriodic acid, and this re-acting on the iodate forms free iodine, $6HI + KIO_3 = 3H_2O + KI + I_6$. Solution of nitrate of silver added in excess forms a yellowish-white precipitate, which, when agitated with ammonia, yields by subsidence a clear liquid in which excess of nitric acid causes no turbidity, B.P. (absence of chloride). Iodide of silver is insoluble in ammonia, but chloride is readily soluble, so the chlorides, if present, would be taken up by the ammonia and re-precipitated on the addition of acid. Its aqueous solution is only faintly precipitated by the addition of saccharated solution of lime.

DOSE.—2 to 10 grains.

PREPARATIONS CONTAINING IODIDE OF POTASSIUM.

B.P.	STRENGTH.
Linimentum Iodi	22 grs. in 1 fl. oz. nearly
,, **Potassii Iodidi cum Sapone**	4½ grs. in 1 fl. oz. nearly.
Liquor Iodi	30 grs. in 1 fl. oz.
Tinctura Iodi (Dose, 1-5 min.)	5½ grs. in 1 fl. oz. nearly.
Unguentum Iodi	16 grs. in 1 oz. nearly.
,, **Potassii Iodidi**	1 part in 8¾, nearly.

U.S.P.	DOSE.
Unguentum Potassii Iodidi	
Liquor Iodi Compositus	2-6 min. (0·10-0 40 c.c.)

Unguentum Potassii Iodidi, B. and U.S.P. OINTMENT OF IODIDE OF POTASSIUM. Iodide of potassium, 64 grains, carbonate of potash, 4 grains, distilled water, 1 fluid drachm, prepared lard, 1 ounce. Dissolve the iodide of potassium and carbonate of potash in the water, and mix thoroughly with the lard. B.P.

Iodide of potassium 12, hyposulphite of sodium 1, boiling water 6, benzoated lard 81, U.S.P.

The ointment is apt to become discoloured by the liberation of free iodine when iodide of potassium and lard only are used. The carbonate of potash, B.P., is added

in order that it may combine with any iodine set free, and the hyposulphite, U.S.P., is also used to prevent this discoloration.

B.P. Linimentum Potassii Iodidi cum Sapone. LINIMENT OF IODIDE OF POTASSIUM AND SOAP.—It contains hard soap, iodide of potassium, glycerine, oil of lemon, distilled water.

U.S.P. [Liquor Iodi Compositus. Iodine 5, iodide of potassium 10, distilled water 85. The iodide of potassium is used to hold the iodine in solution.

ACTION.—The action of iodide of potassium appears to depend partly on the iodine and partly on the potassium it contains. It differs from that of free iodine (p. 490) in being much less irritant. On this account it is of little use as a local stimulant, but it can be given in much larger doses. It has been supposed that iodine is set free from iodides in the stomach, but probably this is not the case, at least to any great extent, unless the iodides are contaminated with iodates. Iodide of potassium and other alkaline iodides are readily **absorbed.** It is conveyed by the blood to the various tissues of the body. It has been supposed by Binz to be partially **decomposed** by some of them, with the evolution of free iodine both in the blood and in the tissues, and he attributes its most important actions to this decomposition. The iodine set free from the iodide is taken up by **albuminous substances,** and the entrance of the iodine molecule into their composition causes them to undergo more rapid metamorphosis. Gummatous deposits appear to be especially affected in this way.

Lead and **mercury** also appear to be set free by it, from their combinations with the tissues, and entering once more into the circulation are eliminated. Iodides are **eliminated** very rapidly by the kidneys, salivary glands, probably by all mucous membranes, and by the skin. During the process of elimination iodine is occasionally set free and causes local irritation. This is especially marked in the mucous membrane of the **nose,** and in the skin, but it may occur also in the conjunctivæ, bronchi, and stomach. The irritation of the nasal mucous membrane thus produced gives rise to the symptoms generally known as **iodism.** They are exactly the same as those produced by prolonged exposure to the fumes of iodine. They consist of running at the nose, and frontal headache, which probably depends upon swelling of the mucous membrane lining the frontal sinuses. There is also frequently running of the **eyes.** Not unfrequently the **bronchial** mucous membrane becoming congested there is cough and pain in the chest. These symptoms are most readily produced by small doses of 2-5 grains, and they may usually be arrested either by discontinuing the medicine or increasing the dose. When the dose is raised to 10 grains the symptoms usually disappear, and I have only seen one case in which they persisted after the dose had been raised to 30 grains. In some persons the congestion is not confined to the nose but extends to the back of the throat and to the **larynx,** so that serious symptoms of suffocation may follow the laryngeal congestion produced in them by iodide. As the iodine is eliminated in the tears,

serious conjunctivitis may follow application of calomel to the eyes of persons who are taking iodide at the same time. Affections of the **skin** usually occur with large doses of iodide. The most common form of eruption is acne, but tubercular eruptions are also met with. They appear to be caused by decomposition of the iodide with elimination of free iodine in the sweat and sebaceous matter. They are said to be lessened by the simultaneous use of arsenic, and to be prevented by perfect cleanliness and daily baths. Occasionally the iodide causes **gastric** irritation with diminished appetite. It is readily excreted by the **salivary** glands, and may give rise to salivation (p. 313). It sometimes gives rise not only to congestion of the bronchial mucous membrane and cough, but to hæmoptysis, exudation into the pleural cavity, and even pneumonic consolidation.

In some persons it greatly depresses the **genital** functions.

During its excretion by the **kidneys** it acts as a diuretic, though not a very powerful one.

USES.—Although iodide of potassium is probably absorbed in very small quantity by the unbroken skin, even when mixed with oil or fat, yet the iodide of potassium and soap liniment, especially when mixed with its own bulk of opium liniment, sometimes gives considerable relief when applied to inflamed and rheumatic joints by means of flannel or lint. Iodide of potassium is chiefly used, however, internally in syphilis, rheumatism, scrofula and chronic poisoning by lead or mercury. In the primary and secondary stages of syphilis, mercury is generally used either alone or in combination with iodine. In the tertiary stage, iodide of potassium is more generally given alone, although it is said by some to have but little effect unless mercury has been administered at some previous time. If this opinion be correct, the beneficial action of iodide of potassium may be due, in part at least, to its again liberating part of the mercury which has been in a state of more or less dormant combination with some of the tissues. The powerful action of iodide of potassium in removing syphilitic deposits is readily seen when these deposits are superficial, as nodes on the shin or on the sternum, or when they can be readily seen like deposits in the larynx. Sometimes such deposits are unaffected by small doses, such as five grains of iodide, but disappear rapidly when the dose is increased to ten grains or more. From its beneficial action on visible deposits we may infer that it has a similar action on those which are deeply situated, and indeed sometimes we may observe enlargement and induration of the liver, probably dependent on a syphilitic condition, rapidly disappear under the use of the iodide. In chronic rheumatism, especially when the pain is worse at night, it is sometimes useful.

It apparently increases the activity of the lymphatic system, and is used in enlargement of glands connected with this system, *e.g.* enlarged thyroid, enlarged spleen, and the enlarged lymphatic glands which occur in scrofula, as well as in scrofulous conditions generally.

It is given wherever absorption is deficient and organs become hypertrophied, *e.g.* the breasts, testicles, prostate, uterus, ovaria, &c. In cancer and tubercle it is of little benefit, but it is sometimes given, and possibly with benefit, in order to aid the absorption of pneumonic consolidation.

In bronchitis with much congestion and deficient secretion it is a useful expectorant, rendering the mucus more abundant and less tenacious, so that it is more readily expectorated.

As syphilitic skin diseases often disappear under its use it has been applied to other skin diseases not dependent on syphilis, such as psoriasis, lepra, herpes, impetigo, lichen, prurigo, sycosis, acne, lupus, &c., especially in scrofulous patients.

In frogs it destroys sensibility and voluntary motion, by acting on the spinal cord. It is useful in large doses to diminish the pain in cases of aneurism, and is also used in neuralgia, paralysis, convulsions, &c.

The relief which it affords to the pain of aneurism is very marked, but it must be given in large doses, *e.g.* thirty grains. The benefit which it affords may be partly due to weakening of the circulation, partly to diminished sensibility by the action of the drug on the nervous system, and partly to beneficial alterations in the morbid condition of the walls of the affected vessels, which are often syphilitic in character.

It is exceedingly useful, as already mentioned, in chronic metallic poisoning, *e.g.* by mercury or lead.

It is used in dropsies as a diuretic, and is also employed as an emmenagogue.

Potassii Bromidum, B. and U.S.P. BROMIDE OF POTASSIUM. KBr.

CHARACTERS.—In colourless cubical crystals, with no odour, but a pungent saline taste, readily soluble in water, less soluble in spirit. Its aqueous solution gives the reactions of potassium and a bromide.

IMPURITY.—Iodide and bromate.

TEST.—For the iodide *vide* p. 543. Bromate is detected by adding dilute sulphuric acid to the crushed crystals. They should not at once assume a yellow colour. The acid liberates hydrobromic acid from the bromide, and if bromate be present the reaction between it and the hydrobromic acid liberates free bromine. $5HBr + HBrO_3 = 3H_2O + 3Br_2$.

ACTION.—Bromide of potassium does not seem to have, like the iodide, any marked influence on the lymphatic system ; and although it has been occasionally used instead of the iodide in lymphatic swellings and enlargements of organs, this use of it is not general. When swallowed in small doses it produces no effect, but when taken in **large doses** for a considerable time it causes an eruption like acne upon the face, the complexion at the same time

becoming muddy or bronzed. The chief symptoms are, however, impairment of the functions of the **spinal cord** and the **brain.** There is a great diminution of reflex action, so that touching the pharynx no longer produces any tendency to vomit, even though the touch itself be felt. There is drowsiness and heaviness, a great inclination to sleep and insensibility to outward impressions, the memory is impaired, the speech becomes hesitating and articulation imperfect, the intellect is less clear, the genital functions are much diminished, the gait becomes tottering and unsteady and the muscles weak. To these symptoms the name of **bromism** is given.

USES.—Its chief use is in **nervous diseases** for the purpose of producing sleep, allaying excitement, and diminishing spasm.

Bromide of potassium is most useful as a **hypnotic** in cases of sleeplessness due to mental excitement and worry. Some persons, after hard study or close attention to business, instead of sleeping at night are no sooner in bed than the brain seems to become doubly active, the carotids throb and they toss about from side to side trying in vain to get rid of the ideas which come in a constant train before them. In such cases when bromide of potassium is taken, the throbbing of the carotids and temporals and the fulness in the head disappear and sleep is induced. A dose of 10—15 grains given before bed-time may be sufficient in mild cases, but when the agitation is great 30 or 40 grains must be given, and should be assisted by cold ablution to the head and a prolonged warm foot-bath. The dose may be repeated, if necessary, every hour or two hours, until the desired effect has been obtained. One great advantage that bromide of potassium possesses over other hypnotics is that it can be pushed without fear, and the same is true of other bromides. They are not dangerous to life, and even when they are pushed so far as to cause bromism, the symptoms usually pass off rapidly when the drug is discontinued.

It is very useful in lessening the excitability, susceptibility to worry, and **irritability** of temper from which gouty persons often suffer. It should be given with a considerable proportion of water

In delirium tremens where there is sleeplessness with fearful visions it may be given in doses from 20—30 grains or even more, every two hours till sleep is induced. It is of most benefit in the earlier stages before the delirium has become furious, and is useful also at the end of the attack in dispelling delusions which may still remain.

During the later months of pregnancy, women are sometimes troubled at night with the imagination that they have committed or are about to commit some great crime, such as murdering their husbands or children, and these delusions, according to Ringer, are removed by potassium bromide.

It is also useful, he says, in the treatment of night screaming in children apparently allied to nightmare. They awake out of

sleep screaming, seem very much frightened, and do not appear to recognise their mother or other friends who try in vain to soothe them. In the sleeplessness of mania it is frequently, though not always successful. It may be used in fevers and inflammation when sleep is absent, and whenever opium and belladonna or hyoscyamus fail to produce sleep or cause sickness.

In **convulsive nervous affections** such as whooping cough, laryngismus stridulus and spasmodic asthma, it is very useful, and also to some extent in St. Vitus's dance and hysteria.

It is especially beneficial in **epilepsy,** and by its use the convulsions can almost always be lessened if not entirely stopped. A similar result has been obtained in experiments on animals (p. 156). It is not so useful when the convulsions are violent, and is not so beneficial when there is only a transitory loss of consciousness as in *petit mal.* It is perhaps, however, not so much a curative as an alleviative remedy, and the fits are apt to return when its administration is discontinued.

It is useful in relieving **sickness,** especially in pregnancy. In sea-sickness it is perhaps more useful than any other remedy. It should be taken in thirty-grain doses twice or thrice a day, for a day or two before the voyage begins, and should be kept up while it continues. In severe cases it may be necessary to push the bromide so far as to keep up a state of more or less somnolency and stupidity during the whole voyage.

From its power of lessening the sexual passion it is used as an **anaphrodisiac** in priapism and nymphomania.

It is also useful in menorrhagia, especially when this occurs in young women, according to Ringer, while Ganod says it is more useful in old women.

It is useful in neuralgia occurring in debilitated subjects, and sometimes accompanied by flushed face with cold hands and feet. It has been used in diabetes.

SODIUM. Na; 23.

SOURCES OF SODA SALTS.—The chief source of soda is common salt obtained by the evaporation of sea-water, or from salt mines. Two subsidiary sources are the nitrate of soda and borax, both of which are found native.

GENERAL REACTIONS OF SODA SALTS.—They are not precipitated by any of the ordinary reagents. The special test for them is the yellow colour which they give to flame. The mere appearance of the yellow colour is the test adopted by the British Pharmacopœia, but it is improved upon in the American Pharmacopœia, which directs that the flame should not appear more than transiently red when observed through a blue glass. In this way soda salts are both more readily distinguished from those of potash, and the presence of the slightest impurity is easily observed; for soda salts are so widely distributed in nature, and the yellow colour

which they give to the flame is so bright, that minute quantities of soda mixed with potash may disguise the violet colour which the potash gives, although it should be present in much greater quantity than the soda. To distinguish between potash salts and soda salts, it is therefore necessary to look at the flame through a blue glass which cuts off the yellow rays emitted by the sodium of the flame, and allows thus the violet ones of the potassium to be seen.

PREPARATION OF SODA SALTS.

	Prepared from	By
Sodium sulphate.	Sodium chloride.	Heating with sulphuric acid in the preparation of hydrochloric acid.
Sodium carbonate.	Sodium sulphate.	Roasting with calcium carbonate and coal.
Dried sodium carbonate.	Sodium carbonate.	Heating.
Sodium bicarbonate.	Do.	Mixing with dry carbonate and saturating with carbonic acid.
Sodium acetate.	Do.	Neutralising with acetic acid.
Effervescent citrotartrate.	Do.	Heating dry carbonate with tartaric and citric acids.
Tartrate of soda and potash (Soda tartarata).	Do.	Neutralising solution with acid tartrate of potash, evaporating and crystallising.
Sodium benzoate, U.S.P.	Do.	Neutralising a hot solution with benzoic acid and crystallising.
Sodium phosphate.	Do.	Decomposing bone ash with sulphuric acid, and saturating the acid phosphate of calcium thus obtained with sodium carbonate.
Sodium hypophosphite.	Do.	Decomposing hypophosphite of lime with sodium carbonate.
Liquor sodæ chloratæ.	Do.	Passing chlorine through its solution.
Sodium salicylate, U.S.P.	Do.	Neutralising solution by salicylic acid with slight excess of acid and evaporating.
Sodium sulphocarbolate, U.S.P.	Do.	Decomposing by barium sulphocarbolate. The barium sulphocarbolate is prepared by mixing equal parts of carbolic and strong sulphuric acid, allowing them to stand for some days, diluting and neutralising with barium carbonate.

PREPARATION OF SODA SALTS—(*continued*).

	Prepared from	By
Sodium bisulphite, U.S.P.	Sodium carbonate.	Saturating its solution with sulphurous acid.
Sulphite.	Sodium bisulphite.	Adding an equal weight of sodium carbonate to the bisulphite prepared as above.
Hyposulphite.	Sulphite.	Heating with sulphur.
Borax.	——	Found native.
Nitrate.	——	Found native.
Arseniate.	Carbonate and nitrate.	Fusing with arsenious acid.

GENERAL IMPURITIES OF SODIUM SALTS.—As sodium carbonate is prepared from sodium sulphate, and the latter from sodium chloride, sulphates and chlorides may be present as impurities in it. As the other sodium salts are chiefly obtained from the carbonate, chlorides and sulphates also come to be present as impurities in them. They also occur even in the nitrate of soda found native.

GENERAL TESTS FOR IMPURITIES IN SODA SALTS.—In order to distinguish between salts of potash and soda, as well as to prove the absence of potash as an impurity, the B.P. directs that the solutions of soda salts, when acidulated, should not give a precipitate with perchloride of platinum. The U.S.P. directs that the yellow colour which sodium salts give to the flame should not appear more than transiently red. The absence of chlorides and sulphates is ascertained by the usual tests and the absence of metals by the want of any colour or precipitate on the addition of hydrosulphuric acid or ammonium sulphide.

GENERAL ACTION OF SODIUM SALTS.—Salts of sodium **diffuse** more slowly than those of potassium. They are neither absorbed nor excreted so readily, and have not a marked diuretic action. When locally applied to **muscle** and **nerve** in large doses they paralyse both, but not so powerfully as salts of potassium, nor have they such a paralysing action upon the involuntary muscle, either of the **heart** or the **intestine.** In large doses they lengthen the muscular curve, and increase the length of the curves produced by calcium and strontium instead of shortening them like potassium (p. 117).

Urate of sodium is less soluble than urate of potassium or lithium. It is therefore less readily excreted, and forms the nodules known by the name of chalk stones in gouty patients.

Sodii Chloridum, B. and U.S.P. CHLORIDE OF SODIUM. COMMON SALT. NaCl; 58·4.

CHARACTERS AND TESTS.—In small white crystalline grains, or transparent cubic crystals, free from moisture, has a purely saline taste, imparts a yellow colour to flame, is soluble in water. The solution gives the reaction of a chloride, and does not give that of potassium.

PREPARATIONS IN WHICH CHLORIDE OF SODIUM IS USED.

Acidum Hydrochloricum. Hydrargyri Perchloridum.
Hydrargyri Subchloridum.

ACTIONS.—Although chloride of sodium is not much used as a remedy, it is most important as a **food.** It forms a large proportion of the salts of the body, and no doubt plays a very important part in tissue change. When persons are deprived of it for a length of time, the longing for it becomes intense, and animals will go very great distances to obtain it. When mixed with water, in the proportion of **0·65 to 100, the solution does not destroy animal tissues** like water alone, and may be mixed with blood without destroying the corpuscles. Strong solutions, however, are intensely irritating. When injected into the lymph sac of a frog it causes increased **diapedesis** of the red corpuscles, which then pass out through the vessels in considerable numbers. It is possible that an increase in the proportion of sodium chloride may have something to do with the production of scurvy, as this disease appears to be relieved by salts containing another base than sodium and another acid radical than chlorine.

USES.—Externally it is used as a **stimulant** to the skin in the form of baths (pp. 404 and 413). A solution of salt of $\frac{1}{2}$ to 1 per cent. has been recommended by Kühne to wash wounds and raw surfaces in place of water, as it does not destroy the vitality of the tissues, and a similar solution may be used instead of water to wash out the nasal cavities, either alone, or mixed with other medicaments. When taken in considerable quantities it produces vomiting, and may be used as an **emetic**, either alone or to aid the action of other emetics. Half a teaspoonful of dry salt, repeated until nausea is produced, is said sometimes to arrest hæmoptysis. It appears to diminish the secretion of mucus, and may be given to children suffering from worms, where the intestinal mucus is excessive and affords a nidus for the parasites.

After hæmorrhage there is generally excessive thirst, and the addition of chloride of sodium to the water drunk by the patient has been recommended in order to prevent destruction of the blood corpuscles which might arise from the absorption of slight amounts of pure water. During convalescence patients sometimes exhibit a desire for salt and indigestible food, which, if given, would probably derange the digestion, but the craving may be allayed by giving salt alone. It has been used in bilious diarrhœa, in doses of 10 to 60 grains, three or four times a day.

As an **enema** to destroy ascarides it is frequently used. The proportion generally is 1 or 2 table-spoonfuls to the pint of water.

Sodæ Carbonas, B.P.; Sodii Carbonas, U.S.P. CARBONATE OF SODA. $Na_2CO_3.10H_2O$; 286.

Obtained from the ashes of marine plants, or produced by chemical decomposition with chloride of sodium.

CHARACTERS AND TESTS.—In transparent, colourless, laminar crystals, of a rhombic shape, efflorescent, with a harsh alkaline taste and strong alkaline reaction. By heat it undergoes aqueous fusion, and then dries up, losing 63 per cent. of its weight.

20 grains Carbonate of Soda } neutralise { 9·7 grains Citric Acid / 10½ grains Tartaric Acid

DOSE.—5 to 30 grains.

PREPARATIONS.

B.P.	DOSE.
Sodæ Carbonas Exsiccata. Dried carbonate of soda (used for pills.)	3-10 grs.

USES.—It is not much used as a remedy. Its chief use is in the preparation of other soda salts. A dilute solution of it may be used as a wash to the skin to remove itching.

Soda Caustica, B.P.; Soda, U.S.P. CAUSTIC SODA, B.P.; SODA, U.S.P.—Hydrate of soda, NaHO, 40, with some impurities.

CHARACTERS AND TESTS.—Hard, greyish-white pencils or fibrous pieces, deliquescent in moist air, dry and efflorescent in dry air, very alkaline and corrosive. It gives the tests of sodium, and not of potassium. It imparts a yellow colour to flame, and its solution in water, acidulated by nitric acid, effervesces only slightly (limit of carbonate) and gives only scanty white precipitates with nitrate of silver and chloride of barium (limit of chlorides and sulphates).

IMPURITIES.—Carbonate, chlorides and sulphates.

PREPARATION CONTAINING CAUSTIC SODA.

Liquor Sodæ .....18·8 grains in 1 fluid ounce.

USE.—Is used as a **caustic** like potash, but has less affinity for water, and so does not take it from the tissues and destroy them so powerfully. At the same time it has less tendency to run over adjacent parts.

Liquor Sodæ, B. and U.S.P. SOLUTION OF SODA.—An aqueous solution of hydrate of sodium (NaHO; 40) containing about 3 per cent. of the hydrate, U.S.P. (4·1 per cent. B.P.).

CHARACTERS.—Like those of liquor potassæ, but it is not precipitated by tartaric acid nor by perchloride of platinum.

USES.—Is used in preparing ferric oxide and in other pharmaceutical processes, as it is cheaper than solution of potash. Internally it may act on the blood, rendering it and the secretions more alkaline, but will not alter nutrition in the way that potassium salts do.

Sodæ Bicarbonas, B.P.; Sodii Bicarbonas, U.S.P. BICARBONATE OF SODA. $NaHCO_3$; 84.

CHARACTERS AND TESTS.—In powder, or small opaque irregular scales, white, of a saline not unpleasant taste. It gives the reactions showing the presence of sodium, and of carbonic acid. It is distinguished from carbonate by its solution in cold water giving a white and not a coloured precipitate with solution of perchloride of mercury.

20 grains of Bicarbonate of Soda } neutralise { 16·7 grains of Citric Acid, or 17·8 grains Tartaric Acid.

DOSE.—10 to 60 grains.

PREPARATIONS CONTAINING BICARBONATE OF SODA.

B.P. DOSE.

Liquor Sodæ Effervescens (soda water)...30 grains in 1 pint .....½-1 pint.
Sodæ Citro-tartras Effervescens.....17 parts in 31.....6 grs. to ¼ oz.
Trochisci Sodæ Bicarbonatis.....5 grains in each lozenge ...1 to 6.

U.S.P.

Sodii Bicarbonas Venalis. COMMERCIAL BICARBONATE OF SODA.—Should contain 95 per cent. of pure bicarbonate, which it resembles in appearance and tests.

Misturæ Rhei et Sodæ. MIXTURE OF RHUBARB AND SODA.—Bicarbonate of soda 3, fluid extract of rhubarb 3, spirit of peppermint 3, water q.s. to make 100.

USES.—Bicarbonate of soda has a slight local irritant action. It may be used as a wash in cases of itching skin diseases, *e.g.* prurigo, and as a lotion to eczema. The strength is 2 grains to the ounce, and it is applied like water dressing.

A solution of this strength when used to rinse the mouth sometimes relieves the pain of toothache, and also relieves headache, either temporal or occipital, depending on decayed teeth, even though no pain should be felt in the tooth itself.

It may also be used to prevent injury to the teeth from acid tonics.

Mixed with tincture of opium, and introduced into the cavity of a decayed tooth by means of a pledget of cotton-wool, it will often arrest the pain of toothache. When swallowed, it stimulates the secretion of gastric juice, and is a most efficient remedy when given from ten minutes to half an hour before meals, in cases of atonic dyspepsia, where the patient complains of weight or pain at the pit of the stomach, pain between the scapulæ, and much flatulence unaccompanied by constipation. In such cases it is often advantageous to combine it with a bitter tonic and some carminative. As dyspepsia often occurs in persons engaged in business who cannot carry mixtures about with them, the lozenges (B.P.) are very useful, for they can be easily carried about and taken when necessary.

It also relieves frontal headache, unaccompanied by constipation, where the headache is situated just at the junction of the forehead with the hairy scalp. Frontal headache, lower down, just

above the eyebrows, is better treated by nitro-hydrochloric acid. In persons who suffer from great acidity after meals, it may be used as an antacid. A solution of ½ or 1 grain to the ounce of water or milk is exceedingly useful in the diarrhœa and marasmus of infants.

It is also serviceable in cases of diabetes, to lessen the amount of sugar. It renders the bronchial secretion less tenacious, but is not so useful as bicarbonate of potash. The lozenges are very convenient in such cases.

It seems to have less tendency than potash to produce catarrh of the stomach, and may be used for a longer time (p. 532).

As soda naturally exists in large quantity in the blood, the amount we can add is but a small fraction of that quantity and its alterative action is very slight. It will increase the alkalinity of the blood, and has been given instead of bicarbonate of potash in acute rheumatism, but it is perhaps not so good. The urate of soda is not so soluble as that of potash, so it is not so good in uric acid diathesis, and its diuretic power is also less.

B.P. Sodæ Citro-Tartras Effervescens. EFFERVESCENT CITRO-TARTRATE OF SODA.

CHARACTERS.—A granular powder which effervesces on the addition of water.

DOSE.—60 grains to ¼ ounce.

USE.—If absorbed there may be some slight difference between the effect of this salt and of tartarated soda, which contains some potash, but this is very slight, and of no importance. It is used only for its laxative effect. It is both pleasanter to take than tartarated soda, and it is less likely to cause unpleasant feelings in the stomach.

Soda Tartarata, B.P.; Potassii et Sodii Tartras, U.S.P. TARTARATED SODA, B.P.; TARTRATE OF POTASSIUM AND SODIUM, U.S.P. ROCHELLE SALT. $NaKC_4H_4O_6.4H_2O$; 282.

CHARACTERS AND TESTS.—In colourless, transparent prisms, or halves of prisms, of the right rhombic order, generally eight-sided; tasting like common salt. Heated with sulphuric acid it blackens, evolving inflammable gases and the odour of burnt sugar (tartrate). It imparts a yellow colour to flame (sodium). A strong solution gives a crystalline precipitate with a small quantity of acetic acid (potassium).

IMPURITY.—Bitartrate of potash.

TEST.—Entirely soluble in cold water.

DOSE.—¼ to ½ ounce; as diuretic 30 to 60 grains.

USES.—In large doses it retains water, quickens peristalsis, acts as a purgative and is chiefly used as such. In small doses it is absorbed from the intestines, is converted in the blood into carbonate of potash and soda, causes diuresis and renders the urine alkaline. It may be used as a remote antacid.

Sodæ Acetas, B.P.; Sodii Acetas, U.S.P. ACETATE OF SODA, B.P.; ACETATE OF SODIUM, U.S.P. $NaC_2H_3O_2.3H_2O$; 136.

CHARACTERS AND TESTS.—In transparent colourless crystals, soluble in water, forming a solution which gives the reactions of sodium and an acetate.

PREPARATIONS IN WHICH ACETATE OF SODA IS USED.

Ferri Arsenias. Ferri Phosphas. Syrupus Ferri Phosphatis.

USE.—Is converted in the blood into carbonate. Is a less powerful diuretic than the corresponding salt of potash.

DOSE.—20 to 60 grains.

Borax, B.P.; Sodii Boras, U.S.P. BORAX, B.P.; BORATE OF SODIUM, U.S.P. BIBORATE OF SODA. $Na_2B_4O_7.10H_2O$; 382.

A native salt. It is also made artificially by boiling together, in proper proportions, boracic acid and carbonate of soda.

CHARACTERS AND TESTS.—In transparent, colourless crystals, sometimes slightly effloresced, with a weak alkaline reaction; insoluble in rectified spirit, soluble in water. A hot saturated solution, when acidulated with any of the mineral acids, lets fall, as it cools, a scaly crystalline deposit (boracic acid), the solution of which in spirit burns with a green flame.

DOSE.—5 to 40 grains.

PREPARATIONS.

B.P.

Glycerinum Boracis..... 1 part in 6 by weight = (1 oz. in 4 fluid oz. glycerine.)
Mel Boracis ..... 56 grains in 1 ounce.

USES.—Borax destroys low vegetable organisms and prevents their germination. It thus acts as a **disinfectant.** Applied to the skin, it removes the epidermis, and may be used for this purpose instead of soap. It is used as a lotion in acne. It forms a useful wash to remove scurf from the head, chloasma or liver spots, and to allay itching in urticaria, psoriasis, impetigo, and pruritus pudendi, scroti, and ani. As an injection it is useful in leucorrhœa and gonorrhœa. It is much employed in aphthous conditions of the mouth and throat, either alone or combined with chlorate of potash. It may be given simply in solution, or in the form of the honey, or glycerine. It has been supposed to have a special action upon the **uterus,** and has been employed in amenorrhœa, dysmenorrhœa, and puerperal fever and convulsions. On account of its asserted power to increase the uterine contraction, it ought either to be avoided or employed with care during pregnancy. Borax is useful in some cases of epilepsy in doses of 10—15 grains three times a day. It acts as a solvent to benzoic acid.

Sodæ Sulphas, B.P.; Sodii Sulphas, U.S.P. SULPHATE OF SODA, B.P.; SULPHATE OF SODIUM, U.S.P. GLAUBER'S SALT. $Na_2SO_4.10H_2O$; 322.

PREPARATION, B.P.—May be obtained from the residue left in the manufacture of hydrochloric acid, by neutralising it with carbonate of soda, and crystallising from solution in water.

CHARACTERS AND TESTS.—In transparent oblique prisms; has a salt and bitter taste; effloresces on exposure to the air; soluble in water, insoluble in spirit. It gives the reactions of sodium and of a sulphate.

DOSE.—$\frac{1}{4}$ to 1 ounce.

USES.—Sulphate of soda, when introduced into the stomach, is supposed to excite peristaltic movements in it, and to have a similar action upon the intestine. It produces in the intestine a secretion of watery fluid, and acts as a purgative. It is used either alone, or mixed with bicarbonate of soda, in ulcer of the stomach, chronic gastritis, and dilatation of the stomach. A mixture of sulphate and bicarbonate of soda has been used in imitation of the Carlsbad salts obtained by evaporation of the natural mineral water of Carlsbad. The mixture, or the natural salts, ought to be taken dissolved in warm water immediately after rising, and it is better to sip the solution at intervals, while dressing, than to drink the whole off at a draught (p. 356). One third of a teaspoonful of the crystallised salts in a large tumblerful of warm water, taken immediately on rising, is frequently sufficient to produce one free action of the bowels after breakfast and no more. This quantity of salts, with a smaller quantity of water, may have no action; and if a smaller quantity of water be used along with a larger quantity of salts it not unfrequently happens that several scanty motions occur during the day with considerable discomfort in the abdomen.

Carlsbad water, natural or artificial, is also useful in bilious disorders, and in persons of a gouty diathesis. A gentle course will often remove the dulness, irritability, and other symptoms which accompany biliary derangements or precede a gouty attack. It may be used, also, with advantage in chronic constipation and tendency to congestion of the brain or of the abdominal and pelvic organs. A continued course of the water is exceedingly beneficial in cases of excessive obesity, and also in diabetes mellitus.

The Carlsbad waters contain a number of other salts which are not crystallised out, and they often prove much more efficient when drunk at the springs, than the solution of the salts taken by patients at their own homes. The great benefit which is often obtained from a course of the waters at Carlsbad is no doubt due in great measure to the diet and regimen which patients will follow there in company with others, but which nothing would induce them to conform to while at home.

Sodæ Phosphas, B.P.; Sodii Phosphas, U.S.P. PHOSPHATE OF SODA, B.P.; PHOSPHATE OF SODIUM, U.S.P. $Na_2HPO_4.12H_2O$; 358.

CHARACTERS AND TESTS.—In transparent, colourless, rhombic prisms, terminated by four converging planes, efflorescent, tasting like common salt. It imparts a yellow colour to flame. Its solution has a faintly alkaline reaction, it gives a yellow precipitate with nitrate of silver, the resulting fluid acquiring an acid reaction (phosphate).

DOSE.—As purgative $\frac{1}{4}$ to 1 ounce. As alterative 20 to 40 grains.

USES.—It is used as a purgative in children and in delicate persons, both because it acts gently and has little or no taste. It may be easily given to children in a little soup without their knowing it.

It has been used in fevers as a purgative, and in rickets in order to supply phosphoric acid to the bones. It has been found especially useful in children with hepatic derangement, as shown either by white or green stools, or by jaundice. The dose for them is 3 to 10 grains given in food or milk.

U.S.P. Sodii Chloras. CHLORATE OF SODIUM. $NaClO_3$; 106·4.

CHARACTERS.—Colourless, transparent tetrahedrons, of the regular system; permanent in dry air, odourless, having a cooling saline taste and a neutral reaction. Soluble in 1·1 parts of water and in 40 parts alcohol at 15° C. (59° F.); in 0·5 part of boiling water and in 43 parts of boiling alcohol. When heated the salt melts, and afterwards gives off a portion of its oxygen, finally leaving a residue of sodium chloride which gives the reaction peculiar to it.

USES.—Similar to those of chlorate of potassium. As it is more soluble, stronger solutions can be employed.

Sodæ Hypophosphis, B.P.; Sodii Hypophosphis, U.S.P. HYPOPHOSPHITE OF SODA, B.P.; OF SODIUM, U.S.P. NaH_2PO_2. H_2O; 106.

CHARACTERS.—Small, colourless or white, rectangular plates, or a white granular powder, deliquescent on exposure to air, odourless, having a sweetish saline taste and a neutral reaction. Soluble in 1 part of water and in 30 parts of alcohol at 15° C. (59° F.); in 0·12 part of boiling water and in 1 part of boiling alcohol. When heated in a dry test-tube the salt loses water, and then evolves a spontaneously inflammable gas (phosphoretted hydrogen), burning with a bright yellow flame. A fragment of the salt imparts to a non-luminous flame an intense yellow colour, not appearing more than transiently red when observed through a blue glass. On triturating or heating the salt with an oxidising agent the mixture will explode.

DOSE.—1 to 5 grains.

PREPARATION.
U.S.P.
Syrupus Hypophosphitum.

USES.—It is said to have a stimulating action upon the **nervous system,** and to increase digestion and **nutrition.** It is

chiefly given in the earlier stages of phthisis (*vide* p. 646), and in anæmia and nervous debility.

U.S.P. Sodii Benzoas. BENZOATE OF SODIUM. $NaC_7H_5O_2.H_2O$; 162.

CHARACTERS.—A white, semi-crystalline, or amorphous powder, efflorescent on exposure to air, odourless, or having a faint odour of benzoin, of a sweetly astringent taste, free from bitterness, and having a neutral reaction.

TESTS.—When heated the salt melts, emits vapours having the odour of benzoic acid, then chars, and finally leaves a blackened residue of an alkaline reaction and exhibiting the reactions of sodium. On mixing an aqueous solution of the salt with a dilute solution of ferric sulphate a flesh-coloured precipitate is produced.

DOSE.—10 to 20 grains.

USES.—It has been strongly recommended as a remedy in phthisis, and has also been used in puerperal fever and to eliminate uric acid in gout.

U.S.P. Sodii Bromidum. BROMIDE OF SODIUM. NaBr; 102·8.

CHARACTERS.—Small, colourless, or white monoclinic crystals, or a crystalline powder permanent in dry air, odourless, having a saline, slightly bitter taste, and a neutral or faintly alkaline reaction. Soluble in 1·2 parts of water and in 13 parts of alcohol at 15° C. (59° F.). It gives reactions of sodium, and if disulphide of carbon be poured into a solution of the salt, then chlorine water added drop by drop, and the whole agitated, the disulphide will acquire a yellow or yellowish-brown colour (bromide) without a violet tint (absence of iodide).

DOSE.—15 to 60 grains.

ACTION.—Its actions are the same as those of bromide of potassium, but it is said to be less irritating to the stomach.

U.S.P. Sodii Iodidum. IODIDE OF SODIUM. NaI; 149·6.

CHARACTERS.—Minute, colourless, or white monoclinic crystals, or a crystalline powder, deliquescent on exposure to air, odourless, having a saline and slightly bitter taste and a neutral or faintly alkaline reaction. Soluble in 0·6 part of water and in 1·8 parts of alcohol at 15° C. (59° F.). If disulphide of carbon be poured into a solution of the salt, then chlorine water added drop by drop, and the whole agitated, the disulphide of carbon will acquire a violet colour.

DOSE.—5 to 30 grains.

USES.—It is employed in place of iodide of potassium. Its physiological actions are almost exactly the same, but it appears to irritate the stomach less and may thus be given in larger doses.

U.S.P. Sodii Pyrophosphas. PYROPHOSPHATE OF SODIUM. $Na_4P_2O_7.10H_2O$; 446.

CHARACTERS.—Colourless, translucent, monoclinic prisms, permanent in the air, odourless, having a cooling, saline and feebly alkaline taste, and a slightly alkaline reaction. Soluble in 12 parts of water at 15° C. (59° F.) and in 1·1 parts boiling water; insoluble in alcohol. Its aqueous solution with excess of test-solution of nitrate of silver gives a white precipitate and a neutral filtrate.

ACTION.—Its actions in medicinal doses appear to be nearly the same as those of the phosphate, but probably it would have a greater influence on the nervous system.

USES.—To prepare the pyrophosphate of iron.

U.S.P. Sodii Salicylas. SALICYLATE OF SODIUM. $2NaC_7H_5O_3.H_2O$; 338.

CHARACTERS.—Small, white, crystalline plates, or a crystalline powder, permanent in the air, odourless, having a sweetish saline and mildly alkaline taste and a feebly acid reaction. Soluble in 1·5 parts of water and in 6 parts of alcohol at 15° C. (59° F.); very soluble in boiling water and in boiling alcohol. When heated the salt gives off inflammable vapour and leaves an alkaline residue amounting to between 30 and 31 per cent. of the original weight, and which gives the reaction of sodium carbonate.

DOSE.—In rheumatism with high temperature 10-20 grains every two to four hours. The addition of some aromatic spirit of ammonia, or alcohol in some form, tends to lessen the cardiac depression which the salicylate alone may cause.

ACTION.—It agrees in its action with salicylic acid, excepting that it has no power to destroy low organisms. In febrile conditions, and especially in acute rheumatism, it greatly lowers the **temperature** and lessens the pain. Its use should be continued for some time after apparent convalescence, as the temperature is apt to rise again when the administration of the remedy ceases. In small doses it is useful in chronic rheumatism. In doses of ½ to 2½ grains every quarter or half hour it will often cut short headaches. The symptoms of its physiological action are the same as those of salicylic acid, ringing in the ears, &c. (pp. 193 and 194). These symptoms may be lessened by ergot, hydrobromic acid, or bromides. It renders the **bile** more watery, and may be used to prevent gall stones.

U.S.P. Sodii Santoninas. SANTONINATE OF SODIUM. $2NaC_{15}H_{19}O_4.7H_2O$; 698.

PREPARATION.

Trochisci Sodii Santoninatis. Dose—1 grain in each.

CHARACTERS.—Colourless, transparent, tabular, rhombic crystals, slowly coloured yellow by exposure to light, slightly efflorescent in dry air, odourless, having a mildly saline and somewhat bitter taste, and a slightly alkaline reaction. The aqueous solution, on the addition of hydrochloric acid, deposits a crystalline precipitate,

which is soluble in chloroform, and which yields, with alcoholic solution of potassa, a scarlet-red liquid gradually becoming colourless.

DOSE.—8 to 10 grains.

USES.—This substance has been introduced into the U.S.P. as an anthelmintic. It is much more easily absorbed than santonin, and it will therefore have a much greater action on the system. This is exactly what is not wanted in the case of an anthelmintic, where the medicine is given to kill the worm in the intestine and not for its action on the organism.

U.S.P. Sodii Sulphis. SULPHITE OF SODIUM. $Na_2So_3.7H_2O$; 252.

CHARACTERS.—Colourless, transparent, monoclinic prisms, efflorescent in dry air, odourless, having a cooling saline and sulphurous taste, and a neutral or feebly alkaline reaction. Addition of diluted hydrochloric acid to the aqueous solution gives rise to the odour of burning sulphur, and the solution does not become cloudy (difference from hyposulphite).

DOSE.—1 drachm (3·9 Gm.).

USES.—A solution of 1 part in 8 of water is used in cases of aphthæ in the mouth; it has been given also to destroy sarcinæ and torulæ in cases of yeasty vomiting.

U.S.P. Sodii Bisulphis. BISULPHITE OF SODIUM. $NaHSO_3$; 104.

CHARACTERS.—Opaque, prismatic crystals, or a crystalline or granular powder, slowly oxidised, and losing sulphurous acid on exposure to air, having a faint sulphurous odour, a disagreeable sulphurous taste, and an acid reaction (distinguishing it from the sulphite). When strongly heated the salt decrepitates, and is converted into sulphur and sulphate of sodium.

On adding hydrochloric acid to an aqueous solution of the salt sulphurous vapours are evolved and the solution does not become cloudy (difference from hyposulphite).

DOSE.—15 to 60 grains.

USES.—The same as those of the sulphite.

U.S.P. Sodii Sulphocarbolas. SULPHOCARBOLATE OF SODIUM. $NaC_6H_5SO_4.2H_2O$; 232.

CHARACTERS.—Colourless transparent rhombic prisms, permanent in the air, odourless, or nearly so, having a cooling saline somewhat bitter taste, and a neutral reaction. The dilute aqueous solution of the salt is coloured violet by test-solution of ferric chloride.

DOSE.—10 to 15 grains.

USES.—Used in flatulence, in dyspepsia occurring in phthisical patients, and in septic conditions.

B.P. Sodæ Valerianas. VALERIANATE OF SODA. $NaC_5H_9O_2$.

CHARACTERS.—In dry white masses, without alkaline reaction, entirely soluble in rectified spirit, and giving out a powerful odour of valerian on the addition of diluted sulphuric acid.

PREPARATION.—By distilling amylic alcohol with a mixture of dilute sulphuric acid and an aqueous solution of bichromate of potash: $2K_2Cr_2O_7 + 8H_2SO_4 = 2(Cr_2 3SO_4) + 2K_2SO_4 + 8H_2O + 3O_2$; and $C_5H_{11}HO + O_2 = HC_5H_9O_2 + H_2O$. The valerianic acid thus obtained is saturated with a solution of soda and dried: $HC_5H_9O_2 + NaHO = NaC_5H_9O_2 + H_2O$.

DOSE.—½ to 5 grains.

PREPARATION IN WHICH VALERIANATE OF SODA IS USED.

Zinci Valerianas.

USE.—As an antispasmodic in hysteria. It is chiefly used for making the zinc salt.

LITHIUM. Li; 7.

SOURCES OF LITHIUM.—Native silicates and phosphates of lithium and other metals.

REACTION.—It is recognised by the *red* colour which it gives to flame. This appears to be more brilliant when the salt is first converted into chloride by addition of hydrochloric acid.

PREPARATION OF LITHIUM SALTS.

Lithium Salt	Is prepared from	By
Carbonate, B. and U.S.P.	Lithium chloride obtained from minerals	Precipitating with carbonate of ammonium.
Citrate, B. and U.S.P.	Lithium carbonate.	Dissolving in citric acid.
Benzoate, U.S.P.	Do.	Neutralising a hot solution with benzoic acid, filtering, and evaporating to dryness, or crystallising.
Salicylate, U.S.P	Do.	Neutralising hot solution with salicylic acid, filtering and evaporating.
Bromide, U.S.P.	Do.	Neutralising with sulphuric acid, and decomposing the sulphate thus obtained by bromide of potassium.

GENERAL IMPURITIES OF LITHIUM.—Alkalies, alkaline salts, and metals.

TESTS.—The alkalies are detected by igniting the lithium salt and converting the carbonates which remain (when the acid has

been an organic one, as citric or salicylic), into chloride by the addition of hydrochloric acid. On evaporating the filtered solution to dryness, 1 part of the residue should be completely soluble in 3 parts of alcohol, and should give no precipitate on the addition of an equal volume of stronger ether, U.S.P. (Alkaline salts, if present, would give a precipitate.) A solution in water of another portion of the residue should give no precipitate with a solution of oxalate of ammonia (absence of alkaline earths), and no precipitate or colour with hydrosulphuric acid or ammonium sulphide (absence of metals, U.S.P.).

GENERAL ACTION OF LITHIUM SALTS.—The action of lithium upon muscle, nerves, and nerve-centres is very much like that of potassium, but is more powerful.

Lithiæ Carbonas, B.P.; Lithii Carbonas, U.S.P. CARBONATE OF LITHIA, B.P., or LITHIUM, U.S.P. Li_2CO_3; 74.

CHARACTERS AND TESTS.—In white powder or in minute crystalline grains, alkaline in reaction, soluble in 100 parts of cold water, insoluble in alcohol. It dissolves with effervescence in hydrochloric acid; and the solution evaporated to dryness leaves a residue of chloride of lithium, which communicates a red colour to the flame of a spirit lamp, and redissolved in water yields a precipitate with phosphate of soda.

DOSE.—3 to 6 grains.

PREPARATION.

B.P.

Liquor Lithiæ Effervescens. LITHIA WATER (10 grains in 1 pint of water saturated with carbonic acid), given in quantities of 5 to 10 fluid ounces.

USES.—The urates of lithia being much more soluble than those of either potash or soda, lithia is often employed in preference to these other alkalies in gout. It is given internally in order to aid in the elimination of uric acid by the kidneys, to prevent the gouty paroxysm, and to lessen the acidity of the urine, to prevent the deposit of uric acid gravel or calculi in the kidneys or bladder, and also to aid in their solution when already formed. It is applied locally to parts affected with gouty inflammation, in order to aid in the solution and absorption of the urate of soda in the tissues. For this purpose it may be applied to stiff joints and chalk stones, whether covered by the skin or already laid bare by ulceration. A solution of lithia, five grains to the ounce, is kept constantly applied to the part for several weeks together.

Lithiæ Citras, B.P.; Lithii Citras, U.S.P. CITRATE OF LITHIA, B.P., OF LITHIUM, U.S.P. $Li_3C_6H_5O_7$.; 210.

CHARACTERS AND TESTS.—A white amorphous powder, deliquescent, and soluble in water without leaving any residue. Heated to redness it blackens, evolving inflammable gases; and

leaving a residue of lithium carbonate which gives the usual reactions.

DOSE.—5 to 30 grains.

USE.—It has a similar action to the carbonate, and may be used in its stead where we wish to avoid any local action upon the stomach itself.

U.S.P. Lithii Benzoas. BENZOATE OF LITHIUM. $LiC_7H_5O_2$; 128.

CHARACTERS.—A white powder, or small shining scales permanent in the air, odourless or having a faint benzoin-like odour; of a cooling sweetish taste, and a faintly acid reaction. When heated, the salt fuses; at a higher temperature it chars, emits inflammable vapours having a benzoin-like odour, and finally leaves a black residue of an alkaline reaction, and imparting a crimson colour to a non-luminous flame. On mixing the aqueous solution with a dilute solution of ferric sulphate, a flesh-coloured precipitate is produced.

USES.—It has been used as a remedy for gout and uric acid.

DOSE.—15-30 grains.

U.S.P. Lithii Bromidum. BROMIDE OF LITHIUM. LiBr; 86·8.

CHARACTERS.—A white granular salt very deliquescent, odourless, having a very sharp, somewhat bitter taste, and a neutral reaction. Very soluble in water and in alcohol.

DOSE.—15-30 grs.

ACTION.—The same as that of bromide of potassium. It is said by some to have a stronger hypnotic action than the other bromides, but by others to be less effective than the potash salt.

USES.—The same as those of potassium bromide. It may be preferable to the potassium salt in the irritability of gouty subjects.

U.S.P. Lithii Salicylas. SALICYLATE OF LITHIUM. $2LiC_7H_5O_3.H_2O$; 306.

CHARACTERS.—A white powder, deliquescent on exposure to air, odourless or nearly so, having a sweetish taste and a faintly acid reaction. Very soluble in water and in alcohol. When strongly heated the salt chars, emits inflammable vapours, and finally leaves a black residue having an alkaline reaction and imparting a crimson colour to a non-luminous flame. On supersaturating the dilute aqueous solution with hydrochloric acid a bulky white precipitate is obtained, which is soluble in boiling water, from which it crystallises on cooling; also soluble in ether; and producing an intense violet colour with ferric salts.

USES.—It is used as a remedy in gout and rheumatism, and is intended to unite the properties of salicylic acid and lithia. It is less irritant to the stomach than salicylic acid.

DOSE.—20-40 grs. (1·3-2·6 Grm.)

MONAD METALS.—GROUP. II.

AMMONIUM SALTS. AMMONIA. NH_3; 17.

Ammonium salts are well defined like those of potassium and sodium, but the base, instead of being a so-called element, is known to be a compound of nitrogen and hydrogen. They are formed by the direct union of ammonia, NH_3, with acids. Thus ammonia and hydrochloric acid unite directly to form ammonium chloride, $NH_3 + HCl = NH_4Cl$. In the case of other members of the metallic group this direct union with the components of the acid does not occur, the metal replacing hydrogen, *e.g.* $Zn + HCl = ZnCl + H$. This exception to the general rule may be avoided by regarding the compounds of ammonia with acids as not being formed by the direct union of ammonia with the acids, but by the replacement of hydrogen in a basylous radical ammonium NH_4.

In gaseous **ammonia** the nitrogen may be supposed to be **triad** with its three affinities saturated by hydrogen } thus 

In the radical **ammonium** the nitrogen is supposed to be **pentad,** four of its affinities being saturated by hydrogen, the other being free to unite with an atom of some other element } thus 

In ammonium chloride this free affinity is saturated by chlorine 

In liquor ammoniæ this free affinity is saturated by hydroxyl 

The atoms of hydrogen in ammonia or in ammonium can be replaced by organic radicals, and **compound ammonias** are formed. When the organic radical which replaces the hydrogen is of a positive nature, the compounds are termed **amines,** but if it is of a negative nature they are termed **amides.**

Ammonium, NH_4, does not exist in the free state, and whether the double molecule, N_2H_8, or $\begin{matrix} NH_4 \\ | \\ NH_4 \end{matrix}$, exists separately is uncertain.

It has been supposed to form an amalgam with mercury. When mercury, potassium, and sal-ammoniac are mixed, the mercury swells up enormously and forms a pasty amalgam. This may consist of ammonium and mercury, but it soon decomposes into mercury, ammonia, and hydrogen, so that some have supposed it

to be nothing more than mercury which has absorbed a certain quantity of gas, as the mercury in this condition yields to pressure in the same way as froth does in other liquids. At all events the salts of ammonium correspond very closely with those of potassium and sodium. In their general reactions they differ however in the fact that ammonia is volatile, whereas potassium and sodium are not.

SOURCES OF AMMONIUM SALTS.—Ammonia is formed chiefly by the union of the nitrogen and hydrogen contained in animal or vegetable tissues during the processes of decomposition or destructive distillation. The principal commercial source of ammonium salts is the ammoniacal liquor from gas-works, though some of it is also obtained by the dry distillation of bones in making animal charcoal.

GENERAL REACTIONS OF AMMONIUM SALTS.—Like potash and soda, ammonia is not precipitated by most reagents. It is recognised by its volatile alkaline character. It is given off from any of its salts on the addition of caustic potash or soda to them, and is then distinguished by its peculiar smell, and by its volatile alkaline character—turning a piece of red litmus-paper blue and turmeric paper brown, when they are held above the test-glass in which the ammonium salt has been mixed with potash or soda. It also forms white fumes of ammonium chloride when brought near to strong hydrochloric acid.

PREPARATION OF AMMONIUM SALTS.

Is prepared	From	By
Ammonium Chloride, B. and U.S.P.	Gas liquor.	Adding hydrochloric acid and subliming in iron pots covered with leaden domes; or by adding sulphuric acid, and subliming the ammonium sulphate with sodium chloride in the same way.
Ammonium Sulphate, U.S.P.	Do.	Adding sulphuric acid and subliming.
Liquor Ammoniæ fortior, B.P.; Aqua Ammoniæ fortior, U.S.P.	Ammonium chloride, or sulphate.	Heating with lime, and saturating a quantity of water with the gaseous ammonia (NH_3) given off:— $2NH_4Cl + CaHO = CaCl_2 + H_2O + 2NH_3$.
Liquor Ammoniæ, B.P.; Aqua Ammoniæ, U.S.P.	Do.	Is simply liquor ammoniæ fortior diluted with 2 parts of water.
Ammonium Carbonate, B. and U.S.P.	Do.	Subliming with calcium carbonate.

PREPARATION OF AMMONIUM SALTS—(*continued*).

Is prepared	From	By
Ammonium Valerianate, U.S.P.	Ammonium chloride, or sulphate.	Mixing with lime, and neutralising valerianic acid with the ammonia given off.
Ammonium Iodide, U.S.P.	Ammonium sulphate.	Decomposing by potassium iodide, precipitating potassium sulphate by alcohol, filtering, and evaporating.
Ammonium Bromide, B. and U.S.P.	Do.	Same process as for iodide, substituting bromide for iodide of potassium.
Liquor Ammoniæ Acetatis.	Ammonium carbonate	Neutralising with acetic acid.
Spiritus Ammoniæ Aromaticus, B. and U.S.P.	Ammonium carbonate and liquor ammoniæ.	Distilling with volatile oil of nutmeg, oil of lemon, rectified spirit and water, B.P. Oil of lemon, of lavender flowers and of pimenta are the flavouring agents, U.S.P.
Liquor Ammoniæ Citratis, B.P.	Liquor ammoniæ.	Neutralising with citric acid. It would be better prepared by neutralising ammonium carbonate with citric acid.
Ammonium Phosphate, B. & U.S.P.	Do.	Neutralising with phosphoric acid.
Ammonium Sulphide	Do.	Saturating with hydrogen sulphide.
Ammonium Nitrate, B. and U.S.P.	Liquor ammoniæ or carbonate.	Neutralising with dilute nitric acid evaporating and fusing.

GENERAL IMPURITIES OF AMMONIUM SALTS.—As all the salts are obtained from the chloride or sulphate, chlorides or sulphates may be present. Iron may be present, as the chloride is usually sublimed in an iron pot, and if the heat employed be too great, some ferric chloride sublimes along with the ammonium chloride and gives it a reddish colour. Some lead may also be present from the leaden domes into which the ammonium chloride is sublimed.

GENERAL TESTS.—Lead and iron are detected by hydrosulphuric acid, or ammonium sulphide, and iron also by ferrocyanide of potassium. As the gas liquor contains many empyreumatic substances, these may sublime, and they are tested for in carbonate of ammonia (U.S.P.) by solution of permanganate of potash. The colour of this ought not to alter after standing for five minutes.

GENERAL ACTIONS OF AMMONIUM SALTS.—These have already been described, as well as the modifications induced in them by different acid radicals (p. 528). The tetanus produced by ammonia

and ammonium chloride is due to their action on the **spinal cord,** and not on cerebral centres, for it persists, like that of strychnine, after section of the cord. The paralysing action of ammonium chloride on the **muscles** modifies the tetanus, in so far that after the first spasm, irritation applied to the skin does not cause tetanic convulsions, but only a single reflex twitch. This effect is usually ascribed to the paralysing action on the **motor nerves,** but it seems really to be due to an affection of the muscles, as well as to a disturbance of the relation between the muscle and motor nerve. When a muscle has been poisoned by some ammoniacal salt, a single stimulation applied to the nerve causes a strong contraction like that of an unpoisoned muscle, but a second stimulus has sometimes little or no action, and when the muscle is stimulated directly it



FIG. 130.—Tracing to show the paralysing action of ammonium sulphate on muscle. The first contraction of the poisoned muscle is nearly as great as that of the unpoisoned one, but it soon becomes exhausted, and the curve rapidly falls during the continuance of the stimulation, while that of the normal muscle rather rises.

soon becomes exhausted. Ammonia is a powerful muscular irritant causing contraction and subsequent rigor mortis when applied directly to voluntary muscle.

Ammonium salts are said to increase the secretion of the **mucous glands** of the **bronchi** and of the **intestine,** as well as that of the **sweat glands** and of the **kidneys.** Ammonia appears to be converted almost entirely into **urea** in the blood.

It increases the formation of glycogen in the **liver.**

Neither ammonia nor its carbonate nor its salts with organic acids diminish, but rather increase, the acidity of the urine, and in this ammonia differs from potash, soda, and lithia.

Ammonii Chloridum, B. and U.S.P. CHLORIDE OF AMMONIUM. NH_4Cl; 53·4.

CHARACTERS AND TESTS.—In colourless, inodorous, translucent, fibrous masses, tough, and difficult to powder; soluble in water and in rectified spirit. When heated it volatilises without decomposition, and leaves no residue. Its solution in water gives the reactions of ammonia and a chloride.

PREPARATION. U.S.P.

		DOSE.
Trochisci Ammonii Chloridi.	2 grains in each	1 every hour or two.

DOSE.—5 to 20 grains.

ACTION AND USES.—During the process of solution in water of NH_4Cl cold is produced, and so its solution has been used **locally** in headache, inflammation of the brain, mania, and apoplexy. A **small dose** of 5 to 7 grs. of ammonium chloride has no effect, but if taken frequently it causes discomfort and heat in the stomach, slight headache, diuresis, and an increased secretion of mucus from the intestine, although the stools are not more numerous.

Large doses given to animals cause often pain and excitement, then collapse (no diarrhœa), convulsions, and death. The stomach is congested, the mucous membrane swollen, and the epithelial cells easily separated.

The same symptoms are produced when ammonium chloride is applied to a wound, and the same post-mortem appearance is seen in the stomach.

It thus seems to have a special action on the **gastric mucous membrane.** It is used in Germany in cases which are usually supposed to be due to a catarrhal state of the stomach—viz., when there is loss of appetite, sickness, bad taste in the mouth, fulness in stomach, and flatulence, with a coated tongue, and along with these bronchial catarrh without fever is present. Ammonium carbonate is preferred when there is much cough or the person is weak.

It is also used alone in bronchial catarrh, when this has either come on without fever, or the feverish symptoms have passed off. It is supposed to have the power of increasing the secretion of mucus in the bronchi as well as in the intestine, and it is therefore not given when the expectoration is profuse, but only when it is scanty and difficult to bring up.

It has been employed as a lotion to remove ecchymoses, to prevent discoloration in bruises and sprains, and to allay itching in prurigo. It has been applied locally as a dressing in abscess of the mamma, and to remove glandular enlargements. As a gargle, it has been used to cause contraction of the enlarged flabby uvula, and to relieve the cough which the tickling of the pharynx by the uvula often causes. It has been given to relieve the vomiting and heartburn occurring in cancer of the stomach. It is said to have a powerful action on the **liver** (p. 567), and has been strongly recommended in chronic congestion and hepatic abscess, as well as in dropsy depending upon hepatic disease. For its alterative action it has been given in muscular rheumatism, rheumatic pains, and neuralgia. In neuralgia it should be given in half-drachm doses several times a day; but if the pain is not relieved after four or five doses have been given, it may be discontinued. It is also useful in neuralgic headaches.

Liquor Ammoniæ Fortior, B.P.; Aqua Ammoniæ Fortior, U.S.P. STRONG SOLUTION OF AMMONIA, B.P.; STRONGER WATER OF AMMONIA, U.S.P.

CHARACTERS AND TESTS.—A colourless liquid, with a characteristic and very pungent odour, and strong alkaline reaction. Specific gravity 0·891.

PREPARATIONS IN WHICH STRONG SOLUTION OF AMMONIA IS USED.

B.P.	U.S.P.
Ammoniæ Phosphas.	**Spiritus Ammoniæ.**
Linimentum Camphoræ compositum.	
Liquor Ammoniæ.	
,, ,, Citratis.	
Spiritus Ammoniæ Aromaticus.	
Tinctura Opii Ammoniata.	

ACTION AND USES.—When applied to the nose, the vapour of strong ammonia acts as a powerful irritant. It **stimulates** the nasal branches of the fifth nerve, and thus reflexly excites the vaso-motor centre and raises the blood-pressure. It thus tends to prevent or to remove conditions of shock and syncope. When applied for too long a time, or in too concentrated a form, it may produce inflammation of the mucous membrane and respiratory passages. Applied to the skin it quickly evaporates, and has but a slight **rubefacient** effect, but when its evaporation is prevented, it passes through the epidermis, and acts as a powerful **vesicant**. When swallowed in large quantities, and undiluted, it may produce gastro-enteritis, but on account of the vapour gaining access to the air passages and causing immediate suffocation, it may cause death in a few minutes. Along with the gastro-enteritis, there may be comatose symptoms due to the action of the drug itself on the **brain** after absorption, and in this it differs from poisoning by caustic potash or soda. It stimulates the **circulation** reflexly through the nerves of the stomach, and after its absorption stimulates both the **respiration** and circulation by its direct action upon the circulatory and respiratory nerve-centres.

USES.—**Inhalation** of its fumes is used to prevent drowsiness or fainting, or to recover persons from a faint, or from shock, or from the narcosis produced by opium, syncope, or the depression caused by vascular sedatives. It should not be applied for too long a time lest bronchitis be induced. It is sometimes employed in a milder form to cut short nasal catarrh, to lessen pain in the nose and forehead, and diminish the expectoration in chronic bronchitis. It is used as a **counter-irritant** to the skin in rheumatic pains, stiffened rheumatic joints, and bronchitis. As a **vesicant** it may be employed where the use of cantharides is objectionable. A pledget of lint, somewhat larger than the blister desired, is moistened with ammonia, covered with a watch-glass, and applied to the skin until a red ring forms round the glass. The pledget is then removed and a poultice applied. The poison of nettles and insects is frequently of an acid character, and ammonia rubbed over the part stung will lessen the pain and swelling. The injection of ten drops of strong liquor ammoniæ, diluted with three parts of water, into the veins, has been recommended in cases of

snake-bite. It may be useful, possibly, in bites of less poisonous snakes, but is of no utility in bites by the cobra or daboia. It may be given internally, diluted, as a stimulant in cases of syncope, and in the depression, weakness, and faintness to which some women are subject. In these cases the liquor ammoniæ may be employed as a **substitute for alcohol,** and thus the tendency to contract habits of drinking may be counteracted. It may be used, like other alkalies, to stimulate the secretion of gastric juice, and especially where we do not wish to diminish the acidity of the urine or render it alkaline, and also where we wish to stimulate the **nervous system,** as in cases of anæmia and debility, and more especially where the stomach is relaxed and distended with gas. It also stimulates the **intestines,** and aids the expulsion of gas from them. It is therefore very useful in the flatulence and colic of children. It may be employed to lessen the watery discharge from the bowels where this persists after the removal of the irritant which has caused it.

U.S.P. Spiritus Ammoniæ. SPIRIT OF AMMONIA.—An alcoholic solution of ammonia containing 10 per cent. by weight of the gas.

PREPARATION.—By warming strong water of ammonia so as to expel the ammoniacal gas, passing this into cold alcohol, and diluting with alcohol to the necessary strength.

Liquor Ammoniæ, B.P.; Aqua Ammoniæ, U.S.P. SOLUTION OF AMMONIA, B.P.; WATER OF AMMONIA, U.S.P.—Ammoniacal Gas, NH_3; 17; dissolved in water.

PREPARATION.—By mixing 1 part of strong solution of ammonia with 2 of water.

PREPARATIONS.

B.P.	U.S.P.
Linimentum Ammoniæ.	Spiritus Ammoniæ Aromaticus. Linimentum Ammoniæ.

DOSE.—10 to 30 minims well diluted.

Linimentum Ammoniæ. LINIMENT OF AMMONIA.—Solution of ammonia 1, olive oil 3, B.P. Water of ammonia 3, cotton-seed oil 7, U.S.P.

USES.—This may be used as a local application in a similar manner to the liquor ammoniæ fortior, except that it has not the same powerful vesicant action. It may be given internally for similar purposes. When mixed in the proportion of two ounces of liquor ammoniæ with two ounces of common salt and three drachms of camphorated spirit of wine to thirty-two ounces of water, it forms Raspail's sedative solution, for the treatment of headaches occurring at the menopause, or due to uterine derangement.

Ammoniæ Carbonas, B. and U.S.P. CARBONATE OF AMMONIA, B.P.; CARBONATE OF AMMONIUM, U.S.P. NH_4HCO_3 $NH_4NH_2CO_2$; 157.

A volatile and pungent ammoniacal salt, produced by submitting a mixture of sulphate of ammonia or chloride of ammonium and carbonate of lime to sublimation. It consists of a mixture of acid carbonate of ammonia (NH_4HCO_3), and carbamate of ammonia ($NH_4NH_2CO_2$).

CHARACTERS AND TESTS.—In translucent crystalline masses, with a strong ammoniacal odour, and alkaline reaction; soluble in cold water, more sparingly in spirit. It volatilises entirely when heated, and is readily dissolved by acids with effervescence.

20 grains of Carbonate of Ammonia } neutralise { 23½ grains Citric Acid / 25½ grains Tartaric Acid.

DOSE.—3 to 10 grains as stimulant and expectorant, 30 grains as emetic.

PREPARATIONS IN WHICH CARBONATE OF AMMONIA IS USED.

B.P.	U.S.P.
Liquor Ammoniæ Acetatis.	Spiritus Ammoniæ Aromaticus.
Spiritus Ammoniæ Aromaticus.	

USES.—Carbonate of ammonia may be used as an inhalation, and may be given internally, for similar purposes to liquor ammoniæ.

It is an emetic, and may be employed in cases of bronchitis, where the bronchial tubes are choked with mucus, and the patient's circulation is weak. In smaller doses it stimulates the secretion of gastric juice, and may be used in atonic dyspepsia, flatulence, and colic to relieve sinking and depression, and as a substitute for alcoholic stimulants. When employed for this latter purpose, five to ten grains may be given along with ten minims of tincture of capsicum in an ounce of bitter infusion, to be taken whenever the feeling of sinking comes on, or the craving for alcoholic stimulants is experienced.

From its power of stimulating the respiratory centre, it is employed as a stimulating expectorant in chronic bronchitis, in the broncho-pneumonia of children, and in asthma depending on cardiac disease. It is also given in measles, and has been recommended as almost a specific in scarlet fever, in doses of three to five grains, every one, two, or three hours, according to the severity of the case, no acid drinks or fruits being allowed to the patient at the time.

Carbonate of ammonia has been supposed to have the power of preventing iodism, when given along with iodide of potassium.

Spiritus Ammoniæ Aromaticus, B. and U.S.P. AROMATIC SPIRIT OF AMMONIA (SAL VOLATILE).—It consists of carbonate of ammonia, and strong solution of ammonia diluted with alcohol and water. It is flavoured with volatile oil of nutmeg and oil of lemon in the B.P., and with oil of lemon, oil of lavender flowers, and oil of pimenta, in the U.S.P.

DOSE.—20 to 60 minims in water.

PREPARATIONS.

Tinctura Guaiaci Ammoniata. B. and U.S.P.
" Valerianæ Ammoniata. " "

USES.—It is very commonly taken to relieve feelings of faintness and depression, and is much safer than alcohol, which might otherwise be employed. It may be used also for other purposes instead of carbonate of ammonia, to which it has a similar action.

Liquor Ammoniæ Acetatis, B. and U.S.P. SOLUTION OF ACETATE OF AMMONIA.—Acetate of Ammonia, or $NH_4C_2H_3O_2$, dissolved in water.

DOSE.—2 to 6 fluid drachms.

PREPARATION.—*Vide* p. 566.

USES.—It is used as an eyewash, and as a lotion to inflamed parts. When given internally it acts as a diaphoretic, if the body be kept warm, or as a diuretic if it be cool. As a diaphoretic it is given when the skin is hot and dry, and is very frequently used, especially combined with spirit of nitrous ether, whenever a feverish condition is present, whether its cause be known or not. It is especially used in the exanthemata, in influenza and catarrh.

B.P. Liquor Ammoniæ Citratis. SOLUTION OF CITRATE OF AMMONIA.—Citrate of Ammonia, or $3NH_4.C_6H_5O_7$, dissolved in water.

DOSE.—2 to 6 fluid drachms.

PREPARATION.—*Vide* p. 566.

USES.—Like the solution of the acetate, but more agreeable.

Ammoniæ Oxalas, $(NH_4)_2C_2O_4H_2O$.

PROPERTIES.—Colourless prismatic crystals, no smell; soluble in water.

USES.—Used to test for lime, and to separate it from magnesia.

Ammoniæ Phosphas, B.P.; Ammonii Phosphas, U.S.P. PHOSPHATE OF AMMONIA, B.P.; (OF AMMONIUM, U.S.P.) $(NH_4)_2HPO_4$; 132.

CHARACTERS AND TESTS.—In transparent colourless prisms. Soluble in water, insoluble in rectified spirit. The aqueous solution gives the reactions of ammonia, and of a phosphate.

DOSE.—5 to 20 grs. freely diluted.

USES.—It has been used as a remedy in cases of gout, in order to eliminate urate of soda from the system, the theory of its action being that it decomposes the insoluble urate of soda, converting it into soluble urate of ammonia and phosphate of soda.

Ammonii Bromidum, B. and U.S.P. BROMIDE OF AMMONIUM, NH_4Br; 97·8.

CHARACTERS AND TESTS.—In colourless crystals, which become slightly yellow by exposure to the air, and have a pungent saline taste. Its solution gives the reactions of ammonia and a bromide.

IMPURITY.—Iodide.

TEST.—*Vide* p. 520.

DOSE.—2 to 20 grains.

USES.—The bromide of ammonium has been employed for the same purposes as the bromide of potassium. It may be used in cases where the bromide of potassium appears to cause depression, either instead of the potassium salt, or mixed with it, and the mixture of bromide of potassium with bromide of ammonium has been supposed to have a better action than either salt alone.

U.S.P. Ammonii Iodidum. IODIDE OF AMMONIUM. NH_4I; 144·6.

CHARACTERS.—A white granular salt, or minute crystalline cubes, very deliquescent and soon becoming yellow or yellowish-brown on exposure to air; odourless when white, but emitting a slight odour of iodine when coloured, having a sharp saline taste and a neutral reaction.

USES.—A solution of ½ drm. in an ounce of glycerine has been used as an application to enlarged tonsils. An ointment containing 20 to 60 grs. of the iodide to 1 oz. lard has been used in cases of lepra and psoriasis. It is chiefly used internally for syphilis, scrofula, and glandular enlargements, either instead of or along with iodide of potassium. A mixture of the two iodides has been thought by some to be more efficacious than either used singly, and the iodide of ammonium prevents the depressing action often exerted by the iodide of potassium alone.

Ammoniæ Nitras, B.P.; Ammonii Nitras, U.S.P. NITRATE OF AMMONIA, B.P.; NITRATE OF AMMONIUM, U.S.P. NH_4NO_3; 80.

CHARACTERS.—Colourless crystals, generally in the form of long thin rhombic prisms, or in fused masses somewhat deliquescent, odourless, having a sharp bitter taste and a neutral reaction. When gradually heated, the salt melts at 165° to 168° C. (329° to 331° F.), and at about 185° C. (365° F.) it is decomposed into nitrous oxide gas and water, leaving no residue. The aqueous solution of the salt, when heated with potassa, evolves vapour of ammonia. On heating the salt with sulphuric acid, it emits nitrous vapours.

USE.—It is only used for the preparation of nitrous oxide.

U.S.P. Ammonii Sulphas. SULPHATE OF AMMONIUM. $(NH_4)_2SO_4$; 132.

CHARACTERS.—Colourless transparent rhombic prisms, permanent in the air, odourless, having a sharp saline taste, and a neutral reaction.

USES.—It is not used internally, but is only employed for the preparation of other salts of ammonium, of ammonia alum (B.P.) and sulphate of iron and ammonia (U.S.P.)

U.S.P. Ammonii Valerianas. VALERIANATE OF AMMONIUM. $NH_4C_5H_9O_2$; 119.

CHARACTERS.—Colourless or white quadrangular plates, deliquescent in moist air, having the odour of valerianic acid, a sharp and sweetish taste, and a neutral reaction. Very soluble in water and in alcohol. When heated the salt fuses, gives off vapour of ammonia and of valerianic acid, and is finally dissipated without leaving a residue.

USES.—It is chiefly used, like valerian, in cases of hysteria.

DOSE.—2 to 8 grs. (0·13 to 0·52 gm.)

U.S.P. Ammonii Benzoas. BENZOATE OF AMMONIUM, $NH_4C_7H_5O_2$; 139.

CHARACTERS.—Thin white four-sided laminar crystals, permanent in the air, having a slight odour of benzoic acid, a saline, bitter, afterwards slightly acrid taste, and a neutral reaction. When strongly heated the salt melts, emits vapours having the odour of ammonia and of benzoic acid, and is finally wholly dissipated.

USES.—It is used as a diuretic, and to render the urine acid where there is tendency to phosphatic deposits.

B.P. Sulphide of Ammonium. TEST SOLUTION.

PREPARATION.—Saturate a solution of NH_3 by H_2S.

PROPERTIES.—Greenish-yellow transparent liquid, disagreeable pungent odour. S.G. 0·999.

ACTIONS.—In small doses increases secretion, especially of bronchi and skin, so used as sudorific and expectorant in chronic skin diseases, rheumatism, and bronchitis; in large doses it causes giddiness, drowsiness, faintness, and nausea. Little given.

It is chiefly used as a test.

DOSE.—3 minims, cautiously increased.

CHAPTER XXV.

METALS—(*continued*).

Class II.—DYAD METALS.

GROUP I.—METALS OF THE ALKALINE EARTHS.

Calcium, *Strontium*, Barium.

APPENDIX.—METALS OF THE EARTHS.

Aluminium, (? triad) *Beryllium* (dyad), *Zirconium* (tetrad), *Niobium* (tetrad), Cerium, *Lanthanum*, *Didymium*, *Yttrum*, *Erbium* (triads).

GROUP II.—MAGNESIUM.

GROUP III.—COPPER, ZINC, SILVER, CADMIUM.

GROUP IV.—MERCURY.

This large class contains a number of metals which have widely different characters and reactions. Yet it will be seen from the following table that the successive addition of four reagents divides the metals tolerably nearly into those groups which agree in their physiological action. In some respects Groups I. and II. of Class 2 are perhaps more closely connected with the alkaline metals than with the heavy metals.

REACTIONS OF THE METALS IN CLASS II.

	Hydrochloric Acid.	Sulphuretted Hydrogen.	Ammonium Sulphide.	Ammonium Carbonate.	Ammonia and Sodium Phosphate.
GROUP I.					
Calcium	No precipitate.	No precipitate.	No precipitate.	White precipitate.	
Strontium	Do.	Do.	Do.	Do.	
Barium.....	Do.	Do.	Do.	Do.	
(APPENDIX.)					
Aluminium.....	Do.	Do.	White (hydrate).		
All other earthy metals	Do.	Do.	Do.		
GROUP II.					
Magnesium	Do.	Do.	No precipitate.	No precipitate.	White ppt. (phosphate).
Group III.					
Zinc	Do.	Do.	White (sulphide).		
Copper.....	Do.	Black ppt.			
Cadmium.....	Do.	Yellow ppt			
Silver	White curdy ppt. Soluble in ammonia.	Black ppt.			
Group IV.					
Mercury as subsalt	White ppt.	Black ppt.			
Do. as persalt...	No precipitate.	Black ppt.			

It must be borne in mind that the above reagents are used successively, and each remains in the solution. Thus when ammonium sulphide is added part of it is decomposed by the hydrochloric acid and ammonium chloride is formed. It is on account of the presence of the ammonium chloride in the liquid that magnesium is not precipitated by the ammonium sulphide while aluminium is.

CLASS II.—GROUP I.

GENERAL ACTION.—In regard to the action on the nervous system of the chlorides of calcium, strontium, barium, beryllium, didymium, erbium, and lanthanum, these substances fall into two groups—

(*a*) Containing beryllium, calcium, strontium, and barium;

(*b*) Containing yttrium, didymium, erbium, and lanthanum.

Group a has a tendency to **increase reflex** action, as evidenced by spasm or tremor in the frog.

With **group b** reflex action in the cord appears to be little affected, but its members appear to have a tendency to **paralyse** motor-centres of the **brain** in the frog.

Group *a* all paralyse **motor nerves** to some extent. Lanthanum has also a slight paralysing action, but the other members of group *b* have not, agreeing in this respect with sodium and rubidium, and differing from all the others.

In regard to their action on muscle these substances cannot be divided into sub-groups. Their action on muscle has been already described (p. 110).

The lethal activity, on frogs, of the chlorides of the alkalies and earths is not in proportion to their atomic weight. It is as follows, potassium being most powerful, and calcium least powerful :—potassium, beryllium, rubidium, barium, ammonium, cæsium, lithium, lanthanum, didymium, erbium, strontium, yttrium, sodium, calcium.

Barium causes contraction of the ventricle of the frog's heart in much the same way as veratrine, and by its local action on the walls of the vessels causes them to contract. When injected into the circulation it causes enormous rise of blood-pressure at first, followed by stoppage of the heart and consequent fall of pressure. It causes contraction also of the involuntary fibres of the bladder and intestine, so that the lumen of the latter may be almost completely obliterated. The symptoms of poisoning in mammals are probably due to its action on the involuntary muscles of the intestines, heart, and vessels, on the voluntary muscles, and on the nervous system. They are vomiting, colic, diarrhœa, muscular weakness and cramp, ringing in the ears, tightness over the heart, and general convulsions. Injection of sulphate of soda into the veins appears to counteract the effect of barium,[1] and the simultaneous injection of potash salts will prevent death from an otherwise lethal dose of barium.[2] The action of barium on muscles and on the heart is abolished by heat in the same way as that of veratrine (p. 106), and the inhabitants of southern climates tolerate much larger doses of barium than those of northern.[3]

Metals of the Alkaline Earths.

Calcium, *Strontium*, Barium.

The only one of these whose preparations are used internally is calcium. At present barium is only used as a test, though possibly it may yet prove useful in muscular tremor.

CALCIUM. Ca; 40, or 39·9.

Sources of Lime Salts.—The chief source is the carbonate, found native as chalk or limestone.

General Test of Lime Salts.—Calcium oxalate is very insoluble, and forms a white precipitate on the addition of oxalate of ammonia to lime salts. It is soluble in hydrochloric but insoluble in acetic acid.

[1] Hermann, *Lehrbuch d. experimental Toxicologie*, p. 191.
[2] Brunton and Cash, *Centralblatt d. med. Wissenschaften*, 1884, p. 545.
[3] Lisfranc, quoted by Lewin, *Nebenwirkungen d. Arzneimittel*, p. 74.

GENERAL PREPARATION OF SALTS OF CALCIUM.

Is prepared	From	By
Creta præparata.	Chalk.	The process of elutriation, which consists in stirring with water, pouring off the liquid containing fine particles in suspension, and allowing them to subside.
Quicklime (calx).	Chalk or limestone.	Calcining; $CaCO_3 = CaO + CO_2$.
Slaked lime (calcis hydras).	Quicklime.	Slaking with water.
Calcium chloride.	Limestone or chalk (carbonate.)	Neutralising with hydrochloric acid; $CaCO_3 + 2HCl = CaCl_2 + H_2O + CO_2$.
Precipitated carbonate.	Calcium chloride.	Precipitating with excess of carbonate of soda; $CaCl + Na_2CO_3 = CaCO_3 + 2NaCl$.
Chlorinated lime (calx chlorata).	Slaked lime.	Exposing lime to chlorine gas until saturated: thus is formed chlorinated lime, consisting of a mixture of calcium chloride and calcium hypochlorite.
Calcium hypophosphite.	Lime and phosphorus	Heating together with water; removing excess of lime by CO_2; and evaporating.
Calcium phosphate.	Bone ash.	Dissolving in diluted hydrochloric acid, precipitating with ammonia, and drying.

GENERAL IMPURITIES.—The chief impurities are alumina and magnesia.

TESTS.—These are usually detected by converting the lime salt into chloride by hydrochloric acid, and evaporating to dryness so as to drive off all excess of acid. The residue is re-dissolved in water and the tests applied to the solution. On the addition of saccharated solution of lime, alumina and magnesia will be precipitated. The B.P. states that only a very scanty precipitate should occur, showing that only traces of magnesia and alumina are present. The test used in the U.S.P. to detect alumina is water of ammonia; and to detect magnesia, water of ammonia and phosphate of sodium. These reagents should not give more than a faint turbidity with dilute solutions of lime salts.

B.P. Marmor Album. WHITE MARBLE. $CaCO_3$.

Hard white crystalline native carbonate of lime, in masses. Used in producing carbonic acid gas.

Calx, B. and U.S.P. LIME. CaO ; 56.

An alkaline earth, CaO, with some impurities, obtained by calcining chalk or limestone so as to expel carbonic acid.

CHARACTERS AND TESTS.—In compact masses of a whitish colour, which readily absorb water, and which, when rather less than their weight of water is added, crack and fall into powder with the development of much heat. The powder obtained by this process of slaking, when agitated with distilled water, gives, after filtration, a clear solution which has an alkaline reaction, and is shown by the appropriate tests to contain lime and only traces of alumina and magnesia.

PREPARATIONS.

B.P.	U.S.P.
Calcis hydras.	Liquor Calcis.
	Potassa cum Calce (p. 34).
	Syrupus Calcis.

B.P. Calcis Hydras. SLAKED LIME.

Hydrate of lime, CaH_2O_2 ; 78 ; with some impurities, recently prepared by pouring 1 pint of water over 2 lbs. of lime in a metal pot.

CHARACTERS.—It dissolves in water, but only sparingly, 11 grs. being dissolved by a pint of water at 60° F. ; and, contrary to the usual course of things, its solubility is increased by cooling the water and diminished by heating it.

Its solubility is greatly increased by the addition of sugar, as in the Liquor Calcis Saccharatus B.P., or Syrupus Calcis U.S.P.

PREPARATIONS.

Liquor Calcis. Liquor Calcis Saccharatus.

Liquor Calcis Saccharatus, B P. ; Syrupus Calcis, U.S.P. SACCHARATED SOLUTION OF LIME, B.P. ; SYRUP OF LIME, U.S.P.

PREPARATION.—B.P. Like lime-water, mixing 1 ounce of lime with 2 of sugar and using them instead of 2 of lime. This contains 7·11 grains of lime in 1 fluid ounce. U.S.P. Mixing lime (5) and sugar (30) with boiling water (50) ; diluting with an equal volume of water, filtering, and evaporating to 100 parts.

DOSE.—15 to 60 minims.

Liquor Calcis, B. and U.S.P. SOLUTION OF LIME. LIME WATER.

PREPARATION.—B.P. By shaking 2 ounces of slaked lime with 1 gallon of distilled water in a stoppered bottle well for two or three minutes. After 12 hours the excess of lime will have subsided, and the clear solution may be drawn off with a siphon as it is required for use, or transferred to a green glass bottle furnished with a well-ground stopper. In the U.S.P. the lime is first washed with ordinary water and afterwards stirred well with distilled water.

It is a saturated solution, and contains a little over half a grain to an ounce.

DOSE.—1-4 fl. oz.

PREPARATIONS.

B.P.	U.S.P.
Linimentum Calcis.	**Linimentum Calcis.**
Argenti Oxidum.	
Lotio Hydrargyri Flava.	
,, ,, Nigra.	

Linimentum Calcis, B. and U.S.P. LINIMENT OF LIME.
PREPARATION.—By mixing equal parts of lime-water and olive oil B.P., or cotton-seed oil U.S.P.

USES.—When applied to the surface either of the skin or of a mucous membrane from which a watery discharge is issuing, lime seems to act as a slight **astringent,** possibly because it combines with the albumen.

Lime-water is therefore sometimes used as a lotion for cracked nipples and as a dressing to eczematous surfaces, where it eases the smarting and tingling. It is often mixed with oil or glycerine for this purpose. It is also used as an injection to lessen discharges from the ears, urethra, vagina or vulva, in otorrhœa, gleet, and leucorrhœa, while active inflammation is still present, and as an enema to destroy ascarides in the rectum. It may also be used as a wash to the mouth in ulceration. In croup it has been recommended as a solvent for the false membrane. It is either applied as spray or by a camel's hair pencil. When taken into the stomach it will act as an **antacid.** It is especially useful in preventing vomiting, and a mixture of milk and lime-water will often be retained by the stomach and digested when no other food can be borne. In children suffering from chronic vomiting and diarrhœa, where the milk is vomited in hard lumps instead of small flakes, lime-water proves very useful.

In typhoid fever it tends to prevent milk from forming hard undigested lumps which may irritate the intestine, while it has at the same time an astringent action.

It is very useful as an **astringent** in diarrhœa, more especially in slight cases of diarrhœa in children. When the child is at the breast about one teaspoonful of lime-water mixed with an equal quantity of milk should be given to it every three hours, and when it is brought up by hand the lime-water is just mixed with the milk which the child ordinarily takes. It has been used in diarrhœa in adults depending on ulceration of the intestine, with the view of healing the ulcers by forming a coating over them by combining with the albumen on their surface, but it is not so efficient as other remedies for this purpose.

There is not much absorbed by the intestine, and so but little passes into the blood; yet a small quantity does so; and, after it has been used for a little, the urine becomes alkaline from the lime being excreted by the kidneys. Lime-water has been used in cases of stone, and with considerable benefit. It has been supposed to dissolve stones in the bladder; but the good effects which result from its use are probably not due to this cause, which is still problematical. They are most probably produced by the lime lessening the irritating qualities of the urine, and at the same time acting as an astringent on the walls of the bladder and rendering it less irritable.

Linimentum Calcis, better known, perhaps, under the name

of Carron oil, is used as an application to burns and scalds. It derives its name of Carron oil from its being so extensively used by the workmen in the foundries at Carron.

It was formerly made with linseed oil, and this preparation is less fluid, and is often preferable to that made with olive or cotton-seed oil. It is useful not only in burns and scalds, but as a dressing to the face in small-pox, and in some cases of eczema affecting a large extent of skin.

Liquor Calcis Saccharatus, B.P. or Syrupus Calcis, U.S.P. may be given in milk instead of liquor calcis, when it is desired simply to get the effect of the lime and it is unadvisable to dilute the milk, as admixture with liquor calcis would necessarily do. It has been used also in acute rheumatism.

Creta Præparata, B. and U.S.P. PREPARED CHALK.

PREPARATION.—Prepared chalk is simply chalk freed from sand and other impurities by elutriation (p. 578).

PROPERTIES.—It is a white powder, or small lumps which break into powder readily on pressure. It has no taste or smell. It is insoluble in water, but it dissolves in acids such as acetic acid. While doing so it effervesces strongly, showing that it is a carbonate, and the solution gives the reactions of lime.

IMPURITIES.—Silica, barium, strontium, magnesium, iron.

TEST.—It should dissolve without leaving any residue in hydrochloric acid (absence of silica), B.P. The solution in acetic acid should give no precipitate with test solution of sulphate of calcium (absence of strontium and barium), and the tests for magnesium and iron should not indicate more than traces of these substances, U.S.P.

OFFICINAL PREPARATIONS.

B.P.	DOSE.
Mistura Cretæ. Chalk mixture. Chalk (1) suspended in cinnamon water (30) by means of gum (1) and sweetened with syrup (2)	1-2 fl. oz.
Pulvis Cretæ Aromaticus. Aromatic powder of chalk. Cinnamon (8), cardamoms (2), cloves (3), nutmeg (6), saffron (6), sugar (50), chalk (22)	10-60 grs.
Pulvis Cretæ Aromaticus cum Opio. Aromatic powder of chalk thoroughly mixed with powdered opium. 1 part of opium in 40.	10-40 grs.
U.S.P.	
Mistura Cretæ. Chalk mixture. Compound chalk powder (20), cinnamon water (40), water (40)	½-2 fl. oz.
Pulvis Cretæ Compositus. Compound chalk powder. Prepared chalk (30), powdered acacia (20), sugar, (50)	8-60 gr. (½-4 gm.)
Trochisci Cretæ. Chalk lozenges. 4 grains in each. Chalk is also contained in Hydrargyrum cum Creta, B. and U.S.P.	*Ad lib.*

ACTION.—Carbonate of lime or chalk possesses the astringent powers of lime itself, and is without its irritating qualities. It can therefore be given in much larger doses, and so chalk is used, instead of liquor calcis, in the diarrhœa of adults accompanied by acidity.

USES.—Chalk may be used as a dusting powder to the skin in excoriations, burns, and ulcers. It forms a useful tooth-powder. Internally it serves to arrest diarrhœa, and is often given, whatever be the cause of the diarrhœa; but when the disease depends upon some irritating substance in the intestine, the irritant should be removed by a dose of castor oil previous to the administration of the chalk. In the form of whiting, chalk forms a useful antidote in cases of poisoning by acids, and especially by oxalic acid.

Calcii Chloridum, B. and U.S.P. CHLORIDE OF CALCIUM. $CaCl_2$; 110·8.

CHARACTERS.—Colourless, slightly translucent, hard and friable masses, very deliquescent, odourless, having a hot, sharp, saline taste, and a neutral or faintly alkaline reaction. Soluble in 1·5 parts of water, and in 8 parts of alcohol at 15° C. (59° F.). The aqueous solution yields the reactions of calcium and of a chloride.

USES.—It is occasionally used in cases of chronic glandular enlargement, but is not much used in medicine. It has a great affinity for water, and is used to remove water from other substances in pharmacy, *e.g.* in the preparation of absolute alcohol or ether.

OFFICINAL PREPARATION.

B.P.

Solution of Chloride of Calcium consists of 1 ounce of CaCl dissolved in 10 of water. It is used as a test for tartrates, citrates, and oxalates. Saturated solution of chloride of calcium is used for determining the percentage of nitrous ether in spirit of nitrous ether.

Calcis Carbonas Precipitata, B.P.; Calcii Carbonas Præcipitatus, U.S.P. PRECIPITATED CARBONATE OF LIME, B.P.; PRECIPITATED CARBONATE OF CALCIUM, U.S.P. $CaCO_3$; 100.

CHARACTERS.—A very fine white impalpable powder, permanent in the air, odourless and tasteless, and insoluble in water or alcohol. Wholly soluble in hydrochloric, nitric, or acetic acid, with copious effervescence.

A neutral solution of the salt in acetic acid yields the reactions of calcium.

USE.—It may be used as an astringent in the same way as chalk.

U.S.P. Calcii Bromidum. BROMIDE OF CALCIUM. $CaBr_2$; 199·6.

CHARACTERS.—A white granular salt, very deliquescent, odourless, having a pungent saline and bitter taste, and a neutral reaction. An aqueous solution of the salt yields the reactions of calcium and a bromide.

DOSE.—15 to 30 grains (1 to 2 Gm.).

USES.—The same as those of potassium bromide. It is said not to depress like the potassium bromide.

Calcis Phosphas, B.P.; Calcii Phosphas Præcipitatus, U.S.P. PHOSPHATE OF LIME, B.P.; PRECIPITATED PHOSPHATE OF CALCIUM, U.S.P. $Ca_3(PO_4)_2$; 310.

CHARACTERS.—A light, white, amorphous powder, permanent in the air, odourless, tasteless, and insoluble in water or alcohol. Wholly soluble in nitric or hydrochloric acid without effervescence (absence of carbonate). A solution of the salt in diluted nitric acid, after being mixed with an excess of acetate of sodium, yields a white precipitate with test solution of oxalate of ammonium (lime), and a lemon-yellow precipitate with test solution of ammonio-nitrate of silver (phosphate).

OFFICINAL PREPARATIONS.

B.P.	U.S.P.	DOSE.
It is contained in Pulvis Antimonialis.	Syrupus Calcii Lactophosphatis.	1-4 fl. dr. (7·5-15 cc.)

U.S.P. Syrupus Calcii Lactophosphatis. SYRUP OF LACTOPHOSPHATE OF LIME. Made by dissolving freshly precipitated phosphate in lactic acid, and mixing with orange-flower water and sugar (22 parts phosphate in 1,000).

ACTION.—Phosphate of lime is an important constituent of the body, and occurs in considerable quantity wherever active cell-growth, either normal or pathological, is going on. It forms a large proportion of bones, and Chossat found that when animals were fed on food containing no lime salts, the bones were soft. During pregnancy, fractures unite slowly, and Milne Edwards found that when animals were supplied with abundance of phosphate of lime fractures united more quickly.

It has been supposed that the constant use of fine flour tends to cause premature decay of the teeth, owing to the want of sufficient proportion of lime salts. The decay of the teeth amongst Americans has been attributed to the perfection of their machinery, which completely separates the external parts of the grain and makes the flour exceedingly fine and white.

USES.—It frequently lessens or removes toothache. It is useful in cases of chronic diarrhœa in children. It has been recommended in cases of rapid growth or deficient repair, as in growing children, anæmia, and debility from over-work, child-bearing, suckling, or diseases such as chronic abscess, diarrhœa, leucorrhœa, bronchitis, and phthisis. It is frequently given in rickets with considerable benefit, although here it is well to combine it with cod-liver oil. It is often advantageously given, along with iron, in the form of Parrish's Chemical Food, containing two and a-half grains of phosphate of lime and one grain of phosphate of iron in every drachm.

Calcis Hypophosphis, B.P.; Calcii Hypophosphis, U.S.P. HYPOPHOSPHITE OF LIME, B.P.; OF CALCIUM, U.S.P. $CaH_4(PO_2)_2$; 170.

CHARACTERS.—Colourless or white six-sided prisms, or thin flexible scales, of a pearly lustre; permanent in dry air, odourless,

having a nauseous, bitter taste and a neutral reaction. The aqueous solution yields the reactions of calcium.

DOSE.—1 to 5 grs.

OFFICINAL PREPARATION.

B.P.	U.S.P.	DOSE.
None.	Syrupus Hypophosphitum.....1-2 fl. dr. (3·75 to 7·5 c.c.	

U.S.P. Syrupus Hypophosphitum. SYRUP OF HYPOPHOSPHITES. Consists of the hypophosphites of lime (35), of sodium (12), and of potassium (12); citric acid (1), spirit of lemon (2), sugar (500), water q.s. to make 1,000.

USES.—Hypophosphite of lime is useful in the early stages of phthisis and in nervous debility consequent upon over-work or worry. It may be given between two thin slices of bread and butter, if no irritability of the stomach be present. It is well to begin with a dose of two grains and gradually increase it, as otherwise it is apt to cause derangement of the digestion.

Calx Chlorata, B. and U.S.P. CHLORINATED LIME; *vide* CHLORINE (p. 486).

U.S.P. Calx Sulphurata. SULPHURATED LIME. A mixture (commonly misnamed sulphide of calcium) consisting chiefly of sulphide of calcium [CaS; 72] and sulphate of calcium [$CaSO_4$; 136], in varying proportions, but containing not less than 36 per cent. of absolute sulphide of calcium.

PREPARATION.—Mix lime in very fine powder (100), and precipitated sulphur (90), intimately; pack the mixture with gentle pressure in a crucible so as nearly to fill it, and having luted down the cover, expose the crucible for one hour to a low red heat, by means of a charcoal fire so arranged that the upper part of the crucible shall be heated first. Then remove the crucible, allow it to cool, rub its contents to powder, and at once transfer the latter to small glass-stoppered vials.

CHARACTERS.—A greyish-white or yellowish-white powder, gradually altered by exposure to air, exhaling a faint odour of hydrosulphuric acid, having an offensive, alkaline taste and an alkaline reaction. Very slightly soluble in water, and insoluble in alcohol. On dissolving sulphurated lime with the aid of acetic acid, hydrosulphuric acid is abundantly given off, and a white precipitate (sulphate of calcium) is thrown down. The filtrate yields, with test solution of oxalate of ammonium, a white precipitate soluble in hydrochloric, but insoluble in acetic acid.

If 1 Gm. of sulphurated lime be gradually added to a boiling solution of 1·25 Gm. of sulphate of copper in 50 c.c. of water, the mixture digested on a water-bath for fifteen minutes, and filtered when cold, no colour should be imparted to the filtrate by 1 drop of test solution of ferrocyanide of potassium (presence of at least 36 per cent. of real sulphide of calcium).

DOSE.—$\frac{1}{10}$-$\frac{1}{2}$ gr.

ACTION.—In large doses it is an irritant to the stomach, but medicinal doses usually cause no trouble, or at most slight discomfort, sometimes giving rise to eructations of sulphuretted hydrogen, and perhaps to some looseness of the bowels.

USE.—It is used chiefly for its effect on the process of suppuration, hastening the discharge of pus if already formed, and checking its formation if the inflammation be still in its early stage.

Class II.

GROUP I.—APPENDIX.

ALUMINIUM. CERIUM.

ALUMINIUM. Al; 27·5.

GENERAL SOURCES OF ALUM SALTS.—Aluminium is very widely distributed in nature clays being silicates of alumina. Two kinds of clay **Kaolin** and **fuller's earth** being inert powders are used as demulcents (pp. 304 and 392) and Kaolin as a pill basis.

GENERAL PREPARATION.—It is prepared on a large scale from a kind of clay-slate called alum-schist. This contains a quantity of ferric sulphide. It is first roasted and moistened and exposed to air. The sulphur is thus converted into sulphuric acid, and ferrous sulphate and aluminium sulphate are formed. These are separated by lixiviation with water and ammonium chloride is added. This forms ammonium sulphate, which combines with aluminium sulphate to form alum; ferrous chloride remaining in solution.

GENERAL REACTIONS OF ALUM SALTS.—Salts of aluminium give a white gelatinous precipitate of hydrate with caustic potash or soda, soluble in excess; with ammonia a similar precipitate, insoluble in excess. The insolubility of the precipitate with ammonia in excess of the reagent readily distinguishes aluminium from zinc, which also gives a white precipitate with ammonium sulphide. Carbonates of potash, soda, and ammonia also precipitate the hydrate, which is insoluble in excess; ammonium sulphide also gives a white precipitate of hydrate.

GENERAL IMPURITIES OF ALUMINIUM SALTS.—The chief is sulphate of iron coming from the schist.

GENERAL TESTS.—Alum should give no blue with either ferro- or ferricyanide of potassium.

Alumen, B. and U.S.P. ALUM.—A sulphate of ammonia and alumina, $NH_4Al(SO_4)_2.12H_2O$, crystallised from solution in water, B.P.; a sulphate of aluminium and potassium, U.S.P. $K_2Al_2(SO_4)_4 24H_2O$; 948.

CHARACTERS AND TESTS. B.P.—In colourless transparent crystalline masses, exhibiting the faces of the regular octahedron, and having an acid sweetish astringent taste. Its aqueous solution gives with caustic potash or soda a white precipitate soluble in an

excess of the reagent (alumina), and the admixture evolves ammonia, especially when heated. The aqueous solution gives an immediate precipitate with chloride of barium (sulphate). U.S.P. Large colourless octahedral crystals, acquiring a whitish coating on exposure to air, no smell, sweet astringent taste, and acid reaction. It is distinguished from the ammonia alum of the B.P. by no ammonia being evolved on the addition of potash.

IMPURITY.—Iron.

TEST.—The solution in water does not acquire a blue colour from the addition of yellow or red prussiate of potash.

DOSE.—10 to 20 grains.

PREPARATION.
B. AND U.S.P.
Alumen exsiccatum.

Alumen Exsiccatum, B. and U.S.P. DRIED ALUM. NH_4AlSO_4, B.P.; $K_2SO_4Al_2(8O_4)$ 516, U.S.P.

PREPARATION.—Water of crystallisation is driven off by heat.

PROPERTIES.—Dry white powder with the taste and other properties of alum.

ACTION.—Alum precipitates **albumen** and **gelatin.** It has no action on the unbroken **skin,** but when applied to parts from which the epidermis has been removed, it causes a film of coagulated albumen to form on the surface, and produces contraction on the tissues and vessels below. It thus lessens the supply of blood to the part, relieves congestion, diminishes the swelling, lessens the discharge from inflamed surfaces, and therefore acts as an **astringent.** By causing contraction of vessels and aiding the formation of coagula it arrests hæmorrhage, and is therefore used either as a strong solution, or, if this prove insufficient, in the form of powder as a **styptic.** Dried alum abstracts water from the tissues and acts as a slight **caustic.** When swallowed in large quantities alum produces gastro-enteritis. In smaller doses it acts as an **emetic.** It is not so powerful as a caustic, astringent, styptic, or emetic as the salts of zinc or copper.

USES.—Dried alum is sometimes used to check exuberant granulations in ulcers. Bleeding from the nose may be stopped by sniffing up or injecting a solution of alum into the nostrils, and if the solution be ineffectual, powdered alum may be blown up by means of a paper funnel. As an astringent alum is used in both purulent and simple ophthalmia, but on account of its solvent action on the cornea it may lead to perforation, and should therefore be avoided (p. 184). It is used as a lotion in otorrhœa; as a wash to the mouth in ptyalism, aphthæ and ulceration of the mouth and gums; as a gargle for sore-throat, and congestion of the pharynx, elongation of the uvula, as well as for the tickling, violent coughs which depend upon them, and are often accompanied by retching (p. 213). Dried alum has been applied in powder to remove the false membrane from the throat in croup and diphtheria.

Alum may be employed as a spray to the larynx in coughs and hoarseness depending upon chronic laryngeal catarrh. As a wash it may be used in inflammation of the vulva in children, to relieve itching in pruritus vulvæ, and to prevent the recurrence of prolapsus ani. It is useful as an injection in gonorrhœa and leucorrhœa. When swallowed it will act on the stomach as an astringent, and is useful in preventing the vomiting of phthisis. It is not improbable that the vomiting which occurs usually after paroxysms of coughing is due to the congestion produced in the stomach by the cough, and that the alum prevents the vomiting by lessening this congestion (p. 328). When given in larger quantities alum is an emetic, acting promptly, and producing little depression. A teaspoonful of powdered alum proves a very useful emetic in cases of croup, and may be given to children mixed with honey. In the intestine alum acts as an astringent also, and is useful in diarrhœa; but, curiously enough, in lead colic it will act as a purgative, relieving the pain and opening the bowels. Its utility in lead-poisoning probably depends, to a considerable extent, on its being a sulphate, and thus precipitating any lead salts it may meet in the intestine in the form of insoluble lead sulphate, and preventing absorption from the intestinal canal. In typhoid fever, and in chronic dysentery and diarrhœa, it is said to be useful in checking the discharges from the bowels.

After its absorption into the blood it is supposed to exercise an astringent action, and is given to check sweating.

As a styptic, it is employed locally in bleeding from the nose, mouth, throat, gums, hæmorrhoids, and uterus. Internally, to check bleeding from the stomach, intestines, lungs, uterus, or kidneys.

DOSE.—As an astringent 10 to 40 grs.; as an emetic, 30 to 60 grs. For a lotion or gargle, 4 to 20 grains to an ounce of water.

ANTIDOTE.—Give tepid water with small doses of carbonate of soda to decompose the alum, and empty the stomach by the stomach-pump or emetics.

U.S.P. Aluminii Hydras. HYDRATE OF ALUMINIUM. $Al_2(HO)_6$; 156.

CHARACTERS.—A white, light, amorphous powder, permanent in dry air, odourless and tasteless, and insoluble in water or alcohol. Soluble without residue in hydrochloric, or in sulphuric acid, also in solution of potassa or of soda.

USES.—It is feebly astringent and desiccant. Is used externally as a powder in inflammatory diseases of the skin.

U.S.P. Aluminii Sulphas. SULPHATE OF ALUMINIUM. $Al_2(SO_4)_3$-$18H_2O$; 666.

CHARACTERS.—A white, crystalline, powder, permanent in the air, odourless, has a sweet, and afterwards an astringent taste, and an acid reaction. Soluble, without leaving more than a trifling residue, in 1·2 parts of water at 15° C. (59° F.), and very soluble in

boiling water; almost insoluble in alcohol. The aqueous solution of the salt yields the reactions of aluminium and of a sulphate.

USES.—It is a powerful antiseptic. A saturated solution has been used as a mild caustic in enlarged tonsils, nasal polypi, nævi, scrofulous and cancerous ulcers, diseases of the os uteri, and various chronic enlargements. Weaker solutions are used as lotions to ulcers, and as injections in fœtid discharges from the vagina. A solution of the sulphate dissolves recently precipitated gelatinous alumina, and thus a benzoated solution of alumina can be prepared by saturating with gelatinous alumina 8 oz. of the sulphate in 1 pint of water, adding 6 drms. of powdered benzoin, keeping it at a temperature of 150° F. for six hours, and putting in a cool place for several days to deposit crystals. This solution is remarkable for its sweet odour and astringent balsamic taste. In the proportion of 2 to 5 fl. drms. to the pint of water it is useful as an injection in leucorrhœa, and in ulcerations of the neck of the uterus accompanied by fœtid discharges.[1]

CERIUM. Ce; 92.

It is a rare metal.

Its salts are supposed to resemble those of bismuth and silver in their action.

Cerii Oxalas. OXALATE OF CERIUM, B. and U.S.P. $CeC_2O_4.3H_2O$. B.P.; $Ce(C_2O_4)_3 9H_2O$; 708; U.S.P.

PREPARATION.—Is prepared by precipitating a soluble salt of cerium with oxalate of ammonia.

CHARACTERS.—It is a white granular powder, insoluble in water. At a red heat it is decomposed into a reddish-brown powder, which dissolves completely in boiling hydrochloric acid without effervescence (oxide).

The resulting solution gives a white crystalline precipitate of double sulphate of potassium and cerium when a saturated solution of sulphate of potash is added to it.

IMPURITIES.—Alumina, carbonates, and metals.

TEST.—When the salt is boiled with caustic potash and filtered the filtrate is not affected by chloride of ammonia, showing that no alumina is present: but when supersaturated with acetic acid it gives with calcium chloride a white precipitate of oxalate of lime. The absence of carbonates and metals is ascertained by the usual tests.

DOSE.—1 to 10 grains. Large doses may succeed when small ones fail.

USES.—It was introduced by the late Sir James Simpson as a remedy to check the vomiting of pregnancy, and for this purpose is sometimes useful. It has also been employed in cases of chronic bronchitis and dyspnœa, and has been used also in nervous cough and nervous palpitation. It has been given, but with doubtful utility, in chorea and epilepsy.

[1] *United States Dispensatory*, 15th ed. p. 167.

Class II.

Group II.—Magnesium.

MAGNESIUM. Mg; 24.

Sources.—The chief source is dolomite, or mountain limestone, which consists of carbonates of magnesium and calcium. Magnesium is also found native as carbonate and silicate.

General Reactions of Magnesium Salts.—They give a gelatinous white precipitate with potash, soda, or ammonia, insoluble in excess, but soluble in a solution of ammonium chloride. They likewise give a white precipitate with potassium and sodium carbonates, but none with ammonium carbonate.

The characteristic test of magnesium is the formation of a precipitate of triple phosphate on the addition of ammonia and a soluble phosphate to a solution of a magnesium salt. Caustic ammonia itself throws down a precipitate of magnesium hydrate insoluble in excess, but soluble in ammonium chloride. As it is easier to prevent the precipitation of hydrate than to redissolve it when down, it is usual to add ammonium chloride first, then the ammonia, and lastly the phosphate of soda.

General Preparation of Salts of Magnesium.

Is prepared	From	By
Magnesium sulphate, B. and U.S.P.	Dolomite.	Dissolving in sulphuric acid; when soluble magnesium sulphate and insoluble calcium sulphate are formed.
Magnesium carbonate (heavy), B.P.	Magnesium sulphate.	Precipitating with sodium carbonate, using hot concentrated solutions.
Ditto (light), B. and U.S.P.	Ditto.	Ditto, using dilute solutions in the cold.
Magnesia (heavy), B. and U.S.P.	Magnesium carbonate (heavy).	Calcining until all the carbonic acid is driven off, as shown by some taken from the centre of the crucible no longer effervescing on the addition of acid.
Ditto (light), B. and U.S.P.	Ditto (light).	Calcining like the heavy magnesia.
Granulated citrate of magnesia, U.S.P.	Ditto.	Mixing with citric acid and water, drying and powdering. The powder is mixed with sugar, sodium bicarbonate, and citric acid, damped with alcohol, passed through a sieve, so as to form a coarse powder, and dried.
Magnesium sulphite, U.S.P.	Magnesia.	Suspending in water and adding excess of sulphurous acid.

GENERAL IMPURITIES.—The chief impurities in the sulphate are the lime and iron from dolomite. Other alkaline earths and alkalies may also be present. The sulphuric acid employed may be impure, or the sulphate may have been prepared by a process in which hydrochloric acid is used, and thus chlorides may occur. In the carbonate prepared from the sulphate the same impurities may occur, as well as unchanged sulphate. In magnesia these may all occur, and carbonate as well.

TESTS.—The absence of iron and other metals is ascertained by the aqueous solution giving no colour or precipitate with ferrocyanide of potassium, hydrogen sulphide, or ammonium sulphide. Chloride of ammonium prevents the precipitation of magnesia by ammonia and ammonium carbonate, but it does not prevent the precipitation of other alkaline earths, and their absence is ascertained by the solution remaining clear after the addition of these three reagents.

GENERAL ACTION OF MAGNESIA.—When administered by the mouth the difference between absorption and excretion is not great enough to allow magnesium salts to accumulate in the blood sufficiently to produce any toxic effects. When injected into the blood, sulphate of magnesia, in doses of about 5 grs. per pound weight of body, paralyses the respiration and heart in cats (Hay), and has a similar effect in other animals also.

Magnesiæ Sulphas, B.P.; Magnesii Sulphas, U.S.P. SULPHATE OF MAGNESIA, B.P.; OF MAGNESIUM, U.S.P. EPSOM SALTS. $MgSO_4,7H_2O$; 246.

PROPERTIES.—In minute, colourless, transparent, acicular crystals, whose form is a rhombic prism. They look exactly like sulphate of zinc. Its taste is bitter, and it is called in Germany *Bittersalz*. This distinguishes it from the zinc salt, which has a strong metallic taste. It readily dissolves in water, and the solution gives the reactions of magnesium and a sulphate.

IMPURITIES.—Lime and iron.

TESTS.—Its aqueous solution is not precipitated at ordinary temperatures by oxalate of ammonia (no lime), nor does it give a brown precipitate with chlorinated lime or soda (no iron).

DOSE.—As a purgative, half an ounce to an ounce and a-half for a single dose. In repeated doses, especially if taken fasting, 60 to 120 grains. As a diuretic, 20 to 60 grs.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
Enema Magnesiæ Sulphatis.	Infusum Sennæ Compositum.
Mistura Sennæ Composita.	

B.P. Enema Magnesiæ Sulphatis. ENEMA OF SULPHATE OF MAGNESIA (Enema Catharticum).—Sulphate of magnesia 1, olive oil 1, starch mucilage 15.

ACTION.—In moderate doses it causes a copious secretion from the intestinal mucous membrane, and acts as a purgative. It does

not stimulate the muscular coat of the bowels much. It thus causes little griping, but neither does it accelerate peristaltic action. Thus a part of the fluid poured out into the intestine may be reabsorbed as it passes slowly along. It is therefore usual when we wish to produce free purgation to combine the salts with some purgative which will stimulate the muscular coat of the bowel, such as senna. When given alone it is apt to produce much flatulent distension of the abdomen and rumbling, and a carminative is therefore often given along with it. Its objectionable bitter taste may be covered by dissolving it in acid infusion of roses and adding spirit of chloroform. It may be employed as a purgative enema. When absorbed into the blood it acts as a diuretic if the skin be kept cool, and as a diaphoretic if the skin be kept warm or moderate exercise taken. It is absorbed more readily when given in small quantities, but a little is also taken up when purgative doses are employed, and it is therefore a useful purgative in febrile states.

USES.—Sulphate of magnesia is one of the most common and useful saline purgatives. For its mode of action and uses, *vide* pp. 342–345. On account of its great solubility it may be used in very concentrated solution to remove dropsy (p. 345) when less soluble salts cannot. Repeated small doses are very serviceable in biliousness.

U.S.P. Magnesii Carbonas. CARBONATE OF MAGNESIUM, $(MgCO_3)_4.Mg(HO)_2.5H_2O$; 484. This corresponds to the two kinds mentioned in the B.P.

B.P. Magnesiæ Carbonas. CARBONATE OF MAGNESIA, $(MgCO_3)_3MgO,5H_2O$.

B.P. Magnesiæ Carbonas Levis. LIGHT CARBONATE OF MAGNESIA.

Both light and heavy magnesia have the same chemical composition, and differ only in their weight.

PREPARATION.—Both are prepared by precipitating a solution of sulphate of magnesia by a solution of carbonate of soda; removing the resulting sulphate of soda, washing the carbonate, and drying it at a temperature not exceeding that of boiling water so as not to decompose it.

In preparing the heavy carbonate, concentrated boiling solutions are used, the mixture evaporated to dryness, and the sulphate of soda removed by subsequent digestion with water. In preparing the light carbonate, dilute solutions are employed; they are mixed cold; boiled for fifteen minutes; and the sulphate of soda separated by filtration.

PROPERTIES.—A white granular powder almost tasteless. It is recognised as a carbonate by dissolving with effervescence in hydrochloric acid, and the magnesia is detected by the appropriate tests in the resulting solution. The two carbonates are distinguished by their weight.

ACTION.—When swallowed, carbonate of magnesia will have a less stimulating effect upon the mucous membrane than potash or soda, as it is nearly insoluble; but on this very account it is to be preferred to them for neutralising acid in the stomach after meals, inasmuch as it will only neutralise the excess of acid without rendering the fluids alkaline. In the intestine it acts as a laxative, and is partly excreted in the fæces and partly converted into magnesium salts which are absorbed and pass out in the urine.

USES.—As an antacid and laxative, especially in children; in heartburn, in dyspepsia, and vomiting during pregnancy; and in cases where it is desirable to render the urine alkaline, as in gouty persons, where potash and soda disagree.

DOSE.—As antacid, 5 to 20 grains; as a laxative, 10 to 60 grains. It may be conveniently given in milk.

OFFICINAL PREPARATIONS.

B.P.	DOSE.
Liquor Magnesiæ Carbonatis	as antacid 1-4 fl. dr., as laxative 1-2 fl. oz.
,, ,, Citratis	as laxative ...5-10 fl. oz.

B.P. Liquor Magnesiæ Carbonatis. SOLUTION OF CARBONATE OF MAGNESIA.—It is a solution of carbonate of magnesia in water containing carbonic acid. It contains about 13½ grains in the fluid ounce. It is a pleasant laxative for children; and laxative and antacid for women, especially useful during pregnancy.

B.P. Liquor Magnesiæ Citratis. SOLUTION OF CITRATE OF MAGNESIA.—Dissolve citric acid 200 grains, in 2 ounces of water, add carbonate of magnesia 100 grains, and stir until it is dissolved. Filter the solution into a strong half-pint bottle, add syrup of lemons ½ fl. oz. and enough water nearly to fill the bottle; then introduce bicarbonate of potash in crystals 40 grains, and immediately close the bottle with a cork, which should be secured with string or wire. Afterwards shake the bottle until the bicarbonate of potash has dissolved.

CHAPTER XXVI.

METALS—(*continued*).

Class II.—DYAD METALS—(*continued*).

General Actions of Heavy Metals.—The heavy metals form compounds with albumen, known as **albuminates**. These are sparingly soluble, and in consequence of this, white of egg is a useful antidote in poisoning with heavy metals. Albuminates of copper have been obtained by Harnack in which the proportion of copper is definite, and is either 1·35 or 2·64 per cent. On account of their affinity for albumen the heavy metals combine with the albuminous constituents of the **tissues,** and act as powerful **astringents** (p. 306), **irritants** (pp. 299 and 346), or **caustics** (pp. 297 and 302), according to the strength of the application. Their action is comparatively slight when they are applied to the unbroken skin, as the epidermis forms an obstacle to their action, but it is strongly marked where the epidermis is absent, as in wounds or ulcers, and on mucous surfaces where the epithelium is soft. In addition to their astringent action on the fluids and tissues, two metals—lead and silver—cause contraction of the **blood-vessels** (p. 306). In considering the action of the heavy metals belonging to this group and those belonging to Classes III.-VIII., on the organism, it is necessary to distinguish carefully between—

(1) The **local action** upon the surface of the body or upon the alimentary canal, with the **reflex effects** upon the nervous, respiratory and circulatory systems consequent on this local action, and—

(2) the effects produced on the various organs of the body by the metal **after its absorption.** Thus, a large dose of corrosive sublimate when swallowed may produce the ordinary symptoms of poisoning, causing vomiting and purging by its local action on the stomach and intestine, and producing reflexly general collapse with feeble circulation and respiration. Yet if the treatment be prompt, none of the metal may be absorbed, and thus the symptoms which would be produced by its action on the various organs when carried to them by the circulation may be absent.

In considering the effects produced by a metal after its absorption, we must remember that the nature of its **action differs** according to the **quantity** present in the blood at any one time, and that this quantity depends on the relation between the rapidity of **absorption** and **excretion.**

The proportion between absorption and excretion depends greatly on the **channel of introduction,** and therefore the same drug may produce quite different effects according to the mode of its administration. Thus solution of perchloride of iron, when injected directly into the veins, will cause almost immediate death from coagulation of the blood. Other salts of iron which have no coagulating action, if injected into the **circulation,** produce paralysis of the central nervous system and of the vaso-motor nerves, causing loss of voluntary motion, an enormous fall of the blood-pressure, and death. When injected **subcutaneously** iron is absorbed, but it enters the blood less rapidly than when injected into the veins, the quantity present in the blood at any one time is less, and these symptoms are not produced. Nevertheless absorption takes place from the subcutaneous tissue so rapidly that enough iron enters the blood to produce a toxic action. But this action, instead of affecting the nervous, is chiefly exerted on the excreting system, and inflammation of the kidneys occurs. When taken into the **intestinal canal** iron is absorbed very slowly, and only a very small quantity appears in the urine. It is hard to say whether the slight headache which is apt to come on from the administration of iron is due to the direct action of the metal on the nerve-centres after its absorption, or is merely reflex and due to the action of the metal on the intestine. No injury is done to the kidneys of healthy persons, though the effect of the iron upon these organs may be manifested by diminution of albumen in cases of renal disease.

The **form** in which metals are **absorbed** from the intestinal canal is probably that of albuminates, or, perhaps, more properly, of peptonates.

The only heavy metals which are rapidly absorbed from the healthy intestinal canal are lead, mercury, and arsenic. Copper, zinc, silver, tin, iron, manganese, nickel and cobalt are absorbed very slowly indeed. This is shown by the fact that when given internally only mere traces of them appear in the urine. That their absence from this secretion is due to non-absorption, and not to their retention in the blood or tissues, is proved by the fact that when they are injected subcutaneously they pass readily through the kidneys.

Contrary to one's expectation, it has been found that metals are much more readily absorbed by the gastro-intestinal mucous membrane when it is in a catarrhal condition than when it is in a healthy state. When large doses of metallic salts are given at once they are very apt to produce acute catarrh of the intestinal canal, and they are then readily absorbed, and appear in large quantity in the urine. If small doses are given at first, instead of large ones, they may be gradually increased without producing any catarrh, and then absorption into the blood and excretion by the urine does not occur, or only to a slight extent, although the dose finally reached may be large.

The therapeutic bearing of this fact is that if we wish to affect the kidneys by metallic remedies, *e.g.* by iron in cases of albuminuria, the best method of administering the remedy is to begin with large doses at once.

After absorption into the **blood** the metals probably remain to a great extent, if not entirely, in the plasma, and do not become combined with the corpuscles, or only to a very slight extent.[1]

They are carried to all parts of the body, and probably unite with certain **tissues.** They remain in combination with the tissues for a greater or less length of time, modifying their nutrition and functional activity, and then, being again set free, they become excreted.

The heavy metals have all a powerful, poisonous action on **muscles, nerves, nerve-centres, and glands.** The slightness of the action which they exert on these structures when administered by the alimentary canal is due to their slow and sparing absorption by it. But their poisonous power at once becomes evident, as in the case of iron, when they are injected either subcutaneously or directly into the circulation in the form of double salts or organic compounds, which produce no local irritation at the point of injection, nor coagulation of the blood when they are introduced directly into the vessels. The alterations in the spinal cord in acute poisoning by some of them, *e.g.* lead and mercury, and also by arsenic, have the characters of acute central myelitis, the grey substance being chiefly affected. In more chronic poisoning the white substance is affected as well, so that the alterations resemble those of diffuse myelitis. The nervous symptoms produced by heavy metals are probably due to such alterations in the nerve-centres, and sometimes to peripheral alterations in the nerves also.

Metals are **excreted** chiefly by the bile (p. 354), by the kidneys, by the mucous membranes of the stomach and intestine; and probably to a slight extent by the skin. Elimination by these channels may commence very soon after the metal has entered the blood.

During the process of elimination the metals may irritate the eliminating organs (Fig. 3, p. 31), and may cause vomiting by their action on the stomach (p. 324), diarrhœa by their action on the intestine, and albuminuria by their action on the kidneys, although they have been injected into the veins, or subcutaneously, and only reach these organs through the blood.

On account of the quantity of metal which is eliminated by the bile and intestinal mucous membrane, purgatives are useful agents in the treatment of chronic metallic poisoning (pp. 334 and 544).

When metals have entered the blood in considerable quantities, the **kidneys** become inflamed during the process of their excretion, and undergo changes which affect both the tubules and the

[1] This is best shown by separating the corpuscles and plasma in a centrifugal machine and analysing them separately, so as to ascertain the amount of metal in each.

glomeruli. The tubules are affected first, and the epithelial cells, both of the convoluted and straight tubules, take up the metal and become gradually disintegrated. They are partly thrown out as casts, and partly block up the tubules, causing secondary degeneration of the glomeruli. Both tubules and glomeruli become atrophied. These effects appear to be produced by all the heavy metals.

The possible effect of mercury on the kidneys should be borne in mind when prescribing a very prolonged mercurial course, and it would be interesting to inquire how far albuminuria in apparently healthy persons is caused by mercurials.

GROUP III.—ZINC, COPPER, CADMIUM, AND SILVER.

GENERAL ACTIONS.—They combine with **albumen** and form insoluble albuminates, and have thus an astringent action.

With the exception of salts of silver, which form a compound with the epidermis, they have no action on the epidermis, but they may pass through the pores, especially chloride of zinc. This salt produces inflammation, or even mortification, acting by its affinity both for water and for albumen. It is used as a caustic for destroying the surface of unhealthy sores and producing a more healthy action. The other preparations of the metals in this group act in the same way, but are less powerful, and are applied to ulcers and to chronic skin diseases.

They are applied for their astringent action to the **eye** in gonorrhœal ophthalmia, ulcerations or opacity of the cornea, and to the **mucous membranes** of the urethra and vagina in gonorrhœa and leucorrhœa.

Insoluble preparations such as oxide of zinc have little action on the skin, but are applied as powder or ointment to raw and excoriated surfaces, where protection from external influences with very slight stimulation is wished, as in intertrigo.

In the **mouth** they combine with the albumen of the tongue and cheeks, and produce a very disagreeable metallic taste. Notwithstanding this they are employed, especially sulphate of copper, for ulcers of the mouth or fauces.

Zinc chloride has been recommended for carious teeth.

In the **stomach** they unite with albumen in its walls, producing irritation and consequent nausea, accompanied by muscular relaxation. They have been used as nauseants in spasmodic affections, as epilepsy, chorea, hysteria, &c.

In a somewhat larger dose they produce vomiting, which is speedy and complete, especially in the case of zinc and copper, which are consequently much used in cases of poisoning where we wish the stomach emptied with all possible speed. They are preferred in such cases to tartar emetic, as they do not produce so much depression, nor are they so liable to cause diarrhœa; and to ipecacuanha, because their action is more rapid and certain.

The compounds of zinc or copper with albumen or peptones

will produce vomiting, either when given by the mouth or when injected into the veins, but they are classed as **local emetics** (p. 325).

Their emetic action when injected into the veins may be due to a direct action on the vomiting centre in the medulla (p. 322); but it may also be that they are carried to the stomach by the blood and act reflexly from it (*vide* Fig. 3, p. 29, and cf. p. 324).

The albuminates of copper and zinc, and probably those of the other metals, undergo changes both in the stomach and intestine before absorption which we do not perfectly understand. Albumen is not simply dissolved and absorbed in the intestinal canal, but is converted into peptone. Albuminate of copper has been introduced into a gastric fistula in a dog, and the blue colour was seen to disappear at the edges, and finally all copper was removed from it before the albumen was itself completely digested. Whether or not the copper was removed in combination as a peptone or not we cannot as yet say. Copper salts combine with peptone, forming easily soluble precipitates.

In the **intestine** small doses lessen the frequency of the stools, and have been thus used in chronic diarrhœa and dysentery, but larger doses have an irritant effect and cause diarrhœa. The insoluble salts, as oxide and carbonate of zinc, have a much weaker action than the soluble ones, and thus a large quantity has the same action as a small one of the soluble salts.

Chronic poisoning by copper is said to have occurred in consequence of the use of copper salts to give a bright green colour to tinned peas or other vegetables, as well as from the employment of imperfectly-cleansed copper pans. Some doubt has been thrown on the possibility of producing chronic poisoning by the internal administration of copper in small doses, as in some experiments it was given to animals for a length of time without injury. More recent experiments show, however, that at least in ruminants chronic poisoning may be produced. The symptoms are loss of appetite, imperfect rumination, periodical constipation, imperfect nutrition, muscular weakness, languor, jaundice, albuminuria, and towards the end hæmoglobinuria or hæmaturia. On post-mortem examination granular degeneration of the muscles and heart, enlarged spleen, fatty degeneration of the liver, dark brown colour of the blood, and granular deposits of methæmoglobin in the renal tubules along with hæmorrhagic parenchymatous nephritis are found.

Chronic poisoning by copper may occur among coppersmiths, or in families where copper pans have been used. The symptoms are a metallic taste, a feverish state, with symptoms of subacute gastro-enteritis, not unfrequently jaundice, trembling of limbs, and cramps. A purple line is said to form on the gums.

ZINC. Zn; 65·2.

Sources of Zinc.—The chief are native carbonate or calamine ($ZnCO_3$) and zinc blende (ZnS).

GENERAL REACTIONS OF ZINC SALTS.—The most characteristic test is that it forms a white sulphide, which is precipitated on the addition of ammonium sulphide to a solution, and which is insoluble in caustic alkalies. Caustic potash, soda, or ammonia, give a white precipitate of hydrate, soluble in excess; ammonium carbonate gives a similar precipitate, soluble in excess; but sodium and potassium carbonate give a white precipitate, insoluble in excess.

GENERAL PREPARATION OF ZINC SALTS.

Prepared	From	By
Zinc, B. and U.S.P.	Zinc blende or calamine.	Roasting, to drive off sulphur or carbonic acid, and then distilling the oxide with charcoal.
Granulated zinc, B.P.	Zinc.	Melting and throwing into water.
Zinc chloride, B. and U.S.P.	Zinc.	Dissolving in hydrochloric acid ($Zn_2 + 4HCl = 2ZnCl_2 + 2H_2$): it is then purified from lead or iron by passing chlorine through it, and adding carbonate of zinc, $2FeCl_2$ (Ferrous chloride.) $+ Cl_2$ (Chlorine.) $= Fe_2Cl_6$ (Ferric chloride.) Fe_2Cl_6 (Ferric chloride.) $+ 3ZnCO_3$ (Carbonate of zinc.) $+ 3H_2O =$ Fe_26HO (Ferric hydrate.) $+ 3ZnCl_2$ (Chloride of zinc.) $+ 3CO_2$. (Carbonic acid gas.) $PbCl_2$ (Chloride of lead.) $+ Cl_2$ (Chlorine) $+ 2ZnCO_3$ (Carbonate of zinc.) $= PbO_2$ (Peroxide of lead.) $+ 2ZnCl_2$ (Chloride of zinc.) $+ 2CO_2$. (Carbonic acid gas.)
Zinc sulphate, B. and U.S.P.	Zinc.	Dissolving in sulphuric acid, and purifying in the same way as chloride.
Zinc carbonate, B. and U.S.P.	Zinc sulphate.	Precipitating with carbonate of soda.
Zinc acetate, B. and U.S.P.	Zinc carbonate.	Dissolving in acetic acid.
Zinc oxide, B. and U.S.P.	Do.	Calcining.
Zinc valerianate, B. and U.S.P.	Zinc sulphate.	Mixing with sodium valerianate.
Zinc bromide, U.S.P.	Do.	Mixing with hot solution of potassium bromide, precipitating potassium sulphate by alcohol, filtering, and evaporating. Or by acting on zinc with bromine.
Zinc iodide, U.S.P.	Zinc.	Digesting with iodine in water and evaporating.
Zinc phosphide, U.S.P.		Passing phosphorus vapour in dry hydrogen over melted zinc.

GENERAL IMPURITIES OF ZINC SALTS.—Iron, lead, copper, and arsenic.

GENERAL TESTS.—A solution of zinc salt acidulated with hydrochloric acid gives no precipitate with sulphuretted hydrogen (absence of lead, copper, or arsenic). The absence of copper is further ascertained by ammonia giving with a solution of zinc salts a white precipitate, soluble in excess without colour. If copper be present the solution would be blue. Solutions should give no blue with ferro- or ferri-cyanide of potassium, nor any black colour with tincture of galls (absence of iron).

GENERAL ACTION OF SALTS OF ZINC.—They combine with albumen and coagulate it. The chloride of zinc thus acts as an **escarotic** after the epidermis has been previously removed by caustic potash. Neither it, nor the sulphate, nor acetate of zinc has any action on the unbroken skin, but when applied to mucous membranes they will act as **irritants** in large, and as **astringents** in small doses.

Sulphate and acetate of zinc are prompt **emetics**, causing rapid evacuation of the contents of the stomach with little nausea or depression.

The mode of action of zinc salts as emetics has not been perfectly determined. It is probably partly due to the **local** effect upon the stomach, and partly to the stimulant action upon the vomiting centre in the medulla oblongata after absorption into the circulation.

Vomiting is produced by the injection of zinc salts into the circulation, but this may be partly due to irritation of the stomach by the zinc salts during the process of excretion by its mucous membrane, as well as to the action upon the medulla.

In small doses zinc salts act also as **nervine tonics,** and lessen sweating.

Zincum. B. and U.S.P. ZINC. 64·9. Zinc of Commerce, B.P. Metallic zinc in the form of thin sheets or irregular granulated pieces, U.S.P.

CHARACTERS.—A bluish white metal having the sp. gr. 6·9. When treated with warm diluted sulphuric acid it is almost completely dissolved, forming a colourless liquid which yields a white precipitate with test solution of ferro-cyanide of potassium, or of sulphide of ammonium. U.S.P.

PREPARATIONS CONTAINING ZINC.

B.P.	U.S.P.
Liquor Zinci Chloridi.	Liquor Zinci Chloridi.
Unguentum Zinci.	Unguentum Zinci Oxidi.
Zinci Acetas.	Zinci Acetas.
,, Carbonas.	,, Bromidum.
,, Chloridum.	,, Carbonas Præcipitatus.
,, Oxidum.	,, Chloridum.
,, Sulphas.	,, Iodidum.
,, Valerianas.	,, Oxidum.
Zincum Granulatum.	,, Phosphidum.
	,, Sulphas.
	,, Valerianas.

B.P. Zincum Granulatum. GRANULATED ZINC—(Zinc fused and poured into water).

IMPURITIES.—Very frequently it contains sulphur or arsenic.

TESTS.—Zinc is chiefly used for preparing hydrogen, and these impurities are tested by adding pure dilute hydrochloric or sulphuric acid to it and holding over it a piece of paper dipped in acetate of lead. If sulphur be present the paper is blackened. If the piece of paper be wetted with solution of nitrate of silver, a brown or black stain is produced if arsenic is present. On lighting the hydrogen and depressing a piece of porcelain on it, a black stain is produced if arsenic be present.

Zinci Oxidum, B. and U.S.P. OXIDE OF ZINC. ZnO. 80·9.

CHARACTERS.—A soft nearly white tasteless and inodorous powder, becoming pale-yellow when heated.

IMPURITIES.—Undecomposed carbonate, chloride, sulphates, iron and copper.

TESTS.—Dissolves without effervescence in diluted nitric acid, forming a solution, which is not affected by chloride of barium or nitrate of silver, and gives with carbonate of ammonia a white precipitate which dissolves entirely (no iron) without colour (no copper) in an excess of the reagent, forming a solution which is precipitated white by sulphide of ammonium.

DOSE.—2 to 10 grains.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
Unguentum Zinci.	Unguentum Oxidi Zinci.

B.P. Unguentum Zinci. ZINC OINTMENT.—Oxide of zinc 80 grs., benzoated lard 1 oz., or 1 in 6½ nearly.

U.S.P. Unguentum Oxidi Zinci. OINTMENT OF OXIDE OF ZINC.—Oxide of zinc 20, benzoated lard 80, or 1 in 5.

USES.—Oxide of zinc is sparingly soluble in the stomach. It dissolves to a slight extent, too little to act as an emetic, but sufficient to produce the action of small doses of soluble zinc salts as a nervine tonic and astringent.

It may be used as a dusting powder in intertrigo, and the zinc ointment is one of the most efficacious remedies we possess for application to excoriated surfaces and eczema. It has been given in whooping-cough, epilepsy, hysteria, nervous headache, and to check profuse sweating in phthisis, and profuse secretion from the bronchi in bronchitis. In the sweating of phthisis it is frequently combined with hyoscyamus, and it is somewhat difficult to say how much of the beneficial action is due to the hyoscyamus.

Zinci Carbonas, B.P.; Zinci Carbonas Præcipitatus, U.S.P. CARBONATE OF ZINC. B.P. PRECIPITATED CARBONATE OF ZINC. $ZnCO_3(ZnO)_2.3H_2O$. B.P.; $(ZnCo_3)_2.3Zn(HO)_2$; 546·5, U.S.P.

CHARACTERS AND TESTS.—White, tasteless, inodorous, insoluble

in water; soluble, with effervescence and without residue, in diluted nitric acid. This solution gives the reactions of zinc.

DOSE.—1 to 10 grains.

USES.—Used sometimes in skin diseases instead of oxide, and preferred to it by some. Formerly native carbonate was used as calamine cerate or Turner's cerate, corresponding to the ointment of the oxide.

Zinci Chloridum, B. and U.S.P. CHLORIDE OF ZINC, $ZnCl_2$; 135·7.

CHARACTERS AND TESTS.—Colourless opaque rods or tablets very deliquescent and caustic; soluble almost entirely in water, alcohol, and ether. The watery solution gives the reactions of zinc and of a chloride.

PREPARATION CONTAINING CHLORIDE OF ZINC.

Liquor Zinci Chloridi .....366 grains in 1 fluid ounce.

Liquor Zinci Chloridi, B. and U.S.P. SOLUTION OF CHLORIDE OF ZINC, $ZnCl_2$; 135·7, U.S.P. Prepared like the solid but not so much evaporated.

USES.—It is a powerful **caustic** distinguished by its property of burning **deeply** and not spreading sidewise like many others. It is applied, in substance, or made into a paste with starch or gypsum, to cancers, sloughing or unhealthy sores, and nævi. Diluted it is applied to ulcers.

It has been used to destroy the exposed pulp in decayed teeth, warty growths, condylomata, syphilitic sores, and lupus. In the proportion of one to two grains in a pint of water it has been recommended by Ringer as an injection in gonorrhœa.

Burnett's (Sir W.) disinfectant and deodorising solution is solution of chloride of zinc (of sp. gr. 2), and it is by the accidental use of this, that most cases of zinc poisoning occur.

Zinci Sulphas, B. and U.S.P. SULPHATE OF ZINC. $ZnSO_4.7H_2O$; 288·9.

CHARACTERS AND TESTS.—In colourless transparent prismatic crystals with a strong metallic styptic taste. Its solution in water gives the reactions of zinc and of a sulphate.

DOSE.—1 to 3 grains (as a tonic); 10 to 30 grains (as an emetic).

USES.—Sulphate of zinc is used as an **astringent** to lessen discharges from mucous-membranes; it is employed as a lotion in gonorrhœa and leucorrhœa; as a wash to the eye in ophthalmia; and, mixed with honey, in gangrene of the mouth in children. It is used as a gargle to the throat in relaxed sore-throat, pendent uvula, and enlarged tonsils.

As an **emetic** it is chiefly employed in narcotic poisoning, where the rapidity of its action, unaccompanied by any depressing influence on the circulation, is very serviceable. It is sometimes used,

also, to cause vomiting in croup. It is employed as an **astringent** in chronic diarrhœa and dysentery. It has also been used as a **tonic** in flatulence and flatulent distension of the colon. After absorption into the blood it has a tonic action on some parts of the nervous system, and is used in the treatment of convulsive diseases, such as chorea, epilepsy, hysteria, as well as in spasmodic affections of involuntary muscular fibre, such as angina pectoris and spasmodic asthma.

Zinci Acetas, B. and U.S.P. ACETATE OF ZINC. $Zn(C_2H_3O_2)_2.2H_2O$, B.P.; $Zn(C_2H_3O_2)_2 3H_2O$; 236·9, U.S.P.

CHARACTERS AND TESTS.—Thin translucent and colourless crystalline plates, of a pearly lustre, with a sharp unpleasant taste; soluble in water; the solution gives the reactions of zinc, and evolves acetic acid when decomposed by sulphuric acid.

DOSE.—1 to 2 grains (as a tonic); 10 to 20 grains (as an emetic).

USES.—It is used for much the same purposes, and in the same doses, as the sulphate. An unchemical but useful injection for gonorrhœa, gleet, and leucorrhœa, consists of six grains of sulphate of zinc, with four ounces of the dilute solution of sub-acetate of lead. In this mixture the sulphate of lead which is precipitated has probably a beneficial action in keeping apart the surfaces of the mucous canal into which it is injected (p. 392).

U.S.P. Zinci Bromidum. BROMIDE OF ZINC. $ZnBr_2$; 224·5.

CHARACTERS.—A white, or nearly white, granular powder, very deliquescent, odourless, having a sharp saline metallic taste, and a neutral reaction. Very soluble in water and in alcohol. The aqueous solution of the salt yields the reactions of zinc and of a bromide.

USES.—In large doses it is irritant and emetic like other salts of zinc. It has been recommended in epilepsy with the idea of combining the actions of bromine and zinc.

DOSE.—2 to 8 grains given in syrup.

U.S.P. Zinci Iodidum. IODIDE OF ZINC. ZnI_2; 318·1.

CHARACTERS.—A white, or nearly white, granular powder, very deliquescent, odourless, having a sharp saline and metallic taste, and an acid reaction. Very soluble in water and in alcohol. The aqueous solution yields a white precipitate with test solution of ferrocyanide of potassium or of sulphide of ammonium, a yellow precipitate with test solution of acetate of lead, and a red one with test solution of mercuric chloride (iodide.)

USES.—Locally it has been used in solution as an application to enlarged tonsils. An ointment, 1 part to 8 of lard, has been used in place of the ointment of iodide of potassium or of cadmium to reduce swellings. A solution of 2 grains to 1 oz. has been used in gonorrhœa. Internally it has been used in scrofula,

chorea and hysteria. It is best administered in the form of syrup.

DOSE.—$\frac{1}{2}$ to 2 grains.

Zinci Valerianas, B. and U.S.P. VALERIANATE OF ZINC. $Zn(C_5H_9O_2)_2$; 284·9.

CHARACTERS.—In brilliant, white, pearly, tabular crystals, with a feeble odour of valerianic acid, and a metallic taste; scarcely soluble in cold water or in ether, soluble in hot water and alcohol. Heated to redness in an open crucible it leaves a residue which, when dissolved in diluted sulphuric acid, yields with ammonia a precipitate which entirely dissolves in an excess of the reagent, and the resulting solution gives a white precipitate with sulphide of ammonium (zinc).

PREPARATION.—Mixing hot aqueous solutions of sulphate of zinc and valerianate of soda, evaporating at a gentle heat, and crystallising. The crystals are washed with water until free from sulphate.

IMPURITIES.—Sulphate and butyrate of zinc from imperfect preparation.

TESTS.—Its solution in hot water is not precipitated by chloride of barium (no sulphate). It gives when heated with diluted sulphuric acid a distillate, which when mixed with the solution of acetate of copper, does not immediately affect the transparency of the fluid, but forms after a little time oily drops, which gradually pass into a bluish-white crystalline deposit (no butyrate).

DOSE.—$\frac{1}{2}$—4 gr.; the dose may be increased till some nausea is produced.

USES.—Valerianate of zinc has been supposed to combine the nervine tonic action of zinc with the antispasmodic effect of valerian but it is much better to use valerian itself or its oil along with a salt of zinc as the acid has no important physiological action. It is used in chorea, especially when occurring in hysterical persons, and should not be discontinued until symptoms of nausea begin to make their appearance. It is also employed in epilepsy and neuralgia.

U.S.P. Zinci Phosphidum. PHOSPHIDE OF ZINC. Zn_3P_2; 256·7.

CHARACTERS.—Minutely crystalline friable fragments, having a metallic lustre on the fractured surfaces, or a greyish black powder permanent in the air having a faint odour and taste of phosphorus, insoluble in water or alcohol, but completely soluble in hydrochloric or sulphuric acids with evolution of phosphoretted hydrogen.

USES.—Its action is similar to that of phosphorus, and it is used in place of it. Each grain contains nearly $\frac{1}{4}$ grain of phosphorus.

DOSE.—Not more than $\frac{1}{20}$ grain at first.

COPPER. Cu. 63·4.

SOURCES.—Its chief source is copper pyrites, which is a double sulphide of copper and iron.

GENERAL REACTIONS.—Ammonia throws down a pale blue precipitate of hydrate, which is soluble in excess, forming a deep blue solution. Potassium ferrocyanide gives a maroon red precipitate.

Prepared	From	By
Copper.	Copper pyrites.	Roasting with sand and coal.
Copper sulphate.	Copper.	Heating copper or its oxide with sulphuric acid.
Copper acetate.	Copper sulphate.	Precipitating with acetate of lead.

GENERAL IMPURITY.—Iron.

GENERAL TEST.—If an aqueous solution of a copper salt be mixed with twice its volume of chlorine water, any iron present is converted into a ferric salt. If solution of ammonia be now added, cupric hydrate will fall as a precipitate of a pale blue colour, but is redissolved by excess, forming a deep blue solution. If iron be present it will be precipitated by the ammonia and not redissolved.

Cuprum. = Cu 63·5. B.P. COPPER.—Fine copper wire, about No. 25.

USE.—To detect the presence of metals, as silver, mercury, and arsenic, by their being precipitated on its surface and forming a stain. It is employed in the preparation of sulphate of copper and of spirit of nitrous ether.

Cupri Sulphas, B. and U.S.P. SULPHATE OF COPPER. $CuSO_4.5H_2O$; 249·2.

May be obtained by heating sulphuric acid and copper together, dissolving the soluble product in hot water, and evaporating the solution until crystallisation takes place on cooling.

CHARACTERS AND TESTS.—A blue crystalline salt, in oblique prisms, soluble in water, forming a pale blue solution which strongly reddens litmus. The aqueous solution gives the reactions of copper and a sulphate.

DOSE.—As an astringent, $\frac{1}{4}$ grain to 2 grains; as an emetic, 5 to 10 grains.

B.P. Sulphate of Copper, Anhydrous. $CuSO_4$. Sulphate of copper deprived of its water by a heat of 400°.

CHARACTERS.—A yellowish-white powder, which becomes blue when moistened with water.

ACTION.—Sulphate of copper has little or no action on the skin covered by epidermis, but when applied to the denuded skin it combines with the albuminous constituents of the tissues, forming an albuminate of copper. It thus acts as a mild **caustic,** and is an **astringent.** It has a similar astringent action on mucous membranes, and when swallowed in large doses it acts as a powerful **emetic,** like the sulphate of zinc, and in smaller doses as an astringent. Like sulphate of zinc, it probably exerts its action partly on the stomach itself and partly on the vomiting centre. Small doses absorbed into the blood appear to have a **tonic** action on some parts of the nervous system, and to exert an **astringent** action on mucous membranes. The copper is **excreted** by the mucous membrane of the intestine, by the bile, sweat, and kidneys. It is probable that its effect as an emetic when injected into the blood is partially due to the action it produces upon the stomach or intestines in the process of elimination (p. 29). Its action as an astringent upon other mucous membranes is probably due to a similar cause.

USES.—Sulphate of copper in substance is used as a mild caustic to the edges of sores, to repress exuberant granulations, and as a styptic to arrest the blood from leech-bites. When mixed with honey it may be applied to the mouth in cancrum oris. In solution it may be applied to indolent ulcers, and to remove warts and parasitic skin diseases, and as an injection into the nose to stop epistaxis. It is used as a wash to the eyes in ophthalmia, as an injection in gonorrhœa and leucorrhœa, and as a gargle in sore-throat. It is an efficient and rapid emetic in cases of narcotic poisoning, in phosphorous poisoning, and in croup. It is a powerful astringent in chronic diarrhœa, dysentery, and colliquative diarrhœa of phthisical patients. It is employed, like zinc, in chorea, epilepsy, and hysteria, but seems less useful than zinc.

B.P. Test Solution of Ammonio-Sulphate of Copper.

Used as a test for arsenious acid, forming with it Scheele's green.

B.P. Subacetate of Copper of Commerce. $Cu.CuO(C_2H_3O_2)_2$. VERDIGRIS, AERUGO.—Used in solution as a test.

B.P. Test Solution of Acetate of Copper.

USE.—In testing for butyric acid in valerianates.

U.S.P. Cupri Acetas. ACETATE OF COPPER. $Cu(C_2H_3O_2)_2 H_2O$; 199·2.

CHARACTERS.—Deep green, prismatic crystals, yielding a bright green powder, efflorescent on exposure to air, odourless, having a nauseating metallic taste and an acid reaction.

TESTS.—If the aqueous solution of the salt be treated with hydrosulphuric acid until all the copper is precipitated, the filtrate should leave no residue on evaporation (alkalies, alkaline earths, or iron). If the aqueous solution be heated to boiling with solution of

soda in excess, it will yield a filtrate which should not be clouded by hydrosulphuric acid (absence of lead and zinc).

USES.—Same as those of sulphate of copper. Not used internally.

CADMIUM. Cd. 112.

It is a somewhat rare metal occurring in certain zinc ores. It is more volatile than zinc, and when the native zinc carbonate or calamine is heated with charcoal the cadmium volatilises first. It is like tin, but is rather harder.

B.P. Cadmii Iodidum. IODIDE OF CADMIUM, CdI_2.

PREPARATION.—It is prepared by acting on cadmium with iodine in the presence of water.

CHARACTERS.—It forms white micaceous crystals, which have a pearly lustre. When heated to 600° they melt and form an amber-coloured fluid. When the heat becomes dull red they give off violet fumes, showing that iodine is present in them. The presence of cadmium is shown by adding H_2S or NH_4S to the solution in water when the yellow sulphide, so much used in painting under the name of cadmium yellow, is precipitated. This precipitate is insoluble in excess of sulphide of ammonium, and is thus distinguished from antimony and arsenic, whose sulphides are soluble. The solution also gives a white gelatinous precipitate with potash, insoluble in excess.

IMPURITIES.—It might be contaminated with tin and zinc.

TESTS.—These are detected by adding ammonium sulphide to the filtrate after the cadmium has been precipitated by potash from the aqueous solution.

OFFICINAL PREPARATION.

B.P. Unguentum Cadmii Iodidi. OINTMENT OF IODIDE OF CADMIUM (62 grains to 1 oz. of simple ointment).

USE.—When applied to the skin, iodide of cadmium acts as a rubefacient, and has been used to promote the absorption of glandular enlargements. Its advantages over iodine and iodide of lead are that it does not cause poisoning like lead, and it does not stain the skin, and may therefore be applied to cause absorption of glands in the neck, where stains would be unsightly.

ARGENTUM. Silver.

Argentum Purificatum. B.P. REFINED SILVER.

Pure metallic silver.

IMPURITIES.—Gold, copper, and lead.

TEST.—If ammonia be added in excess to a solution of the metal in nitric acid, the resulting fluid exhibits neither colour nor turbidity.

PREPARATION.—Argenti Nitras.

Argenti Nitras, B. and U.S.P. NITRATE OF SILVER.—$AgNo_3$; 169·7.

PREPARATION.—By dissolving silver in nitric acid, evaporating and crystallising.

CHARACTERS.—In colourless tabular crystals, the primary form of which is the right rhombic prism; or in white cylindrical rods; soluble in distilled water, and in rectified spirit. The solution gives with hydrochloric acid a curdy white precipitate, which darkens by exposure to light, and is soluble in solution of ammonia. A small fragment heated on charcoal with the blowpipe, first melts, and then deflagrates, leaving behind a dull white metallic coating.

IMPURITIES.—Nitrate of potash, metallic impurities.

TESTS.—Ten grains dissolved in two fluid drachms of distilled water give with hydrochloric acid a precipitate, which, when washed and thoroughly dried, weighs 8·44 grains. The filtrate when evaporated by a water-bath leaves no residue.

DOSE.—$\frac{1}{6}$ to $\frac{1}{2}$ grain.

ADMINISTRATION.—As an application to the eyes or injection it is used of various strengths, but an ordinary safe one is 2 grains to the ounce. When made into pill it must not be mixed with tannin, which reduces the silver to the metallic condition and becomes converted into gallic acid with evolution of carbonic acid gas. It is best made up into pill with kaolin and a very little tragacanth. As a draught it may be made up with dilute nitric acid, syrup, and mucilage.

U.S.P. Argenti Nitras Fusus. MOULDED NITRATE OF SILVER.

Prepared by fusing together nitrate of silver, 100 parts, hydrochloric acid 4 parts, and pouring into suitable moulds.

CHARACTERS.—A white, hard solid, generally in form of pencils or cones of a fibrous fracture, becoming grey or greyish-black on exposure to light in presence of organic matter.

U.S.P. Argenti Nitras Dilutus. DILUTED NITRATE OF SILVER.

PREPARATION.—Prepared by fusing together equal parts of nitrate of silver and nitrate of potassium.

CHARACTERS.—A white, hard solid, generally in the form of pencils or cones, of a finely granular fracture, becoming grey or greyish black on exposure to light in presence of organic matter.

TESTS.—An aqueous solution of 1 Grm., acidulated with nitric acid, when completely precipitated by hydrochloric acid should yield not less than 0·84 Grm. of dry chloride of silver. The filtrate separated from the precipitate, when evaporated to dryness, leaves a residue which is completely soluble in water, and which yields a white crystalline precipitate with a concentrated solution of bitartrate of sodium (potassium).

GENERAL ACTION OF SILVER SALTS.—Soluble silver salts, such

as the nitrate of silver, have a strong affinity for the cement by which epithelial or endothelial cells are united, and are therefore much used in staining microscopic preparations. They also unite with albumen, forming albuminates of silver. When applied to the **skin,** nitrate of silver produces a white mark which rapidly becomes blackened by exposure to light, and the epidermis, either alone or with a slough varying in depth according to the strength of the application, is thrown off. Locally, it causes greater contraction of the **vessels** than other metals. In the **mouth** it has an unpleasant astringent taste, corrugates the mucous membrane, and acts as an irritant or caustic. In the **stomach,** in small doses, it acts as an astringent, and occasionally lessens vomiting, but in larger doses it acts as an irritant, and causes vomiting, and symptoms of irritant poisoning (p. 347). In the **intestine** small doses are astringent, and, when absorbed from the blood, appear, like zinc or copper, to have a tonic action on some parts of the **nervous system.** When taken for a length of time it is apt to cause a livid discoloration of the skin. This discoloration appears to depend upon the amount of silver taken independently of the time during which its administration has been continued, so that it is advisable, when administering nitrate of silver to a patient, to inquire whether he has previously taken it or not, as the silver remaining in the system, together with that administered in the second instance, might cause a darkening of the skin which the quantity employed in the second course alone would not have produced. When taken for a long time, silver salts appear to produce fatty degeneration of the **tissues.** They are probably very slowly **eliminated** by means of albuminous secretions such as bile.

USES.—Nitrate of silver may be applied to destroy parasitic fungi and remove tinea; to destroy the epidermis itself or epidermic structures, such as warts, and to check the bleeding from leech bites. In solution it relieves the itching of pruritus and of lichen. When sponged over the skin it hardens the epidermis and may prevent the formation of bed-sores. It is said to arrest vesication in herpes if painted over the surface as soon as the vesicles begin to form. It is also said that the pitting of small-pox is prevented by opening the vesicle and touching the surface beneath with a solution of the salt, or even by painting the solution over the skin. It has been recommended as a remedy in erysipelas, and is applied either by painting the strong solution over and beyond the inflamed surface, or by drawing a line with solid nitrate of silver upon the skin a little way beyond the margin of the inflammation. The alteration produced in the tissues underneath this line is said to prevent the extension of the inflammation beyond the limit thus formed. It is of little use in poisoned wounds, such as the bite of a mad dog (p. 303). Dilute solutions may be applied to the eye in tinea tarsi and conjunctivitis. In the mouth it may be used as an application to ulceration of the tongue, soft palate or tonsils, and is

often employed for this purpose on account of the readiness with which it can be applied. In thus applying it care should be taken that it is well fixed in the holder, as otherwise a quick motion of the patient may break off the portable stick of nitrate of silver which will probably fall into the pharynx, be swallowed, and may produce symptoms of irritant poisoning. The treatment of poisoning is to give common salt in order to form insoluble, and therefore inert, chloride of silver. Where the stick of nitrate of silver has been swallowed in substance this treatment has not always proved efficacious, and salt should therefore then be administered in combination with mucilaginous substances such as porridge and gruel, along with an emetic, so that the stick of silver may be at once evacuated from the stomach, while the mucilaginous envelope prevents it from doing any harm to the œsophagus on its way. It has been used to destroy the false membrane in croup, and as a useful application to the larynx in laryngeal phthisis. It may be applied either in solution, by means of a brush, or in the form of lycopodium, which, after being dipped in the solution and then dried, may be blown by a curved tube into the larynx. It is sometimes used as an injection in gonorrhœa. Internally, it may be employed in irritable stomach, and also as an astringent in chronic diarrhœa and dysentery, and as a nervine tonic in chorea and epilepsy.

Argenti Oxidum, B. and U.S.P. OXIDE OF SILVER. Ag_2O; 213·4.

CHARACTERS AND TESTS.—An olive-brown powder, which at a low red heat gives off oxygen, and is reduced to the metallic state. It dissolves completely in nitric acid without the evolution of any gas, forming a solution which has the characters of nitrate of silver. 29 grains heated to redness leave 27 grains of metallic silver.

DOSE.—$\frac{1}{2}$ grain to 2 grains.

USES.—It has been used internally in neuralgic pain in the stomach, irritable dyspepsia, and pyrosis. Another drug not unfrequently given in similar affections is creasote, but creasote and oxide of silver are incompatible, as the former becomes oxidised at the expense of the silver oxide, and the mixture may undergo spontaneous combustion. It has been used in hæmorrhage from the stomach and lungs, and has been highly recommended in menorrhagia.

U.S.P. Argenti Cyanidum. CYANIDE OF SILVER. AgCN; 133·7.

CHARACTERS.—A white powder permanent in dry air, but gradually turning brown by exposure to light, odourless and tasteless and insoluble in water or alcohol. Insoluble in cold, but

soluble in boiling nitric acid with evolution of hydrocyanic acid; also soluble in water of ammonia and in solution of hyposulphite of sodium. When heated, the salt fuses, gives off cyanogen gas, and on ignition metallic silver is left.

OFFICINAL PREPARATION.

U.S.P.

Acidum Hydrocyanicum Dilutum.

U.S.P. Argenti Iodidum. IODIDE OF SILVER. AgI; 234·3.

CHARACTERS.—A heavy, amorphous, light-yellowish powder, unaltered by light if pure, but generally becoming somewhat greenish-yellow, without odour and taste, and insoluble in water, alcohol, diluted acids or in solution of carbonate of ammonium. Soluble in about 2,500 parts of stronger water of ammonia. It is dissolved by an aqueous solution of cyanide of potassium and the resulting solution yields a black precipitate with hydrosulphuric acid or sulphide of ammonium (silver). If a small quantity of chlorine water be agitated with an excess of the salt, the filtrate acquires a dark blue colour on the addition of gelatinised starch (iodide).

DOSE.—1 to 2 grains.

USE.—It has been used instead of nitrate of silver in irritability of the stomach, dysmenorrhœa, and epilepsy.

CLASS II.—GROUP IV.

MERCURY, Hg; 200.

Mercury is a liquid metal. It forms two series of compounds, viz., mercurous, in which it is univalent, *e.g.* Hg_2Cl_2; and mercuric, in which it is bivalent, *e.g.* $HgCl_2$. In constitution these salts are analogous to the cuprous and cupric salts.

GENERAL SOURCES.—The chief source is native sulphide or cinnabar.

Metallic mercury is prepared from this by roasting it either alone or with lime or iron.

GENERAL REACTIONS OF SALTS OF MERCURY.—They are all, either volatile, or decomposed by heat with the liberation of free mercury. The soluble salts are decomposed by stannous chloride; the mercuric salts giving first a white precipitate changing into black, and the mercurous salts a black one of finely divided mercury at once. Mercurous salts are most readily distinguished from mercuric salts by their reactions with alkaline carbonates with ammonia, or with potassium iodide. The differences will be readily seen from the following table. The difference between the reactions of potash and ammonia with mercuric salts is noteworthy.

GENERAL REACTIONS OF SALTS OF MERCURY.

Reagent.	Mercurous Salts.	Mercuric Salts.
Stannous chloride.	Black ppt. (finely divided mercury).	White ppt., turning black (calomel changing into mercury).
Caustic soda or potash.	Black ppt.	Yellow ppt. (oxide).
Carbonates of ditto.	White ppt. turning black.	Red-brown ppt.
Ammonia.	Black ppt.	White ppt. (double salt of mercury and ammonia).
Ammonium carbonate.	White ppt. turning black.	White ppt.
Potassium iodide.	Greenish-yellow ppt.	Bright scarlet ppt., soluble in excess either of mercuric chloride or of potassium iodide.

GENERAL IMPURITIES.—Other metals, especially lead, arsenic, and antimony, may be present. But there is such an enormous difference between the activity of the mercurous and the mercuric salts, that the latter form the most important impurities of the former. Corrosive sublimate, for example, is so active that a slight trace of it as an impurity in calomel might cause a medicinal dose of the latter to produce poisonous effects.

GENERAL TEST.—Mercuric salts are readily soluble in alcohol, and especially in ether, and also in a solution of sodium chloride, while mercurous salts are not. The presence of mercuric compounds as an impurity in mercurous preparations can be ascertained by shaking them with ether (B.P.), or with a solution of common salt (U.S.P.), filtering, and testing the filtrate for mercury. If no mercuric salt has been present, neither the ether nor salt solution will dissolve anything, and so the test will show the absence of mercury. When ether or alcohol is used, the absence of mercury may be ascertained by evaporating it and finding that no residue remains.

GENERAL ACTION.—Metallic mercury, mercurous salts, and mercuric salts all have actions differing from each other as far as their local effect is concerned, but agreeing together in their general result after absorption into the system. When applied locally to the skin, **mercury,** either in a state of vapour or when finely subdivided in the form of ointment, will pass through the epidermis without exciting any local irritation, and be absorbed into the circulation, where it will produce the general effects of the drug. Taken in the form of vapour into the lungs, it will have a similar action. The **mercurous salts** are also absorbed in the same way as metallic mercury. They have a slightly more stimulating

effect than it, but do not produce the same intense irritation that the mercuric salts cause. The **mercuric salts** unite with albumen, forming albuminates. They have little action on the epidermis, but when applied to the denuded skin, or to a mucous membrane, they precipitate the albumen, and, when used in a concentrated form, produce a slough. When swallowed, they cause the symptoms of gastro-enteritis produced by other irritant poisons, but these may be quickly succeeded by the symptoms of special mercuric poisoning from the absorption of the substance into the circulation.

The general effects on the body which are produced alike by mercury and its salts are termed **mercurialism.**

The first symptoms produced by mercury, however it is applied, are almost always connected with the alimentary canal, and more especially the **mouth**. A metallic unpleasant taste is observed in the mouth, along with a feeling of heat; the saliva is somewhat increased and the breath has a most unpleasant smell. The teeth feel sticky, as if their edges were glued together with some adhesive substance, when the patient tries to separate them; they feel as if they were longer than usual. The gums are red and swollen and tender, and chewing is painful. The tongue is covered with a thick coating, and the appetite is small. The **medicinal administration** of mercury is generally **stopped** when the gums become sore and salivation begins. In children salivation occurs with difficulty, and mercury may be discontinued when the breath becomes fœtid. When the administration of mercury is continued the symptoms increase: the gums become still more inflamed, their edges are covered with a white sticky substance, and they bleed on the slightest touch; the teeth become loosened in their sockets, and the **salivation** becomes still greater.

In still worse cases ulcers form on the gums and inside of the cheeks, the tongue itself becomes swollen so that articulation becomes difficult, mastication is so painful as to be nearly impossible, the fœtor of the breath is insupportable, and the saliva pours from the mouth in great quantities.

Along with these symptoms there is a certain amount of **fever,** which, indeed, sometimes is present before any local symptoms have appeared. There is general depression, chilliness, and even rigors, followed by a rise of temperature, a feeling of heat, thirst, loss of appetite, quick pulse, weight or pain in the epigastrium, nausea, belching, vomiting, and purging, sometimes bloody, or more rarely, constipation. These last several days and then decrease, sweating occurring at this time, or salivation if the fever has preceded it. Mercurial fever occurs most readily after a lengthened application of blue ointment.

When the administration of mercury is stopped the symptoms decrease, though in the case of broken-down individuals necrosis of the jaw and even death has occurred.

Occasionally it has happened that even healthy individuals, instead of recovering after profuse salivation, have become permanently dyspeptic.

These symptoms appear in adults, generally with great regularity, when a similar quantity of mercury has been taken in a similar time, though the effect is modified by various conditions, as age, sex, &c.

When persons are exposed for a long time to the fumes of mercury, and the metal is thus taken in in very small quantities for a lengthened period, a different effect is sometimes produced. This is called **mercurial cachexia.** In this condition the appetite is lost, the gums become livid and bleed easily, the breath is fœtid, and a tendency to diarrhœa is often present. In bad cases vomiting and purging generally occur..

The lips become pale, the complexion earthy, the person becomes emaciated, the hair sometimes falls out, the muscles become weak and small. The person is easily affected by changes of weather; there is a tendency to fainting, uneasiness, and anxiety; the pulse and respiration become quick; the pulse is also small and intermittent; and palpitation becomes very troublesome. The intellect is dull, and rheumatic pains are felt in the muscles of the extremities, more rarely in those of the trunk.

These symptoms go on increasing, and new ones also appear. **Mercurial tremors** occur in the muscles, beginning generally in the upper extremities, and gradually extending till the patient cannot execute any movement and the speech itself becomes stammering.

Mercurial paralysis of muscles or groups of muscles occasionally occurs. Generally this is confined to the muscles of the upper extremities, but sometimes affects other muscles, such as those of the larynx, causing mercurial aphonia. These paralyses generally occur in the later stages of mercurial erethism, and rarely occur before the other symptoms.

The **mental qualities** become also affected. Ill-humour, irritability, melancholy, and fear of death occur in some persons, and in others, though very rarely, idiocy, and still more rarely, furious mania. In some instances epilepsy has been observed.

Mercury in the form of organic compounds appears to have a special action on the **brain.** The symptoms are those of impairment of the special senses, sight, taste, hearing, of motor power, and of the cerebral functions. Two chemists who were engaged in the preparation of mercuric methide during three months suffered from weakness and dimness of vision, and one of them from some soreness of the gums, nausea, and vomiting. At the end of this time the symptoms became much worse, deafness and numbness came on, and were succeeded by a semi-comatose condition with great restlessness. In the one who had not previously suffered from soreness of the gums, this now appeared,

along with fœtor of the breath ; the urine was albuminous, Cheyne-Stoke's breathing was observed, the evacuations were passed involuntarily, and he died comatose a fortnight after the symptoms became severe. Sensibility was retained nearly to the last. In the other patient, impaired sensation, loss of power to direct movement, and muscular feebleness were succeeded by involuntary passage of evacuations, an idiotic condition with restlessness, and violent muscular movements, especially when he was touched. After remaining in an idiotic state for a year he died of pneumonia.

The action of mercury may be **modified** by sex, age, or idiosyncrasy. Women as a rule, are more easily affected than men, whilst children may take mercury in considerable quantities without showing any symptom of salivation. In certain persons large quantities of mercury may be administered for a length of time without producing much more effect than in children, but in others exceedingly injurious results may follow very minute doses. A case of salivation from as little as a grain and a-half of calomel has been recorded, and from one-eightieth of a grain of corrosive sublimate. In typhus it is very hard to produce salivation, but in persons suffering from Bright's disease, although mercury may be useful as a purgative it requires to be given with caution, on account of the violent effects which may follow even small doses.

Mercury combines with **albumen,** and forms albuminate of mercury, which is insoluble in water, but is easily soluble in excess of albumen or in chloride of sodium. This compound may be formed in the stomach or intestines, and a compound of mercuric oxide with albumen is probably the form under which mercury, however administered, circulates in the blood. When taken into the **stomach,** mercuric salts are powerful irritants, and, when given in large quantities, cause gastro-enteritis, vomiting, and purging. Finely divided metallic mercury and mercurous salts are less irritating, and act simply as purgatives.

A good deal of discussion has arisen regarding the action of mercury on the **liver.** It has long been ranked as a cholagogue, and there can be no question whatever, that mercury and its compounds are very beneficial in cases of so-called bilious disorder characterised by feelings of laziness and apathy, inability to think, dislike of exertion, not unfrequently combined with irritability of temper, deranged digestion, and slight yellowish tinge of the eyes. When bile was supposed to be formed in the blood, and to be only excreted by the liver, the beneficial effect of mercury was attributed to a stimulating action on the liver, whereby it increased the rapidity of the secretion, and thus removed the bile more quickly from the blood. But it was found on experiment by Dr. Scott that mercury does not increase the rapidity of the biliary secretion, and this result was confirmed by a committee of the British Medical Association, the chief members of which were Hughes Bennett, Rutherford, and Gamgee, and also by later experiments

made by Rutherford alone. As we now know that bile is formed from the liver, and not merely separated by it from the blood, we can understand that the real action of mercury as a cholagogue consists, not in its stimulating the liver to form more bile, but in removing more readily from the body the bile which is already present in excess. It appears to perform this function by stimulating the upper part of the small intestine, and thus causing the evacuation of the bile before time has been allowed for its reabsorption. For the liver does not merely form bile, it also excretes bile which has been previously formed and reabsorbed from the intestine. The bile may thus serve several times over. It is formed, passes from the liver into the duodenum, is reabsorbed and carried by the portal blood to the liver, where it is again excreted and poured out through the bile-duct a second time (p. 353). Part of it, however, is carried down the intestine, decomposed, and evacuated, and to supply the place of this a certain amount of new bile is constantly being formed, which is poured into the intestine along with the old. It is evident that any drug which acts upon the lower part of the intestine will have little power to remove the bile, as this will have undergone absorption already in the upper part of the digestive tract. But any drug acting upon the duodenum will cause the bile to be rapidly moved on and its absorption to be prevented. More especially will this be the case if the cholagogue be combined with a saline purgative, which, by causing a profuse secretion of watery fluid, will wash the bile out. This action on the upper part of the small intestine is probably possessed by mercury, and the reasons for this supposition are: (1) that it is so beneficial in bilious disorders; (2) that it does cause the appearance of bile in the stools, for Buchheim has found by analysis that the green stools which occur after purgation by calomel actually owe their colour to bile; and (3) that in the stools passed after mercurial purgatives, leucin and tyrosin, the products of pancreatic digestion have been found. Mercury acts as a **disinfectant of the intestinal contents.**

After the absorption of mercury into the **blood,** it is said, in small doses, to increase the number of blood corpuscles; in larger doses, however, it produces anæmia, but how far these results are dependent upon the improvement or disturbance of the digestion, and how far upon the action of the mercury itself upon the blood, has not been ascertained. Albuminate of mercury, when added to blood out of the body, gradually destroys the corpuscles.

Mercury appears to have the power of causing absorption of **fibrinous exudations,** for the fibrinous adhesions observed in syphilitic iritis have been seen to disappear as the patient was brought under the influence of mercury. When mercury is used for a long time, it appears to lessen greatly the force of the pulse, and large doses of mercuric preparations, when brought into contact with a frog's **heart,** will arrest its pulsations immediately.

The **respiration** is affected in persons who have been taking too much mercury, and becomes laboured and accompanied by a feeling of constriction. The **temperature** is rarely affected, excepting secondarily, in consequence of local inflammations which the mercury may excite, although sometimes mercurial fever (p. 612) precedes any marked local change.

Mercury is **excreted** by the saliva, bile, urine, sweat, and milk. The **salivation** which it produces is probably due in part to reflex excitement of the salivary glands by the irritation of the tongue, but it is no doubt also in part due to irritation of the nerves of the gland, or of the gland structure itself, by the mercury. The **urine** is said to be somewhat increased, and it is stated that the addition of a little mercury to digitalis and squill greatly increases the diuretic action of these drugs.

Hydrargyrum, Hg.; B. and U.S.P. MERCURY; 192·7.

CHARACTERS AND TESTS.—A metal, fluid at common temperatures, brilliantly lustrous, and easily divisible into spherical globules. Volatilises at a heat below that of visible redness, leaving no residue.

PREPARATIONS CONTAINING MERCURY.[1]

I.—**In the metallic state.**

Hydrargyrum, Mercury, B. and U.S.P.

Emplastrum Ammoniaci cum Hydrargyro, B. and U.S.P. Plaster of ammoniac with mercury.

Emplastrum Hydrargyri, B. and U.S.P. Plaster of mercury.

Hydrargyrum cum Creta, B. and U.S.P. Mercury with chalk.

Massa Hydrargyri, U.S.P.; Pilula Hydrargyri, B.P. Mass of mercury; mercurial pill; blue pill.

Unguentum Hydrargyri, B. and U.S.P. Mercurial ointment.

B.P. Linimentum Hydrargyri. Liniment of mercury.

B.P. Suppositoria Hydrargyri. Mercurial suppositories.

B.P. Unguentum Hydrargyri Compositum. Compound ointment of mercury.

II.—**Oxidised.**

B.P. Lotio Hydrargyri Nigra. Black mercurial lotion (mercurous oxide).

Hydrargyri Oxidum Rubrum, B. and U.S.P. Red oxide of mercury; red precipitate.

Unguentum Hydrargyri Oxidi Rubri, B. and U.S.P. Ointment of red oxide of mercury; red precipitate ointment.

Hydrargyri Oxidum Flavum, B. and U.S.P. Yellow oxide of mercury.

B.P. Lotio Hydrargyri Flava. Yellow mercurial lotion.

U.S.P. Unguentum Hydrargyri Oxidi Flavi. Ointment of yellow oxide of mercury.

U.S.P. Oleatum Hydrargyri. Oleate of mercury.

III.—**Sulphuretted.**

U.S.P. Hydrargyri Sulphidum Rubrum. Red sulphide of mercury; cinnabar.

IV.—**As Mercurous Chloride.**

Hydrargyri Chloridum Mite, U.S.P.; Hydrargyri Subchloridum, B.P. Mild chloride of mercury; mercurous chloride; calomel.

Pilulæ Antimonii Compositæ, U.S.P.; Pilula Hydrargyri Subchloridi Compositæ, B.P. Compound pills of antimony; compound pills of calomel; Plummers' pills.

U.S.P. Pilulæ Catharticæ Compositæ. Compound cathartic pills.

[1] Altered from the *United States Dispensatory*, p. 773.

PREPARATIONS CONTAINING MERCURY—(*continued*).

V.—**As Mercuric Chloride.**

Hydrargyri Chloridum Corrosivum, U.S.P.; Hydrargyri Perchloridum, B.P. Corrosive chloride of mercury; corrosive sublimate.

Hydrargyrum Ammoniatum, B. and U.S.P. Ammoniated mercury; white precipitate.

Unguentum Hydrargyri Ammoniati, B. and U.S.P. Ointment of ammoniated mercury; white precipitate ointment.

B.P. Liquor Hydrargyri Perchloridi. Solution of perchloride of mercury.

VI.—**Combined with Iodine.**

Hydrargyri Iodidum Rubrum, B. and U.S.P. Red iodide of mercury; mercuric iodide.

U.S.P. Liquor Arsenii et Hydrargyri Iodidi. Solution of iodide of arsenic and mercury; Donovan's solution.

B.P. Unguentum Hydrargyri Iodidi Rubri. Ointment of red iodide of mercury.

Hydrargyri Iodidum Viride, B. and U.S.P. Green iodide of mercury; mercurous iodide.

VII.—**Combined with Cyanogen.**

U.S.P. Hydrargyri Cyanidum. Cyanide of mercury.

VIII.—**Oxidised and combined with Acids.**

Liquor Hydrargyri Nitratis, U.S.P.; Liquor Hydrargyri Nitratis Acidus, B.P. Solution of nitrate of mercury; mercuric nitrate.

Unguentum Hydrargyri Nitratis, B. and U.S.P. Ointment of nitrate of mercury; citrine ointment.

B.P. Hydrargyri Sulphas. Sulphate of mercury; mercuric sulphate.

U.S.P. Hydrargyri Sulphas Flava. Yellow sulphate of mercury; Turpeth mineral; mercuric oxysulphate.

IMPURITIES.—Other metals.

TESTS.—The presence of other metals is ascertained by their being left behind as a residue when the mercury is volatilised. It is indicated by the formation of a grey scum or dust on the surface of the metal after exposure to air, and by the mercury forming globules which are not spherical but elongate to a tail when allowed to run over a piece of paper. They are also recognised by shaking the mercury in a perfectly dry bottle, when a grey powder will be formed if they are present.

On boiling 5 grms. of distilled water with 5 grms. of mercury and 4·5 grms. of hyposulphite of sodium in a test-tube for a minute, the mercury should not lose its lustre nor acquire more than a slightly yellowish shade (absence of more than a trace of other metals, U.S.P.).

PURIFICATION.—Other metals may be separated by distillation, or by mixing the mercury with strong sulphuric acid and letting it stand in the cold for twenty-four hours. The other metals will be converted into sulphates, but mercury is only attacked by sulphuric acid when it is aided by heat. The mercury is then washed with water to remove the sulphates, and dried with blotting-paper. Mercury is freed from dust and mechanical impurities by pressing it through chamois leather or filtering it through a paper filter in the apex of which several small holes have been made with a needle or pin.

USES.—Metallic mercury in mass has no action whatever on the body. As much as a pound has been taken without producing any

physiological effect. Such a dose as this is sometimes given in cases of intestinal obstruction in the hope that the weight of the mercury may carry the obstruction before it. The theory of its action formerly held was purely mechanical: that the mercury passed from the stomach to the intestines and meeting with the obstruction drove it on, but latterly Traube has supposed that the mercury remains chiefly in the stomach, and by pulling on it excites the intestines reflexly to peristaltic action. Whatever the correct theory may be, however, it is certain that the mercury does not always stay in the stomach but does get down into the intestine, and consequently some precautions must be observed in its administration, and it is never given except when all other measures fail. The precautions are not to give it in cases of intussusception, as it may very probably render this worse; nor in cases where the intestine is considerably inflamed, as the tissues being weak are then easily torn; nor in hernia, as better means, viz., external means, can be employed.

Hydrargyrum cum Creta, B. and U.S.P. MERCURY WITH CHALK.

PREPARATIONS.—By rubbing up chalk (2) and mercury (1) together, B.P. By rubbing up mercury (38), chalk (50), and sugar of milk (12) together, moistening them with a mixture of equal parts of ether and alcohol, U.S.P.

CHARACTERS AND TESTS.—A powder of light-grey colour; free from grittiness; insoluble in water; partly dissolved by diluted hydrochloric acid, leaving the mercury in a finely divided state.

IMPURITY.—Mercuric oxide.

TEST.—The solution formed with hydrochloric acid is not precipitated by the addition of chloride of tin.

DOSE.—3 to 8 grains.

USES.—It has been much recommended by Ringer as a remedy in many diseases both of adults and of children. In simple tonsillitis, or the inflamed throat of scarlatina, or in mumps, he recommends a third of a grain every hour, and the same dose three or four times a day will, he says, clean the tongue, remove the disagreeable taste from the mouth, and improve appetite and digestion in the dyspepsia occurring in chronic disease or of commencing convalescence. A similar dose will cut short an attack of jaundice, with vomiting and pale stools, occurring in nervous persons after exposure to cold, fatigue, or excitement; and half a grain thrice a day will restore the colour to the stools and remove the dyspepsia in patients suffering from acidity, flatulence, and vomiting in the morning. Diarrhœa in children, accompanied by pale, offensive motions, or by muddy, or green-coloured, or curdy stools, whether accompanied by sickness or not, is successfully treated by similar doses of this remedy. It may also be used to produce the general action of mercury combined with opium or Dover's powder

Pilula Hydrargyri, B.P. MERCURIAL PILL; BLUE PILL.—Contains mercury (2), confection of roses (3), powdered liquorice root (1). 3 grs. contain 1 of mercury.

DOSE.—3 to 8 grains

USES.—Blue pill may be given either for its **local** action upon the intestines or to produce the action of mercury upon the system. This pill is one of the most effectual remedies for the condition usually termed biliousness. The patient complains of feeling dull, heavy, and often sleepy, suffers from occasional headache, has little appetite, and occasionally feels sick. The complexion is often of a dirty yellow, muddy colour, and the white of the eyes likewise. The use of blue pill in such conditions was recommended by Mr. Abernethy. Five grains of blue pill are given overnight and a draught of salts and senna in the morning. This is very effective, but the disadvantage of it is said to be that the bilious state is more apt to return, and that when a patient has once become habituated to the use of mercurials no other medicine will do instead.

It is one of the best preparations for producing **mercurialism**: 5 grains. with $\frac{1}{2}$ a grain of opium are given in the morning, and 5 or 10 also with $\frac{1}{2}$ a grain of opium in the evening.

The addition of a small quantity of blue pill to digitalis and squill sometimes increases their efficacy in cases of cardiac disease.

B.P. Suppositoria Hydrargyri. MERCURIAL SUPPOSITORIES.—Each contains 60 grs. of ointment of mercury, benzoated lard and white wax each 20 grs., oil of theobroma 80 grs.

USES.—They are employed where we wish to produce mercurial action without the risk of interfering with the digestion.

Unguentum Hydrargyri, B. and U.S.P. OINTMENT OF MERCURY, B.P.; MERCURIAL OINTMENT, U.S.P.—Contains 1 lb. each of mercury and prepared lard. As this would be too soft, 1 oz. of prepared suet is added.

PREPARATIONS.—Linimentum Hydrargyri; Suppositoria Hydrargyri; Unguentum Hydrargyri Compositum.

USES.—It may be used either for its general or its local action. When employed to produce the **general action** of mercury in the system, it is rubbed into some part of the body where the skin is thin, as the armpits or the sides of the thighs. If it is rubbed in by another person, and not by the patient himself, it is advisable to protect the operator's hand by a piece of bladder soaked in oil, in order to prevent absorption through the palm. In cases of congenital syphilis, the mercurial ointment may be put upon a flannel roller, and bound round the child's belly.

It has been applied **locally** in inflammation of the skin, as erysipelas; of the veins in phlegmasia dolens; or of the genital organs, as in ovaritis, orchitis, and indurated testicles.

B.P. Unguentum Hydrargyri Compositum. COMPOUND OINTMENT OF MERCURY.—Contains mercurial ointment (6), yellow wax (3), olive-oil (3), and camphor ($1\frac{1}{2}$).

The compound ointment is used to cause absorption of effusion or thickening around joints in cases of disease or injury after the inflammation has subsided. It ought to be combined with pressure and rest.

Emplastrum Hydrargyri, B. and U.S.P. MERCURIAL PLASTER.

PREPARATION.—Rub mercury with olive-oil, and sulphur B.P. or resin U.S.P., and add lead plaster to give it consistency. Sulphur and resin are used to extinguish the globules of mercury, *i.e.* make them so small as to be invisible.

Emplastrum Ammoniaci cum Hydrargyro, B. and U.S.P. AMMONIACUM AND MERCURY PLASTER, B.P.; AMMONIAC PLASTER WITH MERCURY, U.S.P.

PREPARATION.—B.P. By rubbing mercury 3 oz. with warm olive oil 1 fl. dr., and sulphur 8 grs. until the globules of mercury are no longer visible, then adding melted ammoniacum 12 oz. and mixing. U.S.P. Mercury 180 is extinguished with sulphur 1 and olive oil 8 as in the B.P. process. Ammoniacum 720 is digested with diluted acetic acid 1,000, strained, evaporated until it hardens on cooling. It is then added while hot to the mercury and mixed. Then enough lead plaster previously melted is added to make up to 1,000 parts.

Both plasters are used to promote the absorption of glandular enlargements, buboes, nodes, and are applied over the liver in chronic enlargement and induration.

B.P. Linimentum Hydrargyri. LINIMENT OF MERCURY.—Contains equal parts of mercurial ointment, solution of ammonia, and camphor liniment.

Used for similar purposes as the plaster or ointment. It is more irritating than either on account of the ammonia it contains.

It is said to cause salivation more readily than mercurial ointment, as the camphor and ammonia with which it is mixed assist its absorption.

B.P. Hydrargyri Sulphas. SULPHATE OF MERCURY. $HgSO_4$.

PREPARATION.—Heat mercury 20 oz. with sulphuric acid 12 fl. oz. in a porcelain vessel, stirring constantly until the metal disappears, then continue the heat until a dry white salt remains.

CHARACTERS.—A white crystalline heavy powder, rendered yellow by affusion of water. Entirely volatilised by heat; sub-sulphate formed by water.

PREPARATIONS IN WHICH SULPHATE OF MERCURY IS USED.

Hydrargyri Perchloridum. Hydrargyri Subchloridum.

U.S.P. Hydrargyri Subsulphas Flavus. YELLOW SUB-SULPHATE OF MERCURY. $Hg(HgO)_2SO_4$; 727·1.

CHARACTERS.—A heavy lemon-yellow powder, permanent in the air, odourless and almost tasteless, insoluble in water or in alcohol, but soluble in nitric or hydrochloric acid. When heated the salt turns red, becoming yellow again on cooling. At a red heat it is volatilised without residue, evolving vapours of mercury and of sulphurous acid.

TESTS.—As it is a mercuric oxysulphate, it should be soluble in 20 parts of hydrochloric acid without residue (no mercurous salt).

USES.—The yellow oxysulphate has been used under the name of Turpeth mineral as an errhine in chronic ophthalmia. It is a prompt emetic, and is sometimes preferred to other emetics in croup, as it is quick and certain, and does not produce depression nor purging. The dose for a child two years old is 2-5 grains (0·13-0·33 Gm.), repeated in fifteen minutes if necessary. It may also be used as an alterative.

Hydrargyri Subchloridum, B.P.; Hydrargyri Chloridum mite, U.S.P. SUBCHLORIDE OF MERCURY, B.P.; MILD CHLORIDE OF MERCURY, U.S.P. CALOMEL. Hg_2Cl_2; 470·2.

PREPARATION.—Calomel is prepared by rubbing up mercury with sulphate of mercury moistened with water till globules are no longer visible, adding sodium chloride, mixing the whole by trituration, and subliming the mixture into a large chamber.

The mercury and mercuric sulphate form mercurous sulphate, and this, with sodium chloride, forms calomel and sulphate of soda, $HgSO_4 + Hg + 2NaCl = 2HgCl + Na_2SO_4$.

When the calomel is sublimed into a small receiver it forms a thin crystalline crust which adheres to the sides, but when sublimed into a large chamber, as directed in the B.P., it falls as a powder on the floor. As some corrosive sublimate is often formed, the powdered calomel is washed with water till all the sublimate is removed, as shown by the water no longer giving a precipitate with ammonium sulphide.

It is then dried under 212°, and kept in a well stoppered and dark bottle.

CHARACTERS.—A dull-white heavy and nearly tasteless powder, rendered yellowish by trituration in a mortar; insoluble in water, spirit, or ether. It is very heavy, and can be distinguished by its weight from almost every other white powder. Its weight is noticed more distinctly by giving the bottle an up-and-down shake. Digested with solution of potash it becomes black (mercurous oxide); and the clear solution, acidulated with nitric acid, gives a copious white precipitate with nitrate of silver (chloride). Contact with hydrocyanic acid also darkens its colour.

ADULTERATIONS.—Chalk, sulphate of lime, sulphate of baryta, carbonate of lead, corrosive sublimate.

TESTS.—It is entirely volatilised by a sufficient heat (no earthy impurities). Warm ether which has been shaken with it in a bottle leaves, on evaporation, no residue (no corrosive sublimate).

DOSE.—$\frac{1}{2}$ grain to 5 grains.

PREPARATIONS IN WHICH SUBCHLORIDE OF MERCURY IS USED.

B.P.

Lotio Hydrargyri Nigra	3 grains to 1 fluid ounce.
Pilula Hydrargyri Subchloridi Composita	1 part in 5.
Unguentum Hydrargyri Subchloridi, Calomel Ointment (with prepared lard)	1 part in $6\frac{1}{2}$, nearly.

U.S.P.

Pilulæ Antimonii compositæ.
Pilulæ Catharticæ compositæ.

Pilula Hydrargyri Subchloridi Composita, B.P.; Pilulæ Antimonii Compositæ, U.S.P. COMPOUND PILL OF SUBCHLORIDE OF MERCURY, B.P.; COMPOUND PILLS OF ANTIMONY, U.S.P. COMPOUND CALOMEL PILL. PLUMMER'S PILL.—Contains subchloride of mercury (1), sulphurated antimony (1), guaiacum resin, in powder (2), made up with castor-oil, B.P. Sulphurated antimony (50), mild chloride of mercury (5), guaiac (100), mucilage of tragacanth (q.s.), U.S P.

DOSE.—5 to 10 grains.

USES.—Calomel may be employed as a dusting powder to remove condylomata from the skin, and condylomatous patches from the tongue, throat, and larynx. As an ointment it may be applied to relieve the itching in pruritus ani, and pityriasis of the scalp, and to heal strumous sores and lupus in children. Internally it may be given in cases of biliousness, and followed by a saline purgative in the same manner as is recommended under "Blue Pill." In some cases of diarrhœa it is very useful in combination with opium (p. 85).

It may also be used to produce the general action of mercury in syphilitic patients, and for this purpose may either be given internally, in combination with opium, or applied to the skin in the form of calomel fumigations (p. 414).

Calomel ointment is useful in allaying the itching of many skin affections. In pruritus ani and pruritus scroti it often removes the itching at once. In pruritus pudendi it is also of service, though not quite so much as in the other cases (Ringer). It should not be applied in large quantities, lest so much of it be absorbed as to cause its physiological action.

Lotio Hydrargyri Nigra, B.P. BLACK MERCURIAL LOTION. BLACK WASH.—Consists of half a drachm of calomel mixed with half a pint of lime-water.

USES.—It contains suboxide of mercury. It is a good application to varicose ulcers, and is used as an application to syphilitic ulcerations, as a wash to the mouth in syphilitic sore throat, and in cancrum oris. The compound pill of subchloride of mercury may be used in cases of biliousness, gout, or rheumatism.

Hydrargyri Perchloridum, B.P.; Hydrargyri Chloridum Corrosivum, U.S.P. PERCHLORIDE OF MERCURY, B.P.; CORROSIVE CHLORIDE OF MERCURY, U.S.P. $HgCl_2$; 270·5.

PREPARATION.—By mixing mercuric sulphate with sodium chloride and subliming into a small chamber. To prevent the formation of any calomel some peroxide of manganese is added.

CHARACTERS AND TESTS.—In heavy colourless masses of prismatic crystals, possessing a highly acrid metallic taste; more soluble in alcohol, and still more so in ether, than in water. Its aqueous solution gives the reactions of mercuric salts and of a chloride.

DOSE.—$\frac{1}{16}$ to $\frac{1}{8}$ grain. In cholera this dose may be given every quarter of an hour, half-hour, or hour.

OFFICINAL PREPARATION.

B.P.	U.S.P.
Liquor Hydrargyri Perchloridi.	None.

B.P. Liquor Hydrargyri Perchloridi. SOLUTION OF PERCHLORIDE OF MERCURY.—Contains $\frac{1}{2}$ grain of perchloride of mercury in 1 oz. of water, with 1 grain of ammonium chloride to keep it in solution and prevent precipitation.

DOSE.—$\frac{1}{2}$ fluid drachm to 2 fluid drachms.

USES.—When mixed with **albumen**, corrosive sublimate precipitates it, forming a mercuric albuminate. It is one of the most powerful **antiseptics** known (p. 73). It may be applied to the skin to destroy vegetable and animal parasites present upon it, such as the fungus in pityriasis versicolor, sycosis and favus, the acarus in scabies and the pediculus pubis. It is useful in allaying the itching of pruritus scroti and pudendi, prurigo, and urticaria. It may be employed as a wash in ophthalmia, as a gargle in syphilitic sore throat, and as an injection in gonorrhœa, gleet, and leucorrhœa. When swallowed in strong solution it sometimes causes an irritant **poisoning**; and if this should pass off, it may be succeeded by intense salivation due to the absorption of the drug. The treatment in such cases is to give albuminous substances, such as white of egg or milk, in order to form mercuric albuminate in the stomach, and thus prevent its irritant action on the mucous membrane. If the irritation which the drug itself produces is not sufficient to cause vomiting, the stomach should be emptied by an emetic or a stomach-pump, in order to prevent digestion and absorption of the mercuric albuminate and the poisoning which might occur from its absorption. In small doses it is useful in dysenteric diarrhœa of adults or children and in cholera, its utility probably depending, to a great extent at least, on its antiseptic power, which is not destroyed, like that of other antiseptics, by considerable admixture with organic matter, such as the fæcal contents of the intestine (p. 85). After its absorption it has the same effect as the other salts of mercury, and may be used for this purpose in syphilitic cases.

B.P. Lotio Hardrargyri Flava. YELLOW WASH.

PREPARATION.—By mixing 18 grs. of corrosive sublimate with half a pint of lime-water.

USES.—It is used as a stimulating application to syphilitic sores in cases where the black wash is not sufficiently powerful.

Hydrargyri Oxidum Flavum, B. and U.S.P. YELLOW OXIDE OF MERCURY. HgO; 215·7.

CHARACTERS.—A light orange-yellow, heavy, impalpable powder, permanent in the air, and turning darker on exposure to light; odourless and tasteless, insoluble in water or alcohol, but wholly soluble in nitric or hydrochloric acid. When strongly heated it assumes a red colour; at a higher temperature it is decomposed, giving off oxygen and separating metallic mercury, and is finally volatilised without residue. When digested on a warm bath for fifteen minutes with a strong solution of oxalic acid, it forms mercuric oxalate of a white colour (difference from red mercuric oxide).

PREPARATIONS.

U.S.P.

Oleatum Hydrargyri (yellow oxide 10, oleic acid 90, parts).
Unguentum Hydrargyri Oxidi Flavi (1 in 10 of Unguentum).

Hydrargyri Oxidum Rubrum, B. and U.S.P. RED OXIDE OF MERCURY. HgO; 215·7.

PREPARATION.—Triturate nitrate of mercury and metallic mercury together and heat. $Hg2NO_3 + Hg = 2HgO + N_2O_4$.

CHARACTERS.—An orange-red powder readily dissolved by hydrochloric acid, yielding a solution which, with caustic potash added in excess, gives a yellow precipitate, and with solution of ammonia a white precipitate.

IMPURITY.—Undecomposed nitrate.

TEST.—Entirely volatilised by a heat under redness, being at the same time decomposed into mercury and oxygen. If this be done in a test-tube, no orange vapours are perceived.

PREPARATIONS.

B. AND U.S.P.

Unguentum Hydrargyri Oxidi Rubri (Ointment of Red Oxide of Mercury).... } 1 part in 8, B.P.; 1 in 10, U.S.P.
With yellow wax and olive oil, B.P.; with ointment, U.S.P.

USES.—The red oxide is rarely given internally. The ointment may be used in ophthalmia and conjunctivitis in the same way as the nitrate of mercurial ointment, and as an application to the auditory meatus in otorrhœa occurring after scarlet fever. It is also useful in scaly skin diseases, syphilitic sores on the skin, and in ulcers within the margin of the anus.

Hydrargyrum Ammoniatum, B. and U.S.P. AMMONIATED MERCURY. WHITE PRECIPITATE. NH_2HgCl; 251·1.

PREPARATION.—By dissolving corrosive sublimate in water, and precipitating by ammonia.

CHARACTERS. — An opaque white powder on which cold water, alcohol, and ether have no action. Digested with caustic potash, it evolves ammonia, acquiring a pale yellow colour, and the fluid, filtered and acidulated with nitric acid, gives a white precipitate with nitrate of silver. Boiled with a solution of chloride of tin it becomes grey, and affords globules of metallic mercury.

IMPURITIES.—Chalk, sulphate of lime, baryta, lead, carbonates, mercurous salts.

TESTS.—Entirely volatilised at a heat under redness (no chalk, etc.). It should dissolve in hydrochloric acid without residue (no mercurous salt) and without effervescence (no carbonate).

PREPARATION.

B. AND U.S.P.

Unguentum Hydrargyri Ammoniati ...1 part in 8, B.P.; 1 in 10, U.S.P.
With simple ointment, B.P.; with benzoated lard, U.S.P.

USES.—Not used internally. The ointment is used in order to destroy parasitic fungi, but more especially to kill pediculi in the hair or on the body. It is also useful in lichen, pityriasis, herpes, and other skin diseases.

Liquor Hydrargyri Nitratis Acidus, B. and U.S.P. ACID SOLUTION OF NITRATE OF MERCURY. $(HgNO_3)_2$; 327·7.

CHARACTERS AND TESTS.—A colourless and strongly acid solution, which gives a yellow precipitate with solution of potash added in excess (mercuric oxide). If a crystal of sulphate of iron be dropped into it, in a little time the salt of iron, and the liquid in its vicinity, acquire a dark colour (nitrate).

USES.—It is a powerful caustic, and is used as such in lupus. It is to be applied with a camel's-hair brush to the extent of a crown piece over the ulcers, tubercles, and scars which are soft and ready to break. The part is then covered with lint moistened in the solution. It soon becomes white, a kind of erysipelatous inflammation sets in around it, and it falls off as a yellow scab. The solution is also applied to the os uteri when there are large ulcers with flabby, unhealthy granulations upon it. It has been used in cancer and in chancres, condylomata, syphilitic and scrofulous ulcers, favus, and obstinate psoriasis. If applied often it may cause mercurialism, and indeed salivation has occurred after one application to the os uteri. To prevent this it should be washed off immediately after being applied.

Unguentum Hydrargyri Nitratis, B. and U.S.P. OINTMENT OF NITRATE OF MERCURY. CITRINE OINTMENT.

PREPARATION.—By mixing a hot solution of mercury in nitric acid with lard and olive-oil, B.P.; or with lard-oil, U.S.P.

CHARACTERS.—It has a fine lemon-yellow colour and a consistence like butter. It is apt to become decolorised when mixed with metals or deoxidising powders, and hence an excess of acid is used in order that it may reoxidise them as necessary. It should be spread with a wooden or ivory spatula.

USES.—This ointment was made in imitation of Singleton's golden eye ointment, and it is of remarkable service in ophthalmia tarsi. It should be mixed with its own weight of almond-oil and applied to the lids.

It is also applied to phagedenic ulcers and syphilitic sores, and soon destroys the parasitic fungi on which ringworm, &c., depend.

Hydrargyri Iodidum Viride, B. and U.S.P. GREEN IODIDE OF MERCURY. Hg_2I_2: 652·6.

PREPARATION.—By rubbing iodine and mercury together in a porcelain mortar, occasionally moistening with a few drops of spirit.

CHARACTERS AND TESTS.—A dull green powder, insoluble in water, which darkens in colour upon exposure to light. When it is shaken in a tube with ether nothing is dissolved. Gradually heated in a test-tube, it yields a yellow sublimate, which, upon friction, or after cooling, becomes red, while globules of metallic mercury are left in the bottom of the tube.

DOSE.—1 to 3 grains.

USES.—It is employed for the purpose of combining the action

of iodine with that of mercury, as in cases of secondary and tertiary syphilis occurring in persons of a scrofulous constitution, and especially in the syphilis of children.

Hydrargyri Iodidum Rubrum, B. and U.S.P. RED IODIDE OF MERCURY.

PREPARATION.—By mixing solutions of corrosive sublimate with potassium iodide in the proper proportions.

CHARACTERS AND TESTS.—A crystalline powder of a vermilion colour, becoming yellow from an alteration in its crystalline form when gently heated over a lamp on a sheet of paper, and again becoming red when placed on a sheet of paper and rubbed with a smooth substance. It is almost insoluble in water, dissolves sparingly in alcohol, but freely in ether, or in an aqueous solution of iodide of potassium. When digested with solution of soda it assumes a reddish-brown colour (mercuric oxide); and the fluid cleared by filtration and mixed with solution of starch, gives a blue precipitate on being acidulated with nitric acid (iodide). Entirely volatilised by a heat under redness.

DOSE.—$\frac{1}{16}$ to $\frac{1}{4}$ grain.

PREPARATION. B.P., NOT IN U.S.P.

Unguentum Hydrargyri Iodidi Rubri (Ointment of Red Iodide of Mercury).... With yellow wax and almond oil.	1 part in 28.

USES.—It may be used for the same purposes as the green iodide, but, like all the mercuric salts, it is much more powerful than the corresponding mercurous one. It is a powerful local irritant, and is used in the form of ointment in cases of goître. The mode of employing it is to rub the ointment upon the tumour, and afterwards to expose the patient either to the heat of the sun or of a fire as long as he can bear it. This iodide was first used in India. In this country, where the sun's rays are not so powerful, the heat of a fire has been employed, but has not been found so efficacious.

It is useful in obstinate skin diseases, especially lupus. It is frequently given in syphilis, one of the most common ways of prescribing it being to give $\frac{1}{2}$-1 drachm of the solution of the perchloride with several grains of potassium iodide. The periodide is thus formed, and is dissolved in excess of the potassium iodide.

U.S.P. Hydrargyri Cyanidum. CYANIDE OF MERCURY. $Hg(CN)_2$; 251·7.

CHARACTERS.—Colourless or white prismatic crystals, becoming dark-coloured on exposure to light; odourless, having a bitter metallic taste, and a neutral reaction. When slowly heated the salt decomposes into metallic mercury and cyanogen gas, which is inflammable, burning with a purplish flame. On further heating, the blackish residue containing globules of metallic mercury is

wholly dissipated. On adding hydrochloric acid to the aqueous solution, hydrocyanic acid vapour is evolved.

TESTS.—A 5 per cent. aqueous solution of the salt, when mixed with a dilute aqueous solution of iodide of potassium, should not yield a red or reddish precipitate soluble in excess of either liquid (absence of mercuric chloride).

DOSE.—$\frac{1}{16}$ to $\frac{1}{8}$ grain.

USES.—It may be given in syphilis. A solution of 5-10 grains in an ounce of water, painted on with a camel's-hair brush, is a useful application to syphilitic sores of the tongue or mouth.

U.S.P. Hydrargyri Sulphidum Rubrum. RED SULPHIDE OF MERCURY. HgS; 231·7.

CHARACTERS.—Brilliant dark-red crystalline masses, or a fine bright scarlet powder, permanent in the air, odourless and tasteless, insoluble in water, alcohol, nitric or hydrochloric acid, or in dilute solutions of alkalies. It is dissolved by nitrohydrochloric acid, and on adding an excess of stannous chloride, metallic mercury is precipitated.

USES.—It is used for mercurial fumigation. Thirty grains may be used instead of calomel in the way already described (p. 414).

CLASS IV.

TETRAD METALS.

LEAD. *Titanium.* TIN.

GENERAL ACTIONS.—Lead and tin resemble one another to a considerable extent in their physiological action. After absorption into the circulation lead affects the muscles, involuntary and voluntary, and the central nervous system. Its action on muscle appears to be first irritant then paralysing. The irritant action on the muscle of the intestine leads to colic, and on the voluntary muscle to cramps in man. In animals, when the quantity administered in experiments at one time is much larger, paralysing action is more marked, and in frogs and rabbits, muscular weakness and rapid loss of irritability both in the voluntary muscles and heart are marked symptoms. In cats the paralysis of voluntary muscle is less marked, and in dogs it is absent.

The motor areas of the central nervous system appears to be much more affected by lead than the sensory; and in dogs, cats, and pigeons choreic movements and even convulsions occur without impairment of sensation or consciousness. The irritation of the motor centres is succeeded by paralysis and death.

Tin has an action resembling lead in increasing the contractions of the intestinal canal and causing paralysis of the spinal cord. In rabbits it produces weakness and apparent recovery, and then paresis and death.[1]

[1] T. P. White, *Archiv f. exp. Path. u. Pharm.* 1880, viii. p. 33.

LEAD. Pb.; 207.

GENERAL SOURCE OF LEAD SALTS.—Lead is obtained entirely from the native sulphide called galena by roasting.

GENERAL REACTIONS.—The chief reactions of lead salts are shown in the following table:—

Reagent.	Reaction.
Hydrogen sulphide..... } Ammonium sulphide..... }	Black precipitate.
Caustic potash or soda.....	White ,, soluble in excess.
Ammonia.....	,, ,, insoluble ,,
Carbonates of potash, soda, or ammonia	,, ,, ,, ,,
Sulphuric acid or sulphates	,, ,, ,, in nitric acid.
Potassium iodide	Yellow ,, ,,

GENERAL IMPURITIES.—Alkaline earths, zinc or copper.

GENERAL TESTS.—As alkaline earths and zinc are not precipitated by sulphuretted hydrogen, they can be detected by passing this gas through the solution of a lead salt until all the lead has been precipitated as sulphide. On removing the sulphide by filtration, and evaporating the filtrate to dryness, no residue should remain if the lead be pure, U.S.P.

Copper may be detected by precipitating the lead from a solution by sulphuric acid, filtering, and super-saturating with ammonia. If copper be present, the solution will exhibit a blue colour, U.S.P. Insoluble salts, as the oxide, may be dissolved in dilute nitric acid super-saturated with ammonia. The filtrate should show no blue colour.

ACTION.—Soluble lead salts unite with **albumen,** and form albuminate of lead. They have little or no irritating action when applied directly to the denuded **skin** or to a mucous membrane. In the mouth they have an astringent action, but a sweet instead of corrosive taste. In large doses in the **stomach** they may excite vomiting and may produce symptoms of irritant poisoning. In the **intestine** they act as powerful astringents. After absorption into the blood lead is carried by the blood to all parts of the body, and there becomes deposited. It appears to be eliminated very slowly, so that when even very minute quantities are taken continuously chronic lead poisoning may be produced.

One of the most important **sources of lead poisoning** of this sort is drinking water. Soft water attacks the leaden pipes in which it may be conveyed, or the cisterns in which it may be stored, and dissolves enough lead to cause lead poisoning, the small quantity of one grain per gallon appearing to be sufficient. Hard waters are not injurious, as they cause a coating of phosphate or sulphide of lead

to form on the surface of the pipe or cistern, and thus protect it from further attacks. Other sources of lead poisoning, are beer which has stood in the pipes leading to the tap, and snuff, from the decomposition of the lead foil which surrounds it. There are certain trades the workers in which are very liable to lead poisoning, such as colour grinding, painting, plumbing, type founding, and printing (compositors.) The chief source of poisoning in these trades is the lead which adheres to the hands and is swallowed along with the food, and the precautions to be adopted are cleanliness, washing the hands carefully before taking meals, taking the food in a different room from that in which the work is carried on, changing the clothes when the work is over, and, if necessary, drinking water acidulated with sulphuric acid.

Treatment of chronic lead poisoning consists in eliminating the poison, first from the tissues and then from the body. Various means have been employed, such as sulphur baths, the internal administration of sulphur, frequent doses of castor oil. As the lead is eliminated by the skin and mucous membrane, sulphur, applied either to the skin or taken internally, will convert it into an insoluble sulphide and prevent its re-absorption. Castor oil will remove from the intestinal canal the lead excreted into it. But the treatment which I employ, and which I find very satisfactory, is to combine the use of iodide of potassium with that of sulphate of magnesia, giving from five to ten grains of the iodide three times a day, and a drachm of the sulphate also three times a day, with an interval of about two hours between the medicines. The object of this treatment is (1) to dissolve the lead deposited in the tissues, and to cause its elimination by the mucus of the alimentary canal, and (2) to render the lead insoluble after it has passed into the intestine, and to remove it thence as quickly as possible.

The **symptoms of chronic lead poisoning** are a blue line on the gums, lead colic, lead cramps, and lead paralysis. The **blue line** on the gums may appear when neither the colic, cramps, nor paralysis are present. It appears to be produced by sulphuretted hydrogen in the mouth precipitating the lead as black sulphide in the gums just at the margin of the teeth, and this, shining through the tissue above it, appears of a bluish colour. It is absent when the teeth have been lost, and slight if they are kept clean.

The **lead colic** may either be preceded by symptoms of digestive derangement, such as loss of appetite, or may appear at once. It is characterised by a tearing pain referred chiefly to the region of the umbilicus, and generally accompanied by obstinate constipation. It is usually, though not always, relieved by pressure, but may sometimes be somewhat increased by it.

Lead cramps are almost entirely confined to the flexor surfaces specially marked in the calves of the legs, and are usually worse

at a change of weather. They may either accompany or succeed the colic.

Lead paralyses are usually confined to the extensor surfaces, and more particularly affect the extensors of the wrist, so that this form of paralysis is sometimes known as **wrist-drop.** The affected muscles become atrophied, and, as the extensor tendons also act as ligaments of the wrist, the bones of the carpus may become displaced. The paralysis probably depends on an affection of the spinal cord rather than of the muscles themselves; for the muscles are affected in physiological groups which act together, although supplied by different nerves, and the degeneration of the muscle does not occur until after the paralysis has set in for some time.

Lead appears to cause contraction of the muscular walls of the arteries, and to raise the arterial tension and to slow the heart. It has been supposed that this action depended on a local astringent effect upon muscular fibre itself, but as in cases of chronic poison the proportion of lead in the nervous system is much greater than in muscular fibre, it is more probable that these effects are of nervous origin. The contraction of the intestine which gives rise to the colic is probably due more to the action of the lead upon the nerves of the intestine than upon its muscular coats.

Lead is **eliminated,** to a slight extent, in the urine, and probably largely by the mucus of the intestinal canal. It appears to check the elimination of uric acid, and in London gout occurs very frequently among patients who work in lead.

Lead salts may be administered in medicinal doses for a considerable time without bringing on any sign of lead poisoning; but Garrod has observed, and I can confirm the statement, that the administration of medicinal doses of lead salts will bring on a fit of gout in persons predisposed to it. Lead poisoning appears to occur readily in gouty subjects. Chronic lead poisoning has a tendency to induce cirrhotic changes in the kidneys, the tubules becoming blocked by plugs of lead carbonate and atrophy ensuing.

USES.—Lead lotions are sometimes applied externally to sprains and bruises. They are useful in relieving the itching of pruritus, and the discomfort and in lessening the discharge of eczema. As injections they may be applied in otorrhœa, vulvitis in children, gonorrhœa, and leucorrhœa. They are not used in ulceration of the cornea, lest lead should be deposited in the ulcer and leave a permanent opacity. Internally, lead is used for its local action on the stomach in pyrosis, and on the intestine in diarrhœa and dysentery, and for its astringent action on the vessels in hæmatemesis, hæmoptysis, and bleeding from the kidneys and uterus. It has also been employed in palpitation from hypertrophied heart, and in aortic aneurism.

Plumbi Oxidum, B. and U.S.P. OXIDE OF LEAD. PbO; 222·5.
PREPARATION.—By roasting lead in a current of air.

CHARACTERS AND TESTS.—In heavy scales of a pale brick-red colour, completely soluble without effervescence in diluted nitric and acetic acids, either solution, when neutral, giving the reactions of lead. It should contain no copper.

PREPARATIONS IN WHICH OXIDE OF LEAD IS USED.

Emplastrum Cerati Saponis.	Liquor Plumbi Subacetatis
,, Plumbi.	Plumbi Acetas.

Emplastrum Plumbi, B. and U.S.P. LEAD PLASTER.

PREPARATION.—By heating oxide of lead with olive oil and water. The oleic acid of the oil combines with the lead, forming oleate of lead and leaving glycerine. This plaster is a lead soap.

PREPARATIONS.

B.P.	U.S.P.
Emplastrum Ferri.	Emplastrum Ammoniaci cum Hydrargyro.
,, Galbani.	,, Asafœtidæ.
,, Hydrargyri.	,, Ferri.
,, Resinæ.	,, Galbani.
,, Saponis.	,, Hydrargyri.
	,, Opii.
	,, Resinæ.
	,, Saponis.
	Unguentum Diachylon.
	And several other plasters into which it enters as resin plaster.

USES.—Lead plaster is used to hold together the edges of wounds, to protect irritable surfaces, either alone or by keeping other dressings in contact with them by means of its adhesive power. It is also used as a means of applying pressure.

Plumbi Carbonas, B. and U.S.P. CARBONATE OF LEAD. $(PbCO_3)_2Pb(HO)_2$; 773·5.

PREPARATION.—By exposing lead to the fumes of vinegar and to CO_2.

CHARACTERS AND TESTS.—A soft, heavy, white powder, blackened by sulphuretted hydrogen, insoluble in water, soluble with effervescence in diluted acetic acid without leaving any residue, and forming a solution, which gives the reaction of lead.

IMPURITY.—Lime.

TEST.—The acetic solution when treated with excess of sulphuretted hydrogen, boiled and filtered, gives no precipitate with oxalate of ammonia.

PREPARATION.

B. AND U.S.P.

Unguentum Plumbi Carbonatis.....1 part in 8, B.P.; 1 in 10, U.S P.
With simple ointment, B.P.; with benzoated lard, U.S.P.

USES.—Carbonate of lead is used as an application to excoriated surfaces, piles, boils, and ulcers.

The ointment is used in the same way.

Plumbi Acetas, B. and U.S.P. ACETATE OF LEAD. $Pb(C_2H_3O_2)_2 3H_2O$; 378·5. (Sugar of Lead.)

PREPARATION.—By dissolving oxide of lead in acetic acid.

CHARACTERS AND TESTS.—In white crystalline masses, slightly efflorescent, having an acetous odour, and a sweet astringent taste. Its solution in water slightly reddens litmus, and gives the reactions of lead and of an acetate.

IMPURITY.—Slight amount of carbonate.

TEST.—Its solution in distilled water is clear, or has only a slight milkiness, which disappears on the addition of acetic acid.

DOSE.—1 to 4 grains.

PREPARATIONS IN WHICH ACETATE OF LEAD IS USED.

B.P.	U.S.P.
Liquor Plumbi Subacetatis.....5 ounces to 1 pint.	Liquor Plumbi Subacetatis.
Pilula Plumbi cum Opio.....36 parts in 48.	
Suppositoria Plumbi Composita....6 parts in 30.	
Unguentum Plumbi Acetatis.....1 part in 38.	

USES.—The acetate is the preparation of lead most frequently used as a local application in inflammations, ulcers, ophthalmia and gonorrhœa, or for its general actions on the system.

B.P. Pilula Plumbi cum Opio. PILL OF LEAD AND OPIUM.—Contains 6 grains of lead acetate, 1 of opium, and 1 of confection of roses in every 8 grains of the pill.

DOSE.—3 to 5 grains.

USES.—It is a powerful astringent, used either for the purpose of obtaining the local astringent action of lead upon the bowels in diarrhœa, or for its general effect upon the system after absorption, as in hæmoptysis.

B.P. Suppositoria Plumbi Composita. COMPOUND LEAD SUPPOSITORIES.—Each suppository contains 1 grain of opium and 3 grains of acetate of lead.

USES.—Used in piles and dysentery accompanied by much tenesmus, or in phthisis, where we wish to stop hæmoptysis without putting lead or opium into the stomach and thus running the risk of interfering with digestion.

B.P. Unguentum Plumbi Acetatis. OINTMENT OF ACETATE OF LEAD.—Acetate of lead (12 grains), benzoated lard (1 ounce).

USES.—It is used as a sedative and astringent application to ulcers, excoriations, painful piles, irritable and itching skin diseases, erysipelas, burns, bruises, &c.

Liquor Plumbi Subacetatis, B. and U.S.P. SOLUTION OF SUBACETATE OF LEAD.

Subacetate of lead, $Pb(C_2H_3O_2)_2.PbO.$, dissolved in water, B.P. An aqueous liquid containing in solution about 25 per cent. of subacetate of lead, U.S.P.

PREPARATION.—By boiling acetate of lead, oxide of lead, in powder, and distilled water together.

CHARACTERS AND TESTS.—A dense clear colourless liquid, with alkaline reaction and sweet astringent taste, becoming turbid by exposure to the air, and forming with mucilage of gum-arabic an opaque white jelly. It gives the reactions of lead and of an acetate.

PREPARATIONS.

B.P.			U.S.P.		
Liquor Plumbi Subacetatis Dilutus			Ceratum Plumbi Subacetatis.		
Unguentum ,, ,,		Compositum	Linimentum ,,	,,	
			Liquor ,,	,,	Dilutus.

USES.—It is recommended by Ringer as an application to pityriasis and eczema, and in combination with one or two parts of glycerine to the milder forms of lupus after the crusts have been removed. Diluted, and mixed with liquor morphiæ acetatis, it is a useful application to hæmorrhoids.

Liquor Plumbi Subacetatis Dilutus, B. and U.S.P. DILUTED SOLUTION OF SUBACETATE OF LEAD.—Consists of 2 fl. dr. of solution of lead and 2 fl. dr. of rectified spirit diluted with water up to a pint, B.P. Solution of acetate of lead 3, distilled water 97 parts, U.S.P.

USES.—Used as a mild astringent and sedative to irritable and itching skin diseases and superficial inflammation; as an eye wash unless ulceration of the cornea be present; as an injection in leucorrhœa and pruritus pudendi.

Unguentum Plumbi Subacetatis Compositum, B.P.; Ceratum Plumbi Subacetatis, U.S.P. COMPOUND OINTMENT OF SUBACETATE OF LEAD, B.P.; CERATE OF SUBACETATE OF LEAD, U.S.P.—Contains solution of subacetate of lead (6 fluid ounces), camphor (60 grains), white wax (8 ounces), oil of almonds (1 pint), B.P. Solution of subacetate of lead (20 parts), camphor cerate (80 parts), U.S.P.

USES.—Chiefly as an application to chapped hands and ulcers.

U.S.P. Linimentum Plumbi Subacetatis. LINIMENT OF SUBACETATE OF LEAD.—Solution of subacetate of lead (40 parts), cotton seed oil (60 parts).

USES.—To allay itching in chilblains and skin diseases.

Plumbi Nitras, B. and U.S.P. NITRATE OF LEAD. $Pb(NO_3)_2$; 330·5.

PREPARATION.—By dissolving lead in nitric acid with the aid of heat and crystallising.

CHARACTERS AND TESTS.—In colourless octahedral crystals which are nearly opaque, permanent in the air, of a sweetish astringent taste, soluble in water and alcohol. The aqueous solution gives the reactions of lead. Added to sulphate of indigo it discharges the colour.

PREPARATION IN WHICH NITRATE OF LEAD IS USED.

Plumbi Iodidum.

USES.—It is sometimes applied as a disinfectant, and occasionally to cracked hands or lips and fissured nipples. It has been given in order to check hæmorrhage from the lungs.

Plumbi Iodidum, B. and U.S.P. IODIDE OF LEAD. PbI or PbI_2; 459·7

PREPARATION.—By mixing solutions of nitrate of lead and potassium iodide.

CHARACTERS.—A heavy, bright, citron-yellow powder, neutral, no taste nor smell. Sparingly soluble in water, readily soluble in chloride of ammonium. When strongly heated it first fuses and

then is decomposed, emitting violet vapours of iodine, and leaving a citron-yellow residue.

IMPURITIES.—Chromate, zinc, alkalies, and alkaline earths.

TESTS.—On triturating 1 part of the salt with 2 parts of chloride of ammonium in a porcelain mortar, and adding 2 parts of water, a colourless liquid should result (with absence of, and different from, chromate). This liquid, diluted with water, affords a white precipitate with diluted sulphuric acid, and a black one with hydrosulphuric acid. If all the lead has been precipitated from a portion of the solution by the last-named reagent, the filtrate should leave no residue on evaporation and gentle ignition (absence of zinc, alkalies, or alkaline earths).

PREPARATIONS.

B.P. Emplastrum Plumbi Iodidi. Iodide of Lead Plaster, 1 part in 9 (with soap and resin plaster).

Unguentum Plumbi Iodidi; B. and U.S.P. Ointment of Iodide of Lead with simple ointment, 1 part in 8, B.P. ; with benzoated lard, 1 part in 10, U.S.P.

USES.—It has been used externally as an application to ringworm, and as a counter-irritant in scrofulous enlargement of the glands. It has been given internally in enlarged glands, and in chronic enlargement of the spleen. In the latter case the iodine may be supposed to have a beneficial effect upon the corpuscles of the spleen, and the lead to cause contraction by acting upon the involuntary muscular fibre of the organ.

The ointment is used for enlarged glands.

TIN. Sn.; 118.

B.P. Tin, granulated.

Grain tin, reduced to small fragments by fusing and pouring into cold water.

USE.—Used formerly in powder as an anthelmintic in $\frac{1}{2}$ ounce doses.

Solution of Chloride of Tin. $SnCl_2$.

PREPARATION.—By dissolving granulated tin in diluted hydrochloric acid.

USES.—It has a powerful affinity for oxygen and for chlorine. When added to trichloride of gold it gives a precipitate called purple of Cassius whose composition is not known. It is used as a test for mercury. When added to calomel it abstracts chlorine and precipitates metallic mercury. When added to corrosive sublimate it precipitates calomel, which it afterwards reduces to mercury.

Salts of tin are not used in practice, but have been given in nervous diseases in somewhat the same way as zinc.

Chloride of tin is a caustic of considerable power. In poisoning by it the treatment would be to give milk and alkaline carbonates.

CHAPTER XXVII.

Class V.

PENTAD ELEMENTS.

Nitrogen, Phosphorus, *Vanadium*, Arsenic, *Niobium*, Antimony, *Tantalum*, Bismuth.

In the heading to this class I have substituted the word elements for metals, for nitrogen and phosphorus belong to it, although they are non-metallic elements.

They form analogous compounds with oxygen and hydrogen.

		1	2	3	4	5	
Nitrogen.....	N	N_2O	N_2O_2	N_2O_3	N_2O_4	N_2O_5	NH_3
Phosphorus.....	P			P_2O_3		P_2O_5	PH_3
Vanadium.....	V	V_2O	V_2O_2	V_2O_3	V_2O_4	V_2O_5	
Arsenic.....	As			As_2O_3		As_2O_5	AsH_3
Antimony.....	Sb			Sb_2O_3		Sb_2O_5	SbH_3
Bismuth.....	Bi			Bi_2O_3		Bi_2O_5	

Nitrogen. N; 14. Non-officinal.

Nitrogen when free is chemically inactive, and does not readily unite with other elements. It is also physiologically inactive, but has been used as an anæsthetic. The anæsthesia is due to asphyxia from absence of oxygen; but as the carbonic acid is constantly removed by the inhalation of nitrogen, the symptoms of irritation produced by it in ordinary asphyxia are absent.

The 1st, 3rd, and 5th, of its compounds in the above table can take up the elements of water and of metallic oxides to form salts.

Hydrogen Salt.		Metallic Salt, *e.g.* of Potassium.	
Hyponitrous acid	H_2ON_2O or HNO.	Potassium hyponitrite	K_2ON_2O or KNO.
Nitrous acid	$H_2ON_2O_3$ or HNO_2.	,, nitrite	$K_2ON_2O_3$ or KNO_2.
Nitric acid	$H_2ON_2O_5$ or HNO_3.	,, nitrate	$K_2ON_2O_5$ or KNO_3.

The acid compounds of nitrogen with oxygen resemble those of phosphorus and arsenic in this, that the nitrites are considerably more active than the nitrates, just as the phosphites and arsenites are more active than the phosphates and arseniates. The action of nitrites on the organism was first investigated in the case of

nitrite of amyl, but by some unpublished experiments made in Professor Ludwig's laboratory in 1869-70, I satisfied myself of the correctness of Dr. B. W. Richardson's observation,[1] that other nitrites such as those of ethyl and sodium had an action on the blood-pressure similar in kind though less in degree. In other experiments Dr. Gresswell and I found that the nitrites of propyl and butyl had also this action, and that all nitrites were muscular poisons.[2] Mr. Tait and I found that nitroglycerine had an action resembling the nitrites both in its effect on blood-pressure and the change it caused in the colour of the blood, but the headache it produced deterred us from employing it in the treatment of patients.[3]

Nitrous Oxide. NITROGEN MONOXIDE. Laughing gas. N_2O. Not officinal.

PREPARATION.—By heating nitrate of ammonia.

ACTION.—When a mixture of nitrous oxide and air is inhaled it causes excitement generally characterised by fits of involuntary laughter, dancing, singing, and shouting, although it sometimes appears to arouse pugnacity. When inhaled pure, it produces, first of all, a feeling of increased circulation through the body generally, accompanied by warmth and a little singing in the ears. If the inhalation be now stopped, the effect may pass off, but occasionally, after a few breaths of pure air have been taken, the same excitement may ensue which is usually produced by the inhalation of mixed air and gas. On one occasion having inhaled pure gas for a short time, I felt a little warmth of the skin, and a humming in the head, and, thinking it was time to desist, laid down the mask of the inhaler. After a few breaths of fresh air, I noticed that on attempting to speak, the speech was slow and hesitating. An electric shock then seemed to shoot through the spine, and I was seized with an uncontrollable desire to laugh, jump, and throw the arms about, while the perceptive faculties appeared quite unaffected. Although unable to control my movements, I was perfectly conscious of their ludicrous nature, and was astonished that two men who were sitting by, and who afterwards informed me that they thought the whole thing a bad joke, were able to preserve their gravity. After lasting for one or two minutes, the effect of the gas suddenly and completely passed off.

When inhalation is continued for a longer time, the feelings of warmth and buzzing in the ears are succeeded by gradually increasing dimness of perception; sight, sounds, and tactile impressions become much dimmer than usual; and then the person beomes unconscious. At this time the face usually assumes a livid aspect, and during the period of insensibility small operations may be performed without the patient being the least aware of them.

[1] B. W. Richardson, *Brit. and For. Med. Chir. Rev.*, July, 1867.
[2] *St. Bartholomew's Hospital Reports*, 1876, p. 143. [3] *Ibid.* p. 140.

When the administration of the gas is stopped, recovery quickly and completely occurs, often passing off without leaving any after effects, though occasionally more or less headache is experienced for some hours. No stage of exhilaration such as that which has already been described as occurring after the administration of a small quantity of nitrous oxide is noticed during recovery from complete narcosis.

Nitrous oxide appears to act as an anæsthetic, chiefly by depriving the nerve centres of oxygen. As the inhalation of pure nitrogen has a similar anæsthetic power, the exhilarating effect of small doses of nitrous oxide seems to show besides that it has a special relation to the nerve-centres.

USES.—It is useful as an anæsthetic for extraction of teeth, evulsion of the toe-nail, and other minor operations. The intense venosity of the blood which occurs during its use renders it unsuitable for continued administration, and therefore inadmissible in the case of a lengthy operation.

MODE OF ADMINISTRATION.—The most convenient mode of administering it is to have it condensed in a large iron bottle, from which the gas may be readily conveyed to the patient by means of a flexible tube attached to a mask. The mask ought to be provided with a margin of inflated india-rubber, so that it will fit perfectly tightly to the face, and thus prevent the escape of gas.

PHOSPHORUS. P; 31. B. and U.S.P.

A non-metallic element obtained from bones.

PREPARATION.—By treating bones with sulphuric acid, when sulphate of calcium is precipitated and acid phosphate of calcium remains in solution. This is evaporated and distilled with charcoal, which removes the oxygen. The phosphorus distils over and is condensed under water.

CHARACTERS. — A semi-transparent, yellowish, waxy-looking solid. When exposed to air it emits white fumes which are luminous in the dark and have a garlicky odour.

OFFICINAL PREPARATIONS.

B.P.	DOSE.
Pilula Phosphori (with balsam of tolu and yellow wax $\frac{1}{15}$ gr. in 5 grs.)	1-5 grs.
Oleum Phosphoratum (phosphorus in almond oil, $\frac{1}{32}$ gr. in 5 m.)	1-10 m.

U.S.P.	DOSE.
Pilulæ Phosphori ($\frac{1}{100}$ gr. in each)	1-5 pills.
Oleum Phosphoratum (with stronger ether and almond oil 1 per cent.)	1-5 min.

ACTION OF PHOSPHORUS.—Living protoplasm has the power of oxidising all the members of this group, and also of reducing the products of their oxidation (Binz). It is probable that this action goes on more easily with phosphorus than with nitrogen. Hence if phosphorus replaces nitrogen in a living cell it will

quicken metabolism. It is absorbed unchanged into the blood, and is excreted by the kidneys either as phosphorus or phosphoric acid. In **small doses** it appears to cause development of the fibrous tissue in the **liver,** and in doses too small to affect the liver or stomach it acts upon the osseous tissues. Its action upon the **bones** is somewhat peculiar, and has been fully investigated by Wegner. When phosphorus is given to growing animals the bone, as it develops, is denser than usual, the cancellous tissue being like the denser tissue in the long bones. Cancellous tissue formed before the administration of phosphorus remains unchanged. If the administration be still continued, the cancellous tissue formed previously to the use of the drug is absorbed, and serves to form the cavity of the bone, and after a while the normal cancellated tissue at the end of the epiphysis is also replaced by solid bone. Afterwards even the dense bone thus formed becomes absorbed, and forms the cavity of the long bone. In adult animals phosphorus also causes the bones to become denser, and this is especially noticeable in chickens, in which the cavity of the bone may be completely filled up, so that long bones form a solid rod instead of a tube. The influence of phosphorus upon osseous tissues is not due to excess of phosphates produced by it in the blood, but to stimulation of tissue growth itself by the phosphorus, for Wegner found that in animals fed with phosphorus but almost entirely deprived of phosphates, the same dense, bony substance was formed, except that instead of the bone being hard, it was like that which occurs in rickets. In men exposed to the fumes of phosphorus, *e.g.* those employed in the manufacture of lucifer-matches, caries of the **lower jaw** is a frequent occurrence. This is not due to the action of the phosphorus after absorption into the circulation, but to the direct effect of the fumes upon the bone itself. For it has been found that when a bone of an animal fed by phosphorus was exposed, no carious change took place; but if one were exposed to the fumes, caries was produced, and amongst lucifer-match makers it has been noticed that only those who have carious teeth suffer from necrosis of the jaw. When doses larger than those which induce induration of the bones are given, the phosphorus appears to act upon the **connective tissue** of the **stomach** and **liver,** causing chronic inflammation of these organs, and atrophy of the secreting cells, so that cirrhosis of the liver appears. In **poisonous doses** the phosphorus first produces the symptoms of gastro-enteritis, with a garlicky taste in the mouth, the vomited matters having a similar odour, containing bile, and but rarely blood. They sometimes shine in the dark. At the end of twenty-four to thirty-six hours, the symptoms of gastro-intestinal irritation cease, and the patient is apparently well with the exception of vague pains in the limbs and loins. During this period, however, fatty degeneration of the liver, stomach, and **kidneys** is going on, and the effect of the changes in

these organs soon manifests itself. Sometimes, after two or three days, the patient may die suddenly, without exhibiting any fresh symptoms, but usually, on the second or third day, jaundice appears, while the urine contains bile, and often albumen. There is occasionally vomiting and purging, headache, sleeplessness, delirium, and coma, and death with or without convulsions. In some cases, when the poisoning runs a less acute course, the effect of fatty degeneration of the **vessels** is most prominent, discharges of blood occurring from the stomach, intestines, nose, lungs, bladder, uterus, and ears, and ecchymosis appearing on the surface. Increasing anæmia and debility finally kill the patient.

The **treatment** in cases of poisoning by phosphorus is to wash out the stomach freely by means of the stomach-pump, or by an emetic of sulphate of copper, and to give oxidised oil of turpentine in 40 minim doses in mucilage every fifteen minutes for an hour. Fats and oils should be withheld, as they dissolve any phosphorus which may be present in the stomach, and assist its absorption.

The **fatty degeneration** produced by phosphorus appears to depend on a more rapid splitting up of albuminous tissues, along with deficient oxidation. This was shown by Voit and Bauer, who produced fatty degeneration of the organs by the administration of phosphorus in dogs absolutely deprived of food, where the fat found after death could neither have come from food nor from fat deposited in other parts of the body, as that had all been absorbed before the administration of the drug had been commenced. It must therefore have been formed *in situ* from the decomposition of albuminous substances, and these were shown to have split up more quickly than usual by the amount of urea in the urine being increased by the phosphorus, while oxidation in the body was shown to have diminished by the amount of oxygen absorbed and carbonic acid given off being lessened. In man, the products of albuminous waste are often not converted into urea, but appear in the urine as leucin and tyrosin.

The action of **compounds** containing phosphorus appears to depend considerably on the more or less complete saturation of its affinities, and the readiness with which the phosphorus may attach itself to the organic constituents of the tissues. Thus, phosphoric acid, in which the affinities of the phosphorus are fully saturated by oxygen, appears simply to act as an acid without exerting any specific action, and when combined with soda, its effects are simply those of a neutral alkaline salt.

Metaphosphoric and pyrophosphoric acids appear to have a specific poisonous action more nearly resembling that of phosphorus. Pyrophosphate of soda paralyses the nerve-centres in the spinal cord and medulla oblongata, producing drowsiness, loss of reflex action, paralysis, and death, which is sometimes preceded by convulsions. It lowers the blood-pressure in mammals, slows the beats of the frog's heart, renders them powerful and finally arrests

them in systole. When death does not occur rapidly, marked fatty degeneration of the heart and kidneys are found, and a similar change, though to a less extent, in the liver. Although it acts as a poison when injected subcutaneously or into the circulation, pyrophosphate of sodium has no poisonous action when taken into the intestinal canal.

Metaphosphate of soda has a similar but less powerful action.

USES.—Phosphorus forms an important constituent of nervous tissue, and has been employed in cases of nervous debility, neuralgia, wakefulness, paralysis, locomotor ataxia, and impotence. In some cases of leucocythæmia it is useful. It has been used in osteomalacia, and instead of arsenic in skin diseases (*vide* also p. 646). Even in small doses it may cause nausea, with unpleasant eructations. It is well, therefore, to commence with a very small dose, such as $\frac{1}{100}$ of a grain.

GENERAL REACTIONS OF ARSENIC, ANTIMONY, AND BISMUTH.

	Arsenic.	Antimony.	Bismuth.
Hydrosulphuric acid	Yellow precipitate (soluble in ammonium sulphide and re-precipitated by acids).	Orange or brick-red precipitate (soluble in ammonium sulphide, and precipitated by acids).	Black precipitate (insoluble in ammonium sulphide).
Water	. . . . .	Strong solution thrown into much water gives a white precipitate, which becomes orange on the addition of hydrosulphuric acid.	Strong solution thrown into water, gives a white precipitate, which becomes black on the addition of hydrogen sulphide.

ARSENIC. As; 75.

Metallic arsenic is not used in medicine. It is steel-coloured, crystalline, and brittle, and when heated gives off garlic fumes. Very light (sp. gr. 5·8), very volatile. It forms two classes of salts. In one, the arsenious salts, it is tri-, in the other, arsenic salts, pent-atomic. Arsenious oxide, As_2O_3, usually called arsenious acid, forms arsenites. Arsenic oxide, As_2O_5, or arsenic acid, forms arsenates, or, as they are termed in the B. and U.S.P., arseniates.

GENERAL SOURCES OF ARSENIC.—It occurs in many ores combined with metals, oxygen, and sulphur. Its presence as a frequent impurity in sulphur has already been mentioned. It is chiefly obtained by roasting the arsenides of iron, nickel and cobalt, and condensing the arsenious oxide in a long nearly horizontal chimney.

GENERAL TESTS FOR ARSENIOUS ACID.—With hydrosulphuric acid it gives a yellow precipitate, which is brightest in acid solutions. Silver nitrate gives a canary-yellow and copper sulphate a brilliant green precipitate (Scheele's green). These are very

soluble in acid and neither of them is thrown down from simple aqueous solutions of arsenious acid (a little acid being freed in the reaction); a little alkali must be present. Both are very soluble in excess of ammonia, so that to avoid adding excess ammonio-nitrate of silver and ammonio-sulphate of copper are used as reagents, in preference to adding ammonia along with simple solutions of nitrate of silver or of sulphate of copper. Arseniates throw down a brick-red precipitate with ammonio-nitrate of silver, and are thus distinguished from arsenites.

GENERAL ACTION OF ARSENIC.—Although arsenic, like antimony, has no great affinity for albumen, and does not produce with it a coagulum, yet, when applied to the **skin** denuded of its epidermis, it acts as a caustic and produces a slough. If used in a dilute form, and over a large surface, it may be absorbed, and may produce the general effects of the drug upon the system. When applied in a concentrated form it appears to produce a slough more rapidly, and the dead tissue forms a barrier to its farther absorption. In the **mouth** it has a somewhat sweetish taste, and in small doses excites in the **stomach** a feeling of appetite. In larger doses it produces irritation, colicky pains, diarrhœa, and mucous evacuations, sometimes tinged with blood. In still larger doses it causes symptoms of gastro-enteritis, vomiting, and purging, the stools being finally of a rice-watery appearance, closely resembling those of Asiatic cholera. These are also occasionally accompanied by collapse, with pale, pinched, and somewhat livid surface, and violent cramps of the extremities, so that cases of arsenical poisoning may be readily mistaken for cholera, and *vice versa*. There is sometimes strangury, priapism, suppression of urine or bloody urine; the consciousness is retained to the last. In some cases there are no symptoms at all of gastro-intestinal irritation, the **nervous system** being affected, and the patient presents the symptoms of coma, very much resembling those of opium poisoning.

The **treatment** in cases of arsenical poisoning is to wash out the stomach freely by means of the stomach-pump, and the copious administration of diluents, taking care to insure their evacuation by the subsequent speedy administration of such emetics as mustard or sulphate of zinc if they are not at once rejected by the vomiting caused by the arsenic itself. Peroxide of iron may be administered in doses of a tablespoonful every ten minutes, and alcohol has been given when the moist peroxide could not be obtained. Demulcents should afterwards be given to allay the irritation.

Chronic poisoning by arsenic may occur from the inhalation of arsenical vapour or dust, arising from wall-papers, dresses, or other substances containing arsenic. The proportion of arsenic necessary to produce poisoning when taken into the lungs in this way appears to be very small. The symptoms are at first increased

appetite, then colicky pains and mucous or dysenteric stools, with great prostration, irritation of the eyes, running at the nose, a short cough, which is dry or accompanied by slight expectoration, and a white, silvery appearance of the tongue. These symptoms may sometimes continue for months, or even years, without the cause being suspected, until the recovery which ensues upon the removal of the offending wall-paper gives the clue to their cause.

When taken internally for a length of time a condition of **tolerance** may be induced in the case of arsenic, as well as in antimony. This is seen in the arsenic-eaters of Styria, who, beginning with small quantities, are gradually capable of taking larger and larger doses, until they can swallow at once, with safety, as much as five grains. In taking such doses as these they are careful not to take water with the arsenic, so that it is probably slowly absorbed from the stomach, and is, very possibly, rapidly evacuated. Dr. Craig Maclagan watched a noted arsenic-eater swallow his dose, and obtained from the urine which he afterwards passed a considerable quantity of the poison. By using the arsenic in this way, these people are said to undergo much greater exertion than usual without exhaustion, and to be able to ascend the steep Styrian hills without being affected with breathlessness. Some, no doubt, die in the attempt to acquire the habit, but those who have once become accustomed to the drug appear to continue its use without deriving any harm from it, and, moreover, seem sturdy and vigorous, and live to an old age.

After absorption into the blood, arsenic appears to some extent to modify **tissue change.** When a solution of arsenious acid is added to **blood** outside the body, it retards coagulation, prevents putrefaction, and conserves the form of the red blood corpuscles. A very dilute arsenical solution also conserves the irritability of the excised nerve and muscle of the frog.

Considerable doses of arsenic given for a length of time produce fatty degeneration of the liver and other organs, and cause the glycogen to disappear from the liver, so that puncture of the fourth ventricle no longer produces glycosuria.

Minute doses of arsenic appear to increase the rapidity of the **pulse.** Larger doses diminish the pulse and blood-pressure. In frogs the heart is slowed, and finally stands still in diastole. This stoppage of the **heart** appears to be due to paralysis of the motor ganglia, as the muscular substance will still continue to contract upon direct irritation. In warm-blooded animals it appears to prolong the irritability of the heart, so that it will still continue to beat for many hours after the death of the animal. According to Küntzer, this is due to retardation of the vital processes in the mammalian heart, so that it comes to resemble that of a cold-blooded animal. In animals arsenic has been found to diminish the **blood-pressure** from the beginning. This appears to be due partly to diminished activity of the heart, but chiefly to paralysis of

the splanchnics allowing the abdominal vessels to dilate (p. 243). In frogs it produces apparent paralysis, but this appears rather due to diminished sensibility of the grey matter in the posterior cornua of the spinal cord than to real paralysis, for the nerves and muscles in this state are found to be still quite irritable, and although the animal is insensible to pinching it can and does move when laid on its back. As, according to Schiff, the muscular sensations are conveyed in the white substance of the posterior columns, this would appear to be unaffected, while the grey substance which conveys sensations of pain is completely paralysed (p. 133).

In some cases of poisoning by arsenic, **paralysis** of one or more limbs occurs after the acute symptoms have passed off. It usually affects the extensors more than the flexors, and generally is temporary, though it may be permanent.

The action of arsenic on the **skin** is peculiar. Ringer and Murrell noticed that in frogs poisoned by it the cuticle could be



FIG. 131.—Vertical section of the healthy epidermis of a frog. *a*, Columnar layer of cells. *b* Malpighian layer. *c*, Intermediate layer. *e*, Corneous layer. *f*, Sheet of connective tissue forming boundary between dermis and epidermis. After Nunn.



FIG. 132.—Vertical section of epidermis from a frog poisoned by arsenic. *b*, vacuole in the softened protoplasm of the columnar layer of cells. At *a* the protoplasm is more softened and the vacuoles enlarged so that the cells are attached to the dermis only by threads of protoplasm. After Nunn.

stripped off the whole body with the greatest readiness within a few hours after its administration. This condition was found by Nunn to depend upon softening of the protoplasm of the columnar layer of cells in the epidermis, so that the cuticle remained attached to the dermis only by a few protoplasmic threads (Figs. 131 and 132).

Other epithelial structures are also affected, and Cornil has found fatty degeneration of the epithelium lining the alveoli of the **lungs** in animals poisoned by arsenic (Fig. 133).

Arsenic is **eliminated** chiefly by the urine, and to a less extent by the bile, and slightly by the skin. Its elimination by the urine is very rapid.

USES.—Arsenic has been used externally as an application to cancers, and forms the basis of most of the secret "cures" for this disease. The old recipe for this purpose consists of the following ingredients: arsenious acid, 2 drachms; cinnabar, 2 drachms; ashes of old leather, 8 grains; dragon's blood, 12 grains, made into a paste with water or saliva.

In applying a paste of this sort it is advisable that it should consist of at least one-fifth of arsenic, and that it should not be applied to too large an extent of surface at a time.

Internally, arsenic is used for its local action on the intestinal canal as a tonic and astringent, for its action on tissue change, and as a tonic and anti-spasmodic in cases of nervous disease. In the stomach, small doses stimulate the appetite, and are useful in allaying pain and checking vomiting. It may be given in irritative dyspepsia, in gastralgia, heartburn, in the vomiting of drunkards, and in gastric ulcer or cancer. It is also recommended by Ringer in cases of regurgitation of food unaccompanied by nausea. It is very useful in cases of diarrhœa where the tendency comes on during or immediately after the ingestion of food, whether in adults or children.



FIG. 133.—Section of lung, hardened in osmic acid, from guinea-pig poisoned by arsenious acid. The capillaries, *v*, project into the cavities of the alveoli, and are full of red blood corpuscles. The protoplasm, *a*, of the cells is filled with fatty granules. The nuclei are well preserved. After Cornil.

Arsenic is a powerful antiperiodic, nearly rivalling quinine; it seems less serviceable than quinine in well-marked cases of ague, but is sometimes as good, or even better than it in the irregular malarious manifestations such as headache, neuralgia, &c., which are known under the head of masked malaria. It is sometimes useful in chronic rheumatism and rheumatic gout, and in neuralgia of various sorts its effects are occasionally almost magical.

It has been used, not only in tic and hemicrania, but in spasmodic nervous diseases such as angina pectoris, chorea, and epilepsy, whooping-cough and asthma. It is often very serviceable in hay fever, and in cases of spasmodic sneezing coming on after exposure to dust or even without any apparent cause. It has been employed in chronic bronchitis with copious expectoration, and in ordinary catarrh without febrile disturbance. It appears to be very useful in the commencement of phthisis. Under its influence the author has seen consolidation of the lung, consequent on catarrhal pneumonia, clear up completely even in a subject having a very bad family history.

Probable mode of action of Arsenic in Phthisis.

The treatment of phthisis is so important that it may be advisable to discuss in a few words the probable mode of action of arsenic and hypophosphites in its early stages. It is now probable that this disease depends on the presence of a **bacillus** (*B. tuberculosis*, p. 67). In order that it should grow within the body, however, it is necessary that a suitable **nidus** should be present, and the different susceptibility to the disease of different individuals, or of the same individual at different times, probably depends on their liability to present a suitable nidus. The *Bacillus tuberculosis* differs from such bacilli as the *B. anthracis* in being of very slow growth, so that when it is cultivated artificially on a solid medium it takes about ten days before it succeeds in establishing itself and begins to grow. Consequently, when applied to an open wound, or when inhaled into the lungs of a healthy person, it does not, like the *Bacillus anthracis*, at once begin to multiply and produce disease in the organism, but it is usually removed by washing in the case of a wound, or by expectoration in healthy persons. But if its removal be interfered with it will produce disease. Thus, if instead of being applied to an open wound it be injected under the skin so that it cannot be removed by washing, it will after a time begin to grow, and produce tuberculosis, first local and then general. It is probable that the case is similar in the lungs. In the healthy lung it finds no nidus, and is removed by expectoration, but if a portion of the lung be consolidated by catarrhal pneumonia, the consolidated part probably affords a nidus to the bacillus, and the longer the consolidation lasts the greater the risk of bacilli finding entrance. In croupous pneumonia the exudation into the alveoli, consisting chiefly of fibrin with a few leucocytes, quickly breaks up and is absorbed, so that it is comparatively rarely followed by phthisis. But the proliferated epithelial cells which fill the alveoli of the lung in catarrhal pneumonia are much more resistant; they break down and are absorbed much more slowly, and hence a much longer time is given during which bacilli may find a nidus. The marked hereditary nature of phthisis is a curious point in a disease which we suppose to depend on the presence of a bacillus, and is a character in which it differs from such diseases as anthrax, ague, or relapsing fever, which are also due to foreign organisms. But the difference probably depends on the slow growth of the tubercle bacillus, which renders a prolonged undisturbed rest at the point where it enters the body necessary for its farther growth. **The disease is not** hereditary, **but the predisposition** to such morbid changes in the lungs as afford a nidus to the bacilli **is hereditary.**

The more rapidly the effused products in pneumonia can be removed from the lung, the less chance have the bacilli of finding a nidus. It is probable that arsenic, which causes fatty degeneration

of the normal epithelial cells lining the alveoli, also causes a similar degeneration of such cells when filling the alveolar cavities. By thus breaking them up and quickening their absorption, arsenic will lessen the risk of bacilli finding a nidus in them and converting catarrhal consolidation into phthisis. Probably the hypophosphites act in a similar way. If the patient should be in places where there are no tubercular bacilli, the consolidation may persist for a long time without phthisis occurring, and hence one advantage of sea voyages in cases of recent consolidation.

MODE OF ADMINISTRATION.—In those cases where the local action of arsenic on the stomach and intestine is desired, it is best to give it in small doses before meals, but where the action of the drug on other organs of the body is desired, it should be administered immediately after meals.

The symptoms which show that arsenic is beginning to produce its physiological effect, and that it is time to diminish the dose or cease its administration, are irritation of the eyes, the conjunctivæ being somewhat injected, and the patient showing a tendency to rub the eyes; or the digestive canal may be the first to show the effect of the drug, the appetite may fail, and colicky pains with a tendency to diarrhœa may appear before the eyes are affected. Either of these symptoms indicates that the drug should be discontinued, or the dose diminished.

In skin diseases arsenic is used more frequently than any other internal remedy. As it increases metabolism in the cells of the epidermis (p. 643) it is contraindicated in acute cases. Its administration should not be commenced while there is any active cutaneous inflammation, and it should be given until either the amendment begins, or the signs of conjunctivitis or gastric irritation appear. When these are noticed, the dose should be diminished until they become just perceptible, and the administration of the drug should be continued for some time after the eruption has disappeared, in order to prevent its recurrence.

Acidum Arseniosum, B. and U.S.P. ARSENIOUS ACID. As_2O_3; 197·8.

An anhydrous acid, obtained by roasting arsenical ores, and purified by sublimation.

CHARACTERS AND TESTS.—Occurs in sublimed masses which usually present a stratified appearance caused by the existence of separate layers differing from each other in degrees of opacity, or as a heavy white powder. When slowly sublimed in a glass tube it forms minute brilliant and transparent octahedral crystals. It is sparingly soluble in water, and its solution gives with ammonio-nitrate of silver a canary-yellow precipitate insoluble in water, but readily dissolved by ammonia and by nitric acid. Sprinkled on a red-hot coal, it emits an alliaceous odour.

IMPURITIES.—Gypsum and chalk.

TEST.—It is entirely volatilised at a temperature not exceeding 400°. Four grains of it dissolved in boiling water with eight grains of bicarbonate of soda, discharge the colour of 808 grain-measures of the volumetric solution of iodine. $As_2O_3 + 2H_2O + 4I = As_2O_5 + 4HI$.

DOSE.—$\frac{1}{60}$ to $\frac{1}{12}$ of a grain, in solution.

PREPARATIONS OF ARSENIOUS ACID.

B.P.

Liquor Arsenicalis ..... 4 grains in 1 fluid ounce.
,, Arsenici Hydrochloricus ..... 4 grains in 1 fluid ounce.

U.S.P.

Liquor Acidi Arseniosi.
Liquor Potassii Arsenitis.

PREPARATIONS OF ARSENIC ACID.

Ferri Arsenias
Sodæ Arsenias
,, Arseniatis, Liquor

Liquor Arsenicalis, B.P.; Liquor Potassii Arsenitis, U.S.P. ARSENICAL SOLUTION, B.P.; SOLUTION OF ARSENITE OF POTASSIUM, U.S.P. FOWLER'S SOLUTION.—Is a mixed solution of arsenite and carbonate of potash flavoured with compound tincture of lavender. Contains 4 grs. arsenious acid in 1 fl. oz. B.P.; 1 in 100, U.S.P.

CHARACTERS.—A reddish liquid, alkaline to test-paper, and having the odour of lavender.

TEST.—After being acidulated with hydrochloric acid, it gives, with sulphuretted hydrogen, a yellow precipitate, which is brightest when the arsenical solution has been previously diluted.

DOSE.—2 to 8 minims.

USE.—This is the preparation of arsenic most commonly employed. It may be given along with alkalies.

Liquor Arsenici Hydrochloricus, B.P.; Liquor Acidi Arseniosi, U.S.P. HYDROCHLORIC SOLUTION OF ARSENIC, B.P.; SOLUTION OF ARSENIOUS ACID, U.S.P.—A solution of arsenious acid, 4 grs. with 6 min. of hydrochloric acid in 1 fl. oz. of water, B.P.; 1 part arsenious acid and 2 of hydrochloric in 100 of water, U.S.P.

CHARACTERS AND TESTS.—A colourless liquid, having an acid reaction. Sulphuretted hydrogen gives at once a bright yellow precipitate.

DOSE.—2 to 8 minims.

USE.—Some think it milder than the ordinary liquor. Garrod thinks not. It can be given along with perchloride of iron in solution, or with acids.

Sodæ Arsenias, B.P.; Sodii Arsenias, U.S.P. ARSENIATE OF SODA, B.P.; OF SODIUM, U.S.P. $Na_2HAsO_4.7H_2O$; 311·9.

PREPARATION.—By fusing arsenious acid with nitrate and carbonate of soda. The As_2O_3 is oxidised by the nitrate to As_2O_5, which combines with the soda to form arseniate.

CHARACTERS AND TESTS.—In colourless transparent prisms, soluble in water; the solution is alkaline, giving white precipitates with chloride of barium, chloride of calcium, and sulphate of zinc, and a brick-red precipitate with nitrate of silver (arseniate), all of which are soluble in nitric acid.

DOSE.—$\frac{1}{16}$ to $\frac{1}{8}$ gr.; of the dried salt $\frac{1}{24}$ to $\frac{1}{12}$ gr.

PREPARATIONS.

B.P.

Liquor Sodæ Arseniatis { 6·6 grains or 4 grains dried } in 1 fl. oz. of water, B.P.; 1 in 100, U.S.P.

DOSE.—5 to 10 minims.

ACTION.—It acts like other preparations of arsenic, but does not irritate the stomach so much, and may be given in larger doses. In frogs it produces, like arsenious acid, paralysis of the brain and spinal cord, but is much less powerful (Ringer and Murrell).

USES.—It may be used in the same diseases as arsenious acid. It is perhaps one of the best remedies for neuralgia which we have.

U.S.P. Arsenii Iodidum. IODIDE OF ARSENIC. AsI_3; 454·7.

PREPARATION.—By gently warming arsenious acid and iodine together.

CHARACTERS.—Glossy orange-red crystalline masses, or shining orange-red crystalline scales, gradually losing iodine when exposed to the air, having an iodine-like odour and taste and a neutral reaction. The aqueous solution has a yellow colour, and on standing gradually decomposes into arsenious and hydriodic acids. On passing hydrosulphuric acid through the solution a lemon-yellow precipitate is thrown down. If the salt be heated with diluted nitric acid, vapour of iodine will be given off.

USE.—In skin diseases.

DOSE.—$\frac{1}{8}$ gr. (0·008 Gm.)

U.S.P. Liquor Arsenii et Hydrargyri Iodidi. SOLUTION OF IODIDE OF ARSENIC AND MERCURY. DONOVAN'S SOLUTION.—Iodide of arsenic, 1; red iodide of mercury, 1; water up to 100.

CHARACTERS.—A pale or orange-yellow solution, with a somewhat styptic taste.

INCOMPATIBLES.—Solutions of opium or morphine.

USES.—In skin diseases, syphilis, rheumatism, and nocturnal pains.

DOSE.—5 to 10 minims (0·3 – 0·6 cc.)

ANTIMONY. Sb; 122.

Antimony forms two classes of salts, antimonious and antimonic. In the former it is tri- and in the latter pent-atomic.

GENERAL SOURCES.—It is chiefly found native in the form of the black antimonious sulphide, Sb_2S_3.

GENERAL REACTIONS.—It is recognised by the orange-coloured precipitate which it gives with sulphuretted hydrogen in acid solutions. A characteristic reaction is the white precipitate which

falls on throwing a strong solution of a salt of antimony, such as the chloride, into water and the change of the white into an orange colour on the addition of sulphuretted hydrogen. A similar reaction occurs with salts of bismuth, but the white precipitate becomes black on the addition of sulphuretted hydrogen.

A solution of chloride of antimony gives with potash or soda a white precipitate which only dissolves in large excess, and with ammonia a white precipitate insoluble in excess. But if tartaric acid be present the precipitate dissolves in a slight excess of potash or soda, and with ammonia only a slight precipitate is formed.

General Actions of Antimony.—Salts of antimony probably combine with **albumen,** but in alkaline solutions they form no precipitate. They only form precipitates in acid solutions, and they consequently appear to exert an irritant action only on those parts of the animal body where they meet with an acid secretion, such as the orifices of the sweat-glands and the stomach. When applied to the **skin** the chloride of antimony destroys the cuticle, and acts as a powerful escharotic, producing a deep slough and a slowly healing sore.

The other preparations, however, instead of affecting the whole surface to which they are applied, produce inflammation in isolated spots, which, beginning with papules, proceeds to pustules resembling those of small-pox. A similar pustular irritation is sometimes noticed upon the fauces of persons who have been taking antimony for some time, or have been poisoned by it. When taken **internally, small doses** produce little more than a feeling of warmth in the stomach and slightly increased diaphoresis, but larger doses cause loss of appetite, nausea accompanied by enfeeblement of the circulation, and a feeling of great depression and weakness. Not only the secretion of sweat, but those of the mucous membranes, stomach, intestine, and respiratory passages, seem at the same time to be considerably increased. In still **larger doses** antimony produces vomiting, with great depression of the circulation, and relaxation both of the voluntary and involuntary muscles. In large and **poisonous doses** it causes gastro-enteritis, with profuse diarrhœa and extreme collapse. The pulse is small and quick, the surface cold, and covered with clammy perspiration. There is great weakness and severe cramps of the extremities, and the symptoms somewhat resemble those of Asiatic cholera. **Death** may occur in this condition. It is sometimes preceded by delirium and convulsions, and tonic or clonic convulsive spasms.

The **treatment** of antimonial poisoning consists in the administration of tannin, and in some readily accessible form. The most easily obtained is a strong infusion of tea, and the tannin is more readily extracted from this by the addition of a small quantity of bicarbonate of soda. Infusions of oak bark or of cinchona may also

be used if obtainable. Milk and mucilaginous drinks may also be used. A diffusible stimulant should be given to counteract the collapse.

The mode in which tartar emetic causes **vomiting** has given rise to considerable dispute. It acts as an emetic even when injected into the veins, as well as when given by the stomach, and it was found by Magendie that when the stomach of an animal was excised, and a pig's bladder filled with liquid attached to the lower end of the œsophagus, an injection of tartar emetic into the circulation caused movements of vomiting, and the contents of the bladder were expelled just as if the stomach had been *in situ*. This experiment seemed to prove not only that the act of vomiting was independent of the movements of the stomach itself, but also that tartar emetic caused vomiting by acting upon the vomiting centre, and not upon the stomach. The objection, however, has been raised that the action of the drug upon the vomiting centre is not direct, but reflex; and it has been urged that, although the stomach was removed, the antimony might still be carried by the circulation to the œsophagus and intestines, and by there causing irritation might produce reflex vomiting. This seems improbable, especially as the antimonial salts have a comparatively slight action on organs having, like the œsophagus and intestines, an alkaline reaction, instead of an acid one, as the stomach has.

It is probable, then, that tartar emetic does produce vomiting by its direct action on the vomiting centre in the medulla oblongata, but probably this direct action is not the only way in which it stimulates the vomiting centre—it also produces a reflex action upon it through the stomach. For it has been found that even when tartar emetic is injected into the veins, it is eliminated by the mucous membrane of the stomach (p. 29), and may thus act upon that organ in the same way as when introduced directly into it. If its emetic action be due in any great measure to irritation of the stomach, one would expect that a smaller dose would be found sufficient to produce vomiting, when introduced directly into the stomach, than when injected into the veins, for in the former case the whole of it will come in contact with the stomach and will do so at once; in the latter case only a fraction of the quantity injected into the veins will reach the stomach, and some time will be required before it accumulates in the gastric mucous membrane sufficiently to cause irritation. This is exactly what is found by experiment, and vomiting is produced more quickly, and by a smaller dose, when the drug is introduced into the stomach, than when injected into the veins, just as we should expect to be the case if its emetic action were due in considerable measure to its action upon the stomach itself. This view is also supported by another experiment, for after the nervous channel by which impressions are conducted from the stomach to the vomiting centre is destroyed by section of the vagi, double the dose of the drug is

required in order to produce vomiting. It may then be concluded that antimony acts chiefly as an emetic by irritating the stomach, and thus exciting the vomiting centre reflexly, but that it also acts directly on this centre when conveyed to it by the blood (p. 325).

After its absorption into the blood, antimony diminishes the blood-pressure, and slows the pulse. When applied directly to the **heart** of a frog, it first increases, then slows, and finally arrests its pulsations in diastole. This action appears to be chiefly due to paralysis of the cardiac muscle itself, and possibly also to the effect upon motor ganglia.

The effect of antimony upon the **circulation** appears to depend partly upon the direct action of the drug upon the heart and vessels, and partly on its reflex action upon them through the nerves of the stomach. In warm-blooded animals the pulse becomes quicker as the feeling of nausea increases, and, after the vomiting, again falls nearly to the normal. Its volume is, at the same time, diminished. After the nausea has ceased, the pulse again becomes quicker, and after this secondary acceleration has reached a greater or less height, according to the dose, it again sinks to the normal.

As the primary acceleration during the stage of nausea, ceases with vomiting, it is probably to be attributed to reflex irritation of the accelerating centres, or reflex depression of the vagus through the gastric nerves, whereas the cause of the secondary acceleration is more probably to be sought in diminished power of the vagus nerve itself. The **blood-pressure** sinks constantly, from the very beginning, and this sinking is probably due to diminished power of the cardiac pulsations. The **temperature** in the extremities appears to be diminished during the stage of nausea, owing to the smaller amount of blood going to them. As less blood reaches the surface in this condition, there is less opportunity afforded for its being cooled by contact with the atmosphere, and the temperature in the body gradually rises, even above the normal. When the spasm of the vessels in the extremities relaxes, they also become warmer than normal. As the effects pass off, the temperature sinks to the normal, or below it.

The **respiration** is first increased, and then diminished.

Large doses of antimony affect the **spinal cord** both in cold- and warm-blooded animals. It appears to paralyse, after, perhaps, slightly exciting both the sensory and motor tracts of the spinal cord, and as this paralysis appears in frogs while the heart still continues to beat, it must be due to the direct action of the drug upon the nervous system itself, and not to its indirect action through the circulation. The **motor** and **sensory nerves** appear also to be paralysed. The **muscles** are weakened (p. 104).

When given for a length of time, antimony seems to produce **fatty degeneration** of various organs.

The action of antimony upon the **skin** in frogs is even more rapid than that of arsenic, and differs from it in this respect, that

the softening does not affect the cells of the columnar layer only, but extends to those of the intermediate layer (Fig. 134). In consequence of this, the cuticle does not merely become detached from the dermis and peel off in strips as in poisoning by arsenic, but, the cells of the epidermis becoming detached from each other, the cuticle becomes converted into a soft jelly-like mass which can be scraped or brushed off.



FIG. 134.—Vertical section of epidermis from a frog poisoned by antimony. *a*, Columnar layer in which large cavities are formed. *b*, Columnar cells in which the reduced protoplasm is drawn into processes. *c*, Spaces in the intermediate layer. *d*, Light lines between cells indicating a softening and separation of cells. After Nunn.

Tartar emetic appears to be **eliminated** by the mucus of the stomach and alimentary canal, by the bile, and by the kidneys. Its action upon the renal secretion is somewhat uncertain. It appears to increase urea, uric acid, and pigment, and to diminish the water and the chloride of sodium, probably by increasing the perspiration.

USES.—The local uses of antimony will be considered under the special preparations.

When antimony is given **internally** for its action on the system generally, tartar emetic is the preparation usually employed, but the other preparations of antimony have a similar action when given in appropriate doses. It can be used for its emetic action, nauseant and depressant action, or diaphoretic action. As an **emetic** it has been employed in cases of croup, in order to cause expulsion of the false membrane; but for this purpose other emetics, such as ipecacuanha, alum, or sulphate of zinc, are now more generally employed, as they do not cause so much depression. It has also been used with considerable success to cut short an attack of intermittent fever, either alone or combined with a purgative. Indeed in cases where malarial poisoning has been intense, quinine sometimes proves ineffectual unless preceded by the administration of an emetic and purgative. It has sometimes been injected into the veins to produce vomiting, in cases of obstruction of the œsophagus, as, for example, by a piece of meat firmly lodged in it, and to cause expulsion of a biliary calculus lodged in the gall-duct, by the pressure from behind which the movements of vomiting produce, along with the relaxation of the muscular fibres of the gall-duct itself.

When large doses are administered several times, what is termed **tolerance** of the drug sets in, and it no longer produces vomiting. It has been used in this way in pneumonia, but the plan is now rarely followed. How this tolerance is produced is not at present understood. It is not improbable that it may be caused by the irritant action of the first few doses upon the stomach arresting the secretion of the acid juice, and producing a condition similar to that which occurs in fever. In this condition, subsequent doses of the tartar emetic, meeting with no acid, will have but a feeble action upon the stomach.

In cases of obstinate constipation it has been used along with sulphate of magnesia. As a **nauseant** it has been given to relax the cervix uteri in labour; in acute inflammations, *e.g.* in acute orchitis, where the emetic is first given, and nausea is kept up by a continued administration of smaller doses, and also in pericarditis, pneumonia, pleurisy, peritonitis, meningitis, bronchitis, and hepatitis, as well as in acute rheumatism. As an **expectorant** it is used in bronchitis. The cases in which it is especially serviceable are those in which there is great congestion and much dyspnœa, with little or no secretion, as shown by loud, sibilant *râles* over the chest, the pulse being full, and the face flushed, with a tendency to lividity. It has also been given to check hæmoptysis when there was much excitement of the circulation. In nervous diseases, attended with much excitement, such as certain cases of insanity, delirium tremens, and puerperal convulsions, it is of use. In the delirium of fever, it has been highly recommended by Dr. Graves, in combination with opium, as a means of producing sleep. Where the delirium is furious the tartar emetic must be given in full, and the opium in small doses; while if the delirium is milder and the sleeplessness great, the opium dose must be increased and that of the tartar emetic diminished. The same treatment may be adopted in the delirium and sleeplessness of delirium tremens.

For its **diaphoretic** action, antimony has been used to arrest commencing inflammations, such as catarrh, and to check febrile conditions. For this purpose it is not unfrequently given as tartar emetic in doses of $\frac{1}{16}$ grain frequently repeated, or as James's powder. In acute dropsy it appears to be occasionally useful, especially as a diaphoretic, in combination with bitartrate of potash and squills.

PREPARATIONS CONTAINING ANTIMONY.

B.P.	U.S.P.
Antimonii Oxidum.	Antimonii et Potassii Tartras.
Antimonium Nigrum.	,, Oxidum.
,, Sulphuratum.	Antimonii Sulphidum.
,, Tartaratum.	,, ,, Purificatum.
Liquor Antimonii Chloridi.	,, Sulphuratum.
Pilula Hydrargyri Subchloridi Composita.	Pilulæ Antimonii Compositæ.
Pulvis Antimonialis.	Pulvis Antimonialis.
Unguentum Antimonii Tartarati.	Syrupus Scillæ Compositus.
Vinum Antimoniale.	Vinum Antimonii.

Antimonium Nigrum, B.P.; Antimonii Sulphidum, U.S.P. BLACK ANTIMONY, B.P.; SULPHIDE OF ANTIMONY, U.S.P.—Native sulphide of antimony, Sb_2S_3; 336; purified from siliceous matter by fusion, and afterwards reduced to fine powder.

CHARACTERS AND TESTS.—A greyish-black crystalline powder. It dissolves almost entirely in boiling hydrochloric acid, evolving sulphuretted hydrogen. H_2O added to the solution precipitates a white oxychloride.

PREPARATIONS IN WHICH BLACK ANTIMONY IS USED.

B.P.	U.S.P.
Antimonium Sulphuratum	Antimonii Sulphidum Purificatum.
Liquor Antimonii Chloridi	

This is the ore from which the other compounds are prepared. It seems to be inert, and is not used internally.

U.S.P. Antimonii Sulphidum Purificatum. PURIFIED SULPHIDE OF ANTIMONY. Sb_2S_3; 336.

PREPARATION.—The crude sulphide is obtained in very fine powder by elutriation, then digested with ammonia to remove arsenic, washed and dried.

CHARACTERS.—A dark grey powder, odourless and tasteless, and insoluble in water or alcohol. It fuses at a temperature below red-heat. When boiled with ten parts of hydrochloric acid it is nearly all dissolved, hydrosulphuric acid being evolved. The solution when added to water yields a white precipitate which is soluble in a solution of tartaric acid. After separation of the precipitate by filtration, the filtrate gives an orange-red precipitate with hydrosulphuric acid.

IMPURITIES.—Other sulphides and arsenic.

TESTS.—If 2 Gm. of the salt be mixed and cautiously ignited in a porcelain crucible with 8 Gm. of pure nitrate of sodium, and the fused mass boiled with 25 Gm. of water, there will remain a residue which should be white or nearly so, and not yellowish or brownish (absence of other metallic sulphides). On boiling the filtrate with an excess of nitric acid until no more nitrous vapours are evolved, then dissolving in it 0·1 Gm. of nitrate of silver, filtering again if necessary, and cautiously pouring a few drops of water of ammonia on top, not more than a white cloud, but no red nor reddish precipitate should appear at the line of contact of the two liquids (absence of more than traces of arsenic).

PREPARATION.
Antimonium Sulphuratum.

Antimonium Sulphuratum, B. and U.S.P. SULPHURATED ANTIMONY.

B.P. Sulphide of antimony, Sb_2S_3; 336; with a small and variable amount of oxide of antimony, Sb_2O_3.

U.S.P. Chiefly antimonious sulphide, Sb_2S_3; 336; with a very small amount of antimonious oxide.

PREPARATION.—By boiling black sulphide with caustic soda the sulphide is partly converted into oxide and partly unites with sodium, forming sulphantimonite and antimonite of sodium.

Sulphide of Antimony. Soda. Sulphantimonite of Sodium. Oxide of Antimony.

$$2Sb_2S_3 + 6NaHO = 2Na_3SbS_3 + Sb_2O_3 + 3H_2O,$$

and

Oxide of Antimony. Soda. Antimonite of Sodium.

$$Sb_2O_3 + 6NaHO = 2Na_3SbO_3 + 3H_2O.$$

These antimony compounds are soluble in caustic soda, but when this is neutralised they are precipitated, the greater part of them being decomposed and the Sb_2O_3 reconverted into Sb_2S_3

Sulphantimonite of Sodium. Sulphuric Acid. Sodium Sulphate. Sulphate of Antimony.

$$2Na_3SbS_3 + 3H_2SO_4 = 3Na_2SO_4 + Sb_2S_3 + 3H_2S.$$

Antimonite of Sodium.

$$2Na_3SbO_3 + 3H_2SO_4 = 3Na_2SO_4 + Sb_2O_3 + 3H_2O.$$

CHARACTERS AND TESTS.—B.P. An orange-red powder, readily dissolved by caustic soda, also by hydrochloric acid with the evolution of sulphuretted hydrogen and the separation of a little sulphur. Boiled in water with acid tartrate of potash it dissolves, and the resulting solution is precipitated orange-red with sulphuretted hydrogen.

U.S.P. A reddish-brown, amorphous powder, odourless and tasteless, and insoluble in water and in alcohol. When heated with 12 parts of hydrochloric acid, it is nearly all dissolved with evolution of hydrosulphuric acid. The residue, after having been washed and dried, burns, on the application of a flame, with the characteristic odour of sulphur, and should leave not more than a scanty ash. On dropping a solution of sulphurated antimony in hydrochloric acid into water, a white precipitate is produced, which, after washing and drying, should weigh not less than 85 per cent. of the sulphide. The liquid filtered from this precipitate yields an orange-red precipitate with hydrosulphuric acid.

Distilled water boiled with sulphurated antimony, filtered and acidulated with hydrochloric acid, should be rendered not more than slightly opalescent by test-solution of chloride of barium (limit of sulphate).

DOSE.—1 to 5 grains.

PREPARATIONS.

B.P.

Pilula Hydrargyri Subchloridi Composita (Plummer's pill) (p. 621) ..... 1 part in 5.

U.S.P.

Pilulæ Antimonii Composita (Plummer's pill) (p. 621) ..... 1 part in 4.

The oxide it contains is probably the active part, and as this is variable the action is rather uncertain.

Liquor Antimonii Chloridi, B.P. SOLUTION OF CHLORIDE OF ANTIMONY.

PREPARATION.—By boiling black antimony with hydrochloric acid, $Sb_2S_3 + 6\ HCl = 2\ SbCl_3 + 3\ H_2S$.

CHARACTERS AND TESTS.—A heavy liquid usually of a yellowish-red colour. A little of it dropped into water gives a white precipitate, and the filtered solution lets fall a copious deposit on the addition of nitrate of silver. If the white precipitate formed by water be treated with sulphuretted hydrogen it becomes orange-coloured. The specific gravity of the solution is 1·47. One fluid drachm of it mixed with a solution of a quarter of an ounce of tartaric acid in four fluid ounces of water, forms a clear solution, which, if treated with sulphuretted hydrogen, gives an orange precipitate, weighing, when washed and dried at 212°, at least 22 grains.

PREPARATION IN WHICH SOLUTION OF CHLORIDE OF ANTIMONY IS USED.
Antimonii Oxidum.

USES.—Is a powerful caustic—sometimes applied to cancers and to poisoned wounds.

Antimonii Oxidum, B. and U.S.P. OXIDE OF ANTIMONY. Sb_2O_3; 288.

PREPARATION.—By pouring solution of chloride of antimony into water and treating the precipitate of oxychloride with sodium carbonate.

Chloride of Antimony. — Oxychloride of Antimony. — Hydrochloric Acid.

$$12SbCl_3 + 15H_2O = 2SbCl_3{,}5Sb_2O_3 + 30HCl.$$

Oxychloride of Antimony. — Carbonate of Sodium. — Oxide of Antimony. — Sodium Chloride.

$$2SbCl_3{,}5Sb_2O_3 + 3Na_2CO_3 = 6Sb_2O_3 + 6NaCl + 3CO_2.$$

CHARACTERS AND TESTS.—A greyish-white powder, fusible at a low red-heat, insoluble in water, but readily dissolved by hydrochloric acid. The solution, dropped into distilled water, gives a white deposit, at once changed to orange by sulphuretted hydrogen. It dissolves entirely when boiled with an excess of the acid tartrate of potash.

DOSE.—1 to 4 grains.

PREPARATIONS.

B. AND U.S.P.		DOSE.
Pulvis Antimonialis.	Antimonial powder or James's powder (one part of oxide of antimony with two of phosphate of lime)	3-10 grs.

USES.—Oxide of antimony may be used for the same purposes as tartar emetic, but it is not soluble in water, and it depends very much on the state of the stomach how much of it will be dissolved. It is therefore less certain in its action than tartar emetic and the latter is consequently to be preferred. In consequence of its insolubility it is said to be slower and milder than tartar emetic, but this advantage is more than counterbalanced by its uncertainty.

James's powder is given as an antipyretic in fever and rheumatism. It is also given in chronic skin diseases along with mercury.

Antimonium Tartaratum, B.P.; Antimonii et Potassii Tartras, U.S.P. TARTARATED ANTIMONY, B.P.; TARTRATE OF ANTIMONY AND POTASSIUM, U.S.P.

$KSbC_4H_4O_7.H_2O$, B.P.; $2KSbOC_4H_4O_6.H_2O$; 664, U.S.P.—A tartrate of potash and antimony.

PREPARATION.—By boiling acid tartrate of potash and oxide of antimony together, $2KHC_4H_4O_6 + Sb_2O_3 = 2K(SbO)C_4H_4O_6 + HO$.

CHARACTERS AND TESTS.—In colourless transparent crystals exhibiting triangular facets, soluble in water, and less so in proof spirit. It decrepitates and blackens upon the application of heat (tartrate). Its solution in water gives with hydrochloric acid a white precipitate, soluble in excess, and which is not formed if tartaric acid be previously added.

DOSE.—As a diaphoretic $\frac{1}{16}$ to $\frac{1}{6}$th of a grain; as an emetic, 1 to 2 grains. Of the wine as a diaphoretic, 10 to 40 min.; as an emetic for children, $\frac{1}{2}$ to 1 fl. dr. repeated frequently.

PREPARATIONS.

B.P.	STRENGTH.
Unguentum Antimonii Tartarati ..... (with simple ointment.)	1 part in 5.
Vinum Antimoniale. Antimonial Wine ...	2 gr. in 1 fl. oz. of sherry.
U.S.P.	DOSE.
Syrupus Scillæ Compositus.....	5 min.—1 fl. dr.
Vinum Antimonii. Wine of Antimony...	4 parts in 60 of water and stronger white wine up to 1,000.

USE.—This preparation of antimony is readily soluble, and as the proportion of the dose administered which actually takes effect is more constant than that of the other preparations of antimony, it has gradually displaced them. For its uses *vide* p. 653.

Tartar emetic ointment has been used as a counter-irritant in cases of neuralgia, paralysis of children, enlarged joints, acute meningitis, laryngitis, acute bronchitis, hooping-cough, phthisis, asthma, angina pectoris, and subacute ovaritis. For many of these purposes the application of iodine preparations is now preferred.

BISMUTH. Bi; 210.

Bismuth forms three classes of compounds in which it is bi- tri- and quinqui-valent respectively.

GENERAL ACTION.—The soluble salts of bismuth, such as the citrate of bismuth and ammonia, when given in large doses have an action like that of antimony or arsenic and cause gastro-enteritis with fatty degeneration of the liver. Small doses of soluble preparations, or larger doses of sparingly soluble preparations, have a sedative effect on the stomach like that of minute doses of arsenic.

The subnitrate is so sparingly soluble that its utility in gastric catarrh is probably due to its mechanical action, like charcoal (p. 478) or binoxide of manganese.

GENERAL SOURCES.—It is found native in the metallic state.

GENERAL REACTIONS.—It is distinguished by the white precipitate which falls on throwing a solution of the nitrate or chloride into water, and the blackening of this by sulphuretted hydrogen.

GENERAL PREPARATION OF SALTS OF BISMUTH.

SALT	PREPARED FROM	BY
Sub-nitrate, B. and U.S.P.	Bismuth.	Dissolving in nitric acid, throwing the solution into a large quantity of water, collecting and drying the precipitate.
Carbonate, B.P.; Sub-carbonate, U.S.P.	Do.	Dissolving in nitric acid, evaporating to a small bulk and adding to solution of ammonium carbonate.
Oxide, B.P.	Subnitrate.	Boiling with solution of soda.
Citrate, U.S.P.	Do.	Boiling with citric acid and washing with a large quantity of water, when insoluble citrate is formed.
Solution of citrate of bismuth and ammonia, B.P.	Bismuth.	Dissolving in nitric acid as for subnitrate, evaporating to a small bulk, adding citric acid, and adding ammonia until the precipitate of citrate is redissolved and the liquid is neutral or slightly alkaline.
Citrate of bismuth and ammonia, U.S.P.	Citrate of bismuth.	Mixing the citrate to a smooth paste with water and adding ammonia until it is dissolved and the liquid is neutral or faintly alkaline.

USES.—Subnitrate of bismuth is used under the name of Spanish or pearl white to whiten the complexion, and as a dusting powder, lotion, or ointment to chapped nipples and hands, abraded surfaces and chronic oozing from the skin, as eczema, in order to take up moisture and allay smarting and itching.

It has also been employed externally as an application in scaly diseases, and in intertrigo. From its power of diminishing the irritability of mucous membranes it was applied by Ferrier, along with morphia in the form of a snuff to arrest nasal catarrh, and has been used as an injection in ozœna, leucorrhœa, and gonorrhœa to diminish the irritability. It is applied as a local sedative to diminish the pain, nausea, or vomiting in irritable dyspepsia, and to lessen the irritability of

the intestine in diarrhœa and dysentery. It is very serviceable, either alone or combined with lime or alkalis in the gastro-intestinal catarrh caused by cold, which is commonly known as cold in the stomach, as well as in the same affection occurring in children at the period of dentition.

It is useful in pyrosis, gastralgia and vomiting, whether the vomiting be from ulcer of the stomach or other causes. It acts remarkably well in the indigestion and pain in the stomach caused by the use of alcohol. In such cases it is best given with a little magnesia, about ten grains of the subnitrate with an equal quantity of magnesia or its carbonate.

The carbonate of bismuth is more soluble in the gastric juice than the subnitrate, and is supposed to be more powerful, and the same advantage, if advantage it be, is possessed by the citrate of ammonia and bismuth. My own experience leads me to prefer the less soluble subnitrate to either of the other preparations.

B.P. Bismuthum. BISMUTH.—A crystalline metal. As met with in commerce it is generally impure.

PREPARATION.—Bismuthum Purificatum.

B.P. Bismuthum Purificatum. PURIFIED BISMUTH.

PREPARATION.—By fusing with nitrate of potash.

CHARACTERS.—A crystalline metal of a greyish-white colour, with a distinct roseate tinge. Specific gravity 9·83. Dissolved in a mixture of equal volumes of nitric acid and distilled water, it forms a solution which by evaporation yields colourless crystals, that are decomposed on the addition of water, giving a white precipitate.

IMPURITIES.—Iron and copper.

TEST.—If the mother liquor from which the crystals have been separated be added to solution of carbonate of ammonia, the precipitate formed and the solution are free or nearly free from colour.

PREPARATIONS CONTAINING BISMUTH.

B.P.	U.S.P.
Bismuthi Carbonas.	Bismuthi Carbonas.
,, Subnitras.	,, Citras.
Liquor Bismuthi et Ammoniæ Citratis.	,, et Ammonii Citras.
Trochisci Bismuthi.	,, ,, Citratis Liquor.
	,, Subnitras.

Bismuthi Subnitras, B. and U.S.P. SUBNITRATE OF BISMUTH. $BiNO_4.H2O$, B.P.; $BiONO_3.H_2O$; 306, U.S.P.

CHARACTERS AND TESTS.—A heavy white powder in minute crystalline scales, blackened by sulphuretted hydrogen; insoluble in water, but soluble in nitric acid mixed with half its volume of distilled water, forming a solution which poured into water gives a white precipitate. It forms with sulphuric acid diluted with an equal bulk of water a solution which is blackened by sulphate of iron (nitrate). The nitric acid solution gives no precipitate with

diluted sulphuric acid (no lead) nor with solution of nitrate of silver (no chloride).

IMPURITIES.—Lead, nitrates, chlorides.

DOSE.—5 to 20 grains.

PREPARATION.

B.P.	DOSE.
Trochisci Bismuthi, 2 grs. in each lozenge.....	1 to 6 lozenges.

Bismuthi Carbonas, B.P.; Bismuthi Subcarbonas, U.S.P. CARBONATE OF BISMUTH, B.P.; SUBCARBONATE OF BISMUTH, U.S.P. $2(Bi_2CO_5).H_2O$, B.P.; $(BiO)_2CO_3.H_2O$; 530, U.S.P.

CHARACTERS AND TESTS.—A white powder, blackened by sulphuretted hydrogen; insoluble in water, but soluble with effervescence in nitric acid. The solution gives the reactions of bismuth.

IMPURITIES.—Nitrate.

TEST.—When added to sulphuric acid coloured with sulphate of indigo the colour of the latter is not discharged.

DOSE.—5 to 20 grains.

B.P. Liquor Bismuthi et Ammoniæ Citratis. SOLUTION OF CITRATE OF BISMUTH AND AMMONIA.

CHARACTERS.—A colourless solution with a saline and slightly metallic taste. Neutral or slightly alkaline to test paper; mixes with water without change. It gives the reactions of ammonia and bismuth. One fluid drachm contains 3 grains of oxide of bismuth.

DOSE.—$\frac{1}{2}$ to 1 fluid drachm.

U.S.P. Bismuthi Citras. CITRATE OF BISMUTH. $BiC_6H_5O_7$; 399.

CHARACTERS.—A white amorphous powder, permanent in the air, odourless and tasteless, insoluble in water or alcohol, but soluble in water of ammonia.

USES.—Not given internally, but used to prepare the solution with ammonia.

PREPARATION.—Bismuthi et Ammonii Citras.

U.S.P. Bismuthi et Ammonii Citras. CITRATE OF BISMUTH AND AMMONIUM.

CHARACTERS.—Small, shining, pearly or translucent scales, becoming opaque on exposure to air, odourless, having a slightly acidulous and metallic taste, and a neutral or faintly alkaline reaction. The aqueous solution of the salt gives the reaction of bismuth, of ammonia and of a citrate.

DOSE.—2 to 4 grains.

USES.—The solution of bismuth and ammonia, B.P., and the soluble salt, U.S.P., are more astringent and irritant in their action than the insoluble subnitrate, oxide, or carbonate. They may be used as astringents but are inferior to the insoluble preparations as a means of allaying irritation.

CHAPTER XXVIII.

Class VIII.

GROUP I.

Iron—*Nickel*—*Cobalt*—Manganese.

FERRUM; IRON; Fe; 55·9.

Metallic iron in the form of fine, bright, and non-elastic wire.

Iron forms ferrous salts in which it is bivalent, *e.g.* $FeCl_2$ or $FeSO_4$, and ferric, in which it is either trivalent or quadrivalent. Ferric chloride may be regarded as $FeCl_3$ or as Fe_2Cl_6, in which each of two atoms of quadrivalent iron have one affinity saturated by union with each other, and the other three by chlorine, $Cl_3-Fe-Fe-Cl_3$.

GENERAL SOURCES.—It is found native in the metallic state, and also as oxide, sulphide, chloride, carbonate, phosphate, sulphate, and arseniate. It is obtained from its ores by smelting with coke and clay or limestone.

GENERAL REACTIONS.—These are shown in the accompanying table. The reactions most generally mentioned in the pharmacopœias are those with ferrocyanide and ferricyanide of potassium. It is to be remembered that a preparation of iron containing it in both the ferrous and ferric condition or which, by its decomposition, yields iron in these two states gives a precipitate with both of these reagents. The arseniate of iron, B.P., magnetic oxide, and the citrate of iron and quinine are examples of this.

GENERAL REACTIONS OF IRON SALTS.

REAGENT.	FERROUS SALTS.	FERRIC SALTS.
Hydrogen sulphide.	No precipitate.	White precipitate of sulphur (the ferric are reduced to ferrous).
Ammonium sulphide	Black precipitate.	Black precipitate.
Caustic alkalis and ammonia.	Nearly white precipitates of ferrous hydrate rapidly becoming green, and then brown.	Foxy-red precipitates of ferric hydrate.
Carbonates of ditto.	Whitish precipitate of ferrous carbonate which changes like the hydrate.	Foxy-red precipitates. Carbonic acid escapes.
Potassium ferrocyanide.	Nearly white precipitate becoming blue on exposure	Deep blue precipitate (Prussian blue).*
Potassium ferricyanide.	Deep blue precipitate.	No precipitate. Dark coloration.
Tincture of galls.		Intense black.

GENERAL IMPURITIES.—Zinc, copper, and fixed alkalis may be present in its salts. Ferrous salts may be present as impurities in ferric and *vice versâ*.

TESTS.—The test used for the chloride in the U.S.P. is as follows:—If the iron be completely precipitated from a solution of the salt by an excess of water of ammonia the filtrate should not yield either a white precipitate (absence of zinc) or a dark-coloured precipitate with hydrosulphuric acid (absence of copper), nor should it leave a fixed residue on evaporation and gentle ignition. The absence of ferrous salts as impurities in ferric is ascertained by their giving no precipitate with ferricyanide of potassium. The absence of ferric salts as an impurity in ferrous is ascertained by the precipitate not being blue at first, but nearly white, and only becoming blue on exposure.

GENERAL PREPARATION OF SALTS OF IRON.

	PREPARED FROM	BY
Ferrous Sulphate (p. 667)	Iron.	Dissolving in sulphuric acid.
Dried Sulphate (p. 668)	Ferrous sulphate.	Heating to drive off water of crystallisation.

* With the tartrate of iron and ammonia (U.S.P.) no colour nor precipitate is produced unless the solution is acidulated with hydrochloric acid.

GENERAL PREPARATION OF SALTS OF IRON—*continued.*

	PREPARED FROM	BY
Granulated, B.P., or Precipitated, U.S.P. (p. 668)	Ferrous sulphate.	Pouring an aqueous solution into spirit.
Carbonate (Saccharated) (p. 668)	Do.	Decomposing (by ammonium carbonate, B.P.), (by sodium bi-carbonate, U.S.P.), and mixing with sugar.
Do. (Mistura Ferri Composita) (p. 668)	Do.	Decomposing by potassium carbonate and mixing with myrrh, &c.
Ferric Sulphate, B.P. (p. 669) ,, Tersulphate, U.S.P. (p.669)	Do.	Adding sulphuric acid and oxidising by heating with nitric acid. ($6FeSO_4 + 3H_2SO_4 + 2HNO_3 = 3Fe_2(So_4)_3 + 4H_2O + N_2O_2$).
,, Subsulphate (p. 669)		Do. using too little sulphuric acid to form tersulphate.
,, Oxide (p. 669)	Ferric sulphate.	Mixing with magnesia and water, U.S.P.
,, Do. (Humid, B.P., Hydrated, U.S.P.) (p.669)	Do.	Pouring the diluted solution into solution of soda, B.P.
,, Do. Hydrated, B.P. (p. 670)	Do.	Pouring the diluted solution into solution of soda, B.P.; and drying below 212°.
,, Do. Magnetic (p. 670)	Do. and ferrous sulphate.	Pouring the diluted solution into solution of soda, B.P.
Reduced Iron (p. 670)	Ferric oxide.	Passing hydrogen over it while heated ($Fe_2O_3 + 6H = F_2 + 3H_2O$).
Ferric Chloride (p. 671)	Iron.	Dissolving in hydrochloric acid and oxidising by nitric acid. ($3Fe_2 + 12HCl = 6FeCl_2 + 12H - 6FeCl_2 + 6HCl + 2HNO_3 = 3Fe_2Cl_6 + 4H_2O + N_2O_2$).
,, Nitrate (p.673)	Iron.	Dissolving in nitric acid ($Fe_2 + 8HNO_3 = Fe_2(NO_3)6 + 4H_2O + N_2O_2$).
,, Acetate (Tincture of, B.P.) (p. 671)	Ferric sulphate.	Decomposing an alcoholic solution of acetate of potash, by a solution of ferric sulphate and separating the potassium sulphate by filtration.
,, Do. (Solution of), U.S.P. (p. 671)	Do. Tersulphate.	Precipitating ferric oxide by ammonia, washing, and dissolving in glacial acetic acid, and diluting to the necessary strength.
,, Citrate (p.674)	Do. (Tersulphate).	Precipitating oxide by ammonia, washing and dissolving in citric acid. This forms the Liquor Ferri Citratis, U.S.P. Ferri Citras is prepared by evaporation of the Liquor under 60° C.

GENERAL PREPARATION OF SALTS OF IRON—*continued.*

	PREPARED FROM	BY
Tartrate of iron and potassium, U.S.P. (Ferrum Tartratum, B.P.) (p. 673)	Persulphate.	Precipitating ferric oxide by ammonia, washing and mining with acid tartrate of potash.
Tartrate of iron and ammonia (p. 673)	Do.	Do. using tartaric acid and tartrate of ammonium in place of acid tartrate of potash.
Citrate of iron and ammonia (p. 674)	Do.	Do. using citric acid and ammonia.
Citrate of iron and quinine (p. 674)	Do. and sulphate of quinine.	Precipitating ferric oxide and quinine by ammonia and dissolving it in citric acid.
Citrate of iron and strychnine (p. 675)	Ferric sulphate and strychnine.	Precipitating ferric oxide by ammonia and dissolving it along with strychnine in citric acid.
Sulphate of iron and ammonia (p. 675)	Ferric sulphate and ammonium sulphate	Heating them together.
Ferrous Lactate (p. 675)	Iron.	Dissolving in lactic acid.
Ferrous Oxalate (p. 676)	Ferrous sulphate.	Precipitating a solution with oxalic acid (ferrous oxalate is very slightly soluble).
Ferrous Iodide (p. 676)	Iron.	Heating with iodine and water. (The completion of the process is recognised by the brown colour of the iodine disappearing and the froth becoming white.)
,, Do. Syrup of (p. 676)	Do.	Same as ferrous iodide, and then adding sugar.
,, Bromide (Syrup of) (p. 676)	Do.	Same as syrup of iodide, using bromine instead of iodine.
Arseniate of iron (p. 677)	Ferrous sulphate, arseniate of soda, and acetate of soda.	Mixing a solution of arseniate and acetate of soda with one of ferrous sulphate. If arseniate of soda alone were used, free sulphuric acid would be formed, which would react on the arseniate $3FeSo_4 + 2Na_2HAsO_4 = Fe_3As_2O_8 + 2Na_2SO_4 + H_2SO_4$. To avoid this acetate of soda is added. The sulphuric acid combines with the soda and sets free acetic acid which has no action on the arseniate of iron. $3FeSO_4 + 2Na_2HAsO_4 + 2NaC_2H_3O_2 = Fe_3AsO_8 + 3Na_2SO_4 + 2HC_2H_3O_2$.

GENERAL PREPARATION OF SALTS OF IRON—*continued*.

	PREPARED FROM	BY
Phosphate of iron (p. 677)	Ferrous sulphate, phosphate of soda, and acetate of soda.	The same process as in the preparation of arseniate. The reactions are similar. $3FeSO_4 + 2Na_2HPO_4 + 2NaC_2H_3O_2 = Fe_3P_2O_8 + 3NaSO_4 + 2HC_2H_3O_2$.
Pyrophosphate of iron (p. 677)	Citrate of iron.	Decomposing solution by solution of sodium pyrophosphate.
Hypophosphite of iron (p. 678)	Ferrous sulphate.	Decomposing by hypophosphite of calcium when ferrous hypophosphite is precipitated, but on evaporation becomes ferric.
Valerianate of iron (p. 678)	Ferric sulphate.	Decomposing by valerianate of soda.

GENERAL ACTION OF IRON SALTS.—Iron differs from most of the other heavy metals in forming a normal constituent of the animal body, so that it may be regarded as a food as well as a medicine. It forms an important constituent of the hæmoglobin in the blood. This acts as the oxygen carrier to the tissues, and, therefore, the tissue-oxidation and the functional activity of the organs depend more or less upon the amount of iron present in the body. Both per- and proto-salts of iron form compounds with **albumen,** but they differ in their properties. The ferrous salts give a yellow colour with albuminous solutions, but do not precipitate them, the albuminous compound being, apparently, usually soluble. Diluted ferric salts, on the contrary, precipitate albumen slowly, and concentrated solutions precipitate it rapidly. The precipitate is soluble in dilute acids and in gastric juice.

When applied to the **skin** neither ferrous nor ferric salts have any action, as they do not dissolve the epidermis nor pass through it in any appreciable quantity. When applied to a denuded surface, or to a mucous membrane they combine with albumen. The ferrous salts have but a slight astringent action, whereas the ferric salts coagulate the albumen on the surface and also blood. They are thus powerful astringents and styptics. In the **mouth** they all have an inky taste, and as they are liable to form black sulphides with sulphurated hydrogen, which is not unfrequently present in the breath, they are apt to discolour the teeth or tongue. In the **stomach** they have an astringent and irritant action, that of the ferric being more powerful than that of the ferrous salts. In the **intestine** they have a somewhat similar action; meeting here as they often do, with sulphurated hydrogen they become converted, in great part, into sulphides, and, passing out into the stools, give to them an inky, black colour which sometimes alarms

patients. In small doses they usually have an astringent action, and tend to cause constipation. Larger doses, on the other hand, seem to stimulate peristalsis, and increase the number of stools, and sometimes even small doses will cause diarrhœa in some individuals. After absorption into the **blood** they are found to increase, not only the number, but the percentage of hæmoglobin contained in the blood corpuscles, and they may also cause a little free iron to be present in the serum. By thus increasing oxidation in the **tissues** they increase the functional activity of the various organs. The effect of ferrous and ferric salts added to the blood is very different, ferric salts producing a firm coagulum, whereas the ferrous salts tend rather to diminish the coagulability of the blood.

Iron has an action on the **nervous system** which varies according to the dose and mode of administration. When injected subcutaneously in **frogs,** iron salts cause slight excitement and then paralysis of the central nervous system. In the later stages of poisoning the irritability of the voluntary muscles is diminished, but the heart is not affected. In mammals they cause congestion of the stomach and intestine, and **diarrhœa.** They produce **paralysis** both of sensation and motion. The **blood-pressure** falls. This is due to paralysis of the **vaso-motor nerves,** especially of the intestine, resembling that produced by arsenic, antimony, emetine, and colchicine.

Iron is **eliminated** to a considerable extent by the bile, by the mucous membrane of the intestine, and by the kidneys.

USES OF IRON.—The ferrous salts are rarely employed for their local action. The ferric salts are used as styptics. The strong solution of perchloride may be employed to arrest bleeding from the cavity of a tooth after extraction, or to stop the oozing from a wound where it is impossible to ligature all the bleeding points. When diluted it may be used as an injection to arrest hæmorrhage from the nose, or may be injected into the cavity of the uterus to arrest bleeding from that organ. Mixed with laudanum it has been used as an injection in gonorrhœa and gleet. Both ferrous and ferric salts are administered internally in order to produce the general action of iron in increasing the blood corpuscles. They differ to some extent, however, the ferrous salts having a less astringent action on the intestines than the ferric. In cases where the mucous membrane of the alimentary canal is irritable this is advantageous, as in such instances the ferric salts might cause digestive disturbances and headache. In other instances, however, especially those where the tongue is pale and flabby, the more astringent preparations are to be preferred. The chief condition in which iron is useful is where we have anæmia and chlorosis, whether these be due to loss of blood, imperfect nutrition, chronic discharges, scrofula, syphilis, malarial poisoning, amenorrhœa or albuminuria, or be consequent upon acute febrile

disease, but it is also serviceable in a number of disturbances of the nutritive and nervous systems. It has been recommended in large doses in cases of blood-poisoning, such as diphtheria and erysipelas, and in nervous diseases like chorea, epilepsy, giddiness, formication, twitching of the fingers and subjective sensations of light and heat or cold to which some patients are liable, especially about the climacteric period. It is also used internally in order to diminish discharges from the mucous membranes of the intestines, as in chronic diarrhœa and dysentery, and from the vagina in leucorrhœa. It acts as an astringent on the kidney, lessening the amount of blood in hæmaturia, and sometimes the amount of albumen in albuminuria. It is also a useful adjunct to diuretics in cardiac and renal dropsy (p. 295).

B.P. Vinum Ferri.—This is prepared by macerating iron wire in sherry for a month. Some of it is converted into tartrate and dissolved by the bitartrate of potash in the wine.

USE.—It is useful in anæmia both in children and adults.

DOSE.—1 to 2 fl. dr. or more.

B.P. Mistura Ferri Aromatica.—This is a curious preparation containing tannate of iron in very small quantities. It is sometimes called Heberden's ink. It is usually said that iron and tannin are incompatible, and so they are in so far that they produce ink, but this preparation is said to be a very useful one.

Iron cannot be taken up in very large quantities, and its absorption is often prevented by the condition of the patient's stomach. This preparation has been put together evidently with the view of combining all the drugs, which were likely to do good by themselves, and in total disregard of the chemical action which would take place among themselves.

PREPARATION.—By macerating pale cinchona bark (1 oz.), calumba root ($\frac{1}{2}$ oz.), cloves ($\frac{1}{4}$ oz.), and fine iron wire ($\frac{1}{2}$ oz.), in peppermint water (12 oz.) for three days, agitating occasionally; then filtering and adding as much peppermint water to the filter as will make the product measure $12\frac{1}{2}$ fl. oz.; to this add compound tincture of cardamoms (3 fl. oz.) and tincture of orange peel ($\frac{1}{2}$ fl. oz.), and preserve the mixture in a well stopped bottle. The pale cinchona bark contains tannin, which combines with the iron. Both it and calumba are gastric tonics, and the carminatives relieve flatulence.

DOSE.—1 to 2 fl. oz.

Ferri Sulphas, B. and U.S.P. SULPHATE OF IRON. $FeSO_4.7H_2O$; 277·9.

CHARACTERS AND TESTS.—In oblique rhombic prisms, of a pale greenish blue colour and styptic taste; insoluble in rectified spirit, soluble in water. The aqueous solution gives the reaction of a sulphate and of a ferrous salt.

DOSE.—1 to 5 grains.

PREPARATIONS.

B.P.	U.S.P.
Ferri Sulphas Exsiccata.....	Ferri Sulphas Exsiccata.
Pilula Aloes et Ferri ..... 1 part in 7.	

Ferri Sulphas Exsiccata, B.P.; Ferri Sulphas Exsiccatus, U.S.P. DRIED SULPHATE OF IRON. $FeSO_4.H_2O$; 169·9.

Prepared by heating sulphate. It is less apt to oxidise, and is well fitted for pills.

DOSE.—$\frac{1}{2}$ grain to 3 grains.

PREPARATION.

U.S.P.

Pilulæ Aloes et Ferri.

Ferri Sulphas Granulata, B.P.; Ferri Sulphas Precipitatus, U.S.P. GRANULATED SULPHATE OF IRON, B.P. PRECIPITATED SULPHATE OF IRON, U.S.P. $FeSO_4.7H_2O$; 277·9.

CHARACTERS AND TESTS.—In small granular crystals of a pale greenish blue colour. In other respects corresponds to the characters and tests for sulphate of iron.

DOSE.—1 to 5 grains.

USES.—It is very astringent. It has been used externally as ointment or lotion to the skin in erysipelas, as a lotion in ophthalmia, and as a lotion or injection in prolapsus ani, and bleeding piles. It has also been used as an injection in gonorrhœa and leucorrhœa.

Internally it is used in cases of anæmia, especially where this is accompanied by a tendency to profuse sweating, passive hæmorrhages, or mucous discharges, such as chronic catarrh or leucorrhœa. Its astringent action on the stomach has been said to render it serviceable in gastrodynia and gastric ulcer.

Ferri Carbonas Saccharata, B.P.; Saccharatus, U.S.P. SACCHARATED CARBONATE OF IRON, B.P.; SACCHARATED FERROUS CARBONATE, U.S.P.

Carbonate of iron, FeO,CO_2 or $FeCO_3$, mixed with peroxide of iron and sugar, the carbonate forming at least 37 per cent. of the mixture, B.P., 15 per cent., U.S.P.

CHARACTERS AND TESTS.—Small coherent lumps, or powder, of a grey colour with a sweet very feeble chalybeate taste. It dissolves with effervescence (carbonate) in warm hydrochloric acid diluted with half its volume of water, and the solution gives only traces of sulphate (p. 521) and exhibits the reactions of a ferrous salt.

DOSE.—5 to 20 grains.

PREPARATION.

B.P.	(with confection of roses.)	DOSE.
Pilula Ferri Carbonatis	1 part in $1\frac{1}{4}$	.....5-20 grs.

Mistura Ferri Composita, B. and U.S.P. COMPOUND MIXTURE OF IRON. GRIFFITH'S MIXTURE.

COMPOSITION.—Sulphate of iron, 25 grs.; carbonate of potash, 30 grs.; myrrh and refined sugar, of each 60 grs.; spirit of nutmeg, 4 fl. drs.; rose water, $9\frac{1}{2}$ fl. oz., B.P. Sulphate of iron, 6;

myrrh, 18; sugar, 18; carbonate of potassium, 8; spirit of lavender, 50; rose water, 900, U.S.P.

DOSE.—1 to 2 fluid ounces.

USES.—Carbonate of iron in its various preparations is one of the most useful forms of iron for administration as a hematinic and emmenagogue.

Liquor Ferri Persulphatis, B.P.; Tersulphatis, U.S.P. SOLUTION OF PERSULPHATE OF IRON, B.P.; OF TERSULPHATE, U.S.P. $Fe_2(SO_4)_3$; 399·8.

CHARACTERS AND TESTS.—A dense solution of a dark-red colour, inodorous and very astringent, miscible in all proportions with alcohol and water. Diluted with ten volumes of water, it gives the reactions of a sulphate and of a ferric salt only.

PREPARATIONS IN WHICH SOLUTION OF PERSULPHATE OF IRON IS USED.

Ferri et Ammoniæ Citras	Ferri Peroxidum humidum
,, et Quiniæ Citras	Ferrum Tartaratum
,, Oxidum magneticum	Tinctura Ferri Acetatis.

USES.—Not used as a remedy, but to prepare peroxide, &c.

U.S.P. Liquor Ferri Subsulphatis. SOLUTION OF SUBSULPHATE OF IRON. SOLUTION OF BASIC FERRIC SULPHATE. (MONSEL'S SOLUTION.)

CHARACTERS.—Like the tersulphate; but on mixing two volumes of the solution with one of concentrated sulphuric acid a solid white mass separates on standing.

DOSE.—3 to 10 minims (·18—·64 c.c.).

ACTIONS.—Astringent, styptic, hæmatinic. Less irritating than the tersulphate.

USES.—Like the chloride. It is a useful astringent in relaxed sore throat and tonsillitis.

Ferri Peroxidum Humidum, B.P. MOIST PEROXIDE OF IRON. Hydrated peroxide of iron with about 86 per cent. of uncombined water. It should be recently made, B.P.

Ferri Oxidum Hydratum, U.S.P. HYDRATED OXIDE OF IRON. $Fe_2(HO)_6$; 213·8.

CHARACTERS AND TESTS.—A soft, moist, pasty mass, of a reddish-brown colour. Dissolves readily in diluted hydrochloric acid, and gives the reaction of a ferric salt only.

DOSE.—$\frac{1}{4}$ to $\frac{1}{2}$ ounce.

USE.—As an antidote for arsenic, it should be given in doses of a tablespoonful every five or ten minutes. It may be used in anæmia and amenorrhœa.

PREPARATIONS.

U.S.P. Emplastrum Ferri (Hydrated oxide dried, with Canada turpentine, Burgundy pitch, and lead plaster).

U.S.P. Trochisci Ferri (Troches of iron). Iron lozenges, 5 grs. in each lozenge.

U.S.P. Ferri Oxidum Hydratum cum Magnesia. HYDRATED OXIDE OF IRON WITH MAGNESIA.—Antidote to arsenious acid.

PREPARATION.—Mix solution of tersulphate of iron 1000 grs. (65·00 gm.) with twice its weight of water. Rub the magnesia, 150 grains (10·00 gm.) with water to a smooth and thin mixture; transfer this to a bottle capable of holding 32 fl. oz., or about 1 litre, and fill it up with water. When the preparation is wanted for use, mix the two liquids by adding the magnesia mixture gradually to the iron solution, and shake them together until a homogeneous mass results.

NOTE.—The diluted solution of tersulphate of iron and the mixture of magnesia with water should always be kept on hand, ready for immediate use.

USE.—As an antidote in poisoning by arsenic.

B.P. Ferri Peroxidum Hydratum. HYDRATED PEROXIDE OF IRON.

CHARACTERS.—A reddish-brown powder, destitute of taste and not magnetic. It dissolves completely, though slowly, with the aid of heat, in hydrochloric acid, diluted with half its volume of water, and the solution gives the reactions of a ferric salt only.

DOSE.—5 to 30 grains.

B.P. PREPARATION.

Emplastrum Ferri. IRON PLASTER.—Hydrated peroxide of iron in fine powder, Burgundy pitch, and lead plaster.

USES.—Not astringent. Given in powder or electuary chiefly in cases of tic and neuralgia.

Iron plaster is often called "strengthening plaster." It forms a mechanical support to weak parts and keeps them warm. Used in pains or weakness across the loins in females, in rheumatic pains, as lumbago, weak joints, &c.

B.P. Ferri Oxidum Magneticum. MAGNETIC OXIDE OF IRON.—Magnetic oxide of iron, Fe_3O_4, combined with about 20 per cent. of water of hydration, and containing some peroxide of iron.

CHARACTERS AND TESTS.—Brownish-black, destitute of taste, strongly attracted by the magnet. It dissolves without effervescence in hydrochloric acid diluted with half its volume of water, and the solution thus obtained gives the reactions both of ferrous and ferric salts.

DOSE.—5 to 10 grains.

USES.—It is but sparingly soluble, and so not so good as reduced iron.

Ferrum Redactum, B. and U.S.P. REDUCED IRON.—Metallic iron, with a variable amount of magnetic oxide of iron.

CHARACTERS AND TESTS.—A fine greyish-black powder, strongly attracted by the magnet, and exhibiting metallic streaks when rubbed with firm pressure in a mortar. It dissolves in hydrochloric acid with the evolution of hydrogen, and the solution gives

a light blue precipitate with the yellow prussiate of potash. ($Fe + 2HCl = Fe\,Cl_2 + H_2$.

IMPURITY.—Magnetic oxide.

TEST.—When ten grains are added to an aqueous solution of fifty grains of iodine and fifty grains of iodide of potassium ($Fe + I_2 = Fe\,I_2$ which dissolves in KI), and digested in a small flask at a gentle heat, the reduced iron is converted into iodide and dissolved, and not more than five grains should be left undissolved, which should be entirely soluble in hydrochloric acid (oxide.)

DOSE.—1 to 5 grains.

Trochisci Ferri Redacti, B.P. REDUCED IRON LOZENGES, B.P.—Each lozenge contains one grain of reduced iron.

DOSE.—1 to 6 lozenges.

USES.—This preparation is generally well borne even if the stomach be somewhat irritable. It has no astringent action. When dissolved by the gastric juice it evolves hydrogen, and if sulphur be present as an impurity eructations of sulphuretted hydrogen are produced.

Tinctura Ferri Acetatis, B. and U.S.P. TINCTURE OF ACETATE OF IRON.

DOSE.—5 to 30 minims.

USE.—May be given along with acetate of potash in dropsy.

U.S.P. Mistura Ferri et Ammonii Acetatis. MIXTURE OF ACETATE OF IRON AND AMMONIUM (BASHAM'S MIXTURE) comprises tincture of chloride of iron (2 parts), diluted acetic acid (3), solution of acetate of ammonium (20), elixir of orange (10), syrup (15), water (50).

DOSE.—½-1 fluid ounce.

USE.—As hæmatinic generally, and in cases of renal disease especially.

U.S.P. Ferri Chloridum. CHLORIDE OF IRON.—$Fe_2Cl_6.12H_2O$; 540·2.

CHARACTERS.—Orange-yellow crystalline pieces, very deliquescent, odourless or having a faint odour of hydrochloric acid, a styptic taste, and an acid reaction. Freely and wholly soluble in water, alcohol, or ether. The dilute aqueous solution gives a brown-red precipitate with water of ammonia, a blue one with test solution of ferrocyanide of potassium, and a white one, insoluble in nitric acid, with test solution of nitrate of silver.

USE.—In the solid state it keeps indefinitely, whereas in solution it is apt to deposit ferric oxide leaving excess of acid in the solution which renders it irritating. When required it may be dissolved in water in the proportion of 1½-6 drachms to the ounce of water. When semi-deliquesced it is an efficient styptic.

Liquor Ferri Perchloridi Fortior, B.P. Liquor Ferri Chloridi, U.S.P. STRONG SOLUTION OF PERCHLORIDE OF IRON, B.P. SOLUTION OF CHLORIDE OF IRON, U.S.P.

CHARACTERS AND TESTS.—An orange-brown solution with a strong styptic taste, miscible with water and rectified spirit in all proportions. Diluted with water it gives the reactions of a chloride and of a ferric salt only.

Applied externally as a styptic and caustic.

PREPARATIONS.

B.P.		DOSE.
Liquor Ferri Perchloridi (with water)	1 volume in 4.	10-30 min.
Tinctura Ferri Perchloridi (with spirit) ...	1 volume in 4.	10-30 min.

U.S.P. Tinctura Ferri Chloridi. TINCTURE OF CHLORIDE OF IRON. DOSE.—10 to 30 minims.

PREPARATION.

Mistura Ferri et Ammonii Acetatis, U.S.P.

USES.—The strong solution is one of the most powerful **styptics** we possess. It forms, almost immediately, a hard black coagulum with blood, and by blocking up the mouths of the vessels arrests further hæmorrhage. Cotton wool steeped in this may be used to arrest the hæmorrhage from the cavity of a tooth after its extraction, and to stop the bleeding from leech bites. It has been applied as a caustic in hospital gangrene, in bleeding from the uterus, and, diluted with three volumes of water, it may be injected into the uterine cavity, but is better applied by swabbing it over the interior of the uterus with a sponge. It has been injected into aneurisms, in order to produce coagulation within them. There is, however, great danger that part of the clot may become detached and carried onwards, producing embolism, or that inflammation and ulceration may take place within the aneurismal sac itself.

It has also been injected into varicose veins and nævi for a similar purpose, but in nævi on the face it may cause sloughing, and leave scars. It has been used as a spray for the purpose of arresting hæmorrhage from the lungs.

The liquor and tincture are perhaps more often employed than any other preparation of iron. They are **astringent,** generally causing constipation, but sometimes they irritate the intestine, increasing the number of stools. They are amongst the most efficient preparations of iron as **hæmatinics.** They are contraindicated by a red irritable tongue, and succeed best when the tongue is pale, flabby, and marked with the teeth at the edges.

I have found that when patients bear iron badly and complain of headache even after small doses, they can take with benefit a single drop of the tincture or solution of the perchloride in a full tumbler of water. In its great dilution the mixture somewhat resembles chalybeate waters, which often succeed much better than pharmaceutical preparations. The tincture has been given in erysipelas in very large doses, 20 — 30 min., repeated every hour or two.

Liquor Ferri Pernitratis, B.P.; Liquor Ferri Nitratis, U.S.P. SOLUTION OF PERNITRATE OF IRON, B.P.: NITRATE OF IRON, U.S.P. $Fe_2(NO_3)6$; 483·8.

CHARACTERS AND TESTS.—A clear solution of a reddish-brown colour, slightly acid and astringent to the taste. When to a little of it placed in a test-tube half its volume of pure sulphuric acid is added, and then a solution of sulphate of iron is poured on, the whole assumes a dark-brown colour (nitrate). It gives the reactions of a ferrous salt only.

DOSE.—10 to 40 minims.

USES.—It has been used as an astringent in the diarrhœa of children, and, also as an astringent, to diminish discharges from mucous surfaces, also to arrest hæmorrhage from internal organs. It can be given along with spirit of nitrous ether or nitrate of potash in cases of anæmia with albuminuria and dropsy.

Ferrum Tartaratum, B.P.; Ferri et Potassii Tartras, U.S.P. TARTARATED IRON, B.P.; TARTRATE OF IRON AND POTASSIUM, U.S.P.

CHARACTERS AND TESTS.—Thin transparent scales of a deep garnet colour, slightly sweetish and astringent in taste, soluble in water and sparingly soluble in spirit. The aqueous solution, when acidulated with hydrochloric acid, gives the reactions of a ferric salt only. When the salt is boiled with solution of soda, peroxide of iron separates, but no ammonia is evolved (not the ammonio-citrate), and the filtered solution when slightly acidulated by acetic acid gives, as it cools, a crystalline deposit (potassium).

DOSE.—5 to 10 grains.

The double salts of iron with potassium, ammonium, quinine, &c., are usually called the **scale preparations of iron** from their appearance. These are less astringent than, and do not confine the bowels so much as, either the proto-sulphate or the per-salts. Another advantage is that they may be given along with alkaline carbonates without being precipitated. They are employed in cases where the other preparations cause headache, or where other preparations derange the digestion, on account of the stomach being irritable.

U.S.P. Ferri et Ammonii Tartras. TARTRATE OF IRON AND AMMONIUM.

CHARACTERS.—Transparent scales varying in colour from garnet-red to yellowish-brown, only slightly deliquescent, without odour, having a sweetish and slightly ferruginous taste and a neutral reaction. It is not precipitated by ammonia but gives a brown precipitate of ferric oxide with potash and evolves the vapour of ammonia. On adding test solution of ferrocyanide of potassium to the salt, no blue colour or precipitate is produced unless the solution is acidulated with hydrochloric acid.

Ferri et Ammoniæ Citras, B.P.; Ferri et Ammonii Citras, U.S.P. CITRATE OF IRON AND AMMONIA, B.P.; CITRATE OF IRON AND AMMONIUM, U.S.P.

CHARACTERS.—In thin transparent scales of a deep red colour, slightly sweetish and astringent in taste. It feebly reddens litmus paper, is soluble in water, but almost insoluble in rectified spirit. Heated with solution of potash it evolves ammonia and deposits peroxide of iron. The alkaline solution from which the iron has separated does not, when slightly supersaturated with acetic acid, give any crystalline deposit (distinction from and absence of tartrate).

DOSE.—5 to 10 grains.

PREPARATIONS.

B.P.	DOSE.
Vinum Ferri Citratis. 8 grains in 1 fl. oz. of orange wine.	1-4 fl. drs.

U.S.P.

Ferri et Strychninæ Citras	
Liquor Ferri et Quininæ Citratis	
Vinum Ferri Citratis	1-2 fl. drs.

U.S.P. Vinum Ferri Citratis. (Citrate of iron and ammonia, 4; tincture of sweet orange peel, 12; syrup, 36; stronger white wine, 44.)

U.S.P. Liquor Ferri Citratis. AN AQUEOUS SOLUTION OF FERRIC CITRATE, $Fe_2(C_6H_5O_7)_2$; 489·8, containing about 35 per cent. of the anhydrous salt.

CHARACTERS.—A dark brown liquid, odourless, having a slightly ferruginous taste and acid reaction. It gives the reactions of a citrate and a bluish green precipitate with ferrocyanide of potassium, which is increased and rendered dark blue by the subsequent addition of hydrochloric acid.

DOSE.—Ten minims (0·6 cc.), equal to 5 grains of the salt.

U.S.P. Ferri Citras. CITRATE OF IRON. $Fe_2(C_6H_5O_7)_2.6H_2O$; 597·8.

CHARACTERS.—Transparent garnet-red scales, permanent in the air, odourless, having a very faint, ferruginous taste and an acid reaction. Slowly but completely soluble in cold water and readily so in boiling water; insoluble in alcohol.

PREPARATION.

Ferri et Quininæ Citras.

USE.—Is pleasant. A solution of 240 grains in 1 fl. oz. of water keeps perfectly, and may be given in doses of 10 minims, equal to 5 grains, as a tonic.

Ferri et Quiniæ Citras, B.P.; Ferri et Quininæ Citras, U.S.P. CITRATE OF IRON AND QUINIA, B.P.; CITRATE OF IRON AND QUININE, U.S.P.

CHARACTERS AND TESTS.—Thin scales of a greenish golden-yellow colour, somewhat deliquescent, and entirely soluble in cold water. The solution is very slightly acid, and is precipitated reddish-brown (iron) by solution of soda, white (quinine) by solution of ammonia, blue by the yellow ferric and red prussiates (ferrous) of

potash, and greyish-black by tannic acid. The taste is bitter (quinine) as well as chalybeate.

DOSE.—5 to 10 grains.

U.S.P. Liquor Ferri et Quininæ Citratis. SOLUTION OF CITRATE OF IRON AND QUININE. (Citrate of iron and ammonium, 65; quinine, 12; citric acid, 28; alcohol, 30; distilled water up to 200.)

DOSE.—8 to 15 minims ($\frac{1}{2}$-1 c.c.)

PREPARATION.

U.S.P.

Vinum Ferri Amarum. BITTER WINE OF IRON. (Solution of citrate of iron and quinine, 8; tincture of sweet orange peel, 12; syrup, 36; stronger white wine, 34.) Dose 1-2 fl. drs. (4-16 c.c.).

U.S.P. Ferri et Strychninæ Citras. CITRATE OF IRON AND STRYCHNINE.

CHARACTERS.—Transparent garnet-red scales, deliquescent on exposure to air; odourless, having a bitter and slightly ferruginous taste and a slightly acid reaction. If one Gm. of the salt be dissolved in 4 cc. of water in a small test-tube, then 1 cc. of solution of potassa added and the mixture shaken with 2 cc. of chloroform, the residue left on evaporating the chloroform will answer to the reaction of strychnine. (See "Strychnina.")

DOSE.—3 to 5 grains (0·20 — 0·33 Gm.).

USES.—As **tonic** and chalybeate to combine the uses of strychnine and iron.

U.S.P. Ferri et Ammonii Sulphas. SULPHATE OF IRON AND AMMONIUM. AMMONIO-FERRIC SULPHATE OR AMMONIC-FERRIC ALUM. $Fe_2(NH_4)_2(SO_4)_4.24H_2O$; 963·8.

This is an ammonia iron-alum in which the place of the aluminium oxide is occupied by the ferric oxide.

CHARACTERS.—Pale violet octahedral crystals efflorescent on exposure to air, odourless, having an acid styptic taste and a slightly acid reaction.

DOSE.—5 to 10 grains.

USES.—It is more **astringent** than common alum, and has not the stimulating properties of other iron salts. It is useful in leucorrhœa. Internally it is sometimes very useful in lessening albumen in cases of intermittent albuminuria.

U.S.P. Ferri Lactas. LACTATE OF IRON. $Fe(C_3H_5O)_2.3H_2O$; 287·9.

CHARACTERS.—Pale greenish-white, crystalline crusts or grains, permanent in the air; odourless, having a mild sweetish ferruginous taste and a slightly acid reaction. When heated on platinum foil the salt froths up, gives out thick white acrid fumes and chars, a brown-red residue being finally left. If the salt be boiled for fifteen minutes with nitric acid of the sp. gr. 1·200, white granular mucic acid will be deposited on cooling the liquid.

PREPARATION.

U.S.P. Syrupus Hypophosphitum cum Ferro. (Lactate of iron, 1 ; syrup of hypophosphites, 99.)

DOSE.—12-20 grains per diem ; of syrup, ½ to 1 fl. dr.

USE.—In chlorosis and anæmia.

U.S.P. Ferri Oxalas. OXALATE OF IRON. $FeC_2O_4.H_2O$; 161·9.

CHARACTERS.—A pale yellow, or lemon-yellow crystalline powder, permanent in the air, odourless and nearly tasteless, very slightly soluble in cold or hot water, but soluble in cold concentrated hydrochloric acid and in hot diluted sulphuric acid.

DOSE.—2 to 3 grains (0·13 to 0·20 Gm.)

Ferri Iodidum, B.P. IODIDE OF IRON. FeI_2 ; 309·1.—Iodide of iron, FeI or FeI_2, with about 18 per cent. of water of crystallisation and a little oxide of iron.

CHARACTERS AND TESTS.—Crystalline, green with a tinge of brown, inodorous, deliquescent, almost entirely soluble in water, forming a slightly green solution which gradually deposits a rust-coloured sediment, and acquires a red colour. Its solution gives the reaction of an iodide and of a ferrous salt.

DOSE.—1 to 5 grains.

PREPARATIONS.

B. AND U.S.P.	DOSE.
Pilula Ferri Iodidi. 1 part in 3 (with sugar and liquorice.)	3-8 grs.
Syrupus Ferri Iodidi. 4·3 grains in 1 fluid drachm	½-1 fl. dr.

U.S.P. Ferri Iodidum Saccharatum. SACCHARATED IODIDE OF IRON.

CHARACTERS.—A yellowish-white or greyish powder, very hygroscopic, odourless, having a sweetish ferruginous taste, and a slightly acid reaction.

DOSE.—2 to 5 grains (0·13 to 0·33 Gm.).

USES.—Iodide of iron is given when a combination of the effect of iodine on the lymphatic system is desired along with the hæmatic action of iron. It is thus very useful in the form of the syrup in dispensary practice in large towns, where pale, anæmic, flabby, and scrofulous children abound, and come in large numbers to be treated. It is generally advantageous to combine it with cod-liver oil, a few drops of the syrup being dropped into the oil and taken along with it. It has been given in phthisis in the same way, and has been useful in rheumatic arthritis and syphilis.

U.S.P. Syrupus Ferri Bromidi. SYRUP OF BROMIDE OF IRON.—A syrupy liquid containing 10 per cent. of ferrous bromide. $FeBr_2$; 215·5.

DOSE.—½ to 1 fluid drachm (1·9 to 3·75 cc.).

USE.—In nervous diseases accompanied by anæmia. It is doubtful, however, whether it is not better to give the iron and

bromine separately, as sufficient bromine cannot be given in this form. It may, however, be advantageously combined with other bromides.

B.P. Ferri Arsenias. ARSENIATE OF IRON.—Arseniate of iron, $Fe_3As_2O_8$, partially oxidised.

CHARACTERS AND TESTS.—A tasteless amorphous powder of a green colour, insoluble in water, but readily dissolved by hydrochloric acid. This solution gives a copious light-blue precipitate with the yellow prussiate of potash (ferric), and a still more abundant one of a deeper colour with the red prussiate of potash (ferrous). A small quantity boiled with an excess of caustic soda and filtered, gives, when exactly neutralised by nitric acid, a brick-red precipitate on the addition of solution of nitrate of silver (arseniate).

DOSE.— $\frac{1}{16}$ to $\frac{1}{2}$ grain.

USES.—Used when we wish to employ arsenic and iron together, as in skin diseases in anæmic subjects.

Ferri Phosphas, B. and U.S.P. PHOSPHATE OF IRON.—Phosphate of iron, $Fe_3P_2O_8$, partially oxidated.

CHARACTERS AND TESTS.—A slate-blue amorphous powder, insoluble in water, soluble in hydrochloric acid. The solution yields a precipitate with both the yellow (ferric) and red prussiate of potash, that afforded by the latter being the more abundant (ferrous); and when treated with tartaric acid and an excess of ammonia, and subsequently with the solution of ammonio-sulphate of magnesia, lets fall a crystalline precipitate (phosphate). When the salt is digested in hydrochloric acid with a lamina of pure copper, a dark deposit does not form on the metal (distinction from and absence of arseniate).

DOSE.—5 to 10 grains.

PREPARATIONS CONTAINING PHOSPHATE OF IRON.

B.P. DOSE.

Syrupus Ferri Phosphatis (freshly precipitated phosphate (p. 665) is dissolved in dilute phosphoric acid and sugar added) 1 gr. in 1 fl. dr... 1 fl. dr.

U.S.P.

Syrupus Ferri Quininæ et Strychninæ Phosphatum. (Phosphate of iron, 133; quinine, 133; strychnine, 4; phosphoric acid, 800; sugar, 6,000; distilled water up to 10,000.) This preparation resembles Easton's Syrup.

USES.—It is used in diabetes, in rickets, and in nervous depression. It is frequently given along with the phosphates of lime, potash, and soda, as the preparation usually called Parrish's Chemical Food, or with the phosphates of quinine and strychnine as in Easton's Syrup.

U.S.P. Ferri Pyrophosphas. PYROPHOSPHATE OF IRON.

CHARACTERS.—Thin, apple-green, transparent scales, permanent in dry air when excluded from light, but turning dark on exposure to light. Odourless, having an acidulous slightly saline taste, and a slightly acid reaction. When heated with solution of potassa in

excess a brown-red precipitate is thrown down, and the filtrate, after being supersaturated with acetic acid, yields a white precipitate with test-solution of nitrate of silver (difference from phosphates).

DOSE.—2 to 5 gr. (0·13 to 0·33 Gm.)

USES.—Has no disagreeable taste, and is very soluble, so that it can be given in any form.

U.S.P. Ferri Hypophosphis. HYPOPHOSPHITE OF IRON.—$Fe_2(H_2PO_2)_6$; 501·8.

CHARACTERS.—A white or greyish-white powder, permanent in the air, odourless and nearly tasteless, only slightly soluble in water, more readily so in presence of hypophosphorous acid, freely soluble in hydrochloric acid, or in solution of citrate of sodium, forming with the latter a green solution. When strongly heated in a dry test-tube, the salt evolves a spontaneously inflammable gas (phosphorated hydrogen), and on ignition leaves behind ferric pyrophosphate. The salt is readily oxidised by nitric acid or other oxidising agents. It should be completely soluble in acetic acid (absence of ferric phosphate). This solution, when mixed with test-solution of oxalate of ammonium, should not afford a white precipitate soluble in hydrochloric acid (absence of calcium).

DOSE.—5 to 10 grains in pill, more generally given in syrup.

USES.—In nervous debility with anæmia, and also in phthisis.

U.S.P. Ferri Valerianas. VALERIANATE OF IRON. $Fe_2(C_5H_9O_2)_6$; 717·8.

CHARACTERS.—A dark tile-red amorphous powder, permanent in dry air, having a faint odour of valerianic acid, and a mildly styptic taste. Insoluble in cold water, but readily soluble in alcohol. Boiling water decomposes it, setting free the valerianic acid and leaving ferric hydrate. When slowly heated the salt parts with its acid without fusing, but when rapidly heated it fuses and gives off inflammable vapours having the odour of butyric acid.

DOSE.—1 grain or more.

USES.—In hysteria with anæmia.

MANGANESE. Mn; 55·54.

Manganesii Oxidum Nigrum, B.P.; Mangani Oxidum Nigrum, U.S.P. BLACK OXIDE OF MANGANESE.—Native crude peroxide of Manganese containing at least 66 of the pure oxide. MnO_2; 86. U.S.P.

CHARACTERS AND TESTS.—A heavy black powder, which dissolves almost entirely in hydrochloric acid with evolution of chlorine, and gives off oxygen when heated to redness.

USES.—Used for producing chlorine, and for making oxygen. It has been used instead of bismuth in pyrosis and irritable conditions of the stomach, with pain after eating; and instead of

iron in debilitating diseases, anæmia, syphilis, scurvy, and in skin diseases.

U.S.P. Mangani Sulphas. SULPHATE OF MANGANESE. $MnSO_4,4H_2O$; 222.

CHARACTERS.—Colourless or pale rose-coloured, transparent right rhombic prisms, odourless, having a slightly bitter and astringent taste, and a faintly acid reaction. The aqueous solution of the salt yields, with sulphide of ammonium, a flesh-coloured precipitate completely soluble in moderately-diluted acetic acid (absence of zinc); with test-solution of ferrocyanide of potassium it affords a reddish-white precipitate, and a brown one with test-solution of ferricyanide of potassium.

ACTION OF MANGANESE SALTS.—When injected into the blood, or subcutaneously, manganese salts **paralyse** voluntary movement and reflex action, and stop the **heart** in diastole. The paralysis of reflex action is due to destruction of the transverse conduction of the **spinal cord** (p. 131), longitudinal conduction remaining intact until death (Kobert). Proto-sulphate produces purging in doses of 1 to 2 drms., and in consequence of Gmelin's experiments has been thought to increase the secretion of bile.

USES.—Has been used in place of iron in anæmia, but without good results. Possibly it may be serviceable in amenorrhœa.

Class VIII.

GROUP II.—GOLD, PLATINUM.

AURUM; GOLD, Au.

B.P. Gold, Fine. GOLD, FREE FROM METALLIC IMPURITIES. Gold foil is used for stopping teeth and to make the test solution.

B.P. Solution of Chloride of Gold.

PREPARATION.—By dissolving gold foil in a mixture of nitric and hydrochloric acids and diluting.

U.S.P. Auri et Sodii Chloridum. CHLORIDE OF GOLD AND SODIUM.

A mixture composed of equal parts of dry chloride of gold, $AuCl_3$; 302·4; and chloride of sodium, NaCl; 58·4.

PREPARATION.—By dissolving gold in nitro-hydrochloric acid and evaporating to dryness chloride of gold is obtained. This is dissolved in water, and mixed with its own weight of pure decrepitated common salt also dissolved in water. The mixed solution is then evaporated to dryness.

CHARACTERS.—An orange-yellow powder, slightly deliquescent, in damp air odourless, having a saline and metallic taste and a slightly acid reaction. The compound is very soluble in water; at least one half of it should be soluble in cold alcohol. When exposed

to a red heat it is decomposed and metallic gold is separated. A fragment of the compound imparts an intense persistent colour to a non-luminous flame.

DOSE.—$\frac{1}{10}$ to $\frac{1}{5}$ grain (·006-·012 Gm.) once or twice a day.

ACTION.—Salts of gold cause rapid **paralysis** of the central nervous system in frogs, which appears to affect first the optic lobes and cerebellum, then the cord, and lastly the cerebral lobes (*vide* p. 153). In mammals small doses appear to increase the appetite; larger ones cause symptoms of irritation in the **stomach** and **intestines,** viz., loss of appetite, diarrhœa, and emaciation, followed by paralysis of the limbs, a catarrhal condition of the **respiratory** passages, and death by asphyxia. Large doses injected into the veins cause œdema of the **lungs,** and rapid death, with convulsions, from asphyxia. In man they are said to increase the **secretions,** and to produce salivation like mercury, but without stomatitis. They are **eliminated** in the urine.

USES.—Salts of gold have been supposed to act like those of mercury and silver. They have been given like mercurial salts in syphilis, scrofula, and cancer; and, like silver salts, have been used in myelitis. Gold has been supposed to act specifically on the genital organs, and has been used in chronic uterine inflammation and irritation, and inflammation and neuralgia of the ovaries.

PLATINUM. Pt. 197.

B.P. Platinum Foil.

A heavy whitish metal, 8·921. Withstands considerable heat. The foil is convenient for holding salts of organic acids which it is wished to char.

B.P. Solution of Perchloride of Platinum. $PtCl_4$; 339.

PREPARATION.—By dissolving thin platinum foil in a mixture of nitric acid and hydrochloric acid and diluting.

USES.—Used to distinguish potassium from sodium and to precipitate salts of ammonium, and of compound ammoniums, *e.g.* organic alkaloids.

ACTION.—Soluble salts of platinum are as poisonous as arsenic. In frogs they appear to paralyse the centres for voluntary motion in the cerebral lobes, and irritate the motor centres between them and the cord, so that voluntary motion is diminished, but reflex convulsions occur. The excitability of voluntary **muscle** is much lessened, that of the heart is not apparently altered. In **mammals** the most prominent symptom is paralysis of the peripheral ends of the **vaso-motor nerves.** In consequence of this, diarrhœa, blood in the motions, hyperæmia of the abdominal viscera, and ecchymoses of the mucous membrane of the stomach and intestine and bladder occur.

B.P. Platinum Black.

Platinum in a state of minute division, obtained by adding excess of carbonate of soda and some sugar to solution of perchloride of platinum, and boiling until a black precipitate is formed, which is washed and dried.

ACTION.—Platinum black appears to have a greater power than even charcoal to condense gases, and especially oxygen in its pores. By giving the oxygen off again it acts as an oxidising agent.

USE.—To test amylic alcohol by oxidising it into valerianic acid.

SECTION IV.

ORGANIC MATERIA MEDICA.

This Section contains Organic Compounds artificially prepared, and not merely extracted from Vegetable Substances containing them. Although it is small, it contains some of the most important remedies we possess, and by and by will probably replace to a great extent, and perhaps entirely, the vegetable materia medica.

CHAPTER XXIX.

CARBON COMPOUNDS—FATTY SERIES.

CARBON is a tetrad element. It is sometimes represented graphically thus: . It combines with four atoms of a monad, or two of a dyad element, *e.g.*  . It combines with itself, and thus the number of its compounds is almost endless.

These compounds are divided into two great classes, according to the mode in which the atoms are linked.

In the first class, or fatty series, the carbon atoms are supposed to be linked so as to form an open chain, *e.g.*:



In the second class, or aromatic series, the carbon atoms are supposed to be linked, so as to form a closed chain.



Some of the simpler compounds of carbon have already been considered—carbonic acid, CO_2 (p. 509), hydrocyanic acid, HCN (p. 512), acetic acid, $C_2H_4O_2$ (p. 503).

GENERAL ACTION.—It will be noticed that compounds of carbon with hydrogen alone, as in the hydrocarbons of the marsh-gas series; with oxygen alone, as in carbonic acid, CO_2; with sulphur alone, as in bisulphide of carbon, CS_2; or with chlorine alone, as in tetrachloride of carbon, CCl_4, all tend to **paralyse** the **nervous system,** and to destroy the functional activity of its various parts in a definite order. Thought fails first, next sensation, and next reflex action (p. 174).

The compounds with hydrogen have a comparatively slight action on **muscle,** but those containing chlorine are more powerful muscular poisons, and destroy the contractility of muscular fibre, both voluntary and involuntary.

Many compounds containing oxygen in addition to carbon and hydrogen have an **anæsthetic** action, *e.g.* alcohol and ether; others, like acetic acid, have a strongly irritant action. Compounds of carbon with nitrogen, hydrogen, and oxygen may have a very complicated chemical constitution, and, as in the organic alkaloids, have physiological actions which are too varied and specialised to allow of their being classed at present under a general law.

U.S.P. Carbonei Bisulphidum. BISULPHIDE OF CARBON. CS_2; 76.—Bisulphide of carbon should be kept in well-stopped bottles, in a cool place, remote from lights or fire.

CHARACTERS.—A clear, colourless, highly refractive liquid, very diffusive, having a strong, characteristic odour, a sharp, aromatic taste, and a neutral reaction. It is insoluble in water; soluble in alcohol, ether, chloroform, and fixed or volatile oils. Specific gravity 1·272. It vapourises abundantly at ordinary temperatures, is highly inflammable, boils at 46° C. (114°.8 F.), and, when ignited, burns with a blue flame, producing carbonic and sulphurous acids.

It should not affect the colour of blue litmus-paper moistened with water (abs. of sulphurous acid). A portion evaporated spontaneously in a glass vessel should leave no residue (sulphur). Test-solution of acetate of lead agitated with it should not be blackened (abs. of hydrosulphuric acid).

ACTION.—When inhaled it is a rapid, powerful, but transient anæsthetic.

USES.—It is not used as an internal remedy. It can be used to produce local anæsthesia by atomisation. It has been employed as a local irritant in enlarged lymphatic glands, neuralgia, and deafness accompanied by insufficiency of wax.

FATTY SERIES.

HYDROCARBONS.

The chemical nature of a carbon compound depends on the arrangement of its constituent atoms, but its physical characters on the number of the atoms.

The **physical character** of a compound greatly influences its physiological action, a gaseous body being more easily absorbed and excreted than a liquid, and a liquid more easily than a solid. There will also be differences amongst the gaseous, liquid, and solid bodies themselves; for if a liquid, for example, has a low boiling-point so as to volatilise readily at ordinary temperatures, it will more resemble a gas in its action, while a liquid which has a high boiling-point will act more like a solid.

Thus in the group of hydrocarbons belonging to the paraffin series the lowest members are gaseous at ordinary temperatures, the highest members form solid wax-like bodies, while those which are intermediate are liquid. Obviously we cannot expect a gas which can be inhaled in large quantities, and which will be quickly excreted when pure air is inhaled instead, to have the same action as a solid wax-like substance which can only be slowly absorbed, and slowly excreted or broken up in the organism.

The **boiling-point** of substances belonging to a series differs somewhat according to the chemical nature of the substance, but amongst the members of the series having the same chemical nature it rises with the number of atoms. It will be seen from the accompanying table that the boiling-point differs according to the series, *e.g.* that of chlorides is lower than that of bromides; this, again, is lower than that of iodides. In each series also of chlorides, bromides, or iodides, the boiling-point rises with the number of carbon atoms which the member of the series contains.

As the action of substances depends so much on their volatility, it may be convenient to give here the boiling-points of the various members of the paraffin series:—

Radical.	Chloride, $C_nH_{2n+1}Cl$.	Bromide, $C_nH_{2n+1}Br$.	Iodide, $C_nH_{2n+1}I$.	Hydride, $C_nH_{2n+1}H$.	Alcohol, $C_nH_{2n+1}OH$.	Aldehyde, $C_nH_{2n}O$.	Ether.
Methyl, CH_3 .	...	...	40°	Gas.	66·0°	...	Gas.
Ethyl, C_2H_5 . .	12·5°	39°	72°	Gas.	78·4°	20°·8	35°
Propyl, C_3H_7 .	46·4°	71°	102°	Gas.	97·4°	48·8°	85°
Butyl, C_4H_9 . .	77·6°	100·4°	129·6°	1°	116·9°	58°	140°
Amyl, C_5H_{11} .	105·6°	128·7°	153·4°	38°	138°	92·5°	163°
Hexyl, C_6H_{13} .	...	...	179·4°	70°	158°	127·9°	205°
Heptyl, C_7H_{11} .	...	...	...	99°	176°	150°	...
Octyl, C_8H_{17} . .	180°	199°	221°	124°	192°	...	281°
Dodecyl, $C_{12}H_{25}$	...	...	...	202°	...	...	...
Hexdecyl, or Cetyl, $C_{16}H_{33}$	...	...	...	278°	...	...	300° Melting point 55°

PHYSIOLOGICAL ACTION OF HYDROCARBONS BELONGING TO THE MARSH-GAS SERIES.—These hydrocarbons may be regarded

as hydrides of the radicals, methyl, &c. Those low in the series—methane, ethane, propane, and butane—are permanent gases at ordinary temperatures, and when inhaled pure produce anæsthesia much like that of nitrous oxide. The intermediate fluid members of the series, *e.g.* pentane, and substances containing them, as benzin, petroleum oil, &c., give off vapour having an anæsthetic action somewhat like that of chloroform.

The higher members of the series are solid at ordinary temperatures, and are used as a basis for ointments under the names of petrolatum, vaseline, cosmoline, &c.

U.S.P. Benzinum. BENZIN. PETROLEUM BENZIN. PETROLEUM ETHER.—A purified distillate from American petroleum, consisting of hydrocarbons, chiefly of the marsh-gas series [C_5H_{12}; C_6H_{14}, and homologous compounds], having a specific gravity from 0·670 to 0·675, and boiling at 50° to 60° C. (122° to 140° F.).

Benzin should be carefully kept in well-stopped bottles or cans, in a cool place, remote from lights or fire.

CHARACTERS.—A transparent, colourless, diffusive liquid, of a strong, characteristic odour, slightly resembling that of petroleum, but much less disagreeable; neutral in reaction; insoluble in water, soluble in about 6 parts of alcohol, and readily so in ether, chloroform, benzol, and fixed and volatile oils. It is highly inflammable, and its vapour, when mixed with air and ignited, explodes violently.

Benzin, when evaporated upon the hand, should leave no odour, and, when evaporated in a warmed dish, should leave no residue (abs. of heavy hydrocarbons). When boiled a few minutes with one-fourth its volume of spirit of ammonia and a few drops of test-solution of nitrate of silver, the ammoniacal liquid should not turn brown (abs. of pyrogenous products, and sulphur compounds); and it should require 6 parts of officinal alcohol to dissolve it (difference from benzol). If 5 drops are added to a mixture of 40 drops of sulphuric acid with 10 drops of nitric acid, in a test-tube, the liquid warmed and set aside for half an hour, and then diluted, in a shallow dish, with twice its volume of water, it should not have the bitter-almond-like odour of nitrobenzol (abs. of benzol).

DOSE.—As a vermifuge, 30 min.

USES.—It is a good **solvent** for fats, resins, caoutchouc, and some of the alkaloids. It has been used externally as a **sedative** in prurigo and other cutaneous diseases, and internally as a **vermifuge** for tape-worm.

U.S.P. Petrolatum. PETROLATUM. [PETROLEUM OINTMENT. VASELINE.]—A semi-solid substance, consisting of hydrocarbons, chiefly of the marsh-gas series, $C_{16}H_{34}$, &c., obtained by distilling off the lighter and more volatile portions from American petroleum, and purifying the residue. Melting-point about 40° C. to 51° C. (104°

F. to 125° F.), the first constituting the softer, and the second the firmer variety.

When petrolatum is prescribed or ordered, without specifying its melting-point, the low-melting variety, which liquefies at about 40° C. (104° F.), is to be dispensed.

CHARACTERS.—A yellowish or yellow, fat-like mass, transparent in thin layers, more or less fluorescent, especially when melted, completely amorphous, tasteless and odourless, or giving off, at most, only a faint petroleum odour when heated, and having a neutral reaction. When gently heated, until the mass is almost entirely melted, the liquid portion has a specific gravity varying from 0·835 to 0·860. It is insoluble in water, scarcely soluble in alcohol, or in cold absolute alcohol, but soluble in 64 parts of boiling absolute alcohol, and readily soluble in ether, chloroform, bisulphide of carbon, oil of turpentine, benzin, benzol, and in fixed or volatile oils. When heated on platinum foil, it is completely volatilised without emitting the acrid vapours of burning fat or resin.

If 5 Gm. of petroleum ointment be digested, for half an hour, with 5 Gm. of soda and 25 Gm. of water, the aqueous layer separated, and supersaturated with dilute sulphuric acid, no oily substance should separate (abs. of fixed oils or fats of vegetable or animal origin, or of resin). Liquefied petroleum ointment agitated with sulphuric acid of specific gravity 1·540 should not acquire a dark colour within two hours (abs. of readily carbonised organic impurities).

USES.—These hydrocarbons, which are not liable to become rancid, have been found very useful as a bland protection, and as a substitute for animal and vegetable fats in the preparation of ointments.

ALCOHOLS.

ALCOHOLS OF THE SERIES $C_2H_{2n+1.OH}$.—These may be regarded as hydrates of the radicals. They differ from the hydrides by the radical being united in them to hydroxyl, HO, instead of to hydrogen. The most important of them are:—

Methyl alcohol, CH_4O. Wood spirit.
Ethyl alcohol, C_2H_6O. Spirit of wine.
Propyl alcohol. C_3H_8O.
Amyl alcohol, $C_5H_{12}O$. Fusel oil or potato spirit.

These alcohols have all a toxic action when given in sufficiently large doses. The general effect they produce on the organism appears to be much the same in all, viz. **paralysis** affecting the **nerve-centres** in the inverse order of their development. Their lethal power and the symptoms they produce are modified by their physical characters, such as their solubility in water, and their volatility; for if they are not readily soluble in water they cannot be readily absorbed, and probably will not be readily excreted.

Their **toxic power** increases with their atomic weight, so that a less quantity of the higher alcohols will produce death. This is shown in the following table by Dujardin-Beaumetz. It will be noticed, however, that the lowest term and also the higher terms of the series form exceptions. This may possibly be due to rapid absorption as compared with excretion (p. 29) in the case of methylic alcohol, and to slow absorption in the case of œnanthic and caprylic alcohols :—

	Kind of Alcohol.	Mean toxic dose in grammes per kilogramme weight of the animal.	
		Pure.	Diluted.
Non-fermented...	Methylic Alcohol, CH_4O	...	7·0
Fermented ...	Ethylic ,, C_2H_6O	8·0	7·75
	Propylic ,, C_3H_8O	3·9	3·75
	(Isopropylic) ,, (C_3H_8O)	...	(3·7 to 3·8)
	Butylic ,, $C_4H_{10}O$	2·0	1·85
	Amylic ,, $C_5H_{12}O$	1·7	1·50
Non-fermented	Œnanthylic ,, $C_7H_{16}O$	8·0	...
	Caprylic ,, $C_8H_{18}O$	7· to 7·5	...

All the alcohols produce **symptoms** which are divided by Dujardin-Beaumetz into three stages, the first of which corresponds to the first and second stages of action I have given at p. 174, and his second and third corresponding to the third and fourth of mine respectively. These stages are **modified by** (*a*) the kind of alcohol used, (*b*) its quantity, and (*c*) the resistance of the subjects.

Ethylic alcohol has the most typical action, and in poisoning by it all the stages succeed one another in regular order. In the case of the other alcohols obtained by fermentation the stages are also regular, but the farther the alcohol is from ethylic, the less regular do the stages become. They succeed one another more rapidly, their character is less marked, and convulsive phenomena appear.

In the case of **methylic** alcohol the excitement is greater, the subsequent stages succeed one another more quickly, and reach their acme sooner; but if the dose be insufficient to cause death, the effects pass off more quickly.

In the case of **œnanthic** and **caprylic** alcohol, the stages do not present the same regularity, and convulsions occur.

All the alcohols now mentioned lower the **temperature.**

On post-mortem examination after acute poisoning by alcohols, the blood, stomach, intestines, liver, lungs, and kidneys are found to be affected. It is possible, however, that some of these **lesions** are not to be regarded as specific consequences of the

action of alcohol, but rather as due to the **death by asphyxia** which ensued from the respiratory paralysis. The blood is of a dark colour, and forms clots in the heart. When the alcohol is given **by the mouth,** the **stomach** and **intestine** are much congested and softened, the congestion being greater when the alcohol is undiluted. When the alcohol is injected **subcutaneously,** the stomach is little altered, but the **intestine** is congested, the congestion being probably due, according to Dujardin-Beaumetz, to elimination of the alcohol by the intestinal mucous membrane. The **liver** is the gland most affected. It is congested, soft, and friable. The **spleen** is also gorged with blood, and soft. The lungs are congested with small extravasations, which are most abundant when the alcohol has been given by the mouth. Hæmorrhages are observed in the **kidneys,** especially in the case of the non-fermented alcohols.

Methyl Alcohol, $CH_3.OH$; WOOD SPIRIT. Synonyms—CARBINOL, HYDROXYMETHANE, METHOL. Not officinal.

PREPARATION.—By destructive distillation of wood, and neutralisation and repeated distillation of the product.

CHARACTERS.—A colourless, mobile liquid. When pure it has a taste and smell somewhat like ethyl alcohol; but ordinary wood spirit contains many impurities which give it a disagreeable odour and burning taste.

USES.—The admixture of wood spirit with alcohol renders the latter so disagreeable as to unfit it for drinking, so that it can be sold under the name of methylated spirit as a solvent, and for other uses in the arts, without interfering with the duties on potable alcoholic drinks.

Alcohol. ETHYL ALCOHOL. $C_2H_5.OH$.

GENERAL SOURCE AND PREPARATION.—Alcohol is prepared from solutions of grape sugar by adding to them a ferment, which causes the glucose to split up into alcohol and carbonic acid.

The solutions of grape sugar which yield alcohol are generally prepared from malt. This is made by steeping barley for a while in water till it begins to germinate. The barley when fresh contains starch and a ferment termed diastase, which converts the starch into sugar during the process of germination.

When this has gone far enough, as is ascertained by the radicle attaining a certain length, the process is stopped by roasting the malt, as the sugar would all be used up again by the plant if it were allowed to continue its growth. The malt is then infused in warm water, and the solution of grape sugar which it yields is fermented by yeast, a small fungus which causes the grape sugar to split up and yield alcohol. The alcohol thus obtained is very much diluted with water, and in order to separate them the liquor is distilled, when the alcohol passes over first and the greater part of the water is left behind.

GENERAL IMPURITIES.—Water, fusel oil, and aldehyde. The water may have come to be present either as an accidental impurity or as an intentional adulteration. One of the most important impurities of alcohol is the presence of organic alkaloids. A good deal of spirit is made from spoiled grain, maize, &c., which cannot be used for food. In diseased grain alkaloids are formed, and these appear to pass over with the alcohol during distillation.

TESTS.—Water is detected by the use of the hydrometer, as any admixture of water with alcohol raises the specific gravity of the latter.

The presence of oily, fatty, or resinous substances in alcohol is recognised by diluting it with water, when these substances, being insoluble in weak spirit, are precipitated and render the solution turbid.

Traces of fusel oil and aldehyde are almost always present, and they are reckoned as impurities by the B.P. only when they rise above a certain amount. The quantity of them present in alcohol is determined by adding to 4 oz. of it 30 grain measures of standard solution of nitrate of silver and exposing it to the sunlight for 24 hours. The nitrate of silver is deoxidised by these substances and a black precipitate consisting of oxide or of some organic compound is deposited.

GENERAL ACTION OF ALCOHOL.—When alcohol is added in sufficient quantity to **albuminous** solutions it precipitates them, apparently simply by withdrawing the water from them, because when water is added to the freshly precipitated albumen it redissolves easily. When, however, the precipitate is kept for some time in alcohol, it loses its solubility, and is no longer redissolved by water. When applied to the **skin,** alcohol evaporates readily, and gives rise to a sensation of cold. It renders the epidermis drier and harder, and if kept in contact with the skin, evaporation being prevented, it passes through the epidermis, and, acting upon the tissue below, stimulates it, causing an increased supply of blood to the part, and producing a feeling of warmth or burning. A similar action takes place when it is applied to a mucous membrane, *e.g.* when taken into the **mouth.** It here produces a slight precipitate of albumen on the surface and acts as an astringent, drawing the parts slightly together, and forming on the surface a whitish pellicle, which, however, rapidly disappears. It causes considerable reflex secretion of saliva. When taken into the **stomach** in small quantities, it has a similar action on that organ, causing increased vascularity and increased secretion, accompanied by a feeling of warmth, and it excites a feeling of appetite, for which purpose it is taken by some persons before meals. It aids the expulsion of flatulence from the stomach and intestines. In cases of diarrhœa it has a somewhat astringent action in the **intestine,** but in persons accustomed to take alcohol to excess the bowels are always rather loose, constipation occurring very rarely, if at all.

After absorption into the **blood,** it appears to form a compound

with hæmoglobin, which takes up and gives off oxygen less readily than hæmoglobin itself (Schmiedeberg). It thus lessens the oxidising power of the blood, and will, consequently, diminish oxidation in the **tissues.**

Considerable dispute has arisen as to whether alcohol is a **food** or not. The chief argument in favour of its not being a food is that it is eliminated in the urine unchanged, but this seems to occur only when it is given in considerable quantities. In small doses it is partly **eliminated** by the breath, but most of it appears to undergo combustion in the body, and very little of it passes out in the urine. In this respect it agrees with other foods, such as cane sugar. Hammond found that when on insufficient diet he was losing weight, the addition of a little alcohol not only enabled him to reach his former weight, but to add to it.

The argument in favour of alcohol being a food is that it is retained in the body, and supplies the place of other foods, so that the quantity of food which would without it be insufficient, with its aid becomes sufficient.

The conclusion to which all the evidence points is that alcohol is a food, and in certain circumstances, such as febrile conditions, it may be a very useful food, but in health, when other kinds of food are abundant, it is unnecessary, and, as it interferes with oxidation, it is an inconvenient kind of food.

After its absorption into the **circulation** it causes dilatation of the vessels on the surface of the body, and increases the rapidity of the pulse. From the freer circulation which thus takes place in the capillaries of the surface, the skin of the face and hands become more flushed. The blood flows so freely from the arteries into the veins that there is no longer time for it to become completely venous in its passage. In consequence of the capillaries being dilated, the skin is no longer mottled, but of a uniformly pink colour. The veins are distended; they fill more rapidly when emptied, and are of a lighter blue than usual owing to the blood they contain being more arterial.

The action of alcohol upon the **temperature** seems to depend upon two factors. One of these is its power of lessening oxidation, but this only comes into consideration with large doses, when this factor may aid considerably in reducing the temperature. The other factor is the dilatation of the vessels on the surface, which occurs even after moderate doses. This dilatation allows the warm blood from the interior of the body to circulate more readily near the surface, and thus subjects it to the cooling influence of the surrounding air, and also to the cooling effect of evaporation from the skin. By increasing the sweat it may lessen the temperature of the body, even when that of the surrounding air is as high or higher than it, and it will also cool the blood by freer radiation when the temperature of the atmosphere is below that of the body. It is evident that the cooling effects of alcohol will thus

depend to a great extent on the atmospheric conditions of temperature and moisture to which the person taking it is subjected, as well as on the quantity of alcohol. Normally, when a person is subjected to cold, the vessels of the skin contract and prevent the warm blood in the interior of the body from approaching the surface and thus becoming cooled; but when large quantities of alcohol are taken, this mechanism becomes paralysed, the blood from the interior circulates over the surface, and is cooled down more and more until its temperature becomes so much reduced as to be incompatible with life, and the patient is frozen to death. The dangerous effects of alcohol under such circumstances are well known to the lumberers in Canada, and to Arctic voyagers, who dread alcohol, and generally avoid it altogether. The utility of this selfsame action of alcohol is very evident when a person comes from the cold atmosphere into a warm room; for here the individual may still remain cold, although in front of a fire, as the contraction of the surface vessels now continues, and the blood is no longer able to convey warmth to the interior, just as it was formerly unable to convey the cold. If alcohol be now taken, and the vessels dilated, the blood is allowed to circulate in the surface, soon becomes warm, and thus diffuses the warmth equally through the body.

In considering the action of alcohol upon the **nervous system,** one must distinguish between the effect it produces upon the various nerve centres by increasing the circulation through them, and the effect of the alcohol on the nervous structures themselves. By increasing the circulation it may stimulate the functions of all the nerve centres, and render them, for the time being, capable of greater activity. It may thus enable its consumer to think more clearly, to express himself more fluently, or to perform feats of greater bodily activity than usual, but its action on the nerve-centres themselves is a paralysing one.

The mode of action of alcohol on the circulation has not been well ascertained; but it seems probable that in considering it we must take into account both its direct action upon the circulatory apparatus itself and its reflex action upon that through other organs. Thus it is not improbable that even from the mouth it exercises an influence over the **cranial circulation** (p. 161). Although we have no experiments on the effect of irritation of the branches of the fifth nerve on the cranial circulation, yet individuals of all nations, when desiring to think more accurately, are accustomed to irritate some branch of this nerve, either by scratching the head, rubbing the forehead or chin, striking the nose, or taking snuff. Chewing sweet or pungent substances has a similar effect in enabling some persons to think more clearly, while, under similar circumstances, alcohol is sipped by others. From the stomach it probably stimulates the heart and vascular system reflexly, and thus increases both the cranial and general circulation. When

given in very large doses, as when a bottle of whisky has been drunk at a draught, the reflex action on the heart has been so great that death has occurred immediately from shock.

Its action upon the **nervous tissues** themselves seems to be one of progressive paralysis, affecting them in the inverse order of their development, the highest centres being affected first, and the lowest last. Thus the power of **judgment** usually goes first, while the imagination may be lively, and the **emotions** even more than usually active, so that, after a man becomes incapable of discussion, he is combative, affectionate, or lachrymose! The **motor centres** may be next affected, either after or before the perceptive centres, so that the **speech** may be uncertain and thick while the power of judgment is little affected, or the speech may remain tolerably distinct after the power of clear conception is entirely gone. The **cerebellum** appears to be affected sometimes before and sometimes after the cerebrum. This depends partly upon the constitution of the individual, and partly on the quality of the alcoholic liquor. The affection of the cerebellum gives rise to double vision, and inability to walk, from the relations of surrounding objects being no longer correctly perceived. After both cerebrum and cerebellum are paralysed, the **cord** may still retain its functional activity, so that the man who cannot walk may be able to ride, owing to the reflex contraction of the adductors produced by the impression of the saddle. The **respiratory centre** is next paralysed, if the quantity taken be sufficiently large. The **heart** continues to beat although the respiration may be paralysed; but if a sufficient dose of alcohol be administered, and respiration be kept up artificially in an animal, so as to allow it to act upon the heart, the cardiac ganglia may also become paralysed.

The sensibility of the **vaso-motor centre** to reflex impressions appears to be early destroyed, and the consequence of this is that injuries which in a sober man would produce death by shock, have comparatively little effect on a man who is drunk.

The **diagnosis** of drunkenness from opium-poisoning and from apoplexy is of great practical importance, for it occasionally happens that cases brought into hospital by the police have been dismissed as cases of drunkenness, and have proved afterwards to be apoplectic cases. The difficulty of diagnosis is increased by the fact that the patient may have had alcoholic drinks poured down his throat by sympathetic bystanders, so that the first indication of drunkenness, viz., the smell of alcohol in the breath, may occur equally in apoplexy. The other chief points of diagnosis are given under "Opium" (p. 769).

EFFECT OF IMPURITIES ON THE ACTION OF ALCOHOL.—It will be seen by the following table from Dujardin-Beaumetz that the toxic action of alcohol is greatly increased by impurities, so that inferior brandy from a public-house has a lethal action nearly one-half greater (as 5·30 to 7·75) than pure ethylic alcohol.

Kind of Spirit.	Mean toxic doses per kilogramme weight of body of dog, to cause death in 24—36 hours.		
	Spirits & brandies.	Crude.	Rectified.
	grammes.	grammes.	grammes.
Ethylic alcohol	7·75	...	...
Spirit of wine of Montpellier	7·50	...	...
,, ,, from pears	7·35	...	...
,, ,, from cider and from the marc of grapes	7·30	...	...
Spirit from grain	...	6·96	7·25
,, from molasses and beetroot	...	6·90	7·15
Brandy from a public-house (ordinary quality)	7·0	...	...
,, ,, (inferior quality)	5·30	...	...
Spirit from potatoes	...	6·85	7·10
,, ,, (said to have been ten times rectified)	...	...	7·35

CHRONIC ALCOHOLIC POISONING.—In persons who are accustomed to take an excessive quantity of alcoholic stimulants for a length of time, although perhaps never sufficient to produce the symptoms of acute intoxication, alterations are produced in the digestive and nervous systems. One of the commonest evidences of this condition is **vomiting** of watery fluid in the morning immediately after rising. The **bowels** are rarely, if ever, constipated, being generally open three or four times daily. There is a tendency to fatty degeneration of various organs, the **skin** acquires a satiny feeling, and the capillaries on the surface of the face often become prominently dilated, giving a characteristic hue to the complexion, which is often especially marked upon the nose. The **liver** is apt to undergo fatty degeneration, and, at first, to be congested. Afterwards, the connective tissue becomes increased, the organ contracts, interfering with the circulation in the abdominal viscera, and producing ascites. This may be complicated by cirrhosis of the **kidney** also. The **nervous system** may also be affected, the mental powers becoming impaired, the temper, at the same time, frequently being irritable, while a tremulousness appears in the tongue, lips, and hands.

When those accustomed to indulge freely in stimulants are attacked by acute disease, or when they receive injuries, or when, in consequence of a drinking bout, their stomachs are so deranged as to bring on loss of appetite and vomiting, and to lower their nutrition, they are liable to **delirium tremens.** So long as the drunkard is able to eat and digest his food, he is little liable to this disease. As a rule, delirium comes on in from two to four days after he has lost his appetite and begun to vomit. This delirium is marked by a peculiar tremor of the tongue, as well as of the limbs, and by delusions which are especially connected with the sense of

sight, the unfortunate patient imagining that he sees noxious animals crawling around him, or that he is plagued by demons, which are sometimes of a blue colour, from which the disease is popularly known as "blue devils." The tongue is moist, and covered with a thick white fur. There is loss of appetite and vomiting, which is often obstinate. The delirium is constant and active. It may become violent, and there is great restlessness and sleeplessness. It may gradually subside, and the patient recover his health, or a condition of mania may ensue. Patients sometimes die suddenly, without any warning symptoms.

The **treatment** of delirium tremens consists in keeping up the strength of the patient by a nutritive diet, and preserving him from exhaustion by combating the sleeplessness which would cause it. The vomiting, which is the chief obstacle to nutrition, is often well combated by a combination of bismuth, magnesia, and hydrocyanic acid, to which small quantities of morphine may be added. Until the patient is able to retain food, he ought to be fed by nutritive enemata, while chloral may be administered for the sleeplessness. A combination of chloral with bromide of potassium is often very useful. Large doses of digitalis have been given in order to quiet the delirium, and sometimes with benefit; but this is a very dangerous treatment, and it seems not improbable that the reason why the enormous doses of such a powerful drug have produced so little effect has simply been that they have not been absorbed from the stomach, for I have seen a case in which food lay undigested and unabsorbed in the stomach for a period of four days, after which it was vomited.

CAUSES OF CHRONIC ALCOHOLISM.—The craving for stimulants which leads to chronic alcoholic poisoning may be acquired by the habit of drinking in society; but it is not seldom due to the practice of taking alcohol in order to relieve depression of spirits, bodily or mental weakness, or inability to work as long or as well as might be desired. In men, the depression of spirits and feeling of weakness may be due to unfavourable physical surroundings, close atmosphere, over-work, exhausting discharges, or mental worry. In women, it may not only be connected with any of these, but also with uterine derangement. The craving appears to be partly gastric and partly systemic, and it is to be combated by the substitution for alcohol of other stimulants which will not have the same deleterious action. As a stimulant to the stomach, producing a sensation of warmth, tincture of capsicum is very useful, and aromatic spirit of ammonia stimulates both the stomach itself and the circulation and nervous system generally. A useful formula consists of 20 or 30 minims of aromatic spirit of ammonia, with 5 to 10 minims of tincture of capsicum, in two ounces of infusion of gentian or cascarilla. This draught, which amounts to an ordinary wineglass-full, should be taken when the craving is felt. In place of this draught a lemon may be sucked, or a glass of iced or cold water, or

effervescing water may be slowly sipped so as to get its stimulating action on the cerebral circulation (p. 161) and heart (p. 162). At the same time, chalybeate tonics and strychnine may be given in order to increase the nutrition of the tissues generally. The liquid extract of red cinchona bark has been recommended in such cases, and no doubt this medicine, along with easily digested food, beef-tea, and warm nutritious drinks, such as hot cocoa, may prove a useful adjunct in the treatment of chronic alcoholism.

In some patients the tendency to drink appears to be epileptic in character. The person affected by it will remain sober for weeks or even months, and then be suddenly seized with the fit, begin to drink, and remain drunk for several days together, and, after the conclusion of the bout, will again remain sober for a long time. I have seen a case in which this species of intermittent drunkenness was brought on by a fall from a horse, and was associated with epilepsy. The fit began with an intense craving for drink, and after one or two days' drunkenness epilepsy came on. If the desire for drink was not gratified, the fit came on sooner after the craving began than it would otherwise have done, but it was not so violent. The treatment in these cases is bromide of potassium combined with tonics.

USES.—The cold produced by the evaporation of alcohol when it is applied to the skin and rapidly dissipated by fanning or blowing upon it is useful in preventing syncope, in relieving headache, or in rousing from fainting or coma. For these purposes one of the most convenient forms of application is eau-de-cologne, and in cases of headache this may be used, diluted with equal parts of water, and applied by means of a thin handkerchief. The power of alcohol to harden the epidermis renders it a useful application in cases where we desire to hinder the formation of bed-sores or prevent the nipples from cracking. Brandy is the form most frequently employed for this purpose, as it stimulates the circulation when its evaporation is prevented, and especially when aided by friction. It has been used as a liniment in the form of brandy or spirit to sprained joints. A little brandy held in the mouth increases the secretion of saliva, and often relieves toothache. Alcohol is also a useful gargle in relaxed sore-throat, port wine being a form in which it is frequently applied for this purpose. It is also a useful astringent wash to the mouth in cases of profuse salivation. As in small doses it increases the secretion of gastric juice, it forms a useful addition to the meals of persons whose digestive powers are weak either in consequence of temporary exhaustion or from permanent debility, occurring in convalescence from acute disease, general malnutrition, or from old age. Some men, after being busily engaged all day, go home exhausted, and dine immediately on their arrival. The consequence of this is that their food remains undigested, and they suffer from weight of the stomach and drowsiness. This condition may generally be prevented

in persons below middle age, by simply making them rest for a while, so that the stomach, as well as the body generally, may recover from fatigue before the meal is taken, but in elderly individuals the addition of a little alcoholic stimulant may be necessary to insure digestion. This use of alcohol was noticed in the Ashantee campaign, in which the effect of alcohol as a stimulant, compared with beef-tea, was carefully tested. It was found that when a ration of rum was served out the soldier at first marched more briskly, but after about three miles had been traversed the effect of it seemed to be worn off, and he then lagged more than before. If a second ration were then given its effect was less marked, and wore off sooner than that of the first. A ration of beef-tea, however, seemed to have as great a stimulating power as one of rum, and not to be followed by any secondary depression. At the end of the march a short rest during the cooking of the evening meal seemed sufficient to enable the younger men to eat and digest it without the aid of rum, which they did not desire; but the men who had passed middle age not only wanted their own share of the alcohol, but were glad to get that of their younger comrades also.

In the intestine alcohol is used as a carminative to relieve flatulent distension, as an antispasmodic in colic, and as an astringent in diarrhœa.

Alcohol as a Stimulant.—As a stimulant alcohol seems serviceable in acute diseases running a limited course, where we wish to sustain the patient's strength until the crisis is past, as well as to prevent it sinking from debility afterwards. The various **rules** which have been given for the administration of alcohol (in fever) may be condensed into one. If the alcohol tends to bring the patient nearer to his normal condition it is doing good; if it takes him further away from a healthy condition it does harm. The points which are usually specially attended to are the condition of the tongue, pulse, respiration, skin, and nervous system.

If it is found that the alcohol (*a*) renders the dry tongue moist, (*b*) slows and strengthens the pulse when it is too quick, or quickens it when it has been abnormally slow, (*c*) slows the hurried respiration, (*d*) renders the skin cooler or moister when too hot and dry, and (*e*) lessens delirium and brings on sleep,—then its action is beneficial. If it have an opposite effect it is harmful. Useful indications regarding the advantage of alcohol, and the amount to be given in any particular case may be obtained by the practitioner remaining beside the patient, counting the pulse, and watching the tongue, respiration, skin, and general condition for a quarter of an hour after the dose has been given. He will thus be able to give more definite directions than he otherwise could as to its continuance when he is absent. Particular care should be taken in the administration of alcoholic stimulants to patients in the small hours of the morning. It is about this time that attendants are most apt to become sleepy, and therefore careless, and just at this time, also,

the external temperature is lowest, the fire is apt to get low, and the vital powers of the patient are most likely to sink. In giving alcoholic stimulants to support the strength in disease, care must be taken that they are not given so frequently, and in such large quantities, as to disorder the stomach and produce subacute gastritis. Sometimes, when given very freely to support the failing circulation, they have this effect; the result of which is that both food and stimulants are vomited, and the patient may be brought to death's door. The treatment here consists in the free administration of ice, along with two or three minims of solution of morphine and of hydrocyanic acid, frequently repeated until the vomiting is arrested.

During its **elimination** by the urine, alcohol may act as an irritant to the urinary passages when these are already inflamed. It is, consequently, injurious in gonorrhœa; and some sorts of beer, especially Bavarian beer, will even bring on gonorrhœa in persons who have previously had it, but who have been free from it at the time of taking the beer.

B.P. Alcohol. ABSOLUTE ALCOHOL. C_2H_5HO; 46.

PREPARATION.—By mixing rectified spirit with potassium carbonate and lime, both of which have a strong affinity for water, and then distilling.

CHARACTERS AND TESTS.—Colourless and free from empyreumatic odour. Specific gravity 0·795. It is entirely volatilised by heat; is not rendered turbid when mixed with water (no oils); and does not cause anhydrous sulphate of copper to assume a blue colour when left in contact with it (no water).

U.S.P. Alcohol. ALCOHOL.—A liquid composed of 91 per cent. by weight (94 per cent. by volume) of ethyl alcohol (C_2H_5HO; 46), and 9 per cent. by weight (6 per cent. by volume) of water.

CHARACTERS.—A transparent, colourless, mobile, and volatile liquid, of a characteristic, pungent and agreeable odour, and a burning taste. It should not change the colour of blue or red litmus paper previously moistened with water. It boils at 78° C. (172°·4 F.), and is readily inflammable, giving a blue flame without smoke. Specific gravity 0·820 at 15°·6 C. (60° F.), and 0·812 at 25° C. (77° F.).

IMPURITIES.—Fusel oil, amyl alcohol, methyl alcohol, aldehyde, oak tannin, foreign organic matters.

TESTS.—If a portion of at least 50 cc. be evaporated to dryness in a glass vessel, no residue or colour should appear. If mixed with its own volume of water and one-fifth its volume of glycerine, a piece of blotting paper on being wet with the mixture, after the vapour of alcohol has wholly disappeared, should give no irritating or foreign odour (no fusel oil). And if a portion be evaporated to one-fifth its volume, the residue should not turn reddish upon the addi-

tion of an equal volume of sulphuric acid (no amyl alcohol). When treated in a test-tube with an equal volume of solution of potassa, there should not be an immediate darkening of the liquid (no methyl alcohol, aldehyde, and oak tannin). If a portion of about 150 cc. be digested for an hour with 20 grs. of carbonate of lead and filtered, the filtrate then distilled from a water-bath, and the first 20 cc. of the distillate treated with 1 cc. of test-solution of permanganate of potassium, the colour should not disappear within one or two minutes (absence of methyl alcohol). If 20 cc. are shaken in a glass-stoppered vial, previously well rinsed with the same alcohol, with 2 cc. of test-solution of nitrate of silver, the mixture should not be rendered more than faintly opalescent during one day's exposure to direct sunlight (absence of more than traces of foreign organic matters, fusel oil, &c.).

B.P. Spiritus Rectificatus. RECTIFIED SPIRIT.—Alcohol, C_2H_6O, with 16 per cent. of water; obtained by the distillation of fermented saccharine fluids.

CHARACTERS AND TESTS.—Colourless, transparent, very mobile and inflammable, of a peculiar pleasant odour, and a strong spirituous burning taste. Burns with a blue flame without smoke. Specific gravity 0·838. Remains clear when diluted with distilled water. Odour and taste purely alcoholic. Four fluid ounces with thirty grain-measures of the volumetric solution of nitrate of silver exposed for twenty-four hours to bright light, and then decanted from the black powder which has formed, undergoes no further change when again exposed to light with more of the tests (no fusel oil).

IMPURITIES.—Water, fusel oil.

Spiritus Tenuior, B.P.; Alcohol Dilutum, U.S.P. PROOF SPIRIT, B.P.; DILUTED ALCOHOL, U.S.P.

Rectified spirit, 5 pints, mixed with distilled water 3 pints; specific gravity 0·920, B.P. Alcohol and distilled water equal parts; specific gravity 0·928 at 15·6° C. (60° F.), and 0·920 at 25° C. (77° F.), U.S.P.

Spiritus Vini Gallici, B. and U.S.P. SPIRIT OF FRENCH WINE. BRANDY.

Spirit distilled from French wine. It has a peculiar flavour, and a light sherry colour derived from the cask in which it has been kept, B.P. An alcoholic liquid obtained by the distillation of fermented grapes and at least four years old, U.S.P. It should contain from 39 to 47 per cent. by weight, or 46 to 55 per cent. by volume, of alcohol.

PREPARATION.

B.P.

Mistura Spiritus Vini Gallici.

B.P. Mistura Spiritus Vini Gallici. MIXTURE OF SPIRIT OF FRENCH WINE. EGG FLIP (*vide* also Eggs). Beat up together brandy and cinnamon-water, of each 4 fl. oz., the yolks of two eggs, and sugar ½ ounce. DOSE.—1-2 fl. oz.

B.P. Vinum Xericum. SHERRY.—A Spanish wine.

CHARACTERS.—Pale yellowish brown, containing about 17 or 18 per cent. of alcohol.

USES.—As a stimulant, and in preparing all the wines of the B.P. except Vinum Ferri Citratis and Vinum Quiniæ.

U.S.P. Vinum Album. WHITE WINE.

CHARACTERS.—A pale, amber-coloured or straw-coloured alcoholic liquid, made by fermenting the unmodified juice of the grape freed from seeds, stems, and skins. White wine should have a full fruity agreeable taste without excessive sweetness or acidity; and it should have a pleasant odour free from yeastiness. Its sp. gr. at 15°·6 C. (60° F.) should not be less than 0·990 nor more than 1·010.

IMPURITY.—Tannic acid.

TESTS.—If 10 cc. of white wine be diluted with an equal volume of distilled water, and treated with 5 drops of test-solution of ferric chloride, only a faint greenish-brown colour should make its appearance (absence of tannic acid.) Upon evaporation and twelve hours' drying on the water-bath, it should leave a residue of not less than 1·5 per cent. nor more than 3·0 per cent. Using litmus-paper as an indicator 250 cc. of white wine should require for complete neutralisation not less than 15 nor more than 26 cc. of the volumetric solution of soda.

U.S.P. Vinum Album Fortius. STRONGER WHITE WINE.

COMPOSITION.—White wine 7 parts, alcohol 1 part. When tested for alcohol it should not contain less than 20 nor more than 25 per cent. of absolute alcohol by weight.

USE.— In preparing all the medicated wines in the U.S.P.

U.S.P. Vinum Rubrum. RED WINE.

A deep red alcoholic liquid, made by fermenting the juice of coloured grapes in presence of their skins.

CHARACTERS.—Red wine should have a full, fruity, moderately astringent, pleasant taste without decided sweetness or excessive acidity. It should have a pleasant odour free from yeastiness. Its sp. gr. at 15°.6 C. (60° F.) should not be less than 0·989 nor more than 1·010.

TESTS.—If 10 cc. of red wine be diluted with an equal volume of distilled water, and treated with 5 drops of test-solution of ferric chloride, the liquid should acquire a brownish-green colour due to tannic acid. Upon evaporation and twelve hours drying on the water-bath, it should leave a residue of not less than 1·6 per cent. nor more than 3·5 per cent.

Using litmus-paper as an indicator, 250 cc. of red wine should require for complete neutralisation not less than 15 nor more than 26 cc. of the volumetric solution of soda. If 50 cc. of red wine be treated with a slight excess of water of ammonia, the liquid should acquire a green or brownish-green colour; if it

be then well shaken with 25 cc. of ether, the greater portion of the ethereal layer removed, and evaporated in a porcelain capsule with excess of acetic acid and a few fibres of uncoloured silk, the latter should not acquire a crimson or violet colour (absence of aniline colours). With test-solution of acetate of lead, red wine should form a heavy precipitate, which may vary in colour from bluish-green to green.

B.P. Alcohol Amylicum. AMYLIC ALCOHOL.

Amylic alcohol, $C_{10}H_{12}O_2$ or $C_5H_{12}O$, with a small proportion of other spirituous substances. An oily liquid, contained in the crude spirit produced by the fermentation of saccharine solutions with yeast, and separated in the rectification or distillation of such crude spirit.

CHARACTERS AND TESTS.—A colourless liquid with a penetrating and oppressive odour, and a burning taste. When pure its specific gravity is ·818, and its boiling point 270°. Sparingly soluble in water, but soluble in all proportions in alcohol, ether, and essential oils. Exposed to the air in contact with platinum-black it is slowly oxidised, yielding valerianic acid.

PREPARATIONS IN WHICH AMYLIC ALCOHOL IS USED.

Sodæ Valerianas. Amyl Nitris.

USES.—It is oxidised into valerianic acid.

ALDEHYDES.

These substances in their chemical constitution lie between alcohols and acids. They are obtained from alcohols by the removal of two atoms of hydrogen, hence the name aldehyde (*al*cohol *dehyd*rogenatum).

Ethyl Aldehyde.—Synonyms—aldehyde, acetic aldehyde, or ethylidene oxide. C_2H_4O. Not officinal.

PREPARATION.—It may be prepared in several ways, as the hydrogen can be removed from alcohol either by oxidising agents or chlorine. $C_2H_6O + O = C_2H_4O + H_2O$, or $C_2H_6O + Cl_2 = C_2H_4O + 2HCl$.

CHARACTERS.—A colourless, mobile liquid, with an ethereal, acrid, and suffocating odour. Specific gravity 0·79. Boiling point, 22° C. (71°·6 F.).

ACTION.—It is antiseptic. It has a strong local irritant action. When inhaled it causes excitement followed by anæsthesia. It has a powerfully depressant action on respiration, and rapidly produces asphyxia, so that it is not used as an anæsthetic.

Paraldehyde. $C_6H_{12}O_3$.—It appears to be a polymeric modification of aldehyde. Not officinal.

CHARACTERS.—A colourless fluid.

ACTION.—It is a pure **narcotic**, causing sleep like chloral. It is about half the strength of chloral, and is said to be without any

depressing action on the heart and respiration. It may thus be used instead of chloral in cases of weak heart. Its local action renders its use unadvisable in severe gastric disorders and laryngeal phthisis.

DOSE.—3 to 6 Gm., or more.

ADMINISTRATION.—It is soluble in about 8 parts of water, and may be given with glycerine, syrup of tolu, or syrup of oranges.

SIMPLE ETHERS.

These correspond in structure to oxides in which the place of a metal is taken by an alcohol radical, thus potash, $\left.\begin{matrix}K\\K\end{matrix}\right\}O$ or K_2O, corresponds to $\left.\begin{matrix}C_2H_5\\C_2H_5\end{matrix}\right\}O$ or $(C_2H_5)_2O$, ethylic ether.

Æther, B. and U.S.P. $(C_2H_5)_2O$; 74. ETHER.

A volatile liquid prepared from alcohol, and containing not less than 92 per cent. by volume of pure ether, $C_4H_{10}O$, B.P. A liquid composed of about 74 per cent. of ethyl oxide, C_2H_5O; and about 26 per cent. of alcohol containing a little water. Specific gravity about 0·750 at 15° C. (59° F.), U.S.P.

PREPARATION.—By distilling rectified spirit with sulphuric acid, and freeing the ether thus obtained from water by redistillation with calcium chloride and lime.

In this process ethylsulphuric or sulphovinic acid and water are first formed, ethyl replacing one atom of hydrogen in the sulphuric acid.

Sulphuric Acid.		Alcohol.		Ethylsulphuric Acid.		Water.
$\left.\begin{matrix}H\\H\end{matrix}\right\}SO_4$	+	$\left.\begin{matrix}C_2H_5\\H\end{matrix}\right\}O$	=	$\left.\begin{matrix}C_2H_5\\H\end{matrix}\right\}SO_4$	+	$\left.\begin{matrix}H\\H\end{matrix}\right\}O.$

By the action of fresh alcohol on the ethylsulphuric acid it is decomposed, ether being formed and sulphuric acid being reproduced.

Ethylsulphuric Acid.		Alcohol.		Sulphuric Acid.		Ether.
$\left.\begin{matrix}C_2H_5\\H\end{matrix}\right\}SO_4$	+	$\left.\begin{matrix}H\\C_2H_5\end{matrix}\right\}O$	=	$\left.\begin{matrix}H\\H\end{matrix}\right\}SO_4$	+	$\left.\begin{matrix}C_2H_5\\C_2H_5\end{matrix}\right\}O.$

Theoretically this process might go on *ad infinitum* if fresh alcohol were continually supplied, but practically the acid volatilises partly in the form of oil of wine, so that the process cannot go on indefinitely.

CHARACTERS AND TESTS.—A colourless, very volatile and inflammable liquid, emitting a strong and characteristic odour, and boiling below 105°. Specific gravity 0·735. Fifty measures agitated with an equal volume of water are reduced to 45, by an absorption of 10 per cent. It evaporates without residue.

IMPURITIES.—Water, alcohol, and fixed impurities.

TESTS.—Water is detected by the greater sp. gr., and so is alcohol; the fixed impurities by their remaining on evaporation.

DOSE.—20 to 60 min.

PREPARATIONS.

B.P.	
Æther Purus	
Collodium	6 volumes in 8 nearly.
,, Flexile	6 volumes in 8 ,,
Liquor Epispasticus	4 volumes in 5 ,,
Spiritus Ætheris	1 volume in 3 ,,

B.P. Æther Purus. PURE ETHER.—Ether, $C_4H_{10}O$, free from alcohol and water.

PREPARATION.—By washing ether with distilled water, and then distilling from calcium chloride and recently calcined lime.

USES.—Used as an **anæsthetic**; to prepare some alkaloids, as aconitine; to test the amount of quinine in bark.

TEST.—Specific gravity not exceeding 0·720.

U.S.P. Æther Fortior. STRONGER ETHER, $(C_2H_5)_2O$; 75.

PREPARATIONS.

Spiritus Ætheris. Spiritus Ætheris Compositus.

CHARACTERS.—A liquid composed of about 94 per cent. of ethyl oxide and about 6 per cent. of alcohol, containing a little water. Specific gravity not higher than 0·725 at 15° C. (59° F.) or 0·716 at 25° C. (77° F.).

Ether is highly inflammable, and its vapour when mixed with air and ignited explodes violently.

It should boil actively in a test-tube half filled with it and held a short time in the hand on the addition of small pieces of broken glass.

USES.—Used for inhalation as an **anæsthetic.**

Spiritus Ætheris, B. and U.S.P. SPIRIT OF ETHER.—It is a mixture of ether (1), rectified spirit (2).

TEST.—Specific gravity, 0·809.

DOSE.—30 to 90 min.

PREPARATION.

B.P.

Tinctura Lobeliæ Ætherea.

USES.—Spirit of ether is used as carminative and stimulant. It is useful in lessening the pain in passage of biliary or urinary calculi.

ACTION OF ETHER.—When applied to the **skin** ether evaporates very readily, and causes intense cold. The application of ether to the surface will freeze it completely, and render it perfectly insensitive to pain. If the freezing be continued for too long a time,

the frozen part may be killed, and separate as a slough. In the **mouth**, ether acts as a powerful stimulant to the salivary secretion. In the **stomach** it increases the secretion of gastric juice, stimulates the movements of the organ, expels flatulence, and probably tends to increase the co-ordination of the movements of the stomach and **intestine,** so that it diminishes spasm and relieves pain. When absorbed into the circulation from the intestine, or, still more markedly, when absorbed from the lungs after an inhalation, it first stimulates the **circulation,** and, after a very brief, and perhaps hardly perceptible period of stimulation of the nerve centres, it depresses their powers in succession. First of all, it affects the **cerebral hemispheres,** causing delirium and unconsciousness; next, the grey matter of the **spinal cord;** next the white matter of the spinal cord, and lastly, the cardiac and vaso-motor centres in the **medulla oblongata.** It does not appear to destroy the irritability of the **muscles** in animals poisoned by it, but muscles exposed to its vapour soon lose their contractility, and fall into a condition of *rigor mortis.* **Nerves,** also, which are exposed to its vapour, lose their irritability, so that when attempted to be irritated they no longer respond, the irritability of the sensory fibres apparently disappearing before that of the motor fibres. When the vapour is applied only for a short time, they may regain their irritability, but if its application be continued too long, the irritability is permanently destroyed. There is no marked alteration in the blood of animals poisoned by ether, but when mixed in small quantity with **blood** outside the body, it appears to form a compound with the hæmoglobin, and to lessen its oxidising power. If mixed with the blood in large quantity, it destroys the blood corpuscles, probably by dissolving the protogen which forms an essential constituent of them.

The **heart** is very much less easily paralysed by ether than by chloroform. If two rabbits are thoroughly narcotised by ether and chloroform vapour respectively, and the thorax opened, and artificial respiration kept up with air containing these vapours, the heart of one can be readily stopped by increasing the proportion of chloroform vapour in the air blown in, whereas the heart of the other is only arrested when the proportion of ether vapour becomes exceedingly large. It is this peculiarity of ether which gives it the advantage over chloroform, and renders death from syncope during operations less probable when ether is employed as an anæsthetic.

Another **difference between ether and chloroform,** which renders the former much safer as an anæsthetic, is that the vaso-motor centre appears, like the heart, to be very much less readily affected by ether than by chloroform, so that irritation of a sensory nerve continues for a longer time to raise the blood-pressure when ether is employed as an anæsthetic. The disadvantages of ether are that it is less agreeable to take, and that its odour hangs

unpleasantly about the patient for a much longer time than is the case with chloroform. It causes greater irritation of the air passages, and may produce a catarrhal condition. It has to be administered in a more concentrated form than chloroform, and thus is not so convenient as the latter when operations on the face and mouth are necessary. It is frequently administered along with nitrous oxide, the nitrous oxide being first given alone until the patient is sufficiently under its influence not to notice the taste or smell of the ether. Nitrous oxide loaded with ether vapour is then given, and as soon as complete insensibility is induced air is mixed with ether vapour, the anæsthesia being maintained by regulating the proportion of vapour according to the condition of the patient.

SALINE ETHERS.

These correspond to metallic salts, in which the metal is replaced by an organic radical, *e.g.*:

Potassium Sulphate. $\left.\begin{matrix}K\\K\end{matrix}\right\}SO_4$ or K_2SO_4

Ethyl Sulphate. $\left.\begin{matrix}C_2H_5\\C_2H_5\end{matrix}\right\}SO_4$ or $(C_2H_5)_2SO_4$.

U.S.P. Oleum Æthereum. ETHEREAL OIL.—A volatile liquid, consisting of equal volumes of heavy oil of wine and of stronger ether.

The heavy oil of wine is either a mixture of ethyl sulphate $(C_2H_5)_2SO_4$, ethyl sulphite $(C_2H_5)_2SO_3$, and a polymeric form of ethylene (C_2H_4), or else a sulphovinate of a hydrocarbon radical.

PREPARATION.—By mixing alcohol with sulphuric acid, allowing it to stand for twelve hours, and then distilling. The distillate consists of three layers—ether, water and yellow ethereal oil of wine. The yellow oil of wine is separated and exposed to the air for twenty-four hours in a shallow capsule, so that any ether evaporates. It is then put in a wet filter, washed with distilled water, and mixed with an equal volume of stronger ether.

CHARACTERS.—A transparent, nearly colourless, volatile liquid, of a peculiar aromatic ethereal odour, a pungent, refreshing, bitterish taste, and a neutral reaction to dry litmus-paper. Specific gravity, 0·910.

PREPARATION.
Spiritus Ætheris Compositus.

Spiritus Ætheris Compositus, B. and U.S.P. COMPOUND SPIRIT OF ETHER.—Hoffmann's anodyne.

COMPOSITION.—Stronger ether 30, alcohol 67, ethereal oil 3 parts.

USE.—Like that of spirit of ether, but more powerful. It is given in similar doses.

Æther Aceticus, B. and U.S.P. ACETIC ÆTHER. $C_2H_5C_2H_3O_2$; 88. ACETATE OF ETHYL.

PREPARATION.—By distilling rectified spirit with acetate of soda and sulphuric acid, $NaC_2H_3O_2 + H_2SO_4 + C_2H_6O = C_2H_5,C_2H_3O_2 + NaHSO_4 + H_2O$. The acetic ether and water distil over together, and they are separated by means of calcium chloride.

CHARACTERS.—A transparent and colourless liquid, of a strong fragrant ethereal and somewhat acetous odour, a refreshing taste and a neutral reaction.

DOSE.—20 to 60 min.

USES.—It has an action much like ether, but is inconvenient as an anæsthetic. It has a pleasanter taste than ether, and is used as a stimulant, carminative, and **antispasmodic.** It may be given along with the acetates of iron and potash in albuminuria.

Spiritus Ætheris Nitrosi, B. and U.S.P. SPIRIT OF NITROUS ETHER.

A spirituous solution containing nitrous ether ($C_2H_5NO_2$; 75), B.P. An alcoholic solution of ethyl nitrite ($C_2H_5NO_2$; 75), containing 5 per cent. of the crude ether, U.S.P.

PREPARATION.—By distilling rectified spirit with nitric and sulphuric acids and copper wire, and diluting the distillate with spirit. In this process the copper reduces the nitric to the nitrous radical.

$$C_2H_5HO + HNO_3 + H_2SO_4 + Cu = C_2H_5NO_2 + 2H_2O + CuSO_4.$$

IMPURITIES.—Water, free acid.

CHARACTERS AND TESTS.—Transparent and nearly colourless, with a very slight tinge of yellow, mobile, inflammable, of a peculiar penetrating apple-like odour, and sweetish cooling sharp taste. Specific gravity, 0·845. It effervesces feebly or not at all when shaken with a little bicarbonate of soda (no acid). When agitated with solution of sulphate of iron and a few drops of sulphuric acid it becomes deep olive-brown or black. If it be agitated with twice its volume of saturated solution of chloride of calcium in a closed tube, 2 per cent. of its original volume will separate in the form of nitrous ether and rise to the surface of the mixture (proper strength).

DOSE.—$\frac{1}{2}$ to 2 fluid drachms.

USE.—Is used as a **diaphoretic** and **diuretic.**

PREPARATION.

U.S.P.

Mistura Glycyrrhizæ Composita.

Amyl Nitris, B. and U.S.P. NITRITE OF AMYL. $C_5H_{11}N_2O_2$; 117.

PREPARATION.—By distilling dilute amyl alcohol with nitric acid, sulphuric acid and copper wire. The distillate is washed with caustic soda to remove hydrocyanic and other acids; the moisture removed by potassium carbonate, and the nitrite purified by fractional distillation.

CHARACTERS.—A yellowish liquid with a strong ethereal, fruity smell. When freely exposed to air it decomposes, leaving a large residue of amyl alcohol. Insoluble in water, but soluble in all proportions in alcohol, ether, and chloroform.

IMPURITIES.—It is apt to contain free acid, nitrate of amyl, nitro-pentone.

TESTS.—The physiological test is the most certain. One or two sniffs from a bottle containing the nitrite are usually sufficient to produce flushing of the face and fulness in the head. If the preparation is impure or has lost its strength, this effect does not occur. Some specimens are entirely inert.

PHYSIOLOGICAL ACTION.—When mixed with **blood** it forms methæmoglobin; which is not so readily de-oxidised as hæmoglobin itself. The blood, under the influence of the nitrite, becomes of a dark chocolate colour, both in the arteries and veins, and oxidation in the body is interfered with; so much so that in rabbits convulsions almost exactly resembling those of ordinary asphyxia are very rapidly produced by the inhalation of the drug. The methæmoglobin may be broken up by reducing agents, and the blood will then take up oxygen again. It is therefore probable that when the venosity of the blood becomes great, the unoxidised products of tissue-waste will act as reducing agents, and again restore the internal respiration. When **inhaled,** nitrite of amyl causes at first a short dry tickling cough, followed in about half a minute by flushing of the face, throbbing of the carotids and their branches, a quicker and fuller pulse, a feeling of tension in the head, sometimes lachrymation, quickened respiration, and giddiness. The giddiness is more especially felt if the patient is sitting up. If the dose of nitrite be large the respiration becomes very quick, laboured, and dyspnœic. The **blood-pressure** is very greatly lessened by nitrite of amyl, the diminution being chiefly due to dilatation of the arterioles. The **pulse** in man and in dogs is very much quickened by it. In rabbits the acceleration is not so great. This appears to show that the quickening is in a great measure due to diminution in the tone of the vagus roots in the medulla caused by the fall of blood-pressure. The dilatation of the arterioles appears to be due to weakening or paralysis, either of the muscular walls of the arterioles themselves, or of the vaso-motor ganglia in or near them. This is shown by the fact that the nitrite of amyl lowers the blood-pressure in animals, even after the cord has been divided just below the medulla. It has been objected to this that Bernheim has found that when the capillaries are dilated by nitrite of amyl they may still be made to contract, by irritation of the vaso-motor nerves; and he concludes from this that the dilatation is due rather to paralysis of vaso-motor centres than to vaso-motor nerves, or to the arterioles. It is possible that the dilatation may be partly due to weakening of the vaso-motor centres also; but Bernheim's objection is altogether without force, because

in animals killed by curare, the muscles will still contract on the application of an electric current to the motor nerves. In this case the nerves are so far paralysed that they will no longer respond to the stimuli sent down from the nerve-centres, although they will do so to strong currents, and probably the same thing occurs with the muscular walls of the arterioles when paralysed by nitrite of amyl.

Action on Muscles.—The voluntary muscles are not paralysed in animals poisoned by nitrite of amyl, but when the muscles of a frog are exposed to the vapour they soon lose their contractility. It was stated by Dr. Richardson that nitrite of amyl, like curare, paralysed the ends of the **motor nerves,** and that it acted in consequence as an antidote to strychnia. On repeating his experiments other observers have failed to detect any paralysis of motor nerves; I have found that nitrite of amyl alone does not paralyse them, nor does strychnine alone, but if a frog be poisoned with strychnia after one leg has been protected by a ligature from the influence of poison, and is then exposed to the vapour of nitrite of amyl, the joint action of the strychnine and nitrite paralyses the ends of the motor nerves, while the nerves of the limb protected from the strychnine retain their irritability, although both were equally exposed to the nitrite of amyl.[1]

Action on the Nervous System.—It lessens reflex action, apparently by its action on the spinal cord.

On the Urine.—When nitrite of amyl is given to animals either by inhalation or hypodermically, sugar appears in the urine.

USES.—The action of nitrite of amyl in causing flushing was first observed by Guthrie, and Dr. B. W. Richardson recommended it as a remedy in spasmodic conditions, from the power he thought it to possess of paralysing motor nerves. In the spring of 1867 I had opportunities of constantly observing a patient who suffered from angina pectoris, and of obtaining from him numerous sphygmographic tracings, both during the attack and during the interval. These showed that during the attack the pulse became quick, the blood-pressure rose, and the arterioles contracted; for the form of the pulse curve was such as could only be caused by contraction of the arterioles (Fig. 135). The pain, which came on every night, lasted for one and a half or two hours. All other remedies were nearly useless, though bleeding always removed the pain for one night. It seemed probable that the great rise in tension was the cause of the pain, and it occurred to me that if it was possible to diminish the tension by drugs instead of by bleeding, the pain would be removed.

I knew from unpublished experiments by Dr. A. Gamgee, that nitrite of amyl had this power, and therefore tried it on the patient. My expectations were perfectly answered. The pain

[1] These experiments were made with *Rana temporaria*.

usually disappeared in three quarters of a minute after the inhalation began, and at the same time the pulse became slower and much fuller, and the tension diminished. Occasionally the



FIG. 135.—Normal pulse-tracing of a patient suffering from aortic regurgitation and angina pectoris.

pain would disappear, though the pulse regained its normal fulness, and on these occasions the pain always reappeared after the lapse of a few minutes (Fig. 136). Whenever the pulse again regained its

FIG. 136.—Tracing of the same pulse during severe anginal pain.

normal character completely (Fig. 137), I knew that the pain would not again return.



Fig. 137.—Tracing of the same pulse during temporary relief of pain by nitrite of amyl. The pain returned after a few minutes.

In some cases of angina pectoris nitrite of amyl has failed. One reason of this may be either that the drug has not been pure, or that it has undergone changes from age. In one case mentioned to me by Dr. Balfour, the patient was only relieved by nitrite of amyl newly made, the drug appearing to lose its power in a few days. From its power of relaxing vascular spasm, I used it in headache and found it occasionally serviceable. As migraine is generally connected with vascular spasm, I employed the nitrite of amyl in headache, and found that frequently, though not invariably, it relieved the pain. It was also useful in neuralgia of the scalp. As epilepsy has been supposed to depend upon spasmodic contraction of the cerebral vessels, I employed it in this disease, during the fit, without success, but Dr. Crichton Browne found that when administered immediately after the appearance of

the aura it prevented the fit which would otherwise have come on. In sea-sickness, a disease probably of cerebral, rather than gastric, origin, nitrite of amyl appears to give relief. It has been employed to aid circulation in cases of syncope, and in chloroform poisoning, its administration in the latter case being combined with the depression of the patient's head below the level of his body, and the use of artificial respiration. In spasmodic asthma it sometimes affords some relief, but this is not very marked. It is useful in the case of persons who are subject to sudden flushes of heat and profuse perspiration.

The administration of nitrite of amyl is not attended with much danger. I have pushed it in many cases, and have seen no bad effects from its use. In cases of chronic bronchitis and emphysema, however, it is advisable not to give it even for the relief of asthmatic attacks which come on in this disease, as the difficulty of breathing already present may be seriously increased by the action of the drug upon the blood. It has been thought that its administration would be especially dangerous in aortic disease; and no doubt it is well both in this disease and in other cases to give the drug in the recumbent posture and thus avoid the faintness which might otherwise occur. Although it causes a feeling of fulness in the head, little danger of apoplexy is to be apprehended from it, because the blood-pressure, instead of being higher, is much lower than usual, and therefore the tendency of the vessel to burst must be reduced to its minimum.

Nitro-glycerinum. NITRO-GLYCERINE, GLONOINE. $C_3H_5(NO_3)_3$. Not officinal.

PREPARATION.—By dropping pure glycerine into a mixture of sulphuric and nitric acid kept cool by ice, pouring the mixture into water; washing it well; and carefully drying in a warm room.

PROPERTIES.—A colourless transparent liquid; aromatic taste; slightly soluble in water, readily soluble in absolute alcohol and ether, soluble also in oils and fats.

DOSE.—$\frac{1}{200}$ to $\frac{1}{50}$ increased to $\frac{1}{10}$ grain.

PREPARATIONS (Non-officinal).[1]

	DOSE.
Liquor Nitro-glycerini (1 gr. in 100 min. rectified spirit)	...$\frac{1}{2}$-10 min.
Pilula Nitro-glycerini ($\frac{1}{50}$ or $\frac{1}{100}$ gr. with cacao butter)	.....1-2, or more.
Trochischi Nitro-glycerini. (Nitro-glycerine tablets.) ($\frac{1}{100}$ gr. in chocolate)	.....1-2, or more.

ACTION.—Its action is much **like** that of nitrite of amyl and other **nitrites,** but is more persistent. In frogs it causes at first great restlessness, then lethargy, to which convulsions and paralysis succeed. In **mammals** it causes depression, with very rapid pulse and respiration, paralysis of reflex action and voluntary motion, loss of sensation, and death by stoppage of the respiration. It agrees with nitrites in acting as a poison to **muscle.** The **spinal**

[1] Martindale and Westcott, *The Extra Pharmacopœia.*

cord appears to be paralysed before the cerebral ganglia, and the convulsions in frogs are of cerebral rather than spinal origin. It paralyses the **heart** of the frog when directly applied. It diminishes the oxidising power of the **blood** and communicates to it a chocolate colour, like nitrites, and like them also it lessens the **blood-pressure.** In some persons it produces intense **headache** even in exceedingly minute doses. It is curious that its action upon the blood and organs should so exactly resemble that of nitrites, because nitro-glycerine is a nitrate and not a nitrite of glyceryl. Hay has shown, however, that nitro-glycerine is decomposed by alkalies, two-thirds of its nitric acid being reduced to nitrous acid and uniting with the alkali to form a nitrite, whilst the remaining third is set free without reduction and forms a nitrate.

The reasons why nitro-glycerine acts more powerfully than nitrites probably are that the whole of it is absorbed without decomposition, and that nitrous acid being set free in the blood in a nascent condition is more active than it would otherwise be.

USES.—Like nitrite of amyl, it is useful in angina pectoris, headache, neuralgia, epileptic vertigo, and epilepsy. Its action being more persistent than that of nitrite of amyl, it is sometimes more efficacious. It sometimes is of service in spasmodic asthma, uræmic asthma, and in puerperal convulsions. It frequently relieves sea-sickness, and may lessen pain in gastralgia and hepatic colic. By dilating the vessels it may cut short or prevent the cold stage of ague. By lessening the arterial tension and diminishing the resistance the heart has to overcome, it is useful when the heart is weak in old persons, or from fatty degeneration, or where the tension is abnormally high, as in Bright's disease. In conjunction with elaterium it is said to have proved useful in myxœdema.

HALOID COMPOUNDS.

These correspond to haloid salts of metals, *e.g.*:

Potassium Bromide.	Ethyl Bromide.
KBr	$(C_2H_5)Br$.

Æthyl Bromidum. BROMIDE OF ETHYL. C_2H_5Br (Hydrobromic Ether).—Not officinal.

PREPARATION.—By distilling alcohol with bromine and phosphorus.

CHARACTERS.—A colourless volatile liquid; of peculiar odour, sweetish taste. Specific gravity, 1·419.

ACTION AND USES.—When applied as spray it produces local anæsthesia, which seems to depend on the action of the drug on the nerves as well as on the cold produced. It is used as a local anæsthetic in neuralgia. When inhaled it produces **anæsthesia,** and has been recommended as an anæsthetic either alone or as a

mixture of 1 part of it with 3 of chloroform and 4 of alcohol. Its advantages are that it is not inflammable like ether, that it does not irritate the respiratory passages, and that it causes less excitement and struggling than ether or chloroform, and is less depressing than chloroform. Its disadvantages are that it is not absolutely safe, as one death at least has occurred from its use. Its odour remains longer in the breath than either chloroform or ether, and some patients dislike its smell extremely.

Æthyl Iodidum. IODIDE OF ETHYL, C_2H_5I. (Hydriodic Ether).—Not officinal.

PREPARATION.—Like bromide of ethyl, using iodine instead of bromine.

CHARACTERS.—A colourless liquid, with a penetrating odour. It is apt to become decomposed by keeping, and acquire a brown colour from free iodine.

ACTION AND USES.—It has an **anæsthetic** action when inhaled, which is more slowly produced but is more persistent than that of ethyl bromide. It is decomposed in the body, and the iodine is excreted in the urine as iodide of potassium. It has been given internally as an **alterative** in doses of 0·2 to 0·5 Gm. in scrofula and rheumatism, and as a **diuretic** in cases of cardiac dropsy. Its chief use, however, is as an **antispasmodic** in asthmatic paroxysms, either of the purely spasmodic kind, or occurring in chronic bronchitis and emphysema, or in cardiac or laryngeal disease. In some of these cases it gives very great relief, and not only cuts short the paroxysm, but benefits the bronchitic condition, where this is present (cf. p. 546).

ADMINISTRATION.—It is best given in small glass capsules, containing 5 minims, and incased in cotton-wool and silk. These can be readily carried about, and when the paroxysm comes on one is crushed between the finger and thumb, and the vapour inhaled from the cotton-wool, which becomes soaked by the iodide.

Chloral Hydras, B.P.; Chloral, U.S.P. $C_2HCl_3O.H_2O$; 165·2. HYDRATE OF CHLORAL (CHLORAL HYDRATE), B.P.; CHLORAL, U.S.P.

PREPARATION.—By saturating absolute alcohol with dry chlorine gas much hydrochloric acid gas is formed, and the alcohol is first reduced to aldehyde, which is then attacked by the chlorine, forming tri*chloral*dehyde, a word which has been shortened to chloral. Chloral is an oily liquid, which unites with a small quantity of water to form chloral hydrate.

CHARACTERS.—Whitish crystals with a peculiar very pungent odour, a bitterish caustic taste, and a neutral reaction. It melts when heated, forming colourless liquid, and volatilises if the temperature be further raised. It is soluble in less than its own weight of water, alcohol, or ether, and in four parts of chloroform. When mixed with carbolic acid or camphor it liquefies. When

mixed with alkalies it is decomposed into chloroform and a formate of the base.

IMPURITIES.—Hydrochloric acid and oily impurities.

TEST.—The aqueous solution should be neutral or only slightly acid. A solution in chloroform when shaken with sulphuric acid should not impart colour to the acid (absence of oily impurities).

PREPARATION.

B.P.		DOSE.
Syrupus Chloral.	SYRUP OF CHLORAL. Chloral in syrup and water, 10 grs. in each fl. dr.....	1 fl. dr.

ACTION OF ANHYDROUS CHLORAL.—Anhydrous chloral applied to the skin is absorbed and converted in the organism into chloral hydrate. When thus applied it sometimes occasions hæmoglobinuria and nephritis. Anhydrous chloral being little used, the name "chloral" is applied in ordinary conversation to chloral hydrate, and in the following account of the action of chloral hydrate the name chloral is intended to apply to the hydrate.

ACTION OF CHLORAL HYDRATE.—It destroys low organisms, and prevents the decomposition which they occasion. It is therefore sometimes used as an **antiseptic**. In the **mouth** chloral has a hot, burning taste, and when applied to a raw surface, or to the mucous membrane of the eye, it is a powerful irritant. When injected under the skin in a strong solution it is apt to cause inflammation and suppuration. It was introduced into medicine by Oscar Liebreich with the object of attaining by it the same effects as those of chloroform slowly administered for a length of time. When chloral is mixed with an alkali it is split up, yielding formic acid which combines with the alkali and chloroform. Liebreich thought that if chloral were administered internally the alkalies of the blood would slowly split it up, and that chloroform would thus be slowly generated from it in the circulating blood for a considerable length of time. His expectations regarding the utility of chloral as a means of producing sleep and relieving pain have been fully answered, but the theory which led him to employ chloral appears to be erroneous, and it probably acts as a hypnotic and analgesic without undergoing any decomposition in the body. The experiments which have led to the conclusion that chloral is not decomposed in the body are chiefly those of Hammersten, who found that when a stream of carbonic acid was passed through the blood taken from chloralised animals, and then passed through a red-hot tube into a mixture of starch paste and iodine or a solution of nitrite of silver, no reaction occurred, and that the slightest addition of chloroform to the blood or the administration of the chloroform to the animal beforehand always caused a reaction to take place. The expired air of chloralised animals is also free from chloroform. The chloral is excreted in the urine as such so long as the urine is acid,

and it is only when the urine is alkaline that chloroform is found in it, this being formed by the decomposition of the chloral by the alkali in the urine itself. In **frogs,** small doses slow the respiration, and abolish reflex action, but the animal recovers perfectly after several hours. When the dose is increased, the stoppage of the heart follows the cessation of reflex movements and the animal dies. In **mammals,** the respiration also becomes slow, the pupil contracted, and sleep occurs. From this the animal may first be awakened with ease, but it gradually becomes deeper, and the reflex movements disappear. Insensibility occurs first to painful impressions, so that the animal may be cut or burned without showing the slightest symptoms of sensation, whereas it will still withdraw its limb quickly when a slight pressure is made upon the toes. When larger doses are given, the **temperature** gradually falls until it can no longer be measured by an ordinary clinical thermometer. The **respiration** gets slower and weaker, and finally ceases altogether. When chloral is added to the **blood,** it causes the red corpuscles to swell up and become paler, but does not dissolve them.

Action on the Circulation.—It diminishes the blood-pressure in two ways—first by weakening and finally paralysing the **vaso-motor centre,** and thus dilating the vessels; and secondly by weakening the heart. The **pulse** may at first be quickened, possibly, in consequence of the lessened blood-pressure, but it afterwards becomes slow. The slowing of the pulse is not due to any action of the drug upon the vagus, for it occurs after section of the vagi, or after the previous administration of nicotine, atropine, or curare. The weakening and final stoppage of the heart appears to be due to paralysis of the cardiac **ganglia,** as the heart still continues to contract when its muscular substance is irritated directly.

Action on Muscles and Motor Nerves.—The muscles and motor nerves are not paralysed by chloral. The paralysis and loss of sensibility is of spinal origin.

Action on the Spinal Cord.—Chloral first increases and then diminishes the excitability of the spinal cord, and finally abolishes it altogether. It probably acts first upon the grey matter, as impressions which are usually painful are not felt at a time when tactile impressions still produce reflex.

Action on the Brain.—At first it may cause a little excitement of the brain, followed by sleep, and then by coma. These actions are probably due partly to the influence of the drug on the circulation, and partly to its direct action on the cerebral tissue itself. In the first stage of excitement the circulation in the brain is somewhat increased, but as sleep comes on the vessels contract and the brain becomes anæmic.

The **pupil** is almost invariably contracted; the temperature, as has already been mentioned, falls steadily and rapidly, and this fall appears to be due partly, though not entirely, to lessened

production of heat, for it still occurs, though to a less extent, when the animal is wrapped up in cotton-wool, or is put in a warm place.

THE TREATMENT OF CHLORAL POISONING.—In conjunction with Professor Stricker, I found that animals which had received a dose of chloral which would certainly kill them if they were left exposed, would recover from the effects of such a dose if they were wrapped up in cotton-wool. If the dose be still further increased, so as to kill the animal even when carefully so wrapped up, it may still be kept alive by being put in a warm place, so that its temperature is kept up artificially. If, however, the dose be still further increased, the animal will die, notwithstanding these precautions. The treatment of cases of poisoning in man is the same as in animals, viz. to keep up the temperature of the patient by putting him in a warm room, covering him with blankets, and applying hot bottles.

USES.—If equal parts of chloral and powdered camphor are rubbed together, they dissolve, and form a syrup. This is useful in neuralgia, when painted over or gently rubbed into the painful part.

The chief use of chloral is to produce sleep. It is useful as a hypnotic in the sleeplessness due to overwork or worry, and the wakefulness depending on constitutional peculiarity, old age, or disease, such as fever, delirium tremens, insanity, and puerperal mania. In the later stages of Bright's disease, where there is great sleeplessness accompanied by high blood-tension, chloral is very useful. The sleep which it causes is generally quiet and refreshing, and as a rule it is not followed next day by sickness, headache, and depression, like the sleep caused by opium. Usually, also, the sleep is not too deep to prevent the patient being readily awakened for the purpose of taking food.

Chloral may be used to lessen reflex excitability and diminish convulsions, as well as to produce sleep. For this purpose it is given in puerperal convulsions, in the convulsions of children, and in chorea and tetanus. In these two latter diseases it must be given in large doses. It alleviates the dyspnœa in spasmodic asthma, and the asthmatic attacks which occur in persons labouring under chronic bronchitis with emphysema. In cases of this sort, however, it is well to give it with care, for Ringer states that in them it often produces increased lividity and muttering delirium, lasting for several days.

The action of chloral as an anæsthetic or analgesic is much slighter than that of chloroform, but nevertheless it sometimes relieves pain, and for this purpose it has been used in gastralgia, intestinal and renal colic, neuralgia, and chronic rheumatism. It has been recommended by Dr. Playfair in doses of 15 grains, repeated, if necessary in twenty minutes, and before the os uteri has become completely dilated, to lessen pain in labour.

Chloral is an antidote to strychnine, physostigma, and picrotoxin.

Liebreich states that strychnia is an antidote to chloral; and while some observers have confirmed his statement, others have denied it, so that strychnine has certainly not the same power of antagonising the action of chloral as chloral has of antagonising strychnine.

Chloral is a useful remedy in sea-sickness, and in the incontinence of urine in children.

Bromal Hydrate. C_2H_3OH.—Not officinal.

PREPARATION.—It is prepared in the same way as chloral hydrate, bromine vapour being employed in place of chlorine.

CHARACTERS.—An oily colourless substance, with a strong smell and burning taste.

ACTION.—It irritates the eyes and produces running at the nose. It has a **narcotic** action like chloral, but causes more excitement and less profound sleep. It has a more powerful paralysing action on the **heart,** and is poisonous in smaller doses than chloral. It generally causes salivation, and **profuse secretion** from the bronchial mucous membrane accompanied by congestion. In toxic doses it produces cyanosis, dyspnœa, and death with convulsions which are probably due, in great measure at least, to clogging of the respiratory passages.

USE.—It is said to have been of use in epilepsy.

Butyl Chloral Hydrate. CROTON CHLORAL HYDRATE.—Not officinal.

PREPARATION.—By acting on aldehyde with chlorine.

CHARACTERS.—It forms white pearly crystalline scales, with a pungent smell and acrid disagreeable taste. It is sparingly soluble in water (1 in 100), but is readily soluble in glycerine (1 in 4).

DOSE.—To lessen pain, $1\frac{1}{2}$-5 gr. (0·1-0·3 Gm.); as hypnotic, 5-15 gr. (0·3-1·0 Gm.).

ACTION.—It acts much like chloral, though less powerfully, and has a less depressing effect on the heart, and is much less poisonous than chloral. It is said by Liebreich to affect the fifth **nerve** especially, and cause **anæsthesia** in the parts supplied by it before general anæsthesia is produced.

USES.—It has been used especially in facial neuralgia and migraine, and paroxysmal toothache. It has been used also as a hypnotic instead of chloral in cases of weak heart.

ADMINISTRATION.—The disagreeable taste is best covered by syrup of tolu, and it may be suspended in almond mixture or mucilage.

Bichloride of Methylene. CH_2Cl_2.—Not officinal.

PREPARATION.—By acting on chloroform with nascent hydrogen, $CHCl_3 + H_2 = CH_2Cl_2 + HCl$.

CHARACTERS.—A colourless volatile liquid, with a smell like chloroform. Sp. gr. 1·344. Boiling point, 40° C. (104° F.).

ACTION.—Like that of chloroform but more rapid, though a larger quantity is required. It is said to depress the action of the heart more than chloroform, but it has been found a very satisfactory anæsthetic in ovariotomy, and is more used than other anæthetics in this operation.

It is very doubtful whether the substance sold as bichloride of methylene is anything but a mixture of chloroform and alcohol, as the pure substance is expensive.

Chloroformum, B.P.; Chloroformum Venale, U.S.P. CHLOROFORM. $CHCl_3$; 119·2.

PREPARATION.—By distilling alcohol with chlorinated lime and slaked lime, washing the distillate with sulphuric acid, and redistilling from slaked lime and calcium chloride.

In this process the alcohol probably first becomes reduced to aldehyde. From the aldehyde, chloral is formed, and this is broken up by the caustic lime into formate of calcium and chloroform.

$$\underset{\text{Aldehyde.}}{C_2H_4O} + 3Cl_2 = \underset{\text{Chloral.}}{C_2HCl_3O} + 3HCl.$$

$$2C_2HCl_3O + Ca2HO = \underset{\text{Formate of Calcium.}}{Ca2CHO_2} + \underset{\text{Chloroform.}}{2CHCl_3}.$$

Or, disregarding the intermediate steps, the reaction may be represented thus:—

$$\underset{\text{Alcohol.}}{4C_2H_6O} + 8\underset{\text{Calcium hypochlorite.}}{CaCl_2O_2} = 2CHCl_3 + 3(Ca2CHO_2 + 5CaCl_2 + 8H_2O).$$

CHARACTERS AND TESTS.—A limpid colourless liquid, of an agreeable ethereal odour, and sweet taste. Dissolves in alcohol and ether in all proportions; and slightly in water, communicating to it a sweetish taste. Burns, though not readily, with a green and smoky flame. Specific gravity 1·49. It is not coloured by agitation with sulphuric acid, leaves no residue and no unpleasant odour after evaporation.

IMPURITIES.—Hydrochloric acid, chlorine, hydrocarbons, alcohol.

TESTS.—The same as those of purified chloroform.

DOSE.—3 to 10 min.

U.S.P. Chloroformum Purificatum. PURIFIED CHLOROFORM. $CHCl_3$; 119·2.

PREPARATION.—By mixing chloroform (200) with sulphuric acid (60) and allowing them to stand, with occasional shaking, for twenty-four hours; then separating the lighter liquid and adding to it carbonate of sodium (10) previously dissolved in water (20). The mixture is then agitated thoroughly for half an hour and set aside. The chloroform is then separated from the supernatant layer, mixed with alcohol (2), transferred to a dry retort, and lime (1) is added, and the liquid distilled, taking care that the temperature does not rise above 67°·2 C. (153° F.), into a well-cooled receiver, until the residue in the retort is reduced to 2 parts.

TESTS.—If 5 cc. of purified chloroform be thoroughly agitated with 10 cc. of distilled water, the latter when separated should not affect blue litmus-paper (absence of acids), nor test-solution of nitrate of silver (chloride), nor test-solution of iodide of potassium (free chlorine). If a portion be digested warm with a solution of potassa, the latter should not become dark-coloured (absence of aldehyde). On shaking 10 cc. of the chloroform with 5 cc. of sulphuric acid, in a glass stoppered bottle, and allowing them to remain in contact for twenty-four hours, no colour should be imparted to either liquid. If a few cc. be permitted to evaporate from blotting-paper, no foreign odour should be perceptible after the odour of chloroform ceases to be recognised.

PREPARATIONS.

B.P.

Linimentum Chloroformi	1 volume in 2.
Spiritus Chloroformi	1 volume in 20.
Tinctura Chloroformi Composita	1 volume in 10.

U.S.P.

Linimentum Chloriformi	40 per cent.
Mistura Chloroformi	8 per cent.
Spiritus Chloroformi	10 per cent.

Linimentum Chloroformi, B. and U.S.P. LINIMENT OF CHLOROFORM. Equal parts of chloroform and of camphor liniment, B.P. ; Commercial chloroform 40, soap liniment 60, U.S.P.

U.S.P. Mistura Chloroformi. CHLOROFORM MIXTURE. Purified chloroform 8, camphor 2, fresh yolk of egg 10, water 80.

DOSE.—1 to 2 tablespoonfuls.

Spiritus Chloroformi, B. and U.S.P. SPIRIT OF CHLOROFORM.

Chloroform 1 fl. oz., rectified spirit 19 fl. oz., B.P. ; Purified chloroform 10, alcohol 90, U.S.P.

DOSE.—20 to 60 min.

B.P. Tinctura Chloroformi Composita. COMPOUND TINCTURE OF CHLOROFORM.

Chloroform 2 fl. oz., rectified spirit 8 fl. oz., compound tincture of cardamoms 10 fl. oz.

DOSE.—20 to 60 min.

USES.—The liniment is used as a stimulant and local anæsthetic. Spirit of chloroform, chloroform mixture, and compound tincture are used as carminatives and sedatives.

ACTION OF CHLOROFORM.—When mixed with **albumen,** chloroform produces a precipitate, but renders the supernatant albumen more easily filtered than before. It is a powerful solvent of **protogon,** which forms the essential ingredient both of the nerve centres, of the nerves themselves, and of the red blood corpuscles, and some authors have considered that to this solvent property the action of chloroform as an anæsthetic was, in some measure at least, due. This, however, is at present hypothetical. It appears to lessen the oxidising power of the **blood,** although not to a very great extent, for the diminution of this power is hardly perceptible in the blood of animals poisoned by chloroform, although distinct in blood which has been mixed with it. When applied to the **skin,** it evaporates rapidly, and produces a feeling of cold. When its evaporation is prevented, it passes through the epidermis, and

acts as an irritant on the skin, producing rubefaction, and leaving behind a painful burning spot, or even vesication. It greatly assists the absorption of organic alkaloids by the skin, so that a number of them will pass through the epidermis and be absorbed with considerable ease when mixed with chloroform, although they would not pass through at all if applied as an alcoholic solution. In the **mouth** it has an exceedingly sweet taste, and stimulates the secretion of saliva. When swallowed in large quantities, it acts first as an irritant, producing gastro-enteritis, and afterwards, from its absorption, will cause anæsthesia and coma, so that the vomiting, pain at the epigastrium, and purging, which are first observed, gradually pass off, and are succeeded by stupor, coma, and abolition of reflex sensibility, which may either end in death, or may pass off, while the irritation of the intestines and stomach may continue for some time afterwards. In small doses it probably stimulates the secretion of gastric juice and the movements of the **stomach,** and both increases and co-ordinates more perfectly the movements of the stomach and **intestines,** so that it causes expulsion of flatulence and relieves griping.

After absorption into the blood, either from the stomach or from the lungs, it acts on the **nervous system** in somewhat the same way as alcohol, paralysing the nerve centres in much the same order. Its action, however, is more rapid than that of alcohol, and it does not appear to produce the stimulation without derangement of the mental faculties which marks the first stage of the action of alcohol. Chloroform appears to derange the mental faculties from the very first. The effect of chloroform may generally be divided into **three stages:** (1) of imperfect consciousness, (2) of excitement, and (3) of anæsthesia; or perhaps one might divide it more exactly into four stages (p. 174), and add a fourth stage, that of paralysis. Its **first effect** is to produce a feeling of warmth over the surface, with affection of the optic and auditory nerves, noises being heard in the ears, and a sensation of light experienced in the eyes. There is also a feeling of oppression at the chest, and sometimes a choking sensation, occasionally accompanied by cough. The choking and cough are more especially felt if the vapour is administered in too concentrated a form, and not unfrequently the patient will put up, his hand to try and take away the cloth containing the chloroform. External impressions are now slightly felt, sounds are faintly heard, questions are slowly and imperfectly answered, and any sensation of pain which may be present becomes greatly diminished or entirely disappears. In children and weak persons this stage may pass into that of complete anæsthesia, but in most cases it is succeeded by the stage of **excitement.** The patient is no longer conscious of what is going on around him, but he may, according to his temperament, sing, shout, or struggle violently. The violent struggles are more especially noticed in men of irritable tempera-

ment, who have been accustomed to the use of alcoholic stimulants. In them the excitement is greater, and more chloroform is required in order to produce the stage of complete anæsthesia. During the violent struggles, the efforts of the patient may induce him to hold his breath until suffocation seems impending; the face becomes livid, the eyes prominent, and the jugulars distended. The struggling is usually less in women than in men, and is less in patients exhausted by previous illness. In women, hysterical sobbing or crying may occur; occasionally indications of venereal excitement have been observed, and even a complete venereal orgasm. When the chloroform is pushed, this stage soon subsides, and the patient passes into the state of complete **anæsthesia.** The limbs become flaccid; when the hand is taken up it falls like that of a corpse; painful stimuli produce neither reflex action nor any indication of sensation. The last reflex actions to disappear are those from the conjunctiva, the anus, and the vagina. When touching the conjunctiva no longer causes reflex contraction of the eyelid, anæsthesia may be regarded as complete, and surgical operations may be commenced. During the administration of chloroform the **respiration** is generally first rendered somewhat slow, then quicker, and lastly steady, unless the anæsthetic be pushed too far, when it again becomes slower and weaker, and finally ceases altogether. The **pulse** is usually affected in a similar manner. The reason of this appears to be that the chloroform vapour, as it descends the respiratory passages, successively irritates those parts with which it comes immediately in contact, (1) the nasal mucous membrane, (2) the larynx, and (3) the lungs. It causes, through the nerves of the nose and larynx (p. 207), reflex slowing of the respiration and reflex slowing of the pulse. As these nerves gradually become paralysed by the action of the drug, its stimulating effect on the branches of the vagus distributed to the lung becomes manifest in accelerated respiration, usually accompanied by a quickened pulse. Next, as the drug continues to act, it paralyses those nerves also, and the respiratory centre being now no longer affected by any reflex irritation, continues to keep up the respiratory movements with a somewhat slow and steady rhythm. If the drug be now pushed still further, the respiratory centre itself becomes **paralysed,** the respirations become still slower and feebler, and finally cease altogether. These alterations in the respiratory rhythm during the administration of chloroform may sometimes be more or less interfered with by the effect upon the respiratory centre of blood which has become venous in consequence of the altered respiratory movements. The action of the **heart** is also modified by chloroform, the pulse usually becoming somewhat slower just at first; then accelerated during the whole period of excitement; and afterwards steady, at or below its normal rate. The **blood-pressure** is usually lowered, and if the chloroform vapour be strong the pressure may fall very

considerably, and may even be reduced to zero. The fall of blood-pressure is probably due in great measure to the dilatation of the vessels, but it may also be partly owing to enfeebled action of the heart, even at the beginning of the anæsthesia. When the chloroform has been pushed so far as greatly to lower the blood-pressure, the fall is caused, to a great extent, by the weakening of the heart. The dilatation of the vessels is not due to paralysis of the vaso-motor nerves, for these, when irritated directly, will still cause the artery to contract during chloroform narcosis. It appears to be due to paralysis of the vaso-motor centre. The reflex power of this centre is first diminished, and then abolished, by chloroform, so that irritation of a sensory nerve, during imperfect chloroform narcosis, causes only a slight rise of blood-pressure, and in perfect narcosis no rise at all.

The tension of the **intercellular fluid** and the lymph in the **eye** appear to be diminished, so that the **mammæ** become flaccid, the intra-ocular tension is diminished, and irregular astigmatism may occur.

The **nervous system** appears to be paralysed in the following order: first, the cerebral hemispheres; next, the grey matter of the cord; next, the white matter; next, the reflex power of the medulla oblongata; next, the automatic power of the respiratory centre, and lastly, the cardiac ganglia.

The order in which the nerve centres are paralysed may sometimes be changed, and the heart may be affected before the respiration.

DANGERS OF CHLOROFORM.—Cases may arise where it is impossible to obtain assistance, but whenever it is possible to obtain help, anæsthetics should never be given without the presence of a third person, both for the sake of the administrator and of the patient. In consequence of neglecting this rule a number of medical men have suffered severely from false charges of assault and rape brought against them by female patients. These charges, though perfectly false, have frequently been brought by patients in all good faith, and under the belief that they were true. The action of alcohol on the sexual centres in the brain (pp. 394 and 366) is surpassed by that of chloroform, and sexual excitement caused by the latter (p. 722) may be accompanied by delusions, which are afterwards remembered and believed by the patients to have been real events. By having an assistant in the room false charges arising from such delusions may be disproved.

For the patient's sake also no one should attempt, if it can possibly be avoided, both to administer anæsthetics and to operate, for this is more than a single man can do, and the attempt to do both is likely to lead to failure in either one or both.

The dangers resulting from the employment of chloroform are: (1) death by **stoppage of respiration**; (2) death by **stoppage of the heart.** Usually the respiration stops before the heart.

This order, however, may be somewhat varied, because occasionally the heart will fail before the respiration. This may sometimes be due to the employment of too **strong chloroform vapour,** because this very quickly paralyses the heart; but sometimes the stoppage of the heart before the respiration may be due to the **shock** of the operation, and not to the chloroform. The **respiration** may **stop** from (1) **obstruction** to the entrance of air into the glottis by the tongue, by vomited matters, or by blood, (2) by **mechanical interference** with the respiratory movements, (3) by **paralysis** of the respiratory centre.

PRECAUTIONS.—(1) If the patient should partially wake from chloroform narcosis during an operation, sickness is very likely to occur. In order to prevent this, it is well that the patient should take no solid food for four or five hours before the operation; but, at the same time, his strength should be kept from sinking by the administration of beef-tea, along with some alcoholic stimulant three hours before. When vomiting does occur, the head of the patient should be turned on one side, so as to allow an easy exit to the vomited matters, which should, if necessary, be removed from the mouth. Mr. Mills tells me that the most common causes of obstruction to the respiration are either falling back of the tongue or depression of the chin. Both of these may be remedied by changing the position of the head by turning it on one side, or forcibly drawing the chin away from the sternum at each inspiration. Very seldom it may be necessary to draw the tongue forwards with dressing forceps. (2) Mechanical interference with the respiratory movements may occur from unwary pressure upon the chest, interfering with the thoracic movements. The most common cause of this is the weight of the patient's own body, when any operation upon the back requires him to be laid upon his face. In such cases, special watch should be kept upon the respiratory movements. Mechanical interference with respiration may occur in old people who have lost their teeth. The flaccid lips and the alæ nasi are in them drawn inwards at each inspiration, and acting as valves prevent the entrance of air into the trachea. In such cases the mouth should be opened by the fingers (Esmarch).

Stoppage of the respiration may occur from the patient spasmodically holding his breath during the stage of excitement, but this usually soon passes off if the anæsthetic be pushed. The struggling is less if the anæsthetic be given gradually. (3) Paralysis of the respiratory centre takes place when the drug is pushed too far. It may sometimes occur suddenly, after a fresh quantity of chloroform has been poured upon the cloth used in administration. If the respiration ceases the administration of chloroform should be discontinued, and the patient roused by flicking the cheeks and breast with a wet towel. The tongue should be drawn forward with forceps and artificial respiration begun if necessary. As a rule the patient can be restored with comparative ease by means

of artificial respiration, provided the heart continues to beat, but on rare occasions even the prolonged use of this means does not induce any further voluntary respiratory movement. The easiest way of performing artificial respiration is to press the sternum forcibly inwards, and allow it to return to its normal position by its own elasticity. The pressure should be exercised synchronously with the operator's own respiration. Each time the sternum is depressed the ends of the fingers may be pressed under the cartilages of the ribs on the left side, so as to stimulate the heart mechanically also.

Stoppage of the heart may occur suddenly, and may take place while respiration is still going on. It is usually ascribed to the chloroform, and no doubt concentrated chloroform vapour inhaled into the lungs may arrest the heart. Very commonly, however, it is reflex, and when death occurs in such a case it is to be attributed to the want of chloroform rather than to its excess. It is worthy of note that in the greater number of the cases recorded as deaths from chloroform, the statement is made that the quantity administered was very small, and that anæsthesia was incomplete. Before anæsthetics were used at all, death from shock during operation was by no means uncommon, and no doubt it still occurs during imperfect anæsthesia, although complete anæsthesia tends to prevent it. The operations in which death during chloroform chiefly occurs are short and comparatively slight, though painful, such as extraction of teeth, and evulsion of the toe-nail—operations in which the introduction of deep chloroform anæsthesia might be regarded as superfluous, and involving a waste of time. These operations appear to be dangerous during imperfect narcosis, and not so when either no anæsthetic at all has been given, or complete anæsthesia has been produced. The reason of this probably is that when no anæsthetic is given, irritation of the sensory nerves during the operation causes two effects—slowing or stoppage of the heart, and reflex contraction of the vessels. This contraction neutralises the result of cardiac weakness or stoppage, maintains the blood-pressure, and thus prevents syncope. During imperfect anæsthesia the reflex contraction of the vessels is destroyed, whereas the effect on the heart may still persist, so that irritation of a sensory nerve may produce syncope by stopping the supply of arterial blood from the heart, while the blood still flows rapidly from the arterial system through the capillaries into the veins. When the anæsthesia is complete, both reflexes are paralysed, and the circulation remains unaffected by any impression made upon the sensory nerves. Even when chloroform anæsthesia appears perfectly complete, death from shock may still occur, at any rate in the case of animals. I have noticed this on two occasions when engaged in making gastric fistula in a dog. The animal was completely anæsthetised, but in both instances, when drawing upon the stomach in the process of inserting a cannula

the animal died suddenly. On mentioning this to Professor Schiff, he informed me that he had had many similar experiences, so that he had entirely abandoned the use of chloroform in such operations, and substituted ether.

When the heart stops, the treatment to be adopted is to lay the patient's head lower than his body (p. 223), to keep up artificial respiration, and to administer nitrite of amyl by inhalation.

Instead of the plan of artificial respiration already mentioned, Sylvester's may be used. Howard's plan may be used for very strong patients, but is not suitable for delicate ones. Respiration may be assisted by stimulating the diaphragm by the application of a faradaic current to the phrenic nerve. One pole is applied to the epigastrium and the other to the side of the neck during the time that the inspiratory movement is being made artificially.

USES.—The vapour of chloroform may be applied to the eye in photophobia, to the os uteri in pruritus pudendi, neuralgia, ulceration, or cancer of the uterus, in order to relieve pain. A few drops held in the hand of the nurse, and inhaled by a child when a paroxysm of whooping-cough comes on, will lessen its violence.

The power of chloroform to aid the absorption of vegetable alkaloids may be employed in order to assist their action when applied externally, but care must be taken not to apply them over too large a surface when using such drugs as aconite or veratrine in combination with chloroform or chloroform liniment. A pledget of cotton wool dipped in chloroform is frequently employed as a remedy in toothache; but as the chloroform irritates the pulp, and may increase pain afterwards, Ringer recommends a piece of linen moistened with chloroform to be folded over the tooth, so that the vapour may act upon the pulp without irritating it. It relieves vomiting from gastric catarrh or sea-sickness, lessens flatulent distension of the stomach and intestines, and may be used in dyspepsia and diarrhœa after the irritant has been removed.

Chloroform, in combination with small doses of morphia and with some adhesive vehicle such as glycerine, is a useful remedy in coughs, more especially the coughs of phthisis. When inhaled to an extent quite insufficient to produce even the earlier stages of anæsthesia it may relieve the paroxysms of asthma. The first stage of chloroform action, viz. partial anæsthesia and partial loss of consciousness, is useful in biliary and renal colic, and in very severe pain, such as intestinal colic, severe neuralgia, aneurism, and during labour. A most ingenious plan of administering chloroform in such cases has been devised by Mr. Image, of Bury St. Edmunds. A piece of blotting-paper or lint is put in the bottom of a tumbler, and moistened with chloroform. The patient then takes the tumbler in the hand and inhales the vapour. The shape of the tumbler prevents it from being brought too close to the face, so that the vapour is always inhaled with a free admixture of air. As soon as it begins to take effect, the

patient's hand and the tumbler drop, so that the inhalation ceases. When the effect begins to pass off, the patient again raises the tumbler and inhales anew, and so the process may go on for a long time, without any further care on the part of the attendant than to keep the lint or blotting paper in the tumbler moist with chloroform.

In the administration of chloroform for surgical operations, the towel or napkin may be folded so as to form an imperfect cone, into the concavity of which a little chloroform is poured. The towel is then held over the patient's face, a few inches from his nose, the apex of the cone touching the bridge of the nose, its base being directed downwards, and its margin a couple of inches from the face. Care should be taken that no part of the towel which is wet with chloroform touches the face, on account of the burning sensation which it produces, and that a free admixture of air be allowed and the vapour not administered in a too concentrated state.

Another way of giving it is to spread a single fold of the napkin over the patient's face, and allow the chloroform to fall, a drop at a time, upon the napkin a little in front of the nose. The drug may be administered in a similar way upon a wire mask covered with a single layer of flannel. In order to avoid the possibility of the patient inhaling too concentrated a vapour, an apparatus has been devised by Mr. Clover, consisting of a bag of 10,000 cubic inches capacity, which is filled with air containing 4 per cent. of chloroform vapour, and from this the patient is allowed to inhale by means of a flexible tube and a mask. The apparatus is filled by pumping successive quantities of air from a bellows holding 1,000 cubic inches through a box heated by hot water, into which $32\frac{1}{2}$ minims of chloroform have been injected, a quantity just sufficient to charge the air with the proper amount of chloroform.

A mixture of 1 part of alcohol with 2 of chloroform and 3 of ether, known under the name of the A, C, E mixture, is sometimes used instead of chloroform. It is supposed to have the advantage of being more stimulant and less depressing to the heart than chloroform. One disadvantage of it is that the three constituents evaporate with unequal rapidity, so that at the end of an operation a patient may get a much larger proportion of chloroform than of the other two.

U.S.P. Iodoformum. IODOFORM, CHI_3; 392.8—Iodoform should be kept in well-stopped bottles, in a cool place.

PREPARATION.—By mixing alcoholic solution of potash with tincture of iodine, and evaporating; or by acting on dilute alcohol with iodine and carbonate of potash or soda.

CHARACTERS.—Small, lemon-yellow, lustrous crystals of the hexagonal system, having a saffron-like and almost insuppressible

odour, and an unpleasant, slightly sweetish, iodine-like taste. Not perceptibly soluble in water, to which it imparts a slight odour and taste; soluble in 80 parts of alcohol at 15° C. (59° F.), in 12 parts of boiling alcohol, in 5·2 parts of ether, and in chloroform, benzol, benzine, disulphide of carbon, fixed or volatile oils. Its solutions have a neutral reaction. Sp. gr. 2·000. It sublimes slightly at ordinary temperatures, and distils slowly with water; at about 115° C. (239° F.) it melts to a brown liquid, and at a higher temperature yields vapours containing iodine and carbonaceous matter. If iodoform be digested with an alcoholic solution of potassa, the mixture, when acidulated with diluted nitric acid, will give a blue colour with gelatinized starch.

Distilled water shaken with iodoform should not change the colour of blue litmus paper, and when filtered, should give no precipitate with test-solution of nitrate of silver (abs. of iodide). Upon full combustion, iodoform should leave no residue.

DOSE.—1-3 grains.

PREPARATION.

Unguentum Iodoformi (1 part to 9 of benzoated lard).

ADMINISTRATION.—It may be given in the form of pill, made up with sugar of milk, tragacanth and glycerine, or as a suppository made up with cacao butter.

As an inhalation in phthisis a solution may be used containing 20 grains of iodoform, 20 minims of oil of eucalyptus, or 10 of creasote, ½ fl. oz. rectified spirit, and ½ fl. oz. of ether. This is used with an inhaler of horsehair matting lined with cotton wool on the interior of which the solution is dropped (Dreschfeld).

The disagreeable smell of iodoform may be covered by Tonquin bean or Coumarin.

As an external application it may simply be dusted over the sore and covered with cotton-wool, or cotton-wool may be soaked in an ethereal solution of it and then dried. The quantity of iodoform in the cotton-wool should be at least 10 per cent. It may be applied to the nose or throat as snuff, or mixed with half its weight of starch as insufflation, or an ethereal solution may be applied as spray. The nozzle of the spray producer is apt to become choked and must be washed out frequently with pure ether. It may also be applied to the nose in the form of a bougie containing ⅙—½ a grain made up with gelatine and glycerine.

ACTIONS.—Iodoform destroys bacilli, and is an **antiseptic** and **deodorizer** of very considerable power. It also destroys leucocytes. When applied in substance or strong solution it produces no local irritation, but acts as a **local anæsthetic.** Its power in this respect is so great that a suppository containing it when introduced into the rectum may so diminish sensibility that defecation may occur without the knowledge of the person or animal (Wood).

Its absorption from the intestine is probably aided by fat.

It weakens the circulation when taken for some time, and when applied to the frog's **heart** it has a powerful paralysing action on the cardiac ganglia in the same way as chloral and iodal (p. 281).

It has a marked action on the **nervous system.** In cats and dogs it produces narcosis, but not in rabbits. It may be absorbed from wounds and affect the nervous system in man, but this affection instead of sleep or anæsthesia, usually appears in slight cases as sleeplessness, headache, irritability and loss of memory. In severe cases it appears in the form of maniacal attacks, hallucinations, or melancholia.

These disagreeable effects appear to be diminished by bicarbonate of potash in doses of 10 grains hourly.[1] It appears to have an extraordinary power to prevent the development of giant-cells and may thus prevent morbid tissue growth.

USES.—Its **local anæsthetic** and **antiseptic** actions render it useful as a dressing after operations instead of carbolic acid, and it is especially useful where a regular antiseptic dressing cannot be applied, as in operations on the bladder or rectum, or wounds or ulcers of these parts. It is a most useful application to poisoned wounds, chancres, phagedenic or syphilitic sores, and to fungating growths generally. It induces healthy action in indolent sores. It lessens the discharge and disagreeable smell of ozæna. It has been used as a vapour in cases of phthisis, and also given internally but with doubtful result.

[1] Behring, *Wien. Med. Blätt.* 1884, No. 9.

CHAPTER XXX.

CARBON COMPOUNDS.

Aromatic Series.

In this series the carbon atoms are supposed to be linked so as to form a closed chain or chains. The lowest member of the series contains six atoms of carbon, which are so linked that the group has six free affinities, thus :



For convenience' sake, this carbon ring, or nucleus, is often graphically represented simply thus :

When five of the free affinities are saturated by hydrogen, the group forms an organic radical with one free affinity, termed **phenyl :**



When this free affinity is also saturated by hydrogen, the group



forms phenyl hydride, or benzine, or benzol, which must be carefully distinguished from the benzin already mentioned (p. 688).

Bodies belonging to the aromatic group differ from those of the fatty series in the fact that they do not readily link on other substances to themselves, and so form compounds by addition. They rather form them by substitution.

When one atom of hydrogen in benzine is replaced by hydroxyl (OH), phenyl-alcohol or carbolic acid is formed :

The name of **phenol** has been given to this body as it is more convenient than the names phenyl-alcohol or carbolic acid, and its termination, **" ol,"** indicates that it resembles alcoh**ol** in its constitution.

The relations of some of the other members of the aromatic group to each other may be more easily seen if they are put in a tabular form :

Benzine,

Phenol,

in which 1 atom of hydroxyl (OH) replaces 1 of H in benzine.

Nitrobenzine,

in which 1 atom of nitroxyl (NO_2) replaces 1 of H in benzine.

Amidobenzine, or Aniline,

in which 1 atom of amidogen (NH_2) replaces 1 of H in benzine.

Benzoic acid, or Phenylformic acid, 

in which 1 atom of carboxyl (COHO) replaces 1 of H in benzine.

As the carbon atoms in the benzine ring or nucleus are supposed to be arranged symmetrically, it does not matter which atom of hydrogen is replaced by another radical if the substitution takes place only in one atom, *e.g.* in phenol.

If we number the carbon atoms so as to distinguish them from one another, thus :



it is evident that phenol is always the same, whether the hydroxyl is attached to the carbon atom, 1, 2, or 3, &c., &c.:



But this is not the case when **substitution** occurs **at two or more points** in the benzine ring.

Thus when substitution in the benzine ring occurs at two points, these may take three different positions:

1 and 2  The substitution products 1 and 6 are the same as 1 and 2, and are usually termed **ortho** compounds. 

1 and 3  1 and 5 are the same as 1 and 3, and are usually termed **meta** compounds. 

1 and 4  1 and 4 are usually termed **para** compounds.

Thus three isomeric forms may occur.

When two atoms of hydrogen are replaced by two of hydroxyl, instead of by one, as in phenol, we have three isomeric substances, differing from one another only in the relative position of the substituted atoms. These three bodies are pyrocatechin, in which the position is 1 and 2, resorcin, 1 and 3, and hydroquinone, 1 and 4. The relative position of the hydroxyl groups in these three bodies is indicated in their formulæ by the figures (1 : 2), (1 : 3), and (1 : 4), or by the terms **ortho, meta,** or **para** respectively.



Pyrocatechin. $C_6H_4.(OH)_2(1:2)$ Resorcin. $C_6H_4.(OH)_2(1:3)$ Hydroquinone. $C_6H_4.(OH)_2(1:4)$

When two atoms of hydrogen in benzine are replaced, the one by hydroxyl (OH) and the other by carboxyl (CO.OH), we get three isomers, salicylic acid, oxybenzoic acid, and paraoxybenzoic acid.



Salicylic Acid.



Oxybenzoic Acid.



Para-oxybenzoic Acid.

Pyridine (C_5H_5N) is probably formed by one atom of tetrad C in the benzine ring being replaced by triad N:



Naphthaline ($C_{10}H_8$) is formed by the union of two benzine groups, thus:



Chinoline (C_9H_7N) is formed by the union of benzine and pyridine groups:



Chinoline is closely connected with quinine, from which it may be produced, and it is probable that many of the **organic alkaloids** are closely related to the aromatic series.

That morphine, for example, is related to phenol is shown by the fact that when morphine is treated with nitric acid and heated with water under pressure, it yields trinitrophenol, or picric acid.[1]

GENERAL ACTION.—The distinctive action of the lower members of the fatty series is their stimulant and anæsthetic action on the nerve centres (p. 686). The most marked action of the lower members of the aromatic series is their **antiseptic** and **antipyretic** power. The antiseptic action appears to be very easily modified by slight changes in some substances of this group. Thus salicylic acid is antiseptic, but its sodium salt is not; and meta- and para-oxybenzoic acids, which are isomeric with salicylic acid have no antiseptic power.

As alterations in the physiological action of the carbon compounds of this group can be effected by slightly changing their chemical composition, several attempts have been recently made to obtain artificial alkaloids which should possess a strong antipyretic action without depressing the heart or causing sickness. Antipyrin, the most recent introduction, appears to be the best as yet, but further attempts in this direction may be still more successful.

U.S.P. Acidum Carbolicum Crudum. CRUDE CARBOLIC ACID.

CHARACTERS.—A nearly colourless or reddish-brown liquid of a strongly empyreumatic and disagreeable odour, having a benumbing, blanching, and caustic effect on the skin or mucous membrane, and a neutral reaction. Bromine water produces in an aqueous solution of carbolic or cresylic acid a white flocculent precipitate.

TESTS.—Crude carbolic acid should not dissolve in less than 15 parts of water at 15°C. (59°F.), nor should the solution have an alkaline reaction (absence of alkalis). If 50 volumes of crude carbolic acid be diluted with warm water to measure 1,000 volumes, the mixture well shaken, cooled, and allowed to separate, the amount of undissolved impurities should not exceed 5 volumes or 10 per cent. by volume of the crude acid.

Acidum Carbolicum. B. and U.S.P. CARBOLIC ACID. PHENOL. PHENYL-ALCOHOL. C_6H_5HO; 94.

An acid obtained from coal-tar oil by fractional distillation and subsequent purification.

CHARACTERS AND TESTS.—In colourless acicular crystals, which at a temperature of 95° become an oily liquid, having a strong odour and taste, resembling those of creasote, which it also resembles in many of its characters and properties. Its specific gravity is 1·065; boiling point, 370°. The crystals readily absorb

[1] Chastaing, *Compt. Rend.* xciv. 44.

moisture on exposure to the air, and they are thus liquefied; the acid, however, is but slightly soluble in water, but it is freely soluble in alcohol, ether, and glycerine. It does not redden blue litmus paper. A slip of deal dipped into it, and afterwards into hydrochloric acid, and then allowed to dry in the air, acquires a greenish-blue colour. It coagulates albumen. It does not affect the plane of polarisation of a ray of polarised light.

DOSE.—1 to 3 grains.

PREPARATIONS.

B.P.

Glycerinum Acidi Carbolici. Glycerine of Carbolic acid (Carbolic acid (1) Glycerine (4) by measure)..... 1 part in 6 by weight.

Suppositoria Acidi Carbolici cum Sapone. Carbolic Acid Suppositories. Carbolic acid, 1 gr.; curd soap, 15 gr.; starch, q.s. to give consistence.

U.S.P.

Unguentum Acidi Carbolici (with ointment 1 in 10)

ACTION.—Carbolic acid is a powerful **deodorizer** and **disinfectant** (p. 86). It precipitates **albumen,** and destroys low organisms. It prevents the decomposition of albuminous fluids by **bacteria,** and the fermentation of sugar by **yeast.** Quantities smaller than those which are sufficient to kill these organisms suffice to prevent their development. It does not appear to destroy the action of all **organic ferments** so readily, although it does so when applied for a long time, or in concentrated solution; it prevents the conversion of starch into sugar, the conversion of albumen into peptones, and the decomposition of amygdalin with formation of hydrocyanic acid. When applied to the **skin** it produces a white stain, and greatly diminishes the sensibility of the part. The stain afterwards becomes brownish, and of a parchment-like consistence, and the epidermis by and by peels off. Carbolic acid does not act as a vesicant, but appears to cause anæsthesia of the part to which it is applied, extending to some distance below the surface. If applied over a large surface of skin it may be absorbed to such a degree as to cause poisoning, and even death. The symptoms are weakness, delirium, and collapse. When applied to **mucous membranes** it has a similar action. In the mouth it causes a burning pain, and when swallowed produces symptoms of gastro-enteritis, pain in the stomach, and sometimes vomiting and purging. Along with this there is great collapse, delirium, and death, sometimes, though not always, preceded by convulsions. After death the **blood** is found to be very dark, and its **coagulability** greatly diminished. Carbolic acid appears to be a powerful poison to all the tissues, paralysing both **muscle** and **nerve** when applied directly to them without previously stimulating them. After absorption it acts especially on the **medulla oblongata,** but acts also on the

spinal cord, first stimulating and then paralysing these centres. From its action on the cord it produces in frogs **convulsions** resembling those of strychnine, these being followed by paralysis. It first stimulates the **respiratory** and **vaso-motor centres,** and afterwards paralyses them. It thus produces at first quickened respiration with rise of **blood pressure,** and it also quickens the **pulse.** As the centres become paralysed the blood pressure falls greatly, the respiration becomes slower, and the pulse also becomes slower. When it is injected directly into the blood, so that it can act in large quantity on the nerve centres, it paralyses the vaso-motor centre at once, and causes the blood-pressure to fall very greatly without much alteration being observed in the action of the heart itself. That the vaso-motor centre is completely paralysed by carbolic acid is shown by the fact that after its injection the blood-pressure is not raised either by stimulation of sensory nerves, or by asphyxia. Although carbolic acid acts first and most markedly on the nerve centres in the medulla oblongata it affects the **cerebral centres** also. This effect is evidenced in man by headache, giddiness, and lassitude, followed by unconsciousness. In animals it also affects the cerebrum, as shown by alterations in sensibility and motor power. It stimulates the **sweat** centre and **salivary** centres, producing perspiration and salivation. Medium doses appear to cause death by paralysis of the respiration, so that artificial respiration may be of some use in preventing it, but large doses paralyse the heart also, so that death occurs in spite of artificial respiration. It diminishes the **temperature** in cases of poisoning, and also when given to animals in a febrile condition, though when the fever is very high it does not seem to have much effect. It is **excreted** by the kidneys, and can be readily detected in the urine by bromine water. It sometimes gives rise to a very dark coloration of the urine, due to some oxidation product of the carbolic acid, probably hydroquinone (p. 732).

Part of the carbolic acid appears in the urine, in combination with sulphuric acid, as sulpho-carbolates, and if the quantity administered has been large the ordinary sulphates may completely disappear. The hydroquinone occurs also to a great extent in the urine in combination with sulphuric acid. The compound is colourless, and thus the urine, when freshly passed, has a normal appearance ; on standing the hydroquinone becomes free, undergoes further oxidation, and causes the urine to assume a brown colour.

USES.—It has sometimes been applied externally to produce local anæsthesia for slight operations, such as opening abscesses, and, when mixed with oil, in the proportion of ten minims to an ounce of oil, it relieves the pain of burns. One of the best means for removing the pain of toothache is to dip a little cotton wool into carbolic acid melted by the aid of heat, and insert the pledget into the cavity of the tooth, covering it over with dry cotton wool,

to prevent the tongue being burned by contact with the acid. It is used as a stimulant to indolent ulcers and wounds, and to destroy condylomata, and has been applied to the throat in cases of diphtheria, ulceration, and aphthæ. It has been employed as an injection into deep-seated inflammations such as chronic synovitis, inflamed glands, boils, hydrocele, erysipelas, and poisoned wounds. Its chief application, however, is to destroy the minute organisms which cause putrefaction in albuminous fluids, and to prevent the untoward results which would arise from the absorption of putrid discharges.

According to Sir Joseph Lister, the untoward consequences of operations are frequently due, not to the operation itself, but to the poisoning of the wound by the products of decomposing discharges, and poisoning of the system generally by absorption of these products. The decomposition is due to low organisms, such as bacteria, introduced from without, and it may be prevented by the use of such substances as will prevent their development or destroy them when present. In performing operations, therefore, he advises that the skin should first be washed with a watery solution of carbolic acid (1 in 40), that the knife also should be treated with a similar solution, and that the incision should be made under a spray of carbolic acid (1 in 20). After the operation is concluded under a constant use of the spray, the wound is covered with a protective consisting of varnished linen dipped in a solution of carbolic acid, one in forty, above which are laid eight layers of gauze, steeped in a mixture of carbolic acid (1), resin (4), and paraffin (4). Between the sixth and seventh layers is put a piece of waterproof tissue, in order to distribute the discharge and prevent it from oozing out at one spot. If the discharge be great the dressings ought to be changed once in twenty-four hours, under the spray, but as it heals, the intervals between the dressings may be lengthened.

A solution of carbolic acid in oil is frequently used to lubricate, and at the same time disinfect, catheters (p. 85), but, as Koch's experiments show, such a solution has no antiseptic power, and they ought to be disinfected, first with an aqueous solution and afterwards oiled.

Carbolic acid is very useful in what is sometimes known as an influenza cold, beginning with coryza, spreading down the throat to the air-passages, leading to severe bronchitis with much depression, and occasionally also to gastro-intestinal catarrh. This form of cold appears, like true influenza, to be extremely infectious, and to be easily communicated, not only by one member of a family to another, but even by casual visitors. It may sometimes be arrested, and may frequently be rendered less severe, by carbolic acid spray applied to the nostrils and by the use of a gargle containing carbolic acid. Other forms of sore throat are also relieved by gargles containing about 1 per cent. of carbolic acid.

Considerable care must be taken in using the gargle not to swallow it on account of the poisonous properties of the acid. When the cold begins in the nose the solution of carbolic acid for spray may contain 1 per cent., but perhaps a still better method of applying it is by a small ear syringe, as a $\frac{1}{4}$ or $\frac{1}{2}$ per cent. solution. A mixture of 1 part of carbolic acid with 3 of creasote has been used for continuous inhalation in phthisis by means of the oro-nasal respirator.

Carbolic acid is also used as an injection to wash out serous cavities, after the evacuation of fluids; for example, the cavity of the pleura after the evacuation of the fluid in pleurisy, and the cavity of an abscess after the removal of the pus. Internally, the acid has been given in cases of flatulent dyspepsia. It is a useful application to the uterus in chronic inflammation, excoriation, catarrh, and cancer, and as an injection in leucorrhœa.

Creasotum. B. and U.S.P. CREASOTE.

A product of the distillation of wood tar.

CHARACTERS AND TESTS.—A liquid, colourless or with a yellowish tinge, and a strong empyreumatic odour. It is sparingly dissolved by water, but freely by alcohol, ether, and glacial acetic acid. Specific gravity 1·071. It coagulates albumen. A slip of deal dipped into it, and afterwards into hydrochloric acid, acquires on exposure for a short time to the air a greenish-blue colour. Dropped on white filtering paper and exposed to a heat of 212°, it leaves no translucent stain. It turns the plane of polarisation of a ray of polarised light to the right. It is not solidified by the cold produced by a mixture of hydrochloric acid and sulphate of soda.

DOSE.—1 to 3 drops.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Mistura Creasoti (1 min. in 1 fl. oz.)	1-2 fl. oz.	Aqua Creasoti	1-4 fl. dr.
Unguentum Creasoti (simple ointment) 1 part in 9			
Vapor Creasoti			

U.S.P. Aqua Creasoti. CREASOTE WATER. Creasote, 1; distilled water, 99; agitate and filter.

B.P. Mistura Creasoti. CREASOTE MIXTURE.

Take of creasote, 16 min., glacial acetic acid, 16 min., spirit of juniper, 1 oz., syrup, 1 oz., distilled water, 15 ozs.

B.P. Vapor Creasoti. INHALATION OF CREASOTE.

Mix creasote (12 min.) and water (8 fl. ozs.) in an apparatus so arranged that air may be made to pass through the solution, and may afterwards be inhaled.

ACTION.—Creasote destroys low vegetable organisms, and prevents the fermentation which they cause. When administered to small animals, it causes great dyspnœa, weakening of the heart's action, paralysis, and often sudden death. Its action **differs from** that of **carbolic acid** in the **absence of convulsions** and **increased coagulability** of the blood.

Creasote is a powerful **muscular** poison. It coagulates albumen and **blood.** When applied to the **skin** it destroys the epithelium, and has a similar action upon mucous membranes. In the **mouth** it produces a burning sensation and much salivation. Large doses taken internally cause nausea, vomiting, colicky pains, and diarrhœa. The **pulse** is quickened, there is giddiness and headache, the **respiration** is slow and laboured, and the secretion of **urine** is increased.

USES.—It is often employed as a remedy in toothache, a small pledget of cotton wool being dipped into it and placed in the cavity of the decayed tooth. Care should be taken to cover this with fresh cotton wool, to prevent the tongue from being burned. Internally, it is given in cases of vomiting depending upon abnormal processes of fermentation in the stomach, and it is said to relieve vomiting due to other causes, such as ulceration of the stomach, cancer, Bright's disease, sea-sickness, and pregnancy. It is useful in diarrhœa, especially that of children, where the diarrhœa depends upon irritation due to abnormal fermentation processes in the intestinal contents. The vapour is used in phthisis and fœtid bronchitis.

Resorcin.—Not officinal. $C_6H_4(OH)_2(1:3)$ (*vide* p. 732).

CHARACTERS.—White, crystalline, plates somewhat like benzoic acid, melting at 99° C. It has a sweetish harsh taste. It is soluble in less than 2 parts of water and 20 of olive oil. The aqueous solution gives a dark violet colour with ferric salts.

DOSE.—5—30 grs. (0·3-2 Gm.). It is best given with syrup of oranges and freely diluted.

ACTION.—It is a powerful **antiseptic.** It coagulates albumen. A saturated solution has a caustic action on the skin, but a weak solution, *e.g.* 5 per cent., is not irritating to the skin or mucous membranes. In **frogs** it produces stupor, collapse, clonic spasms, and dyspnœa like carbolic acid. In **warm-blooded animals** it also causes clonic convulsions, dyspnœa, dilatation of the vessels and increased secretion of saliva and tears. Death occurs through paralysis. Large doses in **man**, 30 grs. or more, cause giddiness, singing in the ears, symptoms of intoxication, like those of alcohol, convulsive tremors and collapse. In febrile conditions it greatly lowers the temperature.

USES.—It is a powerful antiseptic and has been employed locally in diphtheria. As an **antipyretic** it has proved useful. A 5 per cent. solution has been used as an application to syphilitic sores and skin diseases, and as an injection into the bladder in cystitis. A 1 per cent. solution has been used as a collyrium. In infantile cholera it has proved very useful in doses of $1\frac{1}{2}$-5 grs. (0·1-0·3 Gm.) given in infusion of chamomile. As an antipyretic it lessens the temperature in phthisis and in typhoid, less so in pneumonia and erysipelas. It has also been used in ague.

Its disadvantages are the profuse perspiration which it produces, the short duration of its antipyretic action, and the rapidity with which the temperature again rises.

Hydroquinone, $C_6H_4(OH)_2(1:4)$, not officinal (p. 732).

CHARACTERS.—In crystals or plates with a slight sweetish taste.

ACTION.—Like that of resorcin, but about four times stronger.

USES.—Similar to those of resorcin.

Pyrocatechin, $C_6H_4(OH)_2(1:2)$. Not officinal (p. 732).

CHARACTERS.—It forms crystals or plates readily soluble in water, alcohol and ether. It reduces cupric sulphate

ACTION.—Like that of resorcin, but it is about three times stronger.

USES.—Like those of resorcin.

U.S.P. Acidum Salicylicum. SALICYLIC ACID, $HC_7H_5O_3$; 138 (p. 733).

CHARACTERS.—Fine, white, light, prismatic, needle-shaped crystals, permanent in the air, free from odour of carbolic acid, but sometimes having a slight, aromatic odour, of a sweetish and slightly acrid taste and an acid reaction. Soluble in 450 parts of water, and in 2·5 parts of alcohol at 15° C. (59° F.); in 14 parts of boiling water; very soluble in boiling alcohol; also soluble in 2 parts of ether, in 2 parts of absolute alcohol, in 3·5 parts of amylic alcohol, and in 80 parts of chloroform. When heated to about 175° C. (347° F.) the crystals melt, and at about 200° C. (392° F.) they begin to sublime; at a higher temperature they are volatilized and decomposed with odour of carbolic acid. The aqueous solution is coloured intensely violet-red by test-solution of ferric chloride.

IMPURITIES.—Hydrochloric acid, organic matter, iron and carbolic acid.

TESTS.—A solution of 1 part of salicylic acid in 10 parts of alcohol, mixed with a few drops of nitric acid, should not become turbid upon the addition of a few drops of test-solution of nitrate of silver (abs. of hydrochloric acid). A saturated solution in absolute alcohol, when allowed to evaporate spontaneously in an atmosphere free from dust, should leave a perfectly white crystalline residue, without a trace of colour at the points of the crystals (abs. of organic impurities; also of iron). On agitating a portion of salicylic acid with 15 parts of concentrated sulphuric acid, no colour should be imparted to the latter within fifteen minutes (abs. of foreign organic matter). If 5 c.c. of a saturated aqueous solution of salicylic acid be poured into a test-tube, into which had been introduced, shortly before, a crystal of chlorate of potassium and 2 c.c. of hydrochloric acid, and some water of ammonia be now carefully poured on top, the latter, should not assume a reddish or brownish tint (abs. of carbolic acid).

DOSE.—5 grs.—15 grs.

ACTION.—When mixed in a proportion of 1 to 10 per cent with fluids containing the germs of **bacteria** it will prevent their development, and in the proportion of 1 in 60 will destroy bacteria when swarming in a fluid (p. 73). Salicylic acid likewise destroys the life of the torula, and prevents alcoholic fermentation, as well as the fermentation caused by the organic ferments, &c., (p. 63).

It has little power to reduce the **temperature** in health, but is a most powerful agent in lowering the temperature of fever. When injected into the blood, or administered by the stomach in large quantities, it lowers the pulse rate, blood pressure, and respiration. When taken in medicinal doses for some time, it produces noises in the **ears,** deafness, giddiness, and headache, in this respect resembling quinine. Occasionally it has caused sudden depression of the circulation and collapse.

In large doses salicylic acid causes feeble **circulation,** lowers the blood-pressure, and produces death through paralysis of the **respiration.** It is excreted in the perspiration, saliva, and urine. During its **excretion** it frequently irritates the kidneys and produces albuminuria. It appears in the urine partly as salts of salicylic acid, and partly in combination with glycol as salicyluric acid. After its use the urine is not unfrequently brown by reflected and green by transmitted light, and contains a substance which reduces copper solution.

USES.—Externally it has been employed as an antiseptic instead of carbolic acid, and has been used by insufflation in diphtheria successfully. A mixture of 2 parts with 100 of tallow applied directly to the feet, not to the stockings, has been found most useful in preventing sweating and soreness of the feet in soldiers after a long march. It has been recommended for soft sores, which should be kept covered with the pure acid for two days, and then treated with emollient ointment. It is usually employed internally in the form of salicylate of soda (p. 559). As already mentioned it is useful both in acute and chronic rheumatism, and it has been found also useful in gonorrhœal rheumatism. It is of much less use in typhoid fever than in rheumatism, and although it has some antiperiodic action, is not such a powerful remedy in malarious affections as quinine.

Salicylic acid dissolved in collodion flexile (gr. xxx. to ʒj.) is very useful for corns and warts; also to hasten the peeling of palms and soles after scarlet fever.

Salicylate of soda is useful in phegmasia alba. As already mentioned, it relieves headache. It seems to have a peculiar power of increasing the secretion of bile and rendering it more watery. In this it differs from most other cholagogues, which increase the proportion of solids in the bile. It is therefore indicated in cases where there is a tendency to the formation of gall-stones.

Naphthalin. $C_{10}H_8$ (*vide* p. 733). Not officinal.

SOURCE.—It is prepared from tar.

CHARACTERS. Colourless micaceous crystals with a peculiar smell, insoluble in water, dilute acids or alkalis. Sparingly soluble in cold alcohol, more readily in hot alcohol.

As the commercial naphthalin is often impure it should be purified by washing it with alcohol on a filter until the alcohol is colourless, then drying and subliming.

DOSE.—For adults $1\frac{1}{2}$—8 grains as a single dose. As much as 80 grains may be given during the day. For children $1\frac{1}{2}$—3 grains every three hours.

ADMINISTRATION.—In the form of powder mixed with sugar and scented with oil of bergamot it may be taken in wafers or capsules. It may be used as enema, but as it is quite insoluble in water it must be suspended in a mucilagenous vehicle such as decoction of marsh mallow. The best way of doing this it to mix the quantity of naphthalin required (15—75 grains) with 2 or 3 fluid ounces of boiling distilled water, and stirring until the naphthalin is diffused in very fine drops throughout the liquid. It should then be poured into 15 or 30 fluid ounces of boiling marsh mallow tea and vigorously stirred. The liquid is then allowed to cool and introduced into the rectum by a soft tube and funnel (p. 426).

ACTION.—It destroys low organisms and prevents the germination of their spores. It is a powerful **antiseptic** but it must be intimately mixed with the substances on which it is to have this action. It has little or no poisonous action on the higher animals when given either by inhalation or internally, the reason probably being that it is so sparingly soluble that it is not absorbed in sufficient quantity from the intestinal canal to be injurious to the organism. When given internally it disinfects the whole contents of the intestinal canal so that the fæces have either no smell at all or a faint smell of naphthalin. It is so sparingly soluble that most of it remains in the intestine and acts on the contents of the intestinal tube along its whole length from the stomach to the rectum.

USES.—It may be used wherever it is desirable to destroy germs and stop processes of putrefaction or fermentation in the intestine. It has proved useful in typhoid fever, diarrhœa, acute and chronic, vomiting and diarrhœa in children, and tubercular diarrhœa.[1] It is possible that it may be useful in cholera.

Naphthol. $C_{10}H_7OH$. There are several kinds of naphthol. The only one hitherto used is the beta- or iso-naphthol. Not officinal.

CHARACTERS.—In white crystals with a somewhat agreeable smell. Sparingly soluble even in hot water. Soluble in alcohol, ether and chloroform, in olive oil and vaseline.

[1] Rossbach, *Berlin. klin. Wochenschr.* 1884, No. 42.

ACTION.—It has a therapeutic action on the skin like tar. When absorbed it causes vomiting, loss of consciousness, convulsions, and hæmaturia.

USES.—It is used in scabies, eczema, and local sweating. It may be applied in $\frac{1}{2}$ to 5 per cent. alcoholic solution, or as an ointment (10 per cent.).

Hydrochlorate of Rosaniline. Synonyms: FUCHSIN, MAGENTA, ROSÉINE, ANILINE RED. $C_{20}H_{19}N_3.HCl$. Not officinal.

PREPARATION.—Rosaniline is a colourless substance prepared by acting on aniline with oxidising agents such as arsenic acid. The compounds of rosaniline with monobasic acids have brilliant colours.

CHARACTERS.—Elongated crystals with a brilliant green lustre, readily soluble in water, and giving a bright red solution.

DOSE.—$\frac{1}{2}$-4 gr.

ACTIONS.—Rosaniline hydrochlorate when perfectly pure is said to have no marked physiological action. Fabrics dyed with it have acted as local irritants, producing eczema; but it is probable that this effect may be due, at least in great part, to the presence of arsenic. When given internally it has produced salivation, vomiting, diarrhœa, and when injected into the veins it has caused trembling, staggering, albuminuria, and fatty degeneration of the kidneys. These symptoms may possibly be due to the presence of aniline or of arsenic as impurities. It is excreted by the kidneys, saliva, and bile, and probably also by the intestinal mucous membrane. It gives a magenta colour to the urine.

USE.—To lessen or remove albumen from the urine in albuminuria.

Chinoline. C_6H_7N (p. 733). Not officinal.

CHARACTERS.—A colourless liquid with an aromatic odour. It forms crystalline salts.

DOSE.—Of the tartrate 7—15 grs. (0·5-1 Gm.).

ACTION.—It is a powerful **antiseptic** and **antipyretic.** In moderate doses it lowers temperature and pulse rate. In large doses it produces languor, diminished reflex excitability, dyspnœa, paralysis and collapse.

USES.—It has been used in typhoid fever, rheumatism, and erysipelas, apparently with benefit. It is little used in pneumonia; and in phthisis it is apt to irritate the stomach and produce collapse.

Kairin. Hydrochlorate of oxyethyl-chinoline hydride. Not officinal.

DOSE.—3—30 grs. Best given in wafer-paper or a capsule.

ACTION.—It is a powerful **antipyretic.**

USES.—Used in febrile conditions to lower the temperature. Filehne recommends that doses of 8 grains should be given every hour at first for four times or until the temperature has fallen to

100° F. If the temperature falls after four doses, 4 grains should be given hourly until the temperature again begins to rise, when the dose should be increased. If the temperature has not fallen to 100° after four doses of 8 grains, 12 or 16 grains should be given hourly, until the temperature of 100° is reached, when the dose should be lowered as before. Like resorcin it produces profuse sweating.

Antipyrin. Not officinal. A synthetically prepared alkaloid. There are two substances bearing this name, viz. methyloxychinicine and dimethyloxychinicine. The latter is the commercial drug.

CHARACTERS.—A white powder, very readily soluble in water; taste sweetish bitter and rather pleasant. Its solutions give with ferric chloride a deep red, and with nitrous acid a greenish blue. Chinicine or quinicine is a hypothetical base. The supposed constitution of chinicine and methyloxychinicine may be thus graphically represented:—



Chinicine or Quinicine.



Methyloxychinicine.

DOSE.—Thirty grains hourly for three hours. For children a grain and a half for every year of the child's age may be given hourly for three hours. If it causes vomiting it may be dissolved in half its weight of hot water and injected subcutaneously.

ACTION.—It reduces the temperature for several (1-20) hours when given as above in two or three doses, and when its effect has passed off, the rise of temperature which then occurs is less frequently accompanied by rigor than is the case with Kairin. It causes profuse **perspiration.** It slightly increases the **blood pressure.** It has no action on the **respiration.** It is **excreted** in the urine. It sometimes though rarely causes vomiting, and very seldom causes collapse.

USES.—In febrile diseases generally. It seems specially useful in typhoid fever and phthisis, but is also useful in erysipelas, surgical fever, pleurisy and pneumonia.

SECTION V.

VEGETABLE MATERIA MEDICA.

CHAPTER XXXI.

THALAMIFLORÆ.

Class I.—EXOGENÆ.—Exogens.

Sub-Class I.—THALAMIFLORÆ.

RANUNCULACEÆ.

B.P. Aconiti Folia. Aconite Leaves.—The fresh leaves and flowering tops of *Aconitum napellus*, gathered when about one-third of the flowers are expanded, from plants cultivated in Britain.

Characters.—Leaves have deeply-cut wedge-shaped segments, by which even a fragment of the leaf can be recognised; exciting slowly, when chewed, a sensation of tingling. Flowers are deep blue, helmet-shaped.

Officinal Preparation.

B.P.	DOSE.
Extractum Aconiti (green extract)	1-2 gr.

B.P. Aconiti Radix. Aconite Root.—The dried root of *Aconitum napellus*, collected in winter or early spring before the leaves have appeared.

U.S.P. Aconitum.—The tuberous root of *Aconitum napellus*.

Characters.—Conical and tapering, usually from one to three inches long, not thicker than the finger at the crown, blackish-brown, internally whitish. A minute portion, cautiously chewed, causes prolonged tingling and numbness.

Fig. 138. Aconite.

Properties and Composition.—The chief active principle in both leaves and roots is an alkaloid aconitine or aconitia, which is combined with aconitic acid. It is only present in small quantity in the leaves. In the root resinous and fatty matters and several other active principles are also present. Nepaul aconite, or Bikh, the root of *A. ferox*, contains an alkaloid pseudaconitine, which is much more active than aconitine. Japanese aconite is said to contain an alkaloid which is much more powerful even than pseudaconitine. It is therefore very

important that officinal preparations should be made only from the root of *A. napellus.*

OFFICINAL PREPARATIONS.

B.P.	DOSE.
Tinctura Aconiti	1–5 min.
Linimentum Aconiti	

U.S.P.	DOSE.
Abstractum Aconiti	½–1 gr. (·03–·36 Gm.).
Extractum Aconiti	⅛-⅓ gr. (·01 ·02 Gm.).
Extractum Aconiti fluidum	½-2 min. (·03-12 c.c.)

U.S.P. Abstractum Aconiti.—Exhaust powdered aconite, 200 parts, with alcohol containing 2 parts of tartaric acid. Retain the first 170 parts of the percolate, evaporate the remainder to 30, at a temperature not exceeding 50° C. (122° F.), and mix with the reserve portion. Place the mixture in an evaporating dish, and having added 50 parts of sugar of milk cover it with a piece of thin muslin gauze and set aside in a warm place, where the temperature will not rise above 50° C. (122° F.), until the mixture is dry. Lastly, having added enough sugar of milk to make the mixture weigh 100 parts, reduce it to a fine uniform powder.

B.P. Aconitia.—A white, usually amorphous, solid alkaloid. When rubbed on the skin it causes a tingling sensation, followed by prolonged numbness. It is a very active poison.

PREPARATION.—The aconitate of aconitia is dissolved out of the pounded root by macerating in spirit. If ammonia were now added, the aconitia would be set free, but being soluble in spirit would not be precipitated. The spirit is therefore recovered by distillation, and the residual extract dissolved in water, in which the aconitate of aconitia is soluble, although the alkaloid is very sparingly so. By adding ammonia, aconitia is precipitated mixed with colouring matter and other principles. It is then dissolved in ether, which leaves the colouring matter behind. The ether is recovered by distillation, and the aconitia farther purified by dissolving in water acidulated with sulphuric acid and reprecipitating by ammonia.

CHARACTERS AND TESTS.—A white, usually amorphous, solid, soluble in 150 parts of cold and 50 of hot water, and much more soluble in alcohol and in ether; strongly alkaline to reddened litmus, neutralising acids, and precipitated from them by the caustic alkalies, but not by carbonate of ammonia or the bicarbonates of soda or potash. It melts with heat, and burns with a smoky flame, leaving no residue when burned with free access of air.

OFFICINAL PREPARATION.

B.P. Unguentum Aconitæ.—Aconitia, 8 gr., dissolved in rectified spirit, ½ fl. dr., and mixed with prepared lard, 1 oz.. For external application only.

PHYSIOLOGICAL ACTION—**General Action.**—Its action is exerted most markedly on the peripheral ends of sensory nerves, on the heart, and on the respiration.

In **frogs** it produces steady loss of motion, both voluntary and reflex, with gradually increasing weakness of respiration, and of

the heart, which finally stops in diastole, usually about the same time as the respiration.

In **man** one of the most marked symptoms is the local **tingling** and numbness produced in the mouth by aconite or aconitine if they come into actual contact with it. This irritation is not limited to the mouth, but occurs also in the gullet and stomach, where it produces belching, nausea, and vomiting. If aconite preparations, or aconitine, are taken in capsules so that they do not touch the mouth or tongue, this local tingling and numbness are hardly felt at all.

After absorption, however, the poison is carried by the circulation throughout the body, and then causes a tingling in all parts of the body in the order of their sensitiveness as determined by Weber. The most sensitive parts are affected first, viz., the tongue and lips, the finger-tips, face, perineum, breast, belly, and last the back.

The **heart** is quickly affected even by very small doses, and a single drop of the tincture (B.P.) given in water twice or thrice at intervals of a quarter of an hour will in many cases greatly reduce the rate of the pulse. This slowness of the pulse is due to an action of the aconite upon the vagus roots, and does not occur after the administration of atropine. In some cases of disease also the pulse seems little affected by aconite. In larger doses the vaso-motor centre becomes gradually paralysed, while the heart remains slow, the blood-pressure falls greatly, and the pulse is not only slow but exceedingly weak and irregular.

Great muscular weakness and **dyspnœa** occur, the respirations being slow, shallow, and feeble. The dyspnœa, and probably the weakness also, depend to a considerable extent upon the feebleness of the circulation and consequent imperfect nutrition of the nerve-centres, for the administration of atropine lessens the dyspnœa.

In addition to this, however, there must be a direct paralysing action on the respiratory centre, and **death** usually occurs from stoppage of the respiration.

When the heart is examined immediately after death, it is generally found to be still pulsating, although sometimes it is found to have stopped and even lost its irritability. In the latter stage of aconite poisoning the effects of imperfect respiration may become manifest in the livid colour and anxious appearance of the face, the cold sweat on the skin, and sometimes protrusion of the eyes with dilatation of the pupil.

Death is sometimes preceded by convulsions which do not appear to be entirely due to asphyxia.

Action on Individual Organs.—The **muscles** are little if at all affected by aconite. The terminations of the **motor nerves** appear to be first irritated, so that fibrillary twitchings of the muscles occur in a frog; afterwards they are paralysed. The peri-

pheral ends of **sensory nerves** in the skin and mucous membranes are first irritated, so that the peculiar tingling and numbness is felt, and sometimes also intense neuralgia, affecting branches of the fifth nerve; afterwards they are paralysed. The motor centres of the **spinal cord,** and the respiratory and vaso-motor centres in the **medulla,** appear first to be slightly stimulated, so that clonic convulsions may occur. The reflex power of the cord is diminished, the sensory ganglia being affected before the motor ganglia. The paralysis of the cord is probably to a great extent, however, due to its imperfect nutrition from failure of circulation. The **brain** remains unaffected, the mental faculties being usually clear up till death. Sometimes drowsiness occurs, which may, however, be due to the circulation; and headache is also observed, which seems to involve the interior of the head, and is distinct from the facial neuralgia observed in earlier stages of the poisoning. Like the motor centres in the cord, the **vaso-motor** centre in the medulla oblongata appears to be first stimulated and then paralysed, so that the blood-pressure in rabbits rises at first, but in dogs and cats it falls, apparently from the slowing of the pulse produced by stimulation of the vagus roots. Later on, the vaso-motor centre becomes paralysed to a considerable extent, though not entirely, so that the blood-pressure falls greatly. Although not completely paralysed, it becomes insensible to reflex stimulation, so that irritation of a sensory nerve will no longer raise the blood-pressure.

The **heart** in the frog is first quickened and then slowed. In man or mammals there is first slowness of the pulse, but shortly before death it may become more rapid. This effect appears to depend chiefly upon primary stimulation succeeded by paralysis of the motor ganglia in the heart, the effect in mammals being altered by the simultaneous action of the drug upon the vagus roots in the medulla.

The **respiration** is at first slow and deep with marked expiratory effort; afterwards slow, shallow, and laboured.

This effect appears to be due to the direct action of the poison on the respiratory centre, together with its indirect action through weakening of the circulation (pp. 203 and 204). Before death convulsions occasionally occur, and these are, to a great extent, due to the indirect effect through the circulation, but possibly also to a direct irritating effect of the drug on a convulsive centre in the medulla.

The **temperature** falls constantly throughout. The **stomach** is irritated immediately by the poison taken directly into it, so that violent vomiting may occur; but it may also be irritated by the poison being eliminated by the gastric mucous membrane after injection subcutaneously or into the blood, so that the effects are similar to those produced by the direct introduction of the drug into the stomach (p. 29). The **secretion** of the salivary gland is increased, and usually the sweat also, possibly other secretions.

The intestines are irritated like the stomach, and diarrhœa occurs in consequence.

The **pupil** at the commencement of poisoning alternately contracts and dilates, the tendency to contraction being best marked; and a similar result occurs from the local application of aconitine to the eye. Later on there is extreme dilatation. This dilatation may be due to reflex irritation from the gastro-intestinal mucous membrane (p. 186). Aconite quickly passes from the blood into the **tissues,** for if the greater part of the blood of a poisoned dog is transfused into the veins of a healthy one within a few minutes after poisoning has begun, it produces no effect.

THERAPEUTIC USES OF ACONITE. — Aconitine is applied **locally** in the form of ointment in cases of severe neuralgia, a small piece about the size of a pea being rubbed into the painful part. If the neuralgia affects the temple, great care must be taken that the ointment does not get into the eye, as rapid absorption occurs from the conjunctiva, and general poisoning may result.

Aconite liniment is frequently employed in muscular rheumatism; in various forms of neuralgia, such as sciatica; and over swollen and painful joints. Admixture with chloroform facilitates the absorption of alkaloids through the skin, so that a mixture of aconite liniment with chloroform liniment may be more efficacious than either the one or the other separately; but the mixture should be employed with care, and not over too large a surface, to prevent any risk of too rapid absorption.

As a local sedative to the **stomach** it has been employed in full doses to check the vomiting of pregnancy. Its chief use, however, is in the **febrile condition** depending upon local inflammations, such as tonsillitis, sore throat, pleurisy, pneumonia, phthisis, peritonitis, pericarditis, acute rheumatism, gout, erysipelas, otitis, gonorrhœa, and in urethral fever. In many of those conditions small doses of aconite slow the pulse, lower the temperature, and give much relief to the patient. In **cardiac disease** its action is somewhat uncertain. In nervous palpitation it is sometimes useful, and it may give relief in palpitation depending upon hypertrophy, but frequently it is of no use in this condition. In diseases of the **nervous system** its internal application alone, or combined with its external use, sometimes gives relief in headache, toothache, noises in the ear, neuralgia, especially of the face, in intercostal neuralgia, and neuralgia accompanying herpes-zoster. It has been found useful, also, in some cases of amenorrhœa depending on a sudden check to the menstrual flow, and also in severe menorrhagia.

MODE OF APPLICATION.—Externally it may be applied in the form of ointment or liniment, internally in the form of tincture or extract. The extract is uncertain in its strength, and death has occurred from the two grains laid down as a maximum by the British Pharmacopœia. The tincture should also be administered

in very small doses, as it is difficult to counteract its effect when too much has been given. Instead of giving a large dose, therefore, all at once, it is much better to give it in divided doses, such as one drop in a little water, every quarter or half an hour until the pulse has begun to be affected, and then every hour or two hours afterwards, according to the necessities of the case, so as to maintain the action (Ringer).

U.S.P. Staphisagria. STAPHISAGRIA. STAVESACRE. — The seed of *Delphinium staphisagria.*

CHARACTERS.—From one-eighth to one-sixth of an inch (3 to 4 millimetres) broad, flattish-tetrahedral, one side convex, brown or brownish-grey, with reticulate ridges, containing a whitish, oily albumen and a straight embryo; nearly inodorous; taste bitter and acrid.

COMPOSITION.—It contains several alkaloids, the most important being delphinine and staphisagrine.

ACTION.—**Staphisagrine** paralyses the **motor nerves** in frogs, like curare, and kills mammals without convulsions by paralysing the respiration. **Delphinine** resembles aconitine in many respects, and like it causes slowness of the **pulse** and **respiration**, paralysis of the **spinal cord,** and **death** by asphyxia. It stimulates the vagus centre in the **medulla,** and also the accelerating centre for the heart (p. 274). It slows the respiration, apparently by an action on slowing fibres of the **vagus,** for when the vagi are cut, it quickens respiration, probably by stimulating the respiratory centre in the medulla. In advanced stages of poisoning it paralyses the ends of the vagus in the **heart** and also the cardiac muscle. It removes the still-stand caused by muscarine and digitalin (Boehm). By depressing the action of the spinal cord it arrests the convulsions caused by strychnine.

USES.—Stavesacre is sometimes used externally as a parasiticide in the form of an ointment (3 parts of ground seeds to 5 of lard).

U.S.P. Pulsatilla. PULSATILLA.—The herb of *Anemone pulsatilla* and *Anemone pratensis,* and of *Anemone patens,* var. *Nuttalliana,* collected soon after flowering.

It should be carefully preserved and not be kept longer than one year.

CHARACTERS.—Leaves radical, petiolate, silky-villous, twice or thrice deeply three-parted or pinnately cleft, with linear, acute lobes, appearing after the large, purple (or, in the last-named species, sometimes whitish) flowers; inodorous, very acrid.

DOSE.—1½-6 grains.

COMPOSITION.—The fresh plant yields by distillation with water, an acrid, oily principle, with a burning, peppery taste. A similar oil is got from *Ranunculus bulbosus, R. flammula,* and *R. sceleratus.* Its therapeutic value is not great. When kept

for some time, this oily substance becomes decomposed into anemonic acid and anemonin.

ACTION.—The **oil** acts as a vesicant when applied to the skin. **Anemonic acid** appears to be inert. **Anemonin** sometimes causes local inflammation and gangrene when subcutaneously injected; vomiting and purging when given internally. It is uncertain whether these symptoms are due to anemonin itself or to some impurity in it. The chief action of pure anemonin is a depressant one on the **circulation, respiration,** and **spinal cord**, to a certain extent resembling that of aconite. The symptoms are slow and feeble **pulse,** slow respiration, coldness, **paralysis** affecting first the hind and then the fore-legs, **dyspnœa,** and **death** without convulsions. In poisoning by extract of pulsatilla convulsions are always present. Their absence in poisoning by anemonin appears to be due to its paralysing action on motor centres in the brain (p. 153); it does not paralyse the muscles and motor nerves in frogs.

USES.—It is supposed to be **diaphoretic** and **emmenagogue.** It has been used in amenorrhœa, dysmenorrhœa, catarrh of various mucous membranes, bronchitis, and asthma.

Adonis Vernalis. Not officinal.—This plant is considered by some to be a species of Anemone.

COMPOSITION.—It contains a glucoside adonidin.

ACTION.—Adonidin has an action almost exactly like that of **digitalin,** but is much stronger, and is said not to be cumulative. It appears to be about ten times as powerful as digitoxin.

USE.—It may be used instead of digitalis, and sometimes succeeds when digitalis fails. It is, however, less certainly beneficial in valvular disease than digitalis, and should be used only when digitalis fails (Nothnagel). It appears to produce vomiting and diarrhœa more readily than digitalis (Bubnoff).

ADMINISTRATION.—It may be given in the form of infusion ($\frac{1}{2}$-2 dr. of the root to 6 fl. oz. of water) in doses of $\frac{1}{2}$ fl. oz. every two to four hours.

U.S.P. Cimicifuga. CIMICIFUGA. BLACK SNAKEROOT.—The rhizome and rootlets of *Cimicifuga racemosa* (synonym *Actea racemosa*).

CHARACTERS.—The rhizome is horizontal, hard, two inches (5 centimetres) or more long, about one inch (25 millimetres) thick, with numerous stout, upright or curved branches, terminated by a cup-shaped scar, and with numerous, wiry, brittle, obtusely quadrangular rootlets, about one-twelfth of an inch (2 millimetres) thick; the whole brownish-black, nearly inodorous, and having a bitter, acrid taste. Rhizome and branches have a smooth fracture, with a large pith, surrounded by numerous sub-linear, whitish wood-rays, and a thin, firm bark. The rootlets break with a short fracture, have a thick bark, and contain a ligneous cord branching into about four rays.

OFFICINAL PREPARATIONS.

	DOSE.
Extractum Cimicifugæ Fluidum	30–60 min.
Tinctura Cimicifugæ	½–2 fl. drm.

COMPOSITION.—It contains, when fresh, a volatile oil, a resin, and a bitter neutral substance, but it is not known to which of these its activity is due.

ACTION.—In large doses this drug produces nausea, vomiting, depression, headache, and giddiness. Its action on the heart is said to be like that of digitalis, but is less powerful.

USES.—It is used as a **stomachic** and **cardiac tonic** in various conditions of weakened heart. It has been used in chorea, rheumatic affections, headache, and neuralgia, and is useful as an **expectorant** in bronchitis or acute catarrh, and in phthisis. Under the name of *Actea racemosa* it obtained a great reputation as a cure for acute rheumatism, but this was not confirmed on a more extensive trial.

Podophylli Radix, B.P.; Podophyllum, U.S.P. PODOPHYLLUM ROOT.—The dried rhizome and rootlets of *Podophyllum peltatum*, North America.



FIG. 139.—Podophyllum.

CHARACTERS.—In pieces of variable length, about ⅛ of an inch thick, dark reddish-brown externally, whitish within, breaking with a short fracture. At intervals of about 2 inches the rhizome is thickened, and from each swollen part or joint, a number of pale brown rootlets spring. These are brittle, and many of them break short off close to the rhizome, leaving little round white spots which help to distinguish podophyllum easily from other roots. Powder yellowish-grey, sweetish in odour, bitterish, subacrid and nauseous in taste.

PROPERTIES AND COMPOSITION.—Its most important constituents are podophyllin, which is a resinous substance, and berberine, which is a yellow alkaloid having little physiological action.

Podophylli Resina, B.P.; Resina Podophylli, U.S.P. RESIN OF PODOPHYLLUM.

PREPARATION.—The resin is dissolved out of the powdered root by exhausting with spirit, the greater part of which is recovered by distillation, and the remainder holding the resin in solution is poured into water slightly acidulated with hydrochloric acid, when the resin is precipitated as a fine powder, as it is insoluble in water. The resin itself consists to a great extent of a fatty and

resinous acid, and subsides more quickly in acidulated than in pure water. It is afterwards washed and dried.

CHARACTERS AND COMPOSITION.—A pale greenish-brown amorphous powder, soluble in rectified spirit and in ammonia; precipitated from the former solution by water, from the latter by acids. Almost entirely soluble in pure ether. It consists chiefly of a fatty and a resinous acid having little physiological action, and two active substances, podophyllotoxin and picropodophyllin, the former being much the more powerful.

OFFICINAL PREPARATIONS OF PODOPHYLLUM.

B.P.	DOSE.
Podophylli Resina (Podophyllin)..	$\frac{1}{8}$-1 gr.

U.S.P.	
Resina Podophylli	$\frac{1}{8}$-$\frac{1}{2}$ gr. (0·008-0·03 Gm.)
Abstractum ,, ...	5-10 gr. (0·33-0·67 Gm.)
Extractum ,, ...	1-3 gr. (0·06-0·2 Gm.)
Extractum ,, Fluidum	5-15 min. (0·3-0·9 c.c.)

PHYSIOLOGICAL ACTION. — The resin is the part chiefly employed. It acts as a drastic **purgative,** increasing the secretions of the intestinal mucous membrane, and of the liver (p. 353). It acts on the bowels, when injected subcutaneously as well as when introduced into the intestinal canal. Like many other **hepatic stimulants,** it does not increase the secretion of bile so much when it acts as a purgative (p. 356).

USES.—It is used in cases of biliousness associated with dark stools (Ringer). When the stools are pale, mercurial pill is usually employed. It is often employed in combination with other purgatives, such as colocynth, aloes or rhubarb. It is useful in congestion of the liver and of the portal circulation, in ague with congested liver, and in sick headache with biliousness. Its action is uncertain and it frequently causes griping.

Externally it acts as an irritant; if incautiously handled it often produces conjunctivitis.

U.S.P. Hydrastis. HYDRASTIS. GOLDEN SEAL.—The rhizome and rootlets of *Hydrastis Canadensis.*

CHARACTERS.—Rhizome about an inch and a half (4 centimetres) long and a quarter of an inch (6 millimetres) thick; oblique, with short branches, somewhat annulate and longitudinally wrinkled; externally yellowish-grey; fracture short, waxy, bright reddish-yellow, with a thickish bark, about ten narrow wood-wedges, broad medullary rays and large pith. Rootlets thin, brittle, with a thick, yellow bark, and subquadrangular, woody centre. Odour slight; taste bitter.

OFFICINAL PREPARATIONS.

	DOSE.
Extractum Hydrastis Fluidum.....	1-2 fl. drm.
Tinctura Hydrastis.....	2-5 fl. drm.

COMPOSITION.—It contains the yellow, bitter alkaloid berberine, and the colourless, also bitter, hydrastia, or hydrastine, besides a third alkaloid and a volatile principle not yet isolated.

USES.—Its uses are similar to those of the simple **bitters.** Professor Rutherford found the resinous substance obtained from the root to be an **hepatic stimulant** of moderate power (p. 353). This substance, which is also called hydrastin, must not be confounded with the alkaloid. It consists of a mixture of hydrastine, berberine, and resin in varying proportions. The pure alkaloid hydrastine is said to be **antiperiodic,** and causes ringing in the ears like quinine.

MAGNOLIACEÆ.

U.S.P. Illicium. STAR-ANISE. — The fruit of *Illicium anisatum.*

CHARACTER. — The fruit consists of 8 brown, boat-shaped carpels, joined at their inner ends so as to form a star. Each contains 1 seed with an oily taste. The taste of the fruit is sweet and aromatic.

COMPOSITION. —It contains a volatile oil which so closely resembles that of true anise as to be officinal.

Oleum Anisi, B.P. and **U.S.P.**—A volatile oil distilled from Illicium or Anise. For preparations and action *vide* Anise (p. 849).

MENISPERMACEÆ.

U.S.P. Menispermum. MENISPERMUM. CANADIAN MOONSEED.—The rhizome and rootlets of *Menispermum Canadense.*

CHARACTERS.—Rhizome several feet long, about a quarter of an inch (6 millimetres) thick, yellowish-brown or brown, finely wrinkled longitudinally and beset with numerous thin, rather brittle rootlets; fracture tough, woody; internally yellowish, with a thickish bark, a circle of porous, short, nearly square wood-wedges, and a large, central pith; nearly inodorous; taste bitter.

DOSE.—5-20 gr. in infusion.

COMPOSITION.—It contains a small quantity of berberine and a colourless alkaloid.

USES.—It acts as a **bitter tonic,** and is sometimes used also as a substitute for sarsaparilla.

Calumbæ Radix, B.P.; Calumba, U.S.P. CALUMBA ROOT. —The root, cut transversely and dried, of *Jateorrhiza Calumba,* (*Cocculus palmatus, DC.*). From the forests of Eastern Africa, between Ibo and the Zambezi.

CHARACTERS.—Slices, flat, circular, or oval, about 2 inches in diameter, from $\frac{1}{6}$ to $\frac{1}{3}$ of an inch thick, softer and thinner towards the centre, so as to present the appearance of biconcave discs, greyish-yellow, bitter.

COMPOSITION.—It contains a neutral principle, calumbin, a yellow alkaloid berberine, to which it owes its colour, and calumbic acid. All these are bitter. It contains much starch, which is dissolved by hot water, so that a decoction is blackened by iodine. The



FIG. 140.—Calumba.

infusion is consequently made with cold water to leave the starch behind, as it renders the infusion liable to decompose, especially in hot weather. It contains no tannin, and the infusion can therefore be prescribed along with salts of iron.

PREPARATIONS.

B.P.	DOSE.
Extractum Calumbæ	2-10 gr. or more.
Infusum Calumbæ (1 oz. to 1 pint)	1-2 fl. oz.
Tinctura Calumbæ	½-2 fl. drm.
Also contained in Mistura Ferri Aromatica.	

U.S.P.	
Extractum Calumbæ Fluidum	15-30 min. (0·9-1·9 c.c.)
Tinctura Calumbæ	1-4 fl. dr. (3·75-15 c.c.)

ACTION.—**Calumba** is a pure bitter stomachic tonic.

Neither the berberine nor calumbin which it contains has any powerful physiological action. **Berberine** in doses of 1½ grains given subcutaneously kills rabbits, with symptoms of prostration and fall of temperature; but a dose eight times as great given to them by the mouth has no action, and 15 grains only produce in man slight colicky pains and diarrhœa. It is said to cause contraction of the intestines and of the spleen, and to lessen oxidation in the blood. **Calumbin** seems to have still less action. In small doses it seems, like other bitters, to raise the blood-pressure slightly, and in large doses to lower it.

USES.—Calumba is used as a **bitter tonic** in atonic dyspepsia and debility of the digestive organs. It is said to have a soothing effect, and is therefore given in irritable conditions of the stomach. It is frequently employed in combination with iron, chiefly in the form of infusion; the advantage it possesses over other bitter infusions, except quassia, for this purpose, being, that it contains **no tannin** and consequently does not form an inky-looking mixture.

It may be used as a general tonic during convalescence from various acute diseases, and may be prescribed in combination with either acids or alkalis.

Pareiræ Radix, B.P.; Pareira, U.S.P. PAREIRA ROOT.—The dried root of *Chondodendron Tomentosum*, Brazil.

CHARACTERS.—Generally seen in more or less cylindrical pieces, about ¾ of an inch in diameter and four inches or more in length. The bark is greyish-brown, and the wood greyish-yellow. It is recognised by the well-marked rings and medullary rays on the wood. The rings are irregularly concentric.

COMPOSITION.—It contains an alkaloid pelosine or buxine which appears to be identical with beberine.

PREPARATIONS.

B.P.	DOSE.
Decoctum Pareiræ.....1½ ounce to pint	1½-2 fl. oz.
Extractum Pareiræ	10-20 gr.
Extractum Pareiræ Liquidum.....1 ounce to 1 fluid ounce	½-2 fl. drm.

U.S.P.	
Extractum Pareiræ Fluidum	1-2 fl. dr. (3·75-7·50).

PHYSIOLOGICAL ACTION AND USES.—Pareira is a bitter **tonic,** but is chiefly employed as a **stimulant** to the mucous membrane of the genito-urinary tract, in chronic catarrh of the **bladder.** It is usually given in the form of decoction or liquid extract, frequently combined with an acid or an alkali, according to the condition of the urine.

U.S.P. Picrotoxinum. PICROTOXIN. $C_9H_{10}O_4$; 182.—A neutral principle prepared from the seeds of *Anamirta paniculata.*

CHARACTERS.—Colourless, flexible, shining, prismatic crystals, permanent in the air, odourless, having a very bitter taste, and a neutral reaction. When heated to about 200° C. (392° F.), the crystals melt, forming a yellow liquid; when heated on platinum foil, they char and are finally completely dissipated. Concentrated sulphuric acid dissolves picrotoxin with a golden-yellow colour, which turns violet-red on the addition of a trace of bichromate of potassium. When mixed with three times its weight of nitrate of potassium, moistened with sulphuric acid, and then treated with strong solution of soda in excess, picrotoxin assumes a brick-red colour of short duration. The aqueous solution should remain unaffected by solutions of salts of mercury or platinum, tannic acid, iodide of mercury and potassium, or other reagents for alkaloids (abs. of, and difference from, alkaloids).

ACTION.—It stimulates all the motor and inhibitory centres in the **medulla,** especially the respiratory and vagus centres. It also irritates **motor centres,** either in the cerebrum or in the medulla and **cord,** producing in all vertebrates alternating epileptiform spasms, with periodic stoppage of the motions of the diaphragm and slowness of the pulse. The spasms often take the form

of swimming, running backwards or round in a circle (*manège* movements), or rolling of the body on its axis (pp. 156 and 183). The **temperature** is somewhat raised.

USE.—It is employed as an ointment (10 gr. to 1 oz. of lard) in tinea capitis, and to destroy pediculi. It should be used with care, as its application to the head has been followed by convulsions and death.

BERBERIDACEÆ.

U.S.P. Caulophyllum. CAULOPHYLLUM. BLUE COHOSH. —The rhizome and rootlets of *Caulophyllum thalictroides.*

CHARACTERS.—Rhizome about four inches (10 centimetres) long, and about one-fourth to two-fifths of an inch (6 to 10 millimetres) thick, bent; on the upper side, with broad, concave stem-scars and short, knotty branches; externally grey-brown, internally whitish, tough and woody. Rootlets numerous, matted, about four inches (10 centimetres) long, and one twenty-fifth of an inch (1 millimetre) thick, rather tough; nearly inodorous; taste sweetish, slightly bitter and somewhat acrid.

DOSE.—1-5 gr. in infusion.

COMPOSITION.—It contains the glucoside saponin (p. 832) and resins.

USES.—It has little medicinal virtue, though it has been recommended as a **diuretic, antispasmodic,** and **emmenagogue.**

PAPAVERACEÆ.

B.P. Papaveris Capsulæ. POPPY CAPSULES.—The nearly ripe dried capsules of the white poppy, *Papaver somniferum.* Cultivated in Britain.



FIG. 141.—Poppy capsule.

CHARACTERS.—Globular, two or three inches in diameter, crowned by a sessile stellate stigma, which distinguishes them from colocynth and bael fruits.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Decoctum Papaveris (2 oz. boiled for ten minutes in 1½ pints of water, strained, and made up to 1 pint)	For fomentations.	None.
Extractum Papaveris	2-5 gr.	
Syrupus Papaveris	1 fl. drm.-½ fl. oz.	

COMPOSITION.—The capsules contain a small amount of morphine (more being found when unripe than when ripe), together with meconic acid, and very minute quantities of papaverine and papaverosine. The seeds are devoid of these principles, but contain much bland oil.

ACTION AND USES.—Poppy capsules act in a similar manner to opium, but are much weaker, and not so certain in their action. They are employed in the form of syrup of poppies, and given chiefly to children as an opiate. Considering the uncertainty of its action, and in view of the fact that children are very readily affected by any preparation of opium, the drug should be used with caution. Externally the decoction is used for sedative fomentations to **allay pain.**

Opium, B. and U.S.P. OPIUM.—The inspissated juice obtained from the poppy, *Papaver somniferum*, grown in Asia Minor.

The unripe capsules are incised, or rather deeply scratched. The milky juice which exudes becomes inspissated by spontaneous evaporation, and is scraped off and made into lumps. As these ought to consist only of the tears of thickened juice from the incisions, the lumps should tear with an irregular surface, and when drawn across a piece of paper should leave a light-brown interrupted streak. Sometimes vegetable extracts are used to adulterate opium, and then it has a more even fracture, and makes a more or less even streak on a piece of paper.

CHARACTERS.—Irregular lumps, weighing from four ounces to two pounds; enveloped in the remains of poppy leaves, and generally covered with the chaffy fruits of a species of rumex; when fresh, plastic, tearing with an irregular, slightly moist chestnut-brown surface, shining when rubbed smooth with the finger, having a peculiar odour and bitter taste.

TEST.—100 grs. of opium should yield, when assayed, at least 6 to 8 grains of morphia B.P., and 9 according to the U.S.P.

PREPARATIONS.

B.P.		DOSE.
Confectio Opii (Pulv. Opii Co. 192 gr.; Syrup 1 oz.)	1 part in 40, nearly	5-20 gr.
Emplastrum Opii (with resin plaster)	1 part in 10	for external use
Enema Opii	½ fl. drm. tincture to 2 fl. oz. starch mucilage.	
Extractum Opii	About 1 part from 2	¼-3 gr. or more.
Extractum Opii Liquidum	22 gr. extract in 1 fl. oz., nearly	4-40 ♏ or more.
Linimentum Opii	1 in 2 (Laudanum, 1; Soap Liniment, 1).	
Morphiæ Acetas	About 1 part from 8 or 10	⅛-1 gr.

PREPARATIONS—*continued.*

B.P.		DOSE.
Morphiæ Acetatis Liquor	4 gr. acetate in 1 fl. oz.	10-60 ♏
Morphiæ Hydrochloras	About 1 part from 8 or 10	¼-1 gr.
Morphiæ Hydrochloratis Liquor	4 gr. hydrochlorate in 1 fl. oz.	10-60 ♏
Pilula Ipecacuanhæ cum Scillâ	1 part in 16½, nearly	5-10 gr.
Pilula Plumbi cum Opio	1 part in 8	4-8 gr.
[1] **Pilula Saponis Composita** (Opium 1; Hard Soap, 4; Water)	1 part in 6, nearly	3-5 gr.
Pulvis Cretæ Aromaticus cum Opio	1 part in 40	10-60 gr.
Pulvis Ipecacuanhæ Compositus	1 part in 10	5-15 gr.
Pulvis Kino Compositus	1 part in 20	5-20 gr.
Pulvis Opii Compositus	1 part in 10	2-5 gr.
Tinctura Camphoræ Composita	2 grains to 1 fl. oz.	15 ♏-1 fl. drm.
Tinctura Opii (Laudanum)	33 grains to 1 fl. oz., nearly	4-40 ♏ or more.
Tinctura Opii Ammoniata	5 grains to 1 fl. oz.	½-1 fl. drm.
Trochisci Opii	$\frac{1}{10}$th grain of extract in each	1-4.
Unguentum Gallæ cum Opio	32 grains to 1 oz. galls ointment	for external use.
Vinum Opii	22 gr. extract in 1 fl. oz., nearly	4-40 ♏ or more.

B.P. Pulvis Kino Compositus. COMPOUND POWDER OF KINO.—Kino, $3\frac{2}{3}$; opium, ¼; cinnamon bark, 1.

B.P. Pulvis Opii Compositus. COMPOUND POWDER OF OPIUM.—Opium, 1½; black pepper, 2; ginger, 5; caraway fruit, 6; tragacanth, ½.

B.P. Tinctura Camphoræ Composita. COMPOUND TINCTURE OF CAMPHOR (ENGLISH PAREGORIC).—Opium, 40 gr.; benzoic acid, 40 gr.; camphor, 30 gr.; oil of anise, ½ fl. drm.; proof spirit, 1 pint.

B.P. Tinctura Opii Ammoniata. AMMONIATED TINCTURE OF OPIUM (SCOTCH PAREGORIC).—Opium, in coarse powder, 100 gr.; saffron, 180 gr.; benzoic acid, 180 gr.; oil of anise, 1 fl. drm.; strong solution of ammonia, 4 fl. oz.; rectified spirit, 16 fl. oz.

B.P. Vinum Opii. WINE OF OPIUM.—Extract of opium, 1 oz.; cinnamon bark, 75 gr.; cloves, 75 gr.; sherry, 1 pint.

PREPARATIONS.

U.S.P.		DOSE.
Extractum Opii		½-1 gr. (0·031-0·065 Gm.)
Emplastrum Opii (6 parts in 100)	prepared from Extractum Opii	
Trochisci Glycyrrhizæ et Opii ($\frac{1}{20}$ gr. in each lozenge)	prepared from Extractum Opii	

U.S.P. Opii Pulvis. POWDERED OPIUM.—Opium dried at a temperature not exceeding 85° C. (185° F.), and reduced to a moderately fine powder. It ought not to contain less than 12 nor more than 16 per cent. of morphine.

PREPARATIONS.

U.S.P.	DOSE.
Acetum Opii (Black Drop)	10-15 min. (0·60-1 c.c.)
Opium Denarcotisatum	¼-2 gr. (0·016-0·13 Gm.)
Pilulæ Opii (Opium, 1 gr.; Soap, ¼ gr.)	One pill.
Pulvis Ipecacuanhæ et Opii (1 in 10)	5-15 gr. (0·32-1 Gm.)
Tinctura Ipecacuanhæ et Opii	4-15 min. (0·25-1 c.c.)
Tinctura Opii	6 min.
Tinctura Opii Camphorata	4-15 min. (¼-1 c.c.)
Tinctura Opii Deodorata	6 min.
Vinum Opii	6 min (0·37 c.c.)

[1] Pilula Saponis Composita is purely a preparation of opium. It is sometimes convenient to give opium to patients without their knowledge. If the pill were called Pilula Opii the patients would see from the prescription what they were taking, while they learn nothing about the nature of the medicine from the name Pil. Saponis Co. The name of this pill was changed from Pil. Saponis Co. to Pilula Opii in the B.P. of 1864, but the inconveniences which arose from this were so great that the name was altered again.

U.S.P. Acetum Opii. VINEGAR OF OPIUM.—Opium, 10 ; nutmeg, 3 ; extracted with diluted acetic acid by maceration and percolation up to 80 parts of liquid ; then sugar, 20, is added.

U.S.P. Opium Denarcotisatum. DENARCOTISED OPIUM. — Prepared by removing narcotine and odorous principles by extraction with stronger ether, and adding sufficient sugar of milk to make up the weight to that of opium containing 14 per cent. of morphine.

U.S.P. Tinctura Opii Deodorata. DEODORIZED TINCTURE OF OPIUM.—Macerate opium, 10, with water, 40, evaporate down to 10, shake with ether, 20, pour off the ether, and evaporate until the whole of the ether is gone. Mix with water, 50, filter, adding water up to 80, then add alcohol, 20.

U.S.P. Tinctura Ipecacuanhæ et Opii. TINCTURE OF IPECAC AND OPIUM. —Deodorized tincture of opium, 100, evaporated to 85, then fluid extract of ipecac, 10, is added, the mixture filtered, and diluted alcohol added up to 100.

U.S.P. Tinctura Opii Camphorata. CAMPHORATED TINCTURE OF OPIUM.—Powdered opium, 4 ; benzoic acid, 4 ; camphor, 4 ; oil of anise, 4 ; glycerine, 40 ; diluted alcohol up to 1,000.

U.S.P. Vinum Opii. WINE OF OPIUM.—Powdered opium, 10 ; cinnamon, 1 ; cloves, 1 ; stronger white wine up to 100.

COMPOSITION OF OPIUM.—Besides the usual constituents of vegetable products, such as mucilage, albumen, pectous substances, caoutchouc-like substance, fat, volatile substances, some sugar, salts of ammonia, calcium, and magnesia, it contains seventeen or eighteen alkaloids and two neutral substances, as well as a peculiar **acid**—meconic acid. The **alkaloids** are chiefly combined with meconic acid or sulphuric acid, but may be partly free. The three most important alkaloids are morphine, codeine, and thebaine. The others are papaverine, pseudomorphine or oxymorphine, gnoscopine, codamine, laudanine, laudanosine, meconidine, lanthopine, protopine, cryptopine, narcotine, oxynarcotine, hydrocotarnine, narceine, rhoeadine. The **neutral substances** are meconin and meconiasin. Some at least of the alkaloids in opium may be regarded as **derivatives** from morphine. Thus codeine and pseudomorphine or oxymorphine can be produced from morphine artificially.

Besides the derivatives of morphine found naturally in opium, various series of **alkaloids** can be **artificially prepared** from morphine by (*a*) the addition of alcohol radicals, or by (*b*) oxidation, or (*c*) by dehydration. To the series of alkaloids produced from morphine by the addition of alcohol radicals, the name of **codeines** has been given. An example of these is codethyline, obtained from morphine by the introduction of ether. Among the alkaloids produced by oxidation are oxymorphine and oxydimorphine. Apomorphine is produced by dehydration.

Meconic Acid.—This acid has very little physiological **action.** It has been stated to have a narcotic action, but this is very feeble. It possesses marked **reactions,** and these are important, as they serve to detect the presence of opium. With perchloride of iron

and soluble protosalts of iron, meconic acid and its salts give a blood-red colour even when considerably diluted. Acetates and sulphocyanides give a similar colour, but that due to meconic acid is distinguished from that due to acetates by not disappearing on heating, or on the addition of hydrochloric acid, and from that due to sulphocyanides by not disappearing on the addition of chloride of gold.

U.S.P. Morphina. MORPHINE. $C_{17}H_{19}NO_3,H_2O$; 303.—An alkaloid prepared from opium.

CHARACTERS.—Colourless or white shining prismatic crystals, or a crystalline powder. Permanent in air, having a bitter taste and alkaline reaction. Heated on platinum foil, they fuse, char, and disappear. Solubility—slight in cold water; complete in 500 parts boiling water; in 100 alcohol at 15° C. (59° F.); in 36 boiling alcohol; in 13 boiling absolute alcohol; almost insoluble in ether; slightly soluble in chloroform.

REACTIONS.—Morphine is first reddened and then rendered yellow by nitric acid. With ferric chloride it gives a blue colour, changed to green by excess of the reagent, and destroyed by free acids or alcohol, but not by alkalies. A solution of morphine, acidified by acetic or sulphuric acid, is not precipitated by tannic acid.

IMPURITIES.—Other alkaloids.

TESTS.—On adding 20 parts of colourless solution of soda or potassa to 1 part of morphine, a clear, colourless solution should result without a residue (absence of other alkaloids). Morphine yields a colourless solution with cold, concentrated, sulphuric acid, which should not acquire more than a reddish tint by standing for some time, and which should not assume a purple or violet, but merely a greenish colour, on the addition of a small crystal of bichromate of potassium (absence of and difference from strychnine, brucine, &c.).

Morphiæ Hydrochloras, B.P.; Morphinæ Hydrochloras, U.S.P. HYDROCHLORATE OF MORPHIA, B.P., OR OF MORPHINE, U.S.P. $C_{17}H_{19}NO_3.HCl.3H_2O$.

CHARACTERS AND TESTS.—White, feathery, acicular prisms of a silky lustre, permanent in air, and soluble in water and spirit. The aqueous solution gives a white curdy precipitate with nitrate of silver (HCl), and a white one with potash, soluble in excess (morphine). It exhibits the reactions of morphine. Heated on platinum foil, it leaves no residue (no inorganic salts). Soluble in 24 parts of water at 15° C.

PREPARATION.—Mix concentrated infusion of opium with chloride of calcium, decolorise by animal charcoal, precipitate the morphine by ammonia, and neutralise with hydrochloric acid.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Liquor Morphiæ Hydrochloratis...4 grs. in 1 fl. oz.	10-60 min.	None.
Suppositoria Morphiæ	½ gr. in each suppository....	
,, ,, cum Sapone	½ gr. in each suppository....	
Trochisci Morphiæ	1/36 gr. in each lozenge	one to four.
,, ,, et Ipecacuanhæ	1/36 gr. in each lozenge	one to four.

Liquor Morphiæ Hydrochloratis. SOLUTION OF HYDROCHLORATE OF MORPHIA.—Add diluted hydrochloric acid (8 min.), rectified spirit (2 fl. dr.) to distilled water (6 fl. dr.), and dissolve hydrochlorate of morphia (4 gr.) in the mixture.

Morphiæ Acetas, B.P.; Morphinæ Acetas, U.S.P. ACETATE OF MORPHIA, B.P.; ACETATE OF MORPHINE, U.S.P. $C_{17}H_{19}NO_3.C_2H_4O_2$.

CHARACTERS AND TESTS.—A white powder, with a faintly acetous odour, soluble in water and in spirit. Potash or soda gives a precipitate soluble in excess, and exhibiting the reactions of morphine, U.S.P. When sulphuric acid is added to the salt, acetous vapours are evolved. When freshly prepared it is soluble in 12 parts of water at 15° C.

PREPARATION. — Obtain morphia by precipitating it from the hydrochlorate by ammonia, dissolve it in acetic acid and crystallise, B.P. In the U.S.P. morphine is officinal, and requires only to be dissolved in acetic acid.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Liquor Morphiæ Acetatis...4 gr. in 1 fl. oz.	60 min.	None.
Injectio Morphiæ Hypodermica...1 gr. in 12 ♏	2-6 min. or more.	

Liquor Morphiæ Acetatis. SOLUTION OF ACETATE OF MORPHIA.—It is prepared like the solution of the hydrochlorate, using the acetate of morphia and acetic acid.

Injectio Morphiæ Hypodermica. HYPODERMIC INJECTION OF MORPHIA.—Acetate of morphia is freshly prepared, by precipitating morphia from a solution of 88 grains of hydrochlorate of morphia in 2 ounces of warm distilled water, with sufficient ammonia to render the solution alkaline. The morphia is washed on a filter, dissolved in about an ounce of distilled water with the addition of acetic acid, until the whole of the morphia is dissolved and a slightly acid solution formed. Enough distilled water is now added to make up the solution to 2 fluid ounces exactly. It is then filtered, and kept from the light in a stoppered bottle.

U.S.P. Morphinæ Sulphas. SULPHATE OF MORPHINE. $(C_{17}H_{19}NO_3)_2.H_2SO_4.5H_2O$; 758.

CHARACTERS.—White feathery silk crystals, permanent in air, no smell, bitter taste. Soluble in 24 parts of water at 15° C. In its reactions it corresponds to the hydrochlorate, but is known to be a sulphate by giving with chloride of barium a white precipitate insoluble in hydrochloric acid.

PREPARATIONS.

	DOSE.
Pulvis Morphinæ Compositus	10 grs. (0·65 Gm.)
Trochisci Morphinæ et Ipecacuanhæ	

Pulvis Morphinæ Compositus. COMPOUND POWDER OF MORPHINE (Tully's Powder).—Sulphate of Morphine, 1; camphor, 20; glycyrrhiza, 20; precipitated carbonate of calcium, 20; alcohol, q.s. to mix the camphor intimately with the other ingredients. It is intended as a substitute for Dover's powder.

U.S.P. Apomorphinæ Hydrochloras. HYDROCHLORATE OF APOMORPHINE. $C_{17}H_{17}NO_2HCl$; 303·4.—The hydrochlorate of an artificial alkaloid prepared from morphine. It should be kept in small, well-stoppered vials, in a dark place.

PREPARATION.—By heating morphine with concentrated hydrochloric acid.

CHARACTERS. — Minute, colourless, or greyish-white, shining crystals, turning greenish on exposure to light and air, odourless, having a bitter taste, and a neutral or faintly acid reaction. Soluble in 6·8 parts of water and in 50 parts of alcohol at 15° C. (59° F.); slowly decomposed by boiling water or boiling alcohol; almost insoluble in ether or chloroform; should it impart colour to either of these liquids, it should be rejected, or it may be purified by thoroughly agitating it with either liquid, filtering, and then rapidly drying the salt on bibulous paper, in a dark place. The aqueous solution, on gentle warming, rapidly turns green, but retains a neutral reaction. Solution of bicarbonate of sodium, added to an aqueous solution of the salt, throws down the white, amorphous alkaloid, which soon turns green on exposure to air, and forms a bluish-green solution with alcohol, a purple one with ether or pure benzol, and a violet or blue one with chloroform. Addition of test-solution of nitrate of silver to an aqueous solution of the salt produces a white precipitate, insoluble in nitric acid, but instantly reduced to metallic silver by water of ammonia.

DOSE.—$\frac{1}{10}$-$\frac{1}{5}$ grain (·006-·012 Gm.) hypodermically as emetic.

ACTION.—When given internally or injected hypodermically apomorphine acts as an **emetic**, producing nausea and vomiting in from five to twenty minutes. After vomiting has occurred the nausea usually disappears quickly. It usually produces less depression than tartar emetic, but collapse has occurred from its use in children. It probably causes vomiting, partly reflexly and partly directly, in the same way as tartar emetic (p. 324). It stimulates the **motor centres** in the **brain** and the respiratory and vomiting centres in the **medulla**, and afterwards paralyses them.

In rabbits, which cannot vomit, apomorphine causes constant movement, rapid breathing, convulsions, paralysis, and death. In cats and dogs small doses cause vomiting, while large doses do not, but produce *manège* movements and paralysis.

It paralyses **muscular fibre,** voluntary and involuntary, but does not affect motor or sensory nerves. The **pulse** is at first quickened, while the blood-pressure is unaltered; but large doses paralyse the heart. The **secretion** of bronchial mucus is increased (p. 218).

USES.—It is used as an emetic for the purposes already mentioned (p. 325). Its special advantages are the readiness with which it can be administered by hypodermic injection without causing any local irritation and the short duration of the nausea it occasions. It is useful also as an expectorant, alone or along with morphine (p. 218).

U.S.P. Codeina. CODEINE. $C_{18}H_{21}NO_3.H_2O$; 317.—An alkaloid prepared from opium. It is probably methyl-morphine. Morphine = $C_{17}H_{18}NO_2(OH)$; codeine = $C_{17}H_{18}NO_2(OCH_3)$.

CHARACTERS.—White, or yellowish-white, more or less translucent, rhombic prisms, somewhat efflorescent in warm air, odourless, having a slightly bitter taste and an alkaline reaction. Soluble in 80 parts of water at 15° C. (59° F.), and in 17 parts of boiling water; very soluble in alcohol and in chloroform: also soluble in 6 parts of ether and in 10 parts of benzol, but almost insoluble in benzin. When heated to 120° C. (248° F.), codeine loses its water of crystallisation. At about 150° C. (302° F.) it melts, and, on ignition, it is completely dissipated. Codeine is dissolved by sulphuric acid containing 1 per cent. of molybdate of sodium, to a liquid having, at first, a dirty green colour, which, after a while, becomes pure blue, and gradually fades, within a few hours, to pale yellow. On dissolving codeine in sulphuric acid, a colourless liquid results, which, on the addition of a trace of ferric chloride, and gentle warming, becomes deep blue. An aqueous solution of codeine, added to test-solution of mercuric chloride, should produce no precipitate; and if codeine be added to nitric acid of sp. gr. 1·200, it will dissolve to a yellow liquid which should not become red (difference from and abs. of morphine).

DOSE.—For diabetes $\frac{1}{2}$ grain gradually increased to 5 grains or more three times a day, unless it produces great drowsiness or the sugar disappears. For cough $\frac{1}{6}$ of a grain every three or four hours.

ACTION.—Codeine has only a slight hypnotic action, and may sometimes be given in doses of 15 grains daily without producing any marked drowsiness in diabetic patients. Others again are rendered drowsy by 5 or 6 grains daily. Its most marked action appears to be on the **nerves** of the abdominal **viscera** and on motor centres in the brain. When given for several days it lessens the irritability of the digestive tract so that irritant poisons, like arsenic, produce neither vomiting nor purging.

It increases the irritability of the **spinal cord,** and produces in frogs languor succeeded by convulsions and paralysis. In mammals it appears rather to stimulate **motor centres** in the brain (p. 159). It causes some drowsiness, but the motor phenomena are most marked. These are twitchings, *manège* or swimming movements, paralysis of the hind-legs, and weakened

circulation, followed by a sudden shriek and convulsions. Death may occur at once or recovery occur.

I have observed symptoms very like these in poisoning by pure brucine, and in some points they resemble those of picrotoxin (p. 758).

USES.—Although it is not a powerful hypnotic like morphia, codeine has been strongly recommended in nervous insomnia, and also in cases where sleep is prevented by the pain of rheumatism or cancer or by distressing cough. Its power to lessen the irritability of the intestinal nerves has been already mentioned, and possibly it exerts a similar action on the nerves of other viscera, such as those of the respiratory organs, &c. Such an action would explain its beneficial effects in **cough** when morphia cannot be borne. Its chief use is in **diabetes.**[1] It certainly lessens, and sometimes entirely removes, the sugar from the urine. As Claude Bernard found that irritation of the central end of the cut vagus caused dilatation of the hepatic vessels and the appearance of sugar in the urine, it seems not improbable that the utility of codeine in diabetes is due to its power of lessening the irritability of the afferent fibres in the nerves of the abdominal viscera. This is rendered all the more likely by the fact that codeine does not prevent the occurrence of sugar in the urine in carbonic oxide poisoning,[2] where alterations in tissue change, leading to glycosuria, are probably of a more general nature, and less dependent on local alterations in the hepatic circulation.

Physiological Action of Opium.

GENERAL ACTION.—Opium, and all its alkaloids hitherto examined, act almost exclusively on the **central nervous system,** and in mammals especially on the brain, the brain symptoms preponderating in proportion as the organ is developed relatively to the other nerve centres. This conclusion holds good only for mammals, and must be qualified in regard to the frog, for in it narcotine, codeine, papaverine, and thebaine have also a paralysing action on the motor ganglia of the **heart.** Opium and its alkaloids agree not only in the organ they affect but in the nature of their action. The symptoms may be divided into two stages:—

(1) **Narcosis,** due to a paralytic action on the brain, followed by

(2) **Tetanus,** due to increased irritability of the spinal cord.

Action on Frogs.—If the drug be introduced by injection under the skin of a frog, the **functions of the nerve centres** are **abolished** in the order of their development, the highest centres being first affected (*vide* p. 153).

[1] Pavy, *Guy's Hospital Reports*

[2] The late Otto Schultzen.

The first symptom to appear after the injection of the drug is a diminution of the power of voluntary movement; the frog remains quiet, making no effort at voluntary movement, but when irritated responds to the stimulation by springing in the usual way. Next, the power of co-ordination is lost; the frog springs as before when irritated, but has no control over the direction of its leaps. It then gradually loses the power of springing in response to stimulation, and finally reflex action cannot be excited. The heart is unaffected.

After a time increased excitability of the spinal cord comes on, so that the slightest irritation causes muscular spasms like those of strychnine poisoning. During this condition the spinal cord of the frog does not react to stimuli in the ordinary way, but responds as it were by one violent explosion, after which it seems to become exhausted for a time, but after an interval another violent spasm can be induced, so that there are alternating periods of spasm and exhaustion. If the action of the drug be not pushed beyond this point, the phenomena will pass off in the reverse order of their appearance. If pushed further, there succeeds a deepening paralysis, and respiration becomes first slower and then stops.

Action on Birds.—Birds are peculiarly insusceptible to the action of opium or morphine.

Action on Mammals.—Opium causes partial abolition of voluntary movement, sometimes preceded by a certain amount of increased excitability, followed by sleep. Sometimes the spinal cord shows signs of increased excitability with diminished conducting power, evidenced by convulsions with a tendency to paralysis of the hinder limbs.

Action on Man.—In man the action of opium is chiefly upon the **brain,** producing sleep. When taken in **small doses** of $\frac{1}{4}$ gr. to 1 gr. there is, first, a stage of **excitement** of the circulation, as evidenced by the pulse being fuller and quicker, and by the surface of the skin being warm and flushed. During this stage the individual has the power of directing his energies to any particular object, and the action of the drug causes him to do well whatever he wishes to do. Thus, if he wishes to sleep, and surrounding circumstances be favourable, an agreeable languor followed by quiet sleep comes on. He can be easily aroused from this sleep; and after a few hours the effect passes off, leaving, however, slight headache and languor, with dryness of mouth and slight nausea. If, on the other hand, he wishes to work, he can do this with increased energy; or, if he desires to exert the mind, he will find his imagination more vivid, his thoughts more brilliant, and his power of expression greater (Christison). The after-effects are the same as after sleep.

With **moderate doses** of 1 gr. to 2 grs. the stage of **excitement** is **short** and is followed by **deep sleep,** from which the person can still be aroused. The after-effects are severe headache, with

nausea, furred tongue, and loss of appetite. During the stage of sleep the brain is anæmic, both the arteries and veins being empty (*vide* p. 165).

With **large doses** of 3 grs. or more the **first stage** is very **short. Sleep** rapidly follows, becomes deeper and deeper, and passes into **coma,** from which the patient can no longer be aroused. The arms and limbs are limp; the face is generally pale with a bluish tinge at times; the eyes are sunken, the pupils very much contracted, almost to the size of a pin's point; respiration slow and stertorous. The pulse during sleep and coma is slow and full; as coma proceeds it becomes feebler. Finally **death** by asphyxia occurs, the respiration ceasing before the heart. It may occasionally be preceded by convulsions, though this is rare.

Post-mortem the ordinary appearances of death by asphyxia are found, viz. congestion of the brain and lungs, etc., the ventricles of the brain contain serous fluid, the veins of the brain and spinal cord are distended with dark blood; and there may be slight extravasation of blood in some of the tissues.

Diagnosis between Opium Poisoning, Intoxication, and Apoplexy.—One should obtain the history of the case where it is possible. When this cannot be done, for instance in cases where the patient is found lying unconscious, the diagnosis is sometimes extremely difficult.

Notice first the odour of breath; the **smell** guides one in opium poisoning. The smell of alcohol does not assist one much, as it may be taken with opium; and in apoplexy brandy is frequently given by the person who first finds the unconscious patient.

Secondly, the **pupil,** which is very much contracted in opium, but dilated in alcoholic, poisoning, and often unequally contracted in apoplexy. It must be borne in mind that in apoplexy of the pons varolii, the pupils may be equally and extremely contracted just as in opium poisoning. In apoplexy the arms on being raised and then relaxed fall unequally on the two sides, one being more rigid or flaccid than the other. In no case should the individual be treated roughly or exposed to the slightest chance of a chill, but on the contrary he must be kept warm; and if it appears to be a case of poisoning by alcohol or opium, and not apoplexy, the stomach should be washed out and strong coffee injected.

Treatment in Opium Poisoning.—Evacuate the stomach as soon as possible by administering 20 grs. of zinc sulphate in a little water; if this acts, then give some strong coffee. Sometimes the zinc will not produce vomiting on account of the insensibility of the stomach and vomiting centre due to the action of the opium. If such be the case, employ the stomach pump, wash out the stomach with warm water, and inject coffee. Keep the patient awake by walking him about the room, tapping on the forehead with the finger-nails, or flicking him with a wet towel. Apply mustard leaves to various parts of the body, or use a galvanic

battery. Cold affusion is a good adjunct; but the alternate use of hot and cold water is better both as a stimulant and as preventing the risk of chilling the patient. Lastly, give a subcutaneous injection of 4 minims of liq. atropiæ, B.P. every ten minutes, until symptoms of recovery show themselves or the pulse is quickened or the pupil dilated.

Precautions.—Do not allow the patient to become cold while trying to rouse him, and take care not to chill him when applying cold affusions, as death may result from syncope after recovery from the comatose condition. The average length of insensibility is twelve hours, and if this period be passed, recovery is nearly certain, but sometimes the symptoms may reappear, and death from asphyxia or syncope occur.

Treatment of the Symptoms after an Ordinary Dose.—Strong coffee with or without brandy, or lemon-juice and water, should be administered. The patient should be kept in bed.

Action on Special Organs.—Opium has little action on **muscular contractility**. The action of opium on the **motor nerves** is doubtful. According to some observers it first increases and then diminishes their excitability, the action commencing at the centres and proceeding towards the periphery. Others however have found that opium has little or no action on them, except towards the end of poisoning, when all the functions are paralysed.

The **sensory nerves** are first excited and then paralysed. Opium applied locally is said by some observers to have no action on the sensory nerves, but it has been found to have a paralysing action by Baxt. The results of his experiments are confirmed by clinical experience, for when the drug is injected subcutaneously it lessens sensibility, diminishes the power of distinguishing tactile impressions, and relieves pain when present.

When applied externally to the eye, or to the skin denuded of its epidermis, opium also relieves pain.

Opium lessens first the conducting power of the **spinal cord,** then the reflex functions, producing first inco-ordination of the movements of the hind limbs and then paralysis of reflex action.

Opium acts on the centres of the **brain** in the order of their importance; thus in the frog, there is, first, loss of voluntary motion, such as may be produced by extirpation of the cerebral hemispheres; next, loss of co-ordination, such as is produced by extirpation of the optic lobes; and lastly, effects like those produced by destruction of the medulla (p. 152).

The **pupil** is markedly contracted by opium, the action of the drug being probably central and not peripheral; but the exact mode of action has not been definitely made out. Stimulation of sensory nerves causes reflex dilatation of the pupil, and it is not improbable that the contraction which opium produces is due to its paralysing this reflex action more or less completely (p. 186).

The pupil sometimes dilates just before death. This dilatation

is probably due to the excessively venous condition of the blood, as in the later stages of chloroform poisoning.

The first effect which opium has on the **circulation** is to cause a dilatation of the vessels of the skin, sometimes giving rise to a cutaneous eruption of a roseolar character, accompanied by itching, and coming on either before or after sleep.

The **vaso-motor** centre in the medulla is slightly, if at all, affected by small doses of opium. Large doses paralyse it.

The drug appears to have a peculiar action on the **peripheral vaso-motor apparatus.** It is well known that stimulation of the chorda tympani causes dilatation of the vessels of the submaxillary gland, but I found that after the exhibition of opium the vessels of the gland no longer dilated, but on the contrary contracted, on stimulation of the chorda tympani, so that the blood which issued from the gland was not of a bright arterial hue, but was very dark, and flowed drop by drop. This observation requires confirmation; but if it be confirmed, this result might serve to explain the effect of opium in cutting short inflammations, *e.g.* of the peritoneum.

In peritonitis as in other inflammations the blood-vessels are greatly dilated. Opium by its action on the vaso-motor centre, and (if these experiments be correct) by its action also on the peripheral terminations of vaso-motor nerves, will prevent or diminish the reflex dilatation of the vessels which the local irritation would otherwise produce. Congestion will thus be diminished and inflammation will thus be relieved. The action of opium in peritonitis is therefore probably twofold. First, it lessens peristaltic movements of the intestines and thus diminishes local irritation. Secondly, it lessens the reflex activity of the centres through which local irritation causes dilatation of the vessels and thus diminishes peritoneal congestion. The late Sir Robert Christison used to say that not only coryza but probably all inflammations could be nipped in the bud by opium if it were only given sufficiently early and sufficiently freely.

The blood-pressure appears to be but little affected by opium. It varies after the injection of the drug, but this variation is probably due to an alteration in the general functions of the body, for example, great quiet, &c.

Opium has little direct action on the **heart**, which continues to beat after the nervous centres have been experimentally destroyed in animals.

On Secretion.—The secretions of the body, except those of urine and of sweat, are lessened by opium.

If the lingual nerve of an animal be stimulated, a reflex flow of **saliva** takes place; but when opium has been given in sufficient quantity this reflex action is paralysed, and stimulation of the nerve no longer excites a flow. Very large doses may cause salivation (p. 311) however. Opium also diminishes the other secretions of

the alimentary canal, causing impairment of digestion, and this action serves partially to explain the constipation produced by opium.

The quantity of **sweat** secreted is increased by opium, and especially so when it is combined with ipecacuanha. Just before death by opium the secretion of sweat is greatly increased, so that the surface is bathed in it, but this is due to stimulation of the sweat centres in the spinal cord by the increasing venosity of the blood (p. 385).

The quantity of **urine** is frequently lessened. Sometimes it may be really increased, but appear diminished in consequence of paralysis of the bladder preventing its being evacuated. Sometimes there is constant desire to pass water.

On the Intestines.—The action of opium on the intestines varies with the dose. On isolating a piece of intestine and supplying it artificially with blood, the action of opium may be observed by mixing it with the blood (p. 333). When used in large quantity all peristaltic action ceases, and the intestine becomes tetanically contracted. Hence in large doses, injected directly into the jugular vein, it acts as a most powerful purgative, causing one very copious evacuation. It acts chiefly on the small intestines. In moderate doses it lessens peristaltic action and causes constipation. In very small doses it generally increases peristalsis and acts as a purgative, but not invariably so. This property is made use of in cases of constipation due to reflex irritation starting from the ovary. The mode of action has already been discussed at p. 336.

Elimination.—Morphine is eliminated by the gastric mucous membrane (p. 29), and may be found in the stomach after subcutaneous injection. It is excreted also in the bile, but may remain a long time in the liver. It is found unchanged in the urine. In cases where its use has been continued for some time, some of it probably becomes changed in the body, as a substance with the chemical reactions of oxydimorphine has been found in the liver and kidneys in such cases.

Circumstances Modifying the Action of Opium.

Age.—In childhood the brain is proportionately larger than in adult life, hence the effect of opium is greater than in adults, and children bear it very badly; consequently smaller doses must be given than are proportionate to their ages. Care is necessary from the age of 6 months to 1 year, as one minim has produced fatal results. In old age the dose must be diminished according to the advance in years.

Sex.—Women are more readily affected than men, and are more liable to nausea and headache after its administration.

Idiosyncrasy.—Small doses easily affect some, and on the other hand large doses are nearly inert in other subjects. Excitement and delirium, instead of quietness and sleep, are not unfrequently

produced. In such cases it is best to give a few whiffs of chloroform to quiet the patient and induce sleep, if the excitement has already come on.[1] If it is necessary to give opium or morphine to a patient having this idiosyncrasy, it ought to be combined with chloral or a bromide, or with both. In some persons excitement and wakefulness occur on the night immediately succeeding the dose, and sleep only occurs on the second night.

Habit.—The effect of habit is perceived in two ways—in some cases, large quantities are required to produce a result—in others a long interval is necessary for the drug to take effect. As much as two pints of the tincture have been taken in the course of a day; and as much as 12 gr. of morphine have been subcutaneously injected. Both slowness and weakness of action may result from its continued use, so that it may be necessary not only to give a larger dose but to give it a considerable time beforehand. In one case with which I am acquainted, after a few months during which the time gradually increased, it became necessary to give the dose 24 hours before its effect was desired.

The explanation of this tardy action probably is that the absorptive power of the intestines is diminished by the continual use of the drug, for it is well known that opium-eaters can take large doses of corrosive sublimate without experiencing any ill effects, the drug being but slowly absorbed.

But it is quite possible, indeed probable, that there is, besides delayed absoption, another factor in the tolerance of opium induced by repeated doses. It is possible that part of the morphine introduced is converted in the organism into oxydimorphine, which appears, to a certain extent, to counteract the soporific action of morphine,[2] or into other substances which may have this action. Each dose of morphine will thus leave in the body substances having an action antagonistic to the next dose unless a sufficient interval should elapse between them to allow them to be completely eliminated.

Opium Eating.—When opium is first taken, its action is to stimulate and afterwards depress; to remove this depression the individual takes another dose; a habit of taking the drug thus becomes established. The nervous system suffers, the mental powers become enfeebled, the moral faculties perverted, and there is inability to distinguish between truth and falsehood. Then the motor powers are attacked, the gait becomes shuffling and uncertain, and digestion is impaired. The bowels may be constipated, but are generally loose.

When morphine is taken for some time in medicinal doses, obstinate vomiting sometimes sets in and will not yield to ordinary remedies. It is usually checked by discontinuing the administration of the drug. This vomiting may possibly be due to the morphine

[1] Morrant Baker, *St. Bartholomew's Hospital Reports.*
[2] Diedrich, "Ueber Oxydimorphin," *Inaug. Diss. Göttingen*, 1883.

being converted into oxydimorphine[1] or apomorphine in the system.

If the patient has been accustomed to the use of hypodermic injections of morphine, hypodermic injections of water should be substituted in such cases.

Disease.—When a patient is suffering intense pain, opium is well borne, and must be given in large quantities; as, for example, to a person suffering from peritonitis. In cases of Bright's disease small doses may produce disproportionately great effects (p. 30). Hence in these cases the drug must not be given in large quantities, and the effect of each dose must be carefully watched.

Combination with other Drugs.—Chloroform sometimes modifies the action of opium, the chloroform narcosis passing into opium sleep, or the opium sleep may more resemble chloroform anæsthesia; hence the use of the two drugs together may be of advantage in certain operations, such as excision of the jaw, where it is difficult to continue to administer an anæsthetic (p. 176).

In some cases opium will not produce sleep even in large doses, and it is then advisable to combine it with a small dose of hydrate of chloral. Sometimes when opium has been given to produce sleep, and has only caused excitement, a few whiffs of chloroform will quiet the excitement, and the patient sinks into a quiet sleep.

Action of the Alkaloids of Opium.—The action of the opium alkaloids has not been fully made out, and various results have been obtained by different observers. It is certain, however, that morphine is in mammals almost entirely narcotic, whilst thebaine is purely convulsive. Between these extremes the other alkaloids probably range themselves in such an order that they may be divided into two sub-groups, the first of which may be called the morphine group, characterised by the prominence of the narcotic stage, while in the other, which may be called the codeine group, the tetanic stage is more prominent, and the narcosis less so. The members of these groups may be arranged as follows, so that each subsequent member has a weaker narcotic, and in the codeine group has at the same time a stronger convulsive, action :—

Morphine Group.	**Codeine Group.**
Morphine.	Papaverine.
Oxydimorphine.	Codeine.
	Narcotine.
	Thebaine.

The codeine group contains also hydrocotarnine, laudanosine, and cryptopine; but at present we know too little about them to assign a place in the group to them with certainty. The same may be said of codethyline. The codeine group becomes closely allied by its last members with the strychnine group.

[1] Diedrich, *op. cit.*

By the addition of **alcohol radicals** to morphine, substances to which the name of **codeines** has been given are produced. In some of these, such as codethyline, $C_{17}H_{18}NO_2(OC_2H_5)$, obtained from morphine by the introduction of ethyl, the narcotic action is diminished, whilst, according to Von Schroeder, the convulsive action is increased, in proportion to the number of atoms of hydrogen substituted by alcoholic radicals. If such be the case it is remarkable that by the addition of alcohol radicals to codeine or thebaine, their tetanising action should be altered into a paralysing action, methyl-thebaine producing paralysis like methyl-strychnine.[1]

In the alkaloids produced from morphine by **oxidation** (oxydimorphine and oxymorphine), their narcotic action is diminished, without the convulsant action being increased. Narceine has no apparent physiological action.[2]

Apomorphine has no narcotic action, but is an emetic acting on the vomiting centre in the medulla. In large doses it does not produce vomiting, but causes peculiar *manège* movements.

Morphine is said to be less constipating, less diaphoretic, and less nauseating than opium. Others affirm that opium is less nauseating. It is also said that opium quickens the pulse and raises the temperature at first, and then depresses both, while morphine depresses them both from the first.

The activity of morphine appears to depend on the presence of **hydroxyl** (HO) in it. When this is replaced by SO_4 its activity is greatly diminished.[3]

THERAPEUTICS. **General Uses.**—The general uses of opium in disease are (1) to lessen pain; (2) to produce sleep; (3) to lessen irritation in various organs.

Local Uses.—Opium is a local sedative, and is applied to the skin and irritable surfaces to relieve pain, thus:—

Fomentations or liniments containing it are used for inflamed joints, myalgia, lumbago, pleurisy, peritonitis, herpes zoster, etc.

Morphine dissolved in glycerine and spread on lint is used to allay pain in cancer; and, applied either by the endermic or hypodermic method, is useful in neuralgia. In many cases, however, the injection of pure water will relieve the pain, and hence part of the relief is probably due to the local irritation caused by the injection.

Opium lessens pain in conjunctivitis, earache, and toothache. In conjunctivitis it may be used in the form of liquid extract of opium dropped into the eye; and in toothache applied to the cavity of the tooth, as laudanum on a pledget of cotton wool. In the latter malady it is well to add a little sodium bicarbonate to neutralise the acid secretions in the mouth.

[1] Crum-Brown and Fraser, *Trans. Roy. Soc. of Edinburgh*, vol. xxv.
[2] Von Schroeder, *Archiv f. exper. Path. und Pharm.* p. 96, vol. xvii.
[3] Stolnikow, *Ztschr. f. Physiol. Chemie*, viii. p. 236.

Opium, used in the form of ointment of galls and opium, or of opium or morphine suppositories, relieves pain in the rectum caused either by ulcers, fissure, or hæmorrhoids.

Morphine subcutaneously injected has been used to produce local anæsthesia, as in evulsion of toe-nails.

Digestive System.—Opium often relieves salivation when due to reflex irritation in the mouth; if this fails, belladonna may succeed (p. 316).

It relieves the pain and vomiting due to irritability of the stomach, as in cancer and ulcer of the stomach, but if they are due to simple neuralgia of the stomach, small doses of arsenic are preferable.

In biliary colic opium or morphine is given either by the stomach or hypodermically. It may be used either with, or instead of, the inhalation of chloroform (pp. 176 and 177).

In diarrhœa opium is often useful when other astringents fail.

In dysentery it is generally combined with ipecacuanha.

In cholera opium is frequently given, but during the cold stage absorption is so slow that it has very little action. In these cases patients have been known to die from opium poisoning, as soon as partial recovery had taken place and absorption was re-established.

In peritonitis it is used both internally and externally. It should be given freely in doses of 1–2 gr. every four hours or oftener, and fomentations to the abdomen should be used externally. The action of the opium in this disease is twofold and possibly threefold:—(i.) It stops the peristalsis of the bowel. (ii.) It relieves pain. (iii.) It has possibly an action on the blood-vessels, lessening congestion in the manner already discussed (p. 771).

Very small doses (1 or even $\frac{1}{2}$ drop of tinct. opii in syrup or peppermint water) relieve certain forms of constipation, *e.g.* that caused reflexly by ovarian irritation. The opium probably acts on some reflex centre in the lumbar portion of the cord, and the minute dose probably just turns the reflex impulse from the inhibitory to the motor fibres of the splanchnic (p. 336). If these small doses are insufficient, the opium may be gradually increased until it is clear that it is increasing instead of lessening the constipation.

Respiratory Tract.—Opium will cut short catarrhal conditions of the respiratory tract, and 10 grains of Dover's powder at night is very useful when a "cold" is coming on. It is also used in phthisis to cut short an acute exacerbation due to taking cold (p. 288).

It relieves cough, and is best given in the form of linctus, so as to act locally as well as generally (p. 214). Applied locally it is used to relieve cough and pain on swallowing in tubercular disease of larynx, and a very good method is to mix $\frac{1}{6}$ to $\frac{1}{3}$ gr. of morphine with 1 gr. of starch or 3 grs. of subnitrate of bismuth, and blow the mixture well down into the larynx, the patient taking a deep

inspiration at the same time (*vide* p. 423). Opium is used in asthma and bronchitis, but one should be careful of its use when the secretion from the bronchial mucous membrane is profuse, for during sleep, when the respiratory and other centres are dulled by the opium, the fluid may increase to such an extent as to suffocate the patient, who is unable to expectorate it on awaking.

Circulatory System.—It is useful in cardiac dyspnœa with sleeplessness, and in angina pectoris it sometimes gives relief.

It is useful in hæmorrhages, especially those from the uterus. It may be combined with digitalis (tinct. opii ℥ xxx., tinct. digitalis, ℥ xxx.).

Genito-Urinary Tract.—Opium is used in diabetes to lessen the amount of urine and of sugar, but codeine (½-5 grs. ter die) is often used instead, the advantage it possesses being that it does not render the patient so drowsy. Opium allays irritability and pain, as in renal colic or irritable bladder.

Skin.—If the skin is too dry, Dover's powder will cause diaphoresis, and yet it will check the night sweats of phthisis.

For the probable cause of this peculiar action *vide* p. 389.

The two most important uses of opium and morphine are to **relieve pain** and **produce sleep.** In their power to relieve pain opium and morphine stand unrivalled, for they can be more generally applied than anæsthetics, such as chloroform. They frequently relieve pain even in doses too small to produce any other marked effect. When the pain is great, large doses may be required, but even then the other effects they would usually produce seem frequently to be counteracted by the pain, so that they relieve it without causing drowsiness or stupor. Opium and morphine are employed in neuralgias of various kinds such as tic, sciatica, or intercostal neuralgia, in dysmenorrhœa and in cancer. It is used to lessen both pain and inflammation in rheumatism and inflammatory conditions, such as pleurisy, pneumonia, peritonitis, cystitis. It is used to lessen pain and spasm in ordinary colic, lead colic, and in hepatic and renal colic.

Nervous System.—Opium or morphia is used to relieve sleeplessness due to almost any cause, but in cases of worry or worn-out conditions of the nervous system it is better to use bromide of potassium or chloral, as opium-taking becomes a habit. If these will not act, it may be necessary to use opium.

In fevers and delirium 10 ℥ tinct. opii may be given with ¼ gr. of tartar emetic, and the effect watched.

In mania, delirium tremens, and chorea, morphine may be given subcutaneously, but bromide of potassium and chloral are often preferable.

In intense melancholia subcutaneous injection of morphine may be used, but care must be taken not to establish the opium habit. Small doses of tincture of opium (5-10 min.) by the mouth are also very useful. Care should be taken to disguise the drug so

that the patient may not know what he is taking, and thus to prevent the risk of his taking opium afterwards at his own pleasure. Morphine is sometimes employed to prolong the anæsthesia of chloroform, as in excision of upper jaw, where it is inconvenient to continue the administration of chloroform.

In malarial poisoning there appears to be a hyper-sensibility of the vaso-motor centre, so that a draught of cold air blowing on the surface, slight gastric irritation, or even slight distension of the bladder, will cause contraction of the cutaneous vessels, and shivering, in one suffering from such poisoning. Opium appears to be useful in such conditions, probably by lessening the excitability of the vaso-motor centre.

Opium-eaters are frequently found in the fen districts, and in some forms of ague in the tropics opium has been of service when quinine has failed, and the two drugs combined have been still more serviceable than either alone.

Contra-indications :—

(1) Childhood, till the age of 5 years. Either abstain totally, or be most cautious in the use of opium and its preparations, as small doses act with disproportionate power.

(2) Blocking of the bronchial tubes by excessive secretion.

(3) Congestion of the brain, with suffused eyes and contracted pupils.

B.P. Rhœados Petala. RED POPPY PETALS.—The fresh petals of *Papaver Rhœas.* From indigenous plants.

CHARACTERS.—Of a scarlet colour and heavy poppy odour. On drying, they become dull in colour and lose their odour.

COMPOSITION.—They contain a red colouring matter soluble in water and spirit, but none of the alkaloids of opium. An alkaloid rhœadine which they do contain has no poisonous action.

USE.—They have little or no physiological action, and are only used for colouring.

PREPARATION.

B.P.	DOSE.
Syrupus Rhœados	1 fl. drm. or more.

U.S.P. Sanguinaria. SANGUINARIA. BLOODROOT.—The rhizome of *Sanguinaria canadensis,* collected in autumn.

CHARACTERS.—About two inches (5 centimetres) long, and two-fifths of an inch (10 millimetres) thick, horizontal, cylindrical, somewhat branched, faintly annulate, wrinkled, reddish-brown; fracture short, somewhat waxy, whitish, with numerous small, red resin-cells, or of a nearly uniform, brownish-red colour; bark thin; odour slight; taste persistently bitter and acrid.

COMPOSITION.—It contains an alkaloid—sanguinarine.

ACTION.—Sanguinarine appears to irritate the **intestinal canal,** producing vomiting and diarrhœa. Small doses after absorption **stimulate** the **medullary centres** for respiration and

circulation, and motor centres in the **brain** and spinal **cord.** They thus cause increased respiration, rapid pulse, and increased blood-pressure. Larger doses produce convulsions which are clonic in mammals and tetanic in frogs. In the latter they still persist after section of the cord. Large doses paralyse all these centres, and cause death by paralysis of respiration.

USES.—Except as a stimulant expectorant in chronic bronchitis it is rarely employed.

OFFICINAL PREPARATIONS.

U.S.P.	DOSE.
Acetum Sanguinariæ	15-30 min.
Extractum Sanguinariæ Fluidum	1-5 min.
Tinctura Sanguinariæ	1-3 fl. drm.

U.S.P. Chelidonium. CHELIDONIUM. CELANDINE.—*Chelidonium majus.*

CHARACTERS.—Root several-headed, branching, red-brown; stem about twenty inches (50 centimetres) long, light green, hairy; leaves about six inches (15 centimetres) long, petiolate, the upper ones smaller and sessile, light green, on the lower side glaucous, lyrate-pinnatifid, the pinnæ ovate-oblong, obtuse, coarsely crenate or incised, and the terminal one often three-lobed; flowers in small, long-peduncled umbels with two sepals and four yellow petals; capsule linear, two-valved and many-seeded. The fresh plant contains a saffron-coloured milk-juice and has an unpleasant odour and acrid taste.

DOSE.—10 to 30 gr.

COMPOSITION.—It contains two alkaloids—chelidonine and chelerythrine—the latter being supposed to be identical with sanguinarine. Chelerythrine, however, as obtained from chelidonium, has no tetanising action, but produces **paralysis** and loss of reflex action (Schroff, jun.). Chelidonine has a bitter, acrid taste, but appears to have little physiological action.

USES.—Externally the fresh juice acts as a local irritant, and is used to destroy corns or warts, and to lessen itching in skin diseases. When given internally in large doses it excites violent purging. It was formerly much used in jaundice. It appears to act as a bitter tonic and alterative, and is employed in phthisis and scrofula.

CRUCIFERÆ.

B.P. Sinapis. MUSTARD.—The seeds of *Sinapis niger* and *Sinapis alba.* Also the seeds reduced to powder, mixed.

U.S.P. Sinapis Alba. WHITE MUSTARD.—The seed of *Sinapis alba.*

U.S.P. Sinapis Nigra. BLACK MUSTARD.—The seed of *Sinapis nigra.*

The seeds of black mustard are very small, round, and brownish-black outside; those of the white are larger and yellow. Both are yellow inside.

CHARACTERS OF THE POWDER.—Greenish-yellow, of an acrid, pungent taste, scentless when dry, but exhaling when moist a pungent, penetrating, peculiar odour.

DOSE.—As an emetic, from one teaspoonful to a tablespoonful of mustard flour, mixed with a little water.

ADULTERATIONS.—Starch.

TEST.—A decoction cooled is not made blue by tincture of iodine.

COMPOSITION.—The pungency of the moist powder is due to oil of mustard, but this does not exist in the seeds or fresh powder. Both black and white mustard contain a crystallisable substance, called in the black sinigrin, and in the white sinalbin, and an albuminous body myrosine. When moistened, both sinigrin and sinalbin are split up by the myrosine, which acts as a ferment, and yield a volatile oil. This is not quite the same in the two mustards, that from the black being more pungent; but the oil from both possesses powerful vesicating properties. The action of myrosine as a ferment is destroyed by a heat of 60° C.; so mustard poultices should not be made with boiling water. Black mustard contains less myrosine than white, too little, indeed, to decompose the sinigrin completely, so that its pungency may be increased by admixture with white, as directed by the B.P., and as found in ordinary table mustard. Both mustards also contain a fixed oil.

PREPARATIONS (of Black Mustard).

B.P.	U.S.P.
Cataplasma Sinapis.	Charta Sinapis.
Charta Sinapis.	Oleum Sinapis Volatile.
Oleum Sinapis.	

Charta Sinapis, B. and U.S.P. MUSTARD PAPER.—Consists in the B.P. of black mustard in powder, mixed with solution of gutta-percha, so as to make it stick to the paper upon which it is spread, and then dried. In the U.S.P. the fixed oil is removed from the mustard by percolation from benzin before it is spread on the paper. It is used as a substitute for a mustard poultice by immersing it for a few seconds in tepid water and then applying it to the skin. Rigollot's mustard leaves are more frequently used than those of the Pharmacopœia. They cause, as a rule, sharper pain than the ordinary mustard poultice, and can rarely be borne as long. They are, however, more convenient and readily applied, and in cases of narcotic poisoning the sharp pain they cause renders them preferable to the ordinary poultice.

B.P. Cataplasma Sinapis. MUSTARD POULTICE.—Mix linseed-meal (2½ ounces) gradually with boiling water (10 fluid ounces), and add powdered mustard (2½ ounces), with constant stirring. The mixture of linseed-meal and water gets somewhat cooled before the mustard is added, and so the formation of the volatile oil is not completely prevented; but it would increase the irritant power of the poultice if the mustard were mixed with a little cold water a few minutes before adding it to the linseed.

Oleum Sinapis, B.P.; Oleum Sinapis Volatile, U.S.P. OIL OF MUSTARD, B.P.—The oil distilled with water from the seeds of black mustard, *Sinapis nigra*, after the expression of the

fixed oil, B.P. A volatile oil obtained from black mustard by maceration with water, and subsequent distillation, U.S.P. It is sulphocyanide of allyl (C_3H_5, CNS).

CHARACTERS.—Colourless or pale yellow. Has an intensely pungent, acrid odour, and burning taste. Soluble in alcohol and ether, slightly in water.

ACTION.—Applied to the skin, it produces almost instant vesication.

PREPARATIONS.

B.P.	U.S.P.
Linimentum Sinapis Compositum. 1 volume in 41.	Linimentum Sinapis Compositum. 3 parts by weight in 100, 1 volume in 42.

Linimentum Sinapis Compositum. COMPOUND LINIMENT OF MUSTARD. —Volatile oil of mustard, 3 ; extract of mezereon, 2 ; camphor, 6 ; castor oil, 15 ; alcohol up to 100 parts by weight, U.S.P. The liniment of the B.P. is slightly stronger.

PHYSIOLOGICAL ACTION.—Locally applied to the **skin** or mucous membranes, mustard acts as a stimulant causing warmth, redness, pain passing off if the application is short, but if the action is prolonged vesication is produced. **Internally,** it is a prompt direct emetic (a tablespoonful of mustard in a tumbler of hot water).

THERAPEUTICS.—Externally it is used as a **counter-irritant** in myalgia, lumbago, headache, in the form of poultice or paper to the back of neck ; in congestion of the brain, apoplexy, and opium poisoning, in the form of poultices or leaves to the calves of the legs and other parts of the body. It is applied to the chest in catarrh, bronchitis, congestion of the lung, and catarrhal pneumonia. In phthisis, mustard leaves applied to the chest are useful to check the spread of consolidation when the patient has taken cold. It is applied to the spine for the relief of pains in the loins, and loss of power in walking accompanying spinal irritation. For this purpose a very useful application is the linimentum sinapis compositum sprinkled on some spongio-piline. Mustard baths to the feet are used in amenorrhœa (p. 398) and sleeplessness (p. 166).

When Rigollot's leaves are used, the pain they cause in persons with delicate skins renders them almost unbearable, and in such cases two or three layers of damped muslin should be placed next to the skin, to modify their action.

With the leaves of the B.P. it is advisable to use one layer of muslin to prevent the mustard coming off the leaf and sticking to the skin.

Internally mustard is used as a condiment, to increase the appetite by stimulating the mucous membrane. One important use is that of an **emetic** in indigestion or narcotic poisoning. In irritant poisoning, *e.g.* by croton oil, it is best given in linseed tea or thin gruel.

B.P. Armoraciæ Radix. Not in **U.S.P.** HORSE-RADISH ROOT. The fresh root of *Cochlearia Armoracia*, cultivated in Britain.

FIG. 142.—Horse-radish Root

CHARACTERS.—A long, cylindrical, fleshy root, internally white. It has a pungent taste and smell. Aconite root, which has been mistaken for it, is short, and conical, and has a numbing instead of a pungent taste.

COMPOSITION.—A volatile oil identical with that of black mustard is developed in it after it has been cut.

PREPARATION.

B.P.	DOSE.
Spiritus Armoraciæ Compositus.....	1–2 fl. drm.

B.P. Spiritus Armoraceæ Compositus. COMPOUND SPIRIT OF HORSE-RADISH.—Sliced horse-radish, dried orange-peel, and bruised nutmeg are mixed with diluted proof-spirit and distilled.

THERAPEUTICS.—Horse-radish is chiefly used as a condiment in cases of deficient digestion; also as a masticatory in hoarseness. It is sometimes used in atonic dyspepsia, and as a diuretic in dropsies. The spirit is used as a pleasant vehicle.

VIOLACEÆ.

U.S.P. Viola Tricolor. VIOLA TRICOLOR. [PANSY.]—The wild-grown, flowering herb of *Viola tricolor.*

CHARACTERS.—Stem angular and nearly smooth; leaves alternate, petiolate, ovate or oblong, crenate, with leaf-like, pinnatifid stipules; flowers with an obtuse spur, and the variegated petals shorter or longer than the calyx; inodorous; taste somewhat bitter and acrid.

COMPOSITION.—It contains a little violine, a substance similar to emetine, and having an emeto-cathartic action.

USES.—It is used externally in the form of an ointment or a poultice in eczema and impetigo. It is sometimes given internally in bronchitis.

DOSE.—15 to 17 gr. (1-5 Gm.) in decoction.

LINACEÆ.

Lini Semina, B.P.; Linum, U.S.P. LINSEED, B. and U.S.P. **Flax Seed, U.S.P.** The seed of *Linum usitatissimum.*

CHARACTERS.—About one-sixth of an inch long, oval, pointed, flattened, smooth, shining, brown externally, yellowish-white within.

COMPOSITION. — The covering of the seeds contains much mucilage, and the seed itself contains nearly one-third of its weight of oil. The oil is obtained by expression, and the remaining cake when powdered forms linseed-meal.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Farina Lini		Oleum Lini.
Infusum Lini	2 fl. oz. ad lib.	
Oleum Lini		

B.P. Infusum Lini. LINSEED TEA.—Infuse 160 grains of linseed, with 60 grains of fresh liquorice-root sliced, in 10 ounces of water for four hours and strain.

ACTION.—Linseed tea is a most useful **demulcent** in coughs, depending in whole or in part on irritation of the pharynx and upper part of the respiratory passages. It may be kept warm all night in a baby's food-warmer, and a sip taken whenever the patient awakes. This often prevents troublesome paroxysms of coughing, and enables the patient to obtain a fair night's rest.

USE.—Internally it is used as a demulcent drink in enteritis, diarrhœa, dysentery, catarrh, and irritation of urinary organs, also in phosphorus poisoning.

B.P. Lini Farina. LINSEED MEAL.—The cake of linseed from which the oil has been pressed reduced to powder. It is used not only in the cataplasma lini but also in the cataplasma carbonis, conii, sinapis, and sodæ chloratæ.

B.P. Cataplasma Lini. LINSEED POULTICE.—Mix a quarter of a pound (about 4 tablespoonfuls) of linseed-meal gradually with half a pint of boiling water and add a tablespoonful of olive-oil with constant stirring.

USES.—Linseed meal forms an excellent vehicle for applying warmth and moisture, and is used in the form of poultices in inflammation of both superficial and deep-seated parts (p. 412).

Oleum Lini. B. and U.S.P. LINSEED OIL. OIL OF FLAX SEED, U.S.P.—A fixed oil expressed without heat from linseed.

CHARACTERS.—Viscid, yellow, with a faint odour, and oleaginous taste. It thickens, and finally solidifies on exposure to air.

USES.—It is sometimes employed as a soothing application to burns, scalds, and eczematous eruptions, either alone or with lime-water (p. 581). It is sometimes added to purgative enemata and has been recommended as a cure for piles in the dose of two ounces of the fresh oil morning and evening.[1]

GERANIACEÆ.

U.S.P. Geranium. GERANIUM [CRANESBILL]. The rhizome of *Geranium maculatum.*

CHARACTERS.—Horizontal, cylindrical, two to three inches (5 to 7 centimetres) long; half an inch (12 millimetres) or less thick;

[1] *United States Dispensatory*, p. 1017.

tuberculated, longitudinally wrinkled, dark brown; fracture short, pale red-brown; bark thin; wood-wedges yellowish, small, forming a circle near the cambium line; medullary rays broad; central pith large; rootlets thin, fragile; inodorous; taste astringent.

OFFICINAL PREPARATION.

	DOSE.
Extractum Geranii Fluidum	½ fl. drm. to 1 fl. drm.

COMPOSITION.—It contains a considerable amount of tannic and gallic acids.

USES.—It is a mild and not disagreeable **astringent,** especially useful for children. It is used internally for diarrhœa, and is employed also as an astringent gargle in sore throat and as an injection in gonorrhœa and gleet.

POLYGALACEÆ.

Senegæ Radix, B.P.; Senega, U.S.P. SENEGA ROOT.—The dried root of *Polygala Senega.* North America.



FIG. 143.—Senega.

CHARACTERS.—A knobby rootstock, with spreading, tortuous rootlets, twisted and *keeled.*

ADULTERATIONS.—Ginseng and other roots, detected by absence of keel.

COMPOSITION.—The active principle which is contained in the cortex, is called senegin or polygalic acid. It appears to be identical with saponin obtained from *Saponaria officinalis,* which is a glucoside splitting up when boiled into grape-sugar and sapogenin. It is a white powder easily soluble in hot water and alcohol, forming a soapy emulsion when mixed with boiling water even in small quantities.

PREPARATIONS.

B.P.	DOSE.
Infusum Senegæ	1-2 fl. oz.
Tinctura Senegæ	½-2 fl. drm.

U.S.P.

Abstractum Senegæ	5-10 gr. (0·3-0·6 Gm).
Extractum Senegæ Fluidum	10-20 min. (0·6-1·25 c.c.)
Syrupus Senegæ	1-2 fl. dr (3·75-7·5 c.c.)
Syrupus Scillæ Compositus	For children 10 min. to 1 fl.drm. (0·6-3·75 c.c.) Expectorant for adults 20-30 min. (1·25-1·9 c.c.)

ACTION AND USE.—It is employed as a **stimulating expectorant,** diuretic and diaphoretic. The indications for its administration as an expectorant are when the power to expectorate is small, but the quantity of expectoration is abnormally large, and it is more or less purulent in character, as in the second stage of acute bronchial catarrh, or pneumonia in the stage of resolution. When the expectoration is tough and scanty, senega is of little use.

It is also used in chronic pneumonia, and chronic bronchitis, and in dropsy dependent on renal disease. It is usually combined with other expectorants and diuretics. Its taste is to many very disagreeable, but spirit of chloroform both makes it more agreeable and tends to lessen cough. It has been recommended in palpitation due to **aortic disease** (pp. 275 and 276), and also in amenorrhœa. (*Vide* also p. 832.)

KRAMERIÆ.

Krameriæ Radix, B.P.; Krameria, U.S.P. RHATANY ROOT.—The dried root of *Krameria triandra*, B. and U.S.P., and of *Krameria tomentosa*.

CHARACTERS.—About an inch thick, knotty above, and branched below, the branches are long, often broken or torn, brownish-red and rough externally, reddish-yellow internally, strongly astringent.

The root of *Krameria tomentosa* (Savanilla Rhatany), U.S.P., is less knotty and more slender, and has dark purplish brown bark.

COMPOSITION.—The bark contains about 20 per cent. of a kind of tannin called Ratanhia-tannic acid, a red matter, Ratanhia-red, and a neutral substance, Ratanhin.

PREPARATIONS.

B.P.	DOSE.
Extractum Krameriæ	5-20 gr.
Infusum Krameriæ	1-2 fl. oz.
Pulvis Catechu Compositus	
Tinctura Krameriæ	½-2 fl. dr.

U.S.P.			
Extractum Krameriæ			5-20 grs. (0·3-1·3 Gm.)
,,	,,	Fluidum	5 min.-1 fl. drm. (0·3-3·75 c.c.)
Syrupus	,,		1 fl. oz. (30 c.c.)
Tinctura	,,		½-2 fl. drm. (1·9-7·5 c.c.)
Trochisci	,,		

ACTION.—It is strongly **astringent.**

USES.—The powder is used as a dentifrice when the gums are spongy and bleed easily. The infusion or tincture is employed in bleeding from the nose, mercurial affections of the mouth, relaxed sore throat, leucorrhœa, prolapsus ani. Internally it is given in diarrhœa, and hæmorrhage from the kidneys or genito-urinary passages.

SAPINDACEÆ.

U.S.P. Guarana. GUARANA.—A dried paste prepared from the crushed or ground seeds of *Paullinia sorbilis*.

CHARACTERS.—Sub-globular, or elliptic cakes, or cylindrical sticks, hard, dark reddish-brown; fracture uneven, somewhat glossy, showing fragments of seeds invested with a black testa; odour slight, peculiar, resembling chocolate; taste astringent, bitter; it is partly soluble in water, and in alcohol.

PREPARATION.

	DOSE.
Extractum Guaranæ Fluidum	15 min. to 1 fl. oz.

COMPOSITION.—It contains four or five per cent. of caffeine (p. 797) and a considerable amount of tannic acid, and it is upon these that its medicinal value depends.

USES.—It is chiefly used to cut short attacks of sick headache. It may be given in doses of one or two drachms of the powder, mixed with hot water, or as fluid extract, when the headache is coming on.

ERYTHROXYLACEÆ.

U.S.P. Erythroxylon. ERYTHROXYLON [COCA.]—The leaves of *Erythroxylon Coca*.

CHARACTERS.—Oval or obovate-oblong, two to three inches (50 to 75 millimetres) long, short-petiolate, entire, rather obtuse or emarginate at the apex, reticulate on both sides, with a prominent midrib, and, on each side of it, a curved line running from base to apex; odour slight and tea-like; taste somewhat aromatic and bitter.

PREPARATION.

	DOSE.
Extractum Erythroxyli Fluidum	1 fl. drm. to 4 fl. drm.

COMPOSITION.—This drug contains the alkaloids cocaine and hygrine and a volatile constituent which gives a pleasant fragrance to the fresh leaves. Different specimens of the leaves vary greatly in their strength.

ACTION.—Cocaine is a powerful **local anæsthetic**. When applied to the tongue it destroys both taste and tactile sensibility, so that salt and sugar cannot be distinguished, nor the prick of a pin felt. In the eye it causes local anæsthesia along with dilatation of the pupil, paralysis of accommodation, slight lachrymation, and enlargement of the palpebral fissure.[1] When injected into the back of the orbit it causes protrusion of the eyeball. Its effects appear to be due to stimulation of the peripheral ends of the sympathetic. Subcutaneous injection also produces

[1] Jessop, *Practitioner*, January 1885.

local anæsthesia at the point of application, so that subsequent irritation at that spot produces no sensation in man and no reflex action in animals. When taken **internally** it appears to have, in small doses, a stimulant, and, in large doses, a paralysing action on the **nerve centres** somewhat like that of caffeine. It affects first the cerebral hemispheres, next the medulla, and afterwards the spinal cord. In small doses it is said to **lessen fatigue,** and enable the Indians in Peru to make long marches, and a similar result has been obtained in trials upon soldiers in Germany. **Larger doses** cause fulness in the head, weariness, slight deafness, loss of memory, and inability to control ideas. It appears sometimes to cause restlessness, singing in the ears, giddiness, headache, and delirium.

In animals large doses appear to affect specially the **semicircular canals**, possibly by an anæsthetic action upon the nerves connected with them. This is shown by constant movement of the head in mammals, disturbances of equilibrium, loss of co-ordination, and rotatory convulsions and opisthotonos. The **convulsions** are of cerebral origin (p. 157), and cease when the spinal cord is divided. The motor columns of the **spinal cord** appear to be unaffected, but the sensory columns are paralysed. In its action on respiration and circulation cocaine, to a certain extent, resembles atropine, and it does so also in its action on the pupils, intestinal movements, and salivary and sweat glands. The **respiration** is greatly increased at first, afterwards diminished, and death occurs from respiratory paralysis. Small doses quicken the **pulse** and raise the **blood-pressure.** Large doses slow the pulse and lower the blood-pressure. The quickness of the pulse appears to be due to paralysis of the vagus, and the action of cocaine on both pulse and blood-pressure is very like that of atropine. Small doses increase, large ones paralyse, the intestinal movements. The secretion of **saliva** and **sweat** is diminished. The **urine** does not appear to be affected. The **temperature** is generally raised.

USES.—The expectations of practical utility of cocaine, founded on a knowledge of physiological action which Rossbach [1] expressed, have been completely fulfilled, and it now bids fair to replace as a local anæsthetic the use of chloroform in many minor operations. Its local anæsthetic action was first observed by Niemann. Its actual introduction into practice we owe to Koller. A 4 per cent. solution dropped into the eye is sufficient to produce local anæsthesia, so that operations for cataract or squint can be readily performed, and foreign bodies extracted from the eye, under its influence. A 20 per cent. solution applied once or twice to the nasal mucous membrane at intervals of three or four minutes causes such complete anæsthesia that the application of the galvano-cautery is not felt. A similar effect is produced on the soft palate

[1] Nothnagel and Rossbach, *Arzneimittellehre*, 5th edition.

and larynx, and the solution may be applied to facilitate the use of the laryngoscope and lessen pain and spasm in operations on the larynx. It has been applied with benefit to the interior of the nose in acute coryza, nasal polypus, and hay fever. It is useful in producing local anæsthesia of the uterus and rectum in operations on these parts; in vaginismus and in pruritus of the anus and valva. Internally cocaine or coca is useful as a tonic, especially in debility with nervousness, and in mental diseases accompanied by depression. It may be given in the form of the fluid extract either alone or with a glass of wine. A non-officinal wine made from the leaves is also a useful tonic.

MALVACEÆ.

U.S.P. Gossypii Radicis Cortex. COTTON ROOT BARK.—The bark of the root of *Gossypium herbaceum* and of other species o gossypium.

CHARACTERS.—Thin flexible bands or quills, brownish-yellow outside, whitish and silky inside, no smell, taste faintly acrid and astringent.

COMPOSITION.—It contains a colourless acid resin becoming red on exposure.

PREPARATION.	DOSE.
Extractum Gossypii Radicis Fluidum	½-1 fl. dr. (1·9-3·75 c.c.)

ACTION AND USES.—It is said to cause contraction of the **uterus,** and is used instead of ergot. It may be given either as the officinal fluid extract or as a decoction made by boiling 4 oz. of the bark in a quart of water down to a pint. Of this a wineglassful (60 c.c.) is given every 20 or 30 minutes.

U.S.P. Oleum Gossypii Seminis. COTTON SEED OIL.—A fixed oil, expressed from the seed of *Gossypium herbaceum* and of other species of gossypium and subsequently purified.

CHARACTERS.—A bright, pale yellow, oily liquid, odourless, having a bland nut-like taste and a neutral reaction. Sp. gr. 0·920 to 0·930. It is only slightly soluble in alcohol, but readily so in ether. When cooled to near 2° C. (35·6° F.) it begins to congeal. Concentrated sulphuric acid instantly renders it dark reddish-brown.

USES.—It is a bland oil very much like olive oil, and answers perfectly well most purposes for which olive oil is generally used except for making lead plaster. A great deal of the oil exported from France and Italy under the name of olive oil is really cotton-seed oil either alone or mixed with a proportion of olive oil. Eighty-eight per cent. of the cotton-seed oil exported from New Orleans in 1880 was sent to the Mediterranean.

OFFICINAL PREPARATIONS.

U.S.P.

Linimentum Ammoniæ.
,, Calcis.
,, Camphoræ.
,, Plumbi Subacetatis.

B.P. Gossypium. COTTON WOOL.—The hairs of the seed of various species of gossypium carded.

U.S.P. Gossypium. COTTON. (Purified Cotton. Absorbent Cotton.)—The hairs of the seed of *Gossypium herbaceum* and other species, freed from adhering impurities and deprived of fatty matter.

PREPARATION.—It is made by boiling the raw cotton in a dilute alkaline solution, such as a 5 per cent. solution of caustic potash or soda. The alkali unites with the fatty matter of the cotton to form a soap, which is removed by repeated washings, in the course of which chlorinated lime and dilute hydrochloric acid are used as well as water.

TEST.—When thrown upon water it should immediately absorb the latter and sink, and the water should not acquire either an acid (no hydrochloric acid) or alkaline reaction.

PREPARATIONS.

B.P.	U.S.P.
Pyroxylin (Gun Cotton).	Pyroxylinum (Gun Cotton).

USES.—Cotton wool is employed as a local application to the skin in cases of burns and erysipelas, to exclude external irritation and protect the part from cold. Cotton wool is also used to surround gouty or rheumatic joints.

A pledget of cotton wool placed in the ears tends to prevent sore throat. The explanation of this seems to be that catarrh may result reflexly from irritation of the auricular branch of the vagus. (cf. Rossbach's experiments, p. 216, where congestion of the trachea followed irritation of the abdomen by the application of ice.)

When subjected to heat, so as to destroy any adherent germs, it is used in experiments on antiseptics (p. 72) to plug the orifice of the test-tubes and prevent the accidental entrance of germs. With a somewhat similar object it has been used as a dressing to wounds, from which it excludes the germs which might cause pyæmia, erysipelas, etc. As a dressing the absorbent cotton of the U.S.P. appears much preferable to the crude cotton wool. It may be impregnated with various antiseptics and deodorising substances, such as iodine, picric acid, salicylic acid, or benzoic acid. Some of these form useful applications to the os uteri to destroy fœtor and induce healthy action.

Pyroxylin, B.P.; Pyroxylinum, U.S.P. GUN COTTON.—Prepared by the action of sulphuric and nitric acids on cotton.

TEST.—Readily soluble in a mixture of ether and rectified spirit; leaves no residue when exploded by heat.

USE.—To prepare collodium (collodion), B. and U.S.P.

Collodium. B. and U.S.P. COLLODION. A solution of pyroxylin in ether and alcohol.

CHARACTERS.—A colourless highly inflammable liquid with ethereal odour, which dries rapidly upon exposure to the air, and leaves a thin transparent film, insoluble in water or rectified spirit. The great inflammability of its vapour must be carefully remembered. After successfully completing the operation of ovariotomy, a surgeon covered the wound with a layer of collodion. In order to inspect it more closely he brought a light near, when the ethereal vapour caught fire, and the patient died from the effects of the burns which she received (Binz).

PREPARATIONS.

B.P.	U.S.P.
Collodium Flexile.	Collodium cum Cantharide.
	,, Flexile.
	,, Stypticum.

B. and U.S.P. Collodium Flexile. FLEXIBLE COLLODION. Collodion mixed with Canada balsam and castor oil.

USES.—Collodion applied to the skin acts both as a protective, and also, through its contraction, exerts a gentle pressure on the part, and is hence applied to cut surfaces, chapped nipples, and to check hæmorrhage from leech bites. The flexible collodion does not crack, and therefore is more useful as a protective, but it exerts less pressure than ordinary collodion.

U.S.P. Collodium cum Cantharide. CANTHARIDAL COLLODION.

PREPARATION.—By dissolving a chloroform extract of cantharides in flexible collodion.

ACTION.—When painted on the skin it acts as a rapid and powerful vesicant. If covered immediately with oiled silk, so as to prevent the evaporation of the ether, it is said to act more rapidly.

USES.—*Vide* Cantharides (p. 1002).

U.S.P. Collodium Stypticum. STYPTIC COLLODION.

PREPARATION.—By dissolving tannin in a mixture of alcohol, ether and collodion (20 parts tannin in 100).

USES.—To stop bleeding from leech bites, abrasions, and wounds. When painted over the bleeding surface the tannin coagulates the blood and lymph; and this, with the collodion, forms a film over the surface which prevents further bleeding and protects the raw surface from exposure to air or from accidental irritation.

U.S.P. Althæa. ALTHÆA. [MARSHMALLOW].—The root of *Althæa officinalis.*

CHARACTERS.—In cylindrical or somewhat conical pieces, from three to six inches (7 to 15 centimeters) long, about half an inch (12 millimeters) in diameter, deeply wrinkled; deprived of the brown, corky layer and small radicles; externally white, marked with a number of circular spots, and of a somewhat hairy appearance from the loosened bast-fibres; internally whitish and fleshy. It breaks with a short, granular and mealy fracture, has a faint, aromatic odour, and a sweetish, mucilaginous taste.

PREPARATION.

	DOSE.
Syrupus Althææ	1-4 fl. dr.

COMPOSITION.—It contains some 35 per cent. each of vegetable mucus and starch.

USES.—It is bland and unirritating, and a useful **demulcent** in sore throat, coughs, or intestinal irritation. An ointment made by boiling the cut fresh leaves with lard for half an hour, and then straining, has proved successful in palmar psoriasis after other means failed.[1]

AURANTIACEÆ.

U.S.P. Aurantii Flores. ORANGE FLOWERS.—The partially expanded fresh flowers of *Citrus vulgaris* and *Citrus aurantium*. They may be preserved by mixing them well with half their weight of chloride of sodium, pressing them into a jar, and keeping in a cool place.

CHARACTERS.—Fragrant and somewhat bitter.

PREPARATION.

Aqua Aurantii Florum.

U.S.P. Oleum Aurantii Florum. OIL OF ORANGE FLOWERS, OIL OF NEROLI.—A volatile oil distilled from fresh orange flowers.

CHARACTERS. — Yellowish or brownish; has fragrant odour of orange flowers, and aromatic, somewhat bitter taste.

COMPOSITION.—It consists chiefly of a hydrocarbon and a little neroli camphor.

PREPARATION.

Spiritus Odoratus. U.S.P.

USE.—As a **flavouring** matter.

Aqua Aurantii Floris, B.P.; Aqua Aurantii Florum, U.S.P. ORANGE FLOWER WATER.—The distilled water of the flowers of the bitter orange tree (*Citrus bigaradia*), and of the sweet orange tree (*Citrus aurantium*). Prepared mostly in France.

CHARACTERS.—Nearly colourless; has the fragrant odour of the flowers.

[1] Berry, *Practitioner*, vol. xxxi. p. 346.

IMPURITIES.—Lead from the vessels in which it has been kept.

TEST.—It should not be coloured by sulphuretted hydrogen.

COMPOSITION.—It contains a volatile oil (Oil of Neroli).

PREPARATION.

B.P.	DOSE.
Syrupus Aurantii Floris	1-2 fl. dr.

U.S.P	
Syrupus Aurantii Florum	1-2 fl. dr. (4-8 cc.)

B.P. Aurantii Fructus. BITTER ORANGE.—The ripe fruit of the *Citrus vulgaris* (Risso), *Citrus bigaradia* (Duhamel). Imported from the South of Europe.

Aurantii Cortex, B.P.; Aurantii Amari Cortex, U.S.P. BITTER ORANGE PEEL.—The dried outer part of the rind of the ripe bitter orange.

CHARACTERS.—Thin strips of dark orange colour, with a fragrant odour and an aromatic bitter taste. It should be nearly free from the white part of the rind.

COMPOSITION.—The inner part of the rind is white, spongy, and useless; the outer part is yellow when fresh, but brownish green when dried, and contains a fragrant volatile oil, a bitter neutral principle hesperidin, and a small quantity of some sort of tannin.

PREPARATIONS.

B.P.	DOSE.
Of the fresh peel—	
Tinctura Aurantii Recentis	1-2 fl. dr.
Vinum Aurantii	
Of the dried peel—	
Infusum Aurantii (½ oz. in ½ pint)	1-2 fl. oz.
,, ,, **Compositum**	1-2 fl. oz.
,, Gentianæ Compositum	1-2 fl. oz.
Mistura Gentianæ	1-2 fl. oz.
Spiritus Armoraciæ Compositus	
Syrupus Aurantii (Tinct. 1, Syrup 7)	
Tinctura Aurantii	1-2 fl. dr.
,, Cinchonæ Composita	
,, Gentianæ Composita	½-2 fl. dr.

U.S.P.	
Extractum Aurantii Amari Fluidum	2-4 fl. dr. (8-15 cc.)
Tinctura Aurantii Amari	1-2 fl. dr. (4-8 cc.)

B.P. Infusum Aurantii Compositum. COMPOUND INFUSION OF ORANGE PEEL.—Bitter orange peel, ½ oz.; fresh lemon peel, 60 gr.; cloves, bruised, 30 gr.; boiling distilled water, 10 fl. oz.

U.S.P. Aurantii Dulcis Cortex. SWEET ORANGE PEEL.—The rind of the fruit of *Citrus aurantium*.

CHARACTERS.—Closely resembling bitter orange peel, but having an orange yellow colour. It has a sweetish fragrant odour and an aromatic slightly bitter taste.

PREPARATIONS.	DOSE.
Syrupus Aurantii	
Tinctura Aurantii Dulcis	

USES.—The preparations of oranges are used almost entirely as **flavouring** vehicles. The rind is an aromatic stomachic, and is used with other bitters in the treatment of dyspepsia.

U.S.P. Oleum Aurantii Corticis. OIL OF ORANGE PEEL.—A volatile oil extracted by mechanical means from fresh orange peel.

PREPARATION.—It is prepared from the outer part of the rind by expression; by putting it in hot water and skimming off the oil; or by rubbing it in a kind of bowl lined with short spikes in the same way as oil of lemons.

CHARACTERS.—Pale yellow, has smell of oranges, an aromatic somewhat bitter taste. By keeping it becomes thicker, and gets a turpentine-like taste. This may be prevented by mixing the fresh oil with 5 per cent of alcohol and decanting from the sediment.

COMPOSITION.—Contains two camphenes and a glucoside hesperidin.

OFFICINAL PREPARATIONS.	DOSE.
Elixir Aurantii	2-8 fl. dr. (4-30 cc.)
Spiritus Aurantii	2-4 fl. dr. (4-15 cc.)
Spiritus Myrciæ	Used as perfume.

ACTION AND USE.—Externally it is **rubefacient.** Internally, in large doses, an irritant poison. It is used as a **flavouring** matter.

U.S.P. Elixir Aurantii. ELIXIR OF ORANGE (Simple Elixir).—Oil of orange, 1; cotton, 2; sugar, in coarse powder, 100; alcohol and water, of each a sufficient quantity to make 300 parts. Mix alcohol and water in the proportion of 1 part of alcohol to 3 parts of water. Add the oil of orange to the cotton in small portions at a time, distributing it thoroughly by picking the cotton apart after each addition; then pack tightly in a conical percolator and gradually pour on the mixture of alcohol and water until 200 parts of filtered liquid are obtained. In this liquid dissolve the sugar by agitation, without heat, and strain.

USE.—To **cover** the **taste of drugs** and render them agreeable to the palate. By mixing tinctures and liquid extracts with simple elixir, preparations are obtained which are both palatable and efficient.

U.S.P. Oleum Bergamii. OIL OF BERGAMOT.—A volatile oil extracted by mechanical means from the rind of the fresh fruit of *Citrus Bergamia var. vulgaris.*

CHARACTERS.—A greenish or greenish-yellow, thin liquid of a peculiar, very fragrant, odour, an aromatic, bitter taste, and a slightly acid reaction. Sp. gr. 0·860 to 0·890. It is soluble in all proportions in alcohol and in glacial acetic acid.

USE.—In flavouring.

PREPARATION.

Spiritus Odoratus. PERFUMED SPIRIT (Cologne Water).—Oil of bergamot, 16; oil of lemon, 8; oil of rosemary, 8; oil of lavender flowers, 4; oil of orange flowers, 4; acetic ether, 2; water, 158; alcohol, 800.

USES.—For perfuming lotions. When bathed on the temples or forehead and evaporated quickly by fanning the face, it is useful

in headaches or tendency to faintness. Eau de Cologne is not unfrequently taken as a stimulant by ladies, who have no idea that it contains alcohol.

Limonis Cortex, B. and U.S.P. LEMON PEEL.—The outer part of the rind of the fresh fruit of *Citrus limonum*. Southern Europe and West Indies.

CHARACTERS.—Like those of orange peel, but the colour is a deep lemon yellow.

COMPOSITION.—Similar to orange peel.

PREPARATIONS.

B.P.	DOSE.
Infusum Aurantii Compositum	1-2 fl. oz.
,, Gentianæ Compositum	1-2 fl. oz.
Oleum Limonis	1-5 min.
Syrupus ,,	1-2 fl. dr. or more.
Tinctura ,,	1-2 fl. dr.

U.S.P.	
Oleum Limonis	1-5 min.
Spiritus ,,	
Syrupus ,,	1-2 fl. dr. or more.
Mistura Potassii Citratis	4-8 fl. dr. (15-30 cc.)

Oleum Limonis, B. and U.S.P. OIL OF LEMONS.—A volatile oil expressed or distilled (B.P.), or extracted by mechanical means (U.S.P.), from fresh lemons.

CHARACTERS.—A pale yellow liquid, having the fragrant odour of lemon; an aromatic, somewhat bitterish taste, and a neutral reaction. By keeping it becomes thicker, and acquires a disagreeable terebinthinate taste. This may be prevented by mixing it while fresh with 5 per cent. of alcohol, and decanting the oil after it has become clear from the sediment. When wanted for use a quantity of water equal to the alcohol may be added, when they unite and subside, leaving the oil on the top.

PREPARATION.—It is sometimes obtained by rasping the outside of the rind and expressing the oil it contains, sometimes by distillation, but the best is got by rubbing the lemons over the interior of a sort of cup lined with short points, when the oil flows into a reservoir at the bottom of the cup.

COMPOSITION.—It is said to consist of two isomeric oils and a kind of camphor formed from them by exposure to air.

ACTION.—Externally it is a strong **rubefacient**; internally, in small doses, it is stimulating and carminative. It is chiefly used as a **flavouring** matter.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.	DOSE.
Linimentum Potassii Iodidi cum Sapone.	**Spiritus Limonis** ...	
Spiritus Ammoniæ Aromaticus (1 in 185).	Spiritus Odoratus	

Limonis Succus, B. and U.S.P. LEMON JUICE.—The freshly expressed juice of the ripe fruit of *Citrus limonum*.

CHARACTERS.—Slightly turbid, yellowish liquid, with an acid taste, and usually a slight odour of lemon from a little of the oil contained in the rind.

PREPARATION.—By squeezing the fresh fruit.

COMPOSITION.—It contains some acid salts, especially those of potash, and 7 per cent. of citric acid (U.S.P.); 32·5 grains to the fluid ounce (B.P.).

OFFICINAL PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Syrupus Limonis	...½-2 fl. dr.	Mistura Potassii Citratis	...4 fl. dr. (15 cc.)
		Syrupus Limonis	*Ad. lib.*

U.S.P. Mistura Potassæ Citratis. MIXTURE OF CITRATE OF POTASSIUM (Neutral Mixture).—Fresh lemon juice strained, 100; bicarbonate of potassium about 10 parts, or enough to neutralise.

Syrupus Limonis. SYRUP OF LEMONS, B. and U.S.P.—Boiling lemon juice, strained, 1 pint, with fresh lemon-peel, 2 oz.; refined sugar, 2½ pounds (B.P.). Boiling lemon juice, 40; fresh lemon-peel, 2; sugar, 60; water up to 100 (U.S.P.).

Not officinal. **Decoction of Lemon.**—Cut a *fresh* unpeeled lemon (best when pulled immediately from the tree) into thin slices, put it into three teacupfuls of water, and boil it down to one teacupful in a clean earthenware jar. Allow it to stand overnight in the open air, and give it the first thing in the morning. Free it by compression and filtration from rind, pulp, and seeds just before it is drunk.

USES.—It is used locally as a gargle in sore throat; to relieve itching in pruritus of the scrotum, in uterine hæmorrhage after delivery, and mixed with equal parts of glycerine as an application to the face in sunburn. Internally it is **refrigerant,** and forms a pleasant drink, allaying the thirst in fevers. It is used, in place of citric acid, to make effervescent mixtures and drinks. It is **anti-scorbutic,** and is employed to prevent scurvy in long voyages.

The decoction of lemon is said to be a powerful **antiperiodic,** and to be exceedingly useful as a substitute for large doses of quinine in cases of ague, typho-malarial fevers, and malarious conditions generally. It appears to be useful in reducing the temperature in typhoid fever even when no malarial complication exists.

Belæ Fructus, B.P. BAEL FRUIT.—The dried half-ripe fruit of *Ægle marmelos,* from Malabar and Coromandel.

FIG. 144.—Bael.

CHARACTERS.—Fruit roundish, about the size of a large orange, with a hard woody rind. Usually seen in fragments

consisting of portions of the hard grey rind and dry adherent red pulp and seeds. The moistened pulp is mucilaginous.

COMPOSITION.—Not well ascertained. It contains no appreciable amount of tannin.

USES.—Although it contains no tannin it is used in diarrhœa and dysentery. The fresh pulp is sometimes used as a laxative. Possibly bael fruit may owe its utility in dysentery to its possessing some action similar to that of cotoine, p. 337.

PREPARATION.	B.P. DOSE.	U.S.P.
Extractum Belæ Liquidum	1 fl. dr. to ½ fl. oz.	None.

STERCULIACEÆ, or BYTTNERIACEÆ.

Oleum Theobromæ, B. and U.S.P. OIL OF THEOBROMA; CACAO BUTTER.—A concrete oil obtained by expression and heat from the ground seeds of *Theobroma cacao.*

CHARACTERS.—Of the consistency of tallow; colour yellowish-white; odour like chocolate; taste bland and agreeable; reaction neutral. Does not become rancid from exposure to the air. Melts at 30°—35° C. (86°—95° F.).

PREPARATION AND COMPOSITION.—Consists chiefly of stearin and olein.

ADULTERATIONS.—Paraffin, wax, tallow, stearin, &c.

TESTS.—If 2 parts of it be dissolved in 4 parts ether in a test-tube, by immersing the tube in water of 17° C. (63° F.), and if this be afterwards plunged into water of 0° C. (32° F.), the mixture should not become turbid, nor separate a granular deposit in less than 3 minutes; and if the mixture, after congealing, be exposed to a temperature of 15° C. (59° F.), it should gradually become entirely clear. (Absence of impurities mentioned above.)

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Suppositoria Acidi Tannici	1 part in 2	For suppositories of various kinds, each weighing 15 gr. or 1 Gm.
,, Hydrargyri	1 part in 2	
,, Morphiæ	1 part in 2	
,, Plumbi Composita	4 parts in 9	

USES.—As a basis for suppositories. Also as a non-irritant application to the skin.

TERNSTRŒMIACEÆ.

Not officinal. **Thea.** TEA.—The dried leaves of *Thea sinensis.* China, Assam, Ceylon, &c.

CHARACTERS—Both green and black tea are prepared from the same species of thea. Green teas are obtained by drying the freshly-gathered leaves on a hot iron plate until they shrivel. Black teas

are obtained by allowing the leaves to lie in heaps and undergo a kind of fermentation before drying them.

COMPOSITION.—They contain caffeine, a volatile oil, and tannin.

ACTION.—The action probably depends partly on the caffeine and partly on the volatile oil they contain. Both green and black teas are powerful **cerebral stimulants.** They render the mental faculties more active, and tend to prevent sleep. Green tea is much more powerful than black, and its admixture with black is sometimes the cause of **sleeplessness** in persons who have thus taken it unconsciously. In some persons it produces giddiness, restlessness, and such severe muscular trembling that the hand shakes violently. Both green and black teas are apt to cause **indigestion.** This is probably due, in some measure at least, to the tannin they contain. Tea mixed with gastric juice lessens its power of digesting fresh meat, but not of digesting smoked meat. This is probably due to the tannin hardening the soft fibre of fresh meat, but leaving the comparatively hard fibre of dried meat, ham, &c. unchanged. Tea along with fresh meat not unfrequently causes indigestion, whilst ham, dried fish, &c. may be taken along with it without injury. To avoid getting much tannin it is advisable not to let the tea stand long on the leaves, but pour it off quickly so that the volatile oil which gives the aroma only is extracted.

USE.—As a cerebral stimulant to relieve drowsiness and headache.

U.S.P. Caffeina. CAFFEINE (THEINE).—$C_8H_{10}N_4O_2.H_2O$; 112.

A proximate principle of feebly alkaloidal power, generally prepared from the dried leaves of *Camellia Thea* or from the dried seeds of *Coffea arabica* (Nat. Ord., *Rubiaceæ*); or from Guarana, and occurring also in other plants.

CHARACTERS.—Colourless, soft and flexible crystals, generally quite long, and of a silky lustre, permanent in the air, odourless, having a bitter taste and a neutral reaction. Soluble in 75 parts of water and in 35 parts of alcohol at 15° C. (59° F.); in 9·5 parts of boiling water and very soluble in boiling alcohol; also soluble in about 6 parts of chloroform, but very slightly soluble in ether or in disulphide of carbon. When heated to 100° C. (212° F.), the crystals lose 8·49 per cent. in water (of water of crystalisation); and, when heated on platinum foil, they are completely volatilised without carbonising. On heating caffeine with chlorine water, or treating it with concentrated nitric acid, it is decomposed; on evaporating afterward, at a gentle heat, a yellow mass is left, which, when moistened with water of ammonia, assumes a purplish colour.

Sulphuric or nitric acid should dissolve it without colour,

and its aqueous solution should not be precipitated by test-solution of iodide of mercury and potassium (abs. of other alkaloids).

DOSE.—2 to 5 grains. Caffeine is very soluble in solutions of benzoate, cinnamate, or salicylate of sodium. By using these as solvents concentrated solutions of caffeine can be made for hypodermic injection. Caffeine 20 grs., salicylate of soda 17½ grs., water 1 fl. dr. makes a non-irritating solution containing 1 gr. of caffeine in 3 min., but stronger solutions may be made if required.

ACTION.—Caffeine causes at first stimulation and subsequently paralysis of **nerve centres** in cerebrum, cord and medulla. It has also a marked action on **muscular fibre,** both voluntary and involuntary. In large doses it acts as a gastro-intestinal irritant. Its action on **frogs** varies according to the species. In *rana temporaria* it produces a rigid condition of the muscles resembling rigor mortis, especially when locally applied to them. In *rana esculenta* this action on the muscles is slight, and the chief symptom is tetanus which, like that of strychnine, depends on the action of the drug on the spinal cord. This is followed by paralysis (of voluntary movement) and then of reflex action. In **warm-blooded animals** also caffeine produces tetanic convulsions, which may be arrested by artificial respiration, and death frequently prevented even from a very large dose. Morphine lessens the convulsions but does not prevent death.

From its stimulant action on the **brain**, doses of 2—8 grains sometimes cause heaviness of the head, flashes of light before the eyes, singing in the ears, loss of sleep, great restlessness, and delirium.

Its stimulant action on the **medulla** and cardiac centres increases the **respiration** and pulse-rate and raises the **blood-pressure** in moderate doses. Large doses depress the respiration and pulse, and lower the blood-pressure. In man the **pulse,** after somewhat large doses, becomes very frequent, irregular, and intermittent. This effect occurs in some persons even after a single cup of coffee, but it is prevented in such cases by adding a little brandy to the coffee as is usually done when coffee is taken without milk.

It appears sometimes to increase the **salivary** secretion. It has little action on the peristaltic movements of the **intestine,** but it causes the intestinal veins to become much dilated, and appears to cause hæmorrhoids.

The **temperature** is not altered by small doses of caffeine, but is increased by large doses.

Caffeine acts as a **diuretic**, though not invariably so. Its diuretic action may partly depend upon its stimulant action on the heart and vaso-motor centre, and consequent rise of blood-pressure. It may also be due in part to a stimulant action on the cells of the urinary tubules, as Brackenridge states that

it increases the excretion of urinary solids as well as urinary water.

USES.—It is used in headache, especially migraine and in cases where the headache seems to be inside the head without any external tenderness. As a diuretic it is especially useful in cardiac dropsy, though it may be given also in cases of hepatic dropsy. It acts as a diuretic even when the kidneys are diseased, and is useful even in very advanced cardiac cases. It is best given alternately with digitalis or along with it.

GUTTIFERÆ.

Cambogia, B. and U.S.P. GAMBOGE.—A gum resin obtained from *Garcinia morella, var. pedicellata* (B.P.); *Garcinia Hanburii* (U.S.P.). Imported from Siam.

CHARACTERS.—In cylindrical pieces, sometimes hollow in the centre, 1 or 2½ inches in diameter, breaking easily with a smooth conchoidal glistening fracture; colour tawny, changing to yellow when it is rubbed with water; taste acrid; powder, bright yellow.

PROPERTIES AND COMPOSITION.—Contains a resin, gambogic acid, and a soluble gum.

ADULTERATION.—Starch fraudulently added.

TEST.—An emulsion made with boiling water, and cooled, does not become green with the solution of iodine.

PREPARATION.

B.P.	DOSE.	U.S.P.	DOSE.
Pilula Cambogiæ Composita	5-15 grs.	Pilulæ Catharticæ Compositæ,	1-3 pills.

B.P. Pilula Gambogiæ Composita. COMPOUND GAMBOGE PILL.—Gamboge, Barbados aloes, and compound cinnamon powder, of each 1 oz.; hard soap, 2 oz.; syrup, 9 oz. Mix and beat to a uniform mass.

ACTION AND USE.—It is a **drastic hydragogue purgative,** and in large doses causes violent irritation of the alimentary canal, with vomiting and griping. It is used in combination with other purgatives as a derivative in cerebral affections, also with cream of tartar in dropsies. It has been used as an **anthelmintic.**

CANELLACEÆ.

B.P. Canellæ Albæ Cortex. CANELLA ALBA BARK.—The bark of the *Canella alba.* South Florida and the West Indies.

CHARACTERS.—Large quills or flattish pieces about 1 inch in diameter; pinkish-white externally; white internally. Taste bitter, pungent, acrid; odour cinnamon-like.

COMPOSITION.—A volatile oil (about 1 per cent.) consisting of several oils, of which one is identical with eugenic acid, from oil of cloves; a bitter principle, canellin, together with resin, starch, and mannite. There is no tannin.

PREPARATION.

B.P.

It is used in **Vinum Rhei.**

DOSE.—Of the powdered bark, 15—30 grs.

ACTION AND USE.—It is an **aromatic bitter** and **tonic.** Given sometimes in atonic dyspepsia. It has been employed in rheumatism and gout.

VITACEÆ.

B.P. Uvæ. RAISINS.—The dried fruit of the *Vitis vinifera.*

COMPOSITION.—They contain grape sugar and acid tartrate of potash.

PREPARATIONS.

Tinctura Cardamomi Composita.
,, Sennæ.

USES.—They are used to sweeten preparations. They are a useful stimulant in weariness from mental work (p. 161); and in active physical exertion, such as alpine climbing, they not only tend to maintain the strength and prevent exhaustion, but they somewhat relieve thirst when water cannot be had (p. 315).

Vinum Xericum, B.P. SHERRY WINE. **Vinum Album, U.S.P.** WHITE WINE.—A pale amber or straw-coloured alcoholic liquid, made by fermenting the unmodified juice of the grape freed from seeds, stems, and skins. It should contain not less than 10 per cent. nor more than 12 per cent. by weight of absolute alcohol.

PREPARATION.

U.S.P.

Vinum Album Fortius, prepared by mixing 7 parts white wine with 1 of alcohol. This should contain not less than 20 per cent. nor more than 25 per cent. by weight of absolute alcohol.

Vinum Rubrum, U.S.P. RED WINE.—A deep red alcoholic liquid made by fermenting the juice of coloured grapes in presence of their skins.

It should not contain less than 10 per cent. nor more than 12 per cent. by weight of absolute alcohol.

ACTION AND USES.—*Vide* Alcohol.

ZYGOPHYLLACEÆ.

Guaiaci Lignum, B. and U.S.P. GUAIACUM WOOD.—The heart-wood of *Guaiacum officinale* and *G. Sanctum.* St. Domingo and Jamaica. Coarse powder or small chips.

CHARACTERS.—The wood is known as *Lignum vitæ,* occurs in logs, and is very hard and heavy. The alburnum, or sapwood, is yellow in colour, the duramen, or heart-wood, is dark greenish

brown, which should become dark blue-green on the addition of nitric acid.

COMPOSITION.—Contains resin, chiefly in the heart-wood.

PREPARATION.

B.P.	DOSE.
Decoctum Sarsæ Compositum	2-10 fl. oz.

U.S.P.	
Decoctum Sarsaparillæ Compositum	4-6 fl. oz. (200-300 cc.)

Guaiaci Resina, B. and U.S.P. GUAIACUM RESIN.—The resin of *Guaiacum officinale*. Obtained from the stem by natural exudation, by incisions, or by heat.

CHARACTERS.—In masses of a greenish-brown or reddish-brown colour; fractured surface resinous, translucent at the edges, where the greenish colour is usually well marked, and serves to distinguish this from other resins. A solution in rectified spirit strikes a clear blue colour when applied to the inner surface of a paring of raw potato (p. 54), or on the addition of tincture of perchloride of iron. Powder greyish, turning green on exposure to air.

COMPOSITION.—It contains several resinous acids, guaiaconic, guiaretic, and guiacic acids; these are soluble in alkalies and are precipitated on neutralisation.

PREPARATIONS.

B.P.	DOSE.
Mistura Guaiaci	1-1½ fl. oz.
Tinctura Guaiaci	½-1 fl. dr.
,, ,, **Ammoniata**	½-1 fl. dr.
Pilula Hydrargyri Subchloridi Composita	5-10 gr. (of the resin) 10-30 gr.

U.S.P.	
Tinctura Guaiaci	1-3 fl. dr. (4-12 cc.
,, ,, **Ammoniata**	1-2 fl. dr. (4-8 cc.)
Pilulæ Antimonii Compositæ	

B.P. Mistura Guaiaci. GUAIACUM MIXTURE.—Guaiacum, ½ oz.; refined sugar, ½ oz.; gum acacia, ¼ oz.; cinnamon water, 1 pint.

Tinctura Guaiaci Ammoniata, B. and U.S.P. AMMONIATED TINCTURE OF GUAIACUM.—Guaiacum resin, 4 oz.; aromatic spirit of ammonia, to 1 pint (B.P.). Guaiac, 20; aromatic spirit of ammonia, 100 (U.S.P.).

ACTION.—It causes a burning sensation in the mouth and throat when given in small doses. Large doses cause vomiting and purging. When absorbed it acts as a stimulant, an alterative, and a diuretic.

USES.—It is employed in the treatment of tonsillitis, *Mistura Guaiaci* being in my experience more efficacious than the ammoniated tincture. Others prefer the simple powder, as it remains longer applied to the tonsils and pharynx. It is also used in chronic rheumatism. It has been used in the treatment of gout and syphilitic periosteal diseases.

MELIACEÆ.

U.S.P. Azedarach. AZEDARACH.—The bark of the root of *Melia Azedarach.*

CHARACTERS.—In curved pieces or quills varying in size and thickness; outer surface red-brown, with irregular, blackish, longitudinal ridges; inner surface whitish or brownish, longitudinally striate; fracture more or less fibrous; upon transverse section tangentially striate, with yellowish bast-fibres; almost inodorous, sweetish, afterward bitter and nauseous.

If collected from old roots, the bark should be freed from the thick, rust-brown, nearly tasteless, corky layer.

ACTION.—It produces vomiting and purging and symptoms of narcotic poisoning.

USE.—It is used as an **anthelmintic,** to destroy the ascaris lumbricoides, in the form of a decoction (2 oz. of the herb to a pint of water, boiled down to ½ a pint). This is given in doses of a tablespoonful every two or three hours until the bowels are freely opened.

RUTACEÆ.

RUTEÆ.

Oleum Rutæ, B. and U.S.P. OIL OF RUE.—A volatile oil distilled from the fresh herb of *Ruta graveolens.*

CHARACTERS.—Colourless, pale yellow, or greenish yellow; odour peculiar; taste bitter, acrid.

COMPOSITION.—Consists of a hydrocarbon and an oil containing oxygen.

DOSE.—2 to 5 min. (0·12-0·3 cc.).

USES.—Externally it is **rubefacient,** internally it is stimulant, **antispasmodic, emmenagogue,** and carminative; used in amenorrhœa, hysteria, convulsions, and flatulence.

B.P. Cuspariæ Cortex. CUSPARIA, or ANGOSTURA BARK.—The bark of *Galipea cusparia,* the Angostura bark tree. Tropical America.



FIG. 145.—Cusparia.

CHARACTERS.—Consists of quills, grey outside, light brown inside; several inches long, about an inch in breadth, and one-eighth of an inch thick. Generally readily recognised by one edge being cut obliquely or feathered, from the oblique introduction of the knife by which the bark has been detached. Odour, peculiar; taste, bitter.

COMPOSITION.—A bitter substance, cusparine, and some volatile oil.

B.P.	DOSE.
Infusum Cuspariæ (1 oz. in 1 pint at 120° F.)	1-2 fl. oz.

ADULTERATION.—The bark of *Strychnos nux vomica*.

TESTS.—Nitric acid gives a blood-red colour when applied to the inner surface of the false bark from the brucine present in it, but gives a bluish-black colour with the true bark.

ACTION AND USE.—Cusparia is an **aromatic bitter tonic,** and is used in cases of atonic dyspepsia and in cases of weak digestion, especially during convalescence from acute diseases.

DIOSMEÆ.

Buchu Folia, B.P.; Buchu, U.S.P. BUCHU LEAVES, B.P.; BUCHU, U.S.P.—The dried leaves of (1) *Barosma betulina*, (2) *Barosma crenulata*, (3) *Barosma serratifolia*. Cape of Good Hope.

FIG. 146.—Barosma betulina.

FIG. 147.—Barosma crenulata.

FIG. 148.—Barosma serratifolia.

CHARACTERS.—Smooth, marked with pellucid dots at the indentations and apex; having a powerful, somewhat mint-like odour, and a warm camphoraceous taste. (1) Obovate, with a recurved truncated apex and sharp cartilaginous spreading teeth; (2) oval-lanceolate, obtuse, minutely crenated; (3) narrow linear-lanceolate, tapering at each end, sharply and finely serrated.

COMPOSITION.—The leaves contain a volatile oil in the vittæ which appear as dots on the leaves, and a bitter substance.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Infusum Buchu (1 oz. in 1 pint)	1-2 fl. oz.	Extractum Buchu Fluidum.	20-45 min.
Tinctura ,,	1-2 fl. dr.		

ACTION AND USE.—Buchu is slightly **tonic.** It is also diuretic and diaphoretic. Its chief use is as a **stimulant** to the mucous membrane of the **bladder** in cases of vesical catarrh and irritation. It is also used with other drugs as an **expectorant** in chronic bronchitis. It is used in South Africa in doses of 20 grains of the powdered leaves, in the treatment of diarrhœa and dysentery.

XANTHOXYLEÆ.

U.S.P. Xanthoxylum. XANTHOXYLUM. PRICKLY ASH.—The bark of *Xanthoxylum fraxineum*, and of *Xanthoxylum carolinianum*.

CHARACTERS.—*Xanthoxylum fraxineum* is in curved or quilled fragments, about one-twenty-fifth of an inch (1 millimetre) thick; outer surface brownish-grey, with whitish patches, and minute, black dots, faintly furrowed, with some brown, glossy, straight, two-edged spines, linear at the base, and about a quarter of an inch (6 millimetres) long; inner surface whitish, smooth; fracture short, non-fibrous, green in the outer, and yellowish in the inner, layer; inodorous; bitterish, very pungent.

Xanthoxylum carolinianum resembles the preceding, but is about one-twelfth of an inch (2 millimetres) thick, and is marked by many conical, corky projections, sometimes four-fifths of an inch (2 centimetres) high, and by stout, brown spines, rising from a corky base.

Xanthoxylum should not be confounded with the bark of *Aralia spinosa*, which is nearly smooth externally, and beset with slender prickles in transverse rows.

PREPARATION.

	DOSE.
Extractum Xanthoxyli Fluidum	30-60 min.

COMPOSITION.—It contains a volatile oil, resins, and possibly berberina.

USES.—Its action seems to be that of an **aromatic** and somewhat irritant **bitter,** somewhat resembling mezereum and guaiac. Like these drugs it is used in rheumatism. The bark is chewed to relieve toothache, and to aid recovery in palsy affecting the tongue.

U.S.P. Pilocarpus. PILOCARPUS. JABORANDI.—The leaflets of *Pilocarpus pennatifolius*.

CHARACTERS.—About four inches (10 centimetres) long, short-stalked, oval or ovate-oblong, entire and slightly revolute at the margin, obtuse and emarginate, unequal at the base; coriaceous, pellucid-punctate, mostly smooth; when bruised, slightly aromatic; somewhat pungent and bitter.

PREPARATION.

	DOSE.
Extractum Pilocarpi Fluidum	5-60 min.

U.S.P. Pilocarpinæ Hydrochloras. HYDROCHLORATE OF PILOCARPINE.—The hydrochlorate of an alkaloid prepared from Pilocarpus. It should be kept in small, well-stopped vials.

CHARACTERS.—Minute, white crystals, deliquescent, odourless, having a faintly bitter taste, and a neutral reaction. Very soluble in water and in alcohol, but almost insoluble in ether or chloroform. When heated on platinum foil, the crystals melt, and are finally

completely dissipated. With concentrated sulphuric acid, the crystals yield a yellow colour, with nitric acid (sp. gr. 1·400), a faintly greenish-violet tint, with sulphuric acid and chromate of potassium, an emerald-green colour. If an aqueous solution of the salt is slightly acidulated, the addition of water of ammonia produces no precipitate. Solution of soda produces a cloudiness only in a concentrated solution. The aqueous solution yields, with test-solution of nitrate of silver, a white precipitate insoluble in nitric acid, but soluble in ammonia.

DOSE.—$\frac{1}{12}$ to $\frac{1}{3}$gr. internally or by subcutaneous injection.

USES.—Its action and uses are similar to those of pilocarpus.

COMPOSITION.—The leaves contain a volatile oil and two alkaloids, pilocarpine and jaborine.

ACTION.—**Jaborine** has an action like that of atropine and antagonistic to that of pilocarpine. The amount of jaborine in the leaves is insufficient to antagonise the pilocarpine, so that the leaves have an action like that of pilocarpine. It is probable that some discrepancies between the statements of different observers regarding the action of pilocarpine may be due to the presence of more or less jaborine in the pilocarpine which they supposed to be pure.

Pilocarpine stimulates the peripheral terminations of **efferent nerves** going to **glands,** and first stimulates and then paralyses the efferent nerves going to structures composed of **involuntary muscular fibre.** In large doses it lessens but does not quite destroy the irritability of voluntary **muscle** and **motor nerves.**

It appears to have a certain action on the **nerve-centres.** It produces in *Rana esculenta* convulsions like those of picrotoxin. In *Rana temporaria* it only produces paralysis. Frogs poisoned by it croak, when stroked, in the same way as when the cerebrum is removed. In mammals it causes dyspnœa, convulsive twitching and shivering, and movements of rotation (p. 182; cf. also Apomorphia). These may, however, be partly due to the action of the drug on the heart. It seems however to stimulate the **centres** of the salivary and sweat glands as well as the peripheral terminations of the secreting nerves.

From its stimulating action on secreting nerves it produces enormous secretion of **saliva** from the submaxillary, sublingual, and parotid glands, and enormous secretion of sweat from the **sweat** glands, beginning either in the face or at the point of subcutaneous injection, and extending over the whole surface of the body. It produces, though to a less extent, secretion of **tears** from the lachrymal gland; of wax from the **ears;** of mucus from the **nose** and from the **bronchial** mucous membrane; of gastric juice from the glands of the **stomach;** probably of intestinal juice from the **intestinal glands,** and of urine from the **kidney.** The secretion of **milk** is sometimes but not always increased. It does not appear to increase the secretion of **bile.**

Its stimulating action on nerves supplying **involuntary**

muscular fibre is observed in the eye, intestine, heart and vessels, bladder, **uterus** and spleen. By stimulating the terminations of the third nerve in the **eye** it causes contraction of the pupil and spasm of accommodation, and indistinct vision. After this passes off there may be dilatation of the pupil. By stimulating the **intestinal ganglia** it causes increased peristalsis. By stimulating the vagus ends in the **heart** like nicotine, **large doses** of it cause the pulse to become slow in frogs and in mammals, and the blood-pressure to fall. In small doses its effect is more complicated, as will be afterwards noticed. In **larger doses** it paralyses the **vagus** ends (A, Fig. 80, p. 271), but not the inhibitory ganglia. By acting on the **bladder** it causes contraction, and may produce strangury and sometimes retention. It causes contractions of the **uterus,** which, in rabbits, begin at the openings of the Fallopian tubes and proceed to the os uteri. This depends also on a peripheral action of the drug, and is not arrested by destruction of the spinal cord. It causes contraction of the **spleen** in man both in its normal condition and when abnormally enlarged.

As **vomiting** is a complex movement demanding the co-operation of the abdominal muscles and diaphragm, it is evident that it would not ensue merely from increased contraction of the gastric walls. Jaborandi appears, however, to irritate the stomach, and often causes nausea and vomiting; and so does pilocarpine, though to a less extent, even when subcutaneously injected.

It is probable that even when injected subcutaneously it is eliminated by the mucous membrane of the stomach in the same way as tartar emetic, morphine, atropine, quinine and strychnine, and that it thus acts as a local irritant to the gastric nerves (Fig. 3 p. 29).

Its action on the **circulation** is a complicated one, as the direct effect of the drug on the heart and vessels is probably much modified by the reflex action from the stomach, intestines, &c., which have been stimulated by it. The **vessels** usually become much dilated at first, the carotids pulsating violently, the pulse becoming rapid, and a feeling of heat being perceived over the body. When perspiration sets in there is sometimes a feeling of cold and shivering. The blood-pressure usually falls a little at first with quicker pulse, then rises with slower pulse (p. 231), and finally falls greatly from vaso-motor paralysis.

Respiration.—There is sometimes a feeling of slight dyspnœa just after the dose has been given, but this only lasts a few moments. Poisonous doses cause in animals dyspnœa and convulsions, which, as already mentioned, probably depend in some measure on cardiac failure. In animals the abundant secretion into the bronchi and pulmonary œdema produced by large doses also lead to dyspnœa.

The **temperature** rises when the patient is shivering and falls during sweating (p. 386). The secretion of sweat usually lasts for two or three hours, and is so copious that the body loses one or two

pounds and sometimes as much as eight pounds from it and the salivation together.

After the sweating is over there is usually a feeling of debility, languor, and thirst.

Pilocarpine is **excreted** unchanged by the urine. It does not appear in the saliva.

The **injurious effects** sometimes produced by it are, in addition to the dimness of vision and vomiting already mentioned, sudden collapse, swelling of the salivary glands and tonsils, hiccough, diminished secretion of urine, albuminuria, strangury, bleeding from the vagina, and anticipation of the menstrual flux.

Atropine **antagonises** pilocarpine very completely, preventing its action if administered before it, and removing its effects if given after it. Sudden collapse ought therefore to be treated by the subcutaneous injection of atropine.

The nausea and vomiting generally yield easily to morphine.

USES.—As its action is a peripheral rather than a central one, it affects the **eye** more powerfully when applied locally than when taken internally. It has been employed in chronic catarrh, in intraocular hæmorrhage, in separation of the retina, in albuminuric retinitis, and instead of physostigma in glaucoma, &c. (*vide* Myotics, p. 192). In some **skin** diseases it is very useful, especially in prurigo and chronic urticaria and in baldness. In small doses it relieves thirst (*vide* Refrigerants, p. 315) in chronic renal disease, and has been used for a similar purpose in fever.

It has been used in diseases of the **throat,** especially tonsillitis and diphtheria, but its utility in the latter disease is uncertain. In bronchitis, asthma, and hooping-cough it sometimes gives relief, though it is not so useful as might be expected (p. 218). From its action on the **uterus** it has been used as an oxytocic to induce premature labour. As a **diaphoretic** it may be used in small doses to induce diaphoresis and prevent or relieve coryza, bronchial catarrh, or rheumatism consequent on a chill (p. 288).

Its chief use is in dropsy, and especially in uræmia depending on disease of the **kidneys.** It has been employed to remove pleural and peritoneal effusions, and has been used in cardiac dropsy when digitalis failed, but great care is then requisite in its use.

In renal dropsy it not only removes water from the body but it removes urea and possibly other products of tissue waste. Some of the urea is excreted in the sweat, and a considerable amount appears in the saliva. Probably the removal of these products from the body is the reason why pilocarpine cuts short uræmic convulsions. In puerperal eclampsia it is not so successful as in convulsions depending on kidney disease. Pilocarpine has also been used to eliminate other poisons from the body, and has been used in syphilis and chronic poisoning by lead, mercury, and arsenic.

CONTRA-INDICATIONS.—Fatty heart, and impeded pulmonary circulation from valvular disease, emphysema, or pleurisy. These

conditions do not absolutely prohibit the use of the remedy, but it must then be given with care and the patient watched. It may be combined with alcoholic stimulants, and atropine should be ready for subcutaneous injection if necessary.

SIMARUBACEÆ.

Quassiæ Lignum, B.P.; Quassia, U.S.P. QUASSIA WOOD, B.P.; QUASSIA, U.S.P.—The wood of *Picræna excelsa*. Jamaica.

CHARACTERS.—Billets varying in size, seldom thicker than the thigh. Wood dense, tough, yellowish white, intensely and purely bitter. Also chips and raspings of the same.

PROPERTIES AND COMPOSITION.—The wood contains a small quantity of a bitter neutral principle, Quassiin. The wood contains no tannin, and may therefore be used with salts of iron.

PREPARATIONS.

B.P.			DOSE.
Extractum Quassiæ			2-5 gr.
Infusum	,,	(1 drm. in ½ pint cold water for ½ hour)	1-2 fl. oz.
Tinctura	,,		½-2 fl. drm.

U.S.P.			DOSE.
Extractum Quassiæ			3-5 gr. (·18-32 Gm.)
,,	,,	Fluidum	½-1 fl. drm. (2-4 cc.)
Tinctura	,,		½-2 fl. drm. (2-8 cc.)

ACTION AND USES.—Quassia is a pure bitter **stomachic tonic,** having no other action on man. On insects it exerts a narcotic influence and, in the form of an infusion sweetened with sugar, it is often employed to destroy flies.

In small doses it increases the appetite. In large doses it acts as an irritant and causes vomiting. The infusion is made with cold water. As it contains **no tannin** it does not form an inky mixture with iron, like most vegetable bitters, and so can be conveniently prescribed with it. It is used in atonic dyspepsia.

Its action is not thoroughly understood, but it is not improbable that it lessens putrefaction in the stomach and prevents to some extent the formation of acid substances during digestion

It is often administered by using a cup made of the wood; this when filled with water, imparts its active principle to that fluid. An infusion is used in the form of enema to destroy ascarides.

CHAPTER XXXII.

Class I. EXOGENÆ. Sub-class II. CALYCIFLORÆ.

RHAMNACEÆ.

Rhamni Succus, B.P. BUCKTHORN JUICE.—The recently expressed juice of the ripe berries of common buckthorn, *Rhamnus catharticus.*

CHARACTERS.—A green liquid with a sweetish taste and disagreeable odour. It has an acid reaction.

COMPOSITION.—A yellowish uncrystallisable substance Rhamnocathartin, with a bitter taste and soluble in water. Also a glucoside, Rhamnin, and a product of its decomposition Rhamnetin.

PREPARATION.

B.P.	DOSE.
Syrupus Rhamni	½-1 fl. oz.; (for a child) ½-2 fl. drm.

USE.—Buckthorn is used as a domestic remedy for constipation, and is given to children in the form of syrup. It is a hydragogue purgative, stimulating the secretion of the mucous membrane of the intestine. It may cause griping.

Frangula, U.S.P. BUCKTHORN. The bark of *Rhamnus Frangula* collected at least one year before being used.

CHARACTERS.—In quills about $\frac{1}{25}$ of an inch thick; greyish or blackish-brown outside with whitish corky warts; brownish yellow internally. Nearly inodorous, taste sweetish and bitter.

COMPOSITION.—The most important constituent is a cathartic substance, frangulin.

PREPARATION.

U.S.P.	DOSE.
Extractum Frangulæ Fluidum	1 fl. drm. (4 cc.)

ACTION AND USES.—When fresh it acts as an **irritant** poison on the gastro-intestinal canal, but when dried its action becomes less violent, and more like that of rhubarb. It is used as a **purgative** in constipation, and may be given in the form of the fluid extract

or of a decoction ($\frac{1}{2}$ oz. to $\frac{1}{2}$ pint) in tablespoonful doses or as an elixir, 1 fl. dr. of the fluid extract to 3 of elixir of orange.

All the species of buckthorn appear to possess cathartic properties. Lately the bark of the *Rhamnus Purshiana* has been coming into use as a purgative under the name of Cascara Sagrada or sacred bark. It is usually given in the form of fluid extract in doses of $\frac{1}{2}$ to 1 fl. oz, but 1 fl. dr. or less given immediately after rising in the morning is often sufficient. It may also be given with advantage in chronic constipation in doses of 10-15 min. thrice a day before meals.

CELASTRACEÆ.

U.S.P. Euonymus. EUONYMUS. WAHOO.—The bark of *Euonymus atropurpureus.*

CHARACTERS.—In quilled or curved pieces, about one-twelfth of an inch (2 millimetres) thick; outer surface ash-grey, with blackish patches, detached in thin and small scales; inner surface whitish or slightly tawny, smooth; fracture smooth, whitish, the inner layers tangentially striate; nearly inodorous; taste sweetish, somewhat bitter and acrid.

PREPARATION.

	DOSE.
Extractum Euonymi	2-5 gr.

COMPOSITION.—It contains a bitter principle called euonymin, which is precipitated, together with a resin and a fixed oil, when the strong tincture is poured into water.

ACTION.—It acts as an **hepatic stimulant** (p. 353), hydragogue **cathartic,** and diuretic. In large doses it causes intestinal and hæmorrhoidal irritation.

USE.—In constipation accompanied by biliousness, and in chronic malarial conditions.

AQUIFOLIACEÆ.

U.S.P. Prinos. PRINOS. BLACK ALDER.—The bark of *Prinos verticillatus,* Linné (*Ilex verticillata,* Gray).

CHARACTERS.—Thin, slender fragments, about one-twenty-fifth of an inch (1 millimetre) thick, fragile; outer surface brownish ash-coloured, with whitish patches and blackish dots and lines, the corky layer easily separating from the green tissue; inner surface pale greenish or yellowish; fracture short, tangentially striate; nearly inodorous, bitter, slightly astringent.

DOSE.—30 grains.

ACTION.—It is an **astringent** bitter. It is employed in the form of a decoction, prepared by boiling two ounces of the bark in three pints of water down to two pints. This decoction is given

internally, in doses of two or three fluid ounces, in diarrhœa and malarial disorders, and is used externally in indolent sores and chronic skin diseases.

TEREBINTHACEÆ. ANACARDIÆ.

Mastiche, B. and U.S.P. MASTICH.—A concrete resinous exudation from *Pistacia Lentiscus.* Scio.

CHARACTERS.—Globular or elongated tears about the size of a pea, pale yellow, glass-like, brittle, becoming soft and plastic when chewed; faint agreeable odour and slight terebinthinate taste.

COMPOSITION.—Consists of about 90 per cent. of an acid resin (mastichic acid), soluble in alcohol; the remaining 10 per cent. is masticin, a tenacious resin soluble in ether, with traces of an ethereal oil.

PREPARATION.—Some exudes spontaneously, but most is got by incision into the stem.

PREPARATION.

U.S.P.

Pilula Aloes et Mastiches.

DOSE.—20 to 40 gr. if administered internally.

USES.—It is sometimes chewed in order to give pleasant odour to the breath. It is chiefly employed for temporarily stopping decayed teeth, and for arresting hæmorrhage from leech-bites. When used to stop teeth the cavity ought to be well cleaned and dried, and a piece of cotton saturated with a solution of four parts of mastiche should be gently pressed into it so as not to cause pain, but to fill the cavity exactly. Another method is to dissolve one part of mastiche with two of collodion, and fill the cavity with this. Either of these methods may also be employed to stop bleeding from leech-bites. It has been supposed to have a **stimulating** action on the **bronchial** mucous membrane, and has been used in bronchorrhœa, and also in infantile cholera. It is used to cover mercurial pills and prevent the formation of amalgam when they are silvered.

U.S.P. Rhus Glabra. RHUS GLABRA. SUMACH.—The fruit of *Rhus glabra.*

CHARACTERS.—Sub-globular, about one-eighth of an inch (3 millimetres) in diameter, drupaceous, crimson, densely hairy, containing a roundish-oblong, smooth putamen. It is inodorous, and its taste acidulous.

PREPARATION.

	DOSE.
Extractum Rhois Glabræ Fluidum	1-2 fl. drm.

COMPOSITION.—It contains much tannin.

USES.—It may be used as an **astringent** in the form of decoction, or the fluid extract may be diluted, for an effective gargle in inflammation of the throat or mouth.

U.S.P. Rhus Toxicodendron. RHUS TOXICODENDRON. POISON IVY.—The fresh leaves of *Rhus Toxicodendron*, Michaux; *Rhus Toxicodendron* and *Rhus radicans*, Linné.

CHARACTERS.—Long-petiolate, trifoliate; the lateral leaflets sessile, about four inches (10 centimetres) long, obliquely ovate, pointed; the terminal leaflets stalked, ovate or oval, pointed, with a wedge-shaped base; the leaflets entire and glabrous (in *Rhus radicans*, Linné), or variously notched, coarsely toothed or lobed, downy beneath (in *Rhus Toxicodendron*, Linné); when dry, papery and brittle; inodorous; somewhat astringent and acrid.

The fresh leaves abound with an acrid juice which darkens when exposed to the air, and, when applied to the skin, produces inflammation and swelling. The leaves should, therefore, not be touched with bare hands.

Rhus Toxicodendron should not be confounded with the leaves of *Ptelea trifoliata*, Linné, which are similar in appearance, but have all the leaflets sessile.

COMPOSITION.—It contains a volatile acid which appears to be the active principle.

ACTION.—In many persons contact with this plant causes an eczematous eruption of a very distressing character. It is best treated by solutions of lead, permanganate of potash, and ammonia. Internally it causes gastro-intestinal irritation, drowsiness, stupor, and delirium.

USES.—It has been recommended in **incontinence of urine**, paralysis, and cutaneous diseases. A fluid extract of a non-officinal plant, *Rhus aromatica*, has been used successfully in incontinence of urine in doses of 5 to 30 min.

AMYRIDACEÆ, or BURSERACEÆ.

Myrrha, B. and U.S.P. MYRRH.—A gum-resinous exudation from the stem of *Balsamodendron Myrrha*. Arabia Felix and Abyssinia.

CHARACTERS.—In irregular-shaped tears or masses varying much in size, somewhat translucent, of a brownish-yellow or reddish-brown colour, fractured surface irregular and somewhat oily; odour agreeable and aromatic, taste acrid and bitter.

COMPOSITION.—Gum (50-60 per cent.) soluble in water, and of which arabin constitutes a portion. The remainder, insoluble in water, is made up principally of a resinous acid, myrrhic acid, and a volatile oil.

PREPARATIONS.

B.P.	DOSE.
Decoctum Aloes Compositum	½-2 fl. oz.
Mistura Ferri Composita	1-2 fl. oz.
Pilula Aloes et Myrrhæ	5-10 gr.
,, Asafœtidæ Composita	5-10 gr.
,, Rhei Composita	5-10 gr.
Tinctura Myrrhæ	½-1 fl. dr. (of myrrh, 10-30 gr.)

U.S.P.	DOSE.
Mistura Ferri Composita	1-2 fl. oz. (30-60 cc.)
Pilulæ Aloes et Myrrhæ	1 pill.
Pilulæ Ferri Compositæ	2-6 pills.
,, Galbani Compositæ	2-4 pills.
Tinctura Aloes et Myrrhæ	1-2 fl. drm. (4-8 cc.)
Tinctura Myrrhæ	1-2 fl. drm. (4-8 cc.)

ACTION AND USES.—Myrrh is a very useful **astringent** in the form of wash or gargle for spongy gums, aphthous stomatitis, and ulcerated throats. Internally it is used as an **expectorant** in chronic bronchitis; and combined with iron and aloes is used in the treatment of amenorrhœa. It is also useful in bronchorrhœa and leucorrhœa.

B.P. Elemi. ELEMI.—A concrete resinous exudation, the botanical source of which is undetermined, but is probably *Icica Abilo.* Manilla.

CHARACTERS.—A soft sticky mass, yellowish-white, with fennel-like odour; almost entirely soluble in rectified spirit.

COMPOSITION.—Two resins and a volatile oil.

PREPARATION.

B.P.	
Unguentum Elemi (with simple ointment)	1 part in 5.

USE.—Not given internally; is used as a **local stimulant** in ulceration.

LEGUMINOSÆ; PAPILIONACEÆ.

Glycyrrhizæ Radix, B.P.; Glycyrrhiza, U.S.P. LIQUORICE ROOT.—The root or underground stem, fresh and dried, of *Glycyrrhiza glabra.*

CHARACTERS.—In long cylindrical branched pieces, tough and pliable; greyish-brown outside, yellow inside; taste sweet and slightly acrid. Digested with water it yields a solution which gives a precipitate with diluted sulphuric acid.

COMPOSITION.—Contains starch, sugar, and a sweet principle—glycyrrhizin—which is the substance precipitated by sulphuric acid.

PREPARATIONS.

B.P.	DOSE.
Confectio Terebinthinæ	60-120 gr.
Decoctum Sarsæ Compositum	2-10 fl. oz.
Extractum Glycyrrhizæ	10-30 gr.
Infusum Lini	1-2 fl. oz.
Pilula Hydrargyri	3-8 gr.
,, Ferri Iodidi	3-8 gr.
Extractum Glycyrrhizæ Liquidum	1 fl. drm.
Pulvis Glycyrrhizæ Compositus (*vide* p. 824)	30-60 gr.

OF EXTRACT OF LIQUORICE—

Confectio Sennæ (1 part in 94, nearly).....
Decoctum Aloes Compositum (1 oz. in 30 fl. oz.) ...
Mistura Sennæ Composita (½ oz. in 1 pint).....
Tinctura Aloes (1½ oz. to 1 pint) .....
Trochisci Opii.....

U.S.P.	DOSE.
Extractum Glycyrrhizæ Fluidum	1 fl. drm. (4 cc.)
,, ,, **Purum**	1 fl. drm. (4 cc.)
Glycyrrhizinum Ammoniatum	5-15 gr. (0·32-1 Gm.)
Pulvis Glycyrrhizæ Compositus (*vide* p. 824)	30-60 gr. (2-4 Gm.)

U.S.P. Glycyrrhizinum Ammoniatum. AMMONIATED GLYCYRRHIZIN.—Prepared by exhausting powdered liquorice with ammonia, precipitating by sulphuric acid, redissolving in ammonia, and drying. It forms dark brown or reddish scales, very sweet. It is used for flavouring.

ACTION AND USES.—Taken into the mouth, liquorice has a sweet taste; it increases the flow of saliva, and being mucilaginous acts as a **demulcent.** It is used to allay cough by lessening the irritation of the mucous membrane. It is particularly useful when there is violent cough due to irritation of the pharynx and upper part of the respiratory passages (p. 213). It is used as a vehicle to cover the taste of other medicines, and has been used instead of sugar in diabetes. The Pulv. Glycyrrhizæ Co., which is really a preparation of senna, *q. v.*, is a gentle laxative.

Scoparii Cacumina, B.P.; Scoparius, U.S.P. BROOM TOPS, B.P.; BROOM, U.S.P.—The fresh and dried tops of *Sarothamnus Scoparius* (*Cytisus Scoparius*). From indigenous plants.

CHARACTERS.—Thin flexible tough twigs, dark green, angular, of a bitter nauseous taste, and of a peculiar odour when bruised.

COMPOSITION.—It was found by Stenhouse to contain two principles: a neutral body, scoparin, and a volatile poisonous alkaloid, sparteine.

PREPARATIONS.

B.P.	DOSE.
Decoctum Scoparii (1 oz. in 1 pint for 10 minutes and strain)	1-3 fl. oz.
Succus Scoparii	1-2 fl. dr. or more.

None in U.S.P.

PHYSIOLOGICAL ACTION.—Broom tops have a **diuretic** action.

The action of **sparteine** is identical with that of coniine. It **paralyses** the endings of the motor nerves and vagi, diminishes reflex excitability of the cord, and causes death by paralysis of

the respiratory centre in the medulla oblongata. According to J. Fick it has a diuretic action.

Scoparin has been supposed to be the diuretic principle. It has **little** physiological **action,** and in a number of unpublished experiments which I made in 1865 with a specimen given to me by my friend Dr. Stenhouse, I found that in the healthy subject it does not produce diuresis. Similar results have been obtained by Paton. It is quite possible, however, that it may act as a diuretic in cases of dropsy.

THERAPEUTICAL USES.—Broom tops are most useful in dropsy dependent on chronic renal disease. They are also useful in cardiac dropsy, but digitalis is generally more certain. In comparative experiments I have found the decoction of the dried broom tops quite as efficacious as the juice expressed from the fresh tops.

Tragacantha, B. and U.S.P. TRAGACANTH.—A gummy exudation from the stems of *Astragalus gummifer* and from other species of Astragalus. Asia Minor.



FIG. 149.—Tragacanth.

CHARACTERS.—Shell-like bands, slightly curved, white or yellowish, tough and elastic; very sparingly soluble in cold water; but swelling into a gelatinous mass, which is tinged violet by tincture of iodine.

COMPOSITION.—Consists of a mixture of arabin, or common gum-arabic; and bassorin, a gum which does not dissolve in water, but swells up in it.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Confectio Opii	5-20 gr.	**Mucilago Tragacanthæ.**
Mucilago Tragacanthæ	1 fl. oz. or more.	
Pulvis Opii Compositus	2-5 gr.	
,, **Tragacanthæ Compositus**	20 gr. upwards.	

Mucilago Tragacanthæ. MUCILAGE OF TRAGACANTH.—Tragacanth, 60 gr.; water, 10 fl. oz. (B.P.). Tragacanth, 6; glycerine, 18; water up to 100 (U.S.P.).

B.P. Pulvis Tragacanthæ Compositus. COMPOUND POWDER OF TRAGACANTH.—Tragacanth, 1; gum acacia, 1; starch, 1; refined sugar, 3.

USES.—It is used to **suspend heavy powders,** such as subnitrate of bismuth, and is more efficacious than gum-arabic owing to the insoluble gum bassorin, which swells up when water is added. Also used in making lozenges, and emulsions of cod-liver oil.

Pterocarpi Lignum, B.P. RED SANDAL-WOOD.—The wood of *Pterocarpus santalinus.* Ceylon.

Santalum Rubrum, U.S.P. RED SAUNDERS.—The wood of *Pterocarpus santalinus.*

CHARACTERS.—The wood is in billets, chips, or powder. It resembles logwood in appearance, but is denser, and the cut surface is more glistening and of a deeper red colour.

COMPOSITION.—It contains a fine ruby colouring matter named santalin, which may be dissolved out by spirit, ether, acetic acid, &c. insoluble in water.

PREPARATION.

B.P.	DOSE.	U.S.P.
Tinctura Lavandulæ Composita	...½-2 fl. dr.	Not given.

USE.—It is used to give colour to the compound tincture of lavender, and through this to *Liquor arsenicalis.*

Kino, B. and U.S.P. KINO.—The inspissated juice obtained from incisions made in the trunk of *Pterocarpus marsupium.* Malabar.

CHARACTERS.—Small angular brittle glistening reddish-black fragments, translucent and ruby-red on the edges, inodorous, very astringent. When chewed it tinges the saliva blood-red.

COMPOSITION. — Kino-tannic acid and pyrocatechin, which differs very slightly from catechin, obtained from catechu. Through the action of kino-tannic acid, kino strikes a violet colour with ferrous salts, turning to green by exposure.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Pulvis Catechu Compositus (p. 866)	20-40 gr.	**Tinctura Kino**	½-2 fl. drm. (2-8 cc.)
,, **Kino** ,, (p. 761)	5-20 gr.		
Tinctura Kino	½-2 fl. dr.		
	(of powdered kino, 10-30 gr.)		

ACTION AND USES.—Kino has an **astringent** action both externally and internally. It is useful in relaxed sore-throat as a gargle. It is given internally in diarrhœa and in pyrosis. From its insolubility it is most useful when we desire an astringent action on the lower part of the intestinal canal, but when the astringency is required in the upper part it is not so useful as the more soluble astringents.

Balsamum Peruvianum, B. and U.S.P. BALSAM OF PERU.—A balsam obtained from *Myroxylon Pereiræ.* It exudes from the trunk of the tree after the bark has been scorched and removed. Salvador in Central America.

CHARACTERS.—A nearly black liquid, reddish-brown, and translucent in thin films; syrupy consistence, balsamic odour, and an acrid, slightly bitter taste.

COMPOSITION.—Contains resin, volatile oil, and both benzoic and cinnamic acids.

DOSE.—10 min. to ½ fl. drm., and upwards, made into an emulsion with mucilage or yolk of egg.

ACTION AND USES.—It is employed locally as a **parasiticide** in scabies and in cases of skin diseases depending on vegetable fungi. It destroys both the itch acarus and its eggs. It is much more agreeable than sulphur ointment. Before applying it, it is advantageous to take a warm bath, and wash the affected parts thoroughly with soft soap, and then to rub it well in all over the body, especially into the armpits, between the fingers, and on the inside of the thighs. It should be repeated every two or three days, during which time the same linen should be worn; this when cast off should be well disinfected, or the disease may return. It is also useful in prurigo, in pruritus, and in the later stages of an acute eczema. It is a useful **stimulant** to bed-sores and ulcers. It is given internally to lessen discharge from mucous membranes, as in bronchorrhœa, gleet, and leucorrhœa; also as a stimulating **expectorant** in chronic bronchitis.

Balsamum Tolutanum. B. and U.S.P. BALSAM OF TOLU.—A balsam obtained from *Myroxylon toluifera*. It exudes from the trunk of the tree after incisions have been made into the bark. New Granada.

CHARACTERS.—A soft and tenacious solid, with a fragrant balsamic odour; soluble in rectified spirit. The solution shows an acid reaction with test paper.

COMPOSITION.—Contains a resin, volatile oil, and free cinnamic and benzoic acids.

PREPARATIONS.

B.P.	DOSE.
Syrupus Tolutanus	1-3 fl. drm.
Tinctura Benzoini Composita	½-1 fl. drm.
,, Tolutana	½-1 fl-drm. (of the balsam, 10-30 gr.)

U.S.P.	DOSE.
Syrupus Tolutanus	1-3 fl. drm. (4-12 cc.)
Tinctura Tolutana	1-2 fl. drm. (4-8 cc.)

USES.—As a stimulating **expectorant** in chronic coughs. It should not be used while acute inflammation is present. The syrup covers well the taste of chloral or croton chloral.

Abrus. JEQUIRITY SEEDS, PRAYER BEADS, JUMBLE BEADS, GUMCHI, INDIAN LIQUORICE.—The seeds of *Abrus precatorius*. Not officinal.

CHARACTERS.—Small, hard seeds of a brilliant scarlet colour, with a black spot round the hilum. They contain a ferment, and the infusion when left for a short time swarms with bacteria.

ACTION.—When applied to the eye the infusion causes **inflammation** of the conjunctiva. The seeds are sometimes used to kill

cattle illegitimately. The seeds are moistened with water and rolled into small cylinders or needles with which the animal is stabbed, the point being left in the wound. The animal dies in a few hours. The seeds contain no alkaloid, and death is probably due to the **ferment** of the seeds causing micrococci and bacilli to develop in the blood in the same way as papain (p. 70).

USE.—An infusion is used to produce purulent ophthalmia in order to cure granular lids. The infusion is made by mixing the powdered seeds (3) with cold water (500), and adding hot water (500). This is filtered when cold. It is applied three times the first day, and repeated on the second or third day if necessary. An emulsion made by triturating the seeds with water and painted on with a brush is useful in unhealthy ulcers and lupus.

Physostigmatis Faba, B.P.; Physostigma, U.S.P. CALABAR BEAN.—The seed of *Physostigma venenosum*. Western Africa.



FIG. 150.—Calabar Bean (½ natural size).

CHARACTERS.—A kidney-shaped bean about an inch long, chocolate-coloured, shining, and with a broad black groove along the whole length of the convex edge. Internally the bean is white, and tastes like an edible bean.

COMPOSITION.—Contains two alkaloids—physostigmine or eserine, and calabarine.

DOSE.—Of the powdered bean 1 gr. gradually increased.

PREPARATIONS.

B.P.	DOSE.
Extractum Physostigmatis	$\frac{1}{15}$-$\frac{1}{4}$ gr.

U.S.P.	DOSE.
Extractum Physostigmatis	$\frac{1}{15}$-$\frac{1}{4}$ gr. (0·004-0·01 Gm.)
Tinctura Physostigmatis	12 min.

U.S.P. Physostigminæ Salicylas. SALICYLATE OF PHYSOSTIGMINE. $C_{15}H_{21}N_3O_2C_7H_6O_3$; 413.—The salicylate of an alkaloid prepared from physostigma.

CHARACTERS.—Colourless, shining, acicular, or short, columnar crystals, gradually turning reddish when long exposed to air and light, odourless, having a bitter taste, and a neutral reaction. Soluble in 130 parts of water, and in 12 parts of alcohol at 15° C. (59° F.); in 30 parts of boiling water, and very soluble in boiling alcohol. When heated on platinum foil, the salt is completely dissipated. The aqueous or alcoholic solution of the salt, when

exposed to light for a short time, turns reddish. On adding bicarbonate of sodium to the aqueous solution, shaking with ether, and evaporating the ethereal solution, an amorphous residue is obtained, having an alkaline reaction, and assuming, when dissolved for some time in water, a reddish colour, which disappears on the addition of sulphurous acid, but returns again as the latter evaporates. On concentrating the aqueous solution, which has been shaken with ether, to a small bulk, and supersaturating with sulphuric acid, a bulky, white precipitate is obtained which responds to the reactions of salicylic acid (see *Acidum Salicylicum*).

DOSE.—$\frac{1}{16}$ to $\frac{1}{12}$ gr.

PHYSIOLOGICAL ACTION.—It stimulates **muscular fibre,** both voluntary and involuntary, throughout the body, and paralyses the **nerve-centres.**

The alkaloids of Calabar bean have different actions, and different or even contradictory results may be obtained according to the amount of each present in the preparation of the bean employed. **Physostigmine** or eserine **paralyses** the nervous centres and stimulates muscular fibre, but **calabarine** causes **convulsions** like strychnine.

General Action.—A small dose of physostigma, from its action on the muscular fibres of the intestine, causes pain in the abdomen, with nausea and vomiting. From its action on the vagus and motor centres it causes a sense of oppression in the chest and weakness. With larger doses these symptoms become worse; and, in addition, contraction of the pupil, salivation, slowness of the pulse, and spasmodic respiration occur. Death is due to paralysis of respiration.

The excitability of the **muscles** is increased, so that they contract on the application of a slighter stimulus than usual, but their actual working power is not increased. In the first stage of poisoning in frogs muscular tremors are often apparent, and are also seen on the local application of the drug to the muscle of frogs. They are due to the local action of the drug on the intramuscular end-plates, for they occur when the sciatic nerve has been divided before poisoning, but cease after the injection of curare.

The **spinal cord** is paralysed; the posterior columns first and then the anterior columns. This action on the cord is the cause of the general paralysis induced by the drug. Convulsions like those of strychnine poisoning may occur. They are due to calabarine.

The **medulla** is paralysed, and respiratory movements cease before the reflex action of the spinal cord is destroyed.

The **motor nerves** in warm-blooded animals are not usually affected until very late, but in frogs they are paralysed gradually.

The **sensory nerves** are partially paralysed by the local application of physostigma in a concentrated form, but not when it is injected into the blood.

The **brain** in man seems not to be paralysed, for in a number of cases of poisoning, which occurred among children in consequence of eating the beans, consciousness was not impaired at all, and there were neither convulsions nor anæsthesia. Notwithstanding the absence of convulsions in these cases, however, physostigma appears to have an irritant action upon the brain, for when it is administered to epileptic patients, or to animals rendered epileptic by section of the sciatic nerve, it increases the number of fits (p. 156). Cats and guinea-pigs poisoned by it also show symptoms of great cerebral excitement, becoming very timid and running wildly about. This may be partly due to interference with the respiration, but can hardly be the only cause, as this condition is not observed in the case of other drugs which paralyse the respiration. In frogs the brain appears to be paralysed before the spinal cord, so that voluntary motion ceases before reflex action.

Action on the Eye.—When locally applied physostigma causes contraction of the pupil, diminishes intra-ocular tension, and causes spasm of accommodation, preceded by increased power of accommodation for near objects; often twitching of the eyelids and slight supra-orbital pain are observed. These effects are due either to stimulation of the fibres of the third nerve or of the circular muscular fibres of the iris; but are certainly not due to paralysis of the sympathetic, since stimulation of the sympathetic will, during the influence of the poison, cause dilatation of the pupil (p. 189).

Respiration is first quickened and then retarded. The acceleration is due to spasm of the bronchial tubes, according to some observers; but others consider it to be caused by stimulation of the ends of the vagi in the lungs (p. 210); and it is certain that if the vagi are first divided, physostigma no longer causes acceleration of respirations, but slows them from the first. The slowing of respiration is due to paralysis of the respiratory centre in the medulla. Death is the result of this failure of respiration.

Action on the Circulation.—Small doses sometimes cause a slight fall in blood-pressure, larger ones always cause a rise. This rise is chiefly due to the increased contractile power of the heart, but it is not improbable that it is aided by a contraction of the arterioles, the muscular fibres of which, like all other involuntary muscles in the body, are stimulated by the action of the physostigma upon them. According to von Bezold and Goetz the rise is also partly due to tetanic contraction of the intestinal walls, which drives the blood out of them. The irritability of the **vagus** appears to be increased, as a slighter stimulus applied to its trunk will stop the heart after its administration. We should therefore expect the normal stimuli passing to the vagus centre along sensory nerves from various parts of the body to have a greater effect upon the heart than usual, and thus render its beats slower. This seems to be the case, for physostigma causes slowness of the

pulse, which does not appear to depend upon direct stimulation of the vagus roots, as it is absent in animals which have been deeply chloralised before the administration of physostigma. In such animals physostigma, on the contrary, quickens the pulse and raises the blood-pressure.

Muscle.—When applied to the frog's heart it renders the pulsations slower and more powerful. Its stimulant action on the **cardiac muscular fibre** is so great that neither irritation of the vagus nor of the venous sinus can stop the heart. That the vagus is not paralysed is shown by the fact, that when the stimulant action of the physostigma on the muscular fibre is counteracted by a poison having a paralysing action on the muscle, such as a double salt of copper, stimulation of the vagus will again produce the stillstand in diastole.[1] In larger doses physostigma produces the staircase phenomenon (p. 270, and Fig. 16, p. 89), and finally imperfect stillstand in systole. The contracted ventricle still continues to pulsate slightly, and when it is distended by increasing the pressure of the fluid within it the pulsations become vigorous, and there is no tendency, as in the case of digitalis, to rapid paralysis of the cardiac muscle.

The action of the physostigma on the heart is counteracted by atropine, and, though to a less extent, the action of atropine is counteracted by physostigma (p. 435).

From its action on **involuntary muscle** it causes contraction of the **stomach,** retching, and vomiting. It causes also diarrhœa and increased peristaltic movements of the **intestines,** which finally end in tetanic contraction, so that the lumen of the intestine is almost obliterated, and it appears like a hard cord. It causes contraction of the **spleen, bladder,** and **uterus:** these contractions are not prevented by a dose of atropine sufficient to paralyse the nerves. The difference between the action of muscarine, which causes tetanic contraction of the intestine by acting on the nerves, and of physostigma, which produces a similar effect by acting on the muscular fibre, is seen when muscarine, atropine, and physostigmine are administered successively to an animal.[2] The muscarine first causes tetanic contraction. Atropine causes this to disappear, and produces complete relaxation, which is succeeded by a second tetanic contraction after the administration of physostigma. In consequence of its action on the bladder it causes **urination.**

Secretion is increased by physostigma not only in the salivary but in the sweat, lachrymal, and mucous glands. It seems probable that the secretion is not due, like that produced by muscarine, nicotine, or pilocarpine, to an action on the ends of the secreting nerves, but rather to the action of physostigma on the secreting **cells** themselves, because, unlike the secretion produced by the

[1] Harnack, *Buchheim's Arzneimittellehre*, 3te Aufl. p. 712.
[2] Schmiedeberg, *Arzneimittellehre*, p. 70.

three drugs already mentioned, it still persists after the administration of atropine. Physostigmine restores its excitability to the chorda tympani after its secretory fibres have been paralysed by atropine. When the dose of physostigma is large, the secretion of saliva which it occasions lasts only for a short time, because the vessels of the gland become so much contracted through the action of the physostigma that the circulation is insufficient to maintain the secretion (p. 313).

THERAPEUTICS.—It is used in certain diseases of the eye, *e.g.* wounds and ulcers of the cornea, and from its lessening intra-ocular tension it is used in glaucoma and staphyloma (p. 191). It removes dilatation of the pupil and paralysis of accommodation after the use of atropia, and, used alternately with atropia, breaks down adhesions after iritis (p. 192).

It is used in tetanus, strychnia poisoning, general paralysis of the insane, and mania, in paraplegia and in locomotor ataxy.

It is also useful in constipation due to atony of the intestinal walls.

It has been recommended in bronchitis, catarrh and dyspnœa when due to weakness of bronchial muscles (Ringer).

It is used as an antidote to atropine and also to strychnine.

TREATMENT IN POISONING BY PHYSOSTIGMA.—Evacuate the stomach by an emetic, and inject atropine (4 mins. of the liquor every ¼ hour) until the pulse quickens or the symptoms pass off. If the dose of atropine be too great, it seems to intensify the lethal action of the physostigma.

Hæmatoxyli Lignum, B.P.; Hæmatoxylon, U.S.P. LOGWOOD.—The heart-wood of *Hæmatoxylum campechianum*. Imported from Campeachy, Honduras, and Jamaica.

CHARACTERS.—The logs are heavy, hard, purplish-black externally, reddish-brown internally. The chips have often a greenish lustre, they have a feeble agreeable odour, and sweetish taste; a small portion chewed imparts to the saliva a dark pink colour.

COMPOSITION.—The colouring principle of logwood is a crystalline substance, hæmatoxylin. It is soluble in hot water or in alcohol. Logwood also contains tannic acid, which imparts to it its astringent properties.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Decoctum Hæmatoxyli	1-2 fl. oz.	Extractum Hæmatoxyli.	10-30 gr. (0·65-1·95 Gm.)
Extractum ,,	10-30 gr.		

B.P. Decoctum Hæmatoxyli. DECOCTION OF LOGWOOD.—Logwood, in chips, 1 oz.; cinnamon bark, in coarse powder, 60 gr.; distilled water, 1 pint.

Boil the logwood in the water for ten minutes in a covered vessel, adding the cinnamon towards the end. Strain the decoction, and pour as much distilled water over the contents of the strainer as will make the strained product measure a pint.

USES.—It is a useful **astringent** in diarrhœa, especially in children. Its great disadvantage is the stain which it imparts to

clothing. For the diarrhœa of phthisis, decoctum hæmatoxyli with acidum sulphuricum aromaticum is a good prescription. It is also used in dysentery and in atonic dyspepsia.

U.S.P. Chrysarobinum. CHRYSAROBIN.—A mixture of proximate principles (commonly misnamed chrysophanic acid), extracted from goa powder, a substance found deposited in the wood of the trunk of *Andira Araroba*.

CHARACTERS.—A pale orange-yellow crystalline powder, permanent in the air, odourless and tasteless, almost insoluble in water, only slightly soluble in alcohol, readily soluble in ether and in boiling benzol. When heated to about 162° C. (323° ·6 F.), it melts, and may be partially sublimed. On ignition it is wholly dissipated. In solutions of alkalis it is soluble with a yellowish-red or reddish-yellow colour, which is changed to red by passing air through the liquid. Sulphuric acid dissolves it with a deep blood-red colour; on pouring the solution into water, the substance separates again unchanged.

DOSE.—$\frac{1}{6}$ to $\frac{1}{2}$ gr. (·01-·03 Gm.) per diem in water.

PREPARATION.

Unguentum Chrysarobini. Chrysarobin Ointment (Chrysarobin 10, benzoated lard 90).

USES.—It is used in psoriasis and parasitic affections of the **skin.** It may be simply applied to the skin moistened with vinegar or saliva, or used in the form of ointment. It should never be applied to the head, as it may cause œdema of the face. It colours both the skin and clothing, and it is better not to use it over too large a surface at a time as it may cause much irritation. It may also be given internally in eczema, impetigo, acne, psoriasis, urticaria, and other skin diseases.

LEGUMINOSÆ; CÆSALPINIÆ.

Senna, U.S.P. SENNA.—The leaflets of *Cassia acutifolia* (Alexandrian senna), and of *Cassia elongata* (Indian senna).

Senna Alexandrina, B.P. ALEXANDRIAN SENNA.—The leaflets of *Cassia lanceolata* and *C. obovata*. Imported from Alexandria; carefully freed from the flowers, pods, and leaf-stalks of the same, and from the leaves, flowers, and fruit of *Solenostemma Argel*.

CHARACTERS.—Lanceolate or obovate leaflets, about an inch long, *unequally oblique at the base*, brittle, greyish-green, of a faint peculiar odour, and mucilaginous sweetish taste.

Senna Indica, B.P. TINNEVELLY SENNA.—The leaflets of *Cassia elongata* (*Cassia angustifolia*). Southern India.

CHARACTERS.—About two inches long, lanceolate, acute, unequally oblique at the base, flexible, entire, green, without any

admixture; odour and taste those of Alexandrian senna, in place of which it may be used.

COMPOSITION.—The properties of senna are due principally to a glucoside cathartic acid, which, when isolated, is powerfully purgative.

ADULTERATION.—*Solenostemma Argel.*



FIG. 151.—Alexandrian Senna.



FIG. 152.—Indian Senna.

TEST.—Senna leaves have always an unequally oblique base, and are free from bitterness. Other leaves are equally oblique at the base.

PREPARATIONS.

B.P.	DOSE.
Confectio Sennæ	60-120 gr.
Infusum ,,	1-2 fl. oz.
Mistura ,, Composita	1-1½ fl. oz.
Syrupus ,,	1 fl. drm. upwards.
Tinctura ,,	1 fl. drm. to ½ fl oz.
Pulvis Glycyrrhizæ Compositus	30-60 gr.

U.S.P.	DOSE.
Confectio Sennæ	60-120 gr.
Extractum Sennæ Fluidum	1 fl. drm. (4 cc.)
Infusum Sennæ Compositum	2½ fl. oz. (75 cc.)
Pulvis Glycyrrhizæ Compositus	30-60 gr. (2-4 Gm.)
Syrupus Sarsaparillæ Compositus	1-4 fl. drm. (4-16 cc)
Syrupus Sennæ	1-4 fl. drm. (4-16 cc.)

Confectio Sennæ. CONFECTION OF SENNA.—Senna, in fine powder, 7; coriander, 3; figs, 12; tamarind, 9; cassia pulp, 9; prunes, 6; extract of liquorice, ¾; refined sugar, 30; distilled water, 90 (B.P.). Senna, 10; coriander, 6; cassia fistula, 16; tamarind, 10; prunes, 7; figs, 12; sugar, 50; water, 60 (U.S.P.).

B.P. Infusum Sennæ. INFUSION OF SENNA.—Senna, 1 oz.; ginger, sliced, 30 gr.; boiled distilled water, 10 fl. oz.

U.S.P. Infusum Sennæ Compositum. COMPOUND INFUSION OF SENNA. BLACK DRAUGHT.—Senna, 6; manna, 12; sulphate of magnesium, 12; fennel, 2; boiling water, 100. Macerate, strain and make up to 100 with water.

B.P. Mistura Sennæ Composita. COMPOUND MIXTURE OF SENNA.—Sulphate of magnesia, 4 oz.; extract of liquorice, ½ oz.; tincture of senna, 2½ fl. oz.; compound tincture of cardamoms, 10 fl. drm.; infusion of senna, up to 1 pint.

Pulvis Glycyrrhizæ Compositus. COMPOUND LIQUORICE POWDER, B. and U.S.P.—Senna, 2; liquorice root, 2; sugar, 6 (B.P.) Senna, 18; liquorice, 16; fennel, 8; washed sulphur, 8; sugar, 50 (U.S.P.). The powder of the U.S.P. resembles that of the German Pharmacopœia, and is much better than that of the B.P.

Syrupus Sennæ, B. and U.S.P. SYRUP OF SENNA.—Senna, 16 oz.; oil of coriander, 3 min.; refined sugar, 24 oz.; distilled water, 5 pints, or a sufficiency; rectified spirit, 2 fl. oz.; distilled water, up to 2 lb. 10 oz. (B.P.). Senna, 33; sugar, 60; alcohol, 4; oil of coriander, 1; water up to 100 (U.S.P.).

B.P. Tinctura Sennæ. TINCTURE OF SENNA.—Senna, 2½ oz.; raisins, 2 oz.; caraway fruit, ½ oz.; coriander fruit, ½ oz.; proof spirit, 1 pint.

ACTION AND USES.—Senna acts as a **laxative** or brisk purgative, according to the dose. It acts chiefly on the small intestines, and increases both peristalsis and the secretion. It is frequently

combined with other purgatives. A useful remedy in constipation is Mistura Sennæ Co., where we have senna combined with sulphate of magnesia. In habitual constipation, the most convenient preparation, perhaps, is Pulvis Glycyrrhizæ Co., U.S.P., which contains sulphur and fennel-seeds in addition to the constituents of the B.P. powder. One drachm taken regularly at bedtime will generally keep the bowels regularly open without acting too violently. The sulphur in this preparation is in such small quantity that it might seem useless; but in a number of experiments which I made on small quantities (about $\frac{1}{4}$ grain) of sulphur many years ago, I found that they caused an increase of flatus in the intestine which appeared to facilitate the expulsion of its contents.

Cassia Fistula. PURGING CASSIA. U.S.P.—The fruit of *Cassia fistula.*

Cassiæ Pulpa, B.P. CASSIA PULP, B.P.—The pulp obtained from the pods of the purging cassia, *Cassia fistula.*

CHARACTERS.—Blackish-brown, viscid, sweet in taste, and somewhat sickly in odour; usually containing the seeds and dissepiments.

COMPOSITION.—Sugar, with albuminoid matter.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Sennæ.....	60-120 gr. (of cassia pulp, 120 gr. or more).	Confectio Sennæ.....	1-2 drm. (4-8 Gm.)

USE.—A simple **laxative** in doses of 120 gr. upwards. Seldom given alone.

Tamarindus, B. and U.S.P. TAMARIND.—The preserved pulp of the fruit of *Tamarindus indica.* West Indies.

CHARACTERS.—A reddish-brown, sweetish, subacid pulp, preserved in sugar, containing strong fibres, and brown shining seeds each inclosed in a membranous coat.

COMPOSITION.—The pulp contains citric, tartaric, and acetic acids, chiefly in combination with potash. Grape sugar is also present.

IMPURITY.—Traces of copper.

TEST.—A piece of bright iron left in contact with the pulp for an hour does not exhibit any deposit of copper.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Sennæ.....	60-120 gr. (of tamarind, $\frac{1}{4}$ oz. upwards).	Confectio Sennæ...	1-2 drm. (4-8 Gm.)

USES.—Tamarind, in doses of $\frac{1}{4}$ oz. upwards, is both a **laxative** and **refrigerant.** The pulp is said to weaken the action of resinous cathartics in general, but it is frequently prescribed with them, and is used in the form of compressed tablets, called "Tamar

Indien," as a vehicle for the administration of some purgative, probably jalap. A cooling and agreeable drink (tamarind whey) may be made by adding 4 parts of the pulp to 100 of boiling milk, straining and filtering.

Copaiba, B. and U.S.P. COPAIVA, B.P.; BALSAM OF COPAIBA, U.S.P.—The oleo-resin obtained from incisions made in the trunk of *Copaifera multijuga* B.P. (*Copaifera Langsdorfii*, U.S.P.), and other species of Copaifera. Valley of the Amazon.

CHARACTERS.—A more or less viscid liquid, about the consistence of olive oil, light yellow, transparent, with a peculiar odour and a persistently bitter and acrid taste.

COMPOSITION.—Copaiva consists of a solution of several resins in a volatile oil. The resins consist chiefly of crystallisable copaivic acid.

IMPURITIES.—Wood oil, or gurjun balsam, and fixed oils, especially castor oil, fraudulently added.

TESTS.—Perfectly soluble in an equal volume of benzol. Does not become gelatinous after having been heated to 270°. Is not fluorescent (wood oil). After heating on paper it does not leave a greasy ring round the stain (fixed oil).

The absence of turpentine is shown by the smell of it not being given off on heating, and after distilling off the volatile oil the residue, when cool, should be hard and friable (absence of fixed oils). The essential oil distilled off from the oleo-resin, when rectified, should not begin to boil below 200° C. (392° F.). On adding 1 drop of copaiba to 19 drops of disulphide of carbon, and shaking the mixture with 1 drop of a cold mixture of equal parts of sulphuric and nitric acids, it should not acquire a purplish red or violet colour (absence of gurjun balsam).

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Oleum Copaibæ	5-20 min.	Massa Copaibæ	10 30 gr.

U.S.P. Massa Copaibæ. MASS OF COPAIBA.—Copaiba, 94; magnesia recently prepared, 6; mix and set aside till it concretes into a pilular mass. If it does not concrete in eight or ten hours, there is deficiency of water in the copaiba. This may be remedied in subsequent operations by shaking the copaiba with one-twentieth of its weight of water and decanting after the uncombined water has subsided. The mass is divided while fresh into pills weighing 5 gr. (0·33 Gm.) each.

Oleum Copaibæ, B. and U.S.P. OIL OF COPAIVA.—A volatile oil distilled from copaiva.

CHARACTERS.—Colourless or pale yellow, with the odour and taste of copaiva.

DOSE.—Of copaiva, 15 min. to 1 fl. drm.; of oil of copaiba, 5 min. to 20 min.; of the resin (as a diuretic), 15 to 20 gr. in almond emulsion.

Copaiva may be taken mixed with yolk of egg, or floating upon water or some other liquid, or made into pills with burnt magnesia; or, lastly, dissolved in water by the aid of liquor potassæ,

with which it forms a soap. Sometimes, to hide its disagreeable taste, it is put into membranous or gelatinous capsules.

ACTION.—Copaiva has a stimulating action on **mucous membranes,** especially that of the lungs and genito-urinary tract. It is diuretic. Large doses have an **irritant** action, causing vomiting and purging. It is **excreted** by the kidneys and lungs, and may be recognised by its characteristic odour. It is very apt to produce an **eruption** of the skin, generally in the form of rose-coloured spots resembling a syphilitic eruption, but distinguished from it by its affecting chiefly the backs of the arms and legs, by coming on suddenly, and by the intense itching with which it is accompanied. Sometimes it resembles urticaria more in its appearance, but rarely it is eczematous. Copaiba forms a conjugate glycuronic acid in the system, and is eliminated in the urine, which, with nitric acid, gives a precipitate of copaibic acid easily mistaken for albumen, but distinguished by disappearing on the application of heat. The conjugate acid renders the urine antiseptic as it is secreted by the kidneys, so that it does not readily decompose, and bacteria either do not appear in it at all or only in very small numbers, even after the surface has become covered with mould. It is probable that the utility of the drug in diseases of the bladder and urethra is due to the washing out of the urinary passages by the antiseptic urine (p. 392).

USES.—Copaiba is employed in diseases of the mucous membranes, and especially of the genito-urinary passages, the lungs, and, along with digitalis, in cardiac dropsy. It is also useful in chronic bronchitis and bronchorrhœa. Its great disadvantage is its nauseous smell and taste. It is chiefly used in gonorrhœa. It is inadvisable to use it when the inflammation is acute and severe, but it is exceedingly useful after the acuteness of the inflammation has subsided. It is not so useful in gleet. It appears to be of service in chronic cystitis. The resin is a good diuretic, especially in cases of dropsy depending on disease of the liver, where the kidneys are healthy.

Piscidia Erythrina. JAMAICA DOGWOOD.—The part used is the bark. Not officinal.

PREPARATION.	DOSE.
Extractum Piscidiæ Erythrinæ Fluidum	20 min.—2 fl. dr.

ACTION.—It has been employed for stupefying and catching fish. It is a **narcotic** not only to fish but to frogs, rabbits, and man. It lessens reflex action at first, by stimulation of Setschenow's centres (p. 135), and afterwards produces tetanus by stimulation of the **spinal cord.** It stimulates the vaso-motor centre, raises **blood-pressure,** and slows the **pulse.** It dilates the **pupil.** It increases the secretion of the **skin** and **saliva.**

USE.—It is employed as a narcotic instead of opium.

MIMOSEÆ.

Acaciæ Gummi, B.P.; Acacia, U.S.P. GUM ACACIA, B.P.; GUM ARABIC, U.S.P.—A gummy exudation from *Acacia Verek*, and from other species of Acacia.

CHARACTERS.—In roundish tears usually from half an inch to an inch in length, nearly colourless, brittle, and opaque from numerous minute cracks,—or in angular fragments with shining surfaces. Bland and mucilaginous in taste; insoluble in alcohol, but soluble in water. The aqueous solution forms with subacetate of lead an opaque white jelly.

COMPOSITION.—Arabin or arabic acid (gummic acid) combined with calcium, and, in smaller quantities, with potassium and magnesium.

IMPURITY.—Starch fraudulently added.

TEST.—Should not give a blue colour with iodine.

PREPARATIONS CONTAINING GUM ACACIA.

B.P.	DOSE.	U.S.P.	DOSE.
Mistura Creta	1-2 fl. oz.	**Mucilago Acaciæ**	ad lib.
,, Guaiaci	½-2 fl. oz.	**Syrupus Acaciæ**	,,
Mucilago Acaciæ	ad lib.		
Pulvis Amygdalæ Compositus	60-120 gr.		
,, Tragacanthæ ,,	20-60 gr.		
Trochisci, in all.			

USES.—Is a useful **demulcent** in coughs or sore throat, also in irritation of the stomach and intestines due to catarrhal inflammation. It is also serviceable in cases of irritant poisoning, and it has been employed as a masticatory. The mucilage is used to **suspend powders.**

U.S.P. Catechu. CATECHU.—An extract prepared from the wood of *Acacia Catechu*. Pegu.

CHARACTERS.—In dark brown, irregular masses, containing fragments of leaves, brittle, somewhat porous and glossy when freshly broken; soluble in alcohol and partly soluble in water. It is nearly inodorous, and has a strongly astringent and sweetish taste.

It was formerly officinal in the B.P. It is sometimes called black catechu to distinguish it from the pale catechu got from *Uncaria Gambier*.

COMPOSITION.—It contains a form of tannic acid called catechu-tannic acid. This differs from other forms of tannic acid in not being a glucoside. It gives a greenish-black with iron, and precipitates gelatine but not tartar emetic.

PREPARATIONS.

U.S.P.	DOSE.
Tinctura Catechu Composita	15 min.-2 fl. drm. (2-8 cc.)
Trochisci Catechu (1 grain in each)	ad. lib.

Tinctura Catechu Composita. COMPOUND TINCTURE OF CATECHU.—Catechu, 12; cinnamon, 8; diluted alcohol to 100.

USES.—It is a powerful **astringent.** It may be employed as an injection in gonorrhœa and gleet. The lozenges are useful in sore throat, hoarseness, relaxed uvula, and the tickling cough consequent on it (p. 213). Internally it is useful in diarrhœa, and in internal hæmorrhages, especially from the uterus (*vide* also p. 866).

Erythrophlœum. CASCA BARK, SASSY BARK. Not officinal. —The bark of *Erythrophlœum Guïnense,* a large tree growing on the coast of Africa.

COMPOSITION.—It contains an alkaloid, erythrophlœine.

(Not officinal.) PREPARATION.

	DOSE.
Tinctura Erythrophlœi...(1 in 10)	5-10 min.

ACTION.—The powder when inhaled causes violent sneezing. Internally the infusion or tincture causes vomiting and purging. Erythrophleum has an action on the circulation (p. 232) and kidneys **like** that of **digitalis** (p. 377). The alkaloid appears to combine the actions of digitalin and picrotoxin, producing convulsions like the latter. (Harnack).

USES.—I have found it useful in dilated heart without valvular disease. It is also useful in mitral disease and dropsy. It has the disadvantage of disturbing the digestion still more readily than digitalis.

Indigo, B.P. C_8H_5NO. — A blue pigment prepared from various species of Indigofera.

PREPARATION.—Solution of sulphate of indigo.

USE.—As a test for chlorine.

ROSACEÆ.

POMEÆ.

U.S.P. Cydonium. CYDONIUM. QUINCE SEED.—The seed of *Cydonia vulgaris.*

CHARACTERS.—About a quarter of an inch (6 millimetres) long, oval or oblong, triangularly compressed, brown, covered with a whitish mucilaginous epithelium, causing the seeds of each cell to adhere. With water the seeds swell up, and form a mucilaginous mass. The unbroken seeds have an insipid taste.

COMPOSITION.—It contains a large amount of mucilage.

PREPARATION.

	DOSE.
Mucilago Cydonii (cydonium 2, water 100, macerate for half an hour, and strain through muslin)	ad lib.

USE.—It is useful as a bland **demulcent** preparation to relieve irritation of mucous surfaces.

DRYADEÆ.

U.S.P. Rubus. RUBUS. BLACKBERRY.—The bark of the root of *Rubus villosus*, *Rubus canadensis*, and *Rubus trivialis*.

CHARACTERS.—In thin, tough, flexible bands, outer surface blackish or blackish-grey, inner surface pale brownish, sometimes with strips of whitish, tasteless wood adhering; inodorous; strongly astringent, somewhat bitter.

PREPARATION.

U.S.P.	DOSE.
Extractum Rubi Fluidum	30-60 gr.

USES.—It is a pleasant **astringent,** its efficacy being due to tannin. It is useful in the diarrhœa of children, and also in adults.

U.S.P. Rubus Idæus. RASPBERRY.—The fruit of *Rubus idæus*.

CHARACTERS.—Deprived of the conical receptacle and therefore hollow at the base; hemispherical, red, finely hairy, composed of from twenty to thirty coalesced small drupes, each one crowned with the withered style; juice red; of an agreeable odour and pleasant acidulous taste.

The closely allied, light red fruit of *Rubus strigosus*, and the purplish-black fruit of *Rubus occidentalis*, may be employed in place of the above.

PREPARATION.

	DOSE.
Syrupus Rubi Idæi	ad lib.

USE.—To give mixtures an agreeable colour and **flavour.**

ROSEÆ.

Oleum Rosæ, U.S.P. OIL OF ROSE.—A volatile oil distilled from the fresh flowers of *Rosa damascena*.

CHARACTERS.—Pale yellowish, strong odour of rose, sweetish taste.

ADULTERATIONS.—Sandal wood oil, geranium oil, and other volatile oils; fixed oils; spermaceti.

TEST.—When slowly cooled to near 10° C. (50° F.) the oil becomes a transparent solid, interspersed with numerous slender shining iridescent scale-like crystals. When rapidly cooled to 12°·5 C. (54°·5 F.) it congeals to a solid mass of light feathery shining scales or plates.

Rosæ Centifoliæ Petala, B.P.; Rosa Centifolia, U.S.P. CABBAGE-ROSE PETALS, B.P.; PALE ROSE, U.S.P.—The fresh petals, fully expanded, of *Rosa centifolia*.

CHARACTERS.—Pink, fragrant roseate odour; taste sweetish-bitter, and faintly astringent; both readily imparted to water.

COMPOSITION.—A minute quantity of volatile oil, a red colouring matter, a little gallo-tannic acid, fat, sugar, acids, &c.

PREPARATION.

B.P.	DOSE.
Aquæ Rosæ	ad lib.

U.S.P.	DOSE.
Aqua Rosæ	ad lib.
Syrupus Sarsaparillæ Compositus	1-4 fl. drm. (30-118·4 cc.)

U.S.P. Unguentum Aquæ Rosæ. OINTMENT OF ROSE WATER (COLD CREAM).—Expressed oil of almond, 50; spermaceti, 10; white wax, 10; rose water, 30.

USES.—Rose-water is much used as a **vehicle** for gargles and lotions, and sometimes it is used for internal administration.

Rosæ Gallicæ Petala, B.P.; Rosa Gallica, U.S.P. RED-ROSE PETALS, B.P.; RED ROSE, U.S.P.—The fresh and dried petals of *Rosa gallica*, collected before expanding.

CHARACTERS.—Small cones consisting of numerous imbricated deep purple petals, roseate odour, bitterish, astringent taste.

COMPOSITION.—Similar to cabbage rose petals.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Rosæ Gallicæ	60 gr. or more.	Pilulæ Aloes et Mastiches	1 pill.
Infusum Rosæ Acidum	1-2 fl. oz.	**Confectio Rosæ**	ad lib.
Syrupus Rosæ Gallicæ	1 fl. drm. or more.	**Extractum Rosæ Fluidum**	,,
		Mel Rosæ	,,
		Syrupus Rosæ	,,

B.P. Infusum Rosæ Acidum. ACID INFUSION OF ROSES.—Dried red-rose petals, broken up, ¼ oz.; diluted sulphuric acid, 1 fl. drm.; boiling distilled water, 10 fl. oz.

B.P. Rosæ Caninæ Fructus. FRUIT OF THE DOG-ROSE. HIPS.—The ripe fruit of the dog-rose, *Rosa canina*, and other indigenous allied species.

CHARACTERS.—An inch or more in length, ovate, scarlet, smooth, shining; taste sweet, subacid.

COMPOSITION.—Crystallisable sugar, gum, citric and malic acids free and combined.

PREPARATION.

B.P.	DOSE.
Confectio Rosæ Caninæ	60 gr. or more.

USES.—The preparations of roses are used chiefly as **vehicles.** The Confectio Rosæ Gallicæ and Confectio Rosæ Caninæ are used as a basis for pills, and also for linctus. The acid infusion of roses is used as a gargle, and is slightly astringent. Aqua Rosæ is used as a vehicle.

Cusso, B.P.; Brayera, U.S.P. KOUSSO, B.P.; KOOSO, U.S.P.—The female inflorescence of *Brayera anthelmintica* (*Hagenia abyssinica*). Abyssinia.

CHARACTERS.—In bundles, rolls, or compressed clusters consisting of panicles about 10 inches (25 centimetres) long. Flowers small, reddish-brown, on hairy stalks. Odour slight, tea-like, taste bitter and nauseous.

COMPOSITION.—Tannic acid; a bitter acrid resin and some volatile oil and kosin or kousseïn. Kosin is the active principle of of the drug. It is a crystalline substance with an acid reaction. Kousseïn is a resinoid substance, and consists of impure kosin.

PREPARATIONS.

B.P.	DOSE.
Infusum Cusso	4-8 fl. oz.
U.S.P.	**DOSE.**
Infusum Brayeræ	8 fl. oz. (236 cc.)
Extractum ,, Fluidum	20-40 min. (1·25-2·50 cc.)

B.P. Infusum Cusso. INFUSION OF KOUSSO.—Kousso, in coarse powder, ½ oz.; boiling distilled water, 8 fl. oz. Infuse in a covered vessel for fifteen minutes without straining.

U.S.P. Infusum Brayeræ. INFUSION OF BRAYERA.—Brayera in No. 20 powder, 6; boiling water, 100. Pour the boiling water on the brayera and let it macerate in a covered vessel until cool. This infusion should be dispensed without straining.

ACTION AND USE.—Cusso is used as an **anthelmintic** for tapeworm. Kosin or coussine, which is the active principle, administered in 20 gr. doses acts quite as well as the infusion, and has not the disadvantage of producing nausea and vomiting which are sometimes caused by the infusion of the pharmacopœias.

U.S.P. Quillaia. QUILLAIA. SOAP BARK.—The bark of *Quillaia Saponaria.* Chili.

CHARACTERS.—Flat, large pieces, about one-fifth of an inch (5 millimetres) thick; outer surface brownish-white, often with small patches of brown cork attached, otherwise smooth; inner surface whitish, smooth; fracture splintery, checkered with pale brownish bast-fibres embedded with white tissue; inodorous, very acrid and sternutatory.

COMPOSITION.—It contains a glucoside, saponin. Saponin is also contained in senega and sarsaparilla. It appears to be identical with cyclamin from *Cyclamen europæum* and with primulin from *Primula officinalis.* Digitonin from digitalis appears to be a kind of saponin differing somewhat from the others.

ACTION AND USES.—The bark has little or no application in medicine. The powder when snuffed provokes sneezing. Its infusion and extract are used for cleaning cloth and taking out stains. On account of the saponin it contains, the infusion froths easily and the froth remains long. A little of it is sometimes added to syrups, lemonade, or other drinks, to give them a head. It also retains fine powders in suspension and forms **emulsions.** It is used to form an emulsion with coal-tar.

Saponin when applied locally acts as a powerful irritant, local anæsthetic, and muscular poison. On account of its **local irritant**

action, it produces most intense pain when injected subcutaneously; sneezing when applied to the nose; vomiting, diarrhœa, and gastro-enteritis when taken internally in large doses. Locally applied it paralyses nerves both sensory and motor, and muscular fibre both voluntary and involuntary. It therefore produces **local paralysis** and **local anæsthesia** when injected under the skin in a frog's leg. The muscles and motor nerves being paralysed, no irritation to either will cause contraction; and the sensory nerves being also paralysed, local irritation does not produce reflex action. In the voluntary **muscles** it produces a condition of *rigor mortis*, and the muscular substance becomes brittle and structureless as after myositis.

When locally applied to the **intestine,** either by internal administration or injection into the peritoneal cavity, it paralyses the involuntary muscular fibre of the intestinal wall. When applied to the **heart** it causes rapid stoppage in diastole. It **counteracts** the effect of **digitalis** on the heart, and *vice versâ* digitalis counteracts the effect of saponin on the heart, so that when the ventricle of the frog's heart has been brought to a standstill by one of these drugs, its pulsations may be restored by the other.

When absorbed into the circulation, saponin paralyses the **nerve centres** in addition to the nerves and muscular structures. The symptoms it produces depend on the mode in which it is introduced into the body and the structures which it first reaches in consequence. If injected into the jugular vein so as to reach the heart first, it usually kills by producing cardiac paralysis, with slow pulse, and rapid fall of blood-pressure, and convulsions which are probably asphyxial and due to the failure of circulation (p. 204), respiratory movements still continuing. Saponin also paralyses the respiratory and vaso-motor centres, so that the blood-pressure falls much and the respirations become feeble and slow. In large doses saponin may paralyse the respiratory centre before the heart, so that death ensues from failure of the respiration while the heart continues to beat.

It is possible that quillaia might be used instead of sarsaparilla, and it might perhaps be useful in cases of aortic disease with hypertrophy (p. 295).

AMYGDALEÆ.

Amygdala Dulcis, B. and U.S.P. SWEET ALMOND.—The seed of the sweet almond tree, *Amygdalus communis*, var. *dulcis* (*Prunus amygdalus*). Malaga.

CHARACTERS.—Above an inch in length, lanceolate, acute, with a clear cinnamon-brown seed-coat, with a bland sweetish kernel. Does not evolve the odour of bitter almonds when bruised with water.

COMPOSITION.—Contains upwards of 50 per cent. of a fixed oil which consists principally of oleic acid. It contains also an

albuminous substance—emulsin, which is supposed to be produced from a vegetable casein and asparagin.

PREPARATIONS.

B.P.	DOSE.
Oleum Amygdalæ	1 fl. dr. to ½ fl. oz.
Pulvis Amygdalæ Compositus (almonds 8, sugar 4, gum acacia 1)	60 gr. to 120 gr.
Mistura Amygdalæ (2½ oz. of Pulv. Amygd. Co. to 1 pint)	1-2 fl. oz.

U.S.P.	DOSE.
Mistura Amygdalæ	2 fl. dr.-1 fl. oz. (4-16 cc.)
Syrupus Amygdalæ	2 fl. dr.-1 fl. oz. (4-16 cc.)

Amygdala Amara, B. and U.S.P. BITTER ALMOND.—The seed of the bitter almond tree, *Amygdalus communis* (*Prunus amygdalus*), var. *amara*. Mogadore.

CHARACTERS.—Resembles the sweet almond in appearance, but is rather broader and shorter; has a bitter taste, and when rubbed with a little water, emits the odour of hydrocyanic acid.

COMPOSITION.—Bitter almonds contain all the constituents of sweet almonds, the fixed oil, however, being in less proportion, and in addition a glucoside amygdalin upon which emulsin (either of sweet or bitter almonds) acts as a ferment producing hydrocyanic acid and volatile oil of bitter almonds, thus:—

Amygdalin. Bitter almond oil. Glucose.

$$C_{20}H_{27}NO_{11} + 2H_2O = HCN + C_7H_6O + C_{12}H_{24}O_{12}$$

Ammonia and formic acid are also produced in the decomposition. Amygdalin may be extracted by alcohol, and is not poisonous. Emulsin by boiling loses its property of decomposing amygdalin.

PREPARATIONS.

B.P.	DOSE.
Oleum Amygdalæ	1 fl. drm.-½ fl. oz.

U.S.P.	DOSE.
Syrupus Amygdalæ	2 fl. drm.-2 fl. oz. (4-60 cc.)

Oleum Amygdalæ, B.P.; Oleum Amygdalæ Expressum, U.S.P. ALMOND OIL, B.P.; EXPRESSED OIL OF ALMOND, U.S.P.—A fixed oil expressed from bitter and sweet almonds.

CHARACTERS.—Pale yellow, nearly inodorous or having a nutty odour, with a bland oleaginous taste.

PREPARATIONS.

B.P.	U.S.P.
Unguentum Cetacei.	Unguentum Aquæ Rosæ.
,, Hydrargyri Oxidi Rubri.	
,, Plumbi Subacetatis Compositum.	
,, Simplex, and the preparations containing it.	

U.S.P. Oleum Amygdalæ Amaræ. OIL OF BITTER ALMOND.—A volatile oil obtained from bitter almonds by maceration with water, and subsequent distillation.

CHARACTERS.—A colourless or yellowish thin liquid of a peculiar aromatic odour, a bitter and burning taste and a neutral reaction.

PREPARATION.

	DOSE.
Aqua Amygdalæ Amaræ (oil of bitter almond 1, water 999)	2 fl. drm. (7·5 cc.)

USES.—The fixed oil is **demulcent.** It is applied externally to chapped hands and slight excoriations, also to the ear in earache. Internally, in doses of 1 drachm to 2 drachms, it is a mild laxative. The cake left after expression of the bland oil from sweet almonds contains no starch, and is therefore employed instead of bread in diabetes. The oil of bitter almonds is used as a flavouring agent. The **crude oil** of the U.S.P. **contains hydrocyanic acid** and may be used instead of it as a local application in pruritus, and also for external administration. It retains its strength better than pure hydrocyanic acid, but its disadvantage is that the proportion of the acid is not constant. It may be given in doses of $\frac{1}{4}$ to 1 minim cautiously increased.

Prunum, B. and U.S.P. PRUNE.—The dried drupe of the plum, *Prunus domestica.* Southern Europe.

CHARACTERS.—Oblong, shrivelled, blackish-blue.

COMPOSITION.—Malic acid, with saccharine and albuminoid matter.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Sennæ	1–2 dr. (of prunes, 2 oz. or more).	Confectio Sennæ	1–2 dr.

USE.—Stewed prunes form a useful and pleasant laxative for children or adults. If they do not move the bowels when simply stewed, they may be stewed along with senna, which does not impart to the prunes any unpleasant taste, and children will still take them readily.

U.S.P. Prunus Virginiana. WILD CHERRY.—The bark of *Prunus serotina* (*Cerasus serotina*) collected in autumn.

CHARACTERS.—In curved pieces or irregular fragments, one-twelfth of an inch (two millimetres) or more thick, outer surface greenish-brown, or yellowish-brown, smooth and somewhat glossy, marked with transverse scars; if collected from old wood and deprived of corky layer, the outer surface is nut-brown and uneven inner surface somewhat striate or fissured. Upon maceration in water it develops a distinct bitter-almond odour; its taste is astringent, aromatic, and bitter.

The bark of the small branches is to be rejected.

PREPARATIONS.

	DOSE.
Extractum Pruni Virginianæ Fluidum	30-60 min. (2-4 cc.)
Infusum ,, ,, ,,	2-3 fl. oz. (60-180 cc.)
Syrupus ,, ,, ,,	1-4 fl. drm. (4-16 cc.)

USES.—A nervous **sedative** and **tonic,** used in atonic dyspepsia and general debility, associated with general or local irritation. In large doses it renders the action of the heart slow. It has been employed in hectic fever and consumption.

B.P. Laurocerasi Folia. CHERRY-LAUREL LEAVES.—The fresh leaves of *Prunus laurocerasus.* The common or cherry laurel.

CHARACTERS.—Ovate-lanceolate or elliptical, distantly toothed, furnished with glands at the base, smooth and shining, deep green, on strong short footstalks; emitting a ratafia odour when bruised.

COMPOSITION.—By distillation the leaves yield bitter almond oil and hydrocyanic acid.

PREPARATION.

	DOSE.
Aqua Laurocerasi	5-30 min.

ACTION.—Similar to **hydrocyanic acid,** but less certain, owing to its variable strength.

USE.—Cherry-laurel water is supposed to be an elegant mode of giving prussic acid. The advantage which it possesses, viz., a more agreeable taste, is more than counterbalanced by its uncertain strength.

PAPAYACEÆ (PASSIFLORÆ).

Not officinal. **Papayotin.** The dried juice of the papaw tree, *Carica papaya.* **Papain.** A ferment obtained from the juice of *Carica papaya.* The term papain is frequently applied to the dried juice.

PREPARATION.—When scratches are made on the half ripe fruit of the Carica papaya a milky juice exudes in abundance. When dried it forms a powder somewhat like gum-arabic, and to this the name of papayotin is sometimes given. Papain is the pure ferment obtained by precipitation with alcohol and removal of albuminous matters by acetate of lead.

DOSE.—5 to 10 grains.

ACTION.—The fruit of the papaw tree has long been used in the West Indies to render beef tender. The unripe fruit is split open and rubbed over the surface of the meat previous to cooking. Its action probably depends upon the fact that papain has a **digestive** action not only upon muscular fibre, but also upon connective tissue. It digests fibrine and albumen more readily than pepsin. It also rapidly dissolves the false membrane of croup. When injected into the circulation in large doses it paralyses the heart. In smaller quantities it appears to favour the multiplication of micrococci in the blood (p. 70).

USES.—It has been recommended to dissolve the fibrinous membrane in croup and diphtheria, a solution being painted over

the pharynx every five minutes. It has also been recommended to destroy epithelioma. Internally it appears to be useful in dyspepsia and catarrhal conditions of the stomach.

MYRTACEÆ.

Caryophyllum, B.P.; Caryophyllus, U.S.P. CLOVES.—The dried unexpanded flower-buds of *Eugenia caryophyllata*, U.S.P. (*Caryophyllus aromaticus*, B.P.). East Indies.

CHARACTERS.—About ½ an inch long, dark reddish-brown, plump and heavy, consisting of a nearly cylindrical body surmounted by four teeth and a globular head, with a strong fragrant odour, and a bitter spicy pungent taste. It emits oil when indented with the nail.

COMPOSITION.—Cloves contain a large quantity of volatile oil, resin, gum and tannin.

PREPARATIONS.

B.P.	DOSE.
Infusum Aurantii Compositum	1-2 fl. oz.
,, **Caryophylli**	1-2 fl. oz.
Mistura Ferri Aromatica	1-2 fl. oz.
Oleum Caryophylli	1-5 min. or more.
Vinum Opii	10-40 min.

U.S.P.	DOSE.
Oleum Caryophylli	
Tinctura Lavandulæ Composita	½-2 fl. drm. (2-8 cc.)
,, Rhei Aromatica	2-4 fl. drm. (8-15 cc.)
Syrupus ,, Aromaticus	1 fl. drm. (4 cc.)
Vinum Opii	6 min. (0·4 cc.)

ACTION AND USE.—Stimulant **carminative,** used in flatulence, nausea, and atonic dyspepsia, chiefly given along with other medicines to afford an agreeable flavour and prevent griping.

Oleum Caryophylli, B. and U.S.P. OIL OF CLOVES.—A volatile oil distilled from cloves.

CHARACTERS.—Colourless when recent, but gradually becoming red-brown, having the odour of cloves and a pungent spicy taste.

COMPOSITION.—It consists chiefly of a phenol-like substance, eugenol or eugenic acid, which forms permanent salts with alkalis. With its own bulk of strong solution of potash, the oil forms a semi-solid mass.

DOSE.—Of the oil, 2 to 6 drops.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Confectio Scammonii	10-30 gr. or more.	Not given.
Pilula Colocynthidis Composita		
,, ,, et Hyoscyami	5-10 gr.	

ACTION AND USE.—Same as those of cloves. It has a local analgesic action, and is frequently used to relieve toothache by putting a drop on a piece of cotton-wool, and introducing it into the cavity of the tooth.

Pimenta, B. and U.S.P. PIMENTO, B.P.; PIMENTA, U.S.P. ALLSPICE.—The nearly ripe fruit of the allspice tree, *Eugenia Pimenta* (*Pimenta officinalis*). West Indies.

FIG. 153.—Pimenta.

CHARACTERS.—Of the size of a small pea, brown, rough looking, somewhat like black pepper, but distinguished from it by being crowned with the teeth of the calyx. Odour and taste aromatic, hot, and peculiar.

COMPOSITION.—From 3 to 4 per cent. of a volatile oil having the same composition as oil of cloves, also a considerable quantity of tannin and some starch.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Aqua Pimentæ	1-2 fl. oz.	**Oleum Pimentæ**	A few drops.
Oleum ,,	1-5 min.		
Syrupus Rhamni	1 fl. dr.		

Oleum Pimentæ, B. and U.S.P. OIL OF PIMENTO, B.P.; OIL OF PIMENTA, OIL OF ALLSPICE, U.S.P.—A volatile oil distilled from pimenta.

CHARACTERS.—Colourless or slightly reddish when recent, but becoming brown by age, having the odour and taste of pimenta.

COMPOSITION.—Nearly the same as oil of cloves.

USE.—Same as cloves. The oil may be given in a dose of 2 or 3 drops on a piece of sugar in flatulence.

PREPARATIONS.

B.P.	U.S.P.
None.	Spiritus Myrciæ.

Cheken.—Not officinal. The leaves and shoots of *Myrtus chekan* (*Eugenia chekan*). Chili.

APPEARANCE.—They resemble some buchu leaves (*Barosma betulina*), but have the margin entire and a different smell.

COMPOSITION.—They contain a volatile oil resembling that of eucalyptus, a volatile alkaloid—chekanine—and tannin.

ACTION AND USES.—It is **antiseptic, tonic, expectorant,** and diuretic. The expressed juice diluted with water has been used as a lotion in inflammation of the eye, and a decoction of the bark as an astringent in dysentery. It is chiefly used in catarrh of the mucous membranes, especially those of the bronchi and bladder. It appears to be very useful in cases of bronchitis with thick purulent expectoration, also in cases of phthisis. The oil of myrtle appears to have a similar action.

PREPARATIONS, NOT OFFICINAL.

	DOSE.
Infusum Cheken (1 part leaves to 10 of boiling water)	
Extractum ,, Fluidum (prepared like Ext. Cinchonæ Fluid., U.S.P.)	1-3 fl. drm.
Syrupus ,, (1 part leaves to 2 of syrup)	

Oleum Myrti. OIL OF MYRTLE.—Not officinal. A volatile oil obtained from the leaves of *Myrtus communis.*

DOSE.—0·15 Gm. in capsules.

ACTION AND USES.—It has an **antiseptic** action, and may be used in cases of foul ulcers and fœtid discharges from mucous passages, as in otorrhœa. It is not a sufficiently powerful irritant to affect the unbroken skin, but does so when the epidermis is removed. It has been used externally as a **rubefacient** in rheumatism. It causes warmth and increased flow of saliva in the mouth; and in small doses (0·6-0·9 Gm.) appears to aid digestion. In larger doses it acts as an **irritant**, causing nausea, flatulent distension, headache and languor. It is **excreted** in the urine, to which it gives a smell like violets, and like copaiba gives a precipitate when nitric acid is added to the urine. Like copaiba it may be used as an expectorant in chronic bronchitis with profuse expectoration, in phthisis, and in chronic inflammation of the bladder or urethra. (cf. p. 392.)

Oleum Cajuputi, B. and U.S.P. OIL OF CAJUPUT.—A volatile oil distilled from the leaves of *Melaleuca cajuputi*, U.S.P.; *M. minor*, B.P. (*M. Leucodendron*). East Indies.

CHARACTERS.—Pale bluish-green, transparent. Odour strong and agreeable; taste, warm and aromatic, leaving a sensation of coldness in the mouth.

IMPURITY.—Copper, added to preserve the fine green colour which the oil possesses when newly distilled or accidentally present.

TEST.—See Copper.

DOSE.—1 to 5 min. or more.

PREPARATIONS.

B.P.	DOSE.	
Linimentum Crotonis	½ fl. dr.	No Prep. in U.S.P.
Spiritus Cajuputi	1 fl. dr.	

USES.—It is a powerful **stimulant** and **antispasmodic.** Locally it acts as a stimulant and rubefacient. It is used externally in skin diseases—pityriasis, psoriasis, and acne rosacea. In this last disease it is said to be particularly useful and also in eczema.[1] It has also been used externally, alone, or with olive oil, in cases of muscular and articular rheumatism, and gout. Applied to a carious tooth it relieves pain in the same way as oil of cloves. Internally it is used to relieve flatulence. A few drops on a piece of sugar

[1] Claiborne, *Gaillard's Med. Journ.* Virginia, U.S.A.

are useful in neuralgia and hysteria, and its internal use is said to be also useful in chronic rheumatism.

U.S.P. Eucalyptus. EUCALYPTUS.—The leaves of *Eucalyptus globulus*, collected from rather old trees.

CHARACTERS.—Petiolate, lanceolately scythe-shaped, from six to twelve inches (fifteen to thirty centimetres) long, rounded below, tapering above, entire, leathery, grey green, glandular, feather-veined between the midrib and marginal veins; odour strongly camphoraceous, taste pungently aromatic, somewhat bitter and astringent.

COMPOSITION.—Eucalyptol, resin, tannin, &c.

PREPARATIONS.

	DOSE.
Extractum Eucalypti Fluidum	5-15 min.
Oleum Eucalypti	2-5 drops.

U.S.P. Oleum Eucalypti. OIL OF EUCALYPTUS.—A volatile oil distilled from the fresh leaves of *Eucalyptus globulus*, or *Eucalyptus amygdalina*, and some other species of Eucalyptus.

CHARACTERS.—A colourless or very pale yellowish liquid, having a characteristic aromatic odour, a pungent, spicy, and cooling taste, and a neutral reaction. It is soluble in an equal weight of alcohol.

ACTION.—Eucalyptus oil, or eucalyptol, as it is often termed, is a powerful **antiseptic,** even more powerful than quinine (p. 77). The antiseptic action of the oil is greater when it is old and charged with oxygen than when it is freshly distilled. Like quinine (p. 48) it arrests the movements of **white blood corpuscles** and its vapour prevents inflammation in the exposed mesentery of the frog. The **red corpuscles** of frog's blood have their nucleus rendered more distinct, and their surface wrinkled by it. Like quinine it causes contraction of the **spleen.** It is a local irritant. When applied to the **skin** and its evaporation prevented, it acts as a rubefacient, vesicant, or pustulant. When applied to a mucous membrane or injected hypodermically it causes pain. When **swallowed** it causes burning in the throat, stomach, and intestine. It may produce nausea, loss of appetite and slight looseness of the bowels, but is not an active emetic, nor purgative. After absorption in large doses it appears to act chiefly on the **nerve-centres,** producing paralysis and death. In invertebrata killed by exposure to its vapour the paralysis is preceded by excitement, but in vertebrate animals the paralysis is not preceded by excitement. Its depressing action on the **spinal cord** is so great as to abolish reflex action even when it has been previously increased by brucine; and from depression of the **brain, medulla, and heart,** there is drowsiness, feeble respiration, lowered blood-pressure, and fall of **temperature.** Death occurs from paralysis of the respira-

tion. It is **excreted** by the lungs and kidneys. Like turpentine, it imparts a smell of violets to the urine of persons taking it.

USES.—It has been employed as an antiseptic in surgical dressing in the form of eucalyptus gauze, but is apt to cause local irritation. It has proved useful as a lotion to wash out suppurating cavities. As an inhalation it has been employed to check secretion, and remove fœtor in ozæna, in bronchitis with profuse or fœtid expectoration, in phthisis and in diphtheria. It has been used in the form of injections or pessaries in uterine catarrh, and after parturition. It has been recommended as a hypodermic injection in pyæmia.

In three cases of septicæmia I treated by it recovery occurred during its use, and in one of these quinine had proved useless. It has been used as an antiperiodic in ague and an antipyretic in fever, but it has not proved so useful as one would have expected from the resemblance between its action and that of quinine.

Eucalyptus trees when freely planted in malarious districts appear to render them more healthy.

Granati Radicis Cortex, B.P.; Granatum, U.S.P. POMEGRANATE ROOT BARK, B.P.; POMEGRANATE, U.S.P.—The dried bark of the root of *Punica Granatum*. South of Europe.



FIG. 154.—Pomegranate.

CHARACTERS.—In quills or fragments of a greyish-yellow colour externally, yellow internally, having a short fracture, little odour, and an astringent slightly bitter taste.

COMPOSITION.—The most important constituents on which its anthelmintic action depends are two liquid alkaloids, pelletierine and isopelletierine. It contains two other alkaloids which are inactive, tannin, mannite, &c.

PREPARATION.

B.P.	DOSE.	U.S.P.
Decoctum Granati Radicis.....2 ounces to 1 pint..	.....1-3 fl. oz.	None.

USES.—Pomegranate is chiefly used as an **anthelmintic** for tapeworm. As it is not purgative, but rather astringent, its use must be followed by that of a cathartic. Often, several doses are required. The dose of the tannate of pelletierine is $\frac{1}{2}$-$\frac{3}{4}$ gr. (0·03—0·05 gr.), taken fasting and followed in fifteen minutes by a brisk purgative.

CUCURBITACEÆ.

U.S.P. Colocynthis. COLOCYNTH.—The fruit of the *Citrullus Colocynthis*, deprived of its rind.

CHARACTERS.—Globular, from two to four inches (five to ten centimetres) in diameter, white, or yellowish white; light, spongy,

readily breaking into three wedge-shaped pieces, each containing near the rounded surface many flat, ovate, brown seeds, inodorous, taste intensely bitter.

Colocynthidis Pulpa, B.P. COLOCYNTH PULP.—The dried decorticated fruit, freed from seeds, of *Citrullus Colocynthis*. Imported chiefly from Smyrna, Trieste, France, and Spain.



FIG. 155.—Colocynth (peeled).

CHARACTERS.—Light, spongy, white or yellowish-white in colour, intensely bitter in taste.

COMPOSITION.—The active principle is a glucoside colocynthin, which is soluble in water and alcohol, not in ether. The remaining part of the pulp consists principally of resinous matter.

PREPARATIONS.

B.P.	DOSE.
Extractum Colocynthidis Compositum	3-10 gr.
Pilula Colocynthidis Composita	5-10 gr.
Pilula Colocynthidis et Hyoscyami	5-10 gr.
	(of the powdered pulp, 2-8 gr.)

U.S.P.	DOSE.
Extractum Colocynthidis	Seldom used alone.
,, ,, Compositum	5-20 gr.
Pilulæ Catharticæ Compositæ	1-3 pills.

Extractum Colocynthidis Compositum. COMPOUND EXTRACT OF COLOCYNTH, B.P.—Colocynth pulp, 6 oz.; extract of Socotrine aloes, 12 oz.; resin of scammony, 4 oz.; hard soap, in powder, 3 oz.; cardamom seeds, in fine powder, 1 oz.; proof spirit, 1 gallon. An extract of the colocynth is first made, and then mixed with the other ingredients.

In the U.S.P. a simple extract is already officinal, and the proportions are—extract of colocynth, 16 parts; aloes, 50; cardamom, 6; resin of scammony, 14; soap, 14; alcohol, 10.

B.P. Pilula Colocynthidis Composita. COMPOUND PILL OF COLOCYNTH.—Colocynth pulp, 1; Barbados aloes, 2; scammony, 2; sulphate of potash, $\frac{1}{4}$; oil of cloves, $\frac{1}{4}$; distilled water, q.s.

B.P. Pilula Colocynthidis et Hyoscyami. PILL OF COLOCYNTH AND HYOSCYAMUS.—Compound pill of colocynth, 2; extract of hyoscyamus, 1.

U.S.P. Pilulæ Catharticæ Compositæ. COMPOUND CATHARTIC PILL.—Compound extract of colocynth, 130; abstract of jalap, 100; mild chloride of mercury, 100; gamboge, 25; = 355 grains; water, q.s. To make 100 pills.

PHYSIOLOGICAL ACTION.—The active principle colocynthin acts as a powerful **cathartic** on the intestines whether swallowed, administered hypodermically, or injected into the circulation. In

small doses it increases peristalsis, and the secretion from the intestines and liver. It thus produces watery and mucous motions frequently accompanied by griping. In large doses it causes gastro-enteritis with mucous and bloody stools. It appears to act also on the urinary system, as Tidy found inflammation of the kidneys and bladder, as well as of the rectum in dogs, poisoned by it, and it is said to act as a **diuretic.**

THERAPEUTICS.—It is used in obstinate chronic constipation, especially if there is a tendency to congestion of the brain, as in plethoric people. It is also used in amenorrhœa. It is apt to gripe if given alone; hence it is well to combine it with other purgatives and with sedatives such as hyoscyamus. It may sometimes be advantageously combined with mercurial pill.

B.P. Ecbalii Fructus. SQUIRTING CUCUMBER FRUIT.—The fruit, very nearly ripe, of the squirting cucumber, *Ecbalium officinarum.*

PREPARATION.

B.P.	DOSE.
Elaterium	$\frac{1}{16}$-$\frac{1}{2}$ gr.

CHARACTERS.—Oval, about $1\frac{1}{2}$ in. long, covered with soft prickles terminating in white points. When ripe the fruits are suddenly detached from the stalk and the juice and seeds expelled.

COMPOSITION.—The juice deposits elaterium.

B.P. Elaterium. ELATERIUM.—A sediment from the juice of the squirting cucumber fruit.

PREPARATION.—Expressing the juice, separating the deposit by straining, and drying by a gentle heat.



FIG. 156.—Elaterium.

CHARACTERS.—In cakes, about one line thick, light, friable, slightly incurved, greenish-grey, acrid and bitter.

COMPOSITION.—Elaterium is composed of Elaterin, with starch and fibrous and colouring matters.

IMPURITIES.—Chalk and earthy matter fraudulently added.

TESTS.—Does not effervesce with acids (absence of chalk), yields half its weight to boiling rectified spirit. This solution concentrated and added to warm solution of potash yields on cooling not less than twenty per cent. of elaterin in colourless crystals.

DOSE.—$\frac{1}{16}$th to $\frac{1}{2}$ gr.

PREPARATIONS.

B.P.	DOSE.
Pulvis Elaterii Compositus (1 gr. elaterium mixed with 9 of sugar of milk.)	$\frac{1}{2}$-5 gr.

U.S.P. Elaterinum. ELATERIN.—A neutral principle extracted from elaterium, a substance deposited by the juice of the fruit of *Ecbalium elaterium*.

CHARACTERS.—Small colourless shining hexagonal scales or prisms, permanent in the air, odourless, having a bitter, somewhat acrid taste, and a neutral reaction. A solution of elaterin in cold concentrated sulphuric acid assumes a yellow colour, gradually changing to red.

The alcoholic solution should not be precipitated by tannic acid, nor by salts of mercury or of platinum (absence of, and difference from, alkaloids).

DOSE.—$\frac{1}{10}$ gr.

PREPARATION.

	DOSE.
Trituratio Elaterini (1 gr. elaterin, 9 gr. sugar of milk.)	$\frac{1}{2}$-$\frac{3}{4}$ gr.

ACTION AND USES.—Elaterin is the most **powerful hydragogue cathartic** we possess, increasing the peristaltic action and flow of fluid from the intestines. It only acts as a purgative when taken internally, and appears to require bile in order to act. When injected subcutaneously it acts on the **nervous system,** causing salivation, insensibility, tetanus, and dyspnœa. It is used in dropsies, especially those affecting the abdominal cavity and due to cirrhosis of the liver. It is also used as a depletory in cerebral affections. It is usually combined with henbane and volatile oils, as it is apt to gripe. In large doses it may cause gastro-enteritis and fatal collapse, and should be given with care to old or feeble persons.

U.S.P. Pepo. PUMPKIN SEED.—The seed of *Cucurbita Pepo*.

CHARACTERS.—About three-quarters of an inch (2 centimetres) long, broadly-ovate, flat, white or whitish, nearly smooth, with a shallow groove parallel to the edge; containing a short, conical radicle, and two flat cotyledons; inodorous, bland, and oily.

COMPOSITION.—It is probable that the active principle is a resin contained in the endopleuron or greenish envelope immediately surrounding the embryo. This resin is dissolved and rendered more active by castor oil, which should be given before and after the anthelmintic. The decorticated seeds, as well as the oil derived from them, are bland and unirritating.

DOSE.—An ounce or an ounce and a half. The seeds may be crushed, and flavoured with some aromatic oil.

USES.—It is an excellent **anthelmintic** for the removal of tapeworm. It should be given the first thing in the morning after a very light supper, and should be followed in two or three hours by an active purgative. No solid food should be taken until two hours after the purgative.

U.S.P. Bryonia. BRYONIA. BRYONY.—The root of *Bryonia alba*, and of *Bryonia dioica*.

CHARACTERS.—In transverse sections about two inches (5 centimetres) in diameter, the bark grey-brown, rough, thin, the central portion whitish or greyish, with numerous small wood-bundles arranged in circles and projecting, radiating lines; inodorous, taste disagreeably bitter.

PREPARATION.

	DOSE.
Tinctura Bryoniæ	2-10 fl. dr.

COMPOSITION.—It contains a bitter principle, bryonin.

USE.—Its chief use was that of a **hydragogue cathartic,** but it is now superseded by jalap.

UMBELLIFERÆ.

CAMPYLOSPERMÆ.

B.P. Conii Folia. HEMLOCK LEAVES.—The fresh leaves and young branches of spotted hemlock, *Conium maculatum;* also the leaves separated from the branches and carefully dried; gathered from wild British plants when the fruit begins to form.

CHARACTERS.—Fresh leaves, smooth, arising from a smooth stem with dark purple spots; dried leaves of a full green colour and characteristic mousey odour. The leaf rubbed with solution of potash gives out strongly the odour of coniïne.

COMPOSITION.—The fresh leaves and branches contain the same alkaloids as the fruits (which see) although in smaller proportion, while the coniïne is sometimes accompanied by a third alkaloid, conhydrine. These principles are lost when the leaves are dried or heated, both being highly volatile.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Cataplasma Conii	For external use.	None.
Extractum Conii (green extract)	2-6 gr. or more.	
Succus Conii	30 min. to 2 fl. dr. or more.	
Vapor Coniæ	*Vide infra.*	
Pilula Conii Composita	5-10 gr. (of the powdered leaf, 2-8 gr.)	

B.P. Cataplasma Conii. HEMLOCK POULTICE.—Hemlock leaf, in powder, 1 oz.; linseed meal, 3 oz.; boiling water, ½ pint.

B.P. Pilula Conii Composita. COMPOUND PILL OF HEMLOCK.—Extract of hemlock, 2½; ipecacuanha, in powder, ½; treacle, q.s.

B.P. Vapor Coniæ. INHALATION OF CONIA.—Extract of hemlock, 60 gr.; solution of potash, 60 min.; distilled water, 10 fl. drm. Put 20 min. of the mixture on a sponge in an inhaler containing hot water.

Conii Fructus, B.P. HEMLOCK FRUIT.—The dried ripe fruit of *Conium maculatum,* (spotted hemlock).

FIG. 157.—Conium.

CHARACTERS.—About one-eighth of an inch long, broadly ovate, compressed laterally; half-fruit with five waved or crenated

ridges. Reduced to powder and rubbed with solution of potash they give out strongly the odour of coniïne.

Conium, U.S.P. HEMLOCK.—The full-grown fruit of *Conium maculatum*, gathered while yet green.

CHARACTERS.—Similar to those of hemlock fruit, B.P.

COMPOSITION.—Coniïne, a poisonous alkaloid, occurs in hemlock as a yellow, oily liquid, and is separated by distilling the fruits with slightly alkaline water. The fruit contains methyl-coniïne in varying proportion, and a small quantity of volatile oil which does not appear to be poisonous.

PREPARATION.

B.P.	DOSE.
Tinctura Conii	20-60 min.

U.S.P.	DOSE.
Abstractum Conii	7-8 gr.
Extractum Conii Alcoholicum	2 gr.
Extractum Conii Fluidum	15 min.
Tinctura Conii	60 min.

PHYSIOLOGICAL ACTION.—The action of conium depends on the alkaloids, coniïne and methyl-coniïne, which it contains, and as their action differs considerably and the relative quantity of each varies, contradictory results have been obtained by different observers. The symptoms of conium-poisoning are weakness of the legs and staggering gait, passing on to paralysis which gradually progresses upwards and finally causes death by failure of respiration. The mind remains clear to the last. **Coniïne** paralyses the ends of the motor nerves and of the vagus like curare, and afterwards paralyses the motor centres in the brain and spinal cord. It causes death by paralysing the respiratory muscles. Death is usually accompanied by convulsions in warm- but not in cold-blooded, animals. There is dilatation of the pupil, and ptosis from paralysis of the endings of the third nerve. Locally applied, it appears to paralyse the ends of sensory nerves.

Methyl-coniïne acts on the spinal cord, causing paralysis of reflex action.

Dimethyl-coniïne and conhydrine have an action similar to that of coniïne, but less active.

THERAPEUTICS.—It is used locally as a poultice to soothe pain in cancer and ulcers, and as a vapour to relieve cough in bronchitis and pertussis. It is used to allay muscular spasm in chorea, mercurial tremor, and paralysis agitans, but is useless in tetanus and strychnia poisoning. The best preparation to use is the succus in doses of ℥i, gradually increased as the patient becomes tolerant of the drug.

ORTHOSPERMÆ.

Assafœtida, B. and U.S.P. ASSAFŒTIDA, B.P.; ASAFETIDA, U.S.P.—A gum-resin obtained from the root of *Narthex Assafœtida*, B.P. (*Ferula Narthex* and *F. Scorodosma*, U.S.P.). In Afghanistan and the Punjaub.

CHARACTERS.—In irregular masses, composed of whitish tears, which are embedded in a yellowish-grey or brownish-grey sticky mass. The tears, when hard, break with a conchoidal fracture, showing a milk-white colour which changes gradually, on exposure, to pink, and finally to brown. Taste bitter, acrid; odour fœtid, alliaceous.

COMPOSITION.—Volatile oil, resin, and gum. The oil contains a very large proportion of sulphur.

TEST.—It dissolves almost entirely in rectified spirit, B.P.; 60 per cent. soluble in alcohol, U.S.P.

PREPARATIONS.

B.P.	DOSE.
Enema Assafœtidæ	*vide infra.*
Pilula Aloes et Assafœtidæ	4-10 gr.
Pilula Assafœtidæ Composita	5-15 gr.
Spiritus Ammoniæ Fœtidus	½-1 fl. dr.
Tinctura Assafœtidæ	½-1 fl. dr. or more. (of the gum resin, 5-30 gr. or more.)

U.S.P.	DOSE.
Emplastrum Asafœtidæ	for external use.
Mistura Asafœtidæ	4-8 fl. dr.
,, Magnesiæ et Asafœtidæ	4 fl. dr.
Pilulæ Asafœtidæ (3, soap 1)	1-3 pills.
,, Aloes et Asafœtidæ	2-5 pills.
,, Galbani Compositæ	2-4 pills.
Tinctura Asafœtidæ	30 min. to 1 fl. dr.

B.P. Enema Assafœtidæ. ENEMA OF ASSAFŒTIDA (ENEMA FŒTIDUM).—Assafœtida, 30 gr.; distilled water, 4 fl. oz. Rub the assafœtida in a mortar with the water added gradually, so as to form an emulsion.

U.S.P. Mistura Asafœtidæ. ASAFETIDA MIXTURE.—Rub asafetida, 4, with water, 100.

U.S.P. Mistura Magnesiæ et Asafœtidæ. MIXTURE OF MAGNESIA AND ASAFETIDA (Dewees' Carminative). Carbonate of magnesium, 5; tincture of asafetida, 7; tincture of opium, 1; sugar, 10; distilled water up to 100.

B.P. Spiritus Ammoniæ Fœtidus. FETID SPIRIT OF AMMONIA.—Assafœtida, 1½ oz.; strong solution of ammonia, 2 fl. oz.; rectified spirit up to 1 pint.

B.P. Pilula Assafœtidæ Composita. COMPOUND PILL OF ASSAFŒTIDA (PILULA GALBANI COMPOSITA).—Assafœtida, 2; galbanum, 2; myrrh, 2; treacle, by weight, 1.

USES.—It is used as a stimulant, **anti-spasmodic,** and **carminative.** It is useful in hysteria, especially that occurring about the menopause.

It is an exceedingly useful remedy in the form of enema for tympanites, but on account of its disagreeable odour is not much used for flatulent distension of the stomach. It is given as a **stimulating expectorant** in cases of chronic bronchitis and pertussis.

Galbanum, B. and U.S.P. GALBANUM.—A gum-resin, derived from *Ferula galbaniflua*, and probably from other allied plants.

CHARACTERS.—In tears about the size of a pea, or more commonly in masses formed by their agglutination; greenish-yellow or pale brown externally, milky-white internally, translucent, having a strong disagreeable odour, and an acrid, bitter taste.

COMPOSITION.—Gum resin, and volatile oil.

PREPARATIONS.

B.P.	DOSE.
Emplastrum Galbani	for external use.
Pilula Assafœtidæ Composita	5-15 gr. (of the gum resin, 10-30 gr. or more.)

U.S.P.	DOSE.
Emplastrum Asafœtidæ	for external use.
,, Galbani	
Pilulæ Galbani Compositæ	2-4 pills.

U.S.P. Pilulæ Galbani Compositæ. COMPOUND PILLS OF GALBANUM.—Galbanum, 150; myrrh, 150; asafetida, 50; syrup, q.s. up to 350 grains. To make 100 pills. This pill is much like the compound assafœtida pill, B.P., but contains less assafœtida and is made up with syrup instead of treacle.

USES.—It has little antispasmodic power, but is a **stimulant expectorant,** used in chronic bronchitis with much wheezing and abundant discharge, as it lessens secretion. It is also used locally as a stimulant to inflamed joints.

Ammoniacum, B. and U.S.P. AMMONIACUM, B.P.; AMMONIAC, U.S.P.—A gum-resin from *Dorema Ammoniacum*. Persia and the Punjaub.

CHARACTERS.—In roundish tears or irregular masses formed by their agglomeration without any intervening dark-coloured substance. The tears are roundish, pale yellowish-brown externally, milk-white internally, brittle. Peculiar odour, bitter, acrid, nauseous taste.

COMPOSITION.—Gum resin, and volatile oil.

DOSE.—10 to 30 grains.

PREPARATIONS.

B.P.	DOSE.
Emplastrum Ammoniaci cum Hydrargyro	for external use.
Mistura Ammoniaci (¼ oz., water 8 fl. oz)	½-1 fl. oz.

U.S.P.	DOSE.
Emplastrum Ammoniaci	for external use.
,, Ammoniaci cum Hydrargyro	
Mistura Ammoniaci (4, water 100)	2 fl. dr. or more.

USE.—It is used for the **same** purposes as **galbanum,** chiefly as a stimulant to the mucous membrane in bronchorrhœa.

Fœniculi Fructus, B.P.; Fœniculum, U.S.P. FENNEL FRUIT, B.P.; FENNEL, U.S.P.—The fruit of *Fœniculum vulgare*, U.S.P. (*F. dulce*, B.P.). Malta.

FIG. 158.—Fennel.

CHARACTERS.—Longer than conium fruit, being about one-quarter of an inch long. Slightly curved, elliptical, longitudinal ribs, the two lateral being double; taste and odour aromatic. The footstalk is often attached.

COMPOSITION.—A volatile oil, having the same composition as oil of anise.

PREPARATION.

B.P.	DOSE.	U.S.P.
Aqua Fœniculi (1 lb. to 1 gallon)	1-2 fl. oz.	None.

USE.—It is stimulant and **carminative,** used to relieve flatulence, and lessen griping of purgatives.[1]

U.S.P. Anisum. ANISE.—The fruit of *Pimpinella anisum.*

CHARACTERS.—About $\frac{1}{6}$ of an inch (4 millimetres) long, ovate. It has an agreeable aromatic odour and a sweet, spicy taste. It may be distinguished from conium fruit which it somewhat resembles, and which has been mistaken for it, by the conium fruit consisting usually of single mericarps, which are smooth grooved upon the face and have crenate ridges and no oil-tubes.

Oleum Anisi, B. and U.S.P. OIL OF ANISE.—A volatile oil distilled in Europe from the fruit of *Pimpinella anisum*, or from Illicium (U.S.P.), and the oil distilled in China from the fruit of *Illicium anisatum* (p. 756).

CHARACTERS OF OIL OF ANISE.—Colourless or pale yellow; with the odour of anise, and a warm, sweetish taste. Concretes at 10° to 15° C. (50°—59° F.). Oil of illicium has nearly the same properties except that it congeals at 2° C. (35·6° F.).

COMPOSITION.—The same as that of oil of fennel.

PREPARATIONS.

B.P.	DOSE.
Essentia Anisi	10-20 min.
Tinctura Camphoræ Composita	15 min. to 1 fl. dr.
Tinctura Opii Ammoniata	$\frac{1}{2}$-1 fl. dr. (of the oil, 2-5 min.)

[1] I am informed that the wild fennel growing in South Africa will completely drive away fleas from kennels and stables.

PREPARATIONS—*continued.*

U.S.P.	DOSE.
Aqua Anisi	Indefinite
Spiritus Anisi	1-2 fl. dr.
Tinctura Opii Camphorata	1-2 fl. dr.
Trochisci Glycyrrhizæ et Opii	1-3 troches.

USE.—It is an aromatic stimulant **carminative,** and is used as an adjunct to purgatives to lessen griping.

B.P. Anethi Fructus. DILL FRUIT. The fruit of *Anethum graveolens.* England, or middle and southern Europe.



FIG. 159.—Dill.

CHARACTERS.—Oval, flat, about a line and a half in length, and easily distinguished by its membranous wings. Aromatic taste and odour.

COMPOSITION.—Contains a volatile oil.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Aqua Anethi	1-2 fl. oz. (for infants 1-2 fl. dr.)	None.
Oleum Anethi	2-5 min.	

B.P. Oleum Anethi. OIL OF DILL.—A volatile oil distilled from the fruit.

CHARACTERS.—Pale yellow colour, aromatic odour, sweetish taste.

USE.—The chief use of dill water is in the flatulence of children in ʒi doses. It is stimulant and **carminative.**

Carui Fructus, B.P.; Carum, U.S.P. CARAWAY FRUIT, B.P.; CARAWAY, U.S.P.—The dried fruit of *Carum Carui,* B.P. (*Carum Carvi,* U.S.P.).

FIG. 160.—Caraway.

CHARACTERS.—Fruit usually separating into two mericarps about one-sixth inch long, curved, tapering at each end, brown, with five paler longitudinal ridges; having an agreeable aromatic odour and spicy taste.

COMPOSITION.—A volatile oil, which consists of a hydrocarbon carvene, and an oxygenated oil identical with that obtained from oil of dill.

PREPARATIONS.

B.P.	DOSE.
Aqua Carui	1-2 fl. oz.
Oleum Carui	2-5 min.
Confectio Opii	5-20 grs.
Confectio Piperis	60-120 grs.
Pulvis Opii Compositus	2-5 grs.
Tinctura Cardamomi Composita	½-2 fl. dr.
Tinctura Sennæ	1-4 fl. dr.

U.S.P.	DOSE.
Oleum Cari	2-5 min.
Spiritus Juniperi Compositus	2-4 fl. dr.

Oleum Carui, B.P.; Oleum Cari, U.S.P. OIL OF CARAWAY.—The oil distilled in Britain from caraway fruit, B.P. A volatile oil distilled from caraway, U.S.P.

CHARACTERS.—Colourless or pale yellow, odour aromatic, taste spicy, and neutral reaction. It is soluble in an equal weight of alcohol.

PREPARATIONS.

B.P.

Confectio Scammonii, 1 fl. drm. in 10 oz.
Pilula Aloes Barbadensis, 1 fl. drm. in 4 oz.

U.S.P.

Spiritus Juniperi Compositus.

USE.—**Carminative** and stimulant. Used with purgatives to lessen griping and to relieve flatulence.

Sumbul Radix, B.P.; Sumbul, U.S.P. SUMBUL ROOT, B.P.; SUMBUL, U.S.P.—The dried transverse sections of the root of *Euryangium Sumbul*, B.P. (*Ferula Sumbul*, U.S.P.). Imported from Russia and India.

CHARACTERS. — Cylindrical pieces, varying considerably in diameter and thickness. They are covered on the outer edge with a dusky brown rough bark, frequently beset with short, bristly fibres. The cut surface looks like felt from the interior of the root consisting of easily separated fibres. It has a strong odour, resembling that of musk. The taste is at first sweetish, becoming after a time bitterish.

COMPOSITION.—A resin soluble in ether, and a small quantity of an essential oil.

PREPARATIONS.

B.P.	DOSE.
Tinctura Sumbul (2½ oz. in 1 pint)	10-60 min.

U.S.P.	DOSE.
Tinctura Sumbul (10 per cent.)	1-4 fl. drm.

USE.—Sumbul is said by some to be of little service; however it seems useful in the malady for which it is usually prescribed, viz., **hysteria** and nervous conditions occurring in females in feeble health or recovering from an acute disease.

CŒLOSPERMÆ.

Coriandri Fructus, B.P.; Coriandrum, U.S.P. CORIANDER FRUIT, B.P.; CORIANDER, U.S.P.—The fruit of *Coriandrum sativum.*

FIG. 161.—Coriander.

CHARACTERS.—Globular, nearly as large as white pepper, beaked, finely ribbed, yellowish-brown; has an agreeable aromatic odour and flavour.

COMPOSITION.—Contains volatile and fixed oils.

PREPARATIONS.

B.P.	DOSE.
Confectio Sennæ	60-120 grs.
Mistura Gentianæ	½-1 fl. oz.
Oleum Coriandri	2-5 min.
Syrupus Rhei	1-4 fl. drm.
Tinctura Rhei	1-8 fl. drm.
Tinctura Sennæ	1-4 fl. drm.
Syrupus Sennæ	1-4 fl. drm. (of the oil, 2-5 min.)

U.S.P.	DOSE.
Oleum Coriandri	2-5 min.

Oleum Coriandri, B. and U.S.P. OIL OF CORIANDER.—A volatile oil distilled from coriander.

CHARACTERS.—A colourless, or yellowish liquid, having the characteristic aromatic odour of coriander, a warm spicy taste, and a neutral reaction.

PREPARATION.

B.P.

Syrupus Sennæ.

USE.—**Carminative** and stimulant. Used as an adjunct to purgatives.

CHAPTER XXXIII.

Sub-Class III. COROLLIFLORÆ.

CAPRIFOLIACEÆ.

B.P. Sambuci Flores. ELDER FLOWERS.—The fresh flowers of *Sambucus nigra.* From indigenous plants.

CHARACTERS.—Flowers small, white, fragrant, crowded in large cymes.

U.S.P. Sambucus. ELDER. — The flowers of *Sambucus canadensis.*

CHARACTERS.—In level tipped cymes, cream-coloured, odour peculiar, taste sweetish, aromatic, slightly bitter.

COMPOSITION.—A small amount of a light essential oil.

PREPARATION.

B.P.	DOSE.	U.S.P.
Aqua Sambuci	1-2 fl. oz.	None.

USE.—Elder-flower water is used as a **vehicle** in collyria and lotions.

CORNACEÆ.

U.S.P. Cornus. CORNUS. DOGWOOD.—The bark of the root of *Cornus florida.*

CHARACTERS.—In curved pieces of various sizes, about one-eighth of an inch (3 millimetres) thick; deprived of the furrowed, brown-gray, corky layer; outer and inner surface pale-reddish, or light reddish-brown, striate; transverse and longitudinal fracture short, whitish, with brown, yellow striæ; inodorous; astringent and bitter.

PREPARATION.

	DOSE.
Extractum Cornus Fluidum	1 fl. drm.
Cornus	20-60 gr.

COMPOSITION.—It contains a bitter neutral principle.

ACTION.—It acts as an **astringent tonic** and feeble stimulant to the stomach. It was formerly used in ague and malarious conditions, and a resinoid substance obtained from it by alcohol is popularly called **dogwood-quinine.**

RUBIACEÆ; (CINCHONACEÆ).

CINCHONEÆ.

U.S.P. Cinchona. CINCHONA.—The bark of any species of cinchona containing at least 3 per cent. of its peculiar alkaloids.

PREPARATION.

U.S.P.	DOSE.
Infusum Cinchonæ, (cinchona in powder 6, aromatic sulphuric acid 1, water *q.s.* to make 100 parts by percolation)	1-2 fl. oz.

B.P. Cinchonæ Pallidæ Cortex. PALE CINCHONA BARK.—The bark of *Cinchona officinalis*, and several allied species. Loxa in Ecuador.



FIG. 162.—Pale Cinchona Bark.

CHARACTERS.—In single or double quills, brittle, easily splitting longitudinally, and breaking with a short transverse fracture; outer surface brown and wrinkled, or grey and speckled with adherent lichens, with or without numerous transverse cracks; inner surface bright orange or cinnamon brown; powder pale brown, slightly bitter, very astringent.

ADULTERATION.—Inferior barks are sometimes added.

TEST.—200 grains of the bark, assayed in the same manner as yellow cinchona bark, with the substitution of chloroform for ether, should yield not less than one grain of alkaloids.

PREPARATIONS.

B.P.	DOSE.
Mistura Ferri Aromatica	1-2 fl. oz.
Tinctura Cinchonæ Composita	½-2 fl. drm.

B.P. Tinctura Cinchonæ Composita. COMPOUND TINCTURE OF CINCHONA.—Pale cinchona bark, 2 oz.; bitter orange peel, 1 oz.; serpentary, ½ oz.; saffron, 60 grs.; cochineal, 30 gr.; proof spirit, 1 pint.

Cinchonæ Flavæ Cortex, B.P.; Cinchona Flava, U.S.P. YELLOW CINCHONA BARK, B.P.; YELLOW CINCHONA CALISAYA BARK, U.S.P.—The bark of the trunk of *Cinchona*



FIG. 163.—Yellow Cinchona.

Calisaya, containing at least 2 per cent. of quinine. Collected in Bolivia and Southern Peru.

CHARACTERS.—In flat pieces, or quills. The flat pieces are recognised by their tawny yellow colour, and by the long channelled depressions left on the outer side of the bark by the gouge with which the epidermis has been removed. Transverse fracture shows numerous very rigid glistening fibres, short and very fibrous. Powder cinnamon-brown, somewhat aromatic, persistently bitter. The quills are $\frac{1}{2}$ to 2 inches in diameter, and have a grey, corky, fissured epidermis. Internally cinnamon brown, and finely striate from the bark fibres.

ADULTERATION.—Spurious cinchona bark is rarely found, but inferior varieties of cinchona barks are frequently added.

TEST.—100 grains of the bark, when assayed, should yield at least two grains of pure quinine.

PREPARATIONS.

B.P.	DOSE.
Decoctum Cinchonæ Flavæ	1-2 fl. oz.
Extractum Cinchonæ Flavæ Liquidum	10-30 min.
Infusum Cinchonæ Flavæ	1-2 fl. oz.
Quiniæ Sulphas	1-10 grs.
Tinctura Cinchonæ Flavæ	$\frac{1}{2}$-2 fl. drm.

U.S.P.	DOSE.
Extractum Cinchonæ	8-15 grs.
,, ,, Fluidum	30-60 min.
Tinctura Cinchonæ	1-2 fl. drm.

Cinchonæ Rubræ Cortex, B.P.; Cinchona Rubra, U.S.P. RED CINCHONA BARK. RED CINCHONA.—The bark of *Cinchona succirubra*. From Chimborazo.



FIG. 164.—Red Cinchona.

CHARACTERS.—In flat or incurved pieces, less frequently in quills, coated with the periderm, outer surface brown or reddish-brown, frequently warty; inner surface redder; fractured surface often approaching to brick-red; transverse fracture finely fibrous; powder red-brown; taste bitter and astringent.

ADULTERATION.—Some of the brown and red inferior barks are occasionally substituted.

TEST.—100 grains of the bark, assayed in the same manner as yellow cinchona bark, with the substitution of chloroform for ether, should not yield less than 1·5 grains of alkaloids, B.P., 2 grains of quinine, U.S.P.

PREPARATION.

B.P.	U.S.P.	DOSE.
None.	Tinctura Cinchonæ Composita	1-4 fl. drm.

U.S.P. Tinctura Cinchonæ Composita. COMPOUND TINCTURE OF CINCHONA.—Red cinchona, 10; bitter orange peel, 8; serpentaria, 2; glycerin, 10; alcohol and water (in the proportion of 8 of the former to 1 of the latter) *q.s.* to make 100.

PROPERTIES AND COMPOSITION OF THE CINCHONA BARKS.—The cinchona barks contain varying quantities of the following alkaloids:— Cinchonine ($C_{29}H_{22}N_2O$), cinchonidine ($C_{19}H_{22}N_2O$), quinine ($C_{20}H_{24}N_2O_2$), quinidine ($C_{20}H_{24}N_2O_2$), quinamine ($C_{19}H_{24}N_2O_2$), conquinamine ($C_{19}H_{24}N_2O_2$). Quinine, quinidine, and quinamine are abundantly soluble in ether; cinchonidine only sparingly soluble, and cinchonine is almost entirely insoluble. The solutions of quinine and cinchonidine are lævogyrate; those of cinchonine, quinidine, quinamine, and conquinamine are dextrogyrate. If chlorine water and a drop of ammonia be added to a dilute solution of quinine a brilliant green colour appears, and in concentrated solutions of quinine a green precipitate of thalleioquin is produced. Quinidine also gives this reaction, but cinchonine, cinchonidine, and quinamine do not. Solutions of quinine and quinidine are fluorescent, but those of cinchonine, cinchonidine and quinamine, if pure, exhibit no fluorescence.

Both the total quantity of alkaloids and the relative proportions of each vary considerably in the barks of the different species of cinchona. The yellow bark is usually richest in quinine; it yields from 2 to 6 per cent. of the alkaloid. The pale bark contains only about 1 per cent. of alkaloids and these are chiefly cinchonine and cinchonidine. The flat kind of the red bark contains about 3 to 4 per cent. of alkaloids, but the quill red bark is richer, yielding 5 to 10 per cent., of which about one-third is quinine, one-fourth cinchonidine, and the rest cinchonine with traces of quinidine.

By heating solutions of the cinchona alkaloids with excess of a mineral acid they may be converted into amorphous isomeric alkaloids. Quinine yields quinicine, and cinchonine is converted into cinchonicine.

In addition to the alkaloids, the cinchona barks contain certain acid principles. These are:— (1) Quinic or chinic acid, soluble in water and alcohol, but sparingly so in ether. On oxidation it yields quinone or chinone. (2) Cincho-tannic acid. (3) Quinovic acid.

Cinchona bark also contains quinovin, which by means of hydrochloric acid is resolved into quinovic acid and an uncrystallisable sugar. It also contains cinchona-red, which is a colouring matter abundantly found in the red bark.

U.S.P. Quinina. QUININE, $C_{20}H_{24}N_2O_2 3H_2O$ (crystallised) 378.—An alkaloid prepared from different species of cinchona.

PREPARATION.—By adding to the solution of the sulphate a quantity of water of ammonia or solution of soda, just sufficient to precipitate the alkaloid.

Although it is not separately mentioned in the B.P., it is used in the preparation of citrate of iron and quinine.

PREPARATIONS.

U.S.P.	DOSE.
Ferri et Quininæ Citras	3-5 grs.
Liquor Ferri et Quininæ Citratis	8-45 min.
Syrupus Ferri Quininæ et Strychninæ Phosphatum	1-2 fl. dr.

Quiniæ Sulphas. SULPHATE OF QUINIA. **B.P. Quininæ Sulphas.** SULPHATE OF QUININE. **U.S.P.** $(C_{20}H_{24}N_2O_2)_2H_2SO_4.7H_2O$; 872.—The sulphate of an alkaloid, prepared from yellow cinchona bark, and from the bark of *Cinchona lancifolia*, and several other species.

PREPARATION.—Macerate powdered yellow cinchona bark with hydrochloric acid, precipitate the liquid thus obtained with solution of soda, dissolve and neutralise the precipitate by sulphuric acid, concentrate and crystallise.

CHARACTERS AND TESTS.—Filiform, silky, snow-white crystals, of a pure intensely bitter taste, sparingly soluble in water, yet imparting to it a peculiar bluish tint. The solution gives with chloride of barium a white precipitate insoluble in nitric acid, and when treated first with solution of chlorine and afterwards with ammonia it becomes of a splendid **emerald-green colour.** Dissolves in pure sulphuric acid with a feeble yellowish tint, and undergoes no further change of colour when gently warmed. Ten grains with ten minims of diluted sulphuric acid and half a fluid ounce of water form a perfect solution, from which ammonia throws down a white precipitate. This redissolves on agitating the whole with half a fluid ounce of ether, without the production of any crystalline matter floating on the lower of the two strata into which the agitated fluid separates on rest. 25 grains of the salt should lose 3·6 grains of water by drying at 212°.

PREPARATIONS.

B.P.	DOSE.
Ferri et Quiniæ Citras	5-10 grs.
Pilulæ Quiniæ	2-10 grs.
Tinctura Quiniæ	½-2 fl. drm.
Vinum Quiniæ	½-1 fl. oz.
Tinctura Quiniæ Ammoniata	½-2 fl. drm.

U.S.P. Quininæ Bisulphas. BISULPHATE OF QUININE, $C_{20}H_{24}N_2O_2H_2SO_4.7H_2O$; 548.

CHARACTERS.—Colourless, clear, orthorhombic crystals or small needles, efflorescing and becoming opaque on exposure to air, no smell, very bitter taste, strongly acid reaction. It resembles the sulphate in its reactions, but is much more readily soluble. It

dissolves with vivid blue fluorescence in 10 parts, while the sulphate requires 740 parts, of water at 59° F.

U.S.P. Quininæ Hydrobromas. HYDROBROMATE OF QUININE, $C_{20}H_{24}N_2O_2HBr.2H_2O$; 440·8.

CHARACTERS. — Colourless, lustrous needles, no smell, very bitter taste, and a neutral or slightly alkaline reaction. It is soluble in about 16 parts of water at 59° F. The solution gives the reaction of quinine, and with test solution of nitrate of silver yields a white precipitate insoluble in diluted nitric acid, and in solution of carbonate of ammonium.

ACTION.—Useful for **hypodermic injection.** It is supposed to produce fewer unpleasant head symptoms than other preparations of quinine.

U.S.P. Quininæ Hydrochloras. HYDROCHLORATE OF QUININE, $C_{20}H_{24}N_2O_2H\ Cl.2H_2O$; 396·4.

CHARACTERS.—White needles forming tufts, no smell, bitter taste, neutral or faintly alkaline reaction. It gives the reaction of quinine, and with test solution of nitrate of silver produces a white precipitate insoluble in nitric acid, but soluble in ammonia.

USES.—Like those of the bisulphate.

U.S.P. Quininæ Valerianas. VALERIANATE OF QUININE, $C_{20}H_{24}N_2O_2C_5H_{10}O_2.\ H_2O$; 444.

CHARACTERS.—White pearly crystals with a slight odour of valerianic acid, a bitter taste and a neutral reaction. The solution when acidulated with sulphuric acid emits the odour of valerianic acid, and gives the reactions of quinine.

USE.—As a tonic in hysteria and nervous irritability. It is said to be particularly useful in some forms of intermittent and spasmodic nervous affections (*vide* p. 867).

U.S.P. Quinidinæ Sulphas. SULPHATE OF QUINIDINE, $(C_{20}H_{24}N_2O_2)_2H_2SO_4.\ 2H_2O$; 782.—It is chiefly obtained from *Cinchona Pitayensis.*

CHARACTERS.—White silky needles, no smell, very bitter taste, with a neutral or faintly alkaline reaction. It is soluble in 100 parts of water at 59° F. Its solution when acidulated with sulphuric acid has a blue fluorescence, and gives an emerald green reaction like quinine. It is distinguished from quinine by adding water of ammonia to the solution, when a white precipitate is thrown down; and this precipitate of quinidine is only sparingly soluble, while quinine is readily soluble in excess of ammonia or ether.

U.S.P. Cinchonina. CINCHONINE, $C_{20}H_{24}N_2O$; 308.

CHARACTERS.—White somewhat lustrous prisms or needles, no smell, at first nearly tasteless, but developing a bitter after taste and having an alkaline reaction. Almost insoluble in hot or cold water, readily soluble in diluted acids. Forming salts of a very bitter taste. Its solution in diluted sulphuric acid does not

fluoresce if quinine or quinidine be absent. The alkaloid precipitated by ammonia is distinguished from the other cinchona alkaloids by requiring at least 300 parts of ether to dissolve it.

U.S.P. Cinchoninæ Sulphas. SULPHATE OF CINCHONINE, $(C_{20}H_{24}N_2O_2H_2SO_4)_2H_2O$; 750.

CHARACTERS.—Hard, white, shining prisms, no smell, very bitter taste, soluble in about 70 parts of water at 59° F. in 60 of chloroform and readily in diluted acids. Ammonia precipitates cinchonine from its solution, which gives the reactions already mentioned. The salt dried and macerated for half-an-hour with 70 times its weight of chloroform at 59° F. is dissolved (the sulphates of quinine or cinchonidine are not dissolved).

U.S.P. Cinchonidinæ Sulphas. SULPHATE OF CINCHONIDINE $(C_{20}H_{24}N_2O)_2H_2SO_4.3HO$; 768.

CHARACTERS.—White silky lustrous needles, no smell, very bitter taste, and a neutral or faintly alkaline reaction, soluble in 100 parts water at 59° F. Its solutions like those of cinchonine do not fluoresce when pure; when precipitated from its solutions by ammonia cinchonidine dissolves in about 75 times its weight of ether, while cinchonine requires four times as much.

U.S.P. Chinoidinum. CHINOIDIN. (QUINOIDIN). A mixture of alkaloids mostly amorphous obtained as a by-product in the manufacture of the crystallisable alkaloids from cinchona.

CHARACTERS.—A brownish-black or almost black solid, breaking when cold with a resinous shining fracture, becoming plastic when warmed, odourless,, having a bitter taste and an alkaline reaction. Almost insoluble in water, freely soluble in alcohol, chloroform and diluted acids.

USE.—It is of uncertain composition, and liable to adulteration, and is employed instead of quinine on account of its cheapness.

U.S.P. CINCHONA ALKALOIDS AND THEIR SALTS.

	DOSE.
Quinina	½-2 grs. as tonic; 2-5 grs. repeated every 2-4 hours as antipyretic. 15-20 grs. a large dose.
Quininæ Sulphas	The same.
,, Bisulphas	A little larger.
,, Hydrobromas	The same as for quinia.
,, Valerianas	1-2 grs.
Quinidinæ Sulphas	Same as quinia.
Chinoidinum	Somewhat larger than of the crystalline alkaloids.
Chinonidinæ Sulphas	1-15 grs.
Cinchonina	About one half more than of quinia.
Cinchoninæ Sulphas	,, ,, ,, ,,

Physiological Action.

GENERAL ACTION.—A solution of quinine when added to **albumen** loses its fluorescence and seems to enter into combination with it, for the albumen is rendered less soluble and more coagulable (p. 44).

It lessens **protoplasmic** and amœboid **movements** (pp. 47, 48, 51), and destroys low animal and vegetable organisms, but salt water amœbæ seem to withstand the action of quinine to a great extent.

Quinine diminishes **oxidation** (p. 58) and diminishes and prevents the development of a blue colour on the addition of a few drops of blood to a solution of tincture of guiac and ozonic ether (p. 55). A similar but less marked effect is seen if blood be taken from an animal into which quinine has been previously injected, instead of mixing the quinine directly with the blood.

Quinine diminishes and in large doses arrests **fermentation,** especially when it depends on organised ferments (as alcoholic, lactic, or butyric fermentations), but does not prevent the change of starch into sugar by ptyalin, or of amygdalin into oil of bitter almonds by emulsion. It has, however, an action on some enzymes (p. 61), and diminishes the action of pepsin on albumen. It is a powerful **antiseptic** (p. 77), and a dilute solution will preserve meat, milk, butter or urine for a length of time. **It is absorbed** from all mucous membranes, and is better given in solution, as some of the powder passes out in the fœces. It forms with the bile a salt which is sparingly soluble, except in excess of bile; hence before giving quinine in malaria, clear out the liver by administering an emetic and a cholagogue purgative.

SPECIAL ACTION.—**On the Alimentary Canal.**—When taken into the mouth, quinine causes a persistent bitter taste if the solution be neutral or only slightly acid, for then the alkalinity of the saliva precipitates the alkaloid; but if given with an excess of acid, and a little water, the bitter taste soon disappears, leaving a sweetish one behind. The bitter taste produces increased flow of saliva by reflexly influencing the centre in the medulla. When quinine is injected into the duct of the submaxillary gland it prevents the secretion of watery saliva by paralysing the ends of the chorda tympani, or by acting directly on the secretory cells themselves (p. 310). The secretion of the thick ropy saliva is not prevented, for the sympathetic is not paralysed except by large doses (p. 311). The vaso-dilator nerve fibres are not paralysed, for if they be stimulated the blood-vessels dilate, the lymph spaces become full and the gland œdematous, but no secretion takes place.

When taken into the **stomach** small doses increase the appetite, especially in atonic dyspepsia, but if the stomach is irritable quinine causes loss of appetite and may produce nausea and vomiting (p. 317). If the stomach be congested the flow of mucous secretion will be increased by quinine. Large doses diminish the appetite, and may cause nausea and vomiting. When it causes vomiting, the addition of hydrobromic acid will often enable it to be borne.

The action of quinine on the secretions and peristalsis of the

intestines is unknown, as also is its action on the secretion of bile, though it is certain that it does not increase it.

When absorbed into the **blood,** quinine causes contraction of the spleen, and in large doses lessens the contractile power and amœboid movements of the white blood corpuscles. It thus checks the diapedesis of the white blood corpuscles (p. 48).

The size of the red corpuscles is increased (p. 49), but their power of giving up oxygen seems to be diminished, as is shown by the guaiacum test (p. 55).

On the Circulation.—Small and moderate doses increase the strength of the circulation, but how they act has not been ascertained.

Large doses diminish the blood-pressure, chiefly by weakening the heart but partly by paralysing the vaso-motor centre, thus causing dilatation of the vessels. This paralysis occurs from very large doses. It is evidenced by the fact that irritation of a sensory nerve or asphyxia no longer produces contraction of the vessels and rise of blood-pressure.

The **heart's** action is weakened by quinine, from its action on the motor ganglia, and probably also on the muscular fibres of the heart itself.

The **vagus nerve** is little affected by moderate doses, but is finally paralysed by very large doses. In poisoning by quinine **death** generally occurs from failure of the respiration, and only occurs through cardiac paralysis if the drug be injected directly into the circulation in large doses; the animal then dies in convulsions consequent on stimulation of the nerve centres by the venous condition of blood thus produced.

On the Respiration.—Small doses have no effect on it. Moderate doses quicken the respiratory movements, but large doses first slow, and then stop them, by paralysing the respiratory centre. The amount of oxygen taken in and of carbon dioxide exhaled is diminished. This is due to the action of the drug on tissue change and on the red blood corpuscles (p. 58).

On Tissue Change.—Moderate doses diminish tissue change (p. 364) and lessen the nitrogen and sulphates in the urine, but increase its total quantity. In fever, especially when due to septic poisoning, the **temperature** of a patient is lowered by quinine. It is also lowered in an animal even after section of the cord and wrapping up in cotton-wool, showing that the fall is due to the lessened tissue change and oxidation in the body. When given in fever quinine increases the amount of nitrogen in the urine.

On the Nervous System.—In man small doses give tone to the system generally.

Large doses cause symptoms to which the term **cinchonism** (or quinism) has been applied; these consist in a feeling of tightness across the forehead, ringing in the ears, deafness, diminution of the power of sight and accuracy of feeling (p. 194). These symptoms

may generally be relieved by giving 30 minims of hydrobromic acid with each dose. Ergot also tends to prevent or remove them.

By **still larger doses** the powers of hearing and sight are more affected, sometimes complete deafness being produced. Giddiness, headache, staggering gait, and muscular weakness succeed, and the circulation becomes feeble.

With **very large doses** delirium occurs and occasionally death, sometimes in convulsions.

Small doses stimulate, large doses depress, the functions of the **brain**, lessening the powers of thought, but may stimulate the motor centres and cause epileptic fits (p. 159).

Spinal Cord.—Reflex action is diminished, especially in the frog. Immediately after the injection of quinine into the lymph-sac of a frog a great depression of reflex action occurs. This was attributed by Chaperon to stimulation of Setschenow's centres by the quinine. It is probably, however, only reflex depression, due to the local irritation of the injection. At a later stage of poisoning considerable depression of the reflex action is also observed, which has been attributed to gradual paralysis of the cord from feebleness of the heart and consequent failure of the circulation. **Sensory and motor nerves** are only affected by the drug when locally applied. The **muscles** retain their irritability till near death, but their capacity for work as well as their irritability is diminished. The muscular curve is somewhat prolonged (p. 104). During its **excretion** quinine stimulates the genito-urinary tract, and occasionally produces irritability of the bladder and urethra. It is said to produce contraction of the gravid **uterus,** and is therefore to be given with care in pregnancy.

USES.—From its power of destroying germs and preventing putrefaction, quinine is used as a local **antiseptic.** As a lotion it is useful in conjunctivitis, and in the diphtheritic form of this disease quinine destroys the power of the secretion to cause inflammation when inoculated into another eye.

Hay fever, which probably is caused by the presence of the pollen of grasses, is often relieved by washing the nose with a saturated aqueous solution of sulphate of quinine (about $\frac{1}{2}$ grain to 1 fl. oz.), (p. 421). Sometimes it is quite useless.

Sorethroat is often relieved by a gargle of quinine (c.f. p. 737).

Whooping-cough is often relieved by quinine, which may be inhaled in the form of spray.

After the evacuation of an empyema or pleural effusion, a solution of quinine may be injected as an antiseptic into the pleural cavity.

As a **tonic** it is useful in general debility; it increases the appetite and muscular strength; may be advantageously combined with iron.

As an **antiperiodic** it is used in ague, malarial fever, and all malarial remittent affections, with great efficiency, being almost a

specific. It should be given in doses of 3 or 4 grains, three times a day, or in a single dose of 10 grains just before a fit comes on; it will often cut short a fit of moderate intensity. An emetic or chalogogue purgative should be given before it (p. 354). In malarial cachexia without distinct fits, it is much less serviceable.

In neuralgia of the intestine, when due to malaria, 5 grains should be administered in one dose, followed by 5 more in a quarter of an hour if no relief is obtained. It will also cure other forms of neuralgia not apparently due to malaria, and even when not of a periodic character. It is especially useful in supra-orbital neuralgia.

Intermittent headache is often greatly relieved by 5 grains of quinine, especially if calomel, grey powder, or podophyllin be also given along with it (c.f. pp. 326, 355) to act on the liver.

As an **antipyretic** large doses (5-20 grs.) lessen the temperature in typhus, enteric, and other fevers. It is better to give a single large dose once a day, or two doses of 5 grains given in the same hour, between five and six in the evening.

In symptomatic fevers quinine has been used to reduce the temperature, as in pneumonia.

In rheumatism and exanthemata it is not much used.

In the treatment of worms quinine is useful to prevent the accumulation of mucus which forms a nidus for the worm.

As a **prophylactic** agent against ague and all intermittent affections quinine is invaluable.

Warburg's tincture containing quinine and a number of aromatics is very useful in cases of collapse from various causes.

The other alkaloids of cinchona seem to have very much the same action as quinine.

Sometimes people who work with cinchona barks are attacked with great irritation of the skin; this is probably due to the mechanical action of minute spicules of the bark.

COFFEÆ.

Ipecacuanha. IPECACUANHA. IPECAC. U.S.P.—The dried root of *Cephaëlis Ipecacuanha*, Brazil.



FIG. 165.—Ipecacuanha.

CHARACTERS.—In pieces about the size of a small quill, contorted and irregularly annulated. Colour brown, of various shades. It consists of two parts, the cortical or active portion which is brittle, and a slender, tough, white, woody centre. This hard centre and the annulated appearance of the cortex give to the root the appearance of a number of brown beads strung on a white thread.

COMPOSITION.—The woody centre is inert. The cortical part contains an alkaloid, emetine, and an acid, ipecacuanic acid, which is a glucoside allied to tannic acid.

PREPARATIONS.

B.P.	DOSE.
Pilula Conii Composita	5-10 grs.
Pilula Ipecacuanhæ cum Scilla...	5-10 grs.
Pulvis Ipecacuanhæ Compositus	5-14 grs.
Trochisci Ipecacuanhæ ($\frac{1}{4}$ gr. in each)	1-3
Trochisci Morphiæ et Ipecacuanhæ	1-6
Vinum Ipecacuanhæ (as an emetic)	3-6 fl. drm.
,, ,, (as an expectorant)	5-40 min.

(of the powdered root, as emetic, 15-30 grs. ; in dysentery, 20-30 grs. in a bolus.)

U.S.P.	DOSE.
Extractum Ipecacuanhæ Fluidum (as expectorant)	5 min.
,, ,, ,, (as emetic)	25 min.
Pulvis Ipecacuanhæ et Opii	5-15 grs.
Trochisci Ipecacuanhæ ($\frac{1}{4}$ gr. in each)	1-4.
Trochisci Morphinæ et Ipecacuanhæ ($\frac{1}{40}$-gr. of morphine, $\frac{1}{12}$-gr. ipecac.)	
Tinctura Ipecacuanhæ et Opii	4-15 min.
Syrupus Ipecacuanhæ (as expectorant)	2-30 min.
,, ,, (as emetic)	$\frac{1}{2}$-1 fl. oz.
Vinum Ipecacuanhæ (as expectorant)	3-5 min.
,, ,, (to relieve vomiting)	half a drop.

Pulvis Ipecacuanhæ Compositus. COMPOUND POWDER OF IPECACUANHA, B.P. **Pulvis Ipecacuanhæ et Opii.** POWDER OF IPECAC AND OPIUM, U.S.P. (DOVER'S POWDER).—Ipecacuanha, $\frac{1}{2}$; opium, $\frac{1}{2}$; sulphate of potash, 4, B.P. Ipecac, 10 ; powdered opium, 10 ; sugar of milk, 80, U.S.P.

B.P. Pilulæ Ipecacuanhæ cum Scilla. PILL OF IPECACUANHÆ WITH SQUILL. —Compound powder of ipecacuanha, 3 ; squill, 1 ; ammoniacum, 1 ; treacle, q.s.

PHYSIOLOGICAL ACTION.—In **frogs** small doses of emetine cause irregularity of the heart, with final stoppage in diastole and loss of irritability of the cardiac muscle. Larger doses paralyse the central nervous system and diminish the contractile power of the muscles (p. 105).

Locally applied to the skin or mucous membranes, it acts as an irritant and may produce a pustular eruption. In some persons it has a peculiarly irritating action on the respiratory tract, so that almost infinitesimal quantities of the powder cause running at the nose, and sometimes asthma. When taken internally, it is an irritant to the mucous membrane of the **stomach,** and acts as a prompt emetic. This is partly due to the local action of the drug on the ends of the vagus in the stomach, and, when absorbed into the blood, to its action on the vomiting centre in the medulla.

Emetine produces in dogs, both when injected under the skin and when administered internally, diarrhœa which is sometimes bloody. The **intestinal** mucous membrane is swollen, red, and ecchymosed as in poisoning by arsenic, antimony, platinum, iron, or sepsine.

When injected either subcutaneously or into the veins it produces death by cardiac paralysis. It paralyses the **vessels** first,

and then the **heart,** so that the blood-pressure sinks nearly to zero while each cardiac pulsation is still powerful and produces a considerable wave in the blood-pressure tracing.

The **lungs** are often congested, œdematous, or in a state of red hepatisation, especially in rabbits.

In medicinal doses it increases the secretion from mucous membranes often very markedly, and is hence used to increase the expectoration and render it more fluid in bronchitis (p. 218). It is slightly diaphoretic independently of the effect produced by its nauseating qualities.

THERAPEUTICS.—Ipecacuanha is used as an **emetic** in cases of poisoning and in overloaded conditions of the stomach; to clear out the trachea and larynx in croup and diphtheria (1 teaspoonful of vin. ipec. every ¼ hour, in a child, till vomiting occurs); to empty the bronchial tubes in chronic bronchitis when choked up with mucus.

In jaundice depending on catarrhal conditions of the bileducts it is useful to lessen the viscidity of the mucus; also in jaundice depending on the presence of a small calculus.

As a **diaphoretic** it is given in suddenly suppressed menstruation, and in rheumatism, muscular or acute, in the form of Dover's Powder; also in catarrhs. In small doses it is often useful in vomiting from various causes, *e.g.* vomiting of pregnancy.

As an **expectorant** (p. 218) it is very useful when the bronchial secretion is scanty, tough, and difficult to expectorate. Ringer strongly recommends the spray of ipecacuanha wine in winter cough and bronchial asthma.

Ipecacuanha is very useful as an **anti-dysenteric,** especially in the acute dysentery of the tropics; large doses (30 gr.) must be given on an empty stomach, preceded by a dose of laudanum half an hour before, to still the stomach and prevent vomiting. No water must be taken with it and the patient must lie down with his head low.

PRECAUTIONS.—Large doses must not be given to pregnant women, or to old people with atheromatous arteries. The wine is apt to lose its power by keeping, and hence it is best to preserve it in small sealed bottles.

Caffea. COFFEE. Not officinal.—The seed of *Coffea arabica.*

COMPOSITION.—Unroasted coffee contains caffeine and a kind of tannin called caffeotannic acid. During roasting a part of the caffeine is volatilised and an empyreumatic substance called caffeon is developed.

ACTION.—The action of coffee is somewhat like that of caffeine (p. 797). but differs from it in some respects, inasmuch as the caffeon increases the peristaltic movements of the intestine, and causes, indeed, tetanic contraction of it, while caffeine does not alter peristaltic movements. Caffeon quickens the pulse, dilates the vessels and lowers the blood-pressure, and produces a sensation

of warmth on the surface. In some persons coffee produces a feeling of weight in the abdomen and a **tendency to hæmorrhoids.** As tea has not this action, or has it only to a comparatively slight extent, it is probably due to the combined action of the caffeine and caffeon.

USE.—Coffee is used chiefly as a remedy in headache and as a **stimulant** in cases of opium poisoning.

B.P. Catechu Pallidum. PALE CATECHU.—An extract of the leaves and young shoots of *Uncaria Gambier* and *U. Acida.* Eastern Archipelago.

CHARACTERS.—In cubes about an inch square, or masses formed of coherent cubes, externally brown, internally ochrey-yellow or pale brick-red, breaking easily with a dull earthy fracture. Taste bitter, very astringent and mucilaginous, succeeded by slight sweetness.

The catechu of the U.S.P. is an extract prepared from the wood of *Acacia Catechu,* Leguminosæ (p. 828).

COMPOSITION.—Contains catechu-tannic acid and catechuic acid or catechin, which is related to catechu-tannic acid in the same way as gallic to tannic acid. There is also a yellow colouring matter, quercitin.

ADULTERATION.—Starch.

TESTS.—The decoction when cool is not rendered blue by iodine.

B.P.	PREPARATIONS.	DOSE.
Infusum Catechu	(catechu, 160 gr. ; cinnamon, 30 gr. ; water, ½ pint)	1-1½ fl. oz.
Pulvis Catechu Compositus	(pale catechu, 4 oz. ; kino and rhatemy, of each 2 oz. ; cinnamon and nutmeg, of each 1 oz.)	20-40 gr.
Tinctura Catechu		1-2 fl. drm.
Trochisci Catechu		1-3 or more.

USES.—Catechu is employed as a local remedy in relaxed sore throat. It may sometimes be chewed with advantage before taking food by persons suffering from pyrosis. Its use in such cases is probably to diminish the coating of mucus on the gastric mucous membrane. It is also employed in diarrhœa as an **astringent** (*vide* also p. 829).

VALERIANACEÆ.

B.P. Valerianæ Radix. VALERIAN ROOT.—The dried root of *Valeriana officinalis.* From plants indigenous to and also cultivated in Britain.



FIG. 166.—Valerian.

U.S.P. Valeriana. VALERIAN.—The rhizome and rootlets of *Valeriana officinalis.*

CHARACTERS.—A short, yellowish-white rhizome, with numerous fibrous roots about two or three inches long; of a bitter taste and penetrating odour, agreeable in the recent root, becoming fetid by keeping; yielding volatile oil and valerianic acid when distilled with water.

COMPOSITION.—Contains a volatile oil and valerianic acid.

PREPARATIONS.

B.P.	DOSE.
Infusum Valerianæ (2 drm. in ½ pint)	1-2 fl. oz.
Tinctura Valerianæ (2½ oz. in 1 pint spirit)	1-2 fl. drm.
Tinctura Valerianæ Ammoniata (2½ oz. in 1 pint aromatic spirit of ammonia)	½-1½ fl. drm.

U.S.P.	DOSE.
Abstractum Valerianæ	15-45 gr.
Extractum Valerianæ Fluidum	15-30 min.
Tinctura Valerianæ (20 per cent.)	1-2 fl. drm.
Tinctura Valerianæ Ammoniata (20, in aromatic spirit of ammonia up to 100)	1-2 fl. drm.
Oleum Valerianæ	One or more drops.
Quininæ Valerianas	1-2 gr.

U.S.P. Oleum Valerianæ. OIL OF VALERIAN.—A volatile oil distilled from Valerian.

CHARACTERS.—A greenish or yellowish, thin liquid, becoming darker and thicker by age and exposure to air, having the characteristic odour of valerian, an aromatic, somewhat camphoraceous taste, and a slightly acid reaction, sp. gr. about 0·950. It is readily soluble in alcohol.

ACTION AND USES.—The activity of valerian is chiefly due to the volatile oil it contains, and not to the valerianic acid. The **oil** in large doses **paralyses** both the **brain** and **spinal cord,** and lessens the convulsions due to strychnia poisoning, lowers the **blood-pressure** and slows the **pulse**. It is employed as an **antispasmodic** and stimulant in cases of hysteria and is most useful in those occurring in delicate and young women.

Valerianate of zinc has been supposed to combine the nervine tonic action of zinc with the antispasmodic effect of valerian, but it is much better to use valerian itself or its oil along with a salt of zinc, as the acid has no important physiological action. It is used in chorea, especially when occurring in hysterical persons, and should not be discontinued until symptoms of nausea begin to make their appearance. It is also employed in epilepsy and neuralgia.

Valerianate of iron and valerianate of ammonia have also been used in medicine, and may be given in the same doses as the corresponding salt of zinc. For the action of valerianate of quinine (*vide* p. 858).

CAPRIFOLIACEÆ.

U.S.P. Viburnum. VIBURNUM. BLACK HAW.—The bark of *Viburnum prunifolium.*

CHARACTERS.—In thin pieces or quills, glossy purplish-brown, with scattered warts, and minute black dots; when collected from old wood, greyish-brown; the thin, corky layer easily removed from the green layer; inner surface whitish, smooth; fracture short; inodorous; somewhat astringent and bitter.

PREPARATION.

	DOSE.
Extractum Viburni Fluidum	30-60 min.

USES.—It is said to be useful in preventing threatened abortion, and in **dysmenhorrhœa.** Its action is not well understood.

COMPOSITÆ.

Pyrethri Radix, B.P.; Pyrethrum, U.S.P. PELLITORY ROOT, B.P.; PYRETHRUM, U.S.P.—The root of *Anacyclus pyrethrum.* The Levant.

CHARACTERS.—In pieces about the length and thickness of the little finger, covered with a thick brown bark studded with black shining points. It breaks with a resinous fracture and presents internally a radiated structure. When chewed it excites a prickling sensation in the lips and tongue, and a glowing heat.

COMPOSITION.—A resin, the properties of which are not yet fully known; also a volatile oil and sugar.

PREPARATION.

B. and U.S.P.	DOSE.
Tinctura Pyrethri	10-20 m.

ACTION AND USES.—Pellitory is a local irritant, increasing the flow of **saliva** when taken into the mouth. It is used as a masticatory in dryness of the mouth, relaxed conditions of the throat, aphonia, and paralysis of the tongue or throat. It is also employed as a masticatory in headache and neuralgia of the head or face. The tincture diluted with water may be used as a gargle in similar conditions. The tincture may be applied on cotton wool to carious teeth to lessen the pain, but that of the pharmacopœia is hardly strong enough. It has been given internally with success in globus hystericus in doses of 10 to 20 drops four times a day.

U.S.P. Absinthium. WORMWOOD.—The leaves and tops of *Artemisia absinthium.* Leaves about two inches (5 centimetres) long, hoary, silky-pubescent, petiolate, roundish-triangular in outline, pinnately two or three-cleft, with the segments lanceolate, the terminal one spatulate, tracts three-cleft or entire; heads numerous,

subglobose, with numerous small pale yellow florets, all tubular and without pappus; odour aromatic; taste persistently bitter.

PREPARATION.

Vinum Aromaticum.

DOSE.—Of the powder 20-40 gr. It may be given with advantage as infusion (1 oz. to 2 fl. oz.), of which 1-2 fl. oz. may be given. It strikes blue with iron salts.

ACTION.—It contains a volatile oil and a bitter principle, absinthin. To the bitter principle it owes its action in stimulating the digestive organs. The volatile oil is a narcotic poison. In dogs and rabbits it causes trembling, stupor, **epileptiform convulsions** with involuntary evacuations, and stertorous breathing, which may or may not end in death. Similar symptoms may be produced in man.

USE.—It is a bitter **stomachic tonic,** and is used for atonic dyspepsia. It is said to be **anthelmintic.**

U.S.P. Tanacetum. TANSY.—The leaves and tops of *Tanacetum vulgare.*

CHARACTERS.—Leaves about six inches (15 centimetres) long; bipinnatified, the segments oblong, obtuse, serrate or incised, smooth, dark green, and glandular; flower-heads corymbose, with an imbricated involucre, a convex, naked, receptacle, and numerous yellow, tubular florets; odour strongly aromatic; taste pungent and bitter.

COMPOSITION.—Tansy contains a powerful and irritating volatile oil.

USES.—It is seldom used in regular practice. Fatal cases of poisoning from this drug have been reported, the symptoms being epileptiform convulsions and coma, feeble pulse and death. Its action thus resembles that of absinthe. It has been used as a **diuretic** and **stimulant** in rheumatism, ague, and hysteria, as an **emmenagogue** in amenorrhœa, and sometimes as an **anthelmintic.** It is generally given as an infusion.

Santonica, B. and U.S.P. SANTONICA.—The unexpanded flower-heads of *Artemisia maritima,* var. *Stechmanniana.* Imported from Russia.

CHARACTERS.—Flower-heads resembling seeds in appearance, fusiform, blunt at each end, pale greenish-brown, smooth; odour strong, taste bitter, camphoraceous. Flower-heads not round or hairy.

COMPOSITION.—Santonin about 2 per cent., also essential oil and fatty acids.

PREPARATION.

B. & U.S.P.	DOSE.
Santoninum	1-3 gr. for a child. 2-6 gr. or more for an adult.

B. and U.S.P. Santoninum. SANTONIN. $C_{30}H_{18}O_6$ or $C_{15}H_{18}O_3$.—A crystalline neutral principle prepared from *Santonica*

CHARACTERS AND TESTS.—Colourless, flat, rhombic prisms, feebly bitter, fusible and sublimable by a moderate heat; scarcely soluble in cold water, sparingly in boiling water, but abundantly in chloroform and in boiling rectified spirit. Sunlight renders it yellow; not dissolved by diluted mineral acids; entirely destructible by a red heat with free access of air.

PREPARATION.—The santonica is boiled with milk of lime, strained and partially evaporated. Hydrochloric acid is added to the hot solution, which is set aside to allow the santonin to subside and to separate from oily matter which is removed by skimming. The precipitate is washed with water and ammonia, and purified by boiling in spirit with a little animal charcoal, which is separated by filtering. On the liquid cooling crystals, of santonin are deposited. It is to be protected from light.

PREPARATION.

U.S.P.	DOSE.
Sodii Santoninas (p. 559)	8-10 gr.
Trochisci Sodii Santoninatis	1-8 troches.

PHYSIOLOGICAL ACTION.—Large doses of santonin given to a frog cause paralysis of the **cerebrum** with abolition of voluntary movement, followed by stimulation of the **medulla** causing convulsions, which cease on section of the cord. In man, large doses cause headache, giddiness, vomiting, and sometimes death by **convulsions,** with a tendency to paralysis of the respiration between the convulsions; hence in a case of poisoning treat with chloroform to lessen the convulsions and keep up artificial respiration.

It produces a peculiar disturbance of **vision,** so that at first everything appears of bluish and afterwards yellowish or greenish-yellow. The blue appearance lasts only a short time, the yellow vision lasts much longer. This condition is usually regarded as due to stimulation, and subsequent paralysis, of those fibres of the retina by which blue light is perceived. It is eliminated as a soda salt in the **urine** and colours it bright yellow; if the urine is rendered alkaline it becomes blood red; these colours are probably due to some product of the oxidation of santonin. The quantity of urine is increased and the patient has a constant desire to micturate; in children it may give rise to incontinence of urine.

THERAPEUTICS.—It is used almost entirely as a **vermicide** for round worms in doses of 2-5 gr. every other night, followed by a purgative. It should be given three or four times. It is useless against tape-worms. It has been frequently used as an injection against thread-worms (2-5 gr. in ʒi. of castor oil).

The best method of administration probably is to give it in castor oil, although not unfrequently it is given in powder for two or three nights running, the last powder being followed by a dose of castor oil next morning. It is best given at bed-time as the effect on the sight passes off to a great extent during the night.

Anthemidis Flores, B.P.; Anthemis, U.S.P. CHAMOMILE FLOWERS, B.P.; ANTHEMIS, U.S.P.—The dried single and double flower-heads of the common chamomile, *Anthemis nobilis* (collected from cultivated plants, U.S.P.).

CHARACTERS.—Subglobular heads, about three-quarters of an inch (2 centimetres) broad. The single variety consists of both yellow tubular and white strap-shaped florets; the double, of white strap-shaped florets only; all arising from a conical scaly receptacle; both varieties, but especially the single, are bitter and very aromatic.

COMPOSITION.—Essential oil, removed by distillation, also a bitter acid in small quantity.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Extractum Anthemidis	2-10 gr.	None.
Infusum Anthemidis	1-4 fl. oz.	
Oleum Anthemidis	1-5 min.	

B.P. Infusum Anthemidis. INFUSION OF CHAMOMILE.—Chamomile flowers ½ oz.; boiling water, 10 fl. oz.; infuse for quarter of an hour and strain.

B.P. Oleum Anthemidis. OIL OF CHAMOMILE.—The oil distilled in Britain from chamomile flowers.

CHARACTERS.—Pale-blue or greenish-blue, but gradually becoming yellow; with the peculiar odour and aromatic taste of the flowers.

PREPARATION.

B.P.	DOSE.
Extractum Anthemidis	2-10 gr.

USES.—It is an aromatic **tonic, stomachic,** and **carminative.** It is used in atonic dyspepsia accompanied by flatulence; also in summer diarrhœa in children and in sick headache.

U.S.P. Matricaria. GERMAN CHAMOMILE.—The flower-heads of *Matricaria chamomilla.*

CHARACTERS.—About three-fourths of an inch (18 millimetres) broad, composed of a flattish, imbricate involucre, a conical, hollow, naked, receptacle, about fifteen white, ligulate, reflexed ray-flowers, and numerous yellow, tubular, perfect flowers without pappus.

ACTION AND USES.—Strongly aromatic, **bitter, carminative,** and **anthelmintic.** It is generally used as an infusion or decoction like chamomile.

U.S.P. Eupatorium. EUPATORIUM. THOROUGHWORT.—The leaves and flowering tops of *Eupatorium perfoliatum.*

CHARACTERS.—Leaves opposite, united at base, lanceolate, from four to six inches (10 to 15 centimetres) long, tapering, crenately serrate, rugosely veined, rough above, downy and resinous-dotted beneath; flower-heads corymbed, numerous, with an oblong involucre of lance-linear scales, and with from ten to fifteen white

florets, having a bristly pappus in a single row; odour weak and aromatic; taste astringent and bitter.

OFFICINAL PREPARATION.

	DOSE.
Extractum Eupatorii Fluidum	15–30 min.

COMPOSITION.—It contains a volatile oil and a bitter glucoside eupatorin.

USE.—It is used as a **tonic** and **diaphoretic.** In large doses it causes catharsis and emesis. As a tonic it is employed in dyspepsia and general debility. As a diaphoretic it is used to prevent any bad consequences from exposure to cold, and to cut short an attack of catarrh or muscular rheumatism at its commencement. It may then be given as infusion or as fluid extract mixed with hot water. When given in large doses as an emetic and **cathartic,** it is useful in causing expulsion of tapeworm.

Taraxaci Radix, B.P.; Taraxacum, U.S.P. DANDELION ROOT, TARAXACUM.—The fresh and dried roots of *Taraxacum dens-leonis*, var. *officinale.*

CHARACTERS.—Tap-shaped roots, smooth and dark-brown externally, white within, easily broken, and giving out an inodorous, bitter, milky juice, which becomes pale-brown by exposure.

COMPOSITION.—They contain a bitter principle—taraxacin—sugar, inulin, and a considerable quantity of potash and lime salts.

IMPURITY.—Common hawkbit fraudulently mixed.

TESTS.—Not wrinkled or pale-coloured externally; juice not watery; any adherent leaves runicate and quite smooth.

PREPARATIONS.

B.P.	DOSE.
Decoctum Taraxaci (dried root, 1 oz.; water, 1 pint)	2-4 fl. oz.
Extractum Taraxaci (fresh)	5-30 gr.
Succus Taraxaci (fresh)	1-2 fl. drm. or more.

U.S.P.	DOSE.
Extractum Taraxaci	30-60 gr.
,, ,, Fluidum	½-2 fl. drm.

ACTION AND USES.—It is supposed to have a stimulant action on the **liver,** increasing its secretion, and is used in biliary disorders and dyspepsia. It has also a **diuretic** action.

B.P. Lactuca. LETTUCE.—The flowering herb of *Lactuca virosa.*

COMPOSITION.—It contains lactucarium.

PREPARATION.

B.P.	DOSE.	U.S.P.
Extractum Lactucæ	5-30 gr.	None.

U.S.P. Lactucarium. LACTUCARIUM.—The concrete milk-juice of *Lactuca virosa.*

CHARACTERS.—In sections of plano-convex, circular cakes, or in irregular, angular pieces, externally gray-brown or dull reddish-brown, internally whitish or yellowish, of a waxy lustre; odour heavy, somewhat narcotic; taste bitter. It is partly soluble in alcohol and in ether, and when triturated with water, it yields a turbid mixture.

COMPOSITION.—Its chief ingredient is a bitter substance—lactucin.

PREPARATIONS.

	DOSE.
Extractum Lactucarii Fluidum	3-60 min.
Syrupus Lactucarii	2 fl. drm.

DOSE.—Of lactucarium, 5-30 gr.

ACTION AND USE.—Lettuce has a somewhat **soporific** action, and the extract has been used for sleeplessness. Lactucarium is used instead of opium to **allay cough,** quiet nervousness, and induce sleep in cases where, from idiosyncrasy, opium is not borne.

Arnicæ Radix, B. and U.S.P. ARNICA ROOT.—The dried rhizome and rootlets of *Arnica montana.* Middle and Southern Europe and north-west of the United States.

FIG. 167.—Arnica.

CHARACTERS.—Rhizome cylindrical, contorted, rough from the scars of the coriaceous leaves, of which some usually remain attached, and furnished with numerous long, slender fibres; has a peppery taste and peculiar odour.

COMPOSITION.—Arnicin, a substance having some of the properties of a glucoside. Arnica also contains about one per cent. of an essential oil, with a considerable quantity of inulin.

ADULTERATION.—Sometimes adulterated with other and similar roots. These may be distinguished on close inspection.

PREPARATIONS.

B.P.	DOSE.
Tinctura Arnicæ (1 oz. to 1 pint)	30 min. to 1 fl. drm.

U.S.P.	DOSE.
Extractum Arnicæ Radicis	5-10 gr.
Extractum Arnicæ Radicis Fluidum	10-30 min.
Tinctura Arnicæ Radicis	2-5 fl. drm.
Emplastrum Arnicæ	

U.S.P. Arnicæ Flores. ARNICA FLOWERS.—The flower-heads of *Arnica montana.*

CHARACTERS.—About one and one-fifth inch (30 centimetres) broad, depressed-roundish, consisting of a scaly involucre in two rows, and a small, flat, hairy receptacle, bearing about sixteen yellow, strap-shaped, ray-florets ; and numerous yellow, five-toothed, tubular disk-florets having slender, spindle-shaped achenes, crowned by a hairy pappus. It has a feeble, aromatic odour, and a bitter, acrid taste.

PREPARATION.

U.S.P.	DOSE.
Tinctura Arnicæ Florum	½-2 fl. drm.

ACTION.—Arnica, externally, has a **stimulant** effect on the skin, and if evaporation be prevented it will produce redness and sometimes an erysipelatous inflammation, spreading some distance.

Internally it gives rise to a feeling of warmth in the mouth, stomach, and intestines, also increasing their peristaltic movements. In large doses it produces partial insensibility, convulsions, and sometimes syncope.

USES.—It is very generally used in bruises and sprains, but it has been shown by Dr. Garrod to be no more serviceable than spirit of the same strength, and it has the disadvantage of sometimes producing erysipelatous inflammation. It has been used internally in dysentery, chronic bronchitis, rheumatism, nervous diseases, and malarious conditions. Its value is doubtful.

U.S.P. Calendula. CALENDULA. MARIGOLD.—The fresh, flowering herb of *Calendula officinalis.*

CHARACTERS.—Stem somewhat angular, rough ; leaves alternate, thickish, hairy, spatulate or oblanceolate, slightly toothed, the upper ones sessile ; flower-heads nearly two inches (5 centimetres) broad, the yellow strap-shaped ray-florets in one or several rows, fertile, the achenes incurved and muricate ; odour slightly narcotic ; taste bitter and saline.

PREPARATION.

Tinctura Calendulæ (used externally).

COMPOSITION.—It contains a bitter principle and calendulin. Its physiological action is not well understood.

USES.—It is used as an application to sprains and bruises in somewhat the same way as **arnica.**

U.S.P. Grindelia. GRINDELIA.—The leaves and flowering tops of *Grindelia robusta.*

CHARACTERS.—Leaves about two inches (5 centimetres) or less long, varying from broadly spatulate or oblong to lanceolate, sessile or clasping, obtuse, more or less sharply serrate, pale green, smooth, finely dotted, brittle ; heads many-flowered ; the involucre hemispherical, about half an inch (12 millimetres) broad, composed of

numerous, imbricated, squarrosely-tipped scales; ray-florets yellow, ligulate, pistillate; disk-florets yellow, tubular, perfect; pappus consisting of about three awns of the length of the disk-florets; odour balsamic; taste pungently aromatic and bitter.

Preparation.	Dose.
Extractum Grindeliæ Fluidum	15 min.-1 fl. drm.

Composition.—It probably owes its medicinal properties to a resin and a volatile oil.

Uses.—It has been found useful in spasmodic **asthma,** hay asthma, asthmatic attacks in bronchitis and emphysema, hooping cough, and in chronic bronchitis or bronchorrhœa, especially in old persons. It has also been found to give relief in **dyspnœa** depending on cardiac disease. The oleo-resin appears to be **excreted** by the kidneys, and is useful in catarrh of the urinary passages. As a **local application** it has been recommended to relieve the eruption caused by *Rhus toxicodendron* and to relieve itching and pain in vaginitis and in priapism.

The fluid extract of another non-officinal species, *Grindelia squarrosa*, growing in California, has been recommended as a remedy for enlarged spleen, ague, and **malarious conditions** generally, in doses of 1 fl. drm.

U.S.P. Inula. Inula. Elecampane.—The root of *Inula Helenium.*

Characters.—In transverse concave slices or longitudinal sections, with overlapping bark, externally wrinkled and brown; flexible in damp weather; when dry, breaking with a short fracture; internally greyish, fleshy, slightly radiate and dotted with numerous shining, yellowish-brown resin-cells; odour peculiar, aromatic; taste bitter and pungent.

Administration.—The powder may be given in doses of 20-60 gr. It may be given as a decoction made by boiling ½ oz. of the root in a pint of water. The dose of this is 1-2 fl. oz.

Composition.—It contains a substance closely allied to starch—inulin—a bitter neutral principle—helenin—and a little volatile oil.

Uses.—It is used chiefly as a domestic remedy in **amenorrhœa,** chronic **bronchitis,** and skin diseases. Helenin has been said to be peculiarly destructive to the **tubercle bacillus.** If this statement be substantiated, inula may be useful in phthisis.

U.S.P. Lappa. Lappa. Burdock.—The root of *Lappa officinalis.*

Characters.—About twelve inches (30 centimetres) or more long, and about one inch (25 millimetres) thick; nearly simple, fusiform, fleshy, longitudinally wrinkled, crowned with a tuft of whitish, soft, hairy leafy-stalks; grey-brown, internally paler; bark rather thick, the inner part and the soft wood radially striate,

the parenchyma often with cavities lined with snow-white remains of tissue; odour feeble and unpleasant; taste mucilaginous, sweetish, and somewhat bitter.

USES.—It has no marked therapeutic properties, but is said to be **alterative,** diaphoretic, diuretic, and purgative. It is chiefly used as a domestic remedy as a decoction prepared by boiling 2 oz. of the recent bruised root in three pints of water to two. One pint is taken daily. Burdock is employed in obstinate **skin diseases,** both internally and in the form of poultices of the leaves. It is given also in syphilis, scrofula, rheumatism, gout, and renal disease.

LOBELIACEÆ.

Lobelia, B. and U.S.P. LOBELIA.—The dried flowering herb of *Lobelia inflata.* North America, B.P. The leaves and tops of *Lobelia inflata* collected after a portion of the capsules have become inflated, U.S.P.

CHARACTERS.—B.P. Stem angular; leaves alternate, ovate, toothed, somewhat hairy beneath; capsule ovoid, inflated, ten-ribbed. Usually in compressed rectangular parcels. U.S.P. Leaves alternate, petiolate, the upper ones sessile, ovate or oblong, about 2 inches (5 centimetres) long, irregularly toothed, pubescent, pale green; branches hairy, terminating in long racemes of small, pale blue flowers, having a superior five-toothed calyx, which is inflated in fruit, a two-lipped corolla, and five united stamens; odour slight, irritating; taste mild, afterwards burning and acrid.

COMPOSITION.—Lobelina, a yellowish liquid with alkaline reaction, soluble in water, spirit, and ether, and possessing the poisonous properties of the drug; also an acrid principle, lobelacrin, yielding lobelic acid; resins and a volatile oil are obtained in minute quantities.

PREPARATIONS.

B.P.	DOSE.
Tinctura Lobeliæ (2½ oz. in 1 pint spirit)	10 min. to ½ fl. drm.
Tinctura Lobeliæ Ætherea (2½ oz. in 1 pint spirit of ether)	10 min. to ½ fl. drm. or more.

U.S.P.	DOSE.
Acetum Lobeliæ (in dilute acetic acid 10 per cent.)	½-1 fl. drm.
Extractum Lobeliæ Fluidum	1-5 gr.
Tinctura Lobeliæ (20 per cent.)	½-2 fl. drm.

PHYSIOLOGICAL ACTION.—Taken internally it causes a feeling of burning in the œsophagus, stomach, and intestines; vomiting, headache, giddiness, and great prostration; sometimes followed by convulsions and coma. Hence its action is very **like** that of **tobacco,** only differing in the greater intensity of the local burning sensations. It is often used to excess by the Coffinites, whose theory is "Heat is life," and most cases of poisoning by it are due to its employment by such herbalists. It produces death by

paralysis of the **respiratory centre.** Small doses first raise and then depress the **blood-pressure;** large doses paralyse the **vaso-motor centre** and the peripheral **vagi** (Attwood).

THERAPEUTICS.—It is chiefly used as a remedy in **spasmodic asthma** and other affections of air-passages accompanied by dyspnœa, *e.g.*, chronic bronchitis with a tendency to spasm of the bronchial muscles. Ringer states that larger doses must be used than those given in most text-books; he recommends 10 min. every ten minutes while the fit is on. In a case of poisoning, evacuate the stomach; give demulcents and stimulants.

ERICACEÆ.

Uvæ-Ursi Folia, B.P. BEARBERRY LEAVES.—The dried leaves of *Arctostaphylos Uva-Ursi.* From indigenous plants.

Uva Ursi, U.S.P. UVA URSI. [BEARBERRY.]—The leaves of *Arctostaphylos Uva Ursi.*

FIG. 163.—Uva-Ursi.

CHARACTER.—Obovate, entire, coriaceous, shining leaves, about three-fourths of an inch in length, reticulated beneath; with a strong astringent taste, and a feeble hay-like odour when powdered.

COMPOSITION.—Tannic and gallic acids, and a bitter neutral extractive—arbutin—which is soluble in warm water.

ADULTERATION.—Red whortleberry leaves.

TESTS.—Leaves not dotted beneath nor toothed on the margin.

PREPARATIONS.

B.P.	DOSE.
Infusum Uvæ-Ursi (1 oz. to 1 pint)	1-2 fl. oz.

U.S.P.	DOSE.
Extractum Uvæ-Ursi Fluidum	30-60 min.

USES.—Bearberry is an **astringent** and **diuretic.** It is chiefly used in catarrh of the bladder and of other parts of the genito-urinary passages.

The utility of the leaves is probably due not to the tannic and gallic acids which they contain, but to the arbutin. This substance is partially excreted unchanged, and part of it is decomposed in the body, yielding hydroquinone (p. 732). The hydroquinone is excreted by the kidneys in combination with sulphuric acid. Hydroquinone-sulphuric acid is colourless and is not poisonous. It may become decomposed in the bladder, and the hydroquinone becoming oxidised will give a brown colour to the urine and impart to it antiseptic and irritant properties, which are useful in catarrh of the bladder. The

quantity of arbutin, in the infusion, is too small to be very useful, and yet if the infusion be made stronger it may disagree with the stomach. Pure arbutin is therefore to be preferred, and may be given in doses of 4 gr. or more, three or four times a day, either in powder or in solution.

U.S.P. Chimaphila. CHIMAPHILA. [PIPSISSEWA.]—The leaves of *Chimaphila umbellata.*

CHARACTERS.—About two inches (5 centimetres) long, oblanceolate, sharply serrate above, wedge-shaped and nearly entire toward the base; coriaceous, smooth, and dark green on the upper surface. It is nearly inodorous, and has an astringent and bitterish taste.

OFFICINAL PREPARATION.

U.S.P.	DOSE.
Extractum Chimaphilæ Fluidum	1 fl. dr.
" " " of Chimaphila	30-60 gr.

COMPOSITION.—It contains tannin and several neutral principles found in other Ericaceæ. It is **astringent** and has a **diuretic** action.

USE.—It is employed in disorders of the urinary passages and in the treatment of rheumatic pains.

U.S.P. Oleum Gaultheriæ. OIL OF GAULTHERIA.—Oil of winter-green, a volatile oil distilled from gaultheria.

CHARACTERS.—A colourless, yellow, or reddish liquid, of a peculiar, strong, and aromatic odour, a sweetish, warm, and aromatic taste, and a slightly acid reaction. It is readily soluble in alcohol. When heated to about 80° C. (176° F.) the oil should not yield a colourless distillate, having the characteristics of chloroform or of alcohol. On mixing five drops of the oil with five drops of nitric acid, the mixture should not acquire a deep red colour, and should not solidify to a dark red resinous mass (absence of oil of sassafras).

PREPARATIONS.

	DOSE.
Spiritus Gaultheriæ (oil, 3; spirit, 97)	10-20 min.
Syrupus Sarsaparillæ Compositus	
Trochisci Morphiæ et Ipecacuanhæ	

COMPOSITION.—Oil of wintergreen consists chiefly of salicylate of methyl, which forms about $\frac{9}{10}$ths of it, the remaining $\frac{1}{10}$th being a hydrocarbon called gaultherilene.

ACTION AND USE.—It is used on account of its agreeable smell and taste to **flavour** medicines. It is also given as an **antipyretic** to reduce the temperature in rheumatism, its antipyretic action being somewhat the same as that of salicylate of soda or salicine.

SAPOTACEÆ.

Gutta-percha, B. and U.S.P. GUTTA-PERCHA.—The concrete juice of *Isonandra gutta.*

CHARACTERS AND TESTS.—In tough, flexible pieces, of a light brown or chocolate colour. Soluble, or nearly soluble, in chloroform, yielding a more or less turbid solution.

PREPARATION.

B.P.	U.S.P.
Liquor Gutta-percha.	Liquor Gutta-perchæ.

USE.—Chiefly employed on account of its physical properties for making splints, &c.; also as a temporary stopping for decayed teeth. Gutta-percha tissue and similar articles are used to prevent the evaporation of lotions, and to cover poultices and fomentations.

STYRACACÆ.

Benzoinum, B. and U.S.P. BENZOIN.—A balsamic resin obtained from *Styrax Benzoin.* Siam and Sumatra.

CHARACTERS.—In lumps, consisting of agglutinated tears, or of a brownish mottled mass with or without white tears embedded in it; has little taste, but an agreeable odour; gives off, when heated, fumes of benzoic acid; is soluble in rectified spirit and in solution of potash.

COMPOSITION.—Contains about 14 per cent. of benzoic acid in combination with several amorphous resins.

DOSE.—10-30 gr.

PREPARATIONS.

B.P.	DOSE.
Acidum Benzoicum	10-15 gr.
Adeps Benzoatus	
Tinctura Benzoini Composita	½-1 fl.drm.

U.S.P.	DOSE.
Adeps Benzoinatus	
Tinctura Benzoini	½-1 fl. drm.
Tinctura Benzoini Composita	½-1 fl. drm.

Tinctura Benzoini Composita. COMPOUND TINCTURE OF BENZOIN (FRIARS BALSAM).—Benzoin, 2 oz.; prepared storax, 1½ oz.; balsam of tolu, ½ oz.; socotrine aloes, 160 gr.; rectified spirit, 1 pint, B.P.

Benzoin, 12; purified aloes, 2; storax, 8; balsam of tolu, 4; alcohol up to 100, U.S.P.

Acidum Benzoicum, B. and U.S.P. BENZOIC ACID. $HC_7H_5O_2$.

PREPARATION.—By heating benzoin, when benzoic acid sublimes.

PROPERTIES.—In light, feathery, crystalline plates and needles, which are flexible, nearly colourless, and have an agreeable aromatic odour, resembling that of benzoin. It is sparingly soluble in water, but is readily dissolved by rectified spirit; soluble also in solutions of the caustic alkalies and of lime.

REACTIONS.—When dissolved in solutions of caustic alkalies or of lime it is precipitated from them on the addition of hydrochloric acid unless the solution be very dilute. When heated to 462° F. it passes off in vapour, leaving only a slight residue.

PREPARATIONS.

B.P.	DOSE.
Ammoniæ Benzoas	10-20 gr.
Tinctura Camphoræ Composita	15 min. to 1 fl. drm.
Tinctura Opii Ammoniata	½-1 fl. drm.

U.S.P.

Ammonii Benzoas.

Tinctura Opii Camphorata.

Ammoniæ Benzoas, B.P.; Ammonii Benzoas, U.S.P. BENZOATE OF AMMONIA. $NH_4C_7H_5O_2$; 139 (cf. p. 674).

PREPARATION.—By dissolving benzoic acid in a slight excess of ammonia, evaporating and crystallising.

$$HC_7H_5O_2 + NH_4HO = NH_4C_7H_5O_2 + H_2O.$$

PROPERTIES.—In colourless, laminar crystals; soluble in water and in alcohol.

REACTIONS.—It gives a bulky yellowish precipitate with persalts of iron (benzoate). Its aqueous solution when heated with caustic potash evolves ammonia, and, if it be not too dilute, when acidulated with hydrochloric acid it gives a deposit of benzoic acid.

IMPURITIES.—Fixed salts.

TESTS.—When heated it sublimes without any residue.

PHYSIOLOGICAL ACTION.—Benzoic acid is a **stimulant** and irritant to raw surfaces. It has an **antiseptic** action, destroying low organisms, and is used in the form of the tincture for ulcers, wounds, blisters, and chapped hands. It was owing to its antiseptic action that Friars' Balsam was successfully used for the treatment of wounds in the Middle Ages, although at that time its mode of action was unknown (p. 84).

It acts as a stimulating **expectorant,** diminishing the secretion of the mucous membrane.

Benzoic acid when absorbed into the blood is excreted by the kidneys, and acts as a **diuretic.** It does not diminish the uric acid. In the kidneys it unites with glycocoll, and is excreted as hippuric acid, rendering the urine acid and somewhat irritating. This is proved by the following experiments:—

(1) If you give benzoic acid it is found in the urine as hippuric acid, but in the blood still remains as benzoic acid.

(2) If you give to a rabbit hippuric acid, it is excreted as such, but is found in the blood as benzoic acid.

(3) If you tie the renal arteries and give benzoic acid no conversion into hippuric acid takes place, but if you ligature the ureters the change takes place, and hippuric acid is found in the blood. This localises the seat of the change to the kidneys.

THERAPEUTICS.—It is used in chronic bronchitis and phthisis, both internally and as an inhalation, and extraordinary results have been ascribed to its uses; many, however, deny its beneficial effect. It is used in catarrh of the bladder to acidify the urine, and the

compound tincture has been used in urticaria. Ammonium benzoate has a similar action to benzoic acid.

VERBENACEÆ.

Lippia Mexicana. Not officinal.—An evergreen creeping shrub growing in Mexico. The parts used are the leaves and flowers.

COMPOSITION.—It contains a volatile oil—lippiol—a camphor-like body, and a substance allied to quercitin.

ACTION.—Lippiol in doses of 3 gr. (0·2 Gm.) caused in a cat within half an hour slight dilatation of the pupil and nictitation (probably due to gastro-enteric irritation, p. 186). A repetition of the dose caused vomiting, restlessness, and sleep lasting for two hours. In doses of 4½ gr. (0·3 Gm.) it causes warmth, flushing, diaphoresis, and drowsiness (Podwissotzki).

USES.—As a **respiratory sedative** in cough. Given as tincture in doses of ½-1 fl. drm.

OLEACEÆ.

Oleum Olivæ, B. and U.S.P. OLIVE OIL.—The oil expressed in the South of Europe from the ripe fruit of *Olea europæa*, B.P. A fixed oil expressed from the ripe fruit of *Olea europæa*, U.S.P.

CHARACTERS.—Pale-yellow, with scarcely any odour, and a bland, oleaginous taste; congeals partially at about 36°. Specific gravity about 0·916 at 63°.

COMPOSITION.—Olein, the liquid principle of the oil, and the quantity of which determines its excellence. It also contains palmitin and other fatty compounds.

ADULTERATION.—Other, and usually heavier, oils fraudulently added.

TESTS.—Specific gravity. Olive oil when treated with sulphuric acid evolves a small amount of heat compared with other similar oils.

PREPARATIONS.

B.P.

Charta Epispastica.
Cataplasmi Lini.
Emplastrum Ammoniaci cum Hydrargyro.
,, Cerati Saponis.
,, Hydrargyri.
,, Picis.
,, Plumbi.
Enema Magnesiæ Sulphatis.
Linimentum Ammoniæ.
,, Calcis.
,, Camphoræ.
Unguentum Cantharidis.
,, Hydrargyri Compositum.
,, Hydrargyri Nitratis.
,, Veratriæ.

U.S.P.

Emplastrum Plumbi.
,, Resinæ.
,, Ammoniaci cum Hydrargyro.
,, Arnicæ.
,, Assafœtidæ.
,, Belladonnæ.
,, Capsici.
Emplastrum Ferri.
,, Galbani.
,, Hydrargyri.
,, Opii.
,, Saponis.
Unguentum Diachylon.

DOSE.—Of olive oil, 1 fl. dr. to 1 fl. oz. or more, as a demulcent or laxative; of hard soap or soft soap, as an antacid, &c., 5-20 gr.; of glycerine $\frac{1}{2}$-2 fl. dr.

USES.—Lead plaster is the basis of many of the plasters; it is a good **protective** to prevent abrasions. Diachylon ointment is very useful in the treatment of eczema and other skin diseases.

Sapo Durus, B.P. HARD SOAP. **Sapo, U.S.P.** SOAP.—Soap made with olive oil and soda.

CHARACTERS.—Greyish-white, dry, inodorous; horny and pulverisable when kept in dry, warm air; easily moulded when heated; soluble in rectified spirit; not imparting an oily stain to paper. Incinerated it yields an ash which does not deliquesce.

PREPARATIONS.

B.P.

Emplastrum Resinæ.
,, **Saponis.**
Extractum Colocynthidis Compositum.
Linimentum Potassii Iodidi cum Sapone.
,, **Saponis.**
Pilula Aloës Barbadensis.
Pilula Aloës et Assafœtidæ.
,, ,, Socotrinæ.
,, Cambogiæ Composita.
,, Rhei Composita.
,, **Saponis Composita** (p. 761).
,, Scillæ Composita.

U.S.P.

Emplastrum Saponis.
Linimentum ,,
,, Chloroformi.
Pilulæ Aloës.
Pilulæ Aloës et Assafœtidæ.
,, Assafœtidæ.
,, Opii.
,, Rhei.

Sapo Mollis, B.P. SOFT SOAP. **Sapo Viridis, U.S.P.** GREEN SOAP.—Soap made with olive oil and potash, B.P. Soap prepared from potassa and fixed oils, U.S.P.

CHARACTERS.—Yellowish-green, inodorous, of a gelatinous consistence. Soluble in rectified spirit; not imparting an oily stain to paper. Incinerated it yields an ash which is very deliquescent.

PREPARATIONS.

B.P.

Linimentum Terebinthinæ.

U.S.P.

Tinctura Saponis Viridis (green soap, 65, oil of lavender, 2, alcohol up to 100).

USES.—Soft soap is more alkaline than the hard; if too long applied it may be a decided irritant to the skin. Tincture of soft soap is an elegant form of alkaline preparation for certain cutaneous diseases.

Glycerinum, B. and U.S.P. GLYCERINE, B.P. GLYCERIN, U.S.P.—A sweet principle, $C_3H_5(HO)_3$; 92. Obtained from fats and fixed oils, and containing a small percentage of water (not less than 95 per cent. of absolute glycerin, U.S.P.).

CHARACTERS.—A clear, colourless fluid, oily to the touch, without odour, of a sweet taste; freely soluble in water and in alcohol. When decomposed by heat it evolves intensely irritating vapours. Specific gravity 1·25.

PREPARATIONS (*vide* p. 452).

B.P.

Glycerinum Acidi Carbolici.
,, ,, Gallici.
,, ,, Tannici.
Glycerinum Amyli.
,, Boracis.
Linimentum Potassii Iodidi cum Sapone.

U.S.P.

Glyceritum Amyli. Glyceritum Vitelli.
Mucilago Tragacanthæ.

DOSE.—½-2 fl. dr.

ACTION AND USES.—**Olive oil** is used externally in the form of liniments as a **lubricating** substance; internally as a demulcent in cases of irritant poisoning, except by phosphorus. In large doses it is slightly **laxative**, as in oily salads.

Soap is used chiefly as a **detergent,** and for its mechanical effect, in pills and as an adjunct in suppositories. A small piece of soap cut into a conical form and used as a suppository is very useful in constipation occurring in infants. Soap and water forms a useful enema for constipation in adults.

Glycerin acts as a laxative, and when used along with castor oil increases its power. It is largely destroyed in the system, has an influence on nutrition, and has been proposed as a substitute for cod liver oil, but without much benefit. Very large doses cause a red coloration in the urine, due to the colouring matter of the blood, without any free corpuscles.

It is used as a **laxative** in hæmorrhoids; as a **solvent** of other drugs, as borax, tannic acid; as an **emollient** to soften the hands and applied to sore nipples, fissure of the tongue, in advanced phthisis, croup, laryngitis, etc. It has been painted on in eczema, psoriasis, pruritus; also as a preventive of bed sores. It must be diluted with water or it will irritate the part. It has been proposed as a substitute for sugar in diabetes.

Manna, B. and U.S.P. MANNA.—A concrete saccharine exudation from the stem of *Fraxinus ornus* and *F. rotundifolia.* Obtained by making incisions in the stems of the trees, which are cultivated for the purpose, chiefly in Calabria and Sicily, B.P. The concrete saccharine exudation of *F. ornus*, U.S.P.

CHARACTERS.—In stalactiform pieces from one to six inches in length, and one or two inches in width, uneven, porous, and friable, curved on one side, of a yellowish-white colour.

DOSE.—60 grains to 1 ounce.

PREPARATION.

U.S.P.	DOSE.	B.P.
Infusum Sennæ Compositum.....	2½ fl. oz.	None.

COMPOSITION.—It consists principally of mannite, $C_6H_7O_6$ or $C_3H_7O_3$, together with common sugar and extractive matter. The mannite, which forms from 60 to 80 per cent. of the manna, may be extracted by means of boiling rectified spirit, from which it will afterwards separate on cooling in colourless, shining crystals. It

requires five parts of cold water for its solution, and this does not undergo vinous fermentation in contact with yeast, thus distinguished from grape sugar.

USE.—Manna is used as a simple **laxative.**

LOGANIACEÆ.

Nux Vomica. NUX VOMICA.—The seeds of *Strychnos Nux Vomica,* imported from the East Indies.

CHARACTERS.—Nearly circular and flat, about an inch in diameter, umbilicated and slightly convex on one side, externally of an ash-grey colour, thickly covered with short satiny hairs, internally translucent, tough, and horny; taste intensely bitter, inodorous. The seeds to be pulverised must be heated by steam and dried.

COMPOSITION.—Two alkaloids, strychnine and brucine. The former is much less soluble in boiling water than the latter, and differs, further, in not being coloured by nitric acid, with which brucine gives a brilliant red. Both alkaloids are found combined with strychnic or igasuric acid—similar to malic acid.

PREPARATIONS.

B.P.	DOSE.
Extractum Nucis Vomicæ	$\frac{1}{4}$-2 gr.
Strychnia	$\frac{1}{30}$-$\frac{1}{12}$ gr.
Tinctura Nucis Vomicæ	10-20 min.
	(of the powdered seed) 2-5 gr.

U.S.P.	DOSE.
Abstractum Nucis Vomicæ	$\frac{1}{2}$ gr.
Extractum Nucis Vomicæ	$\frac{1}{3}$-1 gr.
Extractum Nucis Vomicæ Fluidum	1-5 min.
Strychnina	$\frac{1}{30}$-$\frac{1}{12}$ gr.
Tinctura Nucis Vomicæ	10-20 min.

U.S.P. Ignatia. IGNATIA. BEAN OF ST. IGNATIUS.—The seed of *Strychnos Ignatii.*

CHARACTERS.—About an inch and a fifth (3 centimetres) long, oblong or ovate, irregularly angular, dull brownish or blackish, very hard, horny; fracture, granular, irregular; the albumen somewhat translucent, inclosing an irregular cavity with an oblong embryo; inodorous; very bitter.

OFFICINAL PREPARATIONS.

	DOSE.
Abstractum Ignatiæ	1 gr.
Tinctura Ignatiæ	15 min.-1 fl. drm.

COMPOSITION.—Its activity depends on its contained brucine and strychnine.

Strychnia. STRYCHNIA, **B.P.** **Strychnina.** STRYCHNINE, **U.S.P.**—$C_{21}H_{22}N_2O_2$; 334.—An alkaloid prepared from Nux Vomica, B.P. An alkaloid prepared from Nux Vomica or Ignatia, and also occurring in other plants of the Nat. Ord. Loganiaceæ, U.S.P.

U.S.P. Strychninæ Sulphas.—SULPHATE OF STRYCHNINE.

PREPARATION.—Softening the tough seeds by steam, chopping drying, and grinding them. Exhausting powdered seeds with rectified spirit which is recovered by distillation. Precipitating colouring matter and acids by acetate of lead. Precipitating strychnine and brucine from concentrated solution by ammonia. Dissolving precipitate in rectified spirit and crystallising out strychnine from concentrated solution. The brucine being more soluble remains in the mother liquor. The strychnine is purified by washing and boiling with rectified spirit.

IMPURITY.—Brucine from imperfect preparation, and mineral matter.

CHARACTERS.—In right square octahedrons or prisms, colourless and inodorous: sparingly soluble in water, but communicating to it its intensely bitter taste; soluble in boiling rectified spirit and in chloroform, but not in absolute alcohol or in ether. Pure sulphuric acid forms with it a colourless solution, which on the addition of bichromate of potash acquires an intensely violet hue, speedily passing through red to yellow. A very active poison.

TESTS.—Not coloured by nitric acid (no brucine), leaves no ash when burned with free access of air (no mineral matter).

PREPARATIONS.

B.P.	DOSE.
Liquor Strychniæ (4 gr. in 1 fl. oz., with 6 min. dilute hydrochloric acid, and 2 fl. drm. of spirit to keep it in solution)	5-10 min.

U.S.P.	DOSE.
Ferri et Strychninæ Citras	1-3 gr.
Syrupus Ferri, Quininæ et Strychninæ Phosphatum (p. 677)	1-2 fl. drm.

PHYSIOLOGICAL ACTION.—Strychnine added to water containing low **organisms** in small doses increases their activity; in large doses it lessens it. The drug lessens **oxidation** of protoplasm and oxidation taking place in the blood; it also lessens **fermentation** but its action on it is not nearly so great as might be expected from its powerful action on higher organisms (pp. 47, 51, 55, 58, 71).

GENERAL ACTION.—The most marked feature in the general action of strychnine is the great increase which it produces in the **reflex excitability** of the spinal cord and other reflex nerve centres, such as vaso-motor and respiratory centres. When the dose is large this increase is so great as to cause **convulsions** and **death.**

Taken in small doses strychnine gives rise to a bitter taste and increases the appetite; sometimes also it increases the peristaltic movements of the **intestines,** and lessens constipation. When taken in small doses for a long time the drug produces increased sensibility of the **sensory nerves,** so that impressions are felt more acutely and are of longer duration, and the sense of touch is rendered more acute; the field of vision is increased and distant

objects are rendered more distinct; the sense of hearing is also sharpened (pp. 193 and 194). Taken in larger doses the drug produces increased sensibility more markedly, and excites sexual desire. If pushed still further the drug causes malaise, anxiety, restlessness, twitchings of the muscles, stiffness of the neck and convulsions.

After a dose of half a grain of strychnine symptoms of **poisoning** appear in a period varying from five minutes to five hours, coming on without vomiting or any other warning, the first symptom being general convulsions; the teeth are clenched, the pupils dilated, and the body forced into the opisthotonic position, resting on the head and feet, with the hands clenched and the arms drawn tightly towards the body; the spasms last from half to one minute, followed by a period of relaxation, during which sensibility to reflex stimuli is enormously increased, the slightest stimulus, such as a draught of cold air, bringing on a fresh attack of spasms. Death results either from asphyxia occurring during a spasm, or from paralysis and collapse coming on during a period of relaxation. The **diagnosis** between convulsions occasioned by strychnine and ordinary tetanus depends (1) on the history of the case, and (2) on the fact that the spasms of tetanus are tonic whilst those of strychnine poisoning are clonic. In tetanus too the muscles of the jaw are first affected, hence the term "lock-jaw"; whilst in strychnine convulsions these muscles are not affected before others.

The **treatment** of strychnine poisoning consists in evacuating the stomach, if possible before the convulsions begin; but, if this cannot be done, chloroform must be given and the stomach washed out whilst the patient is under the influence of the anæsthetic, and, lastly, chloral should be given by subcutaneous injection.

SPECIAL ACTION.—**On the Alimentary Canal.**—Strychnine produces, by its bitter taste, an increased flow of saliva; it also increases the peristaltic action of the bowels.

On the Blood.—When mixed with the blood it lessens oxidation to a slight extent, but probably it has little action on oxidation in the living body, from the small doses which can alone be used.

On the Circulation.—It increases the **blood-pressure.** This is due to several causes: (1) It stimulates the **vaso-motor centre** directly, or else greatly increases its excitability to the ordinary stimuli it receives even when the dose is too small to produce convulsions. When these occur, other factors help to increase the pressure. (2) The vaso-motor centre during the convulsions is stimulated indirectly by the action of the carbon dioxide of the venous blood, which accumulates during the asphyxia caused by the convulsions. (3) The violent muscular contractions during the convulsions increase the resistance to the flow of blood through the arteries and capillaries.

After section of the cord in a normal animal, stimulation of a sensory nerve no longer produces vaso-motor spasm; but in an

animal poisoned with strychnine it does. The explanation of this is that strychnine increases the excitability of the vaso-motor centre to such an extent that that portion of it which is in the cord becomes able to take on to a great extent the normal functions of the whole centre (pp. 245 and 246).

The medicinal use of strychnine is said to cause in some cases fits resembling those of tertian ague.[1] It is not improbable that these are true ague fits, due to malaria, the action of which has been aided by that of strychnine on the vaso-motor centre (cf. p. 246, and action of opium, p. 778).

The **heart** is stimulated, but during the convulsions it is slowed in the frog. In mammals it is quickened during the spasms, but if curare be previously given it is slowed.

Strychnine stimulates the motor ganglia of the heart, for Dr. Cash and I found that when a frog is under the action of strychnine a ligature placed between the sinus venosus and auricle did not stop the auricle and ventricle as in Stannius' experiment (p. 277), and if this experiment has already been performed, strychnine injected into the interior of the ventricle causes the auricle and ventricle to recommence beating (*St. Bartholomew's Hospital Reports*, vol. xvi.). The action of strychnine on the motor centre in the heart is probably similar to its action on the vaso-motor and respiratory centres.

Respiration is quickened and rendered more deep, owing to stimulation of the respiratory centre, just as in the case of the vaso-motor centre the spinal part of the respiratory centre is rendered so active; if strychnine be given to an animal and the cord be divided below the medulla, respiration is not entirely arrested as it usually is; and if strychnine be given to an animal after division of the cord, respiration will recommence (p. 201).

On the Muscles.—These are but little affected directly, but indirectly they become greatly exhausted by the wear and tear due to the convulsions. After death they quickly enter into *rigor mortis*.

Nervous System.—The **sensory** nerves are so stimulated that the slightest impression is most distinctly felt; the action of the drug has not been shown to be on the nerves themselves, but probably is due to stimulation of the nerve centres (pp. 192, 194, and 195). Small doses do not affect the **motor nerves,** large doses paralyse them. This paralysis is partly due to exhaustion from the convulsions, but not entirely, since if one sciatic nerve of a frog be divided before poisoning, so as to prevent any convulsions in the corresponding limb, it still loses its irritability, though not so soon as the undivided nerve.

On the Brain.—Small doses increase the **mental powers** and sharpen the **senses.** Large doses cause anxiety and malaise, but the functions of the cerebrum continue until death, the mind remaining clear to the last. The convulsions are not cerebral (p. 149).

[1] Lewin, *Nebenwirkungen der Arzneimittel*, p. 50.

On the Spinal Cord.—The spinal cord is greatly stimulated, so that a slight stimulus through a sensory nerve produces not merely increased reflex action but, by increasing the diffusion or "radiation" of impulses, causes general convulsions. This action of strychnia has been supposed to be due to increased excitability of the nerve cells in the spinal cord, but is more probably caused by an alteration in the comparative rate of transmission of stimuli from one cell to another (pp. 132 and 143). The convulsant action of strychnine was first localised to the spinal cord by the experiments of Magendie, as already described (p. 149).

Strychnine acts more powerfully when injected into the rectum than when swallowed, contrary to the general rule.

Brucine, thebaine, and some other **opium alkaloids** act in the same way as strychnine.

The effect of brucine in producing convulsions has been said to depend on admixture with strychnine. Mr. Shenstone prepared some pure brucine, and in experiments with this I have found it cause convulsions and death in rabbits when injected subcutaneously. It appears to be both less powerful than strychnine, and to be eliminated more rapidly, for when given to rats as a paste with butter it caused no symptoms whatever.

Methyl-strychnine, methyl-brucine, and methyl-thebaine do not affect the cord, but paralyse the ends of the motor nerves like curare.

THERAPEUTICS.—Strychnine is one of the best gastric tonics in dyspepsia when there is a tendency to catarrh and congestion. It probably acts by perfecting co-ordination between the various functions of the parts concerned in the processes of digestion and assimilation. It probably also increases the movements of the stomach and gives tone to the gastric vessels, and thus relieves congestion of the stomach due to bronchitis, cirrhosis, and cardiac disease (p. 320). As a **tonic** it is very useful during convalescence from acute diseases, in anæmia, in dyspepsia due to indigestible articles of diet or excess of alcoholic stimulants; also in "sick headache" in doses of 1 ♏ of tinct. nux vom. in a teaspoonful of water every ten minutes (Ringer).

In doses of 10 min. before meals I have found it prevent frontal headache in persons liable to it.

It also gives contractile power to the intestines and is used as an adjunct to purgative pills. A very good dinner pill is Pil. Rhei Co. gr. iv. Pulv. Ipec. ½ gr. Ext. Nux Vom. ½ gr.; given before dinner. A few drops of tincture of nux vomica just before dinner both increase the appetite and tend to lessen habitual constipation. In dilated heart it is useful as a cardiac tonic. It is useful as a respiratory stimulant in bronchitis, especially when there is a tendency to failure of respiration.

The night sweats of phthisis are usually checked by taking 10 m. of tinct. nux vom. at bed-time. The probable mode of action

has already been discussed (p. 389). It may also increase the cough during the day.

In depression due to mental overwork it is very valuable, as it increases the mental powers, but we must be cautious not to give it for too long a time. One of the chief dangers of giving it to overworked men is that it increases their powers temporarily and they are tempted to overwork themselves still more.

In some forms of paralysis (hemiplegia, paraplegia, wrist-drop), except where there still exist symptoms of irritation, it is serviceable; it is also useful in some forms of local paralysis, as atony of the bladder.

In sexual debility it is often serviceable. Its marked aphrodisiac action is sometimes inconvenient and interferes with its use as a tonic (p. 395). In some cases where debility is associated with sexual excess, strychnine increases instead of diminishing the weakness, and in such cases bromide of potassium should be employed. It has been used in hysteria and chorea with low spirits. It is a cumulative poison, as it contracts the renal arteries and thus prevents its own excretion (p. 30).

Curare. Not officinal. Synonyms, CURARA, WOORARI, WOURALI, URARI, TIÇUNAS.

This substance appears to be an extract from a species of strychnos mixed with some mucilaginous juice.

CHARACTERS.—A black extractiform body readily soluble in water.

COMPOSITION.—It contains an alkaloid curarine.

ACTION.—It paralyses the peripheral ends of **motor nerves** even when given in very minute doses (p. 121). Larger doses paralyse the **vagus** and the ends of **sensory nerves.** As poisoning progresses the **spinal cord** is paralysed, and finally the heart. Voluntary **muscles** appear to be little affected, yet their contractility is somewhat diminished, and this diminution begins even before the motor nerves themselves are paralysed. The **vessels** of the surface become dilated, and sometimes a peculiar erythematous rash appears on the skin in dogs. The **blood-pressure** is little affected by small doses, but is much lowered by large ones. When injected into the salivary gland it causes intense **salivation** which appears to be paralytic (p. 311). In **men** who have been slightly poisoned by it, it has produced increased secretion of the sweat, tears, nasal mucus, saliva, and urine, with a feeling of weariness and disinclination to move. Large doses produce **death** by paralysis of the muscles of respiration, but, the motor nerves of the extremities being paralysed, no convulsions occur. Although the motor nerves are paralysed to such an extent that they will not excite muscular contractions, even when the nerve centres are powerfully stimulated by asphyxial blood, they still cause muscular contractions when irritated by an interrupted current in a warm-

blooded animal poisoned by curare. In frogs the poisoning may be so complete that no irritation of the trunk of a nerve will excite contraction in the muscles supplied by it. Curare is rapidly **eliminated** by the kidneys, and if artificial respiration be kept up complete recovery occurs. I have succeeded in restoring an animal completely by this means, after it had been apparently dead for four hours. When given internally, curare is so rapidly eliminated that it usually produces no symptoms. When given in a very large dose on an empty stomach, symptoms of poisoning may occur. If elimination be prevented, by excision of the kidneys or ligature of the renal vessels, poisoning occurs, and in this case death is usually preceded by convulsions. So rapidly does elimination occur, that the urine of a frog poisoned by curare will paralyse a second frog injected subcutaneously, and the urine of the second will even paralyse a third.

USES.—It has been employed, but without much benefit, in epilepsy and chorea, and has been used with success in traumatic tetanus. In poisoning by strychnine it is not so useful as chloral. A case of hydrophobia has been described by Offenburg in which the subcutaneous injection of curare, to such an extent as to keep the patient almost, though not quite, paralysed for some time, effected a cure. If this were really so it would be most important, but from a comparison of the symptoms described by Offenburg with those of three fatal cases I have myself seen, I am inclined to think that his case was one of hysteria mimicking hydrophobia.

U.S.P. Gelsemium. GELSEMIUM. YELLOW JASMINE.

The rhizome and rootlets of *Gelsemium sempervirens.*

CHARACTERS.—Cylindrical, long, or cut in sections, occasionally an inch and a quarter (3 centimetres) thick, the roots much thinner; externally light brown yellow, with purplish-brown longitudinal lines; tough; fracture splintery; bark thin, with silky bast fibres, closely adhering to the pale yellowish porous wood, having fine medullary rays, and in the rhizome a thin pith; odour, aromatic, heavy; taste, bitter.

COMPOSITION.—It contains an alkaloid gelsemine.

PREPARATIONS.

U.S.P.	DOSE.
Extractum Gelsemii Fluidum	5-20 min. (·30-1·20 c.c.)
Tinctura Gelsemii	½-2½ fl. dr. (2-18 c.c.)

ACTION.—When applied to the **eye** it produces dilatation of the pupil and paralysis of accommodation It appears to paralyse the sensory columns of the **spinal cord,** while it excites the **motor centres** both in the brain and cord. The motor centres themselves become paralysed subsequently. This action causes in frogs paralysis, which is at first accompanied by increased reflex excitability so that irritation gives rise to tremor or tetanus. Afterwards the reflex excitability completely disappears. In

mammals a peculiar affection of the **head** is noticed, consisting in spasmodic attacks of tremor. The tremor affects the fore feet also and sometimes the hind legs. A kind of ataxia is also observed in the fore legs, which sometimes slip about and sometimes make abnormal running movements. This is succeeded by paralysis of the voluntary muscles and of respiration. The **vagus** is paralysed, the **blood-pressure** is diminished, the **pulse** rapid, and the **heart** weak. **Death** occurs from paralysis of the respiration. In **man** large doses have caused giddiness, double vision, numbness of the fingers, tremor of the head, difficult respiration, nausea, vomiting, and partial paralysis of the tongue and eyes, so that ptosis occurs, and difficulty is felt in moving the eyes or tongue.

USE.—It is chiefly used in cases of **neuralgia** of the fifth nerve, in toothache, sick headache, and in rheumatism.

U.S.P. Spigelia. SPIGELIA. PINKROOT. MARYLAND PINK. CAROLINA PINK.—The rhizome and rootlets of *Spigelia Marylandica.*

CHARACTERS.—Rhizome two inches (5 centimetres) or more long, about one-eighth of an inch (3 millimetres) thick, horizontal, bent, somewhat branched, on the upper side with cup-shaped scars; on the lower side with numerous, thin, brittle rootlets about four inches (10 centimetres) long; dark purplish brown; somewhat aromatic, sweetish, and bitter.

It should not be confounded with the underground portion of *Phlox Carolina,* the rootlets of which are brownish-yellow, rather coarse, straight, and contain a straw-coloured wood underneath a readily removable bark.

PREPARATION.

	DOSE.
Extractum Spigeliæ Fluidum	10-20 min.

USE.—It is very generally used as an **anthelmintic,** and is best given with a cathartic, as senna.

APOCYNACEÆ.

U.S.P. Apocynum. APOCYNUM. CANADIAN HEMP.—The root of *Apocynum cannabinum.*

CHARACTERS.—Long, cylindrical, somewhat branched, one-fourth to one-third of an inch (6 to 8 millimetres) thick, pale brown, longitudinally wrinkled and transversely fissured; brittle; fracture short, white; the bark rather thick; the wood porous, spongy, with delicate, medullary rays and a thin pith; inodorous; taste bitter, disagreeable.

DOSE.—15-30 gr. (1-1·95 Gm.) of powdered root. A decoction is more convenient. It is made by boiling ½ oz. in 1½ pint of water to 1 pint. Of this 1-2 fl. oz. (30-60 c.c.) may be given twice or thrice a day.

COMPOSITION.—It contains an amorphous substance—apocynin—easily soluble in alcohol, but insoluble in water, and a glucoside—apocyneïn—easily soluble in water.

ACTION.—In small doses it is **laxative,** in large doses emetic and cathartic. Apocynin and apocyneïn act on the heart as **cardiac tonics** like digitalis, and are also **diuretic.**

USE.—It is chiefly used in dropsy.

Quebracho Cortex. WHITE QUEBRACHO BARK. Not officinal. The bark of *Aspidospermo quebracho* imported from the Argentine Republic.

CHARACTERS.—In large pieces, about three quarters of an inch thick, greyish-brown outside, yellowish inside, intensely bitter. It contains several alkaloids, the most important being aspidospermine.

PREPARATION.

	DOSE.
Tinctura Quebracho (1 in 5 of proof spirit)	½-1 fl. drm.

ACTION.—In frogs all the alkaloids produce motor **paralysis,** weaken, and finally arrest the respiratory movements and heart. In warm-blooded animals aspidospermine paralyses voluntary movement, the respiration, and the heart. In small doses aspidospermine increases the fulness and frequency of the respiration.

USES.—It has been used to lessen dyspnœa in **asthma** and phthisis.

ASCLEPIADACEÆ.

U.S.P. Asclepias. ASCLEPIAS. PLEURISY ROOT.—The root of *Asclepias tuberosa.*

CHARACTERS.—Root large and fusiform, dried in longitudinal or transverse sections; from one to six inches (25 to 150 millimetres) long, and about three-quarters of an inch (two centimetres) or more in thickness; the head knotty, and slightly but distinctly annulate, the remainder longitudinally wrinkled; externally orange-brown, internally whitish; tough and having an uneven fracture; bark thin, and in two distinct layers, the inner one whitish; wood yellowish, with large, white medullary rays; it is inodorous, and has a bitterish, somewhat acrid taste; when long kept it acquires a grey colour.

COMPOSITION.—It contains resins and an odorous fatty matter.

DOSE.—20-60 gr.

USE.—It may be used as a **diaphoretic** or **expectorant.** In large doses it acts as an emetic and purgative.

Asclepias Incarnata. WHITE INDIAN HEMP. Not officinal.—America. The root appears to act **like digitalis,** strengthening the beats of the heart, and producing diuresis. A fluid extract has been used in doses of ½-1 fl. drm. every three hours.



FIG. 169.—Hemidesmus.

B.P. Hemidesmi Radix. HEMIDESMUS ROOT.—The dried root of *Hemidesmus indicus,* Indian sarsaparilla. India.

CHARACTERS.—Yellowish-brown, cylindrical, tortuous, furrowed and with annular cracks; having a fragrant odour and a very agreeable flavour.

COMPOSITION.—The chemical constituents of the root have not yet been fully investigated. A substance supposed to be a volatile acid has been separated by distillation with water.

PREPARATION.

B.P.	DOSE.
Syrupus Hemidesmi (1 to 10½ oz.)	1-2 fl. drm.

USE.—Hemidesmus is supposed to have the same action as **sarsaparilla** (*q.v.*) and is used in rheumatism and syphilis. The syrup is of little use except for flavouring.

Condurango. Not Officinal. The bark of *Gonolobus Condurango* from Ecuador. It is said, however, that there are several species of plants yielding a bark known by the name "Condurango."

CHARACTERS.—Condurango is a climbing plant; the bark is generally of a greyish colour outside with a few adherent lichens, and occurs in thin, curled pieces.

ACTION.—It does not seem to have any definite physiological action. It has been stated by Gianuzzi to produce tetanus like strychnine. I found that an infusion injected into the jugular vein caused convulsions and death, but this appeared to be really due to embolism of the pulmonary vessels by fine particles suspended in fluid, for when injected into the peritoneal cavity the solution has no action.

USES.—It has been recommended as a remedy in cancer, but is useless in this disease. It has been found beneficial, however, in cases of **dyspepsia,** and has been given also as an alterative in syphilis.

GENTIANACEÆ.

Gentianæ Radix, B.P.; Gentiana, U.S.P. GENTIAN ROOT, B.P.; GENTIAN, U.S.P.—The dried root of *Gentiana lutea.* Mountainous districts of Central and South Europe.



FIG. 170.—Gentian.

CHARACTERS.—From half an inch to one inch in thickness, several inches in length, often twisted, much wrinkled, or marked with close transverse rings; brown externally, yellow within; tough and spongy; taste at first sweetish, afterwards very bitter.

COMPOSITION.—Gentio-picrin, from which the root derives its

bitter taste; it is soluble in water. Also gentianin, which is tasteless and only slightly soluble in water.

PREPARATIONS.

B.P.	DOSE.
Extractum Gentianæ	2-10 gr.
Infusum Gentianæ Compositum	1-2 fl. oz.
Mistura Gentianæ	½-1 fl. oz.
Tinctura Gentianæ Composita	½-1 fl. drm.

U.S.P.	DOSE.
Extractum Gentianæ	2-10 gr.
Extractum Gentianæ Fluidum	8-30 min.
Tinctura Gentianæ Composita	1-4 fl. drm.

B.P. Infusum Gentianæ Compositum.—Root, 60 gr.; bitter orange peel, 60 gr.; fresh lemon peel, ¼ oz.; and boiling water, 10 fl. oz.

B.P. Mistura Gentianæ.—Root, ¼ oz.; bitter orange peel, 30 gr.; coriander, 30 gr.; proof spirit, 2 fl. oz.; and water, 8 fl. oz. By maceration first in spirit, and afterwards in spirit and water.

Tinctura Gentianæ Composita.—Root, 1½ oz.; bitter orange peel, ¾ oz.; cardamoms, ¼ oz.; proof spirit, 20 fl. oz., B.P. Gentian, 8; bitter orange peel, 4; cardamom, 2; diluted alcohol up to 100, U.S.P.

USE.—Gentian is a simple, bitter stomachic tonic. It is used in atonic dyspepsia to give tone to the stomach and increase the appetite. Also used as a general tonic.



FIG. 171.—Chiretta.

Chirata, B. and U.S.P. CHIRETTA.—The entire plant, *Ophelia chirata*. Northern India.

CHARACTERS.—Stems about three feet long, of the thickness of a goose-quill, round, smooth, pale-brown, branched; branches opposite; flowers small, numerous, panicled; the whole plant intensely bitter.

COMPOSITION.—Ophelic acid, soluble in water and forming a soluble compound with tannic acid; and chiratin, soluble in warm water and forming an insoluble compound with tannic acid. Both substances are intensely bitter.

PREPARATIONS.

B.P.	DOSE.
Infusum Chiratæ (1 in 40 of water at 120° F.)	1-2 fl. oz.
Tinctura Chiratæ	½-2 fl. drm.

U.S.P.	DOSE.
Extractum Chiratæ Fluidum	15-30 min.
Tinctura Chiratæ	½-2 fl. drm.

USES.—As a **bitter tonic** like gentian. It has been supposed by some to be specially useful in disorders of the liver.

CONVOLVULACEÆ.

B.P. Scammoniæ Radix. SCAMMONY ROOT.—The dried root of *Convolvulus Scammonia*. Syria and Asia Minor.

CHARACTERS.—Tap-shaped roots, often twisted, sometimes three inches in diameter at the top, brown without, white within, slightly odorous but tasteless. Ether agitated with the powder and evaporated leaves a residue having the properties of scammony resin.

COMPOSITION.—Resina Scammoniæ (*q.v.*).

PREPARATIONS.

B.P.	DOSE.
Resina Scammoniæ	3-8 gr.

U.S.P.	DOSE.
Resina Scammonii	4-8 gr.

Scammonium, B. and U.S.P. SCAMMONY.—A gum-resin, obtained by incision from the living root of *Convolvulus Scammonia*. Chiefly in Asia Minor. B.P. A resinous exudation from the root of *Convolvulus Scammonia*, U.S.P.

CHARACTERS.—In irregular, angular pieces or circular cakes, ash-grey and rough externally; fresh fracture, resinous, splintery, shining, black when dry; odour and flavour cheesy; causes, when chewed, a slight prickly sensation in the back of the throat; easily triturated into a dirty-grey powder, and converted with water into a smooth emulsion.

COMPOSITION.—Gum and resin.

ADULTERATIONS.—Chalk, starch, wood-ashes, and gum.

TESTS.—It does not effervesce with hydrochloric acid (no chalk). Boiling water agitated with the powder, cooled and filtered,

does not strike a blue colour with tincture of iodine (no starch). Ether removes from 80 to 90 per cent. of resin ; and what remains is chiefly soluble gum, with a little moisture (no wood ashes).

PREPARATIONS.

B.P.	DOSE.
Confectio Scammonii	10-30 gr. or more.
Pilula Colocynthidis Composita	5-10 gr.
Pilula Colocynthidis et Hyoscyami	5-10 gr.
Pulvis Scammonii Compositus	10-20 gr.
Resina Scammoniæ	3-8 gr.

U.S.P.	DOSE.
Resina Scammonii	4-8 gr.

B.P. Confectio Scammonii. CONFECTION OF SCAMMONY.—Scammony, 3 oz. ; ginger, 1½ oz. ; oil of caraway, 1 fl. drm. ; oil of cloves, ½ fl. drm. ; syrup, 3 fl. oz. ; clarified honey, 1½ oz.

B.P. Pulvis Scammonii Compositus. COMPOUND POWDER OF SCAMMONY.—Scammony, 4 ; jalap, 3 ; ginger, 1.

Scammoniæ Resina, B.P. Resina Scammonii, U.S.P.

RESIN OF SCAMMONY.

CHARACTERS.—In brownish, translucent pieces ; brittle ; resinous in fracture ; of a sweet fragrant odour if prepared from the root. It cannot form singly an emulsion with water. Ether dissolves it entirely.

PREPARATION.—Extracted from the root by percolating with alcohol.

COMPOSITION.—Principally jalapin soluble in ether, in this respect differing from the convolvulin of jalap. The resin also contains other substances the properties of which are imperfectly known. Contains no gum.

IMPURITY.—Guaiacum fraudulently added.

TEST.—The tincture does not render the fresh cut surface of a potato blue.

PREPARATIONS.

B.P.	DOSE.
Extractum Colocynthidis Compositum	5-15 gr.
Mistura Scammonii	½-2 fl. oz.
Pilula Scammonii Composita	5 gr.

U.S.P.	DOSE.
Extractum Colocynthidis Compositum	5-20 gr.

B.P. Mistura Scammonii. SCAMMONY MIXTURE.—Resin of scammony (2 gr.) triturated with milk (1 fl. oz.).

B.P. Pilula Scammonii Composita. COMPOUND SCAMMONY PILL.—Resin of scammony, 1 ; resin of jalap, 1 ; curd soap, 1 ; strong tincture of ginger, 1 ; rectified spirit, 2.

ACTION and USE.—It increases the secretion of the intestines and acts as a **drastic purgative.** It is used as a derivative in dropsy and cerebral affections. It is also used, in combination with other drugs, as a **vermifuge** for tape worm in children. It combines with the soda in the bile and its solution in bile is necessary to its action (Buchheim).

Jalapa, B. and U.S.P. JALAP.—The dried tubercles of *Exogonium Purga* (*Ipomœa Purga*), B.P. The tuberous root of *Exogonium Purga*, U.S.P. Mexico.

FIG. 172.—Jalap.

CHARACTERS.—Varying from the size of a nut to that of an orange, ovoid, the larger tubercles frequently incised, covered with a thin, brown, wrinkled cuticle; presenting, when cut, a yellowish-grey colour, with dark brown concentric circles.

Jalapæ Resina, B. and U.S.P. RESIN OF JALAP.—Extracted from jalap by rectified spirit.

CHARACTERS and TESTS.—In dark-brown opaque fragments, translucent at the edges, brittle, breaking with a resinous fracture, readily reduced to a pale brown powder, sweetish in odour acrid in the throat, easily soluble in rectified spirit, but only partially so in ether, and insoluble in oil of turpentine.

PREPARATION.—Digesting and gently heating the jalap with rectified spirit, precipitating the resin with water, evaporating by a water bath, and drying.

COMPOSITION.—The resin consists of convolvulin in combination with another resinous substance (gammaresin) which is the part dissolved by ether. The convolvulin of jalap differs from the jalapin of scammony in being insoluble in ether.

PREPARATIONS.

B.P.	DOSE.
Extractum Jalapæ	5-15 gr.
Pulvis Jalapæ Compositus	20-60 gr.
Pulvis Scammonii Compositus	10-20 gr.
Resina Jalapæ	2-5 gr.
Tinctura Jalapæ	½-2 fl. drm.

Resin of Jalap is contained in Pilula Scammonii Composita.

U.S.P.	DOSE.
Abstractum Jalapæ	7-10 gr.
Pulvis Jalapæ Compositus	30-60 gr.
Resina Jalapæ	2-5 gr.
Pilulæ Catharticæ Compositæ	1-3 pills.

Pulvis Jalapæ Compositus. COMPOUND JALAP POWDER.—B.P. Jalap, 5; acid tartrate of potash, 9; ginger 1 part. U.S.P. Jalap, 35; acid tartrate of potash, 65.

ACTION and USES.—Jalap is a hydragogue purgative, used for constipation, dropsy due to renal disease, and cerebral affections. It is best given with acid tartrate of potash, as in Pulv. Jalapæ Co. Like scammony, it is dissolved by the bile, and appears to require it in order to act. It has no action when injected subcutaneously, nor when injected into the veins. It has no irritant action when

locally applied to the skin or mucous membranes of the eye or nose, nor has it any diuretic action, or any action on the nervous system.

SOLANACEÆ.

Dulcamara, B. and U.S.P. DULCAMARA. BITTERSWEET —The dried young branches of *Solanum Dulcamara*. From indigenous plants which have shed their leaves.



FIG. 173.—Dulcamara.

CHARACTERS.—Light, hollow, cylindrical, about the thickness of a goose-quill; bitter and subsequently sweetish to the taste.

COMPOSITION.—It contains solanine, and less dulcamarine, both alkaloids, amorphous, and of a bitter taste. It yields also sugar.

PREPARATIONS.

B.P.	DOSE.
Infusum Dulcamaræ (1 oz. in ½ pint)	1-2 fl. oz. or more.
U.S.P.	DOSE.
Extractum Dulcamaræ Fluidum	1 fl. drm.

ACTION.—The action of dulcamarine has not been investigated. **Solanine,** both in warm and cold-blooded animals, paralyses the central **nervous system** without affecting the peripheral nerves or voluntary muscles. It slows the **heart** and **respiration,** lessens sensibility, and causes death with convulsions. In warm-blooded animals there is constant fall of **temperature,** and there is entire absence of any action on the pupil. In man it produces weakness, laboured breathing, nausea, vomiting, and drowsiness, but no true sleep. The pupil is unaffected and there is no increased movement of the bowels, diuresis, or diaphoresis.

USES.—Dulcamara is chiefly used as an **alterative** in scaly skin diseases, in which it is often combined with antimony. It has been recommended by Husemann in chronic bronchial catarrh, asthma, and whooping cough.

Capsici Fructus, B.P.; Capsicum, U.S.P. CAPSICUM FRUIT, B.P.; CAPSICUM, U.S.P.—The dried ripe fruit of *Capsicum fastigiatum*, and of *C. annuum*. Zanzibar.

CHARACTERS.—Pod membranous, from five to eight lines long, two lines broad, straight, conical, pointed, smooth, shining, but somewhat corrugated, orange-red; intensely hot in taste.

COMPOSITION. — An exceedingly acrid, volatile substance, Capsaïcin, and an alkaloid resembling conine in odour.

ADULTERATION.—The powder is occasionally found adulterated with red lead.

TEST.—Digest in nitric acid and add sulphate of soda. There should be no precipitate of sulphate of lead. Should burn away without residue of lead.

PREPARATIONS.

B.P.	DOSE.
Tinctura Capsici	5-20 min. (as a gargle, ½-2 fl. drm. in 5 oz. of fluid.)

U.S.P.	DOSE.
Extractum Capsici Fluidum	2-10 min.
Oleoresina Capsici	⅛-1 min.
Tinctura Capsici	8 min. to 2 fl. dr.
Emplastrum Capsici	

ACTION AND USES.—Externally capsicum is an **irritant,** producing warmth, redness, and vesication. Internally it is an irritant, and in large doses will produce gastro-enteritis.

It has been used for unbroken chilblains, neuralgia, and rheumatic pains. Internally it may be used as a gargle for tonsillitis, pharyngitis, and relaxed sore throat. It is used as a condiment, and to relieve flatulence. It is also recommended to relieve the sinking in the epigastrium felt by dipsomaniacs. It promotes appetite and stimulates the stomach.

ATROPACEÆ.

Belladonnæ Folia, B. and U.S.P. BELLADONNA LEAVES —The leaves of *Atropa Belladonna*, U.S.P. The fresh leaves, with the branches to which they are attached, of deadly nightshade, *Atropa Belladonna;* also the leaves separated from the branches and carefully dried; gathered from wild or cultivated British plants when the fruit has begun to form, B.P.

CHARACTERS.—Leaves alternate, three to six inches long, ovate, acute, entire, smooth, the uppermost in pairs and unequal. The expressed juice, or an infusion, dropped into the eye, dilates the pupil.

COMPOSITION.—Less than one per cent. of atropine, and a small proportion of asparagine. More atropine is obtained from the leaves of mature plants than from those gathered before inflorescence.

PREPARATIONS.

B.P.	DOSE.
Extractum Belladonnæ (green)	¼-1 gr.
Tinctura Belladonnæ (from dried leaves)	5-30 min.
Succus Belladonnæ (from fresh leaves)	5-15 min.
Unguentum Belladonnæ, Emplastrum Belladonnæ } from extract	

U.S.P.	DOSE.
Extractum Belladonnæ Alcoholicum	¼ gr.
Tinctura Belladonnæ	8-30 min.
Unguentum Belladonnæ	

Belladonnæ Radix, B. and U.S.P. BELLADONNA ROOT.—The dried root of *Atropa Belladonna.*

CHARACTERS.—From one to two feet long, and from half an inch to two inches thick, branched and wrinkled, brownish white. An infusion dropped into the eye dilates the pupil. Roots which are tough and woody, breaking with a splintery fracture, should be rejected.

COMPOSITION.—Two alkaloids, atropine and belladonnine, the former under one per cent. Also a red colouring matter, atrosin.

PREPARATIONS.

B.P.	DOSE.
Atropia	$\frac{1}{200}$-$\frac{1}{20}$ gr.
Linimentum Belladonnæ (1 oz. to 1 fl. oz.)	

U.S.P.	DOSE.
Atropina	$\frac{1}{200}$-$\frac{1}{20}$ gr.
Abstractum Belladonnæ	$\frac{1}{2}$ gr.
Emplastrum Belladonnæ	
Extractum Belladonnæ	1-2 min.
Linimentum Belladonnæ Fluidum	

Atropia, B.P.; Atropina, U.S.P. ATROPIA, B.P.; ATROPINE, U.S.P. $C_{17}H_{23}NO_3$; 289.—An alkaloid obtained from belladonna.

PREPARATION.—It cannot be profitably prepared on a small scale. The chief parts of the process are the precipitation of acid colouring matters from a strong tincture by means of lime removal of the alcohol, addition of water and carbonate of potash, taking up the alkaloid from the alkaline solution by chloroform, and subsequent purification.

CHARACTERS AND TESTS.—In colourless, acicular crystals, sparingly soluble in water, more readily in alcohol and in ether. Its solution in water has an alkaline reaction, gives a citron-yellow precipitate with terchloride of gold, has a bitter taste, and powerfully dilates the pupil. It leaves no ash when burned with free access of air. It is an active poison.

The following test has been proposed for the members of the group of mydriatic alkaloids—atropine, hyoscyamine, daturine, duboisine, and homatropine. To a small portion of atropine in a test tube add about 2 ccm. of a 5 per cent. solution of mercuric chloride in 50 per cent. of alcohol, and warm gently. A precipitate will at once appear, and become brick-red in colour. This test does not answer in dilute solutions, neither does it turn out well if atropine be added to the mercury. Other alkaloids give for the most part a white precipitate (Gerrard).

PREPARATIONS.

B.P.	DOSE.
Atropiæ Liquor (4 gr.; spirit, 1 fl. dr.; water, 7 fl. dr.) 4 gr. in 1 fl. oz.	$\frac{1}{2}$-6 min.
,, Sulphas	$\frac{1}{20}$-$\frac{1}{200}$ gr.
,, Sulphatis, Liquor 4 gr. in 1 fl. oz.	$\frac{1}{2}$-6 min.
,, **Unguentum** (with rectified spirit $\frac{1}{2}$ fl. dr. and prepared lard 1 oz.) 8 gr. in 1 oz.	

Atropiæ Sulphas, B.P.; Atropinæ Sulphus, U.S.P. SULPHATE OF ATROPIA, B.P.; SULPHATE OF ATROPINE, U.S.P.

PREPARATION.—By dissolving atropia in dilute sulphuric acid and evaporating.

CHARACTERS AND TESTS.—A colourless powder, soluble in water, forming a solution which is neutral to test paper, and when applied to the eye dilates the pupil as the solution of atropia does. It leaves no ash when burned with free access of air.

Intended for external application. It is a powerful poison.

PREPARATION.

B.P.	U.S.P.
Liquor Atropiæ Sulphatis (4 gr. in 1 fl. oz. of water)	None.

GENERAL ACTION OF BELLADONNA OR ATROPINE.—The first symptoms to appear after a **small dose** are dryness of the mouth and headache. After **full doses** the pupils become dilated, a red rash appears on the skin like that of scarlatina, and a delirium of a peculiar and often of a pleasant character ensues, in which there is a great desire for movement and activity, with a feeling of great lassitude (p. 168). The pulse becomes rapid. This is generally followed by sleep.

With large doses, the mouth becomes so dry that swallowing is almost impossible, and the attempt to swallow may bring on general convulsions like hydrophobia; these convulsions are followed by paralysis, stupor, often alternating with delirium, coma, and death, preceded by marked failure of the heart's action and of respiration. Death is due to asphyxia.

SPECIAL ACTION.—**Locally applied** it diminishes the sensibility of the sensory nerves (whether applied as liniment or injected subcutaneously). It can be absorbed from the skin and produce its general symptoms.

It stimulates the centres in the **brain,** but tends to paralyse the ends of the motor nerves, hence causing that peculiar form of delirium in which a constant desire for action is associated with lassitude. The **spinal cord** is first stimulated, then paralysed.

In a frog the first stimulation quickly passes off, and there follows gradually increasing weakness both of respiratory and voluntary movements, until these become entirely abolished. If the frog be kept in this condition for four or five days, this state of absolute paralysis passes off and is succeeded by a condition of excitement with violent tetanic convulsions which may be brought on by the slightest afferent stimulus. Various explanations of this action have been given (vide p. 141).

The endings of **motor nerves** in voluntary muscles are paralysed by large doses but small doses will paralyse the efferent nerve endings which terminate in peripheral ganglia (*e.g.* vagus), and in involuntary muscle (p. 114). The converse is the case with curare.

Atropine has no action on voluntary **muscles**. Involuntary muscle is paralysed by large doses (p. 114).

On the Eye.—The pupils are dilated and the eye becomes bright, dry, and injected. The power of accommodation is paralysed, and by large doses intraocular tension is increased. For the mode of action *vide* pp. 187-191.

On the Circulation.—The action of atropine on the excised heart of the frog affords an illustration of the statement I have made (p. 33) that in all probability contradictory observations frequently depend on differences in the temperature at which the observations were made. Thus Bowditch and Luciani found the contractions, both of the frog's heart containing ganglia and of the apex (p. 266) alone, were rendered more powerful by atropine, while Gnauck, on the contrary, found that the contractions of the ventricle were diminished both by atropine and hyoscyamine. Kronecker and Schapiro have found that these contradictory observations are both correct, but at different temperatures. When the temperature is low (7° to 8° C.) the ventricular contractions are enlarged by atropine, but diminished by it when the temperature rises over 15° C. Large doses of atropine completely paralyse the intracardiac inhibitory apparatus, while at the same time they stimulate the vagus centres in the medulla.

Atropine is supposed to act upon inhibitory ganglia in the heart itself, not upon the vagus endings, in which respect it differs from nicotine (*vide* p. 272).

Sometimes there is a primary slowing of the pulse rate, followed by quickening; but it is uncertain whether this is due to stimulation of the vagus centre, or of the inhibitory apparatus in the heart.

Small doses raise the blood-pressure by stimulating the vaso-motor centre in the medulla, but large doses diminish it by paralysing the vaso-motor centre and partly by paralysing the peripheral vaso-motor ganglia or muscular fibres of the walls of the arteries themselves (p. 241). Atropine also diminishes the sensibility of the heart to changes of pressure within it (p. 257).

On Respiration.—Atropine first quickens, and then slows respiration. This is due to stimulation and subsequent paralysis of the respiratory centre in the medulla. When injected into the jugular vein it appears to paralyse the ends of the sensory fibres of the vagus in the lungs, and thus tends to slow respiration at first (p. 210). It arrests secretion from the bronchial mucous membrane (p. 214).

On Secretion.—Atropine paralyses the secreting fibres of the chorda tympani without affecting the vasodilator fibres, so that when the chorda tympani is stimulated, either directly or reflexly, the flow of blood to the gland is increased, but no fluid exudes from the duct (p. 316).

It probably has a similar action on many, if not all, glands,

including the sweat glands, milk glands, mucous glands, pancreas, and liver. When locally applied it stops the secretion of milk and sweat. In the case of the sweat it probably paralyses the efferent sweat-fibres which accompany the vaso-motor fibres and start from centres in the lumbar and lower dorsal parts of the cord (Luchsinger). It does not, however, prevent secretion in the intestine after division of the intestinal nerves (Brunton and Pye-Smith).

The secretion of **urine** is sometimes increased, but large doses may cause retention from paralysis of the bladder.

On the Intestines.—Small doses increase the movements of the intestines. This action is probably due to paralysis of the inhibitory fibres of the splanchnic, since stimulation of the peripheral end of the cut splanchnic will cause arrest of movement in the unpoisoned, but not in the poisoned, animal. Moderate doses completely arrest peristaltic movements, but the muscular fibres of the intestine retain their irritability. Local irritation causes a local contraction but no peristalsis. This is probably due to paralysis of the intestinal ganglia.

Large doses stop the movements and paralyse the involuntary muscular fibres of the intestine, so that they only contract feebly or not at all when directly irritated.

The Temperature is increased by small doses, lessened by large ones.

Certain animals, especially pigeons and rodents, such as rabbits, guinea-pigs, and rats, are peculiarly unsusceptible to the action of atropine. It is not improbable that the **unsusceptibility** of rodents to the action of atropine depends on the very slight tonic action which the vagus exerts on the heart in them in their normal condition. When it is paralysed there is little change in the circulation, while in dogs the case is very different (p. 246).

Methyl- and ethyl-atropine paralyse the ends of the motor nerves, but do not tetanise; they, however, retain the action of atropine on the eye, heart, &c.

THERAPEUTICS.—**Locally applied** belladonna lessens irritability and pain, and is hence used as a lotion in photophobia.

Solution of atropine is employed to dilate the pupil and paralyse accommodation in many conditions which have already been mentioned (p. 192). Migraine frequently depends upon astigmatism or other visual disturbances, and an attack may sometimes be cut short by the local application of atropine to the eye.

In the form of a plaster or liniment over the tender spots, it is useful in myalgia, neuralgia, especially supraorbital and intercostal neuralgia, pleurodynia, hypersensitiveness of skin, and irritability of the chest muscles seen in phthisical patients. The pain arising from old adhesions due to pleurisy is relieved by a belladonna plaster.

In the form of ointment it lessens pain and spasm in fissures of the anus.

It is used to check local sweating on the head, hands, or feet, in the form of the liniment two or three times a day.

Atropine is used internally to check the sweating of phthisis and other exhausting diseases, in doses of $\frac{1}{200}$ gr., gradually increased. It may be given in pill, or mixture, or hypodermically. The beneficial effect may here be due to paralysis of nerves of sweat glands, but is probably due also to the stimulating effect on the respiratory centre (p. 389).

Belladonna stops the secretion of milk, and is hence used when the mother from any cause is unable to suckle her child, and the breast becomes swollen and inflamed. For its uses in ophthalmic practice *vide* p. 191. Given internally atropine is useful in extreme salivation, as in mercurial ptyalism. In chronic constipation, relief is often afforded by small doses of $\frac{1}{4}$-gr. of the extract of belladonna. Its action here may be due to diversion of a stimulus from the inhibitory to the motor fibres of the splanchnic, or to paralysis of the inhibitory fibres of the splanchnics (p. 336). It lessens griping, hence it is a useful adjunct to purgatives. It is useful in cases of spasm of involuntary muscles, as in lead colic, simple colic, asthma, and in the spasm set up by renal and biliary calculi (*cf.* p. 141).

Internally it is useful in palpitation due to cardiac strain (p. 257), and sometimes gives relief in angina pectoris. One of the most useful applications in all cases of palpitation, whether accompanied by pain or not, is a belladonna plaster to the cardiac region. As atropine, while it appears to lessen the excitability of the ends of the vagus in the lung, excites the respiratory centre, its action in preventing cough is slight and uncertain. As it has the power of completely arresting secretion from the bronchial tubes it is useful in cases where there is excessive secretion, but where the bronchial mucous membrane is already too dry, it is injurious (p. 214). In incontinence of urine in children belladonna is a most useful remedy. It probably acts by lessening the irritability of the bladder. It is also very serviceable in irritability of the bladder with frequent micturition in adults (p. 391).

In epilepsy and chorea it is not of much use, but in frontal headaches it is useful in doses of 3 m. of tincture every three hours.

In leucorrhœa with ulceration of the os uteri, a pessary made up of 2 gr. of ext. belladonnæ, with 7 gr. of tannin, and cacao butter q.s., is very useful (Trousseau).

As an antidote to opium 4 min. of liquor atropiæ B.P. may be injected subcutaneously, and repeated every quarter of an hour until the pupil dilates.

It has also been used in poisoning by calabar-bean, and in chloroform poisoning, when death is impending from stoppage of the heart. Doses sufficiently large to paralyse the inhibitory apparatus must be used.

Hyoscyami Folia, B.P.; Hyoscyamus, U.S.P. HYOSCYAMUS LEAVES, B.P.; HYOSCYAMUS, U.S.P—The fresh leaves, with the branches to which they are attached, of *Hyoscyamus niger*, also the leaves separated from the branches and carefully dried, collected from plants of the second year's growth.

CHARACTERS.—Leaves sinuated, clammy, and hairy. The fresh herb has a strong, unpleasant odour, and a slightly acrid taste, which nearly disappear on drying. The fresh juice, dropped into the eye, dilates the pupil.

COMPOSITION.—A volatile alkaloid, hyoscyamine, soluble in water and spirit. It is decomposed, and its physiological action neutralised by caustic alkalies. It is isomeric with, but not identical with, atropine. Nitrate of potassium and other inorganic salts are present in the leaves.

PREPARATIONS.

B.P.	DOSE.
Extractum Hyoscyami	5-10 gr. or more.
Tinctura Hyoscyami	30 min. to 1 fl. drm. or more.
Succus Hyoscyami	30 min. to 1 fl. drm.

U.S.P.	DOSE.
Abstractum Hyoscyami	3-5 gr.
Extractum Hyoscyami Alcoholicum	2 gr.
Extractum Hyoscyami Fluidum	5-10 min.
Tinctura Hyoscyami	1 fl. drm.

U.S.P. Hyoscyaminæ Sulphas. SULPHATE OF HYOSCYAMINE, $(C_{17}H_{23}NO_3)_2.H_2SO_4$; 676.—The neutral sulphate of an alkaloid prepared from hyoscyamus.

CHARACTERS.—Small golden-yellow, or yellowish-white scales or crystals, or a yellowish-white, amorphous powder, deliquescent on exposure to air, odourless, having a bitter and acrid taste and a neutral reaction. Very soluble in water and in alcohol. When heated on platinum foil, the salt chars and is finally completely dissipated. An aqueous solution of the salt is not precipitated by test-solution of platinic chloride. With chloride of gold it yields a precipitate, which, when recrystallised from boiling water acidulated with hydrochloric acid, is deposited on cooling (without rendering the liquid turbid) in brilliant, lustrous, golden-yellow scales (difference from atropine). The aqueous solution yields, with test-solution of chloride of barium, a white precipitate insoluble in hydrochloric acid.

It is found also in the seeds of *Belladonna Stramonium*, and in *Duboisia myoporoides*, the alkaloid of which (duboisine) is identical with hyoscyamine. Hyoscyamine is isomeric with atropine.

DOSE.—$\frac{1}{60}$ gr. to 1 gr.

ACTION AND USES.—The physiological action of hyoscyamine is like that of atropine and daturine. Hyoscyamus is used chiefly as an adjunct to purgatives to lessen griping. It is also used to lessen spasm, and to allay pain and irritation of the bladder. It has also been employed as a sedative to the nervous system.

Stramonii Folia, B. and U.S.P. STRAMONIUM LEAVES.—The dried leaves of *Datura Stramonium*. Thorn Apple. Cultivated in Britain.

CHARACTERS.—Large, ovate, sinuous, deeply cut; of a heavy odour, which is strongest while they are drying, and of a mawkish, faintly bitter, nauseous taste.

COMPOSITION.—A very small proportion of daturine. The other constituents are chiefly saline and mineral matters.

Stramonii Semina, B.P.; Stramonii Semen, U.S.P. STRAMONIUM SEEDS, B.P.; STRAMONIUM SEED, U.S.P.—The ripe seeds of *Datura Stramonium*.



FIG. 174.—Stramonium seeds.

CHARACTERS.—Brownish-black, reniform, flat, rough; inodorous unless bruised, when they emit a peculiar, heavy smell.

COMPOSITION.—Contains an alkaloid daturine, identical with atropine, and also some hyoscyamine.

PREPARATIONS.

B.P.	DOSE.
Extractum Stramonii	$\frac{1}{4}$-$\frac{1}{2}$ gr.
Tinctura Stramonii	10-30 min.

U.S.P.	DOSE.
Extractum Stramonii	$\frac{1}{2}$ gr.
Extractum Stramonii Fluidum	1 min.
Tinctura Stramonii	10-30 min.
Unguentum Stramonii	

ACTION AND USE.—The impure alkaloid daturine, consisting of atropine and hyoscyamine, has exactly the **same** physiological action **as atropine,** though less powerful.

The chief use of stramonium is as an **antispasmodic** in cases of asthma. It is often employed in the form of cigarettes during the attack, or the fumes of the ignited powder are inhaled. A mixture of potassæ nitras, potassæ chloras, stramonium, and ipecacuanha has been employed with good effect in asthma by inhaling the fumes of the ignited mixture. The leaves of *Datura Tatula* have been substituted for *Datura Stramonium*.

Tabaci Folia, B.P.; Tabacum, U.S.P. LEAF TOBACCO, B.P.; TOBACCO, U.S.P.—The dried leaves of Virginian Tobacco, *Nicotiana Tabacum*. Cultivated in America.

CHARACTERS.—Large, mottled-brown, ovate or lanceolate, acuminate leaves, up to twenty inches (50 centimetres) long, bearing numerous short, glandular hairs; having a peculiar, heavy odour and nauseous-bitter, acrid taste; yielding, when distilled with solution of potash, an alkaline fluid, which has the peculiar odour of nicotine, and precipitates with perchloride of platinum and tincture of galls. Not manufactured.

PREPARATION.

B.P.	DOSE.	U.S.P.
Enema Tabaci	20 gr. to 8 fl. oz.	None.

COMPOSITION.—A volatile liquid alkaloid, nicotine, is contained in tobacco as a malate, and is obtained by distillation with an alkali. The leaves contain also nicotianin, or tobacco camphor, which crystallises out from an aqueous distillate. Resin, gum, and several inorganic compounds are also present.

GENERAL ACTION.—Tobacco stimulates and then paralyses the motor nerves of involuntary muscles and the **secreting nerves** of glands. In consequence of this action of tobacco on the **intestine,** there is in poisoning by it nausea and vomiting, with intense prostration and wretchedness. In consequence of the action of the drug on the **heart** and **vaso-motor system,** there is paleness of the face, cold sweats, feebleness of circulation, and tendency to faint. The action of tobacco is the same as that of its alkaloid, nicotine, though less powerful. In **frogs,** nicotine, after a period of temporary excitement, causes a tetanic condition in a peculiar attitude, the head being drawn down, the fore legs back, and the hind legs forward. This is followed by muscular relaxation. In **warm-blooded animals** there is excitement, difficulty of breathing, followed by trembling, with expulsion of urine and fœces, stupor, staggering gait, convulsions, and death. When the dose is very large, the animal may fall with a loud cry and the convulsions begin at once, deepening into muscular paralysis; and death ensues from failure of respiration, the heart continuing to beat after respiration ceases. Convulsions also occur in frogs.

SPECIAL ACTION.—**Spinal cord** is first stimulated (p. 151), giving rise to convulsions, and is afterwards paralysed. The convulsions are of spinal origin in the frog, as is shown by such experiments as have been already mentioned (p. 150), but those which occur before death in mammals are probably asphyxial.

Circulation.—Nicotine causes a great diminution of pulse rate and a fall of blood-pressure, followed by a rise of blood-pressure, the pulse rate still remaining slow; but if a large dose be given, the pulse rate rises very quickly. The drug first stimulates both the **vagus** roots and its ends in the heart (causing slow pulse rate), and then paralyses the latter (causing high pulse rate). It does not, however, paralyse the inhibitory ganglia of the heart, like atropine, since stimulation of the sinus will slow the heart in frogs after nicotine poisoning. The primary fall of **blood-pressure** is due to the slowing of the **heart,** and the subsequent rise to contraction of the peripheral **vessels.**

Alimentary canal.—Nicotine stimulates peristalsis markedly (p. 333).

The methyl and ethyl derivatives of nicotine have no tetanising influence on the cord, neither, curiously enough, do they paralyse the ends of the motor nerves.

THERAPEUTICS.—Tobacco is used as an enema in supposed intussusception, but it must be employed with care.

Owing to its influence on the cord, nicotine has been used in tetanus and strychnia poisoning, but is not of much use.

TOBACCO-SMOKING.—The effects produced on the system by tobacco-smoking may be partly due to nicotine, but are probably rather due to products of its decomposition such as pyridine and collidine. In pipe-smoking pyridine (p. 733) preponderates, but when smoked in cigars, where there is free access of air, the chief product of the dry distillation undergone by the tobacco is collidine, which is far less active than pyridine (Vohl and Eulenburg).

In those accustomed to smoke tobacco, it has a soothing effect on the nervous system, but it often acts as a nervous stimulant to mental work, as in reading. In these cases the effect is probably not due to the nicotine itself, but to the stimulus of the smoke on the sensory nerves of the mouth, which reflexly stimulates the vaso-motor centre, and dilates the vessels of the brain; since some people produce the same effect by sucking sweets, or sipping whisky and water (p. 161).

There is no doubt that smoking in excess is injurious. It produces a furred tongue, irritation of the throat, hoarseness, often dyspepsia, and irritability of the heart, with a characteristic rhythm and palpitation (smoker's heart). This effect on the heart is like that produced by partial paralysis of the vagus, and disappears when the habit is given up for a time.

Sudden faintness is also apt to occur, so that a previously strong and healthy man will suddenly fall down in a state of syncope without apparent cause, or the faint may be brought on by some mental emotion.

The sight is impaired by habitual excess in tobacco smoking.

Tobacco smoking is often very useful in asthma, and a pipe after breakfast will often relieve constipation.

Tobacco snuff is used as an errhine.

SCROPHULARIACEÆ.

Digitalis Folia, B.P.; Digitalis, U.S.P. DIGITALIS LEAF, B.P.; DIGITALIS, FOXGLOVE, U.S.P.—The dried leaf of *Digitalis purpurea*, purple foxglove. Collected from wild indigenous plants, when about two-thirds of the flowers are expanded, B.P. The leaves of Digitalis, U.S.P.

CHARACTERS.—Ovate-lanceolate, shortly petiolate, rugose, downy, paler on the under surface, crenate.

COMPOSITION.—Contains a number of active principles formerly included under the name of digitaline.

PREPARATIONS.

B.P.	DOSE.
Digitalinum	$\frac{1}{60}$-$\frac{1}{30}$ gr.
Infusum Digitalis (3 gr. to 1 fl. oz.)	2-4 fl. drm. or more.
Tinctura Digitalis (54 gr. to 1 fl. oz.)	5-30 min.

U.S.P.	DOSE.
Abstractum Digitalis	$\frac{1}{2}$-1 gr.
Extractum Digitalis	$\frac{1}{4}$-$\frac{1}{3}$ gr.
Extractum Digitalis Fluidum	1-2 min.
Infusum Digitalis	1-2 fl. drm.
Tinctura Digitalis	5-10 min.

Infusum Digitalis. INFUSION OF DIGITALIS.—Digitalis leaves, dried, 30 gr. ; boiling distilled water, 10 fl. oz. Infuse in a covered vessel, for one hour, and strain, B.P. Digitalis in No. 20 powder, 3 ; cinnamon in No. 20 powder, 3 ; boiling water, 185 ; alcohol, 15 ; water, q.s. Pour the boiling water on the mixed powders and macerate for two hours in a covered vessel. Then strain, add the alcohol and pass enough water through the strainer to make the infusion weigh 200 parts, U.S.P.

B.P. Digitalinum. DIGITALIN.

PREPARATION.—Dissolving out digitalin from alcoholic extract of the leaves by acetic acid and water, decolorising by animal charcoal. Neutralising by ammonia and precipitating the digitalin by tannic acid. Rubbing with oxide of lead and spirit to remove the tannic acid. Dissolving out the digitalin with spirit, again decolorising by animal charcoal, evaporating, and purifying by washing with ether.

CHARACTERS AND TESTS.—In porous, mammillated masses or small scales, white, inodorous, and intensely bitter ; readily soluble in spirit, but almost insoluble in water and in pure ether ; dissolves in acids, but does not form with them neutral compounds ; its solution in hydrochloric acid is of a faint yellow colour, but rapidly becomes green. It leaves no residue when burned with free access of air. It powerfully irritates the nostrils, and is an active poison.

DOSE.—$\frac{1}{60}$-$\frac{1}{30}$ of a grain.

CHEMISTRY OF DIGITALIS.—Formerly the active principle of digitalis was said to be digitaline, but the substances prepared and sold by different manufacturers under this name varied much in their solubility and in the intensity of their physiological action. The most important varieties were Homolle's amorphous digitaline, Nativelle's crystallised digitaline, and soluble or German digitalin.

An examination of the chemistry of digitalis by Schmiedeberg has shown that there are at least five principles present in it, and possibly there are present also some products of their decomposition. They are all non-nitrogenous and, with the exception of one, digitoxin, are glucosides. They are : digitoxin, digitalin, digitaleïn, digitonin, and digitin. The first three of these are cardiac poisons. Digitonin has an action like that of saponin, and digitin appears to be inert.

Digitoxin is quite insoluble in water, and forms the chief constituent in Nativelle's digitaline. By boiling with dilute acids digitoxin yields toxiresin and digitalin yields digitaliresin.

Digitalin is also insoluble in water and is the active principle of Homolle's digitalin. Digitaleïn differs from the two former in being readily soluble in water, and forms a large proportion of the soluble digitalin.

The digitaline of the B.P. being almost insoluble in water probably consists chiefly of digitoxin or digitalin.

GENERAL ACTION.—In large doses digitalis causes sickness, vomiting, muscular weakness, diuresis, subjective affections of vision, laboured respiration, and death; the heart usually failing before the respiration. The condition of the heart after death varies. Sometimes I have found it in diastole and sometimes in systole in dogs poisoned by digitalis.

SPECIAL ACTION.—On the **muscles.** In a number of unpublished experiments on this subject made in 1867-68 in the laboratories of Professors Brücke and J. Rosenthal, I found that soluble digitalin did not lessen the excitability of the unweighted muscle but diminished its power to lift a weight. According to Schmiedeberg and Koppe digitalis paralyses all voluntary muscles. Digitalin causes elongation of the muscle with increased elasticity in the frog.

On the **nervous system.** It has no marked action on sensory or motor nerves. It has little action on the spinal **cord.** It has been stated to lessen reflex action in the frog by stimulation of Setchenow's centre, but this may be due to reflex irritation from the point of injection (p. 137). The **brain** is unaffected and in cases of poisoning remains clear to the last. (Two of the products of the decomposition of digitalin, toxiresin and digitaliresin, however, produce convulsions like those of picrotoxin.) Large doses cause subjective affections of vision consisting in dimness, occasional flashes of light, or in the constant appearance of a rainbow or bright light before the eyes. Locally applied to the eye it produces irritation at first, and afterwards causes a halo to surround bright objects.

The **respiration** is generally somewhat slowed, and occasionally before death may become excessively slow.

The effects produced on the circulation by the active principles of digitalis and by substances having a similar action, such as oleandrin, scilliain, adonidin, neriin, convalamarin, antiarin, and helleborein, may be divided according to Schmiedeberg into four stages :—

1. Rise of blood-pressure, usually though not invariably accompanied by slowing of the pulse.
2. Continued rise of blood-pressure, with a quick pulse.
3. Continued high pressure, with irregularity of the heart's action and pulse rate.
4. Rapid fall of the blood-pressure, sudden stoppage of the heart, and death.

The rise in **blood-pressure** is regarded by Schmiedeberg,

Boehm, and others as entirely due to increased action of the **heart** and not at all to contraction of the vessels. With this view I cannot agree, and I still hold to the opinion which I expressed many years ago that the rise in pressure is due in great measure to contraction of the **arterioles.** Not only is it more difficult to raise the pressure in the arterial system by alterations in the heart's action than by contraction of the arterioles, as we find from experiments on a schema (p. 225), but the form of the pulse curve under the action of digitalis conclusively demonstrates that the arterioles are contracted (*vide* p. 235). This has also been



FIG. 175.—Pulse-wave *b* before and *a* after injection of digitalis in a dog.

demonstrated by Donaldson and Stevens,[1] who found that the addition of digitalis to blood lessens the flow through vessels in which circulation was artificially maintained. A similar result has been obtained by Ringer.

The slow pulse in the first stage of digitalis poisoning is partly due to stimulation of the **vagus roots** of the medulla, and partly to increased sensibility or actual stimulation of the ends of the nerves in the heart. This increased sensibility has been shown to exist by Boehm, who found that after the administration of digitalis, a faradaic current which previously had no action on the heart would not only slow the pulse but produce prolonged diastolic arrest.

The rapid pulse in the second stage of digitalis poisoning is due to paralysis of the **vagus ends.** The irregularities in the third stage depend on the action of the drug on the heart itself.

The action of digitalis on the **frog's heart** is very peculiar. At first it causes the pulsations to become slower and more powerful, then the contraction during systole becomes peristaltic, and the dilation during diastole less and less complete, until finally the ventricle stands quite still, in such complete systolic contraction that its cavity is entirely obliterated. The auricles are sometimes distended with blood, sometimes only moderately dilated. According to Schmiedeberg this contraction is not tetanic, but is rather due to

[1] *Journal of Physiology*, vol. iv. p. 165.

increased elasticity of the cardiac muscle which prevents its normal relaxation during diastole. When it is overcome by driving a nutrient fluid into the ventricle under pressure, or by partially paralysing the cardiac muscle by saponin, apomorphine, or hydrocyanic acid, the systolic stillstand is removed, and pulsation again recommences.

Digestive Organs.—Small doses of digitalin have a pleasant bitter taste but exercise no marked effect upon the digestive organs. Larger doses produce loss of appetite, nausea, and vomiting, with rumbling and pain in the abdomen, and sometimes diarrhœa. This occurs even when the drug is injected subcutaneously.

Urine.—All observers are agreed regarding the diuretic power of digitalis in cardiac disease, but most of them state that it has no such power in health. In my own experiments, however, in which I took the same quantity of food by weight and of fluid by measure during more than a hundred days, I found that, while small doses had little or no action, marked diuresis occurred when the drug was pushed so as to produce symptoms of poisoning. In these experiments also I found that while the diuresis continued the absolute quantity of solids excreted daily in the urine was increased, although their proportion to the urinary water was diminished. In cases of poisoning by digitalis, a marked diminution in the flow of urine frequently precedes a fatal issue; and on injecting digitalis into the veins of a dog, Mr. Power and I found that the secretion of urine became entirely arrested when the blood-pressure reached its maximum, and again commenced when the blood-pressure began to fall (p. 377). It is probably to the power of digitalis to arrest the action of the kidneys and thus stop its own excretion that its cumulative action is due (p. 31).

Effect of Temperature on the Action of Digitalis.—It has already been mentioned (p. 35) that digitalis has sometimes no action on the pulse in pneumonia. The inhibitory action of the vagi on the heart is lessened by heat, but their peripheral terminations, although weakened, are not completely paralysed. While this volume was passing through the press Dr. Cash and I have made some experiments which appear to show that a very high temperature has an action on the vagus centre in the medulla similar to its action on the ends of the nerve in the heart. It does not completely paralyse either the centre or the peripheral ends of the nerve, but it greatly weakens them. This weakening action is so great that it practically amounts to paralysis, for when the temperature rises above a certain point the pulse-rate suddenly rises just as it would do if both vagi were cut. This is shown by Fig. 176. When the pulse-rate has been thus quickened by heat, section of the vagi does not render it any quicker (Figs. 177 and 178).

Although the vagus centre is so much weakened by the action of the heat that it ceases to exercise any inhibitory action

upon the heart, yet its functional activity is not completely destroyed even by very high temperatures, and irritation of an afferent nerve will still cause reflex slowing (p. 248) of the pulse,



The unbroken line shows the pulse-rate, the dotted line shows the temperature in the axilla in all the figures.

FIG. 176.—Shows the effect of rise of temperature alone. At the 195th minute both vagi were cut; the section was not followed immediately by any apparent effect. After eight minutes more, the pulse-rate rose slightly and then fell.

until immediately before the death of the animal from hyperpyrexia.

These experiments render it probable that the rapid rise in the pulse-rate, which a high temperature occasions, is chiefly of central origin, and is due to partial paralysis of the vagus centre, although



FIG. 177.—Shows the effect of rise of temperature after injection of digitalis. At the 45th minute ·75 cc. (12 minims) tincture of digitalis were injected, and another similar injection was made at the 55th minute. At the 65th minute the heating was begun. After section of the vagi the pulse continued to rise, but not more rapidly than before.

diminished action of the peripheral ends of the vagus and increased action of the cardiac ganglia also aid in quickening the pulse.

Although neither the vagus centre nor the vagus ends in the

heart are completely paralysed by very high temperatures they are yet weakened so much that digitalis, and probably all drugs which act like it, such as adonidin (p. 289), no longer slow the pulse as they do at normal temperatures. This is shown in Fig. 178 where the pulse remained slow until the temperature rose to nearly 41° C. and then suddenly became very quick. Moderately high temperatures do not prevent digitalis from slowing the heart (Fig. 176).



FIG. 178.—Shows the action of digitalis when given after the temperature has already risen. At the 30th minute the warming was begun; at the 100th minute ·75 cc. of tincture of digitalis was injected.

Action of Different Preparations of Digitalis. — The two most marked effects of digitalis are a reduction in the rate of the pulse, and an increase in the amount of urine. These effects are not coincident, and, according to Christison, the diuretic action is less when the heart is much affected. The preparation generally employed to act on the heart is the tincture, while the infusion is regarded as the best diuretic.[1] The differences between the action of the infusion and tincture of digitalis are probably due, in part at least, to the different proportions in which the active principles of the plant are dissolved by alcohol and water.

In digitalis, as in physostigma (p. 819) and many other plants, there is a mixture of principles having antagonistic actions. Digitonin, which has an action very like saponin (pp. 266 and 833), will to a greater or less extent antagonise the action of digitoxin, digitalin, and digitaleïn. Digitonin is readily soluble in water, forming, like saponin, a solution which froths easily. Digitaleïn is soluble in water, but digitalin is only sparingly so, and digitoxin is hardly soluble in water at all.

The solubility of these substances in alcohol is almost the converse of their solubility in water. Digitonin is sparingly soluble in alcohol, while digitalin and digitaleïn are readily soluble. Digitoxin is only sparingly soluble in cold alcohol.

From the ready solubility of digitonin in water, infusion of

[1] *The National Dispensatory.*

digitalis will contain it in much larger proportion than digitalin or digitaleïn. This, indeed, is readily seen by putting some infusion of digitalis into one bottle and a corresponding dose of the tincture diluted with water until both solutions have the same bulk. On shaking the bottles, the infusion will be found to froth much more strongly and to retain the froth much longer than the diluted tincture, although the latter also froths strongly.

Tincture of digitalis will, on the other hand, contain a larger proportion of digitalin and digitaleïn, with probably a small quantity of digitoxin.

It is quite possible, however, that in addition to differences in the preparations due to the menstruum, there may be differences in the same preparation due to the plants used. Thus in Edinburgh the usual dose of the infusion is half an ounce, and this is usually readily tolerated, while in London I have frequently seen doses of one or two drachms produce considerable gastric disturbance. The infusion of the U.S.P. is nearly twice as strong as that of the B.P., and yet the recognised dose is considerably larger.

Whether these differences are or are not due to the amount and relative proportions of the active ingredients in digitalis plants grown in Scotland, England, and America, is a point which requires investigation, more especially when we have other examples, *e.g.*, cannabis indica, where there is a notable difference between the action of plants of the same species growing in different climates.

THERAPEUTICS.—It is chiefly used as a tonic to the heart, when its action is irregular and feeble, and in dropsy, especially cardiac dropsy (pp. 290 and 294).

It is used in functional palpitation, and in the irritable heart often seen in young soldiers, but its chief use is in mitral disease.

In pure aortic disease, with hypertrophy, it is not only injurious but dangerous, since by slowing the pulse-rate it lengthens the time during which blood can regurgitate (p. 291).

When the aortic disease is accompanied by mitral incompetence and the immediate danger is that from the mitral affection, it may be given with advantage (p. 292). In these cases, whilst taking the drug the patient must be kept perfectly quiet, as there is a great danger of sudden syncope (p. 292).

Digitalis is of great use as a soporific in sleeplessness at night, accompanied by drowsiness during the day, for both these symptoms depend on want of tone in the vessels, the blood gravitating to the feet when the patient is erect and to the head when in a lying posture (p. 162).

It is very useful in hæmorrhages, especially when occurring in the lungs, and it has been added to cough mixtures to lessen congestion of the mucous membrane.

It was formerly used in fever and pneumonia, but is now discarded as being of very little use.

In delirium tremens it has been given in very large doses, but its use is dangerous.

In dropsy depending on mitral disease, also in renal dropsy and ascites, it has been used with good effect.

It is very serviceable in some cases of menorrhagia. Its action in this case is due not to contraction of the vessels of the uterus, but of the walls of the uterus itself, since digitalis did not affect hæmorrhage from a fungoid growth in the cervix (Dickinson).

It is also useful in spermatorrhœa.

PRECAUTIONS.—(1) Stop the administration of digitalis on the appearance of sickness or a tendency to faint, or change the preparation of digitalis and lower the dose.

(2) Do not give digitalis in large doses unless you see the patient frequently, and it is necessary to push the drug. Keep the patient in bed, and do not allow him even to sit up in bed, much less to rise, and above all not to rise up and make water, as otherwise fatal syncope may occur (p. 223).

TREATMENT ON POISONING.—Keep the patient recumbent and give stimulants, *e.g.* alcohol. Tannin has been recommended in order to precipitate digitalin in the stomach.

U.S.P. Leptandra. LEPTANDRA. CULVER'S ROOT.—The rhizome and rootlets of *Leptandra virginica* (*Veronica virginica*).

CHARACTERS.—Horizontal, from four to six inches (10 to 15 centimetres) long, and about a quarter of an inch (6 millimetres) thick, somewhat flattened, bent and branched, deep blackish-brown, with cup-shaped scars on the upper side, hard, of a woody fracture, with a thin, blackish bark, a hard, yellowish wood, and a large, purplish-brown, about six-rayed pith; rootlets thin, wrinkled, very fragile; inodorous; taste bitter and feebly acrid.

PREPARATIONS.

	DOSE.
Extractum Leptandræ	(of the root, 2-4 gr.)
Extractum Leptandræ Fluidum	30-60 min.

COMPOSITION.—It contains a resinous principle, leptandrin.

ACTION.—It is an irritant to the gastro-intestinal mucous membrane, and **stimulates** the secretion of **bile** (p. 353). It may be used as a **cathartic** in biliousness or constipation.

LABIATÆ.

Rosmarinus, U.S.P. ROSEMARY.—The leaves of *Rosmarinus officinalis*.

CHARACTERS.—About one inch (25 millimetres) long, rigid, linear, entire, revolute, dark green above, woolly and glandular beneath; pungently aromatic; somewhat camphoraceous.

PREPARATION.
Vinum Aromaticum.

Oleum Rosmarini, B. and U.S.P. OIL OF ROSEMARY.—The oil distilled from the flowering tops of *Rosmarinus officinalis*, B.P. A volatile oil distilled from rosemary, U.S.P.

CHARACTERS.—Colourless, with the odour of rosemary, and a warm aromatic taste.

PREPARATIONS.

B.P.	DOSE.
Linimentum Saponis	for external use.
Spiritus Rosmarini	10-50 min. or more.
Tinctura Lavandulæ Composita	½-2 fl. drm. (of the oil, 1-5 min.)

U.S.P.	DOSE.
Linimentum Saponis	for external use.
Spiritus Odoratus	do.
Tinctura Lavandulæ Composita	½-2 fl. drm.

ACTION AND USE.—It is a stimulant and **carminative,** and is used to lessen flatulence, and to allay pain and spasm of the intestines. It is a useful adjunct to purgatives, and is used in hysteria.

U.S.P. Lavandula. LAVENDER.—The flowers of *Lavandula vera.*

CHARACTERS.—Calyx tubular, blue-grey, hairy, five-toothed, the upper tooth largest and roundish-rhomboid; corolla violet-blue, hairy and glandular on the outside, tubular and two-lipped, the upper lip two-lobed, the lower lip three-lobed; stamens four, short, on the corolla tube; odour fragrant; taste bitterish, aromatic, somewhat camphoraceous.

PREPARATION.
Vinum Aromaticum.

Oleum Lavandulæ, B. and U.S.P. OIL OF LAVENDER.—The oil distilled in Britain from the flowers of *Lavandula vera*, B.P. A volatile oil distilled from the flowering tops or whole herb of *Lavandula vera*, U.S.P.

CHARACTERS.—Colourless or pale yellow, with the odour of lavender, and a hot, bitter, aromatic taste.

PREPARATIONS.

B.P.	DOSE.
Linimentum Camphoræ Compositum	
Spiritus Lavandulæ	½-1 fl. drm.
Tinctura Lavandulæ Composita	½-2 fl. drm. (of the oil, 5 min.)

U.S.P.	DOSE.
Tinctura Lavandulæ Composita	½-2 fl. drm.

U.S.P. Oleum Lavandulæ Florum. OIL OF LAVENDER FLOWERS.—A volatile oil distilled from fresh lavender.

CHARACTERS.—A colourless or yellowish liquid, having the fragrant odour of lavender flowers, a pungent and bitterish taste, and a neutral reaction while fresh. Sp. gr. about 0·890. It is readily soluble in alcohol and in acetic acid of 90 or more per cent. When heated to about 80° C. (176° F.) it should not yield a colourless distillate having the characteristics of alcohol.

DOSE.—1-5 min.

PREPARATIONS.

U.S.P.	DOSE.
Spiritus Lavandulæ (3 parts of the oil with 97 of alcohol)	½-2 fl. dr.
Spiritus Odoratus	

ACTION AND USES.—Lavender is a **stimulant** and **carminative,** and is used to lessen flatulence, to relieve colic, and in hysteria.

Oleum Menthæ Piperitæ, B. and U.S.P. OIL OF PEPPERMINT.—The oil distilled in Britain from fresh flowering peppermint, *Mentha piperita,* B.P.

A volatile oil distilled from peppermint, U.S.P.

CHARACTERS.—Colourless or pale yellow, with the odour of peppermint; taste warm, aromatic, succeeded by a sensation of coldness in the mouth.

PREPARATIONS.

B.P.	DOSE.
Aqua Menthæ Piperitæ	1½ fl. drm. to 1 gallon...1-2 fl. oz.
Essentia Menthæ Piperitæ	...1 volume in 5 .....10-20 min.
Pilula Rhei Composita	.....1 min. in 1 drm. nearly 5-10 gr.
Spiritus Menthæ Piperitæ	.....1 volume in 50.....½ fl. drm. (of the oil, 1-5 min.)

U.S.P.	DOSE.
Aqua Menthæ Piperitæ	.....1-2 fl. oz.
Spiritus Menthæ Piperitæ	.....10-15 min.
Trochisci Menthæ Piperitæ (Peppermint Lozenges)	..ad lib.

ACTION AND USE.—**Carminative** and stimulant, used to relieve flatulence and colic; and as an adjunct to purgatives, to lessen griping. Mosquito bites may be prevented by rubbing the skin of the face and hands, the lips and the margins of the nostrils with soap strongly scented with peppermint or lavender. A sprig of pepperment or pennyroyal, or a small bottle containing their volatile oils, hung near the head during sleep is said to have a similar effect. Peppermint lozenges are useful in relieving flatulence and tendency to faintness due to it.

Menthol. $C_{10}H_{20}O$. PEPPERMINT CAMPHOR. Not officinal.

PREPARATION.—It separates from peppermint oil after standing, or on cooling to 20° C.

CHARACTERS.—Colourless crystals with a taste and smell of peppermint oil, sparingly soluble in water, readily soluble in alcohol, ether, and etherial oils. When rubbed up with an equal quantity of thymol it forms a colourless oily liquid. The same is the case when it is rubbed with an equal quantity of pure carbolic acid or

of chloral hydrate, or with croton chloral hydrate in the proportion of 1 part to 2 of menthol, or with camphor 2 parts to three of menthol.

ACTION.—It is a powerful **antiseptic.** When applied to mucous membrane or skin it causes a feeling of warmth or burning, replaced by a feeling of coldness when the part is blown upon.

USES.—It is chiefly used as an **anti-neuralgic.** It is either applied in the form of a solid pencil rubbed lightly over the part where the pain is felt, or an alcoholic solution, or the oily liquids prepared by trituration with camphor, carbolic acid, &c., may be painted over the painful spots. These oily liquids are also applied on cotton wool in order to relieve toothache.

Oleum Menthæ Viridis, B. and U.S.P. OIL OF SPEARMINT.—The oil distilled in Britain from fresh flowering spearmint, *Mentha viridis*, B.P.

CHARACTERS.—Colourless or pale yellow, with the odour and taste of spearmint.

PREPARATIONS.

B.P.	DOSE.
Aqua Menthæ Viridis.....1½ fl. drm. to 1 gallon	1-2 fl. oz. (of the oil, 1-5 min.)

U.S.P.	DOSE.
Aqua Menthæ Viridis	1-2 fl. oz.
Spiritus Menthæ Viridis	5-20 min.

ACTION AND USE.—Like other **carminatives** and stimulants, to relieve colic, flatulence, and with purgatives to prevent griping.

U.S.P. Thymol. THYMOL. $C_{10}H_{13}HO$, or $C_6H_3.C_3H_7.CH.OH$.

PREPARATION.—It is obtained from the volatile oils of *Thymus vulgaris* (Labiatæ), *Thonarda punctata* (Labiatæ), and *Ptychotis ajowan* (Umbelliferæ).

These oils contain thymol and thymene, $C_{10}H_{16}$, which is fluid. The thymol is separated by fractional distillation or prolonged refrigeration.

CHARACTERS.—Large crystals of the hexagonal system, nearly or quite colourless, having an aromatic, thyme-like odour, a pungent, aromatic taste, with a very slight caustic effect upon the lips and a neutral reaction. Soluble in about 1,200 parts of water, and in 1 part of alcohol at 15° C. (59° F.); in 900 parts of boiling water; freely soluble in burning alcohol, also in ether, chloroform, benzol, benzin, glacial acetic acid, and in fixed or volatile oils. It liquifies with camphor. Its sp. gr. as a solid is 1·028; after fusion it is lighter than water. It melts at about 50° C. (122° F.), remaining liquid at lower temperatures, and boils at about 230° C. (446° F.). A portion mixed with half its volume of glacial acetic acid, then with an equal or somewhat greater volume of sulphuric acid, and gently heated, gives a bright reddish-violet colour.

IMPURITY.—Carbolic acid.

TEST.—Water saturated with thymol when treated with a few drops of test solution of ferric chloride should not give a blue colour (absence of carbolic acid).

DOSE.—Internally, ½-1½ gr. For spray, 1 in 800 of hot water. As ointment, 5-30 gr. to 1 oz. of petrolatum. As inhalation, 6 gr. to an ounce of warm water.

ACTION.—In respect of its physiological action, thymol appears to stand between carbolic acid and oil of turpentine. Like carbolic acid, it destroys low organisms, and is a powerful **disinfectant.** In higher animals it acts as a local irritant and anæsthetic to the skin and mucous membranes. When absorbed it **paralyses** the **nerve centres** in the **cord** and **medulla,** like carbolic acid, lessening reflex action, slowing **respiration,** and lowering the **blood-pressure** and **temperature.** In poisonous doses it causes weakness, drowsiness, coma, and death. It differs from carbolic acid in being less volatile and less easily oxidised. Its action as a disinfectant is more permanent, and at the same time more powerful than that of carbolic acid. It is less irritating to the skin or mucous membrane, and does not act as a caustic like carbolic acid, and it is a less powerful poison to mammals. Its action on the nerve centres is a paralysing one from the first, and is not preceded by excitement as in the case of carbolic acid. While in the body it appears to effect tissue metabolism, for in animals poisoned by it the liver is found quite fatty, as in phosphorus poisoning. It appears to be **eliminated** by the respiratory and urinary organs, and to cause irritation of these organs during the process of excretion. In poisoning by it the bronchial mucous membrane is extremely congested, the secretion of mucus increased; the lungs congested, and sometimes consolidated; the kidneys inflamed, and the urine albuminous or bloody.

USES.—It has been used as an **antiseptic** instead of carbolic acid for dressing wounds; as an application to skin diseases, ringworm, eczema, or psoriasis; as a gargle, spray, or inhalation in sore throat, or as an injection in ozæna. Internally it has been used in diabetes and vesical catarrh.

U.S.P. Hedeoma. HEDEOMA. PENNYROYAL.—The leaves and tops of *Hedeoma pulegioides.*

CHARACTERS.—Leaves opposite, short-petioled, about half an inch (12 millimetres) long, oblong-ovate, obscurely serrate, glandular beneath; branches roundish-quadrangular; flowers in small, axillary cymules, with a tubular-ovoid, two-lipped and five-toothed calyx, and a pale-blue, spotted, two-lipped corolla, containing two sterile and two fertile exserted stamens; odour strong, mint-like; taste warm and pungent.

OFFICINAL PREPARATION.

U.S.P.	DOSE.
Oleum Hedeomæ	1-5 min.

COMPOSITION.—It contains a volatile oil.

ACTION AND USES.—It is stimulant, **carminative,** diaphoretic, and **emmenagogue.** It is used in flatulence and in amenorrhœa. It is frequently given in the form of hot infusion, to promote the menstrual flow when delay or recent suppression has occurred.

U.S.P. Marrubium. MARRUBIUM. HOREHOUND.—The leaves and tops of *Marrubium vulgare.*

CHARACTERS.—Leaves about one inch (25 millimetres) long, opposite, petiolate, roundish-ovate, obtuse, coarsely crenate, strongly rugose, downy above, white-hairy beneath; branches quadrangular, white, tomentose; flowers in dense, axillary, woolly whorls, with a stiffly ten-toothed calyx, a whitish bi-labiate corolla, and four included stamens; aromatic and bitter.

COMPOSITION.—It contains a volatile oil and a bitter principle marrubiin.

DOSE.—30-60 gr. (2-4 Gm.).

USES.—It is **expectorant,** tonic, diaphoretic, and diuretic. In large doses it is laxative. It is employed in laryngeal and bronchial catarrh, and in chronic affections of the lungs attended with cough and copious expectoration.

U.S.P. Melissa. MELISSA. BALM.—The leaves and tops of *Melissa officinalis.*

CHARACTERS.—Leaves about two inches (5 centimetres) long, petiolate, ovate, obtuse, crenate, somewhat hairy, glandular; branches quadrangular; flowers in about four-flowered cymules, with a tubular, bell-shaped, five-toothed calyx, a whitish or purplish two-lipped corolla, and four stamens; fragrant, aromatic, and bitterish.

COMPOSITION.—It has a small quantity of a volatile oil.

USES.—It has scarcely any remedial action, but is used in the form of warm infusion or tea as a **diaphoretic** in slight febrile conditions.

U.S.P. Origanum. ORIGANUM. WILD MARJORAM.—*Origanum vulgare.*

CHARACTERS.—Stem branched above, often purplish, leaves opposite, petiolate, about an inch (25 millimetres) long, roundish-ovate, obtuse, nearly entire, pellucid-punctate, hairy beneath; flowers in corymbs, with reddish bracts, a five-toothed calyx, a somewhat two-lipped, pale purple corolla, and four exserted stamens; aromatic, pungent, and bitterish.

PREPARATION.

Vinum Aromaticum. Used externally.

COMPOSITION.—It contains a volatile oil, which has been largely superseded by the oil of thyme.

ACTION AND USES.—The infusion is tonic, **diaphoretic,** and **emmenagogue.** It is also used externally as a fomentation.

U.S.P. Salvia. SALVIA. SAGE.—The leaves of *Salvia officinalis.*

CHARACTERS.—About two inches (5 centimetres) long, petiolate, ovate-oblong, obtuse, finely crenulate, thickish, wrinkled, greyish-green, soft-hairy and glandular beneath; aromatic, bitterish, somewhat astringent.

PREPARATION.

Vinum Aromaticum. Externally only.

COMPOSITION.—The leaves contain a volatile oil.

USES.—They are chiefly used as a condiment. The infusion is **tonic,** carminative, and slightly **astringent.** It is used in atonic dyspepsia, and to check hectic sweating.

U.S.P. Scutellaria. SCUTELLARIA. SKULL-CAP.—*Scutellaria lateriflora* (whole plant).

CHARACTERS.—About twenty inches (50 centimetres) long, smooth; stem quadrangular, branched; leaves opposite, petiolate, about two inches (5 centimetres) long, ovate-lanceolate or ovate-oblong, serrate; flowers in axillary, one-sided racemes, with a pale blue corolla and a two-lipped calyx, closed in fruit, the upper lip helmet-shaped; odour slight; taste bitterish.

OFFICINAL PREPARATION.

U.S.P.	DOSE.
Extractum Scutellariæ Fluidum	1-2 fl. drm.

USES.—As a remedy it has little value. It has been used as a nervine **tonic** in neuralgia, chorea, delirium tremens, and nervous exhaustion.

PEDALIACEÆ.

U.S.P. Oleum Sesami. OIL OF SESAMUM. (Benné Oil). A fixed oil expressed from the seed of *Sesamum indicum.*

CHARACTERS.—A yellowish or yellow, oily liquid, inodorous or nearly so, having a bland, nut-like taste, and a neutral reaction.

ACTION.—Similar to olive oil.

CHAPTER XXXIV.

Sub-class IV. APETALÆ.

POLYGONACEÆ.

Rhei Radix, B.P.; Rheum, U.S.P. RHUBARB ROOT, B.P.; RHUBARB, U.S.P.—The dried root deprived of the bark, from one or more undetermined species of Rheum. China, Chinese Tartary, and Thibet, B.P. The root, U.S.P.

CHARACTERS.—Trapezoidal, roundish, cylindrical, or flattish pieces, frequently bored with one hole, yellow externally, internally marbled with fine waving greyish and reddish lines, finely gritty under the teeth; taste bitter, faintly astringent and aromatic; odour peculiar.

COMPOSITION.—The chief constituent is chrysophanic acid, so-named from its forming brilliant yellow crystals. It is extracted by ether or alcohol, not by water. Besides this there is also a glucoside chrysophane, which splits up into chrysophanic acid and sugar. There are also several resinous matters, one of which, phaoretin, is purgative, and mineral compounds are also present, especially oxalate of lime. The astringency of rhubarb is due to a peculiar tannic acid (Rheo-tannic), which is soluble in water and alcohol, but not in ether.

IMPURITIES.—English rhubarb and turmeric fraudulently added.

TESTS.—Odour and taste (English rhubarb). Boracic acid does not turn the yellow exterior brown (turmeric).

PREPARATIONS.

B.P.	DOSE.
Extractum Rhei	5-15 gr.
Infusum Rhei (¼ oz. in ½ pint for 1 hour)	1-2 fl. oz.
Pilula Rhei Composita	5-10 gr.
Pulvis Rhei Compositus	5-10 gr. (child).
,, ,,	20-60 gr. (adult).
Syrupus Rhei	1-4 fl. drm.
Tinctura Rhei	1-2 fl. drm. (stomachic).
,, ,,	½-1 fl. oz. (purgative).
Vinum Rhei	1-2 fl. drm.

(of the powdered root, 1-5 gr. as stomachic, 10-30 gr. as purgative).

PREPARATIONS—(*continued*).—*Vide* p. 1005.

U.S.P.	DOSE.
RHEUM.	
Extractum Rhei	3-10 gr.
Extractum Rhei Fluidum	1-10 min.
Pilulæ Rhei (rhubarb, 3 ; soap, 1)	1-3 pills (3 gr. each).
Pilulæ Rhei Compositæ	1-4 pills.
Pulvis Rhei Compositus	30-60 gr.
Syrupus Rhei	1-4 fl. drm. } for children.
Syrupus Rhei Aromaticus	1-4 fl. drm. } for children.
Tinctura Rhei	1-6 fl. drm.
Tinctura Rhei Aromatica	1-4 fl. drm.
Tinctura Rhei Dulcis	1-4 fl. drm. for children.
Vinum Rhei	1-4 fl. drm.
Mistura Rhei et Sodæ	2 drm.-3 oz.

ACTION AND USES.—Rhubarb when chewed increases the flow of saliva. **Small doses** have a **tonic** and **astringent** action and are employed in atonic dyspepsia, especially when there is an accumulation of mucus in the intestinal tube. **Large doses** are **purgative** in their action, increasing peristalsis. This is followed by an astringent effect. It is especially useful in cases of diarrhœa, when there is some irritating body in the intestines: this is carried off, and then the after astringent action checks the diarrhœa.

U.S.P. Rumex. RUMEX. YELLOW DOCK.—The root of *Rumex crispus* and of other species of Rumex.

CHARACTERS.—From eight to twelve inches (20 to 30 centimetres) long, about half an inch (12 millimetres) thick, somewhat fusiform, fleshy, nearly simple, annulate above, deeply wrinkled below; externally rusty-brown, internally whitish, with fine, straight, interrupted, reddish medullary rays, and a rather thick bark; fracture short; odour slight, peculiar; taste bitter and astringent.

PREPARATION.

	DOSE.
Extractum Rumicis Fluidum	30-60 min.

COMPOSITION.—It contains tannic acid and rumicine, which is identical with chrysophanic acid.

ACTION.—It is **astringent** and bitter, and is supposed to possess **alterative** properties, which render it useful in scorbutic diseases.

PHYTOLACCACEÆ.

U.S.P. Phytolaccæ Bacca. PHYTOLACCA BERRY. POKE BERRY.—The fruit of *Phytolacca decandra.*

CHARACTERS.—A depressed-globular, dark purple, compound berry, about one-third of an inch (8 millimetres) in diameter, composed of ten carpels, each containing one lenticular, black seed; juice purplish-red; inodorous; sweet, slightly acrid.

U.S.P. Phytolaccæ Radix. PHYTOLACCA ROOT. POKE ROOT.—The root of *Phytolacca decandra.*

CHARACTERS.—Branched, wrinkled, yellowish-brown externally, yellowish-white internally. Transverse sections exhibit numerous concentric rings. No smell; taste sweetish, and afterwards acrid.

ACTION.—Poke is **emetic,** cathartic, and somewhat **narcotic,** producing in large doses vomiting, purging, drowsiness, dimness of vision, giddiness, and sometimes convulsions. It has been proposed as an emetic instead of ipecacuan, but its action is too slow. As an **alterative** it has been recommended in rheumatism. Externally a strong infusion or decoction of the root has been used in piles, skin diseases, and cancer.

CHENOPODIACEÆ.

U.S.P. Chenopodium. CHENOPODIUM. AMERICAN WORMSEED.—The fruit of *Chenopodium ambrosioides*, var. *anthelminticum*.

CHARACTERS.—Nearly one-twelfth of an inch (2 millimetres) in diameter, depressed-globular, glandular, dull greenish or brownish, the integuments friable, containing a lenticular, obtusely-edged, glossy, black seed. It has a peculiar, somewhat terebinthinate odour, and a bitterish, pungent taste.

DOSE.—10-40 grains.

U.S.P. Oleum Chenopodii.—A volatile oil distilled from wormseed.

USE.—It is used as a **vermifuge** to expel lumbricoid worms. The powdered seeds, which possess the active medicinal virtues, may be combined with some agreeable elixir, or the essential oil may be given on a lump of sugar, or in emulsion in doses of 3-5 minims.

MYRISTICACEÆ.

Myristica. NUTMEG.—The kernel of the seed of *Myristica officinalis*, B.P. The kernel of the seed of *Myristica fragrans* deprived of its testa, U.S.P. Malayan Archipelago.

CHARACTERS.—Oval or nearly round, about an inch in length, marked externally with reticulated furrows, internally greyish-red with dark brownish veins. It has a strong peculiar odour, and a bitter aromatic taste. Nutmeg resembles areca nut, especially in its internal structure, but the latter is devoid of the strong odour.

COMPOSITION.—Fixed oil (oil of mace) and volatile oil, the latter imparting the aromatic smell and taste.

PREPARATIONS.

B.P.	DOSE.
Oleum Myristicæ	1-5 min.
Oleum Myristicæ Expressum	1-5 min.
Pulvis Catechu Compositus	20-40 gr.
Pulvis Cretæ Aromaticus	10-60 gr.
Spiritus Armoraciæ Compositus	1-2 fl. drm.
Tinctura Lavandulæ Composita	½-2 fl. drm.
	(of powdered nutmeg, 5-15 gr.)

U.S.P.	DOSE.
Tinctura Lavandulæ Composita	½-2 fl. drm.
Pulvis Aromaticus	10-30 gr.

Oleum Myristicæ, B. and U.S.P. VOLATILE OIL OF NUTMEG.—The oil distilled in Britain from nutmeg, B.P. A volatile oil distilled from nutmeg, U.S.P.

CHARACTERS.—Colourless or straw-yellow, having the odour and taste of nutmegs.

PREPARATIONS.

B.P.	DOSE.
Pilula Aloes Socotrinæ	5-10 gr.
Spiritus Ammoniæ Aromaticus	30 min. to 1 fl. drm.
Spiritus Myristicæ (Mistura Ferri Composita).	30-60 min.

U.S.P.	DOSE.
Spiritus Myristicæ	1-2 fl. drm.

B.P. Oleum Myristicæ Expressum. EXPRESSED OIL OF NUTMEG.—A concrete oil obtained by means of expression and heat from nutmegs.

CHARACTERS.—Of an orange colour, firm consistence, and fragrant odour like that of nutmeg.

PREPARATIONS.

B.P.

Emplastrum Calefaciens. Emplastrum Picis.

ACTION AND USES.—Nutmeg is aromatic, **stimulant,** and **carminative.** The expressed oil is used externally as a stimulant, and with other stimulants is contained in emplastrum picis and emplastrum calfaciens. It is very little used in medicine, but chiefly to flavour articles of food.

U.S.P. Macis. MACE.—The arillus of the fruit of *Myristica fragrans.*

CHARACTERS.—In narrow bands, one inch (25 millimetres) or more long, somewhat branched and lobed above, united to broader bands below; brownish-orange; fatty when scratched or pressed; odour fragrant; taste warm and aromatic.

USES.—It contains the **same** volatile oil as **nutmeg,** and has the same uses.

LAURACEÆ.

Cinnamomi Cortex, B.P.; Cinnamomum, U.S.P. CINNAMON BARK, B.P.; CINNAMON, U.S.P.—The inner bark of shoots from the truncated stocks of *Cinnamomum zeylanicum.* Imported from Ceylon.

CHARACTERS.—In closely rolled quills, containing several small quills within them, light yellowish-brown, with a fragrant odour and warm sweet aromatic taste: breaks with a splintery fracture.

COMPOSITION.—A volatile oil to the extent of 1 per cent. with mannite, sugar, mucilage, and tannic acid.

ADULTERATION.—Cassia lignea.

TEST.—Decoction of cassia lignea is coloured blue-black by tincture of iodine.

PREPARATIONS.

B.P.	DOSE.
Acidum Sulphuricum Aromaticum	5-30 min.
Aqua Cinnamomi	1-2 fl. oz.
Decoctum Hæmatoxyli	1-2 fl. oz.
Infusum Catechu	1-2 fl. oz.
Oleum Cinnamomi	1-5 min.
Pulvis Catechu Compositus	20-40 gr.
Pulvis Cinnamomi Compositus	10-30 gr.
Pulvis Cretæ Aromaticus	10-60 gr.
Pulvis Kino Compositus	5-20 gr.
Tinctura Cardamomi Composita	½-2 fl. drm.
Tinctura Catechu	½-2 fl. drm.
Tinctura Cinnamomi	½-2 fl. drm.
Tinctura Lavandulæ Composita	½-2 fl. drm.
Vinum Opii	10-40 min.

U.S.P.	DOSE.
Pulvis Aromaticus	10-30 gr.
Tinctura Cinnamomi	½-2 fl. drm.
Oleum Cinnamomi	1-5 min.
Tinctura Lavandulæ Composita	½-2 fl. drm.
Vinum Opii	6 min.

Pulvis Cinnamomi Compositus, B.P.; Pulvis Aromaticus, U.S.P. COMPOUND CINNAMON POWDER, B.P.; AROMATIC POWDER, U.S.P.—Equal parts of cinnamon, cardamoms, and ginger, B.P. Cinnamon 35, ginger 35, cardamoms 15, nutmeg 15, U.S.P.

Oleum Cinnamomi, B. and U.S.P. OIL OF CINNAMON.—The oil distilled from cinnamon bark.

CHARACTERS.—Yellowish when recent, gradually becoming red, having the odour and taste of cinnamon.

COMPOSITION.—Consists principally of cinnamic aldehyde, or hydride of cinnamyl, with other hydrocarbons, one of which, a camphor, is deposited at low temperatures, thus causing the change in colour. The oil has a specific gravity of from 1·025 to 1·050, so that it sinks in water. It is slightly lævulose.

PREPARATIONS.

B.P.

None.

U.S.P.	DOSE.
Aqua Cinnamomi	Indefinite.
Spiritus Cinnamomi	5-15 min.
Acidum Sulphuricum Aromaticum	5-15 min.

ACTION AND USES.—Cinnamon is an aromatic **carminative,** and since it contains tannic acid slightly **astringent.** It is chiefly used in conjunction with other astringents, and from its agreeable taste is very frequently employed.

Coto Bark. Not officinal. The bark of a tree imported from Bolivia.

COMPOSITION.—It contains an alkaloid, cotoin. Cotoin forms a pale yellow powder or minute crystals sparingly soluble in water, soluble in alcohol, ether, and chloroform.

ACTION.—It appears greatly to **increase intestinal absorption** (p. 337).

USES.—It is useful in gastric and intestinal catarrh, in infantile diarrhœa, and in the diarrhœa of phthisis. It is said also to check salivation and the night sweats of phthisis.

DOSE.—$\frac{1}{2}$ to 2 gr. every two or three hours in mucilage or syrup. A solution of 1 part in 4 of acetic ether is recommended for hypodermic injection. Tincture of coto bark may be used in doses of 10 min.

Paracoto Bark. Not officinal. Contains an alkaloid, paracotoin, similar in its actions and uses to cotoin, but less powerful.

Camphora, B. and U.S.P. CAMPHOR.—A concrete volatile oil (stearoptin, U.S.P.), obtained from the wood of *Cinnamomum camphora*, U.S.P., *Camphora officinarum*, B.P. Imported in the crude state from China and Japan, and purified by sublimation.

CHARACTERS.—White, translucent, tough, and crystalline; has a powerful penetrating odour, and a pungent taste followed by a sensation of cold; floats on water; volatilises slowly at ordinary temperatures; is slightly soluble in water, but readily soluble in rectified spirit and in ether.

COMPOSITION.—A stearoptin having the formula $C_{10}H_{16}O$, and yielding camphoric acid on oxidation.

IMPURITIES.—Fixed salts.

TEST.—Sublimes entirely when heated.

PREPARATIONS CONTAINING CAMPHOR.

B.P.	DOSE.
Aqua Camphoræ (saturated aqueous solution)	1-2 fl. oz.
Linimentum Aconiti	
Linimentum Belladonnæ	
Linimentum Camphoræ	
Linimentum Camphoræ Compositum	
Linimentum Chloroformi	
Linimentum Hydrargyri	
Linimentum Iodi	
Linimentum Opii	
Linimentum Saponis	
Linimentum Sinapis Compositum	
Linimentum Terebinthinæ	
Linimentum Terebinthinæ Aceticum	
Spiritus Camphoræ (camphor 1, rectified spirit 10)	10-30 min.
Tinctura Camphoræ Composita (*vide* Opium)	15 min. to 1 fl. drm.
Unguentum Plumbi Subacetatis Compositum	
Unguentum Hydrargyri Compositum	(of camphor, 1-10 gr.)

U.S.P.	DOSE.
Aqua Camphoræ	1 fl. drm.
Linimentum Belladonnæ	
Linimentum Camphoræ	
Linimentum Chloroformi	
Linimentum Saponis	
Spiritus Camphoræ	5-10 min.
Tinctura Opii Camphorata	1-2 fl. drm.
Ceratum Camphoræ	

Aqua Camphoræ. CAMPHOR WATER, B. and U.S.P.—It is prepared according to the B.P. by tying small pieces of camphor in a muslin bag, which is kept immersed in water in a bottle. The U.S.P. directs camphor (8) to be dissolved in alcohol (16), and then added to cotton (16) After the alcohol has nearly evaporated the cotton is packed in a percolator, and distilled water poured on till 1000 parts are obtained.

Linimentum Camphoræ. LINIMENT OF CAMPHOR, B. and U.S.P.—Camphor 1, dissolved in olive oil 4, B.P. In the U.S.P. the proportions are the same, but cotton-seed oil is used instead of olive oil.

B.P. Linimentum Camphoræ Compositum. COMPOUND LINIMENT OF CAMPHOR.—Camphor, 2½ oz.; oil of lavender, 1 fl. dr.; strong solution of ammonia, 5 fl. oz.; rectified spirit, 15 fl. oz.

U.S.P. Ceratum Camphoræ. CAMPHOR CERATE.—Camphor liniment, 3; olive oil, 12; cerates, 85.

PHYSIOLOGICAL ACTION.—**Externally** camphor is **stimulant** and rubefacient.

Internally in small doses it acts as a carminative, in large doses as an **irritant,** causing nausea and vomiting. It is **diaphoretic** and **antaphrodisiac,** and **stimulates** the **heart** (pp. 274 and 276). It stimulates the circulation, but may slow the pulse; and stimulates the **nerve-centres,** causing exhilaration, but finally paralyses them, causing lassitude. It produces, in large doses, a form of **delirium,** and sometimes death, occasionally preceded by **epileptiform convulsions** and maniacal excitement. In small doses it is said to be aphrodisiac, and in large doses antaphrodisiac (p. 396). It lowers the **temperature.**

THERAPEUTICS.—**Externally,** in the form of liniment, it is applied to sprains, enlarged joints, &c.

Inhalation of its vapour (½-1 dr. in ½ pint hot water) has been recommended for coryza.

Internally it is used in catarrh and coryza. It is very useful in summer diarrhœa, cholera, tympanitic distension of the abdomen, and hysterical vomiting.

It is also used as a nervine stimulant, especially in debility of the respiratory organs; as a nervine and cardiac stimulant in fever; and as an antispasmodic in epilepsy, chorea, pertussis, hysteria, and other nervous affections, especially those connected with the sexual organs.

U.S.P. Camphora Monobromata. MONOBROMATED CAMPHOR.—$C_{10}H_{15}BrO$; 230·8.

PREPARATION.—By heating camphor with bromine and crystallising from petroleum benzin.

CHARACTERS.—Colourless, prismatic needles or scales, permanent in air, unaffected by light, having a mild camphoraceous odour and taste, and a neutral reaction. Almost insoluble in water, freely soluble in alcohol, ether, chloroform, hot benzin, and fixed oils; slightly soluble in glycerine.

DOSE.—2 to 10 grains. It may be given in pills, made by rubbing 5 grains with 1 grain of Canada balsam in a warm mortar.

ACTION.—Like other bromides it produces weakness and paralysis, stupor and sleep. It slows the pulse (p. 276) and respiration and reduces the temperature. In the rabbit the vessels of the eye and ear are contracted. When given for a length of time it produces marked emaciation.

USES.—Monobromated camphor has been used as a **sedative** instead of the bromides, but it is less efficient. It has been recommended in insomnia, chorea, hysteria, and delirum tremens. In large doses it has caused epileptiform convulsions, like camphor.

B.P. Sassafras Radix. SASSAFRAS ROOT.—The dried root of *Sassafras officinalis*. From North America.

CHARACTERS.—In branched pieces; bark externally greyish-brown, internally rusty-brown, of an agreeable odour, and a peculiar aromatic warm taste; wood light, porous, greyish-yellow. Also in chips, resembling quassia, but browner, and distinguished by their smell.

COMPOSITION.—Contains 1 to 2 per cent. of a volatile oil. The bark contains tannic acid to a small extent.

PREPARATION.

B.P.	DOSE.
Decoctum Sarsæ Compositum.....¼ oz. to 1 pint	...2-10 fl. oz. (of the oil, 1-5 min.)

U.S.P. Sassafras. SASSAFRAS.

The bark of the root of *Sassafras officinalis*.

CHARACTERS.—In irregular fragments, deprived of the grey, corky layer; bright rust-brown, soft, fragile, with a short, corky fracture; strongly fragrant; sweetish, aromatic, and somewhat astringent.

U.S.P. Oleum Sassafras. OIL OF SASSAFRAS.—A volatile oil distilled from sassafras.

CHARACTERS.—A colourless or yellowish liquid becoming darker and thicker by age and exposure to air, having the characteristic odour of sassafras, a warm, aromatic taste, and a neutral reaction, sp. gr. about 1·090. It is readily soluble in alcohol. When treated with cold nitric acid it becomes dark red, and is finally converted into a red resin.

PREPARATIONS.

U.S.P.	DOSE.
Oleum Sassafras	1-5 min.
Decoctum Sarsaparillæ Compositum	4-6 fl. oz.
Extractum Sarsaparillæ Compositum Fluidum	30-60 min.
Syrupus Sarsaparillæ Compositus	1-4 fl. drm.

ACTION AND USE.—Sassafras has a destructive action on infusoria (p. 49). It is a stimulant **diaphoretic,** and is used in rheumatism and syphilis, generally in combination with other drugs.

U.S.P. Sassafras Medulla. SASSAFRAS PITH.—The pith of *Sassafras officinalis.*

CHARACTERS.—In slender cylindrical pieces, often curved or coiled, light, spongy, white, inodorous, insipid. Macerated in water it forms a mucilaginous liquid, which is not precipitated on the addition of alcohol.

PREPARATION.

	DOSE.
Mucilago Sassafras Medullæ (sassafras pith, 2 parts ; water, 100 parts)	...Ad libitum.

USES.—As a **demulcent** either internally or externally.

B.P. Nectandræ Cortex. BEBEERU BARK.—The bark of *Nectandra Rodiæi*, the green-heart tree. Imported from British Guiana.

CHARACTERS.—In large flat heavy pieces. External colour greyish-brown, internal dark cinnamon-brown. Taste strongly and persistently bitter, with considerable astringency.

COMPOSITION.—Contains beberine, a peculiar alkaloid. Beberine is a colourless, amorphous substance, soluble in alcohol, but sparingly soluble in boiling water.

PREPARATION.

B.P.	DOSE.	U.S.P.
Beberiæ Sulphas	1-10 gr.	None.

B.P. Beberiæ Sulphas. SULPHATE OF BEBERIA. $C_{35}H_{40}N_2O_6.H_2SO_4$.—The sulphate of an alkaloid prepared from Nectandra or Bebeeru bark.

PROPERTIES.—In dark-brown, thin, translucent scales, yellow when in powder, with a strong bitter taste, soluble in water and in alcohol.

REACTIONS.—Its watery solution gives a white precipitate with chloride of barium (sulphate) ; and with caustic soda a yellowish-white precipitate, which is dissolved by agitating the mixture with twice its volume of ether (beberia).

IMPURITIES.—Mineral matter.

TESTS.—The ethereal solution, separated by a pipette and evaporated, leaves a yellow translucent residue, entirely soluble in dilute acids. It is entirely destructible by heat. Water forms with it a clear brown solution.

ACTION AND USES.—Bebeeru bark is seldom used in medicine ; both it and the sulphate of beberia are said to have a similar action to quinine, and have been used as **tonics** and **antiperiodics,** but sulphate of beberia is but a poor substitute for the cinchona alkaloids.

ARISTOLOCHIACEÆ.

Serpentariæ Radix, B.P.; Serpentaria, U.S.P. SERPENTARY ROOT, B.P.; SERPENTARIA, U.S.P.—The dried rhizome of *Aristolochia Serpentaria*. From the southern parts of North America.



FIG. 179.—Serpentary.

CHARACTERS.—A small roundish rhizome, with a tuft of numerous slender rootlets, about three inches long, yellowish, of an agreeable camphoraceous odour, and a warm bitter camphoraceous taste.

COMPOSITION.—An essential oil, and resin, tannin, and sugar.

ADULTERATION.—Other roots fraudulently or inadvertently added, distinguished by appearance and smell.

PREPARATIONS.

B.P.	DOSE.
Infusum Serpentariæ (¼ oz. to ½ pint)	1-2 fl. oz.
Tinctura Cinchonæ Composita	½-2 fl. drm.
Tinctura Serpentariæ	½-2 fl. drm.

U.S.P.	DOSE.
Extractum Serpentariæ Fluidum	10-30 min.
Tinctura Cinchonæ Composita	1-4 fl. drm.
Tinctura Serpentariæ	1-3 fl. drm.

ACTION AND USES.—Serpentary is a stimulant **tonic,** and is used in atonic dyspepsia with nervous depression. Owing to its having some **diaphoretic** and **diuretic** properties, it is used in chronic rheumatism.

ASARUM EUROPÆUM or ASARABACCA belongs to this order; its leaves were formerly used as an errhine. They cause powerful vomiting and purging when administered internally.

SANTALACEA.

U.S.P. Oleum Santali. OIL OF SANTAL (Oil of sandal wood).

A volatile oil distilled from the wood of *Santalum album*.

CHARACTERS.—A pale yellowish or yellow liquid of a peculiar strongly aromatic odour, a pungent and spicy taste, and a slightly acid reaction. It is readily soluble in alcohol.

ACTION AND USES.—Its action and uses are **similar** to those of **copaiba,** than which its smell is less disagreeable.

DOSE.—10 to 20 min. in capsules or mixture.

EUPHORBIACEÆ.

Cascarillæ Cortex, B.P.; Cascarilla, U.S.P. CASCARILLA BARK, B.P.; CASCARILLA, U.S.P.—The bark of *Croton Eluteria*. Bahama Islands.

FIG. 180.—Cascarilla.

CHARACTERS.—In quills, two or three inches in length and about $\frac{1}{6}$ to $\frac{1}{2}$ inch in diameter, dull brown, but more or less coated with white crustaceous lichens; breaks with a short resinous fracture; is warm and bitter to the taste; and emits a fragrant odour when burned.

COMPOSITION.—The active principle is cascarillin, a bitter substance, soluble in hot spirit or ether. Resin, gum, and a small quantity of volatile oil are also present.

PREPARATIONS.

B.P.	DOSE.
Infusum Cascarillæ (1 oz. to ½ pint)	1-2 fl. oz.
Tinctura Cascarillæ	½-2 fl. drm.
U.S.P.	**DOSE.**
Cascarilla	30 gr.

ACTION AND USES.—Cascarilla is aromatic, **stimulant,** and **tonic.** It is also a stimulant to the mucous membranes, and is used as an **expectorant** in chronic bronchitis. It is useful in atonic dyspepsia and as a general tonic to the system.

U.S.P. Stillingia. STILLINGIA. QUEEN'S ROOT.—The root of *Stillingia sylvatica.*

CHARACTERS.—About twelve inches (30 centimetres) long, and nearly two inches (5 centimetres) thick, sub-cylindrical, slightly branched, compact, wrinkled, tough, greyish-brown, breaking with a fibrous fracture, showing a thick bark and porous wood, the inner bark and medullary rays with numerous yellowish-brown resin-cells; odour peculiar, unpleasant; taste bitter, acrid, pungent.

PREPARATION.

	DOSE.
Extractum Stillingiæ Fluidum	15-30 min.

COMPOSITION.—It contains a resinous substance.

USES.—In large doses it causes vomiting and purging. It has been used as an **alterative** in secondary syphilis and cutaneous diseases.



FIG. 181.—Croton Oil Seeds.

Oleum Crotonis, B.P.; Oleum Tiglii, U.S.P. CROTON OIL.—A fixed oil expressed from the seeds of *Croton Tiglium.* East Indies.

CHARACTERS.—Slightly viscid; colour brownish-yellow, taste acrid, odour faintly nauseous.

COMPOSITION.—Very complex. It contains several fatty acids. Its active principles have not yet been separated. An oily substance named crotonal is said to possess the irritant properties of croton oil.

DOSE.—Of the oil $\frac{1}{3}$-1 min. placed on the tongue, or formed into a pill with crumb of bread. As an adjunct $\frac{1}{12}$ min. upwards.

B.P.	PREPARATION.
Linimentum Crotonis	1 volume in 8.

PHYSIOLOGICAL ACTION.—**Externally** it is an irritant and gives rise to a pustular eruption. This effect is increased by the addition of an alkali.

Internally it is a violent purgative, causing great congestion of the intestinal canal, and may cause death from gastro-enteritis with collapse.

THERAPEUTICS.—**Externally** it is used as a counter-irritant in phthisis, bronchitis, inflammation of the brain and its membranes, and inflammation of the ovary, in the form of the liniment.

Internally it is given as a **purgative** in obstinate constipation ($\frac{1}{2}$-1 min. in pill). It is especially useful in paralysis, mania, and apoplexy, when there is a difficulty in swallowing and a purgative of small bulk is required. It can be mixed with a little bread-crumb, and placed on the back of the tongue and will be swallowed involuntarily. It is sometimes added to castor oil to increase its effect.

One drop of croton oil with 1 drachm of chloroform in 1 ounce of glycerine has proved an effectual anthelmintic, removing tape-worm after other remedies had failed. It should be given the first thing in the morning, and its efficacy is increased by a saline purgative given overnight.

TREATMENT IN POISONING.—Evacuate by stomach-pump after giving demulcents (linseed, oatmeal, &c.), or give linseed-tea or gruel, mixed with mustard, and thus procure emesis.

Oleum Ricini, B. and U.S.P. CASTOR OIL.—A fixed oil expressed from the seeds of *Ricinus communis*. Calcutta.



FIG. 182.—Castor Oil Seeds.

CHARACTERS.—Viscid, colourless, or pale straw-yellow, having a slightly nauseous odour, and a somewhat acrid taste.

B.P.	PREPARATIONS.	DOSE.
Collodium Flexile		For external use.
Linimentum Sinapis Compositum		do.
Pilula Hydrargyri Subchloridi Composita		5-10 gr.
		(of the oil, 1 fl. drm. to 1 fl. oz.)

PREPARATIONS—(*continued*).

U.S.P.	DOSE.
Linimentum Sinapis Compositum	For external use.
Collodium Flexile	do.

COMPOSITION.—Yields several fatty acids, including ricinoleic acid, peculiar to castor oil. The seeds contain an alkaloid, ricinine (not purgative), also an acid drastic principle, of which only a small proportion is separated with the oil.

DOSE.—1 to 8 fl. dr.

ACTION AND USES.—Castor oil is one of our best **purgatives,** as it leaves no injurious effects, and can be given whenever purging is wanted without any irritant effect, as in children, pregnant women, piles and fissure of anus, or after parturition, and to delicate people. Its nauseous taste is its only objection. It is one of the best remedies for acute diarrhœa, given in one dose of ¼ to ½ fl. oz. with 5-10 min. of laudanum. This removes any irritating substances (p. 338) and soothes the intestine. In chronic dysentery 15 min. castor oil and 5-10 min. tincture of opium given three times a day is a useful remedy. In lead colic it acts as a preventive to constipation, and has been used as a cure (p. 629). It is better, however, to give potassium iodide and sulphate of magnesia. A drop of castor oil dropped into the eye will often allay the irritation produced by a particle of sand, &c. As a local application, castor oil or poultices of the leaves of the castor-oil plant, are used to the breasts in order to promote the secretions of milk.

ADMINISTRATION.—If the oil be given the first thing in the morning an hour before breakfast, ten or twenty drops are generally sufficient to open the bowels. This dose may be given in a teaspoonful of peppermint-water or brandy. The brandy should be added in such proportion that the oil neither sinks nor swims in the mixture. The same mixture of peppermint-water and brandy answers well as a vehicle for the administration of larger doses also. In all cases the glass, cup, or spoon, should be thoroughly wetted first with water or peppermint water to prevent the oil adhering to the side. A little brandy is then to be mixed with the peppermint water, the oil carefully poured over the middle of it, and then more brandy added. If the whole be drunk at one draught the taste of the oil is not perceived. Lemon juice, coffee, and the froth of porter are also used as vehicles for the administration of castor oil. It may also be given in capsules, which are perfectly tasteless.

Kamala, B. and U.S.P. KAMALA. WURRUS.—A powder which consists of the minute glands that cover the capsules of *Rottlera tinctoria,* B.P., *Mallotus philippinensis,* U.S.P. India.

CHARACTERS.—A fine granular mobile powder, of a brick-red colour; it is with difficulty mixed with water.

COMPOSITION.—A resin soluble in alcohol and ether, yielding a crystalline substance, rottlerin.

IMPURITIES.—Sand and earthy matters.

TEST.—When boiled with alcohol the greater part is dissolved, forming a red solution. Ether dissolves most of it; the residue consisting principally of tufted hairs.

DOSE.—30 grains to $\frac{1}{4}$ ounce.

ACTION AND USES.—It is used as an **anthelmintic** against tapeworm. It is very efficacious, killing the worm and producing free purgation. It is best given with honey or thick gruel.

PIPERACEÆ.

Piper Nigrum, B.P.; Piper, U.S.P. BLACK PEPPER.—The dried unripe berries of *Piper nigrum*, B.P. The unripe fruit of *Piper nigrum*, U.S.P. East Indies.

CHARACTERS.—Small, roundish, wrinkled; tegument brownish-black, containing a greyish-yellow globular seed. Odour aromatic. Taste pungent and bitterish.

DOSE.—5 to 20 grains.

PREPARATIONS.

B.P.	DOSE.
Confectio Opii	5-20 gr.
Confectio Piperis (pepper 2, caraway 3, honey 15)	60-120 gr. or more
Pulvis Opii Compositus	2-5 gr.

U.S.P.	DOSE.
Oleoresina Piperis	1-2 min.

B.P. Confectio Piperis. CONFECTION OF PEPPER.—Black pepper, 2; caraway fruit, 3; clarified honey, 15.

U.S.P. Oleoresina Piperis. OLEORESIN OF PEPPER.—Exhaust pepper with stronger ether, remove the ether by distillation and evaporation, and separate the oleoresin from the piperine in the residue by expression through a muslin strainer.

COMPOSITION.—Piperine, resin, and volatile oil. Piperine is a crystalline principle, almost neutral, tasteless, inodorous, and insoluble in water, and is isomeric with morphia. The resin possesses the pungent taste of the drug, and gives the oil its aromatic smell.

U.S.P. Piperina. PIPERINE. $C_{17}H_{19}NO_3$; 285.—A proximate principle of feebly alkaloidal power, prepared from pepper, and occurring also in other plants of the Nat. Ord. *Piperaceæ*.

CHARACTERS.—Colourless, or pale yellowish, shining, four-sided prisms, permanent in the air, odourless and almost tasteless when first put in the mouth, but on prolonged contact producing a sharp and biting sensation. It has a neutral reaction, is almost insoluble in water, but soluble in 30 parts of alcohol at 15° C. (59° F.), in 1 part of boiling alcohol, and but slightly soluble in ether. When heated to about 128° C. (about 262° F.), piperine melts, yielding a clear, yellowish liquid, which, on cooling, congeals to a resinous mass. When heated on platinum foil, it takes fire and is consumed without residue. Concentrated sulphuric acid dissolves piperine with a dark, blood-red colour, which disappears on dilution with water. When treated with cold nitric acid, piperine turns

rapidly greenish-yellow, orange, and red, and gradually dissolves with a reddish colour. On adding to this solution an excess of solution of potassa, the colour is at first pale yellow, but on boiling it deepens to blood-red, while, at the same time, vapours of an alkaline reaction and of a peculiar odour (piperidine) are given off.

DOSE.—1 to 10 grains.

ACTION AND USES.—Pepper is a stimulant **stomachic.** It is used chiefly as a condiment, but has been employed in the treatment of hæmorrhoids, and, on account of its stimulating action on mucous membranes, as a substitute for cubebs in the treatment of **gonorrhœa.** The action and uses of piperine are similar to those of pepper.

Cubeba, B. and U.S.P. CUBEBS.—The dried unripe fruit of *Cubeba officinalis* (*Piper Cubeba*). Java.

FIG. 183.—Cubebs.

CHARACTERS.—Is like black pepper, but is distinguished from it by the adherent stalk of rather more than its own length, from which it gets its ordinary name of tailed pepper. It has a warm camphoraceous taste and characteristic odour.

COMPOSITION.—A volatile oil, a resin, and cubebin. Cubebin is neutral and crystalline. It does not seem to have any important physiological action. The resin yields cubebic acid, and a volatile oil consisting of a hydrocarbon holding a camphor in solution.

PREPARATIONS.

B.P.	DOSE.
Oleum Cubebæ	5-20 min.
Tinctura Cubebæ	½-2 fl. drm. (of the powder, 30-120 gr.)

U.S.P.	DOSE.
Cubeba	15 gr.
Extractum Cubebæ Fluidum	8-30 min.
Oleoresina Cubebæ	5-30 min.
Tinctura Cubebæ	8 min. to 3 fl. drm.
Trochisci Cubebæ (each contains ½ gr. oleoresin).	

Oleum Cubebæ, B. and U.S.P. OIL OF CUBEBS.—A volatile oil distilled from cubebs.

CHARACTERS.—Colourless or pale greenish-yellow, having the peculiar odour and taste of cubebs.

COMPOSITION.—A hydrocarbon holding a camphor in solution.

U.S.P. Oleoresina Cubebæ. OLEORESIN OF CUBEB.

PREPARATION.—By extracting cubeb with stronger ether, distilling off most of the ether; letting the rest evaporate; transferring the residue to a closed vessel till waxy and crystalline matter has ceased to deposit, and then pouring off the oleoresin.

DOSE.—5 to 30 min. (0·3 to 2 Gm.) given in capsules.

ACTION AND USES.—Cubebs owes its action to the oil and resin. It is carminative and **stimulant** to mucous membranes. It is used chiefly for its action on the mucous membrane of the bladder and urethra, as in gonorrhœa (p. 392). It is used in the form of lozenges for relaxed sore-throat, and as an errhine for coryza when free secretion has become established. It is slightly diuretic, and has been used as an adjunct to other diuretics. Large doses may produce gastro-enteritis, and it sometimes gives rise to a rash resembling urticaria. The oil has an action somewhat like oil of turpentine or oil of copaiba. The resin is said to be a more active **diuretic** than the oil, and the oleoresin is therefore introduced into the U.S.P.

Maticæ Folia. MATICO LEAVES, **B.P.; Matico,** MATICO, **U.S.P.**—The dried leaves of *Artanthe elongata* (*Piper angustifolium*). Peru.

CHARACTERS.—From two to eight inches long, veined and tesselated on the upper surface, downy beneath. They may be confounded with digitalis leaves, but are distinguished by their marked reticulation in squares.

COMPOSITION.—Essential oil, artanthic acid, tannin, and resin.

PREPARATIONS.

B.P.	DOSE.
Infusum Maticæ (½ oz. in ½ pint for ½ hour)	1-4 fl. oz. (of the powder, 30-60 gr.)

U.S.P.	DOSE.
Extractum Matico Fluidum	½-3 fl. drm.
Tinctura Matico	½-3 fl. oz.

ACTION AND USES.—Matico is employed locally as a **styptic** to arrest hæmorrhage from small wounds, such as leech-bites. It acts mechanically, much in the same way as a spider's web. It has been administered in cases of vesical catarrh and gonorrhœa, but is now not much used.

SALICACEÆ.

U.S.P. Salix. SALIX. WILLOW.—The bark of *Salix alba*, and of other species of *Salix*.

CHARACTERS.—In fragments or quills, from one-twenty-fifth to one-twelfth of an inch (1 to 2 millimetres) thick, smooth; outer surface somewhat glossy, brownish or yellowish, more or less finely warty; under the corky layer, green; inner surface brownish-white, smooth, the liber separating in thin layers; inodorous; bitter and astringent.

COMPOSITION.—It contains tannin and salicine.

USE.—The infusion may be used as a bitter tonic.

U.S.P. Salicinum. SALICIN. $C_{13}H_{18}O_7$; 286.—A neutral principle prepared from the bark of *Salix helix*, and of other species of *Salix*.

CHARACTERS.—Colourless or white, silky, shining crystals, permanent in the air, odourless, having a very bitter taste, and a neutral reaction. Soluble in 28 parts of water, and in 30 parts of alcohol at 15° C. (59° F.); in 0·7 part of boiling water, and in 2 parts of boiling alcohol; insoluble in ether or chloroform. When heated to about 198° C. (388°·4 F.), salicin melts, yielding a colourless liquid, and, on ignition, it emits vapours having the odour of salicylous acid, and is finally wholly dissipated. If 1 part of salicin be agitated with 20 parts of water and 5 parts of solution of potassa, a clear, colourless solution is obtained. Cold, concentrated sulphuric acid dissolves it with a red colour; the solution, after the addition of water, becomes colourless and deposits a dark red powder insoluble in water or alcohol.

The aqueous solution of salicin should not be precipitated by tannic or picric acids, nor by iodide of mercury and potassium (abs. of and difference from alkaloids).

DOSE.—3 to 15 grains.

ACTION.—Its action is similar to that of salicylic acid (p. 740). It appears to be decomposed in the body, and is eliminated in the urine partly as salicin and partly as salicylic acid, as salicyluric acid, and as saligenin. Its action is less powerful than that of salicylic acid, and its depressing effect on the circulation less marked.

USES.—It is an **antipyretic,** and has been used with success instead of salicylic acid in the treatment of acute rheumatism. It is useful also in headaches.

JUGLANDACEÆ.

U.S.P. Juglans. JUGLANS. BUTTERNUT.—The inner bark of the root of *Juglans cinerea,* collected in autumn.

CHARACTERS.—In flat or curved pieces, from an eighth to a quarter of an inch (3 to 6 millimetres) thick; the outer surface nearly free from soft cork; deep brown; the inner surface smooth and striate; transverse fracture short, delicately checkered, whitish and brown; odour feeble; taste bitter and somewhat acrid.

PREPARATION.	DOSE.
Extractum Juglandis	20-30 gr.

USES.—It is a mild **cathartic,** especially useful in the treatment of chronic constipation, dysentery, and congestion of the abdominal viscera. It has a slight action as a **hepatic stimulant** (p. 353), and is useful in malarial conditions (pp. 326 and 356).

HAMAMELACEÆ.

U.S.P. Hamamelis. HAMAMELIS. WITCH-HAZEL.—The leaves of *Hamamelis virginica*, collected in autumn.

CHARACTERS.—Short-petiolate, about four inches (10 centimetres) long, obovate or oval, slightly heart-shaped and oblique at the base, sinuate-toothed, nearly smooth; inodorous; taste astringent and bitter.

OFFICINAL PREPARATION.

	DOSE.
Extractum Hamamelidis Fluidum	15 min. to 2 fl. drm.

COMPOSITION.—It contains tannic acid and a bitter principle.

USES.—It is used as an external application to piles, bruises, and inflammatory swellings. Internally it is a very efficient **hæmostatic** in bleeding from the lungs and other internal organs. In some cases of hæmoptysis I have found it more efficient than digitalis and ergot, although in other cases digitalis and ergot have succeeded better. It checks the flow in menorrhagia when given during the period, and it lessens pain in **dysmenorrhœa.** In one case a patient informed me that it invariably caused seminal emissions, which ceased when it was discontinued. In this action it resembles strychnine (p. 395). It has been supposed by Dujardin-Beaumetz to owe its utility to an action on the muscular fibre of veins.

BALSAMIFLUÆ.

Styrax Præparatus, B.P.; Styrax, U.S.P. PREPARED STORAX, B.P.; STORAX, U.S.P.—A balsam obtained from the inner bark of *Liquidambar orientale* (B.P.), *Liquidambar orientalis* (U.S.P.). Purified by means of rectified spirit and straining.

CHARACTERS.—A semi-transparent brownish-yellow semi-fluid resin, of the consistence of thick honey, with a strong agreeable fragrance and aromatic bland taste. Heated in a test-tube on the vapour-bath, it becomes more liquid but gives off no moisture; boiled with solution of bichromate of potash and sulphuric acid, it evolves the odour of oil of bitter almonds.

COMPOSITION.—Styrol, cinnamic acid, styracin, and resin. Cinnamic acid yields, when oxidised, hydride of benzoyl (oil of bitter almonds).

PREPARATIONS.

B.P.	DOSE.
Tinctura Benzoini Composita	½-1 fl. drm. (of the prepared resin, 5-20 gr.)

U.S.P.	DOSE.
Tinctura Benzoini Composita	½-1 fl. drm.

USE.—Its action and use are **similar** to those of the **balsam of Peru.**

CUPULIFERÆ.

B.P. Quercûs Cortex. OAK BARK.—The dried bark of the small branches and young stems of *Quercus robur*. Collected in spring, from trees growing in Britain.

CHARACTERS.—Covered with a greyish shining epidermis, cinnamon-coloured on the inner surface, fibrous, brittle, and strongly astringent.

U.S.P. Quercus Alba.—The bark of *Quercus alba*.

CHARACTERS.—In nearly flat pieces, deprived of the corky layer, about a quarter of an inch thick, pale brown, inner surface with short sharp longitudinal ridges, tough, of a coarse, fibrous fracture, a faint, tan-like odour, and a strongly astringent taste.

COMPOSITION.—Querci-tannic acid and quercin, a bitter crystalline substance.

PREPARATION.

B.P.	DOSE.	U.S.P.
Decoctum Quercûs (1¼ oz. to 1 pint)	1-2 fl. oz.	None.

ACTION AND USE.—Chiefly used externally as a local **astringent,** *e.g.* as a gargle in relaxed sore-throat or as an injection in gonorrhœa and leucorrhœa.

Galla, B. and U.S.P. GALLS, B.P.; NUTGALLS, U.S.P.—Excrescences on *Quercus lusitanica*, var. *infectoria*, caused by the punctures and deposited ova of *Cynips Gallæ tinctoriæ*, U.S.P. (*Diplolepis Gallæ tinctoriæ*, B.P.). Asia Minor.

CHARACTERS.—Hard, heavy, globular bodies, tuberculated on the surface, the tubercles and intervening spaces smooth; of a bluish-green colour on the surface, yellowish-white within, with a small central cavity; intensely astringent.

COMPOSITION.—Gallo-tannic acid (14 to nearly 70 per cent. according to the quality of the galls), gallic acid (3 per cent.), free sugar and resin in minute quantities.

PREPARATIONS.

B.P.	DOSE.
Acidum Gallicum	2-20 gr.
Acidum Tannicum	2-30 gr.
Tinctura Gallæ	½-2 fl. drm.
Unguentum Gallæ (80 gr. to 1 oz.)	
Unguentum Gallæ cum Opio (80 gr. to 1 oz. nearly)	

U.S.P.	DOSE.
Tinctura Gallæ	½-3 fl. drm.
Unguentum Gallæ (1 part in 10)	

ACTION AND USES.—Galls are used in the form of galls and opium ointment as a local **astringent** in the treatment of hæmorrhoids. The action of galls depends on the contained tannic and gallic acids, *q.v.*

Acidum Tannicum, B. and U.S.P. TANNIC ACID. $C_{14}H_{10}O_9$; 322.—An acid extracted from galls.

PREPARATION.—By dissolving out the tannic acid from powdered galls with ether mixed with a very little water, gently evaporating the solution, and drying the acid. Although tannic acid is very sparingly soluble in pure ether, yet it appears to dissolve readily in ether containing a very little water.

PROPERTIES.—In pale yellow vesicular masses, or thin glistening scales, with a strongly astringent taste, and an acid reaction; readily soluble in water and rectified spirit, very sparingly soluble in ether.

REACTIONS.—The aqueous solution precipitates solution of gelatine yellowish-white, and the persalts of iron of a bluish-black colour.

IMPURITIES.—Mineral matter.

TESTS.—It leaves no residue when burned with free access of air on platinum foil.

PREPARATIONS.

B.P.

Glycerinum Acidi Tannici.
Suppositoria Acidi Tannici.
" " " cum Sapone.
Trochisci Acidi Tannici.

U.S.P.

Collodium Stypticum (tannic acid 20, alcohol 5, stronger ether 20, collodion 55 parts) .....1 part in 5.
Trochisci Acidi Tannici .....1 grain in each.
Unguentum Acidi Tannici (with benzoated lard).....1 part in 10.

PHYSIOLOGICAL ACTION.—When applied externally to the unbroken skin, tannic acid has little or no action; but applied to **skin deprived of its epidermis,** it coagulates the albumen and causes contraction of the cells of the skin.

It acts locally on **mucous membranes,** coagulating the mucus. On account of the dryness in the mouth produced by the drug it was concluded that the vessels are contracted, and that the astringent action is due to this, but Rossbach found from direct observation that the vessels are dilated; in this particular tannin differs from other astringents, such as nitrate of silver. This dilatation is not due to paralysis of the coats of the arteries, since they contract on stimulation or subsequent application of silver nitrate.

Its astringent action on the skin and mucous membranes is probably due to coagulation of albumen and a "tanning" of all the tissues to which it is applied.

When taken into the **mouth** it causes dryness, coagulation of mucus, and a partial paralysis of the ends of the sensory nerves (both the nerves of ordinary sensation and the special nerves of taste), so that it destroys to a great extent the sense of taste, and also lessens irritation in the throat.

When taken into the **stomach** in large doses it is irritant and causes vomiting. When given to animals it does not lessen either

secretion or peristaltic action of the intestines, and yet in man, even from small doses, there is a dryness of the fæces and lessened peristalsis; probably these different results are due to some imperfection in the experiments or to a difference of dose.

Large doses cause diarrhœa, with subsequent constipation.

It is absorbed into the **blood,** and passes out as gallic acid or some product of the oxidation of gallic acid.

It restrains hæmorrhage in distant organs, as the uterus, lungs, or **kidneys,** but the modus operandi is not known, and some authorities deny this action altogether.

USES.—**Externally** applied to the skin **tannic acid** is used in intertrigo, impetigo, and eczema, especially when occurring behind the ears in children.

It is also applied to mucous membranes, such as the external auditory meatus in otorrhœa (fill the meatus with glycerine of tannic acid and keep it there by a pledget of cotton wool). Also to the nasal mucous membrane, when there is ulceration and offensive discharge. In this case it is applied either in aqueous solution by means of the nasal douche or as glycerine of tannic acid with a brush. It is thus of use in ozæna after measles or scarlet fever, and in syphilitic children. In hæmorrhages from the nose dry tannin may be snuffed up.

It is used in stomatitis and ulceration of gums; and as a gargle in relaxed sore-throat or applied locally as glycerine of tannic acid. It is very useful in the hacking cough often met with in children, and also in adults, which is due to an irritation at the back of the pharynx, often accompanied by inflamed throat, covered with mucus; in inflamed tonsils and deafness; also in hooping-cough and other throat affections, either in the form of the glycerine or as lozenges.

It has been used, dissolved in water, or mixed with olive-oil, as an injection in leucorrhœa, gonorrhœa, and chronic discharges from the os uteri.

Internally tannin is used in hæmatemesis and intestinal hæmorrhage; also as an antidote to poisoning by alkaloids, but when used for this purpose it must be followed by a purgative, as the tannates are all more or less soluble in the juices of the alimentary canal. It is also used in poisoning by tartar emetic, as tannic acid forms with antimony an insoluble tannate. It is used in diarrhœa, but usually the more sparingly soluble forms of tannin such as kino are preferred. Tannic acid lessens the amount of albumen in albuminuria.

Acidum Gallicum, B. and U.S.P. GALLIC ACID. $H_3C_7H_3O_5$. H_2O; 188.—A crystalline acid prepared from galls.

PREPARATION.—From galls, by pulverising, moistening with water, and allowing them to ferment for six weeks in a temperature of 60° to 70°. The tannic acid present in the galls is split up

by the fermentation into gallic acid and glucose according to some authors. According to others the glucose is a mere impurity, and the tannic acid simply splits up into gallic acid, $C_{14}H_{10}O_9 + H_2O = 2C_7H_6O_5$. It is purified by solution, and re-solution in boiling water, filtering and crystallising.

PROPERTIES.—Crystalline, in acicular prisms or silky needles, nearly white, or of a pale fawn-colour. Its taste is acidulous and astringent. It requires about 100 parts of cold water for its solution, but dissolves in 3 parts of boiling water. Soluble also in rectified spirit.

REACTIONS.—It gives a bluish-black precipitate with a persalt of iron. It leaves no residue when burned with free access of air. Its aqueous solution gives no precipitate with solution of isinglass, and is thus distinguished from tannic acid.

IMPURITIES.—Tannic acid from imperfect fermentation.

TESTS.—No precipitate with solution of isinglass (no tannic acid).

DOSE.—2 to 10 grains.

PREPARATIONS.

B.P.	DOSE.
Glycerinum Acidi Gallici	12-60 min.

U.S.P.

Unguentum Acidi Gallici (with benzoated lard, 1 part in 10)

USES.—**Gallic acid** resembles tannic acid in its action, but does not coagulate albumen, and is used chiefly in cases of hæmorrhages from the lungs, or kidneys, or where the affected part can only be reached through the circulation.

In hæmoptysis it is useful in ten-grain doses every two hours. Like tannin it lessens the amount of albumen in the urine in albuminuria.

U.S.P. Castanea. CASTANEA. [CHESTNUT.]—The leaves of *Castanea vesca*, collected in September or October, while still green.

CHARACTERS.—From six to ten inches (15 to 25 centimetres) long, about two inches (5 centimetres) wide, petiolate, oblong-lanceolate, acuminate, mucronate, feather-veined, sinuate-serrate, smooth; having a slight odour, and a somewhat astringent taste.

PREPARATION.

	DOSE.
Extractum Castaneæ Fluidum	½-1 fl. drm.

USES.—It has been used in hooping-cough. Its taste is not disagreeable, but it has no extraordinary physiological power.

URTICACEÆ ULMEÆ (ULMACEÆ).

B.P. Ulmi Cortex. ELM BARK.—The dried inner bark of *Ulmus campestris* (broad-leaved elm). From trees indigenous to and cultivated in Britain.

CHARACTERS.—A tough brownish-yellow bark, about half a line thick, without smell; taste mucilaginous, slightly bitter and astringent. Its decoction is turned green by perchloride of iron, and precipitates with a solution of gelatine (tannin).

PREPARATION.

B.P.	DOSE.
Decoctum Ulmi (broad-leaved elm) 2½ oz. to 1 pint for 10 minutes	2-4 fl. oz.

U.S.P. Ulmus. ELM. SLIPPERY ELM.—The inner bark of *Ulmus fulva.*

CHARACTERS.—In flat pieces, varying in length and width, about one-eighth of an inch (3 millimetres) thick, tough, pale brownish-white, the inner surface finely ridged; fracture fibrous and mealy; the transverse section delicately checkered; odour slight, peculiar; taste mucilaginous, insipid.

PREPARATION.

U.S.P.	DOSE.
Mucilago Ulmi (slippery elm 6, boiling water 100, macerate for two hours and strain)	Ad libitum.

USES.—Elm bark is used as a **demulcent,** slight **astringent** and **tonic,** and in the treatment of skin diseases.

MOREÆ.

B.P. Mori Succus. MULBERRY JUICE.—The juice of the ripe fruit of *Morus nigra.*

CHARACTERS.—Of a dark violet colour, with a faint odour, and an acidulous sweet taste.

COMPOSITION.—Colouring matter, sugar, and acid, supposed to be malic.

PREPARATION.

B.P.	DOSE.
Syrupus Mori	1 fl. drm. or more.

USE.—To flavour and colour mixtures.

ARTOCARPEÆ.

Ficus, B.P. FIG.—The dried fruit of *Ficus Carica,* B.P. Smyrna.

Ficus, U.S.P. FIG.—The fleshy receptacle of *Ficus Carica,* bearing fruit upon its inner surface.

CHARACTERS.—Compressed, of irregular shape, fleshy, covered with an efflorescence of sugar; of a sweet, fruity odour, and a very sweet, mucilaginous taste. When softened in water, figs are pear-shaped, with a scar or short stalk at the base, and a small scaly orifice at the apex; hollow internally; the inner surface covered with numerous, yellowish, hard achenes.

COMPOSITION.—Grape sugar (about 70 per cent.), a little gum, and fatty matter.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Sennæ	60-120 gr.	Confectio Sennæ	60-120 gr.

USE.—Figs are used locally as poultices, by splitting them and applying them to the inflamed part, as in gum-boils, dental abscesses, &c.

Figs are chiefly employed as a domestic laxative. They are useful, given in large quantities, when a person has swallowed a hard sharp substance, by forming a bulky mass which will sheath the substance and protect the intestines from injury. In such cases purgatives are to be avoided.

CANNABINEÆ.

Cannabis Indica, B. and U.S.P. INDIAN HEMP.—The dried flowering tops of the female plants of *Cannabis sativa*, the common hemp. (For medicinal use that which is grown in India, and from which the resin has not been removed, is alone to be employed, B.P.) The flowering tops of the female plant of *Cannabis sativa*, grown in the East Indies, U.S.P.

CHARACTERS.—Tops consisting of one or more alternate branches, bearing the remains of the flowers and smaller leaves and a few ripe fruits, pressed together in masses of a dusky green colour and a characteristic odour.

PREPARATIONS.

B.P.	DOSE.
Extractum Cannabis Indicæ	¼-1 gr. or more.
Tinctura Cannabis Indicæ	5-20 min.

U.S.P.	DOSE.
Extractum Cannabis Indicæ Fluidum	5-10 min.
Tinctura Cannabis Indicæ	10-20 min.
Extractum Cannabis Indicæ	⅓ gr.

U.S.P. Cannabis Americana. AMERICAN CANNABIS.—*Cannabis sativa*, grown in the Southern United States and collected while flowering.

CHARACTERS.—Stem about six feet (2 metres) long, rough; leaves opposite below, alternate above, petiolate, digitate; the leaflets linear-lanceolate, serrate; dicœcious, the staminate flowers in pedunculate clusters forming compound racemes; the pistillate flowers axillary, sessile, and bracteate; odour heavy; taste bitter, slightly acrid.

COMPOSITION.—The active constituent is a resinoid substance, cannabin. The tops also contain a small quantity of volatile oil.

PHYSIOLOGICAL ACTION.—Its chief effect is on the brain, and is of a twofold nature; it excites a form of delirium and hallucinations, usually followed by deep sleep.

Small doses give rise to delirium with hallucinations, generally of a gay character, causing much merriment; accompanied by a great inclination to muscular movement.

The nature of the hallucinations depends greatly on the character of the individual, and people seem to be able to determine their nature, as in the case of opium.

Haschish is an Arabian preparation of Indian hemp, and is the origin of the word assassin. An Eastern chief used to dose his fanatic followers with Indian hemp, and they became imbued with the idea that they would be taken to heaven if killed, and hence were not afraid to encounter death.

The dreams produced by Indian hemp in inhabitants of Eastern countries are usually of a sexual character (p. 395), but when taken by the more civilised people of Western nations they are not sexual, and are often of a disagreeable nature.

During this stage of hallucination, the person may conduct himself rationally and answer clearly any question put to him (Wood). The drug produces in some persons a curious loss of sense of time and of space. This stage is generally followed by deep sleep. The **sensory nerves** are benumbed, and there is frequently tingling and partial anæsthesia. The **pupil** is dilated.

Respiration may be either quickened or slowed. Its action on the **pulse** is very uncertain. Usually it is first quickened, then slowed, sometimes *vice versâ*. The **temperature** rises or sinks according as the drug produces muscular movement or sleep. The **urine** is increased. The processes of **digestion** are less altered by cannabis indica than by opium, and the after effects of opium (nausea, headache, &c.) are not produced.

THERAPEUTICS.—**As a soporific** it is used instead of opium when the latter does not agree, or in old opium-eaters; also in cases of mental derangement; in acute and chronic mania it is very useful, especially when combined with potassium bromide.

It has been used in neuralgia to lessen pain; also in spasmodic coughs, asthma, &c. In certain cases of menorrhagia it is useful, but its mode of action is unknown. Ringer recommends it in migraine, with or without nausea.

B.P. Lupulus. HOP.—The dried strobiles of the female plant of *Humulus lupulus*. Cultivated in England.

CHARACTERS.—Strobiles of a greenish-yellow colour, with minute yellow grains (lupuline) adherent to the base of the scales. Odour aromatic, taste bitter.

U.S.P. Humulus. HOP.—The strobiles of *Humulus lupulus*.

CHARACTERS.—Ovate, about an inch and a quarter (3 centimetres) long, consisting of a thin, hairy, undulated axis, and many obliquely ovate, membranous, greenish scales, in the upper part reticulately veined, and toward the base parallel-veined, glandular

and surrounding a subglobular achene; odour aromatic; taste bitter, aromatic, and slightly astringent.

U.S.P. Lupulinum. LUPULIN.—The glandular powder, separated from the strobiles of *Humulus lupulus*.

CHARACTERS.—Bright brownish-yellow, becoming yellowish-brown, resinous, consisting of minute granules which, as seen under the microscope, are subglobular, or rather hood-shaped, and reticulate; aromatic and bitter.

When agitated with water and allowed to stand, no considerable sediment (sand, &c.) should be deposited. When ignited, lupulin should not leave more than 8 per cent. of ash.

COMPOSITION.—The lupulin of hops consists of a bitter principle, lupulite, volatile oil, to which the odour of hops is due, and resin. Hops apart from the grains contain a kind of tannin.

DOSE.—5 to 20 grains or more (·3-1·3 Gm.).

PREPARATIONS.

B.P.	DOSE.
Extractum Lupuli	5-10 gr.
Infusum Lupuli	1-2 fl. oz.
Tinctura Lupuli	½-2 fl. drm.

U.S.P.	DOSE.
Of HUMULUS—	
Tinctura Humuli	1-3 fl. drm.
Of LUPULINUM—	
Extractum Lupulini Fluidum	10-30 min.
Oleoresina Lupulini	2-20 gr.

ACTION AND USE.—Hops are bitter **tonic** and **stomachic,** also slightly **soporific.** In the form of bitter beer they are used in some cases of atonic dyspepsia; and a supper of beer and lettuce, with bread and butter, is markedly soporific, from the combined effect of the hops and lettuce.

A hop-pillow is sometimes used in sleeplessness of fevers, but its use is probably due, not to the action of the volatile principle of the hops, but to the mechanical elasticity and softness of the pillow. The crackling of the leaves in this pillow may be stopped by sprinkling a little alcohol on them.

CHAPTER XXXV.

Class EXOGENS. Division 2, GYMNOSPERMS.

CONIFERÆ.

Terebinthina Canadensis, B. and U.S.P. CANADA BALSAM, B.P.; CANADA TURPENTINE (BALSAM OF FIR), U.S.P.—The turpentine obtained by incision from the stem of *Abies balsamea* (*Pinus balsamea*). Balm of Gilead Fir, B.P. A liquid oleoresin, obtained from *Abies balsamea*, U.S.P. Canada.

CHARACTERS.—A pale-yellow ductile oleoresin of the consistence of thin honey, with a peculiar agreeable odour, and a slightly bitter feebly acrid taste.

COMPOSITION.—An essential oil resembling oil of turpentine, and a resin.

DOSE.—10 to 30 grains.

PREPARATIONS.

B.P.	U.S.P.
Charta Epispastica.	Collodium Flexile.
Collodium Flexile.	

USES.—Used in the preparation of collodion flexile and of charta epispastica; also to mount microscopic objects. It may be given internally as a stimulant to mucous membranes.

B.P. Thus Americanum. COMMON FRANKINCENSE.—The concrete turpentine of *Pinus Tæda* and *Pinus australis*. Southern States of North America.

CHARACTERS.—A softish bright yellow opaque solid, resinous but tough, having the odour of American turpentine.

PREPARATION.

B.P.	U.S.P.
Emplastrum Picis.	None.

USE.—Applied externally is a slight stimulant. Contained in pitch plaster.

U.S.P. Terebinthina. TURPENTINE.—A concrete oleoresin, obtained from *Pinus australis* and from other species of *Pinus*.

CHARACTERS.—In tough, yellowish masses, brittle in the cold, crummy-crystalline in the interior, of a terebinthinate odour and taste.

DOSE.—As a stimulant, antispasmodic, or diuretic, 5-30 min. As an anthelmintic, 2-4 fl. dr.

Oleum Terebinthinæ, B. and U.S.P. OIL OF TURPENTINE.—A volatile oil distilled from turpentine, U.S.P. A volatile oil distilled from the oleoresin (turpentine) obtained from *Pinus palustris* (*P. australis*), *Pinus Tæda*, and sometimes *Pinus Pinaster* and other species, B.P.

CHARACTERS.—Limpid, colourless, with a strong peculiar odour and pungent and bitter taste.

COMPOSITION.—A mixture of several hydrocarbons having the composition $C_{10}H_{16}$.

PREPARATIONS.

B.P.	DOSE.
Confectio Terebinthinæ	60-120 gr.
Enema Terebinthinæ	
Linimentum Terebinthinæ (ol. tereb. 16, camphor 1, soft soap 2)	
Linimentum Terebinthinæ Aceticum (ol. tereb. 1, acetic acid 1, camphor liniment 1)	
Unguentum Terebinthinæ	
U.S.P.	
Linimentum Cantharidis	1 part in 7.
Linimentum Terebinthinæ (ol. tereb. 35, resin cerate 65)	1 part in 3.

Confectio Terebinthinæ. CONFECTION OF TURPENTINE.—Oil of turpentine, 1 fl. oz.; liquorice root, 1 oz.; honey, 2 oz.

Enema Terebinthinæ.—Oil of turpentine, 1 fl. oz.; mucilage of starch, 15 fl. oz.

PHYSIOLOGICAL ACTION.—Oil of turpentine when applied to the skin acts as an irritant and rubefacient, causing a sensation of burning, and if applied for any length of time, especially if evaporation be prevented, it causes vesication.

When inhaled, it produces sneezing, tightness across the eyes, and difficulty of breathing, caused reflexly by the local irritant action of the drug on the nasal mucous membrane.

Internally it causes burning in the mouth, and reflexly a profuse flow of saliva, and in the **stomach** it gives rise to a sensation either of heat or of cold. In large doses it produces gastro-enteritis with vomiting and diarrhœa. Ulceration of the intestine has been found after death from poisoning with turpentine.

After absorption it causes a rise and then a fall of blood-pressure, due to its first stimulating and afterwards paralysing the vaso-motor centres. Its effect on the pulse is uncertain, sometimes it is slowed and sometimes quickened.

Respiration becomes quickened and spasmodic. The drug is partly excreted by the lungs, and acts on the mucous membrane, lessening its secretion.

The **temperature** sometimes rises and sometimes falls.

It acts on the **nerve-centres,** lessening first the functions of the brain, causing diminution of voluntary movement; then the functions of the cord, lowering reflex action; and lastly those of the medulla, causing dilatation of the vessels, lowered blood-pressure, and slowed respiration.

It is excreted by the **kidneys.** In small doses it increases the quantity of urine, to which it gives a sweetish odour resembling that of violets. In large doses it diminishes the quantity of urine and gives rise to pain in the lumbar region, burning in the urethra, painful micturition, and even hæmaturia. Large doses of turpentine have a **purgative** action.

THERAPEUTICS.—**Externally** it is used as a rubefacient and counter-irritant to relieve pain or imflammation, as in chronic rheumatism affecting either the joints or muscles, also in inflammations of internal organs, as chronic bronchitis (liniment over the chest), pleuritis, and peritonitis with tympanites (by means of hot turpentine stupes). It is also very useful as a local application in sciatica and other neuralgias. It is used as an inhalation (as well as internally) in chronic bronchitis (p. 218) with profuse expectoration, and is supposed to be useful in phthisis.

Internally in hæmorrhage and ulceration of the intestine, as in typhoid fever, it is very serviceable in doses of 5-10 minims frequently repeated; also in hæmorrhage from other organs, as lungs, nose, uterus, kidneys; but in hæmaturia it must be given in very small doses (5 minims), as large ones produce harm.

As a **vermifuge,** to destroy tapeworm, it must be given in large doses, which are best combined with castor oil, as it then passes through the alimentary canal rapidly, and consequently is not absorbed and produces no disagreeable renal symptoms. If moderate doses are given, insufficient to produce purgation, the drug may be absorbed, and hæmaturia, nausea, and vomiting may ensue.

It is sometimes employed in biliary colic (1 part of oil of turpentine with 3 of ether).

The French oil of turpentine (old and containing ozone) is used in phosphorus poisoning. New oil of turpentine, free from ozone, is useless. Turpentine is sometimes used as an antispasmodic in hysterical affections.

Non-officinal. **Oleum Pini Sylvestris.** OIL OF SCOTCH FIR. FIR WOOL OIL.—It is a colourless liquid obtained by distilling the leaves of the Scotch fir.

ACTION.—Somewhat similar to that of oil of turpentine.

USES.—It is used as a liniment to rheumatic joints or muscles, and is used as an addition to baths in rheumatism (p. 414). As an inhalation it is useful in sore-throat and laryngeal catarrh, 5 min., mixed with 2½ gr. of light carbonate of magnesia and a drachm of water, being added to 1 pint of water at 140° F., and the steam

inhaled. To get the water at this temperature two parts of boiling should be mixed with one part of cold. The use of water which is too hot may cause loss of voice.

Not officinal. **Sanitas.**—A disinfecting solution obtained by acting on oxidised turpentine with water. Its active principle is peroxide of hydrogen (p. 477). Its advantages are that it is not poisonous and does not stain linen.

U.S.P. Oleum Succini. OIL OF AMBER.—A volatile oil obtained by the destructive distillation of amber and purified by subsequent rectification.

CHARACTERS.—A colourless pale yellow thin liquid, having an empyreumatic balsamic odour, a warm acrid taste, and a neutral or faintly acid reaction. Readily soluble in alcohol.

ACTION AND USES.—Externally it is **stimulant** and may be used like oil of turpentine. Internally it is said to be **antispasmodic.**

DOSE.—5 to 10 minims in capsule.

Resina, B. and U.S.P. RESIN. COLOPHONY.—The residue left after distilling off the volatile oil from turpentine, U.S.P.

CHARACTERS.—Translucent, yellowish, brittle, pulverisable; fracture shining.

COMPOSITION.—Resin is the portion of turpentine fixed by oxidation. The greater part of it consists of abietic anhydride ($C_{44}H_{62}O_4$), this being formed by the dehydrating of abietic acid ($C_{44}H_{64}O_5$) during the distillation of the oil. It is again transformed into abietic acid by treating it with alcohol. A small proportion of pimaric acid is obtained from resin.

PREPARATIONS.

B.P.	U.S.P.
Charta Epispastica.	Ceratum Resinæ.
Emplastrum Calefaciens.	Emplastrum Resinæ.
Emplastrum Cantharidis.	
Emplastrum Opii.	
Emplastrum Picis.	
Emplastrum Resinæ.	
Emplastrum Saponis.	
Unguentum Resinæ.	
Unguentum Terebinthinæ.	

USE.—Resin is only used externally as a **stimulant** application, in the form of ointment or plaster.

B.P. Laricis Cortex. LARCH BARK.—The bark, deprived of its outer layer, of *Larix europœa* (*Pinus larix*), the common larch.

CHARACTERS.—In flat pieces or sometimes large quills, with the inner surface yellow and fibrous, and the outer surface reddish-brown under a greyish epidermis. Odour faint, resembling turpentine, taste astringent.

COMPOSITION.—A peculiar tannin striking olive-green with salts of iron, and larixinic acid or larixin.

PREPARATION.

B.P.	DOSE.	U.S.P.
Tinctura Laricis	20-30 min.	Not given.

ACTION AND USE.—It has the same action as oil of turpentine. It is seldom used except as a **stimulant expectorant** in chronic bronchitis with abundant secretion.

Pix Burgundica, B. and U.S.P. BURGUNDY PITCH.—A resinous exudation from the stem of the spruce fir, *Abies excelsa*. Melted and strained. Imported from Switzerland.

CHARACTERS.—Hard and brittle, yet gradually taking the form of the vessel in which it is kept; opaque, varying in colour, but generally dull reddish-brown; of a peculiar odour and aromatic taste, without bitterness.

COMPOSITION.—An amorphous resin, mixed with oil of turpentine and other oils isomeric with it, and abietic acid.

PREPARATIONS.

B.P.	U.S.P.
Emplastrum Ferri.	Emplastrum Picis Burgundicæ.
Emplastrum Picis.	Emplastrum Picis cum Cantharide.

USE.—It is used as a stimulant in chronic rheumatism and bronchitis in the form of plasters.

U.S.P. Pix Canadensis. CANADA PITCH. HEMLOCK PITCH.—The prepared, resinous exudation of *Abies canadensis*.

CHARACTERS.—It is somewhat softer than the Burgundy pitch.

PREPARATION.

Emplastrum Picis Canadensis.

Pix Liquida, B. and U.S.P. TAR.—A bituminous liquid, obtained from the wood of *Pinus sylvestris* and other pines by destructive distillation, B.P. An empyreumatic oleoresin obtained by the destructive distillation of the wood of *Pinus palustris*, and of other species of *Pinus*.

CHARACTERS.—Thick, viscid, brownish-black, of a well-known peculiar aromatic odour. Slightly soluble in water, soluble in alcohol, fixed or volatile oils, and in solution of potassa or of soda. Water agitated with it acquires a pale brown colour, sharp empyreumatic taste and acid reaction.

PREPARATIONS.

B.P.

Unguentum Picis Liquidæ (tar 5 oz., yellow wax 2 oz.).

U.S.P.	DOSE.
Syrupus Picis Liquidæ	½ fl. oz.
Unguentum Picis Liquidæ (equal parts of tar and suet).	

U.S.P. Syrupus Picis Liquidæ. SYRUP OF TAR.—Pour cold water (12) on tar (6), stir frequently for twenty-four hours, and then throw the water away. Pour on boiling distilled water (50), stir for fifteen minutes, and then set aside for thirty-six hours, stirring occasionally. Decant, filter, and add sugar, 40 parts.

COMPOSITION.—Pyroligneous acid, methyl alcohol, acetic acid, and oily bodies, creasote, with toluene, xylene, and other hydrocarbons.

DOSE.—Of tar, 20 minims to 1 drachm, and upwards, made into pills with flour, or given as tar-water in doses of 1-4 fluid ounces.

ACTION AND USE.—Tar acts as a **stimulant** both to the skin and to mucous membranes. It is used in chronic scaly skin diseases, such as psoriasis, and the scaly stages of eczema. In the form of tar-water or of vapour, it is useful in chronic bronchitis and phthisis.

U.S.P. Oleum Picis Liquidæ. OIL OF TAR.—A volatile oil distilled from tar.

An almost colourless liquid when freshly distilled, but soon acquiring a dark, reddish-brown colour, having a strong tarry odour and taste, and an acid reaction. Specific gravity about 0·970. It is readily soluble in alcohol.

USE.—It is used, dissolved in water or in alcohol, as an external application in skin diseases.

U.S.P. Thuja. THUJA. ARBOR VITÆ.—The fresh tops of *Thuja occidentalis.*

CHARACTERS.—Twigs flattish, two-edged, the scale-like leaves appressed and closely imbricate in four rows, rhombic-ovate, obtusely pointed, with a roundish gland upon the back; of a balsamic, somewhat terebinthinate odour, and a pungently aromatic, camphoraceous, and bitter taste.

DOSE.—Of a saturated tincture or fluid extract 1 fluid drachm.

ACTION.—The twigs of thuja, like those of savin, may produce **abortion.** They probably have no direct specific action on the uterus itself, but cause great gastro-intestinal irritation, and thus act on the uterus reflexly. The oil of thuja has an action somewhat like camphor, and like it produces epileptiform **convulsions** in warm-blooded, and **paralysis** in cold-blooded animals. Both camphor and oil of thuja have only a slight action on the heart. They both produce rhythmical contraction and dilatation of the **vessels** (as seen in the rabbit's ear). Both lessen the **temperature** (Köhne) (c.f. p. 929).

USES.—It is **diuretic,** astringent, and **aromatic,** and its volatile oil has been used as a **vermifuge.** It has been employed in the form of a decoction in coughs, rheumatism, dropsy, and amenorrhœa.

U.S.P. Juniperus. JUNIPER.—The fruit of *Juniperus communis.*

CHARACTERS.—Nearly globular, about one-third of an inch (8 millimetres) in diameter, dark purplish, with a bluish-grey bloom, a three-rayed furrow at the apex, internally pulpy, greenish-brown, containing three ovate, somewhat triangular, bony seeds, with several

large oil-glands on the surface; odour aromatic; taste sweet terebinthinate, bitterish and slightly acrid.

Oleum Juniperi, B. and U.S.P. OIL OF JUNIPER.—A volatile oil distilled from the unripe fruit of *Juniperus communis*.

CHARACTERS.—Colourless or pale greenish-yellow, of a sweetish odour, and warm aromatic taste.

PREPARATIONS.

B.P.	DOSE.
Spiritus Juniperi (with spirit 1 volume in 50)	30 min. to 1 fl. drm. (of the oil, 2-10 min.)

U.S.P.	
Spiritus Juniperi (3 per cent. in alcohol)	30-60 min.
Spiritus Juniperi Compositus	2-4 fl. drm.

U.S.P. Spiritus Juniperi Compositus. COMPOUND SPIRIT OF JUNIPER.—Oil of juniper, 10; oil of caraway, 1; oil of fennel, 1; alcohol, 1,000; water up to 5,000.

ACTION AND USE.—Oil of juniper is a local **stimulant**. It is contained in gin and hollands. It resembles oil of turpentine in its action, but has a more powerful effect on the kidneys. It is used chiefly as a **diuretic** in dropsy depending on cardiac, liver, or kidney disease. In the last case it must be employed with caution. In a healthy man it does not seem to increase the flow of urine. Gin is flavoured with juniper and is frequently employed as a diuretic. The compound spirit of juniper, U.S.P., approximates to gin in strength and may be used in place of it.

Sabinæ Cacumina, B.P.; Sabina, U.S.P. SAVIN TOPS, B.P.; SAVINE, U.S.P.—The (fresh and dried, B.P.) tops of *Juniperus Sabina*.

CHARACTERS.—Twigs densely covered with minute imbricated appressed leaves in four rows; odour strong, peculiar, and unpleasant; taste acrid, bitter, resinous, and disagreeable.

COMPOSITION.—The active principle is a volatile oil.

PREPARATIONS.

B.P.	DOSE.
Oleum Sabinæ, from fresh plant	1-5 min.
Tinctura Sabinæ	20 min. to 1 fl. drm.
Unguentum Sabinæ (8 oz. fresh savin tops, bruised, are digested with melted wax, 3 oz., and prepared lard, 16 oz., for 20 minutes, and strained).	(of dried tops, 4-10 gr. or more.)

U.S.P.	
Extractum Sabinæ Fluidum	5-15 min.

Oleum Sabinæ, B. and U.S.P.—A volatile oil distilled from savine.

CHARACTERS.—Colourless or yellowish, becoming darker and thicker by age and exposure to air, peculiar odour, pungent, bitterish, and camphoraceous taste.

DOSE.—1 to 2 minims.

ACTION AND USES.—Savine owes its properties to its oil.

Externally it is used as an **irritant** to keep open issues or blisters.

Internally it produces symptoms of violent gastro-intestinal irritation, with either stoppage of the urine or hæmaturia and difficulty in micturition. In women it causes congestion of the pelvic organs, and has been used criminally to procure **abortion**; in these cases gastro-enteritis and death have occurred. Small doses may be used as an **emmenagogue** when menstruation is deficient and the patient is not pregnant.

CHAPTER XXXVI.

Class II. ENDOGENÆ. ENDOGENS.

SMILACEÆ.

Sarsæ Radix, B.P.; Sarsaparilla, U.S.P. (JAMAICA, B.P.) SARSAPARILLA.—The (dried, B.P.) root of *Smilax officinalis*, *Smilax medica*, and other undetermined species of *Smilax*. Native of Central America, imported from Jamaica.

CHARACTERS.—Roots not thicker than a goose-quill, generally many feet in length, reddish-brown, covered with rootlets, and folded in bundles about eighteen inches long, scentless.

COMPOSITION.—The active principle is a crystalline body, parillin or smilacin.

PREPARATIONS.

B.P.	DOSE.
Decoctum Sarsæ (2½ oz., water 1½ pint)	2-10 fl. oz.
Decoctum Sarsæ Compositum	2-10 fl. oz.
Extractum Sarsæ Liquidum	½-4 fl. drm.

U.S.P.	
Decoctum Sarsaparillæ Compositum	4-6 fl. oz.
Extractum Sarsaparillæ Compositum Fluidum	30-60 min.
Extractum Sarsaparillæ Fluidum	30-60 min.
Syrupus Sarsaparillæ Compositus	1-4 fl. drm.

Decoctum Sarsæ Compositum, B.P.; Decoctum Sarsaparillæ Compositum, U.S.P.; COMPOUND DECOCTION OF SARSAPARILLA.—Sarsaparilla, cut and bruised, 10 parts, or 2½ oz.; sassafras, guaiacum wood and liquorice root, of each 2 parts or ¼ oz.; mezereon, 1 part or 1 dr.; boiling water up to 100 parts, or up to 1 pint after straining.

U.S.P. Extractum Sarsaparillæ Compositum Fluidum.—Sarsaparilla, 75; glycyrrhiza, 12; sassafras bark, 10; mezereum, 3; glycerin, 10; alcohol and water, of each *q.s.* to make 100 parts.

U.S.P. Syrupus Sarsaparillæ Compositus.—Sarsaparilla, 150; guaiacum wood, 20; pale rose, 12; glycyrrhiza, 12; senna, 12; sassafras, 6; anise, 6; gualtheria, 6; sugar, 600; diluted alcohol and water, of each *q.s.* to make 1000 parts.

ACTION AND USES.—The action of sarsaparilla is very much disputed. Some believe it to be **diuretic, tonic,** and **alterative.** Others deny its beneficial action. It has been used a good deal in

syphilis, scrofula, chronic rheumatism, gout, and skin diseases, but probably the good effects are due to drugs with which it is used.

Syrupus sarsaparillæ compositus, U.S.P., is a convenient vehicle for iodide of potassium.

LILIACEÆ.

U.S.P. Allium. GARLIC.—The bulb of *Allium sativum*.

CHARACTERS.—Bulb subglobular, compound, consisting of about eight compressed, wedge-shaped bulblets, which are arranged in a circle around the base of the stem, and covered by several dry, membranaceous scales. It has a pungent, disagreeable odour, and a warm, acrid taste. It should be preserved in a dry place, and used only in the fresh state.

OFFICINAL PREPARATION.

U.S.P.	DOSE.
Syrupus Allii	1-4 fl. drm.

COMPOSITION.—The bulblets, or cloves as they are commonly termed, owe their strong taste and smell to a volatile oil which is sulphide of allyl $(C_3H_5)_2S$.

ACTION.—Allyl alcohol is a powerful **antiseptic** (pp. 77 and 82), and it is probable that oil of garlic will have a similar action. Like oil of mustard, to which it is allied in chemical composition (p. 781), oil of garlic is a powerful **irritant,** or even vesicant, when applied to the skin. In the intestine it acts in small doses as a gastric tonic and **carminative;** in large doses as an emetic and irritant, causing vomiting, purging, headache, and fever. After absorption, it quickens the pulse and acts as a nervous **stimulant.** It is partly eliminated by the lungs, imparting its peculiar odour to the breath, and acting as an **expectorant.** It is diaphoretic or **diuretic** according as the patient is kept warm or cool. It is said to be an emmenagogue.

USES.—A mixture of garlic juice and oil, or bruised garlic steeped in spirit, is used as a counter-irritant in convulsions or nervous diseases in children, and also in skin eruptions. The syrup may be used as a gastric tonic in atonic dyspepsia, and to check nervous vomiting. It is chiefly employed in nervous coughs of children, and as an expectorant in bronchitis after the acute stage has passed. It is used as an anthelmintic in cases of ascarides, and is given by the mouth and also as an enema.

Scilla, B. and U.S.P. SQUILL.—The sliced (and dried B.P.) bulb of *Urginea Scilla* (*U. maritima*). Mediterranean coasts.

CHARACTERS.—Bulb pear-shaped, weighing from half a pound to ten pounds; outer scales membranous, brownish-red or white; inner scales thick, whitish, fleshy, juicy; taste mucilaginous, intensely and disagreeably bitter, somewhat acrid. The dried

slices are white or yellowish-white, slightly translucent, scentless, disagreeably bitter, brittle and easily pulverisable if very dry.

FIG. 184.—Cut piece of Squill.

COMPOSITION.—The active principle is a glucoside, scillitoxin or scillaïn. The scillitin of some authors is probably slightly impure scillitoxin.

PREPARATIONS.

B.P.	DOSE.
Acetum Scillæ	15-40 min.
Oxymel Scillæ	½-1 fl. drm.
Pilula Ipecacuanhæ cum Scilla	5-10 gr.
Pilula Scillæ Composita	5-10 gr.
Syrupus Scillæ	½-1 fl. drm.
Tinctura Scillæ	10-20 min.
	(of powdered squills, 1-3 gr.)

U.S.P.	
Acetum Scillæ	15 min. to 1 fl. drm.
Extractum Scillæ Fluidum	1-2 min.
Syrupus Scillæ Compositus	10-30 min.
Tinctura Scillæ	8-30 min.
Syrupus Scillæ	½-1 fl. drm.

B.P. Pilula Scillæ Composita. Squill, 1¼ oz.; ginger, ammoniacum, and hard soap, of each, 1 oz.; treacle, 2 oz. or *q.s.*

U.S.P. Syrupus Scillæ Compositus. Squill, 120; senega, 120; tartrate of antimony and potassium, 3; sugar, 1200; precipitated phosphate of calcium, 9; diluted alcohol and water, of each, *q.s.* to make 2000.

ACTION AND USES.—Squill and its active principle, scillitoxin, act like digitalis.

Internally, in **large doses,** it causes vomiting and purging. When absorbed into the blood, it slows the **pulse** and raises the blood-pressure. Like digitalis it acts as a **diuretic,** and also acts like it on voluntary muscle fibre. It is chiefly used as an adjunct to digitalis to produce diuresis in cases of cardiac dropsy; also as an **expectorant,** when, although the secretion is profuse, it is difficult to expel. It is of no use when the expectoration is dry and deficient; in such cases ipecacuanha should first be given and then followed by squill.

Pilula ipecacuanhæ cum scilla, 10 grains night and morning, is a most useful remedy in chronic bronchitis.

Aloe, U.S.P.; Aloe Socotrina, B.P. ALOES, U.S.P.; SOCOTRINE ALOES, B.P.—The inspissated juice of the leaf of *Aloe socotrina*, U.S.P. (one or more undetermined species of *Aloe*, B.P.) Socotra.

CHARACTERS.—In hard, opaque, reddish-brown or yellowish-brown, not greenish, masses, translucent at the edges; breaks with

an irregular or smooth and resinous fracture; has a bitter taste, and when breathed on has a saffron-like odour; dissolves entirely in proof spirit, and during solution exhibits under the microscope numerous minute crystals.

PREPARATIONS.

B.P.		DOSE.
Decoctum Aloes Compositum (Extract)	4 gr. in 1 fl. oz.	½-2 fl. oz.
Enema Aloes	4 gr. in 1 fl. oz.	10 fl. oz.
Extractum Aloes Socotrinæ	1 part from 2, nearly	2-6 gr.
Extractum Colocynthidis Compositum (Extract)	1 part in 2 nearly	3 10 gr.
Pilula Aloes et Asafœtidæ	1 part in 4	5-10 gr.
Pilula Aloes et Myrrhæ	1 part in 3	5-10 gr.
Pilula Aloes Socotrinæ	1 part in 2, nearly	5-10 gr.
Pilula Rhei Composita	1 part in 6	5-10 gr.
Tinctura Aloes	11 gr. to 1 fl. oz.	1-3 fl. dr.
Tinctura Benzoini Composita	8 gr. to 1 fl. oz.	½-2 fl. dr.
Vinum Aloes	16½ gr. to 1 fl. oz.	1-2 fl. dr.

U.S.P.	
Aloes Purificata	½-6 gr.
Extractum Aloes Aquosum	½-6 gr.

B.P. Decoctum Aloes Compositum. COMPOUND DECOCTION OF ALOES.—Extract of Socotrine aloes, 120 gr.; myrrh, 90 gr.; saffron, 90 gr.; carbonate of potash, 60 gr.; extract of liquorice, 1 oz.; compound tincture of cardamoms, 8 fl. oz.; distilled water up to 30 fl. oz.

B.P. Enema Aloes. Aloes (Socotrine or Barbados), 40 gr.; carbonate of potash, 15 gr.; mucilage of starch, 10 fl. oz.

B.P. Extractum Aloes Socotrinæ. Treating with boiling water, separating insoluble matter by subsidence and filtration, and evaporating the clear solution.

B.P. Pilula Aloes et Assafœtidæ. PILL OF ALOES AND ASSAFŒTIDA.—Equal parts of Socotrine aloes, assafœtida, hard soap, and confection of roses.

B.P. Pilula Aloes et Myrrhæ. PILL OF ALOES AND MYRRH.—Socotrine aloes, 2 oz.; myrrh, 1 oz.; saffron, ½ oz.; confection of roses, 2½ oz.

B.P. Pilula Aloes Socotrina. PILL OF SOCOTRINE ALOES.—Socotrine aloes, 2 oz.; hard soap, 1 oz.; volatile oil of nutmeg, 1 fl. dr.; confection of roses, 1 oz.

B.P. Tinctura Aloes. TINCTURE OF ALOES.—Socotrine aloes, ½ oz.; extract of liquorice, 1½ oz.; proof spirit, to 20 fl. oz.

B.P. Vinum Aloes. WINE OF ALOES.—Socotrine aloes, 1½ oz.; cardamom seeds and ginger, of each, 80 gr.; sherry, up to 2 pints.

U.S.P. Extractum Aloes Aquosum. AQUEOUS EXTRACT OF ALOES.—Aloes, 100; boiling distilled water, 1,000. Separate the insoluble matter by subsidence and filtration, and evaporate.

COMPOSITION.—All kinds of aloes contain a bitter substance, **aloïn,** to which their activity is due. It has in each kind of aloes a slightly different composition, and has received a name showing its source—socaloïn from Socotrine aloes, barbaloïn from Barbados aloes, and nataloïn from Natal aloes. According to some authors these substances are isomeric, according to others they form a homologous series. Besides aloïn, aloes contain resinous substances and traces of an ethereal oil.

Barbaloïn and nataloïn are distinguished from socaloïn by giving with a drop of nitric acid, on a porcelain slab, a bright crimson colour. With barbaloïn this gradually fades but is permanent with nataloïn. Socaloïn does not give this reaction. Barbaloïn is

distinguished from nataloïn by the latter giving a fine blue colour, while the former remains unchanged, on adding a minute quantity of each to one or two drops of strong sulphuric acid and then bringing a glass rod dipped in nitric acid so near that the vapour shall pass over the surface.

U.S.P. Aloe Purificata. PURIFIED ALOES.

PREPARATION.—By melting aloes 100, adding alcohol 15, straining and evaporating.

CHARACTERS.—Purified aloes is in irregular brittle pieces of a dull-brown or reddish-brown colour, and having the peculiar aromatic odour of Socotrine aloes. It is almost entirely soluble in alcohol.

PREPARATIONS.

U.S.P.		DOSE.
Pilulæ Aloes	1 part in 2	1 pill.
Pilulæ Aloes et Assafœtidæ	1 part in 3	2-5 pills.
Pilulæ Aloes et Ferri	1 part in 3	1 pill.
Pilulæ Aloes et Mastiches	2 parts in 3	1 pill.
Pilulæ Aloes et Myrrhæ	2 parts in 3½	1 pill.
Pilulæ Rhei Compositæ	1 part in 3	1-4 pills.
Extractum Colocynthidis Compositum	1 part in 2, nearly	5-10 gr.
Pilulæ Catharticæ Compositæ	1 part in 6	1-3 pills.
Tinctura Aloes	1 part in 10	1-4 fl. dr.
Tinctura Aloes et Myrrhæ	1 part in 10	1-2 fl. dr.
Tinctura Benzoini Composita		2 fl. dr. to 1 fl. oz.
Vinum Aloes	6 parts in 100	1 fl. dr. to 1 fl. oz.

U.S.P. Pilulæ Aloes. PILLS OF ALOES.—Aloes and soap, of each 2 gr. in one pill.

U.S.P. Pilulæ Aloes et Assafœtidæ. PILLS OF ALOES AND ASSAFETIDA.—Each pill contains aloes, assafetida, and soap, of each 1⅓ gr.

U.S.P. Pilulæ Aloes et Ferri. PILLS OF ALOES AND IRON.—Each pill contains aloes, dried sulphate of iron, and aromatic powder, of each 1 gr. made up with confection of roses.

U.S.P. Pilulæ Aloes et Mastiches. PILLS OF ALOES AND MASTIC.—Each pill contains aloes, 2 gr.; mastic, ½ gr.; red rose, ½ gr.

U.S.P. Pilulæ Aloes et Myrrhæ. PILLS OF ALOES AND MYRRH.—Each pill contains aloes, 2 gr.; myrrh, 1 gr.; aromatic powder, ½ gr. Made up with syrup.

U.S.P. Tinctura Aloes. TINCTURE OF ALOES.—Aloes, 10; extract of glycerrhiza, 10; diluted alcohol, up to 100.

U.S.P. Tinctura Aloes et Myrrhæ. TINCTURE OF ALOES AND MYRRH.—Aloes, 10; myrrh, 10; alcohol, to 100.

U.S.P. Vinum Aloes. WINE OF ALOES.—Aloes, 6; cardamom, 1; ginger, 1 stronger white wine, up to 100. DOSE as stomachic, 1-2 fl. dr. As purgative, ½-1 fl. oz.

B.P. Aloe Barbadensis. BARBADOES ALOES.—The inspissated juice of the leaf of *Aloe vulgaris*. Barbadoes.

CHARACTERS.—In yellowish-brown or dark-brown opaque masses; breaks with a dull conchoidal fracture; has a bitter nauseous, taste, and a strong, disagreeable odour.

COMPOSITION.—Contains barbaloïn, resin, and volatile oil.

PREPARATIONS.

B.P.		DOSE.
Enema Aloes (*vide supra*)	4 gr. in 1 fl. oz.	
Extractum Aloes Barbadensis	8 parts from 10, nearly	2 6 gr.
Pilula Aloes Barbadensis	1 part in 2, nearly	5-10 gr.
Pilula Aloes et Ferri	1 part in $5\frac{1}{4}$	5-10 gr.
Pilula Cambogiæ Composita	1 part in 6, nearly	5-10 gr.
Pilula Colocynthidis Composita	1 part in 3, nearly	5-10 gr.
Pilula Colocynthidis et Hyoscyami	1 part in $4\frac{1}{2}$, nearly	5-10 gr. (of aloes in powder, 2-6 gr.)

B.P. Extractum Aloes Barbadensis.—Prepared like extract of Socotrine aloes.

B.P. Pilula Aloes Barbadensis. PILL OF BARBADOES ALOES.—Barbadoes aloes, 2 oz. ; hard soap, 1 oz. ; oil of caraway, 1 fl. dr. ; confection of roses, 1 oz.

B.P. Pilula Aloes et Ferri. PILL OF ALOES AND IRON.—Sulphate of iron, $1\frac{1}{2}$ oz. ; Barbadoes aloes, 2 oz. ; compound powder of cinnamon, 3 oz. ; confection of roses, 4 oz.

ACTION AND USES.—It causes a bitter taste in the **mouth,** and reflex salivation. In small doses it seems to have a tonic action like simple bitters. It increases peristalsis of the **intestines** and also intestinal secretion. Its action is particularly exerted on the large intestines, and especially in the **rectum.** This is shown by the great length of time which usually elapses between its administration and its action (ten or twelve, sometimes as much as twenty-four, hours), and by the rectal irritation which it produces, and which is evidenced by tenesmus, hæmorrhoidal swelling, and hæmorrhage. It increases the secretion of **bile** by stimulating the liver (Röhrig and Rutherford). It only acts when mixed with bile, and is consequently useless in jaundice, where the bile does not enter the intestine, as is shown by the whiteness of the stools. It may, however, be rendered active by giving it along with ox-gall. Aloes has little or no purgative action when given alone as an enema, but is active if mixed with ox-bile. In the enema aloes, B.P., it is mixed with carbonate of potash. Aloes appears to cause hyperæmia of the **uterus** and other pelvic organs as well as of the rectum. It sometimes has an **aphrodisiac** action, but this is not constant, and probably is due to irritation caused by hæmorrhoids (p. 394). Aloes differs from other purgatives in not causing subsequent constipation, but on the contrary rendering the intestine more sensitive, so that the dose can be gradually reduced. As it **does not cause subsequent constipation,** it is a favourite purgative, and is contained in most vegetable purgative pills (except pil. scamm. co.). As it **acts slowly,** it should be given a good while before a motion is desired, and a favourite plan is to give it as a **dinner pill** just before the last meal of the day, when it usually acts next morning after breakfast. I have known people who have taken dinner pills regularly every day for thirty years without injury and with apparent benefit. As it tends to cause congestion of the rectum, some authorities prohibit its use in piles, but in small doses, and if the piles are not inflamed, it is often beneficial in these cases, although large doses are injurious. From its action in causing

congestion of the uterus, it is used in amenorrhœa (at the time when the catamenia are expected), but must be avoided in pregnancy and rectal inflammation. In these cases it is usually combined with iron or myrrh.

Veratri Viridis Radix, B.P.; Veratrum Viride, U.S.P. GREEN HELLEBORE ROOT, B.P.; AMERICAN HELLEBORE, U.S.P. —The rhizome and rootlets of *Veratrum viride.* United States and Canada.

CHARACTERS.—Rhizome two or three inches long, one to two inches thick, with numerous shrivelled, light yellowish-brown rootlets.

COMPOSITION.—It contains several alkaloids—jervine, pseudo-jervine, cevadine, very little rubijervine, and traces of veratrine

FIG. 185.—*Veratrum viride* root.

and veratralbine. Veratroidine, which was formerly regarded as one of its constituents, is probably rubijervine and resin.

PREPARATIONS.

B.P.	DOSE.
Tinctura Veratri Viridis	5-20 min. or more. (of the powdered rhizome, 1-3 gr. or more.)

U.S.P.	DOSE.
Extractum Veratri Viridis Fluidum	1-4 min.
Tinctura Veratri Viridis	5-10 min.

ACTION.—In small doses veratrum viride lessens the strength of the **pulse** in man without at first affecting its rate, but afterwards it renders it very slow, soft, and compressible, although sometimes moderately full. At this stage any exertion at once renders the slow pulse rapid, feeble, small, and even imperceptible. The depression of the circulation is accompanied by muscular weakness, and frequently, though not always, by nausea and vomiting. When the dose is large these symptoms become increased, and a state of **collapse** comes on with an exceedingly rapid, almost imperceptible pulse, cold clammy skin, constant nausea and retching, intense muscular weakness, giddiness, loss of vision, and partial unconsciousness.

The action of veratrum viride is due to the jervine and other alkaloids which it contains. It has been mentioned already that veratroidine is not a pure alkaloid, but as no further investigations have been made on the alkaloids of veratrum since those of Professor H. C. Wood, I give his results.

Jervine lessens the functions of the **spinal cord,** both in frogs and mammals, and of the **medulla** (especially the vaso-motor centre), and of the **cardiac ganglia,** and at the same time irritates the motor centres in the **brain,** producing convulsions. Thus the symptoms produced are muscular weakness, loss of reflex action, followed by tremors, lowered blood-pressure, and slow pulse.

Respiration ceases before the heart, and **death** ensues from asphyxia. There is invariably salivation, but no vomiting nor purging. It has no action on the vagus, and the slow pulse is due to an action on the cardiac muscle or its ganglia. Voluntary **muscles** and **motor nerves** are little, if at all, affected by it.

Veratroidine differs from jervine in always causing **vomiting** and purging, and in producing less violent convulsions. It stimulates the **vagus centre** and paralyses the **vagus ends.** It depresses the **spinal cord** and paralyses the **respiratory centre,** but increases the excitability of the **vaso-motor centre.** At first it slows the pulse and lowers the **blood-pressure.** Next the pulsations become very powerful, though still slow, and the blood-pressure rises to normal. Then the **pulse** becomes very rapid, and the pressure rises greatly. This rise is, however, not due to the direct action of the drug, but to stimulation of the vaso-motor centre by asphyxial blood from paralysis of the respiration. If artificial respiration be kept up veratroidine steadily lessens both pulse-rate and blood-pressure.

THERAPEUTICS.—Veratrum viride has been used as a cardiac depressant in inflammations, but not generally.

B.P. Sabadilla. CEVADILLA.—The dried fruit of *Asagræa officinalis.* Mexico.

CHARACTERS.—Fruit about half an inch long, consisting of three light-brown papyraceous follicles, each containing from one to three seeds, which are about a quarter of an inch long, blackish-brown, shining, slightly winged, possessing an intensely acrid bitter taste.

PREPARATION.
Veratria.

COMPOSITION.—Three alkaloids, the first—veratria—being the active principle. The remaining alkaloids—sabadillina and sabatrina—occur in very small quantities, and are of little importance in pharmacy.

Veratria, B.P.; Veratrina, U.S.P. VERATRIA, B.P.; VERATRINE, U.S.P.—An alkaloid obtained from cevadilla; not quite pure, B.P. An alkaloid or mixture of alkaloids prepared from the seeds of *Asagræa officinalis,* U.S.P.

PREPARATION.—A concentrated tincture of the seeds is poured into cold water in order to precipitate albumen. From the filtered solution veratria is precipitated by ammonia, and purified by re-solution in dilute hydrochloric acid, decolorisation by animal charcoal, and reprecipitation by ammonia.

CHARACTERS.—Pale grey, amorphous, without smell, but, even in the most minute quantity, powerfully irritating the nostrils; strongly and persistently bitter, and highly acrid; insoluble in water; soluble in spirit, in ether, and in diluted acids, leaving traces of an insoluble brown resinoid matter. An active poison.

IMPURITIES.—Mineral matter, and sometimes traces of the other alkaloids of cevadilla.

TEST.—Heated with access of air it melts into a yellow liquid, and at length burns away, leaving no residue.

DOSE.—$\frac{1}{12}$-$\frac{1}{8}$ gr.

PREPARATIONS.

B.P.

Unguentum Veratriæ (8 gr. to 1 oz.) for external use.

U.S.P.

Oleatum Veratrinæ .....1 part in 50.....
Unguentum Veratrinæ...1 part in 25.....

PHYSIOLOGICAL ACTION.—**Large doses** of veratrine cause violent sneezing, and great gastro-intestinal irritation, vomiting, purging, and symptoms of collapse, the pulse being rapid, small, and irregular; and often involuntary muscular tremors come on. A peculiar creeping and prickling sensation in the skin generally accompanies these symptoms.

Externally, applied to the unbroken skin, it has no marked action, but if rubbed in with some fat it passes through the epidermis and acts on the true skin, and causes first irritation and then paralysis of the ends of the sensory nerves, producing a prickling and creeping sensation, succeeded by numbness. It is somewhat like aconitine in this respect. This effect is produced whether applied locally or taken internally.

Its irritating action on the sensory nerves is also observed if it be inhaled into the nose, when it causes violent sneezing, which also occurs after absorption from the stomach.

Internally.—It has no marked action on the **brain.** It has probably no action on the **spinal cord.** By some experimenters it is stated that convulsions are produced in frogs, but, from numerous experiments which I performed, I doubt the accuracy of this statement.

Muscles.—The contractile power is increased, but the elasticity very much diminished. The period of contraction is very much prolonged, but neither the latent period nor the ascent of the curve are affected in character; the height of the curve is slightly increased, and the descent of the curve very much prolonged, so that it does not reach the abscissa for several revolutions of the cylinder.

This contraction is not a state of partial rigor, since during its continuance the development of heat is increased to a marked degree; neither is it a true tetanus, since the rheoscopic frog only gives a single contraction when its nerve is laid on the poisoned muscle. It is a **prolonged contraction.** To this alteration in the muscles is due the peculiar behaviour of frogs when poisoned by veratria. The frog jumps readily on stimulation, but after its spring it lies on the table with legs extended for a long time; then it draws the limbs up slowly, for both the flexors and extensors are contracted, and the contraction has to pass off from the extensors before the flexors can act. When it has drawn its limbs up, it remains still for a time, to allow the contraction to pass off from the flexors, after which it springs again. Thus the frog performs the normal movements with very long intervals between them. These movements have probably been mistaken for convulsions. Temperature affects the veratria curve in a remarkable manner. As you cool the muscle down, the curve becomes more and more like the normal, and if the temperature be much raised (keeping below the heat of *rigor caloris*), the effect also disappears; thus extremes of heat and cold remove the veratrine effect on the muscle-curve. The effect of veratrine on the muscle is also removed by potash (p. 106).

Muscles previously exhausted by over-exertion have their powers restored by veratrine.

Motor nerves have their excitability increased at first; afterwards their peripheral ends are paralysed. **Sensory nerves** have their peripheral ends first stimulated (causing pricking, &c). and then paralysed (cf. aconite, p. 150).

Circulation.—The effect of veratrine on the **heart-muscle** of the frog is very similar to that on voluntary muscle; hence the contractions of the heart become slower, and each systole lasts for a length of time, till finally the heart stops in complete systole. The effect of veratrine on the heart is also removed by heat and by potash (Ringer). In mammals, small doses injected into the circulation quicken the **pulse** and raise the blood-pressure; moderate and large doses slow the heart and lower the **blood-pressure.** Small doses quicken the **respiration;** large ones slow it, producing long pauses like those which occur after section of the vagi, and finally paralyse it. These effects are probably due to stimulation at first, and afterwards to paralysis of the ends of the vagus in the lung, and to paralysis of the respiratory centre. The **temperature** is lowered.

THERAPEUTICS.—**Locally,** it is used like aconitine for neuralgia, in the form of the ointment rubbed over the affected part.

Internally, it is sometimes used in rheumatic arthritis, and in sthenic febrile affections, as pneumonia, but its action is uncertain, and its use dangerous; hence it is seldom employed. Possibly one cause of the uncertainty of its action is the high temperature

accompanying febrile affections, by which its action is altered. A similar reason may hold good for aconite, which varies considerably in its action on febrile disorders (cf. digitalis, p. 913).

Colchici Cormus, B.P.; Colchici Radix, U.S.P. COLCHICUM CORM, B.P.; COLCHICUM ROOT, U.S.P.—The (fresh, B.P.) corm of *Colchicum autumnale* (collected about the end of June; and the same stripped of its coats, sliced transversely, and dried at a temperature not exceeding 150°, B.P.)



FIG. 186.—Slice of Colchicum.

CHARACTERS.—Fresh corm about the size of a chestnut; furnished with an outer brown and an inner yellow coat; internally white, solid and fleshy. Dried slices about a line thick, moderately indented on one, rarely on both sides, firm, flat, whitish, amylaceous.

COMPOSITION.—Colchicine, and traces of veratrine; also starch, tannin, and fatty oil. They lose their odour by drying.

PREPARATIONS.

B.P.	DOSE.
Extractum Colchici	½-2 gr.
Extractum Colchici Aceticum	½-2 gr.
Vinum Colchici (88 gr. to 1 fl. oz.)	10-30 min.

U.S.P.

COLCHICI RADIX.

Extractum Colchici Radicis	½-2 gr.
Extractum Colchici Radicis Fluidum	2-5 min.
Vinum Colchici Radicis	8 min.

Colchici Semina, B.P.; Colchici Semen, U.S.P. COLCHICUM SEEDS, B.P.; COLCHICUM SEED, U.S.P.—The fully ripe seeds of *Colchicum autumnale*, B.P. The seed of *Colchicum autumnale*, U.S.P.



FIG. 187.—Colchicum Seeds.

CHARACTERS.—About the size of white mustard seed, very hard, of a reddish-brown colour, and pitted.

COMPOSITION.—Colchicine, generally regarded as an alkaloid, soluble in water and alcohol. Traces of veratrine—in combination with gallic acid—and a fixed oil are found.

PREPARATIONS.

B.P	DOSE.
Tinctura Colchici Seminum.....54½ gr. to 1 fl. oz.	...10-30 min.

U.S.P.

Extractum Colchici Seminis Fluidum	2-10 min.
Tinctura Colchici Seminis	15-30 min.
Vinum Colchici Seminis	15-30 min.

GENERAL ACTION.—The action of colchicum does not vary in proportion to the dose, since, when a certain (fairly large) dose is given, an increased dose does not seem to produce a more marked effect. It acts as a poison both to cold- and warm-blooded animals, but its effect is least marked on cold-blooded animals, and more marked on Carnivora than Herbivora. It has the same effect on the alimentary canal whether swallowed or subcutaneously injected.

When given in continued non-poisonous doses it causes an acrid taste, with reflex flow of saliva, and symptoms of **gastro-intestinal** disturbance, viz. **irritation** of the fauces, loaded tongue, loss of appetite, flatulence, uneasiness, or pain in the stomach and intestines, and diarrhœa. The **pulse** is slowed, and there is a tendency to muscular weakness.

A single large dose, or moderate **doses long continued** may produce symptoms of acute gastro-intestinal inflammation, viz. violent **vomiting** (vomited matter being first bilious and then bloody), and **purging** (the stools being first serous, then mucous, then bloody). Marked symptoms of **collapse** supervene, the pulse becomes small, rapid, and thready, the skin cold and bedewed with sweat, respiration slow and painful. Death ensues from collapse, the brain remaining clear to the last.

Sometimes **nervous symptoms** occur, such as flying pains over the body, numbness, and occasionally, though rarely, convulsions.

SPECIAL ACTION.—When applied to the **skin** it is an irritant, causing redness, prickling, and smarting, and if taken into the nose causes sneezing and running at the eyes.

Internally.—Its action on the brain, if any, is not well marked.

In frogs the **spinal cord** is paralysed, the paralysis being preceded by excitement, sometimes giving rise to convulsions. In the higher animals there is no excitement, the cord being paralysed from the first. The **sensory nerves** are more or less paralysed. The **motor nerves** and **muscles** are unaffected. The **circulation** is affected, but the action is to a great extent reflex, since, if injected directly into the circulation, both the heart and the blood-pressure are only slightly altered. Very large doses are required to paralyse the inhibitory fibres of the vagus, but ultimately they are paralysed.

The Secretion of Urine.—Some authorities affirm that the total solids (both inorganic and organic) are increased, and also the quantity of water. Some say that only the urea is increased, others

that the uric acid is increased, while others, again, contradict both these statements.

The probable explanation of these conflicting statements is that the observers have conducted experiments with different diets.

THERAPEUTICS.—Its chief use is in gout, in the form of vinum or tincture, either in large doses during the fit, or in small ones continued for a length of time. It seems to act best when the bowels are previously freely acted on, hence a very old and useful mixture is colchicum, magnesia, and sulphate of magnesia.

In rheumatic arthritis 10 min. of tincture with 10 gr. of potassium iodide often prove useful.

In subacute rheumatism it is of very much less service.

In acute rheumatism it is hardly ever used, salicylate of soda being more frequently employed.

Treatment in Poisoning.—Evacuate the stomach by an emetic, if vomiting is not induced by the drug itself; give tannic acid in large quantities (which acts as a chemical antidote); white of egg diluted with water may be given freely; or, if pulse is very depressed, give stimulants and keep the patient warm.

ORCHIDACEÆ.

U.S.P. Vanilla. VANILLA.—The fruit of *Vanilla planifolia.*

CHARACTERS.—From six to ten inches (15 to 25 centimetres) long, linear, narrowed and bent or hooked at the base, rather oblique at the apex, wrinkled, somewhat warty, dark brown, glossy-leathery, one-celled, and containing a blackish-brown pulp, with numerous minute seeds, and more or less acicular crystals; odour and taste peculiar, fragrant.

PREPARATION.

	DOSE.
Tinctura Vanillæ	A few drops as a flavouring.

USES.—It is used chiefly as a **flavouring** and a perfume. It is also an **aromatic stimulant** in hysteria and low fevers.

U.S.P. Cypripedium. CYPRIPEDIUM. LADIES' SLIPPER.—The rhizome and rootlets of *Cypripedium pubescens,* and of *Cypripedium parviflorum.*

CHARACTERS.—Horizontal, bent, four inches (10 centimetres) or less, long; about one-eighth of an inch (3 millimetres) thick; on the upper side beset with numerous circular, cup-shaped scars; closely covered below with simple, wiry rootlets varying from four to twenty inches (10 to 50 centimetres) in length; brittle, dark brown or orange-brown; fracture short, white; odour faint but heavy; taste sweetish, bitter and somewhat pungent.

PREPARATION.

	DOSE.
Extractum Cypripedii Fluidum	15 min.

USE.—It has an **antispasmodic** action similar to that of valerian, but it is less powerful.

ZINGIBERACEÆ.

Zingiber, B. and U.S.P. GINGER.—The (scraped and dried, B.P.) rhizome of *Zingiber officinale.* West Indies, India, and other countries.

CHARACTERS.—Irregular lobed decorticated pieces, three or four inches long, yellowish-white but not chalky on the surface, with a short mealy fracture, hot taste, and agreeable aroma. Powder yellowish-white.

PREPARATIONS.

B.P.	DOSE.
Confectio Opii	5-20 gr.
Confectio Scammonii	10-30 gr.
Infusum Sennæ	1-2 fl. oz.
Pilula Scillæ Composita	5-10 gr.
Pulvis Cinnamomi Compositus	30-60 gr.
Pulvis Jalapæ Compositus	20-60 gr.
Pulvis Opii Compositus	2-5 gr.
Pulvis Rhei Compositus	20-60 gr.
Pulvis Scammonii Compositus	10-20 gr.
Syrupus Rhamni	1 fl. drm.
Syrupus Zingiberis	½-1 fl. drm.
Tinctura Zingiberis	15 min. to 1 fl. drm.
Tinctura Zingiberis Fortior	5-20 min.
Vinum Aloes	1-2 fl. drm.

U.S.P.	
Extractum Zingiberis Fluidum	10-30 min.
Oleoresina Zingiberis	1-2 min.
Pulvis Aromaticus	10-30 gr.
Tinctura Zingiberis	15-75 min.
Pulvis Rhei Compositus	30-60 gr.
Syrupus Zingiberis	1 fl. drm.
Vinum Aloes	1-2 fl. drm.

COMPOSITION.—A yellow volatile oil and a resin, the former having the odour, and the latter the taste, of the drug.

ACTION.—Ginger causes a feeling of warmth in the mouth, and reflexly stimulates the secretion of saliva. It has a stimulant action on the stomach, producing warmth at the epigastrium. It promotes the expulsion of flatus.

USES.—It is used in atonic dyspepsia, also to relieve flatulence, and as an adjunct to purgatives to lessen griping. It is also used as a masticatory to increase secretion of saliva, and in relaxed conditions of the throat. Also used as a **carminative** in colic.

B.P. Turmeric.—The rhizome of *Curcuma longa.*

Turmeric Tincture, B.P. Solution of Turmeric, U.S.P.—A solution prepared by macerating 1 part bruised turmeric in 6 parts rectified spirit, B.P., or diluted alcohol, U.S.P., in a closed vessel for 7 days and filtering.

Turmeric Paper, B. and U.S.P.—Unsized white paper coloured by steeping in tincture of turmeric and drying by exposure to the air without heat.

ACTION AND USES.—Turmeric acts similarly to ginger. Chiefly

used as a **condiment.** Turmeric paper is used as a **test for alkalis,** which turn it brown.

Cardamomum, B. and U.S.P. CARDAMOMS.—The fruit, U.S.P. (dried capsules, B.P.), of *Elettaria Cardamomum.* Malabar. The seeds are best kept in their pericarps, from which they should be separated when required for use, the pericarpial coats being rejected.



FIG. 188.—Cardamoms.

CHARACTERS.—Seeds obtusely angular, corrugated, reddish-brown, internally white, with a warm, aromatic, agreeable taste, contained in ovate-oblong, triangular, pale-brown, coriaceous pericarps.

PREPARATIONS.

B.P.	DOSE.
Tinctura Cardamomi Composita	½-2 fl. drm.
Tinctura Chloroformi Composita	

CONTAINED ALSO IN

Extractum Colocynthidis Compositum	3-10 gr.
Pulvis Cinnamomi Compositus	30-60 gr.
Pulvis Cretæ Aromaticus	10-60 gr.
Tinctura Gentianæ Composita	½-2 fl. drm.
Tinctura Rhei	1-8 fl. drm.
Vinum Aloes	1-2 fl. drm.

U.S.P.

Pulvis Aromaticus	10-30 gr.
Tinctura Cardamomi	1-2 fl. drm.
Tinctura Cardamomi Composita	1-2 fl. drm.

CONTAINED ALSO IN

Tinctura Rhei	1-8 fl. drm.
Tinctura Gentianæ Composita	1-4 fl. drm.
Vinum Aloes	1-2 fl. drm.
Extractum Colocynthidis Compositum	5-20 gr.

COMPOSITION.—Fixed oil and aromatic volatile oil, containing a camphor in solution.

ACTION AND USE.—Cardamoms act similarly to ginger. They are **stimulant,** aromatic, and **carminative,** and are less pungent than ginger. Used chiefly as a carminative in flatulence, and as an adjunct to other medicines to lessen griping.

IRIDACEÆ.

Crocus, B. and U.S.P. SAFFRON.—The stigmas of *Crocus sativus,* U.S.P. The dried stigma, and part of the style, of *Crocus sativus,* B.P. Spain, France, and Italy.

CHARACTERS.—Thread-like styles, each terminated by three long

orange-brown stigmas, broadest at the summit. Has a powerful aromatic odour.

PREPARATIONS.

B.P.	DOSE.
Decoctum Aloes Compositum	½-2 fl. oz.
Pilula Aloes et Myrrhæ	5-10 gr.
Pulvis Cretæ Aromaticus	10-60 gr.
Tinctura Cinchonæ Composita	½-2 fl. drm.
Tinctura Croci	½-2 fl. drm.
Tinctura Opii Ammoniata	½-1 fl. drm.
Tinctura Rhei	1-2 fl. drm. (stomachic).
,, ,,	4-8 fl. drm. (purgative).
	(of dried saffron, 20 gr. upwards.)

U.S.P.	DOSE.
Tinctura Croci	½-2 fl. drm.

COMPOSITION.—The colouring matter of saffron is a glucoside—crocin—soluble in water and easily decomposed by dilute acids. A volatile oil is obtainable both directly from the drug and by the decomposition of crocin. It possesses the odour of saffron.

IMPURITIES.—Saffron is often adulterated with parts of other plants dyed, and with coloured chalk.

TESTS.—By throwing saffron on the surface of warm water, the peculiar form of the stigma is at once seen, and admixture of other plants discovered. The chalk is detected by its immediately rendering the water turbid.

ACTION AND USE.—Saffron has but little action. It is used chiefly as a **colouring agent,** and as a slight **carminative.**

U.S.P. Iris. IRIS. BLUE FLAG.—The rhizome and rootlets of *Iris versicolor.*

CHARACTERS.—Rhizome horizontal, consisting of joints, two to four inches (5 to 10 centimetres) long, cylindrical in the lower half, flattish near the upper extremity, and terminated by a circular scar, annulated from the leaf-sheaths, grey-brown; rootlets long, simple, crowded near the broad end; odour slight; taste acrid, nauseous.

PREPARATIONS.

	DOSE.
Extractum Iridis	2-4 gr.
Extractum Iridis Fluidum	5-10 min.

COMPOSITION.—It owes its medicinal virtues to an oleoresin.

ACTION.—It is **emetic** and **cathartic,** and has been proved by Professor Rutherford to act as a **stimulant to the liver** and the intestinal glands (p. 353).

USES.—In constipation and biliousness.

PALMACEÆ.

B.P. Areca. ARECA NUT.—The seed of *Areca Catechu,* the betel-nut tree.

COMPOSITION.—Oil, containing an acid in solution, and red tannic matter resembling rhatany-red.

DOSE.—As an astringent, 15 to 30 gr. As an anthelmintic, $\frac{1}{2}$ to $\frac{3}{4}$ oz.

USE.—It is much used in veterinary practice, and occasionally in ordinary practice, as an **anthelmintic** for tapeworm. It is also astringent, and is used as a masticatory (p. 161).

ARACEÆ.

U.S.P. Calamus. CALAMUS. SWEET FLAG.—The rhizome of *Acorus Calamus*.

CHARACTERS.—In sections of various lengths, unpeeled, about three-quarters of an inch (2 centimetres) broad, subcylindrical, longitudinally wrinkled; on the lower surface marked with the circular scars of the rootlets in wavy lines; externally reddish-brown, somewhat annulate from remnants of leaf-sheaths; internally whitish, of a spongy texture, breaking with a short, corky fracture, showing numerous oil-cells and scattered wood-bundles, the latter crowded within the subcircular nucleus-sheath. It has an aromatic odour, and a strongly pungent taste.

PREPARATION.

U.S.P.	DOSE.
Extractum Calami Fluidum	15-60 min.

COMPOSITION.—It contains a volatile oil and a bitter principle.

USES.—It is used as a feeble aromatic, **stomachic,** and **stimulant.**

GRAMINACEÆ.

B.P. Farina Tritici. WHEATEN FLOUR.—The grain of wheat, *Triticum vulgare*, ground and sifted.

PREPARATION.

Cataplasma Fermenti.

COMPOSITION.—Starch and gluten.

USE.—Chiefly as an article of **food.**

B.P. Mica Panis. CRUMB OF BREAD.—The soft part of bread made with wheat flour.

PREPARATION.

Cataplasma Carbonis (p. 477).

USE.—It is used as a cataplasm, both alone and in cataplasma carbonis. It is also used as a basis for pills, and especially for making up croton oil into pill. Occasionally pills made of it alone are given as a placebo.

Amylum, B. and U.S.P. STARCH.—The starch procured from the seeds of common wheat, *Triticum vulgare*, B.P. The fecula of the seed of *Triticum vulgare*, U.S.P.

CHARACTERS AND TESTS.—In white columnar or irregular angular masses, white, inodorous, and tasteless. Insoluble in alcohol, ether, or cold water. Easily powdered, and when rubbed in a Wedgwood mortar with a little cold distilled water it is neither acid nor alkaline to test-paper, and the filtered liquid does not become blue on the addition of solution of iodine. Mixed with boiling water and cooled, it gives a deep blue colour with iodine.

PREPARATIONS.

B.P.	DOSE.
Glycerinum Amyli .....1 part in 11 by weight.....	
Mucilago Amyli.....12 gr. to 1 fl. oz.	
Pulvis Tragacanthæ Compositus.....1 part in 6.....20-60 gr.	

U.S.P.

Amylum Iodatum (starch, 95 parts ; iodine, 5 parts).
Glyceritum Amyli (starch, 10 parts ; glycerine, 90 parts).

USES.—The glycerine of starch forms a soothing application for chilblains and chapped hands. Amylum iodatum is really a preparation of iodine(*q.v.*). Starch is also used as a vehicle for enemata. Bandages saturated with it are used in surgery.

U.S.P. Triticum. TRITICUM. COUCH-GRASS.—The rhizome of *Triticum repens*, gathered in the spring and deprived of the rootlets.

CHARACTERS.—Very long, but, as met with in the shops, cut into sections about two-fifths of an inch (1 centimetre) long, and about one-twelfth of an inch (2 millimetres) thick: creeping, smooth, hollow in the centre, straw-yellow, inodorous, and of a sweet taste.

PREPARATION.

	DOSE.
Extractum Tritici Fluidum.....1 fl. drm. to 1 oz.	

USES.—It is used as a **demulcent** and diluent, more particularly in cystitis and irritation of the urinary passages.

It probably owes its diuretic effect to its sugar, and is best given in the form of an infusion or decoction, which may be freely used.

B.P. Hordeum Decorticatum. PEARL BARLEY. — The husked seeds of *Hordeum distichon*. Britain.

CHARACTERS.—White, rounded, retaining a trace of the longitudinal furrow.

COMPOSITION.—Starch, albuminous matter, cellulose, and a small quantity of fixed oil.

PREPARATIONS.

Decoctum Hordei. BARLEY WATER.—Pearl barley, 2 oz. ; boiling water, 30 fl. oz. ; the barley is first washed well in cold water, which is thrown away, and then the barley is boiled for twenty minutes and strained.

USE.—The decoction is used as a demulcent drink.

U.S.P. Maltum. MALT.—The seed of *Hordeum distichum*, caused to enter the incipient stage of germination by artificial means, and dried.

CHARACTERS.—Malt should be fresh, of a colour not darker than pale amber, and should have an agreeable odour and a sweet taste.

PREPARATION.

	DOSE.
Extractum Malti	4 fl. drm.

U.S.P. Extractum Malti. EXTRACT OF MALT.

PREPARATION.—Upon malt in coarse powder, not finer than No. 12, 100 parts, contained in a suitable vessel, pour 100 parts of water, and macerate for six hours. Then add 400 parts of water, heated to about 30° C. (86° F.), and digest for an hour at a temperature not exceeding 55° C. (131° F.). Strain the mixture with strong expression. Finally, by means of a water-bath, or vacuum-apparatus, at a temperature not exceeding 55° C. (131° F.), evaporate the strained liquid rapidly to the consistence of thick honey. Keep the product in well-closed vessels, in a cool place.

DOSE.—4 fl. drm.

ACTION.—This officinal extract of malt is similar to various other extracts and foods prepared from malt. It is not only **nutritious,** but, on account of the diastase contained in it, acts as a **digestive ferment.**

In large doses it relaxes the bowels.

USES.—In cases of imperfect digestion and in phthisis, and in general imperfect nutrition in children or adults.

Saccharum Purificatum, B.P.; Saccharum, U.S.P. REFINED SUGAR, B.P.; SUGAR, U.S.P. $C_{12}H_{22}O_{11}$, or $C_{24}H_{22}O_{12}$; 342. —Pure cane sugar prepared from the juice of the stem of *Saccharum officinarum.* West Indies and other tropical countries. B.P. The refined sugar of *Saccharum officinarum,* U.S.P.

CHARACTERS.—Compact crystalline conical loaves, known in commerce as lump sugar.

IMPURITIES.—Salts, foreign matters.

TESTS.—U.S.P. White, dry, hard, distinctly crystalline granules, permanent in the air, odourless, having a purely sweet taste, and a neutral reaction. Soluble in 0·5 part of water, and in 175 parts of alcohol at 15° C. (59° F.); in 0·2 part of boiling water, and in 28 parts of boiling alcohol; also in 80 parts of boiling, absolute alcohol, but insoluble in ether. The aqueous solution, saturated at 15° C. (59° F.), has the specific gravity 1·345, and is miscible with alcohol in all proportions.

Neither an aqueous nor an alcoholic solution of sugar, kept in large, well-closed, and completely filled bottles, should deposit a sediment on prolonged standing (abs. of insoluble salts, foreign matters, ultramarine, Prussian blue, &c.). If a portion of about 1 gm. of sugar be dissolved in 10 c.c. of boiling water, then mixed

with 4 or 5 drops of test-solution of nitrate of silver and about 2 c.c. of water of ammonia, and quickly heated until the liquid begins to boil, not more than a slight coloration, but no black precipitate, should appear in the liquid after standing at rest for five minutes (abs. of grape-sugar and of more than a slight amount of inverted sugar).

USE.—To mask the taste of disagreeable remedies. It is used as a **vehicle,** corrigent, **preservative,** and antiseptic. Syrups have the advantage of protecting the active ingredients against fermentation, and certain ferruginous preparations against oxidation.

PREPARATIONS.

B.P.

Confectio Rosæ Caninæ.
Confectio Rosæ Gallicæ.
Confectio Sennæ.
Ferri Carbonas Saccharata.
Liquor Calcis Saccharatus.
Mistura Ferri Composita.
Mistura Guaiaci.
Pilula Ferri Iodidi.
Pulvis Cretæ Aromaticus.
Pulvis Amygdalæ Compositus.
Pulvis Tragacanthæ Compositus.
All the Syrups and Lozenges.

U.S.P.

Pilulæ Ferri Carbonatis.
Pilulæ Ferri Iodidi.
Ferri Carbonas Saccharatus.
Mistura Ferri Composita.
Pulvis Cretæ Compositus.
Pulvis Glycerrhizæ Compositus.
Troches, Syrups, Compound Syrups, &c.

B.P. Theriaca. TREACLE.—The uncrystallised residue of the refining of sugar.

CHARACTERS.—A thick brown fermentable syrup, very sweet; not crystallising by rest or evaporation. Specific gravity about 1·40.

TEST.—Nearly free from empyreumatic odour or flavour.

PREPARATIONS.

B.P.

Pilula Assafœtidæ Composita.
Pilula Conii Composita.
Pilula Ipecacuanhæ et Scillæ.
Pilula Rhei Composita.
Pilula Scillæ Composita.

USE.—To make up some of the pills of the Pharmacopœia. With sulphur it is used as a domestic **laxative.**

Avenæ Farina. OATMEAL. Not officinal.—The meal prepared from the seeds of *Avena sativa,* the common oat.

COMPOSITION.—The seeds contain starch, gluten, and gum. The pericarp contains an amorphous alkaloid. This alkaloid is soluble in alcohol. It is more abundant in dark than in light oats. It probably gives to them their bitterish taste.

ACTION.—The alkaloid appears to act chiefly as a stimulant of the **motor ganglia.** It increases the excitability of the **muscles,** and in horses causes excitement.

USES.—Oatmeal is chiefly used for making gruel or porridge, which, in addition to being nutritious, acts as a **demulcent** in coughs, and as a slight **laxative.** Warm oatmeal porridge at bed time may have a **soporific** action (p. 166), though the exciting action of the alkaloid may render panada, indian corn, or lentils preferable. An infusion, decoction, or tincture has been recommended as a **stimulant** to replace opium in persons addicted to opium eating, in order to help them to break off that habit.

CHAPTER XXXVII.

Sub-kingdom II. CRYPTOGAMS.

FILICES.

Filix Mas, B.P.; Aspidium, U.S.P. MALE FERN.—The dried rhizome with the bases of the footstalks and portions of the root fibres of *Aspidium Filix mas.* Collected in summer. B.P. The rhizome of *Aspidium Filix mas* and of *Aspidium marginale,* U.S.P.

CHARACTERS.—Tufted, scaly, greenish-brown; powder greenish-yellow, with a disagreeable odour, and a nauseous, bitter, somewhat astringent taste.

PREPARATIONS.

B.P.	DOSE.
Extractum Filicis Liquidum	15 min. to 1 fl. drm. (of the powder, 60-180 gr.)

U.S.P.	DOSE.
Oleoresina Aspidii	30-60 min.

COMPOSITION.—A dark green oil which deposits crystals of filicic acid, also traces of volatile oil. The filicic acid is regarded as the chief, though not the only, active principle; tannin, resin, and sugar have been found in the rhizome.

PHYSIOLOGICAL ACTION AND THERAPEUTICS.—The liquid extract is one of the best **anthelmintics** against tapeworm, killing the *Bothriocephalus latus, Tænia solum,* and *T. mediocanellata.* Pomegranate root bark is said to kill the latter with greater certainty. The dose often given is too small, and hence failure is attributed to the drug when it really depends on the smallness of the dose. Single doses of ʒi-ʒiss of the liquid extract will often cure at once.

METHOD OF ADMINISTRATION.—Allow the patient to take no food after five or six in the evening except a little bread-and-milk. Just before bed-time give ʒi of the liquid extract in ʒi of mucilage, and let the patient lie down immediately and go to sleep. This often prevents the vomiting which sometimes occurs. Next morning administer a purgative, and repeat the treatment until the worm comes away.

Another method is to give a dose of castor oil at night (with the same conditions of feeding) and early next morning give a dose of liquid extract (ʒss-ʒi), and abstain from food till after the bowels have acted.

LICHENES.

Cetraria, B. and U.S.P. ICELAND MOSS.—The entire lichen. *Cetraria islandica.* North of Europe.

CHARACTERS.—Foliaceous, lobed, crisp, cartilaginous, brownish-white, paler beneath; taste bitter and mucilaginous. A strong decoction gelatinises on cooling.

PREPARATIONS.

B.P.	DOSE.
Decoctum Cetrariæ .....1 oz. to 1 pint	.....1-2 fl. oz.

U.S.P.	DOSE.
Decoctum Cetrariæ	.....2-4 fl. oz.

COMPOSITION.—Lichenin and cetrarin or cetraric acid. The former constitutes 70 per cent. of the moss. It swells in cold, and dissolves in hot water, gelatinising on cooling. The latter, which is the bitter principle, is obtained in white acicular crystals, and forms soluble salts with alkalis.

THERAPEUTICS.—It is **demulcent, nutritious,** and slightly **tonic.**

B.P. Litmus.—A blue pigment prepared from various species of Roccella.

Litmus Paper, Blue, B. and U.S.P.—Unsized white paper steeped in tincture of litmus, and dried by exposure to the air.

Litmus Paper, Red, B. and U.S.P.—Unsized white paper steeped in tincture of litmus which has been previously reddened by the addition of a very minute quantity of sulphuric acid, and dried by exposure to the air.

Litmus Tincture, B.P.; Solution of Litmus, U.S.P.—A solution prepared by macerating 1 part of litmus, in powder, in 10 parts of proof spirit, B.P., or diluted alcohol, U.S.P., in a closed vessel for two days, and filtering.

USE.—Red litmus paper is used as a test for alkalis, and blue litmus as a test for acids.

FUNGI.

Ergota, B. and U.S.P. ERGOT. ERGOT OF RYE.—The sclerotium (compact mycelium or spawn) of *Claviceps purpurea,* produced within the paleæ of the common rye, *Secale cereale,* B.P. (replacing the grain of *Secale cereale,* Nat. Ord. *Graminaceæ,* U.S.P.).

CHARACTERS.—Somewhat fusiform, subtriangular, curved, with a longitudinal furrow on the concave side, obtuse at the ends, about an inch long; purplish black outside, pinkish within, solid, breaks with a short fracture, odour peculiar, but strong if the powder be triturated with solution of potash, taste oily and disagreeable.

PREPARATIONS.

B.P.	DOSE.
Extractum Ergotæ Liquidum	1 oz. to 1 fl. oz. ..... 10-30 min.
Infusum Ergotæ	11 gr. to 1 fl. oz. ..... 1-2 fl. oz.
Tinctura Ergotæ	109 gr. to 1 fl. oz. ... 10 min. to 1 fl. drm.

U.S.P.	DOSE.
Extractum Ergotæ Fluidum, 100 Gm. in 100 cc.	..... 30-60 min.
Vinum Ergotæ	..... 2-4 fl. drm.
Extractum Ergotæ	..... 3-12 gr.

COMPOSITION.—The chemical composition of ergot is still very imperfectly known, and the active principle (or principles) to which its most important action, that of causing contraction of the uterus, is due, has not been satisfactorily isolated. The active principles were formerly said to be ergotin and ecbolin, but these do not seem to be pure substances. The term ergotin has been applied to several substances. The preparation known commercially as Bonjean's ergotin is an alcoholic extract of a watery extract of ergot. According to Schmiedeberg, two pure principles have been isolated—ergotinic acid and an alkaloid, ergotinine. According to Dragendorff and Podwyssotzki, the active principles are sclerotinic acid and a colloid substance, scleromucin. Sclerotinic acid is impure ergotinic acid. In addition to ergotinic acid, ergotinin, and probably several other principles, ergot contains about 35 per cent. of oil, a peculiar sugar (mykose), and two colouring matters, scleroxanthin and sclero-erythrin.

The most recent researches are those of Kobert, who states that ergot contains three active principles: ergotinic acid, sphacelinic acid, and an alkaloid cornutine.

GENERAL ACTION.—There is a great difference of opinion as to the action of ergot, due to its preparations undergoing change so rapidly, and hence not being of the same strength. They become quite inactive if kept for any length of time. In certain parts of Germany, where rye bread is much used, epidemics of **ergotism** have occurred. These epidemics depend both upon the continued large doses of ergot and upon the deficiency of food, the nutritive part of the rye being replaced by the fungus. The deficiency of food is probably an important factor, since continued therapeutic doses of ergot rarely produce ergotism, though occasionally they do so.

There are two varieties of symptoms seen in ergotism: (1) the **gangrenous**; (2) the **anæsthetic** or **convulsive.** Both begin with gastro-intestinal disturbance, causing loss of appetite, nausea, vomiting, and diarrhœa.

The **gangrenous** symptoms are redness of the skin followed by well-marked gangrene in the part. The cause of this gangrene is probably stasis due to the great contraction of the small blood-vessels.

The **nervous symptoms** are giddiness, with symptoms of irritation and paralysis of sensory nerves, the irritation being indicated by a sensation as of insects crawling over the skin, flying pains, &c., the paralysis by loss of sensation in the hands and feet. Spasms may occur, and even convulsions of an epileptic nature, but their cause is unknown.

SPECIAL ACTION.—**Ergotinic acid** causes paralysis of the spinal cord both in frogs and mammals, with loss of voluntary motion, paralysis of the vaso-motor centre, and fall of blood-pressure, while respiration and reflex irritability continue. It does not appear to have the power of increasing the uterine contractions, and so cannot be regarded as the most important constituent of ergot. **Ergotinine** is also not the active principle, as it is present in very small quantity in ergot, and is to some extent removed by ether without the ergot losing its power.

Sphacelinic acid causes contraction of the blood-vessels, with rise of blood-pressure and symptoms of gangrene. The heart is unaffected. The gangrene in fowls appears to be due to occlusion of the smaller arteries by a hyaline substance. In rabbits, guinea-pigs, and cats the substance is not formed, and no gangrene appears, but their walls degenerate, and blood is effused into various organs. Sphacelinic acid causes tetanus of the uterus (Kobert). **Cornutine** causes spastic rigidity in **frogs,** lasting many days, even when given in very minute doses ($\frac{1}{32}$ of a milligramme). In warm-blooded animals half a milligramme causes salivation, vomiting, diarrhœa, and active movements of the uterus, which are clonic and not tonic. The vessels are contracted and the blood-pressure raised. Sphacelinic acid and cornutine are therefore the principles which cause uterine contraction (Kobert). As these active principles have not yet found their way into common use, it will be better at present to take the results of experiments, not with pure principles isolated from ergot, but only of an extract such as Bonjean's ergotin.

Action of Extract of Ergot.—A solution of Bonjean's ergotin injected into animals causes an affection of the **nervous system** indicated by incoordination, anæsthesia, and paralysis; and death is due to paralysis of respiration.

The **muscles** are unaffected; the motor nerves are not paralysed, but on the contrary have their power somewhat increased.

The **sensory nerves** are paralysed, but it is uncertain whether the action is central or peripheral. The **spinal cord** is paralysed.

Circulation. Heart.—Its action on the frog's heart is not well marked; sometimes the injection of ergot produces slowing of the pulse-rate with stoppage in diastole, and in these cases direct

mechanical irritation immediately after the poisoning does not cause the heart to contract.

Slowing and diastolic arrest occur after section of the vagi, but not after administration of atropia; hence they are due to the action of the ergot on the inhibitory apparatus in the heart itself.

Vaso-motor System.—The blood-pressure is considerably raised. When injected into the jugular vein, the blood-pressure, according to Holmes, is first lowered and then raised considerably, which he explains by supposing that the ergot passing to the right side of the heart causes contraction of the vessels of the lungs (by acting on their muscular walls), and hence lessens the supply to the aortic system and causes a fall of blood-pressure, but when it reaches the medulla it stimulates the vaso-motor centre, and causes contraction of the vessels throughout the body and consequent rise of blood-pressure. This explanation is confirmed by the fact that if ergot is injected into the femoral artery, instead of a fall occurring at first there is a rise due to contraction of vessels in the limb, then a fall as soon as the blood reaches the lungs, and lastly a final rise.

This explanation is not accepted by Wood, who considers that the primary fall is due to the sudden introduction of a large quantity of ergot into the heart causing temporary paralysis, which will pass off as the drug is removed by the circulation.

The final rise of blood-pressure no doubt is due to the action on the medulla, for, if the cord be divided, very little rise follows the injection of ergot.

One other factor, which usually receives very little attention, must be taken into account (as well in this drug as in many others), viz. the effect on the blood-pressure of contraction of the internal viscera, as the intestines or uterus, for by contraction their blood will be driven out, and a rise of blood-pressure produced without any action on the vessels.

Respiration is usually slowed from the beginning, but in some animals (dogs) it is first quickened and then slowed. Death is due to paralysis of the respiratory centre.

Secretion.—The urine is increased in quantity, and the bladder tends to contract, due to the effect of the drug on its unstiped fibres.

Alimentary Canal.—Ergot markedly increases the peristaltic movements of the intestine.

Uterus.—Ergot causes contraction of the uterus, especially of the pregnant uterus. This contraction is not usually so much rhythmical as **tetanic** in nature, with occasional increases in violence. There is no complete relaxation between the spasms, as in the ordinary labour-pains. This is probably due to an action on the unstriped fibres of the uterus, since ergot causes contraction of involuntary fibres throughout the body, but it may be due wholly or in part to the uterine centre in the spinal cord.

THERAPEUTICS.—Ergot is chiefly used in medicine for two purposes: (1) to cause contraction of the uterus; (2) to check hæmorrhage by causing contraction of the vessels.

It is sometimes used to hasten delivery when the power of the uterine contractions is not sufficient to expel the fœtus. But the tetanic nature of the contraction produced by ergot must be borne in mind. It does not increase the power of the labour-pains, but only the tonic contraction of the uterus. It should be carefully avoided if there be any mechanical obstruction to delivery, such as rigid and undilated os uteri, contracted pelvis, or abnormal presentation, for in such cases it may so far interfere with the circulation in the uterus and placenta as to asphyxiate the fœtus, or cause such contraction of the uterus as to produce rupture of its walls. After the child is expelled, the tetanic nature of the contraction produced by ergot is useful, and hence it is used to prevent post-partum hæmorrhage. In these cases, it is administered either in the form of powdered ergot in warm water, or the liquid extract, or by subcutaneous injection of ergotin. The last method gives the most rapid results, but if the ergotin is injected just beneath the skin it causes irritation and may lead to an abscess, hence it should be injected deep into a muscle, such as the gluteus maximus.

Ergot is also used very largely in the practice of gynæcology, for example, in chronic metritis, in sub-involution of the uterus, after abortions, to promote the expulsion of retained membranes, and in all atonic conditions of the uterus.

It is also used in certain cases of leucorrhœa, also in atony of the bladder and enlarged prostate.

It is used to check hæmorrhage in fibroid tumours of the uterus; in hæmoptysis (either internally ʒss. of liquid extract every two, three, or four hours, or subcutaneously injected). In hæmatemesis also it is sometimes useful.

In some cases of chronic constipation it is useful, and appears to give tone to the bowel.

U.S.P. Ustilago. USTILAGO. CORN SMUT.—*Ustilago Maydis* (Nat. Ord., *Fungi*), grown upon *Zea Mays* (Nat. Ord., *Graminaceæ*).

Ustilago should be preserved in a dry place, and should not be kept longer than a year. This fungus is a form of smut growing upon maize.

CHARACTERS.—Irregular, globose masses, sometimes six inches (15 centimetres) thick, consisting of a blackish membrane, inclosing innumerable, brownish-black, globular and nodular spores; odour and taste unpleasant.

DOSE.—¼-1 dr. (1-4 Gm.)

ACTION.—It **resembles ergot** in its action, and probably also contains the same alkaloid.

B.P. Cerevisiæ Fermentum. BEER YEAST.—The ferment obtained in brewing beer.

CHARACTERS.—Viscid, semi-fluid, frothy, exhibiting under the microscope numerous round or oval confervoid cells (p. 67).

DOSE.—$\frac{1}{2}$-1 oz.

PREPARATION.

Cataplasma Fermenti. YEAST POULTICE.—Mix beer yeast, 6 fl. oz., with water at 100° F., 6 fl. oz., stir in wheaten flour, 14 oz., and place the mass near the fire till it rises.

USE.—It has been given internally along with camphor and nitrous ether, in typhoid fever and dysentery, and to persons suffering from boils. The poultice is applied to sloughing sores. It is apt to cause much pain.

ALGÆ.

U.S.P. Chondrus. CHONDRUS. IRISH MOSS. — *Chondrus crispus* and *Chondrus mammilosus.*

CHARACTERS.—Yellowish or white, horny, translucent; many-forked; when softened in water, cartilaginous; segments flat, wedge-shaped, or linear; at the apex emarginate or two-lobed; it has a slight seaweed-odour, and a mucilaginous, somewhat saline taste. One part of it boiled for ten minutes with thirty parts of water, yields a solution which gelatinises on cooling.

DOSE.—2-4 drm.

USE.—It is a **demulcent,** which is useful in bronchial and catarrhal affections.

SECTION VI.

ANIMAL KINGDOM.

CHAPTER XXXVIII.

Class MAMMALIA. Order RODENTIA.

B.P. Castoreum. Castor.—The dried preputial follicles and their secretion, obtained from the beaver, *Castor fiber*, and separated from the somewhat shorter and smaller oil-sacs which are frequently attached to them. Hudson's Bay Territory.

Characters.—Follicles in pairs, about three inches long, fig-shaped, firm, and heavy, brown, or greyish-black; containing a dry resinous reddish-brown or brown highly odorous secretion, in great part soluble in rectified spirit, and in ether.

Composition.—Several fats, salicin, a bitter resin, and bitter volatile oil.

Preparation.

B.P.	Dose.
Tinctura Castorei.....22 gr. to 1 fl. oz. (of castor, 5-10 gr.)	.....½-1 fl. drm.

Therapeutics.—Castor is used chiefly as an **antispasmodic** and stimulant. It may be given in hysteria and epilepsy. Its action is very like that of musk.

Order RUMINANTIA.

Moschus, B. and U.S.P. Musk.—The inspissated and dried secretion from the preputial follicles of *Moschus moschiferus*. Central Asia.

Characters.—In irregular reddish-black rather unctuous grains; having a strong, peculiar, very diffusible odour, and a bitter aromatic taste; contained in a round or slightly oval membranous sac, about two inches in diameter, covered on the outer side with stiff, greyish hairs arranged in a concentric manner around its central orifice.

Composition.—An odoriferous substance not yet isolated, fats, resins, and salts.

Dose.—5-10 gr. and upwards.

OFFICINAL PREPARATION.

U.S.P.	DOSE.
Tinctura Moschi	20-50 min.

THERAPEUTICAL USES.—Musk is often employed in hysteria, although its physiological action has not been investigated. It is more powerful in its action than castor. It is used as an **anti-spasmodic** and **stimulant.** It is a powerful stimulant, and excellent results have been obtained in cases of collapse, when due to paralysis of the respiration. It has also been given in asthenic pneumonia, bronchitis, fever, and gangrene of the lungs on account of its power of **stimulating** the **respiratory centre** and covering the disagreeable odour of the sputa. There is a temptation to give it in small doses on account of its high price, and probably many failures are due to this. In cases where it is prescribed at all it should be given freely, and in many instances it seems to be of great service.

Sevum Præparatum, B.P.; Sevum, U.S.P. PREPARED SUET, B.P.; SUET, U.S.P.—The internal fat of the abdomen of the sheep, *Ovis Aries*, purified by melting and straining.

CHARACTERS.—White, smooth, almost scentless; fusible at 103°.

COMPOSITION.—Consists principally of stearin.

PREPARATIONS.

Emplastrum Cantharidis. Unguentum Hydrargyri.

USE.—Used in the preparation of certain unguenta and emplastra.

B.P. Sapo Animalis. CURD SOAP.—A soap made with soda and a purified animal fat, consisting principally of stearine.

CHARACTERS AND TESTS.—White, or with a very light greyish tint; dry; nearly inodorous; horny and pulverisable when kept in dry, warm air. Easily moulded when heated. Soluble in rectified spirit; soluble also in hot water, the solution being neutral or only slightly alkaline to test-paper. It does not impart a greasy stain to paper.

PREPARATIONS IN WHICH CURD SOAP IS USED.

Pilula Scammonii Composita.
Suppositoria Acidi Carbolici cum Sapone.
,, Morphiæ cum Sapone.
,, Acidi Tannici cum Sapone.

This soap may with advantage be substituted for the hard soap made with olive oil in preparing the *Linimentum Potassii Iodidi cum Sapone.*

B.P. Lac. MILK.—The fresh milk of the cow, *Bos Taurus.*

PREPARATION IN WHICH MILK IS USED.

Mistura Scammonii.

COMPOSITION.—Fat (butter), casein, milk, sugar, and water.

THERAPEUTICS.—Milk is not strictly speaking a medicine, but rather an article of **diet:** it however plays an important part in medicine, as we rely on it to a great extent in cases of fever and dyspepsia.

Great attention ought to be paid to the milk given to infants if they are fed from the bottle, for the milk may begin to ferment before it reaches the stomach, and, if it does, it is likely to cause vomiting and diarrhœa, and may even act as a nervous poison, paralysing the nerve centres. The best way to prevent this is not to have any tubes to the bottles, but to have the teat fixed directly to the bottle, and to scald the bottle well after every meal. The teats should also be soaked in some antiseptic, such as permanganate of potash and water, when not in use. When milk is drunk in any quantity, the rennet-ferment in the stomach produces large curds, which are sometimes hard like felt, and are very indigestible and irritating to the stomach; hence, in typhoid fever the possibility of these curds should be borne in mind. The milk will not readily curdle if mixed with its own bulk of water or soda-water, or (if diarrhœa be present) with lime-water. One may often with advantage use **koumiss,** which is made in the steppes of Tartary by fermenting mares' milk. Consumption is so rare in Tartary, that Russians suffering from phthisis go to the steppes, and numbers have been cured. No doubt other factors aided the cure, such as climate and change of air, but even in the same conditions of life koumiss often helps to keep the disease in check. It can be made artificially from grape sugar and cows' milk which is allowed to ferment. It is a good stimulant, and is useful in cases of phthisis. It contains lactic acid, alcohol, casein, and fat thrown down in small flakes.

Milk may be used with ferments such as pepsin or pancreatin. The mixture is allowed to stand for a time, and then boiled to stop the fermentation.

Cows' milk diluted with one or more parts of water and a little milk-sugar added, forms a good substitute for human milk as food for infants.

Saccharum Lactis, B. and U.S.P. SUGAR OF MILK.—$C_{12}H_{24}O_{12}$ or $C_{24}H_{24}O_{24}$; 360.—A peculiar crystalline sugar, obtained from the whey of cows' milk by evaporation and purified by re-crystallisation.

CHARACTERS.—Usually in cylindrical masses, two inches in diameter, with a cord or stick in the axis, or in fragments of cakes; greyish-white, crystalline on the surface and in its texture, translucent, hard, scentless, faintly sweet, gritty when chewed. Soluble in 7 parts of water at 15° C. (59° F.), and in 1 part of boiling water; insoluble in alcohol, ether, or chloroform. On adding to a solution of sugar of milk in an equal weight of boiling water

some solution of soda, the liquid turns brownish, and, on further addition of test-solution of sulphate of copper, a brick-red precipitate separates.

IMPURITY.—Cane sugar.

TEST.—If 1 part of sugar of milk be sprinkled upon 5 parts of sulphuric acid contained in a flat-bottomed capsule, the acid should acquire not more than a greenish or reddish, but no brownish or brownish-black colour within one hour (absence of cane sugar).

USES.—Sugar of milk is used as a **diluent** in the abstracts, denarcotised opium, &c., of the U.S.P. It is harder, less sweet, and less soluble than cane sugar, and hence is a better **excipient** and diluent for powders that require trituration.

B.P. Pepsin. PEPSIN.—A preparation of the mucous lining of a fresh and healthy stomach of the pig, sheep, or calf.

The stomach of one of these animals recently killed having been cut open, and laid on a board with the inner surface upwards, any adhering portions of food, dirt, or other impurity, are to be removed and the exposed surface slightly washed with cold water; the cleansed mucous membrane is then to be scraped with a blunt knife or other suitable instrument; and the viscid pulp thus obtained is to be immediately spread over the surface of glass or glazed earthenware, and quickly dried at a temperature not exceeding 100° Fahr.

DOSE.—Of pepsin, 2-10 gr. given with a meal.

U.S.P. Pepsinum Saccharatum.—Pepsin, the digestive principle of the gastric juice, obtained from the mucous membrane of the stomach of the hog, and mixed with powdered sugar of milk.

Saccharated pepsin is a white powder of a slight but not disagreeable odour and taste, and a slightly acid reaction. It is not completely soluble in water, leaving floccules of pepsin floating in the solution, which, however, dissolve on the addition of a small quantity of hydrochloric acid. Strong turbidity of the acidulated solution indicates the presence of mucus, which also imparts to the saccharated pepsin a disagreeable odour and taste, and will eventually impart to it an ammoniacal odour.

U.S.P. PREPARATION.

	DOSE.
Liquor Pepsini	2-4 fl. drm.

THERAPEUTICS.—Pepsin is given as an **aid to digestion,** when the ordinary stimuli do not excite sufficient secretion, and the digestive ferment is insufficient. Such cases occur during a long illness or during recovery from an acute disease, in old people, and in people with atrophy of the mucous membrane and glands of the stomach, due to alcoholic excesses or long-continued dyspepsia.

It may be given either with or just after meals. It has no influence on farinaceous foods or fat, but only acts on gelatinous and albuminous matter; hence it is no use giving it after farinaceous or fatty food.

In these cases the secretion of acid is usually defective, and a little dilute hydrochloric acid given along with pepsin, and again about two hours after meals, is very useful.

In some cases of asthma, dependent on insufficient digestion, pepsin is very useful. Pepsin wines and essences usually contain little or no pepsin, and have little digestive power, but they contain rennet, and are frequently of use in indigestion in children; they also appear serviceable in adults.

U.S.P. Fel Bovis. Ox Gall.—The fresh gall of *Bos Taurus.*

Characters.—A brownish-green, or dark green, somewhat viscid liquid, having a peculiar odour, a disagreeable bitter taste, and a neutral or faintly alkaline reaction. Specific gravity 1·018 to 1·028. A mixture of 2 drops of ox gall and 10 c.c. of water, when treated first with a drop of freshly prepared solution of 1 part of sugar in 4 parts of water, and afterwards with sulphuric acid until the precipitate first formed is redissolved, gradually acquires a cherry-red colour, changing successively to carmine, purple, and violet.

Preparations.

Fel Bovis Inspissatum. Fel Bovis Purificatum.

U.S.P. Fel Bovis Inspissatum. Inspissated Ox Gall.

Heat the ox gall to a temperature not exceeding 80° C. (176° F.), strain it through muslin, and evaporate the strained liquid, on a water-bath, in a porcelain capsule, from 100 parts to 15 parts.

Fel Bovinum Purificatum, B.P.; Fel Bovis Purificatum, U.S.P. Purified Ox Bile.—The purified gall of the ox, *Bos Taurus.*

Preparations.

U.S.P.	DOSE.
Fel Bovis Inspissatum	
,, ,, Purificatum	8-15 gr.

Preparation.—Mix fresh ox bile (1 pint) and rectified spirit (2 pints) by agitation in a bottle, and set aside for twelve hours until the sediment subsides. Decant the clear solution, and evaporate it in a porcelain dish by the heat of a water-bath, until it acquires a suitable consistence for forming pills, B.P. Evaporate ox gall 3 parts in a water-bath to 1 part. Add alcohol 1 part. After twenty-four hours decant, filter, distil off the alcohol, and evaporate to a pilular consistence, U.S.P.

Characters and Tests.—A yellowish-green substance, having a taste partly sweet and partly bitter, soluble in water and in

spirit. A solution of one or two grains of it, in about a fluid drachm of water, when treated, first with a drop of freshly made syrup consisting of one part of sugar and four of water, and then with sulphuric acid cautiously added until the precipitate at first formed is redissolved, gradually acquires a cherry-red colour, which changes in succession to carmine, purple, and violet. Its watery solution gives no precipitate on the addition of rectified spirit.

COMPOSITION. — Tauro-cholic and glyco-cholic acids, mucus, cholesterin, fats, and salts.

DOSE.—Of purified bile, 5-10 gr. or more, formed into pills or given in small gelatin capsules. When the object is to affect the intestines rather than the stomach, the latter mode is preferable.

ACTION AND USES.—Bile precipitates pepsin and interferes with the digestion of albuminous substances in the stomach. It seems also to irritate the mucous membrane and give rise to headache and vomiting. It does not aid the digestion of farinaceous food. It quickens the absorption of fats, it prevents to some extent putrefactive changes in the intestinal contents, and it quickens peristaltic action. Some purgatives, such as aloes and jalap, only act when mixed with bile. It is therefore a useful adjunct to them in cases of jaundice with deficiency of bile in the intestine. It is sometimes used in dyspepsia with constipation, and is given by some along with opium in order to prevent the constipating effect of the latter. Its action in preventing putrefactive changes in the intestine may sometimes be useful in cases of indigestion where these occur (p. 81), and where the flatus has consequently a very disagreeable odour. In order to prevent its local action on the stomach, it may be given as pills coated with keratin.

Keratin. Not officinal.

PREPARATION.—Horn turnings are digested with artificial gastric juice until all the matter soluble in them has been removed. They are then allowed to lie for some weeks in ammonia or glacial acetic acid, which gradually dissolves them. The solvent is then allowed gradually to evaporate until a mucilaginous solution is obtained.

CHARACTERS.—The solution resembles gum in appearance, and when dry forms yellow or yellowish-brown scales. When dried, keratin is absolutely insoluble in gastric juice, but dissolves readily in the juices of the intestine.

USES.—To coat pills containing any substance which we wish to act upon the intestine without acting on the stomach. These are:

1. Such substances as irritate the gastric mucous membrane when long used, *e.g.* arsenic, all anthelmintics, salicylic acid, creosote, chrysarobin, copaiba, cubebs, digitalis, preparations of iron—and especially the iodide and chloride, preparations of mercury—especially the perchloride and periodide, opium, phosphorus, quinine, tartarated antimony.

2. Such substances as impair digestion in the stomach by forming insoluble precipitates with pepsin and peptones, *e.g.* tannic acid, alum, acetate of lead, subnitrate of bismuth, nitrate of silver, corrosive sublimate.

3. Such substances as are partly rendered inert by the gastric juice, and partly decomposed in an undesired manner, *e.g.* alkalies, soap, bile, calcium sulphide, ferric sulphide, charcoal, nitrate of silver, iodide of iron, green and red iodides of mercury, &c.

4. Medicines which we wish to introduce into the duodenum in as concentrated a form as possible, *e.g.* kousso, extract of male fern, santonin, nitrate of silver, acetate of lead or tannin in ulceration of the bowels, bile, charcoal, soaps, and alkalies, &c.

5. Medicines of which we desire the remote without the local action, *e.g.* iron, quinine, arsenic in gastric catarrh, in anæmia, in cardialgia and gastric ulcer.

MODE OF APPLICATION.—The medicine is thoroughly mixed with marsh-mallow powder, liquorice powder, or charcoal, and a few drops of almond oil. It is then made into a pill mass with cacao butter. After the pills have been made of the proper size they are covered with a thin coating of cacao butter, and then with one, or better still with two or three, coats of keratin.

Usually the solution of keratin in ammonia is employed, but the solvent least likely to decompose the medicine may be employed, and thus the acetic acid solution may be used for the chloride of iron or mercury, or salicylic acid.

ORDER **PACHYDERMATA.**

Adeps Præparatus, B.P.; Adeps, U.S.P. PREPARED LARD, B.P.; LARD, U.S.P.—The purified fat of the hog, *Sus scrofa*, B.P.; the prepared internal fat of the abdomen of *Sus scrofa* purified by washing with water, melting, and straining, U.S.P.

IMPURITIES.—Rancidity due to acrid fatty acids, alkalies, common salt, starch, water.

CHARACTERS AND TESTS.—A soft white fatty substance, melting at about 100°. Has no rancid odour; dissolves entirely in ether. Distilled water in which it has been boiled should not acquire an alkaline reaction (absence of alkalies). A portion of the water when cooled and filtered, and another portion acidulated with nitric acid, should give no precipitate with nitrate of silver (absence of salt), and is not rendered blue by the addition of solution of iodine (no starch). When heated for several hours on the water-bath, under frequent stirring, lard should not diminish sensibly in weight (absence of water).

PREPARATIONS

B.P.

Adeps Benzoatus.
Emplastrum Cantharidis.
Unguentum Aconitiæ.
,, Atropiæ.
,, Belladonnæ.
,, Hydrargyri.
,, ,, Nitratis.
,, ,, Subchloridi.
Unguentum Iodi.
,, Potassæ Sulphuratæ.
,, Potassii Iodidi.
,, Sabinæ.
,, Simplex.
,, Sulphuris Iodidi.
,, Terebinthinæ.
,, Veratriæ.

U.S.P.

Adeps Benzoinatus.
Ceratum Resinæ.
Unguentum.
Ceratum.
,, Camphoræ.
,, Cantharidis.
,, Extracti Cantharidis.
,, Plumbi Subacetatis.
,, Sabinæ.
Unguentum Acidi Carbolici.
,, Hydrargyri.
,, ,, Oxidi Flavi.
,, ,, ,, Rubri.
,, Mezerei.
,, Acidi Gallici.
Unguentum Acidi Tannici.
,, Belladonnæ.
,, Chrysarobini.
,, Gallæ.
,, Hydrargyri Ammoniatæ.
,, Iodi.
,, Iodoformi.
,, Plumbi Carbonatis.
,, ,, Iodidi.
,, Potassii ,,
,, Stramonii.
,, Sulphuris.
,, ,, Alkalinum.
,, Veratrinæ.
,, Zinci Oxidi.

Adeps Benzoatus, B.P.; Adeps Benzoinatus, U.S.P. BENZOATED LARD.

PREPARATION.—By mixing powdered benzoin (2 parts, U.S.P.; 2 drachms, B.P.) with melted lard (100 parts, U.S.P.; 1 lb. B.P.), and straining. The benzoin prevents the lard from becoming rancid.

USES.—Lard is **emollient.** It is used in the preparation of ointments, and spread upon poultices to prevent them from getting dry or sticking to the surface of the body.

ORDER **CETACEÆ.**

Cetaceum, B. and U.S.P. SPERMACETI.—A peculiar, concrete, fatty substance obtained from *Physeter macrocephalus*, U.S.P. Nearly pure cetine, obtained, mixed with oil, from the head of the sperm whale, *Physeter macrocephalus*, inhabiting the Pacific and Indian Oceans. It is separated from the oil by filtration and pressure, and afterwards purified, B.P.

CHARACTERS AND TESTS.—Crystalline, pearly-white, glistening, translucent, with little taste or odour, reducible to powder by the addition of a little rectified spirit. Scarcely unctuous to the touch; does not melt under 100°.

PREPARATIONS.

B.P.

Charta Epispastica. Unguentum Cetacei.

U.S.P.

Ceratum Cetacei. Unguentum Aquæ Rosæ.

USE.—It is used as an **emollient** external application.

Class AVES. ORDER GALLINÆ.

B.P. Albumen Ovi. EGG ALBUMEN.—The liquid white of the egg of *Gallus banckiva*, var. *domesticus*.

CHARACTERS.—Transparent, viscid, soluble in water, coagulable on heating to 160° F. When coagulated it is opaque and insoluble in water. It is coagulated by ether.

U.S.P. TEST-SOLUTION OF ALBUMEN.—A solution, recently prepared by triturating the white of one egg with 100 cubic centimetres of distilled water and filtering through cotton moistened with distilled water.

Ovi Vitellus, B.P.; Vitellus, U.S.P. YOLK OF EGG.—The yolk of the egg of *Gallus banckiva*, var. *domesticus*.

PREPARATIONS.

B.P. U.S.P.

Mistura Spiritus Vini Gallici. Glyceritum Vitelli.

PROPERTIES.—Yellow, coagulated on heating, contains vitellin, also cholesterin, and fats, together with salts of lime, &c.

B.P. Mistura Spiritus Vini Gallici.—Is prepared by rubbing up the yolk of an egg with ½ oz. of fine sugar, then adding one wineglassful (2 fl. oz.) of brandy and another of cinnamon-water, and beating them all up together.

THERAPEUTICS.—White of egg forms insoluble albuminates with a number of metals, and hence is employed as an **antidote** in cases of poisoning (especially in the cases of corrosive sublimate and sulphate of copper); in these cases the albuminates generally dissolve readily enough in the gastric juice, and therefore you must give an emetic at once.

The white and yolk of egg are useful as **nutritious** articles of diet, and in the form of egg flip (mistura spiritus vini gallici) is much used in exhausted conditions of the system. One case in which eggs are very useful is cancer of the rectum, since being entirely absorbed in the alimentary canal, disturbance in the rectum is avoided. A good mixture is the white of three eggs, the yolk of two, and a quarter of a pint of beef-tea, beat up separately and then together, put in hot water until set, and given in two or three portions.

Eggs are often mixed with a little pancreatin, and administered as enemata.

Class PISCES. ORDER STURIONES.

Ichthyocolla, U.S.P.; Isinglass, B.P.—The swimming-bladder or sound of *Acipenser huso*, and other species of *Acipenser*.

PROPERTIES.—In fine shreds, B.P.; in separate sheets, &c., U.S.P.

COMPOSITION.—It consists of gelatine, which is precipitated by tannic acid.

PREPARATIONS.

B.P.	U.S.P.
Solution of gelatine.	Emplastrum Ichthyocollæ (Court Plaster).

ORDER TELEOSTEÆ. fam. GADIDÆ.

Oleum Morrhuæ, B. and U.S.P. COD-LIVER OIL.—A fixed oil extracted from the fresh livers of the cod, *Gadus morrhua*, B.P. (or of other species of Gadus, U.S.P.), by the application of a heat not exceeding 180°.

CHARACTERS AND TEST.—Pale yellow, with a slight fishy odour, and bland fishy taste. A drop of sulphuric acid added to a few drops of the oil on a porcelain slab develops a violet colour, which soon passes to a yellowish or brownish red.

COMPOSITION.—Contains olein (7 per cent), palmitin (25 per cent.), and some stearin, also minute traces of iodides, and a peculiar substance probably allied to biliary acids.

DOSE.—From 1 to 8 fl. drm.

PHYSIOLOGICAL ACTION.—Cod-liver oil is rather a **food** than a medicine, and its therapeutical use depends on two properties, viz., its ready absorption and its ready assimilation.

Its **ready absorption** is probably partly due to the presence of biliary matters in the oil, since oil passes more readily through a membrane when it is moistened with bile. If you take two loops of intestine and fill one with ordinary oil and the other with cod-liver oil, and replace them, the one with cod-liver oil will lose more in the same time than that containing ordinary oil.

It is **readily assimilated,** and hence it is used in all diseases where nutrition is slow, as in enlarged glands, catarrhal pneumonia, bronchitis, &c. By means of its property of stimulating nutrition, cod-liver oil improves all the functions of the body, but has no specific action on any of the organs themselves. When large quantities of the oil are taken into the stomach they cause vomiting, but if the oil be finely divided previously, it can be taken without discomfort. Hence it is advisable, when giving it in any quantity, to make it into an emulsion. Potash is sometimes used, but in the stomach the potash is probably neutralised, the

emulsion decomposed, and the oil liberated. A better method is to mix it with an equal volume of mucilage of acacia and a few drops of oil of lemon; this emulsion is not decomposed by the acid of the stomach. The oil can also be mixed with isinglass and taken as jelly. Some people take it best by putting a little salt on the tongue before, and eating a piece of bread after the oil. It is often digested if taken with a little ether, for the ether stimulates the pancreatic secretion.

The oil must not be pressed if it causes nausea or diarrhœa, —for it is a food and not a medicine, and must not be given if detrimental to the appetite.

It can sometimes be taken in a single dose at bed-time, when it cannot be retained during the day. It is rarely well borne when taken on an empty stomach, but is best retained when given not immediately after, but from half an hour to two hours after a meal. Probably the partially digested food then forms it into an emulsion.

THERAPEUTICS.—Cod-liver oil is used in all diseases arising from defective nutrition and in all scrofulous conditions, and as a food during chronic illnesses and in convalescence from acute diseases.

In children emaciated with diarrhœa, a useful mixture is vinum ferri and cod-liver oil; it must not be given in such quantities as to increase the diarrhœa. Often it will also relieve constipation in children.

Its nutritive properties are especially directed to glandular tissues; hence it is used in all cases of enlarged glands, as in tabes mesenterica.

In malnutrition of the heart, and defective circulation, it improves the condition of the heart, increases the red corpuscles, and to some extent also the white corpuscles; hence it is useful in old people with giddiness and a tendency to syncope.

It is also used in chronic rheumatism and tertiary syphilis.

It is also a tonic to the nervous system, and is of great service in cases of nervous debility consequent on hard work, worry, or acute disease. It is used in neuralgia with iron and port wine. In hysteria in middle-aged persons, it is often serviceable.

In rickets it may be given alone or in combination with phosphate of lime.

In inflammations, as bronchitis, newly developed cells are present in great abundance, but nutrition is so defective that they cannot take on the character and functions of mucous cells, and hence, in order to allow them to form a new mucous membrane, they must be supplied with a readily assimilable nutritive material; this is probably the explanation of the benefit obtained by the use of cod-liver oil in bronchitis and other diseases dependent on malnutrition.

In chronic bronchitis, with violent cough and abundant sweetish expectoration, it gives great relief.

In phthisis it is of great service, and is used in all stages of the disease except when the temperature is very high; especially is it useful in the first stage where there is little consolidation. Under its use the patient gains flesh, keeps the disease in check, and even sometimes becomes cured.

In catarrhal conditions of other mucous membranes besides those of respiration it is very useful, as in ozæna in children recovering from measles, and in otitis after scarlet fever.

Class INSECTA. Order HYMENOPTERA.

Mel, B. and U.S.P. Honey.—A saccharine secretion deposited in the honeycomb by *Apis mellifica*, the hive bee.

Characters.—When recently separated from the honeycomb, it is a viscid translucent liquid, of a brownish-yellow colour, which gradually becomes partially crystalline and opaque. It has a peculiar heavy odour, and a very sweet taste.

Composition.—Chiefly glucose and levulose.

Impurities.—Starch, common salt, sulphates, grape sugar, and other foreign substances.

Test.—Water boiled with it for five minutes and allowed to cool does not become blue or green with the solution of iodine (absence of starch).

If 1 part of honey be dissolved in 4 parts of water, a clear solution should result, which should not be rendered more than faintly opalescent by a few drops of test-solution of nitrate of silver (chloride), or of nitrate of barium (sulphate). If a small portion of honey be diluted with 1 volume of water and then gradually mixed with 5 volumes of absolute alcohol, it should not become more than faintly opalescent and should neither become opaque, nor deposit a slimy substance at the bottom and along the sides of the test-tube. When incinerated in small portions at a time, in a platinum crucible, it should not leave more than 0·2 per cent. of ash (any larger percentage of ash and failure to respond to the preceding tests indicating the presence of glucose or other foreign admixtures).

Officinal Preparations.

B.P.	DOSE.
Mel Depuratum (melted and strained)	Ad lib.
Of Mel Depuratum—	
Oxymel (honey, 40; acetic acid, 5; water, 5)	1 fl. drm. to 1 fl. oz.
Mel Boracis	
Oxymel Scillæ	
Confectio Piperis	
,, Scammonii	
,, Terebinthinæ	

U.S.P.

Mel Despumatum (warmed and strained).
Confectio Rosæ.
Mel Rosæ.

USE.—It is slightly **laxative**—chiefly used as a **vehicle.** Oxymel is the old-fashioned household remedy of honey and vinegar, and is used for colds and sore throats.

Cera Flava, B. and U.S.P. YELLOW WAX.—The prepared honeycomb of the hive bee, *Apis mellifica*, B.P.; a peculiar concrete substance prepared by *Apis mellifica*, U.S.P.

CHARACTERS.—Yellowish, or yellowish-brown, solid, firm, breaking with a granular fracture, having an agreeable honey-like odour.

COMPOSITION.—Cerin and myricin.

IMPURITIES.—Fats, fatty acids, Japan wax, resin, soap, and paraffin.

TESTS.—B.P. Not unctuous to the touch; does not melt under 140° (absence of fats); yields nothing to cold rectified spirit (absence of resin), but is entirely soluble in oil of turpentine. Boiling water in which it has been agitated, when cooled, is not rendered blue by iodine (absence of starch).

U.S.P. If 1 Gm. of wax be boiled, for half an hour, with 40 Gm. of solution of soda (specific gravity 1·180), the volume being preserved by the occasional addition of water, the wax should separate, on cooling, without rendering the liquid opaque, and no precipitate should be produced in the filtered liquid by hydrochloric acid (absence of fats or fatty acids, Japan wax, resin); nor should the same reagent produce a precipitate in water which has been boiled with a portion of the wax (absence of soap). If 5 Gm. of wax be heated in a flask, for fifteen minutes, with 25 Gm. of sulphuric acid to 160° C. (320° F.), and the mixture diluted with water, no solid wax-like body should separate (absence of paraffin).

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
Emplastrum Calefaciens.	Ceratum Resinæ.
,, Cantharidis.	,, Cantharidis.
,, Cerati Saponis.	,, Extracti Cantharidis.
,, Galbani.	,, Sabinæ.
,, Picis.	Unguentum—
Unguentum Cantharidis.	,, Acidi Carbolici.
,, Hydrargyri Compositum.	,, Mezerei.
,, ,, Oxidi Rubri.	
,, Picis Liquidæ.	
,, Resinæ.	
,, Sabinæ.	
,, Terebinthinæ.	

USE.—To give proper consistence to **ointments.**

Cera Alba, B. and U.S.P. WHITE WAX.—Yellow wax bleached by exposure to moisture, air, and light.

CHARACTERS.—Hard, nearly white, translucent. Not unctuous to the touch; does not melt under 150°.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
Charta Epispastica.	Ceratum.
Suppositoria Acidi Tannici.	Compound Cerates—
,, Hydrargyri.	Ceratum Camphoræ.
,, Morphiæ.	,, Cetacei.
,, Plumbi Composita.	,, Plumbi Subacetatis.
Unguentum Cetacei.	Unguentum Aquæ Rosæ.
,, Plumbi Subacetatis Compositum.	
,, Simplex.	

USE.—In the preparation of the above **ointments** and **suppositories.**

ORDER **HEMIPTERA.**

Coccus, Cochineal, B. and U.S.P. The dried female of *Coccus cacti*. Mexico and Teneriffe.

CHARACTERS.—Ovate, plano-convex, about one-fifth of an inch (5 millimetres) long; wrinkled, of a purplish-grey or purplish-black colour; easily pulverisable, yielding a dark-red powder. Odour faint; taste slightly bitter. It contains a red colouring matter soluble in water, alcohol, or water of ammonia, slightly soluble in ether, insoluble in fixed and volatile oils. On macerating cochineal in water, the insect swells up, but no insoluble powder should be separated. The greyish-white insect quickly becomes black when warmed before the fire.

USES.—It has little medicinal value; it is used to give an attractive **colour** to various liquid preparations.

PREPARATIONS.

B.P.	DOSE.
Tinctura Cocci (2½ oz. in 1 pint).	Ad lib.
,, Cardamomi Composita.	
,, Cinchonæ Composita.	

ORDER **COLEOPTERA.**

Cantharis, B. and U.S.P. CANTHARIDES. SPANISH FLIES. —*Cantharis vesicatoria*. The beetle, dried. Hungary.

CHARACTERS.—From eight to ten lines long, furnished with two wing-covers of a shining metallic-green colour, under which are two membranous transparent wings; odour strong and disagreeable; powder greyish-brown, containing shining green particles. Free from mites.

COMPOSITION.—Cantharidin, a tasteless, inodorous substance, which may be crystallised from an alcoholic extract. It is insoluble in water and cold alcohol, although it may be extracted from the cantharides by both when in conjunction with the yellow colouring-matter. The other ingredients are unimportant.

PREPARATIONS.

B.P.	DOSE.
Acetum Cantharidis.....2 oz. to 1 pint.....	
Charta Epispastica	
Emplastrum Calefaciens .....1 part in 24, nearly	
,, Cantharidis .....1 part in 3	
Liquor Epispasticus.....1 oz. to 2½ fl. oz.	
Tinctura Cantharidis .....5½ gr. to 1 fl. oz. .....5-20 min.	
Unguentum Cantharidis .....1 part to 7, nearly	

U.S.P.

Ceratum Cantharidis.
,, Extracti Cantharidis.
Charta Cantharidis.
Collodion cum Cantharide.
Linimentum Cantharidis.
Tinctura Cantharidis.

ACTION.—**Externally** the preparations of cantharides produce, when applied to the skin, tingling, redness, and vesication; if the action is prolonged, the vesicles coalesce into a large bleb filled with serum, and if left on too long the true skin becomes irritated, and suppuration, ulceration, and even sloughing occur.

Internally the drug causes irritation of the alimentary canal, with a feeling of warmth in the mouth, œsophagus, and stomach, loss of appetite, and (if its use be prolonged, or if a single large dose be given) burning and pain in the stomach (increased by pressure), nausea, vomiting, and diarrhœa (the vomited and ejected matters often being mixed with blood).

It affects the kidneys and urinary passages, causing pain in the loins, burning in the bladder and along the urethra, irritation of the glans penis, and sometimes increased sexual appetite. If continued for a long time, it causes great pain in the kidneys, painful erections of the penis, difficulty of micturition or suppression of urine, the latter often containing albumen or blood.

The nervous system is usually not affected by small doses, but large doses cause headache and quickened pulse and respiration.

Very large doses produce insensibility, paralysis of respiration, and death with asphyxial convulsions.

The salivary glands and the back of the throat become so much swollen that swallowing is difficult, and the attempt to swallow may give rise to convulsions, like hydrophobia.

Urinary Organs.—The inflammation caused by cantharides begins in the glomeruli, and not in the straight tubes as is often stated.

The first condition of the kidneys noticed after the administration of cantharides is extravasation of leucocytes into the glomeruli and an exudation of a fibrinous matrix; next, following in order, we notice:—

(1) The glomeruli and the proximate tubules are filled with a granular fluid.

(2) The cells of the capsule become swollen.

(3) Cells of collecting tubes are affected, and become swollen.

(4) The cells of the whole urinary tubule become swollen.

(5) In the straight collecting tubes the cells become multiplied, and are thrown off so that the lumen becomes full of exuded cells.

THERAPEUTICS.—It is used externally as an irritant and counter-irritant, and internally for its effect on the genito-urinary tract.

Externally as **irritant**—

(1) To increase the supply of blood to a part, and hence improve its nutrition, as in chronic ulcers in the leg.

(2) To cause disappearance of inflammatory products in chronic inflamed joints and swellings; also in acutely inflamed joints, as in acute rheumatism, in the form of a blister above and below the joint. In chronic rheumatism a large and strong blister should be used.

As **counter-irritant** it is used in pleurisy and pneumonia, and often relieves the pain almost immediately.

It is also used in acute inflammation of the heart and pericardium.

It is better not to apply the blister directly over the affected part, but a little to one side, since there is a risk of getting the vessels just underneath it congested instead of anæmic.

In affections of other serous membranes, as in meningitis, and often in inflammation of the brain itself, the application of a blister is very useful.

When applied to the nape of the neck, it often relieves giddiness and disturbed cerebral functions dependent on tertiary syphilis, diseases of the ear, or of the semicircular canals.

It is occasionally useful to keep up the irritation by means of savine ointment applied to the blistered surface.

It is also locally applied to the perineum in inflammation of the prostate, and over the tender region in inflammation of the ovary.

Internally, in small doses of 1 or 2 min. of tincture, it checks hæmaturia; in larger doses it increases the disease.

In Bright's disease, after the acute stage has passed, but a little albumen and blood still remain in the urine, it is very useful in doses of 1-3 min. every three hours.

In cystitis, especially where there is inability to retain the urine, and also in ordinary incontinence of urine, it is useful; though in both cases atropin generally acts better.

A drop of tincture three times a day will often relieve chordee.

Precautions.—(1) Do not use the blisters on debilitated persons, and children; or do not keep them on long, but just sufficient to start the blister, and then, after two or three hours, put on a poultice to make the blister rise.

(2) Be careful of its use both externally and internally in Bright's disease.

Treatment in Poisoning.—Evacuate the stomach, give mucilaginous drinks to lessen the gastro-intestinal irritation, but

avoid oils or fats, which increase the solubility of cantharidin and the dangers arising from its absorption. Use opium and sitz baths to relieve the strangury.

Class ANNELIDA.

B.P. Hirudo. THE LEECH.—(1) *Sanguisuga medicinalis*, the speckled leech; (2) *S. officinalis*, the green leech. Collected in Spain, France, Italy, and Hungary.

CHARACTERS.—Body elongated, two or three inches long, tapering at each end, plano-convex, wrinkled transversely; back olive-green with six rusty-red longitudinal stripes. (1) Belly greenish yellow, spotted with black; (2) belly olive green, not spotted.

ACTION.—At the anterior extremity the leech has a sucking disc, in the middle of which is a triradiate mouth furnished with sharp teeth. Fixing itself to the surface by its disc, it saws through the skin and sucks the blood. This process is facilitated by the power of destroying the coagulability of the blood which the secretion from the pharynx of the leech possesses (Haycraft). This secretion is probably the cause of the ecchymoses which frequently occur at the bites as well as of the persistent hæmorrhage they sometimes occasion.

USES.—Leeches may be employed as a substitute for general blood-letting in women and children. They are more generally employed for the purpose of local depletion in inflammation. The irritation occasioned by the bites has probably a certain counter-irritant action (p. 298), but the relief they afford is chiefly due to the depletion. They are useful in bruises, fractures, inflamed joints, meningitis, otitis, ophthalmia, persistent headache, laryngitis, pleurisy, pneumonia, pericarditis, hepatitis, orchitis, and hæmorrhoids.

APPLICATION.—Each leech draws on an average about 1½ fl. dr. of blood. By applying fomentations afterwards, as much again, or even more, may be withdrawn. Care should be taken that leeches which have been applied to any one suffering from an infective disease should not be used again, lest they convey the virus. When they are to be applied to a mucous membrane, such as the tonsil, they should be put in a leech-glass. This is a small syringe large enough to hold a leech. The head of the animal is introduced first, and the body gently pushed down with a piston. The nozzle of the leech-glass is large enough to allow the head of the animal to protrude, but not to allow the body to follow.

Leeches may be applied to the skin by simply confining them to the spot with a pill-box; or a piece of blotting-paper, with holes in it at the points where we wish the leeches to fix, may be laid on the skin, and the leeches kept over this by a wine-glass or tumbler. It is sometimes difficult to make leeches bite. The skin should be

carefully washed, and thoroughly dried and warmed, and, if necessary, shaved. The room should be well ventilated and free from tobacco smoke, and from the fumes of vinegar or disinfectants. Leeches should be dried in a soft warm cloth and then applied. If a single one is to be used, the body may simply be held in the cloth, and the head allowed to reach the skin. A slight movement of withdrawal being now made, the leech will probably fix. Care should be taken not to withdraw it so strongly as to tear it from its hold. When difficulty is still experienced in making the leeches bite, a little warm milk sweetened with sugar may be rubbed over the skin, or a drop of blood extracted from the finger by a needle may be used for the same purpose. Usually leeches fall off when they are full, but if they do not they can be detached by sprinkling salt over them. If it is desirable to encourage the bleeding, warm fomentations, poultices, or cupping-glasses may be employed. The bleeding may be stopped by applying a small piece of absorbent cotton-wool, or of lint rolled into a hard cone and fixed over the bite with a compress and bandage. Cobwebs used in the same manner are very efficacious. If these are insufficient, a piece of absorbent cotton-wool dipped in strong solution of perchloride of iron and dried, or the styptic collodion of the U.S.P., may be applied. When other means fail a pointed stick of nitrate of silver may be pushed into the bite, or the bite may be transfixed with a needle and a silk thread passed in a figure of 8 around it. If possible leeches should not be applied at night, especially to feeble individuals or children, unless the patients are carefully watched, as, if hæmorrhage from the bites should occur, it might not be noticed until much blood had been lost. Leeches should not be applied over loose cellular tissue, where pressure cannot be applied. In inflammation of the eyes they should be applied to the temples, and not to the eyelids; and in inflammation of the testicles to the perineum, and not to the scrotum. As the marks of the bites are permanent, care should be taken to apply leeches, if possible, where the marks will not appear. Thus, in applying them to the temples the hair may be shaved off a spot and the leeches applied. When the hair grows the marks will be hidden. In applying them to the chest in girls they should, if possible, be placed so low down that the marks will not be seen when evening dress is worn.

If leeches should get into any mucous cavity, nose, stomach, or rectum, they may be dislodged by the injection of strong brine.

PREPARATIONS OF RHUBARB (*vide* p. 924 and Preface).

B.P. Pilula Rhei Composita. COMPOUND RHUBARB PILL.—Rhubarb, 3 oz.; socotrine aloes, 2¼ oz.; myrrh, 1½ oz.; hard soap, 1½ oz.; oil of peppermint, 1½ fl. dr.; treacle, by weight, 4 oz. The solid ingredients, which must all be in powder, are mixed with the oil, and then the treacle is added.

B.P. Pulvis Rhei Compositus. COMPOUND POWDER OF RHUBARB (GREGORY'S POWDER).—Rhubarb root, 2 oz.; light magnesia, 6 oz.; ginger, 1 oz. Mix the powdered ingredients and pass through a fine sieve.

B.P. Syrupus Rhei. SYRUP OF RHUBARB. Rhubarb root and coriander fruit, both in coarse powder, each 2 oz.; refined sugar, 24 oz.; rectified spirit, 8 fl. oz.; distilled water, 24 fl. oz. Percolate the rhubarb and coriander with the spirit and water; evaporate the filtrate to 13 fl. oz.; filter; dissolve the sugar in the filtrate.

B.P. Tinctura Rhei. TINCTURE OF RHUBARB.—Rhubarb, 2 oz.; bruised cardamom seeds, ¼ oz.; coriander fruit, ¼ oz.; saffron, ¼ oz.; proof spirit, 1 pint.

B.P. Vinum Rhei. WINE OF RHUBARB.—Rhubarb root, 1½ oz.; Canella alba bark, 60 gr.; sherry, 1 pint.

U.S.P. Pilula Rhei Composita. COMPOUND PILLS OF RHUBARB.—Rhubarb, 200 gr.; purified aloes, 150 gr.; myrrh, 100 gr.; oil of peppermint, 10 gr.; beat up with water to make a mass, and divide into 100 pills.

U.S.P. Pulvis Rhei Compositus. COMPOUND POWDER OF RHUBARB. Rhubarb, 25; magnesia, 65; ginger, 10 parts.

U.S.P. Syrupus Rhei. SYRUP OF RHUBARB.—Rhubarb, 90; cinnamon, 18; carbonate of potassium, 6; sugar, 600; water, *q.s.* to make 1,000.

U.S.P. Syrupus Rhei Aromaticus. AROMATIC SYRUP OF RHUBARB.—Aromatic tincture of rhubarb, 10; syrup, 90 parts.

U.S.P. Tinctura Rhei. TINCTURE OF RHUBARB.—Rhubarb, 12; cardamom, 2; diluted alcohol up to 100 parts.

U.S.P. Tinctura Rhei Aromatica. AROMATIC TINCTURE OF RHUBARB.—Rhubarb, 20; cinnamon, 4; cloves, 4; nutmeg, 2; diluted alcohol up to 100.

U.S.P. Tinctura Rhei Dulcis. SWEET TINCTURE OF RHUBARB.—Rhubarb, 8; glycerrhiza, 4; anise, 4; cardamom, 4; diluted alcohol up to 100.

U.S.P. Vinum Rhei. WINE OF RHUBARB.—Rhubarb, 10; calamus, 1; stronger white wine up to 100.

INDEXES.

GENERAL INDEX.

A.

Abdomen, mustard stupes or poultices applied to the lower part of the, act as indirect emmenagogues, 398
Abernethy, Mr., reference to, 619
Abney and Festing, reference to, 22
Abortion, emetics to be avoided where a tendency to, exists, 327 ; the twigs of thuja may produce, 954
Abscesses, especially of the liver, caustics employed to open, 303
Absinthe, as a spinal stimulant, 151 ; action of, on the brain of dogs, 156
Absorption and excretion of drugs, diagram illustrative of, 29 ; effects of rapid or delayed, 30
Abstracts, 443
Abstractum aconiti, 443, 748
Belladonnæ, 443, 930
Conii, 443, 846
Digitalis, 443, 909
Hyoscyami, 443, 905
Ignatiæ, 443, 884
Jalapæ, 443, 897
Nucis Vomicæ, 443, 884
Podophylli, 443, 755
Senegæ, 443, 784
Valerianæ, 443, 867
Acetate, test for, 520
Acetate of aluminium, action of, on enzymes, 63 ; on bacteria, 73
Ammonia, as a vascular stimulant, 287, 288
Ethyl, 707
Lead, 631
Morphia, 764
Morphine, 764
Potash, 535
Soda, 555
Zinc, 602
Acetic acid, action of, on bacteria, 76, 77 ; of the vapour of, on the general circulation, 162 ; action of, on the mucous membrane, 217 ; as a vesicant, 300 ; as a caustic, 301 ; as a poison, with its antidote, 429 ; properties and uses of, &c., 503 ; preparations containing, 504 ; glacial ditto, 504
Acetone, action of, on bacteria, 75, 77
Acetum, 443, 504
Cantharidis, 443, 504, 1001
Lobeliæ, 443, 876
Opii, 443, 761, 762
Sanguinariæ, 443, 779
Scillæ, 443, 504, 959
Acid bath, the, 413
Dilute nitro-hydrochloric as a hepatic stimulant, 353
Ergotinic, 981
Hæmatin, 57
Radicals in metallic salts, general tests for, 519 ; list of tests for the different acids, 520, 521
Solution of nitrate of mercury, 625
Sphacelinic, 981
Tartrate of potash, 536
Acidity, corrected by antacids, 321
Acids, action of, on the secretion of the mucous membranes, 217 ; as stimulating expectorants, 219 ; action of dilute on the frog's heart, 265 ; on the capillaries, 277 ; as caustics, 301 ; as astringents, 305 ; as styptics, 307 ; as sialagogues, 312 ; as artificial digestive substances, 319 ; action of, as irritant poisons, 347 ; strong, may produce death weeks after they have been swallowed, 348 ; as antihydrotics, 387 ; as poisons, with their antidotes, 429 ; general characters and properties of, 493-495 ; general action of, on the tissues, 496 ; on the skin, 496 ; in the mouth, 496 ; in the stomach, 497 ; on the bile and liver, 498 ; treatment of poisoning by, 499
Acids, mineral, action of, on albumen, 44 ; on protoplasm, 46 ; on infusoria, 51 ; as sialagogues, 312
Acids, physiological action of—
Arsenic, 24
Bromic, 24
Hydriodic, 24

Acids, physiological action of—
Hydrochloric, 24
Iodic, 24
Phosphoric, 24
Selenic, 24
Sulphuric, 24
Acids, preparation, properties, action, and uses of—
Acetic, 494, 503
Glacial, 494, 504
Arsenious, 495
Benzoic, 495
Boracic or boric, 494, 508
Carbolic, 495
Carbonic, 494, 509
Chromic, 508
Citric, 494, 507
Dilute hydrobromic, 494, 495, 516
Hydrocyanic, 494, 512
Phosphoric, 495, 505
Gallic, 495, 943
Hydrochloric, or muriatic, 494, 500
Lactic, 516
Nitric, 494, 501
Nitro-hydrochloric, 503
Dilute, 503
Oleic, 495, 517
Oxalic, 495, 507
Phosphoric, 505
Salicylic, 495
Sulphuric, 495, 498
Aromatic, 499
Dilute, 499
Sulphurous, 495, 499
Tannic, 495, 941
Tartaric, 494, 506
Vinegar, 504
Acidum Aceticum, 504
Dilutum, 504
Glaciale, 504
Benzoicum, 879
Gallicum, 941
Hydrochloricum Dilutum, 501
Hydrocyanicum Dilutum, 610
Nitricum Dilutum, 502
Nitro-hydrochloricum, 501
Dilutum, 501, 502
Phosphoricum, 505
Sulphuricum aromaticum, 499, 927
Dilutum, 499
Tannicum, 941
Tartaricum, 536
Aconite leaves, 747 ; and root, 747
Aconitia or Aconitine, action of, on oxidation, 55 ; effects of, on muscle, 128 ; as a sedative, 128 ; as an anodyne, 168, 170 ; action of, on the respiratory centre, 199, 206 ; on the vagus roots, 254 ; on the vagus centre, 274 ; on the heart, 296 ; Ringer's mode of using, 296 ; as a poison, with its antidote, 429 ; antagonism of, to other drugs, 434-437 ; preparation, characters, and tests of, 748 ; general action of, in frogs, 748 ; in man, 749 ; on the heart, 749 ; action of, on individual organs, 749 ; on the muscles, motor and sensory nerves, 749, 750 ; on the spinal cord, brain, and vaso-motor centre, 750 ; on the heart and respiration, 750 ; on the temperature, the stomach, and the secretion of the salivary gland, 750 ; on the pupil of the eye and the tissues, 751 ; therapeutic use of, locally, 751 ; for the stomach, in febrile conditions, in cardiac disease, and on the nervous system, 751 ; mode of application, 751
Aconitum, properties, composition, and preparations of, 747
Actual cautery, as a styptic, 307
Adeps benzoatus, 879, 994
Benzoinatus, 879, 994
Adonidin, as a cardiac tonic, 289
Adonis vernalis, as a cardiac tonic, 289 ; as a refrigerant diuretic, 379 ; composition, action, and use of, 753
Aeby, reference to, 109
Æther purus, 705
Agaricus albus, as an antihydrotic, 387
Ague, utility of quinine in, 1 ; produced by the bacillus malariæ, 81 ; importance of emetics and purgatives in aiding the action of antiperiodics in the cure of, 87 ; value of emetics in, before the administration of quinine, 326 ; sometimes cured by emetics alone, without quinine, 326 ; action of opium in, 778 ; brought on by strychnine, 887
Air-baths, 415
Air-passages, value of emetics in removing obstructions from the, 327
Albertoni, reference to, 156
Albumen, nature of, and action of drugs on, 43 ; effects of acids and organic alkaloids on, 44 ; action of quinine on, 859 ; test solution of, 995 ; albumen of eggs, 995
Albuminous solutions, action of alcohol on, 692
Albuminuria, action of drugs on, 381 ; how far caused in apparently healthy persons by mercurials, 596
Alchemilla, action of, on the bladder, 391
Alcohol, effects of, on the blood, 58 ; change undergone by, when boiled with sulphuric acid, 58 ; action of, on enzymes, 63 ; on bacteria, 73, 75, 77 ; appears to arrest the action of zymotic diseases, 82 ; and preserves animal matter, 83 ; action of, on medusæ, 90 ; on annulosa, 94 ; on muscles, 104-125 ; on the brain of the lower animals, 156 ; on psychical processes, 160 ; a typical stimulant on the action of the brain, 163 ; different action of, in different doses, on the brain, 163 ; has both stimulant and narcotic action on the brain, 167 ; as an antispasmodic, 181 ; action of, on frogs, 183 ; on the respiratory centre, 205 ; on the vaso-motor centre, 246 ; on the motor ganglia,

275 ; as a cardiac stimulant, 286 ; as a vascular stimulant, 287; as a rubefacient, 300 ; as an astringent, 305 ; as a local sedative, 327 ; as an antipyretic, 368 ; as a stimulant diuretic, 379 ; as an aphrodisiac, 396 ; as a poison with its antidote, 430 ; antagonism of, to strychnine, 434-437
Alcohol, 700
Absolute, 700
Amylic, 703
Diluted, 701
Proof spirit, 701
Rectified spirit, 701
Red wine, 702
Sherry, 702
Spirit of French wine, 701
White wine, 702 ; stronger, 702
Alcohol, ethyl, general source and preparation of, 691 ; impurities and tests of, 692 ; general action of, 692 ; on albuminous solutions, 692 ; on the skin, mouth, stomach, intestine, and blood, 692 ; and tissues, 693 ; dispute as to whether it can be regarded as a food, 693 ; its action on the circulation and temperature, 693 ; on the nervous system, 694 ; and cranial circulation, 694 ; on the nervous tissues, on the judgment and emotions, 695 ; on the motor centres, the speech, and the cerebellum, 695 ; on the spinal cord, the respiratory centre, the vaso-motor centre, and the heart, 695 ; importance of a proper diagnosis of drunkenness from effects of opium and apoplexy, 695 ; effect of impurities on the action of, 695 ; effects of chronic poisoning by, 696 ; on the bowels, skin, liver, kidneys, and nervous system, 696 ; nature and effects of delirium tremens, 696 ; and treatment of, 697 ; causes of chronic alcoholism, 697 ; uses of, 698 ; its weakness as a stimulant compared with beef-tea, 699 ; action of, as a stimulant, 699; and on the urine, 700
Alcohol, methyl, preparation, characters, and uses of, 691
Alcoholism, causes of chronic, 697
Alcohols, list of the principal, with their respective toxic powers, 689, 691 ; action of, on the general system, 690, 691
Aldehydes, properties, action, and uses of—ethyl aldehyde, 703 ; and paraldehyde, 703
Alder, black, 810
Ale, intoxicating effects of a single glass of, when sucked through a straw, 162
Algæ, 984
Alimentary canal, action of drugs on the, 308 ; of quinine on the, 863 ; of sulphate of strychnine on the, 886 ; of tobacco, 907 ; of extract of ergot, 982
Alkalies, action of, on protoplasm, 46 ; on infusoria, 51 ; on muscles, 110 *et seq.* ; on the secretions of mucus from the trachea, 216 ; on the amount and nature of moist *râles* in the lungs, 217 ; as stimulating expectorants, 219 ; dilute, on the frog's heart, 265 ; on the capillaries, 277 ; as caustics, 301 ; as sialagogues, 312 ; arrest secretion of saliva, 316 ; dilute, increase the action of the gastric juice, 319 ; strong, may produce death weeks after it has been swallowed, 348 ; as poisons, with their antidotes, 429-433
Alkalies, metals of the, 522 ; (1) alkaline salts, general characters and reactions of the, 522 ; their physiological action, 522 ; and general action, 523 ; on the skin, as caustics, rubefacients, and vesicants, 523, 524 ; in the mouth, 524 ; in the stomach, 524 ; on the gastric juice, 524 ; as antidotes in poisoning by acids, metals, and alkaloids, 524 ; their action on the blood, 525 ; as alteratives, diuretics, and antacids, 525 ; (2) general action of the group of chlorides, 525 ; on the stomach and other parts of the body, 526, 527 ; (3) general action of the sub-group of sulphates, 527 ; comparative action of the alkaline metals, 528
Alkaline bath, 413
Bromides, as antispasmodics, 182
Hæmatin, 57
Sulphur ointment, constituents of, 480
Alkaloids, action of, on the general system, 22, 23 ; on albumen, 44 ; on protoplasm, 47 ; on bacteria, 71 ; formed by putrefaction, 81 ; Albertoni's investigations as to the action of the coto, 337 ; objection to the extremely small doses of, required to produce marked physiological action, 434 ; antagonistic action of certain, to morphine, 436, 437 ; nature and action of, 443 ; and of opium, 774
Alkaloids, cinchona, and their salts, 859
of opium, action of the, 774
Allspice and oil, as carminatives, 330
Oil of, 838
Allyl alcohol, action of, on bacteria, 77 ; extraordinary effect of, 82 ; *vide* also 958
Almond, bitter, 534
Oil of, 834
Oil, as a demulcent, 304 ; nature of, 834
Oil of, expressed, 834
Aloes, as a purgative, 339 ; as a cholagogue, 340 ; as a hepatic stimulant, 353 ; characters, preparations containing, and composition of, 959-961
Barbados, 961 ; action of, in the mouth, the intestines, and the rectum, 961 ; on the bile and the uterus, 961 ; as an aphrodisiac and a purgative, 961

Aloes, Purificata, 960
Purified, 961
Socotrine, 959
Aloin, nature and action of, 960
Alteratives, nature of, 362; list of the principal, 362; action of, 362-364; uses of, 364; alkalies as, 525; lappa as, 876; solanine as, 898; rumex as, 924; phytolacca root as, 925; stillingia as, 933; sarsaparilla as, 957
Althæa (marsh-mallow), characters, composition, and uses of, 790; a useful demulcent, 791
Alum, action of, on bacteria, 75; on the mucous membranes, 247; as a caustic, 301; as an astringent, 305; as a styptic, 307; as a local emetic, 325; as a local sedative, 327; as a vermicide, 357; action of, on the skin, 586; as an astringent, 586; as a styptic, 586; a caustic, and an emetic, 586; properties, action, and uses of, 585-587; of dried ditto, 586
Aluminium, symbol and atomic weight of, 9; physiological action of, 23; action of, on the mouth and stomach, 496, 497; general sources, reactions, &c., of the salts of, 585; hydrate of, 587; sulphate of, 587
Amanita muscaria, as an antihydrotic, 387
Amber, oil of, action and uses of, 952
American cannabis, 946, 947
Wormseed. *See* Chenopodium
Ammonia, nature of, and changes it undergoes, 13; physiological action of, 24; action of, on bacteria, 75; on the muscles, 103 *et seq.*; as a spinal stimulant, 151; stimulating effects of the vapour of strong, and of carbonate of, on the general circulation, 162; action of, on the ear, 194; on the respiratory centre, 205; and movements, 209; of strong liquor of, on the secretion of the mucous membranes, 217; as a stimulating expectorant, 219; carbonate of, as an emetic in chronic bronchitis, 220; action of, on the vagus centre, 274; on the accelerating centre, 274; action of salts of, on the vaso-motor centre, 274; as a cardiac stimulant, 286, 287; as a rubefacient, 300; aromatic spirit of, as a direct antacid, 321; action of, on the uterus, 399; vapour of, as a poison, with its antidote, 428
Ammonia, character, action, and uses of—
Acetate of, 572
Aromatic spirit of, 571
Bromide of, 572
Benzoate of, 574
Carbonate of, 570
Chloride of, 567
Citrate of, 640
Iodide of, 573
Nitrate of, 573
Phosphate of, 572
Ammonia—
Solution of, 573
Solution of acetate of, 572
Solution of citrate of, 572
Spirit of, 570
Strong solution of, 568
Sulphate of, 573
Sulphide of, 574
Valerianate of, 573
Water of, 570; stronger, 568
Ammoniac, 848
Ammoniacum, as an antispasmodic, 182; characters and uses of, 848
Ammoniæ benzoas, 880
Phosphas, 569
Ammoniated mercury, 624
Ammonii benzoas, 880
Iodidum, 489
Ammonio-ferric sulphate, or ammonio-ferric alum, 675
Ammonium, sulphate of iron and, 675
Benzoate, as a hepatic stimulant, 353
Bromide, action of, on the spinal cord, 142
Carbonate, as a cardiac stimulant, 286; as a direct antacid, 321; as a local emetic, 325
Chloride, action of, on bacteria, 75; on muscle, 104 *et seq.*; on the ear, 194; as a stimulating expectorant, 219; antagonism of, to chloral, 334-337; character, action, and uses of, 567, 568; on the liver, 568
Salts, characteristics of, 564; sources, reactions, and preparations of, 565; impurities, tests, and actions of, 566; figure showing the paralysing action of ammonium sulphate on muscle, 567
Sulphide, action of, on bacteria, 76
Amœbæ, nature of, action of drugs on, and method of experimenting on, 45 *et seq.*; an, figured at two different periods during movement, 60; struggle for life between the, and bacilli, 69; the protoplasm of, contracts in any direction, 95; anæsthetics act as poisons to, 173
Amphioxus, mechanism of respiration in the, 197; diagram of an, 199
Amyl nitris, 703
Amyl, nitrite of, use of, in diminishing tension and removing pain in angina pectoris, 2; difference of action of, in different animals, 41; blood treated with, and alcohol, 57; action of, on medusæ, 90; on psychical processes, 160; on the dog and rabbit, 246; as a poison, with its antidote, 432; antagonism of, to strychnine, 433-437; preparation, characters, and tests of, 708, 709; physiological action of, 709; on the blood, blood-pressure, respiration, and pulse, 709; on the muscles and motor nerves, 710; on the nervous

system and urine, 710 ; uses of, 710 ; as a remedy in spasmodic conditions, 710 ; in angina pectoris, headache, &c., 710, 711 ; pulse-tracings illustrative of the action of, in angina pectoris, 711 ; considerations regarding the administration of, 712
Amylum iodatum, 974
Amyridaceæ, 812
Anacardiæ, 811
Anæmia, causes functional inactivity of the cerebro-spinal system, 164 ; loss of albumen thraugh the kidneys, and deficiency of fatty food cause, 361 ; a deficiency of iron in the blood in, 361
Anæsthesia, various modes of inducing, 172, 173 ; may be caused by the direct action of drugs on the nerve cells, 173 ; dangers arising from the efforts to induce, 175 ; action of, and mode of using in animals, 177 ; history of the discovery of, 179
Anæsthetics, nature and uses of, 127, 171 ; action of, on the motor centres of the brain, 156 ; difference between anodynes and, 171 ; divided into local and general, 172 ; chief local and general, 172 ; usual action of general anæsthetics, 172-174 ; the action of, divided into four stages—the stimulant, 174 ; the narcotic, 174 ; the anæsthetic, 174 ; and the paralytic stage, 175 ; uses of, 175 ; dangers of, 175, 176 ; mode of administering, 177 ; action of on, and mode of using in, animals, 177 ; history of the discovery of the uses of, 179 ; action of, on the eye, 186 ; may obstruct respiration, 203 ; fallacies from, in ascertaining the action of drugs on the circulation, 228 ; action of, on the motor ganglia, 275 ; as poisons, with their antidotes, 429 ; iodide of ethyl as an anæsthetic, 714 ; iodoform as, 728, 729 ; erythroxylon and cocoaïne as, 786
Analgesics. *See* Anodynes
Anaphrodisiacs, nature and action of, 393-397 ; diagram illustrating the action of, 394 ; general considerations regarding, 396, 397 ; camphor as an, 929
Anemonin, 753
Aneurism, emetics to be avoided in persons suffering from, 327
Angina pectoris, 2 ; nitrite of amyl diminishes tension and removes pain in, 2
Aniline red, 743
  Sulphate, action of, on the cardiac muscle, 276
Animal charcoal, 478 ; purified, 479
Animal kingdom, 987-1004 ; class mammalia, order rodentia, 987 ; order ruminantia, 987 ; order pachydermata, 993 ; order cetaceæ, 994 ; class aves, order gallinæ, 995 ; class pisces, order sturiones, 996 ; order teleosteæ, family gadidæ, 996 ; class insecta, order hymenoptera, 998 ; order hemiptera, 1000 ; order coleoptera, 1000 ; class annelida, 1001
Animals, utility of, for experiments in medicine, 39-42
Anise, character of, 849 ; oil of, 756, 849 ; as a carminative, 849
Anise and oil, as carminatives, 330
Annelida, 1001
Annulosa, action of drugs on, 93, 94
Anodynes, two classes of local and general, 168, 169 ; nature, action, and uses of, 168-170 ; adjuncts to, 170
Antacids, nature and action of, 321 ; divided into direct and indirect, or remote, 321 ; action of alkalies as, 524 ; slaked lime as an antacid, 580
Antagonistic action of drugs, 434-437
Anthelmintics, nature of, 357 ; divided into two kinds, 357 ; list of the chief, 357 ; adjuncts to, 358 ; uses of, 358 ; benzin as an, 688 ; azedarach as, 802 ; pomegranate root bark as, 841 ; pumpkin seed as, 844 ; bryonia as, 844 ; wormwood as, 869 ; tansy as, 869 ; santonin as, 870 ; spigelia as an, 891 ; oleum chenopodii as, 925 ; kamala as, 936 ; oil of turpentine as, 951 ; thuja as, 954 ; areca nut as, 973 ; male fern as, 978
Anthrax, produced by the bacillus anthracis, 81
Anthrax bacilli. *See* Bacilli
Antiarine, action of, on mollusca, 93 ; on the frog's heart, 265 ; on the cardiac muscle, 276 ; as a cardiac tonic, 289
Antidotes, alkalies serviceable as, in poisoning by acids, metals, and alkaloids, 524
Antidotes, nature and action of, 428 ; list of the more common poisons, with their antidotes, 428-433
Antidysenteric, ipecacuanha as an, 865
Antihydrotics, or anhydrotics, nature, action, and uses of, 387-390 ; on the sweat glands, 388 ; on the secreting cells and nerves, 388 ; on the sweat centres and on the circulation, 388 ; diagram illustrating the action of, 388
Antimonial preparations are depressant expectorants, 219
Antimonii et potassii tartras, 653
  Oxidum, 653, 656
  Sulphidum, 653
    Purificatum, 653, 654
  Sulphuratum, 653
Antimonium nigrum, 653
  Sulphuratum, 653, 654
  Tartaratum, 536, 653

Antimony, symbol and atomic weight of, 9 ; its relations to other members of a group, 15 ; causes sickness, 22 ; action of, on muscle, 104 *et seq.* ; of large doses of, on the lungs, 203 ; on the motor ganglia, 275 ; on the vaso-motor nerves, 276 ; tartarated, as a pustulant, 301 ; as a caustic, 301 ; destroys the glycogenic function of the liver, 352 ; has a special action on tissue change, 364 ; in poisoning by, action of, on the urine, 364 ; employed in diseases of the respiratory organs, 365 ; as a poison, with its antidote, 430 ; general sources and reactions of, 648 ; action of, on the skin and stomach, 649 ; effects of poisoning from, 649 ; and mode of treatment, 649 ; account of the dispute that has arisen regarding the mode in which tartar emetic causes vomiting, 650 ; action of, on the heart of a frog, 651 ; on the circulation, blood-pressure, and temperature, 651 ; on the respiration, spinal cord, motor and sensory nerves and muscles, 651 ; produces fatty degeneration of various organs, 651 ; rapidity of its action on the skin of frogs, 651 ; diagram of vertical section of the epidermis of a frog poisoned by, 652 ; how eliminated, 652 ; uses of, 652 ; as an emetic, 652 ; how tolerance of the drug is produced, 32, 653 ; as a nauseant, 653 ; as an expectorant, 653 ; as a diaphoretic, 653 ; preparations containing, 653

Antimony, properties, action, and uses of—
- Black, 654
- Oxide of, 656
- Purified sulphide of, 654
- Solution of chloride of, 656
- Sulphurated, 654
- Tartarated, 657
- Tartrate of, and potassium, 657

Antineuralgic, peppermint camphor as an, 918

Antiperiodics, list of the chief, 87 ; their action, uses, and adjuncts, 87 ; emetics and purgatives aid the action of, 87 ; they rarely succeed without them if the functions of the liver are disturbed, 87 ; lemon juice as a powerful, 795 ; quinine as, 862 ; sulphate of beberia as, 931

Antipyretics, or febrifuges, divided into two great classes, 365 ; their nature, 365 ; action, 366 ; and uses, 367 ; aromatic series as antipyretics, 734 ; resorcin as, 739 ; chinoline as, 743 ; kairin as, 743 ; quinine as, 862, 863 ; oil of gaultheria as, 878 ; salicin as, 939

Antipyrin, characters, 744 ; action of, in reducing temperature, causing profuse perspiration, and slightly increasing the blood-pressure, 744 ; uses of, in febrile diseases generally, 744

Antiscorbutic, lemon juice as an, 795

Antiseptic, what is required in an, 71

Antiseptics, nature and action of, 83 ; uses of, 84-86 ; externally, 84 ; internally, 85 ; chloral hydrate as an antiseptic, 715 ; iodoform as, 728 ; the aromatic series of the carbon compounds as, 734 ; naphthalin as, 742 ; chinoline as, 743 ; cheken as, 838 ; oil of myrtle as, 839 ; oil of eucalyptus as, 841 ; quinine as, 860 ; benzoic acid as, 880 ; peppermint camphor as, 918 ; thymol as, 920 ; garlic as, 958

Antisialics, nature and action of, 316, 317

Antispasmodics, nature, action, and uses of, 180-182 ; action of, and list of, general, 181, 182 ; adjuvants to, 181 ; acetic ether as an antispasmodic, 708 ; iodide of ethyl as, 714 ; caulophyllum as, 759 ; oil of rue as, 802 ; oil of cajeput as, 839 ; valerian as, 867 ; oil of stramonium leaves as, 906 ; asafœtida as, 847 ; cypripedium as, 969

Antizymotics, nature and action of, 83

Aortic regurgitation. *See* Regurgitation, aortic

Aortic stenosis. *See* Stenosis, aortic

Apetalæ, 923

Aphrodisiacs, nature and action of, 393-396 ; diagram illustrating the action of, 394

Apnœa, nature and cause of, 202-205

Apocynaceæ, 891

Apocynum, characters and action of, 891 ; as a laxative, a cardiac tonic, and a diuretic, 892

Apomorphia, action of, on the cerebellum, 183 ; may lead to obstruction of the bronchi, 203 ; action of, on the respiratory centre, 205 ; on the mucous membranes, 218 ; caution required in the administration of, in catarrhal conditions, 218 ; as a depressant expectorant, 219 ; effect of, on the frog's heart, 266 ; on the cardiac muscle, 276 ; as a general emetic, 325

Apomorphina, 444

Apomorphine, hydrochlorate of. *See* Hydrochlorate of apomorphine

Apoplexy, diagnosis between opium poisoning, intoxication, and, 768

Apples, stewed, as a laxative, 339

Aqua Ammonia, 286
- Ammoniæ, 445
- fortior, 445
- Amygdalæ amaræ, 445, 835
- Anethi, 445, 850
- Anisi, 445, 850
- Aurantii floris, 445
- Aurantii florum, 445, 791
- Camphoræ, 445, 928, 929
- Carui, 445, 851
- Chlori, 445
- Chloroformi, 445
- Cinnamomi, 445, 927
- Cinnamonii, 445

Aqua, Creasoti, 445, 738
Destillata, 445
Fœniculi, 445, 849
Laurocerasi, 445, 836
Menthæ piperitæ, 445, 918
Menthæ viridis, 445, 919
Pimentæ, 445, 838
Rosæ, 445, 831
Sambuci, 445, 853
Aqueous solution of ferric nitrate of iron, 674
Aquifoliaceæ, 810
Arbutin, as an astringent, 305 ; action of, on the kidneys, 382
Areca nut, as a vermicide, 357 ; nature of, 972
Argenti oxidum, 579
Argentum. *See* Silver
Iodidum, 489
Aristolochiaceæ, 932
Arnica, as a rubefacient, 300
Camphor, action of, on the cardiac muscle, 276
Flowers, characters, action, and uses of, 873 ; root, 873
Arnstein, reference to, 271*n*.
Arseniate of iron, 677
Arseniate of soda, and of sodium—properties, action, and uses of, 647
Arsenic, symbol and atomic weight of, 9 ; effect of habit in eating, 32 ; use of a small dose of, for gastric neuralgia, 32 ; action of, on bacteria, 75 ; as an antiperiodic is sometimes more powerful than quinine, 87 ; action of, on muscle, 104 *et seq.* ; on the ends of the vaso-motor nerves, 242 ; on the motor ganglia, 275 ; on the vaso-motor nerves, 276 ; almost tasteless as a poison, 348 ; secondary effects of, as a poison, 348 ; destroys the glycogenic function of the liver, 352 ; as an alterative, 362 ; has a special action on tissue changes, 363 ; in poisoning by, action of, on the urine, 364 ; used in nervous debility, 365 ; in diseases of the skin, 365 ; in some chronic conditions of the respiratory organs, 365 ; as a poison, with its antidote, 430 ; character and general sources, 640 ; action of, on the skin, mouth, stomach, and nervous system, 641 ; treatment in cases of poisoning by, 641 ; how chronic poisoning by, may occur, 641 ; how the system may become habituated to it, as seen in the arsenic eaters of Styria, 642 ; action of, on the blood, pulse, and heart, 642 ; on the blood-pressure in animals, 642 ; causes paralysis, 643 ; peculiarity of its action on the skin, 643 ; diagrams illustrating the epidermis of a frog before and after poisoning by, 643 ; uses of, in various diseases, 643, 644 ; diagram of section of lung of a guinea-pig poisoned by arsenious acid, 644 ; probable mode of action of, in phthisis, 645, 646 ; mode of administration of, 646
Arsenic acid, physiological action of, 24 ; effects of, on the blood, 58 ; iodide of, nature and use of, 648 ; solution of, and mercury, 648
Arsenici iodidum, 489
Arsenious acid, effects of, on the blood, 58 ; as a local sedative (in minute doses), 327 ; properties, preparations, and uses of, 646, 647
Arsenious oxide, as a caustic, 301
Arteries, nature and functions of, 221 ; blood only available for the nutrition of cells while in the, 221 ; action of the pressure of the, on the circulation of the blood, 222 ; action of the heart on the, 222 ; effect of an upright and of a horizontal position on the circulation of the blood in the, 222 ; arrest of circulation in the, the cause of fainting and shock, 223, 224 ; schema of the circulation from the heart to the veins and the, 224-226 ; action of blood-pressure on the, 226 ; method of ascertaining the blood-pressure in the, 227-229 ; causes of alterations in blood-pressure of the, 229 ; how it may be raised and lowered, 230 ; relation of blood-pressure to pulse-rate and the, 230-234 ; effect of the, on pulse curves, 234-236 ; investigation of the action of drugs on the, 236-239 ; another method of ascertaining this, 239-242
Arterioles, action of the, on the blood-pressure, 222 ; effects of rapid dilatation of the, 223 ; schema of the circulation in the, 224-226 ; circulation in the, in the living body, 226 ; blood-pressure in the, and method of ascertaining it, 226-229 ; diagram of the apparatus employed in this, 228 ; alterations in blood-pressure in the, 229 ; relation of pulse-rate and the, to blood-pressure, 230-234 ; diagrams illustrative of this, 231-235 ; effect of the, on pulse curves, 234-236 ; investigation of the action of drugs on the, 236—242 ; two modes of estimating the contraction of the, 237 ; the method of direct observation, 237 ; the method of measurement by rate of flow, 239 ; mode of ascertaining whether a rise or fall in blood-pressure is due to the heart or to the, 252 ; action of digitalin on the, 911
Artocarpeæ, 945
Asafœtida, as an antispasmodic, 181, 182 ; as a carminative, 330 ; characters and uses of, 847 ; as an antispasmodic, carminative, and expectorant, 847
Asarum Europæum or asarabacca, action of, internally, 932
Ascidians, action of drugs on, 93 ; diagram of an ascidian, 198

Asclepiadaceæ, 892
Asclepias, characters and use of, 892 ; as a diaphoretic, or expectorant, 892
Asparagus, as a stimulant diuretic, 380
Asphyxial blood, stimulating effects of, on the medulla, 256
Aspidospermine, as a depressant expectorant, 219
Astringents, action of, on the mucous membranes, 217 ; sulphate of copper as an astringent, 301, 605 ; nature, action, and uses of, 305, 306, 328 ; slaked lime as an astringent, 580 ; alum as, 586 ; salts of zinc as, 599 ; geranium as, 783 ; rhatany root as, 785 ; prinos as, 810 ; rhus glabra (sumach) as, 811 ; myrrh as, 812 ; kino as, 816 ; logwood as, 822 ; catechu as, 828 ; rubus or blackberry as, 830 ; pale catechu as, 866 ; bearberry as, 877 ; chimaphila as, 878 ; saliva as, 922 ; rhubarb as, 924 ; rumex as, 924 ; oil of cinnamon as, 927 ; the bark of quercus alba as, 941 ; galls or nutgalls as, 941 ; elm bark as, 944
Atheroma, emetics to be avoided in persons suffering from, 327
Atomic weight of the elements, 9, 10 ; arrangement according to, 14
Atonic dyspepsia, slight stimulants produce appetite in, 317
Atropaceæ, 899
Atropia, 444, 900
Atropia, preparation and characters of—
  Liquor, 900
  Sulphas, 900
  Sulphate of, 901
  Sulphatis, liquor, 900
  Unguentum, 900
Atropina, 444
Atropine, physiological action of, on the motor or efferent nerves, 20 ; effect of large and small quantities of, on the pulse, 27 ; action of, on oxidation, 55 ; on medusæ, 90 ; on annulosa, 94 ; on muscles, 114, 116, 125, 128 ; as a sedative, 128 ; action of, on the spinal cord, 132, 141-143 ; on the brain of the lower animals, 156 ; as a local and general anodyne, 168-170 ; as a mydriatic, 184, 186 ; action of, on the respiratory centre, 205 ; on the vagus, 209 ; when injected into the jugular vein, 210 ; has a slight and uncertain action on the respiratory centre, 214 ; but a powerful effect in completely arresting the secretion from the bronchial tubes, 214 ; cases in which it is useful as a pulmonary sedative when combined with apomorphine, 214, 215 ; diagram of pulse and blood-pressure curve caused by the actions of, on the heart, 231 ; on the vessels of circulation, 241 ; destroys the inhibitory action of the vagus on the heart in dogs and rabbits, 246 ; acts on the heart through the vagus roots, 256 ; might be useful in lessening pain or palpitation of the heart in persons with high blood-pressure, 257 ; with muscarine, restores the pulsations in the heart-apex of the frog, 264 ; rapid action of, on the heart of the frog, 267 ; on the inhibitory power of the vagi, 268, 269 ; neutralises the action of muscarine on the heart, 272 ; action of, on the vagus centre, 274 ; on the vaso-motor centre, 274 ; as a cardiac stimulant, 286 ; effect of, on the secreting cells of a gland, 310 ; the most powerful of all antisialics, 316 ; paralysing action of, counteracted by physostigmine, 317 ; as a local sedative, 327 ; action of, on the intestines, 333 ; as an antihydrotic, 387 ; strong solutions of, applied to the conjunctiva, 421 ; as a poison, with its antidote, 430 ; antagonistic action of, to other drugs, 434-437 ; general action of belladonna or, in large and small doses, 901 ; special action of, locally applied, 901 ; on the brain, the spinal cord, and the motor nerves, 901 ; on the muscles, the eye, and the circulation, 902 ; on the urine, 903 ; on the intestines in large and small doses, 903 ; and on the temperature, 903 ; certain animals unsusceptible to the action of, 903 ; uses of, 903 ; as an antidote to opium, 904
Aurantiaceæ, 791
Auricular septum, view of the, in the frog, 258
Aves, 995
Azedarach, nature and use of, 802 ; chiefly as an anthelmintic, 802

B.

Bacilli, action of drugs on particular species of, 74 ; mode of experimenting on the action of drugs on reproduction of, 74 ; power of the spores of *Anthrax bacilli* to resist certain substances usually fatal to life, 76, 77 ; action of drugs on the development and growth of, 77. *See* also Bacteria
Bacillus anthracis, nature and action of, 645
  The lactic ferment a, 63 ; treatment for destroying the tubercle bacillus, 468
Bacillus tuberculosis, difference between the action of, and that of *Bacillus anthracis*, 645
Bacteria killed by creasote, 64 ; origin and nature of, 65 ; diagram of the different kinds of, 67 ; diseases caused by, 68 ; importance of a knowledge of, in relation to disease, 68 ; divided by Pasteur into two classes, 68 ; life history of, 68, 69 ; struggle for existence between the differ-

ent species of, 68, 69 ; action of drugs on the movements of, 70 ; and on the reproduction of, in general, 71 ; the most destructive substances to, 71 ; mode of experimenting to test the effects of drugs in destroying the germs of, 71, 72 ; comparative action of different drugs on, 72, 73 ; action of drugs on particular species of, 74 ; mode of experimenting on the action of drugs on the reproduction of, 74 ; results of Koch's experiments on, with three groups of disinfectants, 75, 76 ; action of drugs on the development and growth of, 77 ; table showing the strength of various disinfectants required to prevent the development of, 77 ; influence of temperature on the action of antiseptics on, 78 ; alterations in, by heat and soil, 78 ; possible identity of different forms of, 79 ; may be modified by cultivation, 80 ; action of, and their products on the animal body, 80 ; list of diseases caused by, 80, 81 ; effect of drugs on the action of, in the animal body, 82 ; decomposition of food in the mouth due to, 308 ; action of salicylic acid on, 741
Bael fruit, beneficial action of, in dysentery, 337 ; characters, composition, and uses of, 795
Baker, Morrant, reference to, 773*n*.
Balm. *See* Melissa
Balsam, Canada, 949
Of Copaiva, 826
Fir, 949
Peru, as a stimulant expectorant, 219 ; nature, action, and uses of, 816, 817
Tolu, as an expectorant, 219, 817
Baptisin, as a hepatic stimulant, 353, 355
Barbaloïn, nature and action of, 961
Barium, symbol and atomic weight of, 9 ; its relation to other members of a group, 15 ; physiological action of, 23 ; salts of, action of, on muscles, 106, 111, 112, 117 ; causes contraction of the vessels, 240 ; action of, on the heart of the frog, 265 ; salts of, action of, on the cardiac muscle, 276 ; and on the capillaries, 277 ; antagonism of, to other drugs, 433-437
Barium chloride, action of, on bacteria, 75
Bark, Angostura, 802
Bebeeru, 931
Calisaya, 854
Canella alba, 799
Casca, 829
Cascarilla, 933
Cinchona, Pale, 854
Red, 855
Yellow, 859
Cinnamon, 926
Coto, 927
Cotton root, 788
Bark, Elm, 944
Larch, 952
Oak, 941
Pale cinchona, 854
Paracoto, 928
Pomegranate root, 841
Quebracho, White, 892
Red cinchona, 855
Sassy, 829
Soap, 832
White quebracho, 892
Yellow cinchona, 854
Barley, pearl, 974
Baryta salts, as a poison, with its antidote, 430
Basham's mixture, 671
Baths, cold, as anaphrodisiacs, 396 ; hot foot, hip, and mustard, as indirect emmenagogues, 398 ; may be either local or general, 404 ; three chief kinds, 404, 405 ; the cold bath, 405-407 ; the cold pack, 407 ; cold sponging, 408 ; cold douche, 408 ; the spinal douche, 408 ; the ascending douche, 409 ; sitz bath, 409, 410 ; cold foot bath, 410 ; cold compresses, 410 ; tepid baths, 411 ; warm baths, 411 ; hot baths, 411 ; hot foot bath, 411 ; hot sitz baths, 412 ; poultices, 412 ; medicated baths, 413 ; sea-bathing, 413 ; acid bath, 413 ; alkaline bath, 413 , sulphurous bath, 413 ; mustard bath, 413 ; pine bath, 414 ; vapour baths, 414 ; calomel fumigation, 414 ; air baths, 415 ; the Turkish bath, 415 ; friction and inunction, 415-417 ; carbonic acid baths, 509
Bat's wing, Luchsinger's experiment with a, 113
Baxt, reference to, 770
Baxter, B., references to, 47*n*.
Beads, jumble, 817
Prayer, 817
Bean of St. Ignatius, 884
Bearberry, and bearberry leaves, 877
Beaumont, Dr., references to his observations on the case of Alexis St. Martin, 320, 356
Bebeerin, action of, on bacteria, 71 ; as an antiperiodic, 87
Bebeeru bark, as an antiperiodic, 87 ; characters and composition of, 931
Beberia, sulphate of, properties, action, and uses of, 931
Beef-tea *versus* alcohol, as a stimulant, 699
Beer yeast, 983
Belladonna, difference of action of, in men, rabbits, and dogs, 40, as a sedative, 128 ; action of, on frogs, 141 ; as a spinal stimulant, 151 ; as a narcotic, 168 ; as a local and general anodyne, 168, 170 ; as a mydriatic, 187 ; action of, on the respiratory centre, 214 ; on palpitation of the heart, 295 ; as a local sedative, 327 ; as a purgative, 336 ; as an

antihydrotic, 387; its action in incontinence of urine, 391; as a poison, with its antidote, 430; antagonism of, to opium, 436
Belladonna leaves, 899
Root, 900. For general action of belladonna, *see* Atropine
Belladonnine, as a mydriatic, 186
Bennett, Hughes, reference to, 130
Benzin, properties and uses of, 688
Benzoates, test for, 520
Benzoate of ammonia, 880
of ammonium, 574
of lithium, 563
of soda, action of, on enzymes, 63; on bacteria, 76, 77; nature of, 558
Benzoated lard, 994
Benzoic acid, action of, on enzymes, 63; on bacteria, 73, 76, 77; as a stimulating expectorant, 219; action of, on the kidneys, 383; preparation and properties of, 879; action of, as an antiseptic, and a diaphoretic, 880; uses of, 880
Benzoin, as a stimulating expectorant, 219; characters and preparations of, 879; compound tincture of, 879
Benzol, action of, on bacteria, 75
Benzoyltropine, as a mydriatic, 186
Berberiæ sulphas, 444, 931
Berberidaceæ, 759
Berberine, character and action of, 757
Bergamot, oil of, characters and uses of, 793
Bergmann, references to, 81
Bernard, M., references to, 29, and *n.*, 42, 120, 124, 314, 767
Bernstein, references to, 144, 200, 202
Bert, Paul, reference to, 76
Beryllium, symbol and atomic weight of, 9; physiological action of, 23
Bezold, Von, references to, 244, 246, 254*n.*
Bicarbonates, test for, 520
Bicarbonate of potash, 534
of soda, action of, on the gastric juice, 319; nature of, 553
Bichloride of ethidene, as a general anæsthetic, 172; of methylene, as a general anæsthetic, 172; nature of, 718
Bichromate of potash, as a poison, with its antidotes, 431; nature and uses of, 542
Biedermann, references to, 109, 110
Bigelow, Dr., reference to his use of ether, 179
Bile, utility of emetics to expel, from the gall bladder, 326; and to remove it from the body in cases of biliousness, fevers, and agues, 326; nature and functions of the, 350-356; use of cholagogues in removing the, from the body, 356; action of acids on the, 498; of pilocarpine, 505; of leptandra, 916; of aloes, 962; purified ox bile, 991; its composition, action, and uses, 992
Bin-oxalate of potash (salts of lemon or sorrel), as a poison, with its antidote, 429
Binz, Prof., references to the experiments of, 48, 58, 136, 485, 790,
Birds, action of opium on, 768
Bismuth, properties, preparation, action, and uses of—
Carbonate of, 658, 660
Citrate of, 660
and ammonium, 660
Common, 657-659
Oxide of, 658
Purified, 659
Solution of citrate of, and ammonia, 660
Subcarbonate of, 660
Sub-nitrate of, 658, 659
Bismuth, symbol and atomic weight of, 9; a mild irritant to the stomach, 318; salts of, as a local sedative, 327
Bismuth subnitrate, as an astringent, 305
Bismuthi et ammonii citras, 659
Citratis liquor, 659
Carbonas, 659
Citras, 659
Subnitras, 659
Bisulphide, test for, 521
of carbon, action of, on bacteria, 75
Bisulphite of soda, 560
Bitartrate, test for, 521
Bites of venomous serpents or of rabid dogs, utility of caustics in, 303; necessity for care in cauterising for dog bites, 303
Bittersweet *See* Dulcamara
Blackberry, 830
Haw, 868
Pepper, 936
Wash, 622
Bladder, diagram to show the effects on the cerebral circulation of rapidly emptying the, 233; action of drugs on the, 390-392; situation of the nerve-centre of the, 390; and of the cerebral, 390; action of vesical sedatives on, 391; and vesical tonics, 391; urinary sedatives and astringents, 392; treatment of inflammation of the, 392; result of distension of the, and of stone in the, 396; utility of pareira root in chronic catarrh of the, 758; action of buchu leaves on the mucous membrane of the, 803; of pilocarpine, 805, 806; of physostigmine, 821
Blagdon, Sir Charles, reference to, 386
Blake, reference to, 23
Blastomycetes, 67
Blatta orientalis, as a stimulant diuretic, 379; as an aphrodisiac, 395
Bleeding, local, by leeches or by wet cupping, usefulness of, in inflammation and fever, 367; as an anaphrodisiac, 396

Blisters, probable action of, in inflammation, 299, 300 ; various diseases in which they are useful, 302; as antipyretics, 366
Blood, red corpuscles of the, effect of heat and cold on, 49 ; action of drugs on the, 55 ; effects of oxygen and other gases on the, 55-57 ; various constituents of the—hæmoglobin, 55-57 ; oxy-hæmoglobin, 55-57 ; hæmatin, 56, 57 ; methæmoglobin, 56, 57 ; effects of carbonic acid on the, 56 ; of hydrocyanic acid, 56 ; of nitrites, 57 ; alterations effected in the interchange between the air and the, 58 ; poisoning of the, produced by the bacillus septicæmiæ, 81 ; action of, on the brain, 161-167 ; state of the, in respiratory complications, 202-205 ; effect of excessive venosity of the, on the respiratory centres, 201-203 ; condition of the, in suffocation, and in nitrite and carbonic oxide poisoning, 204, 205 ; difference in the quality of, in the arteries and in the veins, 219 ; importance of the pressure of the arteries and veins on the circulation of the, 222 ; action of the heart in reference to the, 222 ; fainting and shock caused by the sudden arrest of the supply of, to the brain, 223, 224 ; schema of the circulation of the, 224-226 ; diagram illustrating this, 225 ; circulation of the, in the living body, 226 ; nature of arterial tension, or blood-pressure, 226 ; method of ascertaining the blood-pressure, 227 ; alterations in blood-pressure and their causes, 229 ; how this pressure may be raised and lowered, 230 ; relation of pulse-rate and arterioles to blood-pressure, 230-234 ; diagrams illustrative of blood-pressure, 231 *et seq.* ; effect of the arterioles on blood-pressure and pulse-rate, 234-236 ; investigation of the action of drugs on the blood-vessels, 236-239 ; another method of ascertaining this, 239-242 ; venous, causes contraction, and oxygenated, dilatation of the vessels, 241 ; action of other parts on blood-pressure, 243 ; reflex contraction of blood-vessels, 244 ; action of drugs on this reflex contraction, 245 ; comparative effect of heart and vessels on blood-pressure in different animals, 246, 247 ; influence of nerves on blood-pressure, 248-250 ; causes of alteration in blood-pressure and pulse-rate, 251 ; action of the heart on blood-pressure, 252 ; action of styptics on the, 306 ; coagulation of the, caused by alum, lead, acetate and ferric chloride, 307 ; action of hæmatinics in improving the quality of the, 361 ; nature and action of the red corpuscles of the, 361 ; the various constituents of, 362 ; pressure of the, in the glomeruli, and the composition of the, two factors in the rapidity of the secretion of urine, 374, 377 ; experiment with digitalis on blood-pressure, 377, 378 ; action of hydrocyanic acid on the, 513, 514 ; of caustic alkalies injected into the, 525 ; action of the metals on the, 595 ; of mercury, 615 ; of salts of iron, 666 ; of alcohol, 692 ; of spirit of ether, 705 ; of nitrite of amyl, 709 ; of nitroglycerine, 713 ; of chloral hydrate, 716 ; of purified chloroform, 720, 722 ; of carbolic acid, 735, 736 ; of creasote, 739 ; of antipyrin, 744 ; of caffeine, 798 ; of Jamaica dogwood, 827 ; of oil of eucalyptus, 840 ; of quinine, 864 ; of oil of valerian, 867 ; of sulphate of strychnine, 886 ; of curare, 889 ; of gelsemium, 891 ; of tobacco, 907 ; of digitalin, 910 ; of thymol, 920 ; of tannic acid, 943
Blood-letting, as a local anodyne, 169
Bloodroot. *See* Sanguinaria
Blue cohosh, 759
Bocci, reference to, 351
Body, remedies acting on the surface of the, 297-307. *See* Remedies, &c.
Bœhm, references to, 101, 210, 243, 273*n.*, 752, 911
Boerhaave, reference to, 390
Boisbaudran, L. de, on molecules, 21
Bon, M. Gustav le, reference to, 83
Bones, action of phosphorus on the, 638
Boracic acid, action of, on bacteria, 76, 77 ; nature and properties of, 508
Borates, test for, 520
Borax, action of, on enzymes, 63 ; on bacteria, 73, 76, 77 ; as an antiseptic for cleansing the teeth, 308 ; as an antisialic, 316, 317 ; as a direct emmenagogue, 398 ; nature and uses of, 555 ; its derivatives, glycerinum boracis and mel boracis, 555
Boric or boracic acid, properties of, &c., 508
Borneol, action of, on the brain and spinal cord, 181 ; on the cardiac muscle, 276
Boron, symbol and atomic weight of, 9
Borosalicylate of soda, 73
Bouchard, reference to, 351
Bouley, reference to, 320
Bowditch, reference to, 262
Bowels. *See* Intestines
Bowman, references to, 369, 370
Brain, action of drugs on the, 152-183 ; of the lower animals, 152 ; of the higher, 153 ; of frogs, rabbits, guinea-pigs, monkeys, dogs, and cats, 152-155 ; diagram of the brain of a monkey, 154 ; arrangement of the motor and sensory centres of the, in the lower animals, 155 ; depressant action of drugs on the motor centres of the, 155 ; method of investigating the action of drugs on the excitability of the, 156 ; irritant action

of drugs on the motor centres of the, 156-159 ; action of drugs on the sensory and psychical centres of the, 159-183 ; effect of drugs upon the time required for mental processes, 159 ; drugs which increase the functional activity of the, 160 ; nerve stimulants, 160 ; cerebral stimulants, 160 ; effects of posture and mastication on the action of the, 161 ; stimulating effects of smoking, sips of alcohol, and tea and coffee on the, 161 ; suction causes an increased supply of blood to the, 161, 162 ; exercise causes increased activity in the, 162 ; sipping a powerful stimulant to the, 162 ; alcohol one of the typical stimulants of the, 163 ; direct action of strychnine and caffeine on the, 163 ; drugs which lessen the functional activity of the, 163-179 ; hypnotics or soporifics induce sleep, 164 ; effects of different degrees of sleep on the, 164, 165 ; action of hypnotics on the, 164-167 ; of narcotics, 167, 168 ; peculiar action of alcohol on the, 167, 168 ; peculiar physiological conditions of the, 167-168 ; action of anæsthetics on the, 171-177 ; of antispasmodics, 181 ; of drugs on the cerebellum, 182 ; different kinds of spirits appear to affect different parts of the, 183 ; fainting and shock caused by arrest of the supply of blood to the, 223, 224 ; action of the, on vomiting, 322 ; action of bromide of potassium on the, 547 ; of strong solution of ammonia, 569 ; of alcohol, 694 ; of spirit of ether, 706 ; of chloral hydrate, 716 ; of hydrochlorate of apomorphine, 765 ; of codeine, 766 ; of opium, 770 ; of sanguinaria, 778 ; of caffeine 798; of oil of eucalyptus, 841 ; of coniïne, 846 ; of oil of valerian, 867 ; of strychnine, 887 ; of belladonna or atropine, 901

Brandy, as a cardiac stimulant, 286 ; nature, &c., of, 698, 701

Bread, as a demulcent, 304 ; crumb of, 973

Brefeld, his classification of organised ferments, 66

Bromal-hydrate, antagonism of, to atropine, 433-437 ; nature, action, and use of, 718

Bromic acid, physiological action of, 24

Bromides, test for, 520

Bromide of Ammonium as a hypnotic, 166, 167 ; as an anaphrodisiac, 396 ; nature of, 572

Calcium, 167, 582

Ethyl, 172, 713

Lithium, 563

Potash, 547

Soda, 558

Zinc, 167, 602

Bromide of potassium, action of, on the motor centres of the brain, 156 ; lessens the functional activity of the brain, 163 ; as a hypnotic, 166, 167 ; as an anodyne, 170 ; as an antispasmodic, 181 ; action of, as an antispasmodic, 182 ; on the vessels of circulation, 244, 245 ; as an anaphrodisiac, 396 ; uses of, 546-548 ; action of, on the spinal cord and the brain, 547 ; in nervous diseases and as a hypnotic, 547 ; allays excitability and irritability, 547 ; in epilepsy and sickness, especially in pregnancy and sea-sickness, 548 ; as an anaphrodisiac, 548

Bromide of sodium, as a hypnotic, 167

Bromine, symbol and atomic weight of, 9 ; action of, on infusoria, 51 ; on enzymes, 63, 64 ; on bacteria, 71, 73, 75, 77 ; as a caustic, 301 ; as a poison, with its antidote, 428 ; characters, test, and uses of, 488

Bromo-camphor, antispasmodic powers of, 181

Bromoform, as a general anæsthetic, 172

Bronchial tubes, atropine completely arrests the secretion from the, 214

Bronchitis, chronic, cod-liver oil affords more relief in, than any of the ordinary expectorants, 218 ; importance of an emetic in, 219 ; ipecacuanha, either alone or combined with squills, as expectorant in, 220 ; with great depression and feeble circulation, carbonate of ammonia to be preferred, 220 ; importance of warmth and moisture in, 220 ; of respirators, warm clothing, &c., in, 220 ; value of certain plasters in, 220 ; tartar emetic ointment and croton-oil liniment sometimes of use in, 302

Bronchitis kettle, nature and use of, 424

Broom, as a refrigerant diuretic, 379 ; broom and broom tops, characters and composition of 814 ; physiological action and therapeutical uses of, 815

Brown-Séquard, reference to, 208*n*.

Brucia, effects of, on the blood, 58

Brucine, as a spinal stimulant, 151 ; action of, on the respiratory centre, 205 ; antagonism of, to chloral, 433-437 ; acts like strychnine, 888

Brücke, Professor, reference to, 910

Brunton, Dr. L., references to, 27, 31, 35, 41, 101, 105, 124, 146, 155*n*., 193*n*., 232, 235*n*., 247*n*., 252*n*., 254*n*., 270*n*., 332*n*., 351*n*., 377, 378 and *n*., 435, 438, 532, 815, 906

Bryonia, or bryony, characters and use of, as a hydragogue cathartic, 844, 845

Bubnoff, reference to, 753

Buchheim, references to, 28, 124

Buchner, reference to, 80

Buchu, as a stimulant diuretic, 380 ; action of, on the bladder, 391 ; buchu leaves, nature, action, and use of, 803

Buckthorn, nature, action, and use of, 809 ; and of buckthorn juice, 809

Burdock, 875
Burgundy pitch, 953
Burnett, Sir W., reference to, 601; his disinfecting fluid, as a poison, with its antidote, 430
Burseraceæ, 813
Butternut. *See* Juglans
Butyl-chloral, as a general anodyne, 168, 170; characters, action, and uses of, 718
Butyric acid, action of, on bacteria, 75
Buxine, as a spinal stimulant, 151
Byttneriaceæ, 796

C.

Cabbage-rose petals, 830
Cacao butter, 796
Cadmii iodidum, 489
Cadmium, iodide of, 606
Cadmium, symbol and atomic weight of, 9; its relation to other members of a group, 15; physiological action of, 23; effect of, on muscle, 104 *et seq.*; causes slight contraction of the vessels, 240; cadmium sulphate, as an astringent, 305
Cæsalpiniæ, 823
Cæsium, symbol and atomic weight of, 9; its relation to other members of a group, 15; physiological action of, 23
Caffeina, 444
Caffeine, action of, on oxidation, 55; on medusæ, 90; on annulosa, 94; on muscles, 107, 111 *et seq.*; on the spinal cord, 130; on the brain, 163; on the accelerating centre, 274; on the vaso-motor centre, 274; on the cardiac muscle, 276; as a cardiac tonic, 289; as a refrigerant diuretic, 378; antagonism of, to morphine, 433-437; (theine) characters of, 797; action of, on the nerve centres, and on muscular fibre, 798; on frogs and warm-blooded animals, 798; on the brain, medulla, respiration, blood-pressure, and pulse, 798; on the salivary secretion and the intestines, 798; on the temperature, 798; as a diuretic, 798
Cahours, reference to, 124
Cajeput oil, as a rubefacient, 300; and carminatives, 330; oil of, characters and uses of, 839; as a powerful stimulant, antispasmodic and rubefacient, 839
Calabar bean as a myotic, 186; as a poison, with its antidote, 430; character, composition, and preparations of, 818
Calabarine, as a spinal stimulant, 151; antagonism of, to chloral, 437
Calamus, 973
Calcis hydras, 579
Calcium, symbol and atomic weight of, 9; its relation to other members of a group, 15; and specially to lithium, 15; physiological action of, 23; action of, on the muscles, 110, 117; causes great contraction of the vessels, 240; salts of, and distilled water prolong the beating of the frog's heart, 264, 265
Calcium, characters and uses of—
Chloride of, 75, 582
Bromide of, 582
Precipitated Carbonate of, 582
Phosphate of, 583
Hypophosphite of, 583
See also under Lime
Calendula (marigold), 874
Calomel, antiseptic power of, 85; action of, on the stomach, 320; on the pancreatic juice, 357; its action and uses, 621
Calomel fumigation, 414
Calumba and Calumba root, characters, composition, and preparations of, 756, 757; actions and uses of, 757
Calycifloræ (sub-class II.), 809
Camphor, action of, on bacteria, 77; on ascidians, 93; and on annulosa, 94; curious exciting action of, on the brain and the medulla, 158; action of, as an antispasmodic, 181; on the ear, 194; on the vaso-motor centre, 274; on the cardiac muscle, 276; as a cardiac stimulant, 286, 287; as a popular remedy to cut short coryza or catarrh, 288; compound liniment of, and camphor, as a rubefacient, 306; as an anaphrodisiac, 396; characters, composition, and preparations of, 928; action of, as a stimulant and rubefacient, 929; as a diaphoretic and anaphrodisiac, 929; action of, on the heart, nerve-centres, and the temperature, 929; uses of, externally and internally, 929
Camphor, monobromated, characters of, 929; action and uses of, 930; as a sedative, 930
Campylospermæ, 844
Canada Balsam, 949
Pitch, 953
Turpentine, ditto, 949
Canadian hemp. *See* Apocynum
Canellaceæ, 799
Canella alba bark, an aromatic bitter and tonic, 800
Cannabin, action of, on brain of dogs, 156
Cannabineæ, 946
Cannabis, American, 946, 947
Cannabis indica, as a hypnotic, 167; as an anodyne, 170; action of, in producing visions, 193; doubtful value of, as an aphrodisiac, 395; as a poison, with its antidote, 430; character, action, and uses of, 946, 947
Cantharides, as a vesicant, 301; as a stimulant diuretic, 379; action of, on the kidneys, 382; produces both albuminuria and hæmaturia, 382; its action on the urine, 391; as an aphrodisiac, 395; as a direct emmenagogue, 398; as a poison, with their antidotes, 430; cha-

racter and composition of, 1000 ; action of, externally and internally, 1001 ; on the salivary glands and on the urinary organs, 1001 ; uses of, externally as an irritant and a counter-irritant, 1002 ; and internally, 1002 ; precautions, 1002 ; treatment in poisoning by, 1002
Capillaries, list of drugs by which they are stimulated, depressed, or paralysed, 277 ; a certain abnormal condition of the, one of the chief causes of dropsy, 294
Caprifoliaceæ, 853
Capsicum, 898 ; as a rubefacient, 300
Fruit, characters and composition of, 898 ; action and uses of, 899
Caraway, as a carminative, 850
Fruit, 850
Oil of, 850
Caraway and oil, as a carminative, 330
Carbolic acid, action of, on enzymes, 63 ; on bacteria, 73, 74 ; as a deodorizer, 83-86 ; its superiority for removing smell from the hands, 86 ; as a sedative and an anæsthetic, 128 ; one of the chief local anæsthetics, 172 ; action of, on the vaso-motor centre, 274 ; as a caustic, 301 ; as an astringent for the teeth, 308; liquefied as a remedy for toothache, 309; as a local sedative, 327 ; as a poison, with its antidote, 431 ; antagonism of, of, to chloral, 437 ; characters, tests, and preparations of, 734 ; action of, as a deodorizer and disinfectant, 735 ; on the skin and mucous membranes, 735 ; on the blood, muscle, nerve, and medulla oblongata, 735 ; on the spinal cord, respiratory and vaso-motor centres, 736 ; on the cerebral, sweat and salivary centres, 736 ; on the temperature, 736 ; how excreted, 736 ; uses of, 735-738
Carbon, symbol and atomic weight of, 9 ; found in three forms, and in various compounds, 13 ; its relation to other members of a group, 15 ; its forms, 477-479
Carbon, bisulphide of, character, action, and uses of, 686
Carbon compounds, fatty series, 685 *et seq.* ; properties and general action of, 685, 686 ; aromatic series, 730-744 ; general characters of, 730 *et seq.* ; action of, 734 ; the antiseptic and antipyretic power, 734. *See* Hydrocarbons
Carbon monoxide, as a poison, with its antidote, 428
Carbonates test for, 520
Carbonate of Ammonia, 571
Bismuth, 660
Lead, 631
Lithia, 562
Magnesia, 591
Potash, 533
Soda, 552
Zinc, 600
Carbonate of soda, action of, on the ear, 194 ; on the mucus from the trachea, 216 ; as a poison, with its antidote, 429
Carbonic acid, action of, on protoplasm, 47 ; as a local anodyne, 169 ; action of, on the blood, 241 ; as a refrigerant diuretic, 379 ; as a poison, with its antidote, 429 ; as choke damp, with its antidotes, 429 ; properties of carbonic acid, 509 ; action and uses of, 509 ; effects of, in the mouth, the stomach, and the intestinal canal, 510 ; poisoning by, 510 ; has three stages—dyspnœa, convulsions, and paralysis, 511 ; its treatment, 511
Carbonic oxide, action of, on muscles, 104 *et seq.*; on the vagus centre, 274 ; effects of poisoning by, on the colour of the blood, 204
Cardamoms, as carminatives, 330 ; as stimulants and carminatives, 971
Cardiac muscle, drugs which stimulate or depress, 276
Cardiac poisons, action of different kinds of, 266, 276
Cardiac sedatives, nature and action of, 295, 296
Cardiac stimulants, nature and action of, and list of the principal, 286
Cardiac tonics, 214 ; nature of, and list of the principal, 288, 289 ; conditions and diseases of the heart in which they are most useful, 289-292 ; the question as to the use of digitalis in aortic regurgitation considered, 291, 292 ; risks attending the administration of digitalis and other cardiac tonics, 292 ; cimicifuga (black snakeroot), as a cardiac tonic, 754 ; apocynin and apocynein as, 892
Carlsbad water, probable cause of its efficacy in hepatic diseases, 356 ; nature and uses of, 556
Carminatives, nature of the action they exert on the stomach, 328, 329 ; list of the chief, 330 ; their principal uses, 330 ; cloves as, 837 ; asafœtida as, 847 ; fennel fruit as a, 849 ; oil of anise as, 850 ; oil of dill as, 850 ; oil of caraway as, 851 ; oil of coriander as, 852 ; oil of chamomile as, 871 ; oil of rosemary as, 917 ; oil of lavender flowers as, 917 ; oil of peppermint as, 918 ; oil of spearmint, as, 919 ; hedeoma or pennyroyal, 921 ; expressed oil of nutmeg as, 926 ; oil of cinnamon as, 927 ; garlic as, 958 ; cardamoms as, 971 ; saffron as, 972
Carolina pink. *See* Spigelia
Carron oil, origin, composition, and uses of, 581
Carrot as a stimulant diuretic, 379
Casca bark (sassy bark), composition, action, and uses of, 829
Cascara Sagrada as a purgative, 810

Cascarilla, 933 ; cascarilla bark as a stimulant, tonic, and expectorant, 933
Cash, Dr., references to, 33, 101, 105, 110, 112, 117, 124, 239, 240, 435, 532, 887
Cassia, as a laxative, 339 ; cassia pulp, characters and use, 825 ; purging cassia, 825
Castanea, characters and uses of, 944
Castor, antispasmodic action of, 181 ; its characters and therapeutics, 987
Castor oil, nauseous taste of, owing almost entirely to its odour, 195 ; as a purgative, 339 ; as a vermifuge, 358 ; characters and preparations of, 934 ; composition, action, and uses of, 935 ; as a purgative, 935 ; mode of administration, 935
Cat, easiest mode of anæsthetising, 177, 178 ; diagram of curve of the pulse and blood-pressure in a, after division of the spinal cord and injection of erythrophlœum, 232
Catalysis, effects of, on different substances, 58
Cataplasma carbonis, 445, 477, 973
Conii, 445, 845
Fermenti, 445, 973, 984
Lini, 445, 783, 831
Sinapis, 445, 780
Sodæ chloratæ, 445, 487
Cataplasms, or poultices, 445
Catarrh, with copious secretion of mucus, a combination of morphine and atropine useful in, 215 ; camphor a popular remedy in common, 288
Catechu, as an astringent, 305 ; for the teeth and gums, 308 ; characters, composition, and uses of, 828 ; pale, 866
Cathartics. *See* Purgatives
Catheter, importance of cleansing and disinfecting, 85
Caulophyllum (blue cohosh), character, composition, and uses of, 759
Caustic Ammonia, as a poison, with its antidote, 429 ; caustic lime, as ditto, 429 ; caustic potash, or soda, as ditto, 429
Potash, 533
Soda, 552
Caustics, nature and uses of, 302 ; general action of the alkaline group of metals as, 523 ; alum as a caustic, 586
Celandine. *See* Chelidonium
Celastraceæ, 809
Cells, how kept alive, and cause of death of, 221
Cerates, or ointments, 445
Ceratum, 446, 994, 1000
Camphoræ, 446, 928, 929, 994, 1000
Cantharidis, 446, 994, 999, 1001
Cetacei, 446, 995, 1000
Extracti cantharidis, 446, 994, 999, 1001
Plumbi subacetatis, 446, 633, 994, 1000
Ceratum Resinæ, 446, 952, 994, 999
Sabinæ, 446, 994, 999
Cerebellum, action of drugs on the, 182 ; different kinds of spirits appear to affect different parts of the, 183 ; action of alcohol on the, 695
Cerebral affections, blisters useful in, 302 ; circulation, diagram to show the effects on, of rapidly emptying the bladder, 223 ; stimulants, nature and action of, 160-163 ; action of carbolic acid on the cerebral centres, 736 ; tea as a powerful stimulant, 797
Cerium oxalate, as a local sedative, 327 ; character, uses, &c., of, 588
Symbol and atomic weight of, 9 ; physiological action of, 23
Cetaceæ, 994
Cevadilla, 964
Chalk, as an astringent, 305 ; as a dentifrice, 308 ; as a direct antacid, 321
Chalk, prepared, 581 ; officinal preparations of, 581 ; mixture of, 581 ; aromatic powder of, 581 ; compound powder of, 581 ; lozenges of, 581 ; hydrargyrum cum creta contains, 581
Chamomile, characters and uses of, 871
German, 871 ; a bitter, carminative, anthelmintic, 871 ; infusion of, 871
Oil of, 871 ; a tonic, stomachic, and carminative, 871
Chaperon's experiments on inhibitory paralysis, 136
Charcoal, reputed power of, for attracting oxygen, 59 ; as a deodorizer, or antiseptic, 86 ; as a dentifrice, 308 ; action of, on the stomach, 329 ; chief action of, 473
Charcoal, animal, preparation and constituents of, 478
Fumes, as a poison, with its antidote, 429
Purified animal, preparation, characters, and uses of, 479
Wood, its preparation, characters, action, and uses, 477, 478 ; poultice of, how to make, 477
Charta Cantharidis, 446, 1001
Epispastica, 446, 881, 949, 952, 995, 1000, 1001
Potassii nitratis, 446
Sinapis 446, 780
Cheken, composition, action, and uses of, 838
Chelidonium (celandine), characters, composition, and uses of, 779
Chemical constitution and physiological action, connection between, 22 ; the most important subject in pharmacology, 23
Chemical reactions, number and nature of, 19 ; of the metallic elements divided into two groups, 19, 20 ; which only occur between two bodies when a third is present, 58
Chenopodiaceæ, 925

Chenopodii, oleum, as a vermifuge, 925
Chenopodium, characters of, 925
Cherry-laurel water, as a poison, with its antidote, 431; cherry laurel leaves, nature, action, and use of, 836
Cherry, wild, as a nervous sedative and tonic, 836
Chestnut. *See* Castanea
Chilies, as carminatives, 330
Chill, or cold, utility of vascular stimulants in, 288; action of, on bronchi, 216
Chimaphila (pipsissewa), as a stimulant diuretic, 380; as an astringent and diuretic, 878
Chinicine, constitution of, 744
Chinoidin (quinoidin), 859
Chinoidinum, 444, 859
Chinoline, 743
Chinoidinæ sulphas, 859
Chiretta, as a bitter tonic, 895
Chloral, action of, on muscle, 104 *et seq.*; as a sedative, 128; diagram to show the action of, on the spinal cord, 133; a useful hypnotic, 167; as a general anodyne, 168, 170; action of, on the respiratory centre, 205; on the brain, 209; on the vessels and circulation, 241; on the vaso-motor centre, 245, 274; on the motor ganglia, 275; on the intestines, 337; as a poison, with its antidotes, 431; antagonistic action of, and strychnine and picrotoxine, 436, 437; antagonism of, to other drugs, 433-437
Chloral hydrate, action of, on the nervous system, 171, 172; on the vagus centre, 274; antagonism of, to atropine, 433-437; preparation and characters of, 714; action of, 715-717; as an antiseptic, in the mouth, and when injected under the skin, 715; first introduced into medicine by Oscar Liebreich, 715; his speculations regarding its action, 715; its action in the body, 715; in frogs and mammals, 716; on the temperature, respiration, and blood, 716; on the circulation, 716; on muscles and motor nerves, 716; on the spinal cord, 716; on the brain, 716; treatment of poisoning by, 717; uses of, 717
Chlorate of potash, action of, on bacteria, 73, 77; as a remedy for toothache, 309; as an antisialic, 316; action of, on the kidneys, 382; characters, action, and uses of, 538-540
Chlorate of soda, 557
Chlorides, test for, 520
Chloride of Ammonium, 567
Calcium, 582
Gold, 679
Iron, 671
Soda, 550
Sodium, 525 527
Tin, 634
Zinc, 601
Chloride of lime, action of, on enzymes, 63, 64; on bacteria, 75
Chloride of sodium, action of, on bacteria, 77; action of, as compared with bromide of potassium, 182; on the pulsations of the frog's heart, 264; effects of excess of, in the blood, 361, 362; one of the most important constituents of the body, 362
Chlorides, general action of the group of, 525-527
Chlorinated lime, 73; characters of, &c., 486; solution of, 487; inhalation of, 487
Chlorinated soda, solution of, 487; as a cataplasm of, 487
Chlorine, symbol and atomic weight of, 9; its relation to other members of a group, 15; action of, on infusiora, 51; on enzymes, 62-64; on bacteria, 73, 77; as a poison, with its antidote, 428; general source, characters, and mode of preparation of, 483-485; action of, 485; chlorine water, tests and uses of, 485, 486; chlorinated lime, its characters and uses, 486; solution of chlorinated lime, 487; inhalation of chlorine, 487; solution of chlorinated soda, 487; poultice of ditto, 487; uses of ditto, 487, 488
Chlorine water, action of, on bacteria, 75; nature, action and uses of, 485, 486
Chloroform, effects of, on the blood, 58; on enzymes, 63; on bacteria, 73, 75; on medusæ, 90; on mammals and leeches, 94; on muscle, 104 *et seq.*; as a sedative, 128; diagram to show the action of, on the spinal cord, 133; action of, on psychical processes, 160; action of, as an anæsthetic, 171 *et seq.*; acts directly on the nerve cells, 173; dangers arising from the use of, 175, 176; mode of administering, 177; action of, on the respiratory centre, 205; on the brain, 209; on the vagus centre, 274; on the vaso-motor centre, 274; on the motor ganglia, 275; as a cardiac stimulant, 286; as a rubefacient, 300; as a sialagogue, 312; as a local sedative, 327; as a carminative, 330; as a poison, with its antidotes, 430; antagonism of, to amyl nitrite, 437; purified, preparation, 719; tests, 720; preparations of, 720; action of, 720; when mixed with albumen, 720; a powerful solvent of protogon, 720; on the blood and skin, 720; on the mouth, stomach, and intestines, 721; the nervous system, 721; its action divided into three stages, 721; its action on the respiration, pulse, heart, and blood-pressure, 722; on the nervous system, 723; dangers in the administration of, 723; precautions to be taken, 724-726; uses of, and various plans for administering, 726, 727. *See* also Anæsthetics

Chloropicrin, action of, on bacteria, 76
Cholagogues, may act as indirect gastric tonics, 320; nature and action of, 340, 350; experiments with, 353-355; adjuncts to, 355; uses of, 356; remove bile from the body, 356
Cholera, corrosive sublimate in, 622; possible use of naphthalin in, 742
Chondrus, 984
Christison, Sir Robert, references to, 31, 768, 771, 914
Chrome alum, action of, on bacteria, 76
Chromic acid, action of, on bacteria, 76, 77; as a caustic, 301; characters and action of, as a disinfectant and caustic, 509
Chromium, symbols and atomic weight of, 9
Chrysarobin, characters and uses of, 823
Chrysarobinum, 444
Cicutine, as an antisialic, 317
Cicutoxine, action of, on the accelerating centre, 274; on the vaso-motor centre, 274
Cimicifuga (black snakeroot), characters and composition of, 753, 754; action and uses of, 754; as a stomachic, a cardiac tonic, and an expectorant, 754
Cinchona bark and its alkaloids the chief antiperiodics, 87; the former almost a specific in intermittent fevers, periodic headaches, neuralgias, &c., 87; cinchona alkaloids and their salts, 859; action and uses of, 862, 863
Cinchona, characters, &c., of, 854
  Bark, pale, 854
    Red, 855
    Yellow, 854
  Calisaya bark, yellow, 854
  Properties and composition of the cinchona barks, 856; physiological action of, 859, 862; uses of, 862, 863
Cinchonacea, 854, 859
Cinchoneæ, 854
Cinchonidina, 444, 859
Cinchonidine, an antiperiodic, 87; sulphate of, 859
Cinchonina, 444, 859
  Sulphas, 859
Cinchonine, 858
  Action of, on oxidation, 55; on the blood, 58; as an antiperiodic, 87; action of, on muscle, 104
  Sulphate of, 859
Cinnamic acid, action of, on bacteria, 76; on the kidneys, 383
Cinnamon and oil, as a carminative, 330
Cinnamon, characters and composition of, 926
  Aromatic powder of, 927
  Bark, 926
  Powder, compound, 927
  Oil of, 927; as a carminative and an astringent, 927
Circulation, action of drugs on the, 221-296; nature of the, in the arteries and veins, 221; effect of blood-pressure on the, 222; arrest of the, causes fainting and shock, 223; schema of the, 224-226; diagram illustrative of this, 225; nature of the, in the living body, 226; effects of variation in blood-pressure on the, 226, 227; method of ascertaining this, 227; alterations in blood-pressure in the, 229; relation of pulse-rate and arterioles to blood-pressure in the, 230-236; diagram of the, 234; method for maintaining artificial, in the rabbit's ear, 238; in the frog, 239; method of measurement of the, by the rate of flow, 239-242; action of potash salts on the, 532; of strong solution of ammonia, 569; of the heavy metals, 594; of the salts of iron, 594; of antimony, 651; of alcohol, 693; and on the cranial, 694; of the spirit of ether, 706; of chloral hydrate, 716; of salicylic acid, 741; of anemonin, 753; of opium, 771, 777; of pilocarpine, 806; of quinine, 864; of strychnine, 886; of belladonna or atropine, 902; of tobacco, 907; of veratrine, 966; of colchicum, 966; of extract of ergot, 981
Citrate of bismuth, 660; and ammonia, 660
  Iron, 674
    and ammonia, 674
    Ammonicum, 674
  Magnesium, 340
  Quinia, 674
  Quinine, 674
  Strychnine, 675
  Lithia, 562
  Potash, 535
Citrates, test for, 520
Citric acid, properties of, &c., 507; syrup of ditto, 507
Citrine ointment, 625
Citro-tartrate of soda (effervescent), 554
Clover, Mr., his plan of administering chloroform, 727
Cloves, characters, action, and use of, 837; as a carminative, 837; oil of, 837
Cloves and oil, as a carminative, 330
Clysters, injections, or enemas, 448
Coal gas, as a poison, with its antidotes, 428
Coats, reference to, 237
Cobalt, symbol and atomic weight of, 9; physiological action of, 23; causes slight contraction of the vessels, 240
Cobra poison, action of, on the infusoria, 51; convulsions caused by, 158
Coca. *See* Erythroxylon
Cocaine, action of, on muscle, 105; antagonism of, to morphine, 433-437; characters, action, and uses of, 786-788; as a local anæsthetic, 786-786; action of,

on the nerve-centres in man, 787 ; is said to lessen fatigue, 787 ; on animals, on the spinal cord, the respiration, the pulse, blood-pressure, and temperature, 787 ; use of, 788
Coccus, 1000
Cochineal, 1000 ; its characters and uses, 1000
Codeina, 444
Codeine, action of, on oxidation, 55 ; antagonism of, to chloral, 433-437 ; characters of, 766 ; action of, on the nerves and abdominal viscera, 766 ; on the spinal cord and motor centre in the brain, 766 ; uses of, 767 ; action and use of, in diabetes, 767
Codeïnes, artificial, 775
Cod-liver oil, one of the most efficient expectorants, 218 ; great virtue of, in chronic bronchitis, 218 ; a powerful hæmatinic, 361 ; as an alterative, 362 ; as an indirect emmenagogue, 398 ; character, composition, physiological, and therapeutic action of, 996-998
Coffeæ, 863
Coffee, composition, action, and use of, 865
Cohn's solution for experimenting with bacteria, 702
Colchici radix, 967
Collodion cum cantharide, 1001
Colchicine, action of, on the respiratory centre, 205 ; as a hepatic stimulant, 353, 355 ; as an alterative, 361 ; used in gout, 365 ; as a refrigerant diuretic, 379 ; as a poison, with its antidote, 431
Colchicum corm, 967
  Root, 967
  Seed, 967
  Seeds, 967 ; general action of, 968 ; special action of, on the skin, brain, and spinal cord, 968 ; on the sensory and motor nerves and the muscles, 968 ; on the circulation and the secretion of urine, 968 ; uses of, 969 ; treatment in poisoning by, 969
Cold, effects of, on the action of drugs, 33-35 ; on protoplasmic movements, 46 ; on the action of infusoria, 50 ; on muscle, 96, 100, 114 ; extreme, as an anæsthetic, 128 ; on the action of strychnine, 145 ; in preventing and inducing sleep, 166 ; as a local anodyne, 168 ; applied to the surface of a painful part, relieves the pain, 171 ; one of the chief local anæsthetics, 172 ; action of, on the respiratory centres, 205 ; in causing congestion, 216 ; apparatus for ascertaining the effect of, on the vessels of the frog's lung, 239 ; instrument for showing the action of, on the frog's heart, 259 ; one of the most powerful of vascular and cardiac sedatives, 296 ; action of, on inflammation, 298 ; diagram to show the effects of, in lessening the pain of inflammation, 299 ; as an antipyretic, 365, 368 ; local application of, 409
Cold bath, as an anaphrodisiac, 396 ; various uses of, and risks attending, 405-407
  Compresses, 410
  Douche, ascending, 409
    Spinal, 408
  Douches, 408
  Foot bath, 410
  Pack, 407
Coleoptera, 1000
Collodion, as a demulcent, 304 ; and a styptic, 305
Collodion, characters, action, and uses of, 790
  Cantharidal, 790
  Flexible, 790
  Styptic, 790
Collodions, 446
Collodium, 446, 705
  Flexile, 446, 705, 790, 934, 935, 949
  Cum cantharide, 446, 790
  Stypticum, 446, 790, 942
Colocynth, 841
Colocynth as a drastic purgative, 340 ; as a hepatic stimulant, 353, 355 ; colocynth pulp, composition, action, and therapeutics of, 842, 843 ; a powerful cathartic and diuretic, 842, 843
Cologne water, for perfuming, 793
Colophony, 952
Coma, condition of the veins and brain during, 165
Compound radicals, nature of, 19 ; most of them possess a paralysing action on the motor nerves, 23
Condurango, characters, action, and uses of, 893
Confectio opii, 446, 760, 815, 851, 936, 970
  Piperis, 446, 851, 936, 998
  Rosæ, 446, 831, 998
    Caninæ, 446, 831, 976
    Gallicæ, 446, 831, 976
  Scammonii, 446, 837, 851, 896, 970, 998
  Sennæ, 446, 814, 824, 825, 835, 852, 946, 976
  Sulphuris, 446, 480, 536
  Terebinthinæ, 446, 814, 950, 998
Confection of sulphur, mode of preparing, 480
Confections, electuaries, or conserves, 446
Congestion of the internal organs arising from cold, 216 ; utility of vascular stimulants in, 288
Coniferæ, 949
Coniïne, effects of, on oxidation, 55 ; action of, on the spinal cord, 132 ; as a general anodyne, 169 ; on the inhibitory powers of the vagi, 268, 269. *See* Hemlock

Conium, as a local and general anodyne, 169 ; the vapour of, has a local sedative action on the lung, 214 ; as an anaphrodisiac, 396 ; as a poison, with its antidotes, 431; nature, actions, and uses of, 845, 846
Conjunctiva of the eye, action of drugs on the, 184
Constipation, cause of, and remedies for, 335 ; diagram to show how ovarian irritation probably causes, 336 ; action of opium in, 336 ; and of small doses of belladonna, 336
Contraction of the pupil of the eye, origin and nature of, 189
Convallamarin, as a cardiac tonic, 289
Convallaria majalis, as a cardiac tonic, 289
Convolvulaceæ, 895
Convulsions produced by poisoning, 25, 26 ; and by strychnine, and other drugs acting on the spinal cord, 141-151 ; by the absence or excess of oxygen, 145 ; whether convulsions are caused by the action of poison on the brain or the spinal cord, 149 ; certain drugs, when taken, are the cause of, 156 ; they are usually of spinal or cerebral origin, 157 ; asphyxial convulsions, 157 ; experiments to ascertain whether they are asphyxial or not, 158 ; excitement of the respiratory centre causes, 202 ; asphyxial, only occur in warm-blooded animals, 202 ; carbolic acid produces convulsions in frogs, 736
Copaiba, as a stimulant diuretic, 379 ; value of, in inflammation of the bladder, 392
Copaiva, characters, &c., of, 826 ; balsam of, 826 ; oil of, characters, action, and uses of, 826
Copper, sources, reactions, uses, &c., of, 604
  Acetate of, 605
    Test solution of, 605
  Sub-acetate of, 605
  Sulphate of, 604
    Anhydrous, 604
    Test solution of ammonio-, 605
Copper sulphate, action of, on enzymes, 63 ; on bacteria, 75 ; on annulosa, 94 ; as a caustic, 301, 605 ; as an astringent, 305 ; as a local emetic, 325 ; character, action, and uses of, 604-606
Copper, symbol and atomic weight of, 9 ; physiological action of, 23 ; action of, on muscle, 104 *et seq.* ; causes powerful contraction of the vessels, 240 ; double salts of, action of, on the cardiac muscle, 276 ; on the capillaries, 277 ; as a poison, with its antidote, 431; nature, action, and uses of, 604-606
Coriander and oil, as a carminative, 330
Coriander, characters of, 852
  Fruit, 852
  Oil of, a carminative and stimulant, 852
Cornaceæ, 853
Cornea, chief drugs employed in disease of the, 184 ; action of alum on, 184, 586
Corn smut, 983
Cornus, characters and action of, 853
Cornutine, 981
Corolliflorae, 853
Corrosive chloride of mercury, 622
Corrosive sublimate, action of, on infusoria, 51 ; on enzymes, 62-64 ; on bacteria, 71, 73, 75, 77 ; extraordinary destructive power of, might be useful in destroying bacilli, 82 ; owes its curative power in cases of infantile dysentery to its antiseptic action, 85 ; the only trustworthy disinfectant for destroying septic organisms, 86 ; as a poison, with its antidotes, 431 ; nature and uses of, 622, 623 ; one of the most powerful antiseptics known, 623 ; use of, in cholera, 623 ; poisoning by, and treatment for, 623
Coto alkaloids, action of, on the intestines, 367 ; Albertoni's investigations regarding the action of the, 367
Coto bark, composition, action, and uses of, 927 ; paracoto bark, 928
Cotoine, action of, on the intestines, 337
Cotton, gun, preparation and uses of, 789
  Root bark, characters, action, and uses of, 788
  Seed oil, characters and uses of, 788
  Wool, what derived from, 789
Couch-grass, as a demulcent, 974
Cough, chest and stomach, cause of, remedies for, and general treatment of, 211-220 ; diagram of the afferent nerves by which it may be excited, 212 ; action and use of expectorants in, 215-219 ; of emetics, 219 ; of warmth and moisture, 220 ; of respirators, 220 ; of warm clothing, friction, liniments, poultices, and plasters, 220 ; action of lactucarium in allaying, 873
Cowling, Dr., his rule for dosage, 438
Cramps of the muscles, cause and general treatment of, 180, 181
Cranesbill, 783
Cranial circulation, 161 ; action of alcohol on the, 694
Cream of tartar, nature and uses of, 536
Creasote, action of, on infusoria, 51 ; no effect on ptyalin, 62 ; on enzymes, 63, 64 ; on yeast and bacteria, 64 ; as a local anodyne, 169 ; as a remedy for toothache, 309 ; as a local sedative, 327 ; as a poison, with its antidote, 431 ; characters, tests, and preparations of, 738 ; action of, as a muscular poison, 739 ; on the blood, skin, and mouth, 739 ; on the pulse, respiration, and urine, 739 ; uses of, 739

Croix, N. de la, results of his experiments with different drugs on bacteria, 72, 73
Croton chloral, action of, on the vagus centre, 274; character, action, and uses of, 718
Croton oil, as a pustulant, 301; as a drastic purgative, 340; as a poison, with its antidote, 431; action of, externally and internally, 934; use of, ditto, 934; treatment of poisoning by, 934
Cruciferæ, 779
Crum-Brown, reference to, 124*n.*, 775*n.*
Crumb of bread, 973
Cryptogams (sub-kingdom II.), 978-984; filices, 978; lichens, 979; fungi, 979; algæ, 984
Cubeb, oleoresin of, preparation, action, and uses of, 937; as a stimulant and diuretic, 938
Cubeba, 937
Cubebs, as a sialagogue, 312; as a stimulant diuretic, 379; characters and composition of, 937
Oil of, 937
Cucumber fruit, squirting, 843
Cucurbitaceæ, 841
Culver's root. *See* Leptandra
Cumarin, action of, on the cardiac muscle, as an antipyretic, 276
Cupping, wet, 367
Cupuliferæ, 941
Curare, physiological action of, on the motor of efferent nerves, 20; when applied externally and internally, 25, 26; opposite effect of, when differently administered, 29; effects of, on the blood, 58; on mollusca, 93; on muscle, 99, 105, 120, 121; list of drugs which have a similar action to, on the motor nerves, 123, 124; on the muscles of respiration, 203; on the vaso-motor nerves, 243; on the inhibitory power of the vagi, 268, 269; on the vagus ends in the heart, 275; on the nerves of the salivary gland, 311; action of the liver on, 354; as a poison, with its antidote, 431; characters, composition, and action of, 889; on the motor nerves, vagus, and sensory nerves, 889; on the spinal cord, muscles and vessels, 889; on the blood-pressure and on salivation, 889; effects of, on the general system, 889; uses of, 890
Curd soap, 988
Cyanide of potassium, action of, on medusæ, 91; as a poison, with its antidote, 431
Cyanide of silver, 609; of mercury, 626
Cyanogen, action of, on the motor ganglia, 275
Cydonium, characters and use of, 829
Cypripedium, characters and use of, as an antispasmodic, 969

D.

Da Costa, Dr., reference to, 295
Dandelion protoplasm, experiment with, on oxygen, 54, 55
Dandelion root, characters and action of, 872; on the liver, and as a diuretic, 872
Dastre, reference to, 236, 256
Daturine, as a mydriatic, 186; action of, on the vagus centre, 274; on the vaso-motor centre, 274; on the inhibitory ganglia, 275; antagonism of, to morphine, 433-437; nature, action, and use of, 906
Davy, Sir H., split up some supposed elements into oxygen and a metal, 10; his observation on the properties of nitrous oxide, 179
Decoction of lemon, as an antiperiodic 795
Decoctions, 446
Decoctum, aloes compositum, 447, 813, 814, 960, 972
Cetrariæ, 447, 979
Cinchonæ flavæ, 447, 855
Granati radicis, 447, 841
Hæmatoxyli, 447, 822, 927
Hordei, 447, 974
Papaveris, 447, 760
Pareiræ, 447, 758
Quercus, 447, 941
Sarsæ, 447, 957
Sarsæ compositum, 447, 801, 814, 930, 957
Sarsaparillæ compositum, 447, 801, 930, 957
Scoparii, 447, 814
Taraxaci, 447, 872
Ulmi, 447, 945
Delirium tremens, cause, symptoms and treatment of, 696, 697
Delphinine, action of, on the frog's heart, 264; on the accelerating centre, 274; on the vaso-motor centre, 274; nature, action, and use of, 752
Demulcents, nature, action, and therapeutic uses of, 303-305; linseed as a demulcent, 783; liquorice root as a demulcent, 814; gum, acacia or arabica, as a, 828; quince seed as a, 829; sassafras pith as a, 931; elm as, 945; triticum as, 974; Iceland moss as, 979; chondrus as, 984
Deodorizers or deodorants, nature and action of, 83, 86; iodoform as a, 728; carbolic acid as a, 735
Desmobacteria, 67
Dew-Smith, reference to, 93*n.*
Diabetes, action of codeine in, 766
Diaphoretics, action of, on the secretion of sweat, 383; antimony as a diaphoretic, 653; eupatorium as a, 869; ipecacuanha as, 864; asclepias as a, 892; melissa or balm as, 921; origanum as, 921; cam-

phor as, 929 ; oil of sassafras as, 930 ; serpentary root as, 932
Diarrhœa, astringents have a powerful effect in checking, 306
Diastase, 60, 61
Dickinson, reference to, 916
Didymum, symbol and atomic weight of, 9
Diedrich, references to, 773, 774*n*.
Diedülin, reference to, 124
DIGESTIVE SYSTEM, ACTION OF DRUGS ON THE, 308-358 ; on the teeth, 308 ; on the saliva, as sialagogues, 309-315 ; on thirst, as refrigerants, 315 ; on the salivary secretion, as antisialics, 316 ; on the appetite, as gastric tonics, 317-321 ; on acidity, as antacids, 321 ; on vomiting, as emetics, 321-327 ; on the stomach, as gastric sedatives, 327 ; on the gases of the stomach, as carminatives, 328-330 ; on the intestines, 330-339 ; as purgatives, 339-345 ; as irritant poisons, 345-349 ; on the liver, 349-357 ; on the pancreas, 357 ; on the intestines, as anthelmintics, 357
Digestive tract, application of drugs to the, 424-427 ; by the mouth and pharynx, 424 ; as masticatories, 425 ; as gargles, 425 ; by the stomach, 425 ; by the stomach-pump, 426 ; by the gastric syphon, 426 ; to the intestine, 426 ; as enemata, 426 ; as suppositories, 427 ; action of opium on the, 776 ; action of digitalin on the, 912
Digestives, when necessary, 360
Digitalin, effects of, on medusæ, 90 ; action of, on the vision, 193 ; on the frog's heart, 265 ; on the vagus centre, 274 ; on the cardiac muscle, 276 ; as a cardiac tonic, 289 ; antagonistic action of, 436, 437 ; preparation and characters, 909 ; chemistry of, 909 ; general action of, 910 ; special action of, on the muscles, nervous system, and spinal cord, 910 ; on the brain, respiration, and blood-pressure, 910 ; on the heart and arterioles, 911 ; diagram of a pulse-wave before and after injection of, in a dog, 911 ; on the vagus roots and ends, 911 ; peculiar action of, on the frog's heart, 911 ; on the digestive organs and the urine, 912 ; effect of temperature on the action of, 912 ; diagram showing effects of rise of temperature alone, 913 ; ditto, showing effects of rise, after injection of, 913 ; ditto, showing action of, after temperature, 914 ; action of different preparations of, 914 ; uses of, 915 ; precautions, 916 ; treatment of poisoning by, 916
Digitalinum, 444, 909
Digitalis, effect of varied quantities of, on the pulse, 27 ; cumulative action of, 31 ; has sometimes no action on the pulse in pneumonia, 35 ; acts differently on the heart of a frog from that of mammals, 40 ; action of, on oxidation, 55 ; on mollusca, 93 ; action of, on the brain, 165 ; as a cardiac tonic, 214 ; as a vascular tonic, 218 ; diagram showing the blood-pressure and form of the pulse wave before and after the injection of, in the dog, 235 ; on the vagus centre, 274 ; on the cardiac muscle, 276 ; on the capillaries, 277 ; on the heart, as a cardiac tonic, 289, 290 ; the question of the use of, in aortic regurgitation considered, 291 ; caution to be observed in the use of, as a cardiac tonic, 292 ; as a vascular tonic, 293 ; as sedative, 296 ; as a styptic acting on the blood-vessels, 307 ; has the power of lessening or arresting hæmorrhage, 307 ; as a general emetic, 325 ; experiment with, on blood pressure, 377, 378 ; as a refrigerant diuretic, 379 ; as an anaphrodisiac, 396 ; as a direct emmenagogue, 398 ; as a poison, with its antidotes, 431 ; antagonism of, to other drugs, 433-437
Digitalis (foxglove), characters, &c., of, 908
Leaf, 908
Digitin, composition of, 909
Digitonin, composition of, 909, 914
Digitoxin, composition of, 909 ; action of, on the cardiac muscle, 276 ; as a cardiac tonic, 289. *See* Digitalis
Dilatation of the pupil of the eye, origin and nature of, 187-189
Dilator muscle of the iris, nature and functions of, 183
Dill, as a stimulant diuretic, 379
Dill and oil, as a carminative, 330
Dill, fruit, characters and use of, as a carminative, 850
Oil of, 850
Dimethyl-coniïne, 846
Diosmeæ, 803
Diseases caused by mould fungi, 68 ; by bacteria, 68
Disinfectants, Koch's experiments on bacteria with, 74-78 ; nature and action of, 83, 86 ; super-heated steam the best disinfectant under ordinary circumstances, 86 ; borax as a disinfectant, 555 ; carbolic acid as a, 735 ; thymol as, 920
Distilled water, action of, on bacteria, 75 ; and calcium salt, on the frog's heart, 264 ; as a lithontriptic, 382
Diuretics, nature and mode of action of, 378 ; list of refrigerant and stimulant, 379 ; uses of, 380 ; adjuvants to, 381 ; alkalis as, 525 ; iodide of ethyl as a diuretic, 714 ; caulophyllum as, 759 ; caffeine as a, 798 ; tansy as, 869 ; dandelion root as, 872 ; uva ursa as, 877 ; chimaphila as, 879 ; benzoic acid as, 870 ; serpentary root as, 932 ; thuja as, 954 ; oil of juniper as, 955 ; sarsaparilla as, 957 ; garlic as, 958 ; squill as, 959

Dogiel, reference to, 246*n.*, 253
Dog-rose, fruit of the, 831
Dogs, experiments with drugs on, 40-42 ; Magendie's series of experiments on the action of strychnine on the reflex powers of the spinal cord of, 147 *et seq.*; easiest way of anæsthetising, 178 ; diagram of a stopcock by which air or vapour, or two kinds of gas, may be given to, 178 ; diagram showing the blood-pressure and form of the pulse-wave before and after the injection of digitalis in, 235 ; action of the heart in, 246 ; difference between rabbits and, in this respect, 247 ; cause of the stoppage of the heart in, 255 ; effects of large doses of opium injected into, 335 ; diagram of a pulse-wave before and after injection of digitalis in, 911 ; action of, on, 911, 912
Dogwood, 853 ; dogwood-quinine, 854
Jamaica, action and use of, 827
Donaldson, reference to, 911
Donovan's solution, 648
Dosage, the rules which affect correct, 438
Dose, nature, size, and effects of a, on the system, 27, 28 ; rules which regulate the amount of a, for children and adults, 438 ; Dr. Young's rule, 438 ; Dr. Cowling's, 438 ; the author's proposed modification of Dr. Cowling's, 438
Douche, nasal, diagram of a, 421
Douches, cold, nature and uses of, 408 ; the spinal, 408 ; the ascending, 409
Dover's powder, as a vascular stimulant, 287, 288 ; as a sudorific, 368 ; in combination with mercury, 618 ; ten grains of, useful when a cold is coming on, 776 ; will cause diaphoresis, 777
Dropsy, the pathology of, 293-295 ; diagram of Ranvier's experiment on, 293 ; the principal causes of, 293 ; and drugs that are useful in, 294, 295 ; usefulness of upward friction in, 301
Drugs, reaction between, and the various parts of the body, 2, 3 ; changes undergone by, in the body, 3 ; physiological action of, depends chiefly upon their power of acting on one tissue or organ first, 20, 21 ; the effects produced by large and moderate doses of veratrine on the frog an example of this, 21 ; effect of artificially modifying the chemical constitution of, 22, 23 ; CIRCUMSTANCES WHICH AFFECT THE ACTION OF, ON THE ORGANISM, 25-42 ; direct and indirect action of, 26 ; local and remote action of, 26 ; relation of effect to quantity employed, 26 ; the doctrine of homœopathy in, 27 ; the dose, 27 ; size, 28 ; and mode of administration of, 28 ; difference betwixt venous and subcutaneous injection and absorption by the stomach, 28-30 ; action of the liver on, 29 ; absorption and excretion of, 29, 30 ; cumulative action of, 30 ; effect of different preparations of, 31 ; of fasting on the action of, 31 ; of habit, 32 ; of temperature, 32 ; effect of temperature on the action of, on the spinal cord, 34 ; the proper definition of the action of, is the reaction between them and the various parts of the body at a certain temperature, 35 ; effects of climate on, 36 ; time of day, 36 ; season, 36 ; and disease, 37 ; use of experiments in the administration of, 37 ; effects of idiosyncrasies on the power of, 38 ; objections to experiments, 39 ; difference in the effect of, on men and animals, and on different animals, 39-41 ; erroneous deductions from, 41, 42 ; ACTION OF, ON PROTOPLASM, BLOOD, AND LOW ORGANISMS, 43-87 ; on albumen, 43 ; on protoplasmic movements, 45-49 ; on infusoria, 49-51 ; relations of motion and oxidation to, 51-55 ; action of, on oxidation, 54 ; on the blood, 55-58 ; on enzymes, 61-64 ; on the movements of bacteria, 70 ; on the reproduction of bacteria in general, 71 ; and on the destruction of the germs, 71 ; table of the comparative action of different, on bacteria, 72, 73 ; action of, on particular species of, 74 ; mode of experimenting on the action of, on the reproduction of bacteria, 74 ; Koch's experiments with three groups of disinfectants on bacteria, 75 ; action of, on the development and growth of bacilli, 77 ; strength of various disinfectants required to prevent the development of anthrax bacilli, 77 ; effect of, on the action of bacteria in the animal body, 82; ACTION OF, ON INVERTEBRATA, 88-94 ; on the medusæ, 88-92 ; on mollusca, 92 ; on ascidians, 93 ; on annulosa, 93 ; ON MUSCLE, 95-118 ; on voluntary muscle, 95 ; as poisons to the muscles, 103-107 ; the action of, on muscle is voluntary, not absolute, 111 ; on involuntary muscular fibre, 112 ; hypothetical considerations regarding the action of, on muscles, 116 ; ON NERVES, 119-128 ; on motor nerves, 119 ; on motor nerve endings, 121 ; on the trunks of motor nerves, 125 ; on sensory nerves, 126 ; on the peripheral ends of sensory nerves, 128 ; ON THE SPINAL CORD, 129-151 ; on the conducting power of the cord, 129 ; on the reflex action of the cord, 130, 134 ; direct, indirect, and inhibitory paralysis of the cord by, 134-141 ; explanation of the action of certain drugs on a given hypothesis, 141-146 ; stimulating action of, on the reflex powers of the cord, 147-151 ; ON THE BRAIN, 152-183 ; depressant action of, on the motor centres, 155 ; irritant action of, on motor centres in the brain, 156 ; action of, on the sensory and psychical

centres in the brain, 159-183; drugs which increase the functional activity of the brain, 160; nerve stimulants, 160; cerebral stimulants, 160; which lessen the functional activity of the brain, 163; hypnotics, or soporifics, 164; narcotics, 167; anodynes, or analgesics, 168; anæsthetics, 171-179; antispasmodics, 180; action of drugs on the cerebellum, 182; ON THE ORGANS OF SPECIAL SENSE, 184-196; on the eye, 184; on the conjunctiva, 184; on the lachrymal secretion, 184; on the pupil, 185-190; on accommodation, 190; on intra-ocular pressure, 190; on the sensibility of the eye, 192; in producing visions, 193; on hearing, 193; on smell, 194; on taste, 195; ON RESPIRATION, 197-220; action of, when injected into the jugular veins, 204; on the respiratory centre, 205-209; on the respiratory nerves, 209-220; ON THE CIRCULATION, 221-296; method of ascertaining the action of, on the circulation, 227-229; diagrams illustrative of this, 231-236; investigation of the action of, on the arterioles, 236-239; another method of ascertaining the action of, on the blood vessels, 239-242; action of, on the vaso-motor and vaso-dilating nerves, 242; on reflex contraction of vessels, 245; as the cause of alteration in blood-pressure and pulse-rate, 251; on the pulse-rate, 253; on the cardio-inhibitory functions of the vagus, 254; on the reflex stimulation of the vagus, 255; on vagus roots, 255; on the heart of the frog, 258-263; on the muscular substance of the heart, 263-268; on the vagus in the frog, 268; on inhibition of the heart, 268-270; theories regarding the mode of action of, upon the heart, 270-273; diagram to illustrate the action of, on the various parts of the circulatory apparatus, 273; on the vagus centre, 274; on the accelerating and vaso-motor centres, 273; on the vagus-ends in the heart, 275; on the inhibitory and motor ganglia, 275; on the cardiac muscle, 276; on the vaso-motor nerves, 176; on the capillaries, 277; various experiments with, on the heart of a frog, 277-285; thereapeutic use of, acting on the circulation, 285-296; as cardiac stimulants, 286; as vascular stimulants, 287; as cardiac tonics, 288-292; as vascular tonics, 293; as cardiac sedatives, 295; as vascular sedatives, 296; ACTION OF, ACTING ON THE SURFACE OF THE BODY, 297-307; as irritants and counter-irritants, 297-303; as rubefacients, 300-302; as vesicants, 300-302; as pustulants and caustics, 302, 303; as emollients and demulcents, 303-305; as astringents, 305, 306; as styptics, 306, 307; ACTION OF, ON THE DIGESTIVE SYSTEM, 308-358; on the teeth, 308; as sialagogues, 309-315; as refrigerants, 315; as antisialics, 316; as gastric tonics, 317; on the secretion of the stomach, 319; on the movements of the stomach, 320; as antacids, 321; as emetics, 321-327; as gastric sedatives and anti-emetics, 327; as carminatives, 328-330; action of, on the intestines, 330-358; on absorption from the intestines, 337; as intestinal astringents, 337; as purgatives, 339-345; as irritant poisons, 345-349; action of, on the liver, 349; as hepatic stimulants, 352; as cholagogues, 353-355; as hepatic depressants, 356; action of, on the pancreas, 357; as anthelmintics, 357; ON TISSUE CHANGE, 359-368; as tonics, 359; ON EXCRETION, 369-391; on the kidneys, 369 *et seq.*; as diuretics, 378-381; as albuminuria, 381; as lithontriptics, 382; on the skin, as diaphoretics and sudorifics, 383-387; as antihydrotics or anhydrotics, 387-390; on the bladder, 390-392; ON THE GENERATIVE SYSTEM, 393-401; as aphrodisiacs and anaphrodisiacs, 393-397; as emmenagogues and ecbolics, 397-399; upon milk, 399-401; METHODS OF ADMINISTERING, 402-427; by the skin, 402 *et seq.*; as baths, 404; cold baths, 405-411; warm baths, 411; medicated baths, 413; vapour baths, 414; air baths, 415; friction and inunction, 415; endermic application of, 417; hypodermic administration of, 418; application of, to the eye, 420; to the ear, 420; to the nose, 421; to the larynx, 422; to the lungs, 423; to the digestive tract, 424; to the urethra, 427; to the vagina and uterus, 427; as antidotes, 428-433; antagonistic action of, 434-437; table showing the antagonism of, 437

Drunkenness, general effects of, 693 *et seq.*; causes and treatment of, 697

Dryadeæ, 830

Duboisine, action of, as a mydriatic, 186; on the respiratory centre, 205; on the inhibitory ganglia, 275

Dujardin-Beaumetz, reference to, 940

Dulcamara, characters, action, and uses of, 898; action of, on the nervous system, heart, respiration, and temperature, 898; as an alterative, 898

Dumas, M., points out a curious relationship between the potassium and the lithium group of elements, 15

Dyad metals, 575 *et seq.*

Dyspepsia, atonic, slight stimulants produce appetite in, 317

Dyspnœa, nature and cause of, 202-204; action of aconitia on, 749

E.

Ear, various diseases of the, and their treatment, 193, 194 ; action of salicylic acid on the, 741 ; application of drugs to the, 420 ; diagram of a vulcanite syringe for injecting solutions into the, 420 ; action of pilocarpine on the, 805, 806

Eau de Cologne, as a cardiac stimulant, 286 ; as a general stimulant, 749 ; uses of, in headache, fainting, &c., 698

Ecbolics, nature and action of, 397 ; list of the chief, 399 ; uses of, 399 ; adjuncts to, 399

Eckhard, references to, 144*n.*, 145*n.*, 243*n.*

Egg albumen, 995
Yolk of, 995

Elaterin, characters and action of, 844 ; a powerful hydragogue cathartic, 844 ; action of, on the nervous system, 844

Elaterium, as a drastic purgative, 340 ; and a hydragogue, 340 ; characters and composition of, 843

Elder, characters and uses of, 853
Flowers, 853

Elecampane, 875

Electricity, effects of, on the protoplasmic movements, 46, 47 ; on the action of infusoria, 50

Elements composing the earth, list of the, with their symbols and atomic weights, 9, 10 ; nature of the, 10 ; recent spectroscopic researches prove them to be compounds, 10 ; dissociation of the, 11 ; spectrum analysis of the, 11-14 ; evolution of the, 13, 14 ; classification of the, 14 ; according to their atomic weight, 14 ; in groups, 15 ; in series, 16 ; Mendelejeff's classification, 17 ; differences between the even and the uneven series, 18 ; the classification in series not yet perfect, 18 ; general relations of the, 19-24 ; organic radicals, 19 ; chemical reactions of the, 19 ; physiological reactions of the, 20 ; the latter divided into groups, 20 ; relation between atomic weight and physiological action, 21 ; between spectroscopic characters and physiological action, 21 ; connection between chemical constitution and physiological action, 22 ; relation between isomorphism and physiological action, 23 ; Blake's division of the, into nine groups, according to their physiological action, 23 ; his classification and conclusions cannot be accepted as final, 24

Elemi, nature and use of, 813

Elixir aurantii, 447, 793

Elixirs, 447

Elm, characters and uses of, 945 ; as a demulcent, astringent, and tonic, 945
Bark, 944 ; characters of, 945

Embrocations or liniments, 453

Emetics, aid the action of antiperiodics, and sometimes cure ague without their aid, 87 ; powerful adjuncts to expectorants, 219 ; nature and action of, 321 ; divided into two classes, local and general, 325 ; the various uses of, 325-327 ; in simply emptying the stomach, 325 ; in expelling foreign bodies from it, 325 ; in removing the contents of it, 325 ; in removing poison from it, 326 ; and bile, 326 ; and obstructions from the air passages, 327 ; contra-indications of, 327 ; anti, 327 ; salt as an emetic, 551 ; alum as, 586 ; sulphate and acetate of zinc as, 599 ; sulphate of copper as, 301, 605 ; subsulphate of mercury as, 620 ; antimony as, 652 ; hydrochlorate of apomorphine as, 765 ; mustard as a prompt and direct, 781 ; ipecacuanha as an, 865 ; phytolacca root as, 924 ; iris as, 972

Emetine, action of, on muscle, 105 ; as a depressant expectorant, 219 ; action of, on the cardiac muscle, 276 ; as a general emetic, 325

Emmenagogues, nature and action of, 397 ; list of indirect and direct, 398 ; caulophyllum as an emmenagogue, 759 ; oil of rue as an, 802 ; tansy as, 869 ; hedeoma or pennyroyal as, 921 ; origanum as, 921

Emollients, nature, action, and therapeutic uses of, 303-305

Emphysema, with copious secretion of mucus, a combination of morphine and atropine useful in, 215

Empirical therapeutics, explanation and example of, 1

Emplastrum Ammoniaci, 447, 848, 881
cum Hydrargyro, 447, 616, 631, 848, 881
Arnicæ, 447, 873, 881
Asafœtidæ, 447, 631, 847, 848, 881
Belladonnæ, 447, 881, 900
Calefaciens, 447, 926, 952, 999, 1001
Cantharidis, 447, 952, 988, 994, 999, 1001
Capsici, 447, 881, 899
Cerati saponis, 447, 505, 631, 881, 999
Ferri, 447, 631, 669, 881, 953
Galbani, 447, 631, 848, 881, 999
Hydrargyri, 447, 616, 663, 881
Icthyocollæ, 447
Opii, 447, 631, 760, 761, 881, 952
Picis, 447, 881, 926, 949, 952, 953, 999
Burgundicæ, 447, 953
Canadensis, 447, 953
Cum Cantharide, 447, 953
Plumbi, 447, 631, 881
Iodidi, 447, 633
Resinæ, 447, 631, 881, 882, 952
Saponis, 447, 631, 881, 882, 952

Endermic application of drugs, 417
Endocarditis, ulcerative, micrococci present in, 81
Endogenæ, 957
Enema Aloes, 448, 960, 962
Magnesia sulphatis, 448, 881
Opii, 448, 760
Terebinthinæ, 448, 950
Asafœtidæ, 448, 847
Tabaci, 448, 907
Enema of sulphate of magnesia, 590
Enemas, injections, or clysters, 448
Enemata, nature and uses of, 426
Engelmann, reference to, 113, 185*n*.
Enzymes, nature of, 60 ; action of drugs on, 61 ; functions of, 61 ; list of the chief, in the animal body, 61, 62 ; method of ascertaining the action of drugs on, 62 ; table and diagram showing the different action of drugs on different, 63, 64; methods of liberating from zymogens, 65 ; alteratives supposed to alter in some way the action of, 362
Epidermic application of drugs, 402
Epsom salts, 590
Erbium, symbol and atomic weight of, 9
Ergot, action of, on the vaso-motor centre, 274 ; on the motor ganglia, 275 ; as a vascular sedative, 296 ; as a styptic acting on the blood-vessels, 307 ; has the power of lessening or arresting hæmorrhage, 307 ; as a direct emmenagogue, 398 ; one of the chief ecbolics, 399 ; as a poison, with its antidotes, 432 ; its characters, composition, and general action, 980 ; special action, 981
Ergot, extract of, its action on the nervous system, muscles, and sensory nerves, 981 ; on the circulation and heart, 981 ; on the vaso-motor system, respiration, and secretion, 982 ; on the alimentary canal and uterus, 982 ; therapeutics, 983
Ergot of rye, 979
Ergotinic acid, 981
Ergotinin, 981
Ergotism, symptoms of, 980, 981
Ericaceæ, 877
Erysipelas, caused by micrococci, 81
Erythrophlœin, as a cardiac tonic, 289
Erythrophlœum, state of the pulse and blood-pressure in a cat after division of the spinal cord and injection of, 232 ; action of, on the vagus roots, 254 ; on the cardiac muscle, 276 ; as a cardiac tonic, 289 ; diagram showing the effect of, upon the blood-pressure ; and secretion of urine, 377 ; as a refrigerant diuretic, 379
Erythroxylaceæ, 786
Erythroxylon (coca), characters and composition of, 786 ; action of, as a powerful local anæsthetic, 786; on the nerve centres, respiration, pulse, and blood-pressure, 787 ; on mammals, 787 ; on the secretion of saline and sweat, 787 ; on the urine and temperature, 787 ; uses of, 787
Escharotics, acids as, 496
Esmarch, reference to, 724
Essences, 448
Essentia Anisi, 448, 849
Menthæ piperitæ, 448, 918
Ether, action of, on bacteria, 75 ; on annulosa, 94 ; on muscle, 104 *et seq.* ; on psychical processes, 160 ; nature of narcosis by, 171 ; first used as an anæsthetic in dentistry, 179 ; as an antispasmodic, 181 ; action of, on the respiratory centre, 205 ; on the brain, 209 ; on the vaso-motor centre, 274 ; on the motor ganglia, 275 ; as a cardiac stimulant, 285-6 ; as a vascular stimulant, 287 ; as a rubefacient, 300 ; as a sialagogue, 312 ; as a local sedative, 327 ; and acetic acid, as a carminative, 330 ; action of, on the vascularity of and absorption in the intestines, 337 ; as a poison, with its antidotes, 432 ; its preparation, character, and uses, 704 ; action of, on the skin, 705 ; mouth, stomach, and intestine, 706 ; cerebral hemispheres, spinal cord, and medulla oblongata, 706 ; muscles, nerves, and blood, 706 ; and heart, 706 ; difference between chloroform and, 706, 707
Ether, simple and saline—
Acetic, 707
Amyl, nitrite of, 708
Compound spirit of, 707
Nitro-glycerine, glonoine, 712
Oil of, 707
Pure, 705
Spirit of, 705
Nitrous, 707
Stronger, 705
Ether spray as an anæsthetic, 128
Ethereal oils, action of, on bacteria, 82
Ethyl, iodide of, preparation and characters of, 715 ; action and uses of, as an anæsthetic, alterative, diuretic, antispasmodic, 715 ; mode of administration, 714
Ethyl-atropine, action of, on the motor nerves, &c., 903
Eucalyptol, action of, on bacteria, 77 ; as a disinfectant, 86 ; and antiperiodic, 87 ; as a vermicide, 357
Eucalyptus, character, action, and uses of, 840 ; oil of, 840 ; action of, as an antiseptic, 840 ; on the blood, spleen, and skin, 840 ; effects of, when swallowed, 840 ; action of, on the nerve centres, spinal cord, brain, medulla, and heart, 840 ; on the temperature, 840 ; how excreted, and uses of, 841
Eucalyptus oil, action of, on enzymes, 63 ; on bacteria, 73 ; use in blood-poisoning, 86, 841
Eulenberg, references to, 30, 171

Euonymin, as a cholagogue, 340; as a hepatic stimulant, 353
Euonymus, wahoo, nature and action of, 810; acts as a hepatic stimulant, &c., 810
Eupatorium, characters and use of, 872; as a tonic, diaphoretic, emetic, and cathartic, 872
Euphorbia, action of, on the nose, 210
Euphorbiaceæ, 933
Euphorbium, as a vesicant, 301
Eustachian tube, the, some diseases of, and their treatment, 194
Evolution of species and of elements, 13, 14
Ewald, A., reference to, 146
Ewers, references to, 210, 254*n*.
Excretion, action of drugs on, 369-392
Exogenæ, exogens, 747 *et seq.*, 809 *et seq.*, 949 *et seq.*
Expectorants, nature and action of, 215-220; action of, on the secretions of the air passages and the mucous membranes, 215, 216; on the expulsive mechanism, 219; list of depressant, 219; of stimulating, 219; adjuncts to, 219, 220; antimony as an expectorant, 653; cimicifuga (black snakeroot) as an, 754; senega root as a stimulating, 785; myrrh as, 812; balsam of Peru as, 817; balsam of Tolu as, 817; cheken as, 838; galbanum and ammoniacum as, 848; ipecacuanha as, 865; benzoic acid as, 880; marrubium as, 921; cascarilla bark as, 933; garlic as, 958; squill as, 959
Experiments, use of, 37; objections to, answered, 39-41; erroneous deductions from, 41, 42; mode of conducting, for examining the action of drugs on infusoria, 49; for testing the power of protoplasm over oxygen, 54; the action of drugs on oxidation, 54; the action of drugs on alcoholic fermentation, 66; on the movements of bacteria, 70; on the destruction of germs, 71; on the action of drugs on the reproduction of bacilli, 74; and on the development and growth of bacilli, 77; for testing the action of drugs on the motor nerves, 121, 122; on the reflex action of the spinal cord, 133, 134; on the respiratory centre, 205; on the action of drugs on the circulation, 224-226; on blood-pressure, 227-229; on the action of heat and cold on the frog's lung, 237, 238; on the action of the heart on blood-pressure, 252; on the heart of the frog, 258-262; Stannius's, on the action of the various cavities on the frog's heart, 277; Ranvier's on dropsy, 293
Expressed oil of nutmeg, 926
Extract of ergot, 981
Extract of malt, 975
Extracts, 448; fluid or liquid extracts, 449; fresh or green extract, 451
Extractum, Aconiti, 449, 452, 747, 748
Fluidum, 450, 748
Aloes aquosum, 449, 960
Barbadensis, 449, 962
Socotrinæ, 449, 960
Anthemidis, 449, 871
Arnicæ Radicis, 449, 873
Fluidum, 450, 873
Aromaticum fluidum, 450
Aurantii amari, 450, 792
Belæ liquidum, 450, 796
Belladonnæ, 899, 900
Belladonnæ, fluidum, 449, 450, 452
Alcoholicum, 449, 899
Brayeræ fluidum, 450, 832
Buchu fluidum, 450, 803
Calami fluidum, 450, 973
Calumbæ, 757
Fluidum, 449, 450, 757
Cannabis Indicæ, 946
Fluidum, 449, 450, 946
Capsici fluidum, 450, 899
Castaneæ fluidum, 450, 944
Cheken fluidum, 839
Chimaphilæ fluidum, 450, 878
Chiratæ fluidium, 450, 895
Cimicifugæ fluidum, 450, 754
Cinchonæ, 855
Flavæ liquidum, 450, 855
Fluidum, 449, 450, 855
Colchici, 449, 452, 967
Aceticum, 449, 452, 504, 967
Radicis, 967
Radicis fluidum, 449, 450, 967
Seminis fluidum, 450, 968
Colocynthidis, 449, 842
Compositum, 449, 842, 882, 896, 960, 961, 971
Conii, 845
Alcoholicum, 449, 846
Fluidum, 449, 450, 452, 846
Cornus fluidum, 450, 853
Cubebæ fluidum, 450, 937
Cypripedii fluidum, 450, 969
Digitalis, 909
Fluidum, 449, 450, 909
Dulcamaræ fluidum, 450, 898
Ergotæ, 980
Ergotæ fluidum, 449, 450, 980
Liquidum, 450, 980
Erythroxyli fluidum, 450, 786
Eucalypti fluidum, 450, 840
Euonymi, 449, 810
Eupatorii fluidum, 450, 872
Filicis liquidum, 450, 978
Frangulæ fluidum, 450, 809
Gelsemii fluidum, 450, 890
Gentianæ, 894
Fluidum, 449, 450, 894
Geranii fluidum, 450, 784
Glycyrrhizæ, 814
Fluidum, 449, 450, 814

Extractum, Glycyrrhizæ Liquidum, 450, 814
Purum, 449, 814
Gossypii radicis fluidum, 450, 788
Grindeliæ fluidum, 450, 875
Guaranæ fluidum, 450, 786
Hæmatoxyli, 449, 822
Hamamelidis fluidum, 450, 940
Hydrastis fluidum, 450, 755
Hyoscyami, 905
Alcoholicum, 449, 905
Fluidum, 449, 450, 452, 905
Ipecacuanhæ fluidum, 450, 864
Iridis, 972
Iridis fluidum, 449, 450, 972
Jalapæ, 449, 897
Juglandis, 449, 939
Krameriæ, 785
Fluidum, 449, 480, 785
Lactucæ, 449, 452, 872
Lactucarii fluidum, 450, 873
Leptandræ, 916
Fluidum, 449, 450, 906
Lobeliæ fluidum, 450, 876
Lupuli, 449, 948
Lupulini fluidum, 450, 948
Malti, 449, 975
Maticæ fluidum, 450, 938
Mezerei Æthereum, 449
Fluidum, 449, 450
Nucis Vomicæ, 884
Fluidum, 449, 450, 884
Opii, 449, 760, 761
Liquidum, 450, 760
Papaveris, 449, 760
Pareiræ, 758
Fluidum, 449, 450, 758
Liquidum, 450, 758
Physostigmatis, 449, 818
Pilocarpi fluidum, 451, 804
Piscidiæ erythrinæ fluidum, 827
Podophylli, 755
Fluidum, 449, 451, 755
Pruni virginianæ fluidum, 451, 835
Quassiæ, 808
Fluidum, 449, 451, 808
Rhei, 923, 924
Fluidum, 449, 451, 924
Rhois glabræ fluidum, 451, 811
Rosæ fluidum, 451, 831
Rubi fluidum, 451, 830
Rumicis fluidum, 451, 924
Sabinæ fluidum, 451, 955
Sanguinariæ fluidum, 451, 779
Sarsæ liquidum, 450, 957
Sarsaparillæ fluidum, 451, 957
Sarsaparillæ compositum fluidum, 451, 930, 957
Scillæ fluidum, 451, 959
Scutellariæ fluidum, 451, 922
Senegæ fluidum, 451, 784, 824
Sennæ fluidum, 451
Extractum—
Serpentariæ fluidum, 451, 932
Spigeliæ fluidum, 451, 891
Stillingiæ fluidum, 451, 933
Stramonii, 906
Fluidum, 449, 451, 906
Taraxaci, 872
Fluidum, 449, 451, 452, 872
Tritici fluidum, 451, 974
Uvæ ursi fluidum, 451, 877
Valerianæ fluidum, 451, 867
Veratri viridis fluidum, 451, 963
Viburni fluidum, 451, 868
Xanthoxyli fluidum, 451, 804
Zingiberis fluidum, 451, 970
Eye, action of drugs on the, 185-193; chief drugs employed in the treatment of disease of the cornea, 184; on the conjunctiva, 184; on the lachrymal secretion, 184; projection of the eyeball, 184; on the pupil, 185; diagram to show the nervous supply of the, 185; the iris of the, and the two muscles of which it consists—the sphincter and the dilator, 185, 186; drugs which act on the iris—mydriatics and myotics, 186; causes and consequences of the dilatation of the pupil of the, 187, 188; and of the contraction of the, 189; action of drugs on accommodation, 190; on intra-ocular pressure, 190; uses of mydriatics and myotics, 191; action of drugs on the sensibility of the, 193; in producing visions; 193; application of drugs to the, 420; action of purified chloroform on the eye, 723; of aconitine, 751; of opium on the pupil of the, 769, 770; of cocaine, 786; of pilocarpine, 805-807; of Jamaica dogwood on the pupil of the, 827; of gelsemium, 890; of belladonna or atropine, 902; of Indian hemp or American cannabis, on the pupil of the, 947

F.

Fainting, cause of, 223; effect of emptying the bladder on, 223; treatment of, 224
Farina lini, 783
Fasting, rapid effects of drugs when taken, 31
Fats, as emollients, 304
Fatty degeneration, due to a twofold action, 364; of the liver, stomach, and kidneys produced by phosphorus, 638; what this chiefly depends on, 639; of the vessels, and its result, 639; of the liver and other organs produced by arsenic, 643
Febrifuges. *See* Antipyretics
Feet, cold, remedy for, 166
Feitelberg, reference to, 295*n*.
Fel bovis inspissatum, 991
Purificatum, 991

Fennel, as a carminative, 330; as a stimulant diuretic, 379; characters, composition, and uses of, 849
Fruit, characters and use of, as a stimulant and carminative, 849
Ferments, inorganic, 59; organic and organised, 59, 60; nature of, 60; the process of fermentation divided into two kinds, 60, 61; diastatic amylolytic, 61; inversive, 62; proteolytic, 62; action of drugs on, 61-64; yeast and bacteria, 65 *et seq.*; description of the chief organised, 65 *et seq.*; Brefeld's classification of, 66; diagram illustrating the principal organised, 67. *See* also Yeasts, Mould fungi, Bacteria, Bacillus, &c.
Fern, male, its characters, physiological action, and therapeutics, 978; method of administration, 978
Ferri Arsenias, 555, 647
Carbonas Saccharata, 976
et ammoniæ citras, 669
et Quiniæ citras, 669, 674, 857
et Quininæ citras, 857
et Strychninæ citras, 674, 885
Iodidum, 489
Oxidum magneticum, 669
Peroxidum humidum, 669
Phosphas, 555
Sulphas Exsiccata, 668
Ferric chloride, action of, on bacteria, 75; as an astringent, 305; as a styptic, 307
Ferrier, Dr., reference to, 143, 155, 169, 182, 183*n.*, 193, 195; composition and use of his snuff, 658
Ferrous salts, physiological action of, 23
Ferrous sulphate, action of, on bacteria, 75
Ferrum tartaratum, 536, 669
Fever, remittent, depends on the presence of a spirillum in the blood, 87
Fibres, efferent and afferent, position and functions of the, 311
Fibrin, condition of, when digested with pancreatic juice, 357
Fibrine, effects of heating, 60; and of pepsin on, 60
Fick, A., his kymograph, 228, 815
Fick, J., references to, 101
Figs, as demulcents, 304; as laxatives, 339; characters and composition of, 945; uses of, 949
Filices, 978
Filix mas, as a vermicide, 357
Fir wool oil, action and use of, 951
Fire damp, as a poison, with its antidote, 429
Fish, mechanism of respiration in the, 197; diagram of a, 198
Flag, blue, 972; as an emetic or cathartic, and a stimulant, 972
Flag, sweet, as a stomachic stimulant, 973
Flaxseed, 782; oil of, 783
Flies, Spanish, 1000; external and internal action of, 1001; in very large doses 1001; on the salivary glands, 1001; on the urinary organs, 1001; external and internal use of, 1002; as an irritant and counter-irritant, 1002; precautions, 1002; treatment in poisoning by, 1002
Flour, wheaten, 973
Flourens, reference to, 201
Flowers of sulphur, its preparation, characters, &c., 479
Fluorine, symbol and atomic weight of, 9; its relation to other members of a group, 15
Fokker, reference to, 82
Food, discussion as to whether alcohol can be deemed a, 693
Foot-baths, warm, utility of, as direct emmenagogues, 398
Formad, reference to, 80
Formic acid, action of, on bacteria, 76
Foster, M., reference to, 93*n.* 145, 146
Franck, F., reference to, 155*n.* 156*n.*
Frankincense, common, characters and use of, 949
Fraser, reference to, 124, 141-143, 255*n.*, 434
Freusberg, references to, 151
Friars' balsam, 879
Friction, one of the simplest rubefacients, 301; value of friction of the skin, as an adjunct to cold baths, 415
Fritsch, reference to, 153
Frogs, effects of large and small doses of veratrine on, 21; and of various poisons, when modified by heat or cold, 33, 34; various experiments on, 40-42; action of quinine on the mesentery of, 48; action of veratrine on, 105; experiment on the sartorius of, 109; rhythmical action of the ventricle of the heart of, 113; experiment on the leg of, 120; explanation and diagram of the mode of experimenting on the sensory nerves in, 122; experiment on the gastrocnemius of, 130-133; mode of experimenting on the action of drugs on the reflex action of the spinal cord of, 133; on the heart of, 134; diagram, showing the nervous system of, 136; experiments with quinine on the spinal cord of, 136; experiments with, 137-144; on the sartorius of, 146; experiments on the nervous system of the, 152; diagram of the higher nerve centres of, 153; Prevost's experiment with chloroform on the brain of 173; the easiest way of anæsthetising, 177, 178; action of alcohol on, 183; on convulsions in, 202; diagram to illustrate the effects of the horizontal and vertical position of the, in shock, 222; experiments on the arterioles of, 237; as to the effects of drugs on the vessels of, 237; and as to the effect of heat and cold on the lung of, 237; diagram illustrative of this, 238; method of maintaining artificial circulation in, 239;

method of measurement by the rate of flow, 239, 240 ; experiments on the outflow of blood from divided vessels in, while the nervous system is intact, 244 ; heart beats in the, when imperfectly filled, 252 ; the heart of, 258 ; diagram of the heart of, 258 ; diagram of the auricular septum in, 258 ; action of drugs on the heart of, 259 ; instrument for showing the action of heat and cold, and of poisons on the heart of, 259 ; effect of heat and cold on the action of the heart of, 260 ; Ludwig and Coats's apparatus for observing alterations in the pulsations and rhythm of the heart of, 261 ; Williams's, 260, 262 ; tracings showing changes in the pulsations of the apex of the heart of, 264 ; irritation of the vagus of, causes still-stand of the heart of, 268 ; actions of two classes of poisons on the vagus of, 269 ; difference between the action of the accelerating nerves and the inhibitory fibres of the vagus of, 270 ; Stannius's experiments on the heart of, 277-279 : diagrams illustrative of these, 277-279 ; Gaskell's experiments on, 279 ; with illustrative diagram, 279 ; general considerations regarding the heart of, 280, 281 ; vagus stimulation on the heart of, divided into five classes, 281-283 ; diagrams illustrative of this, 282, 283 ; hypothesis regarding the action of the vagus on the heart of, 283 ; with illustrative diagrams, 284 ; inhibition in the heart of, 285 ; experiments with, as to the antagonism of drugs, 435 ; action of chlorides on the nervous system of, 528, 577 ; of soda on, 551 ; action of barium on, 577 ; of mercury, 615 ; of phosphorus, 638 ; of arsenic on the skin of, 643 ; diagrams of the epidermis of, before and after poisoning by arsenic, 643 ; action of antimony on the heart and skin of, 651 ; diagram of the vertical section of the epidermis of a, poisoned by antimony, 652 ; of solution of perchloride of platinum on, 680 ; of salts of iron on, when injected subcutaneously, 666 ; of the nitrite of amyl, 712 ; of chloral hydrate, 716 ; of iodoform, on the heart of, 729 ; carbolic acid produces convulsions in, 736 ; action of resorcin on, 739 ; of aconitia, 748 ; of staphisagrine, 752 ; of opium, 767 ; of caffeine, 798 ; of quinine, 864 ; of belladonna or atropine, 901, 902 ; of nicotine, 907 ; of digitalis on the heart of, 911 ; of veratrine on the heart muscle of the, 966 ; of colchicum on the spinal cord of the, 968 ; and of ergotinic acid, 981 ; of cornutine, 981

Fruit, Bael, 795
Capsicum, 898
Fruit, Caraway, 850
Coriander, 852
Dill, 850
Fennel, 849
Hemlock, 845
Squirting cucumber, 843
of the Dog-rose, 831
Fuchsin, 743
Fuller's earth, as a demulcent, 304 ; nature and uses of, 585

G.

Gadidæ, 996
Galbanum, as an antispasmodic, 182 ; characters and use of, as a stimulant expectorant, 848
Gall, ox, inspissated, 991
Gallic acid, 943 ; properties and uses of, 944
Gallici, mistura spiritus vini, 995 ; its therapeutics, 995
Gallinæ, 995
Gallium, symbol and atomic weight of, 9 ; properties of, 18
Galls, as an astringent, 305 ; characters, action, and uses of, 941
Gamboge, as a drastic purgative, 340 ; and a hydragogue, 340 ; characters, action, and uses of, 799
Gamgee, A., reference to his *Physiological Chemistry*, 52*n*.
Ganglia, motor cardiac, 248 ; inhibitory, 248 ; diagram to show the supposed relation of motor, in the heart to accelerating fibres, 249 ; Remak's and Bidder's, 259, 262, 266 ; motor, inhibitory, and quickening, supposed to be present in the nervous system of the frog, 270-272 ; inhibitory and motor, of the heart, 275 ; functions of the cardiac, 282
Gargles, method of using, 425
Garlic, as a stimulating expectorant, 219 ; action of, 958 ; as an antiseptic, irritant, and carminative, 958 ; as a stimulant, expectorant, and diuretic, 958
Gärtner, references to, 31
Gases, action of different, on the frog's heart, 266 ; poisonous gases, with their antidotes, 428
Gaskell, reference to, 90, 235, 239, 243*n*., 253, 266*n*., 270, 271*n*., 279, 280-283
Gastric juice, action of acids on the, 497
Sedatives, and anti-emetics, nature, number, and uses of, 327, 328 ; divided into local and general, 327 ; adjuvants to, 328
Stimulants, alkalies as, 524
Syphon, nature and uses of, 426
Tonics, nature and action of, 317 *et seq*. ; purgatives and cholagogues may act as indirect, 320 ; states in which they are indicated, 360

Gastro-salivary circulation, diagram of, 314
Gaultheria, oil of, characters, action, and use of, 878 ; as an antipyretic, 878
Gelatine, as a demulcent, 304 ; solution of, 996
Gelsemine, as a spinal stimulant, 151 ; as a local and general anodyne, 169 ; as a mydriatic and myotic, 186 ; action of, on the respiratory centre, 199, 206. *See* Gelsemium
Gelsemium, as a poison, with its antidote, 432 ; antagonism of, to opium and atropine, 433-437 ; characters and action of, 890 ; on the eye, the spinal cord, the motor centres, 890 ; on the head, the vagus, the blood, pulse, and heart, 891 ; uses of, 891
Geltowsky, references to, 47*n*.
GENERATIVE SYSTEM, ACTION OF DRUGS ON THE, 393-401 ; action of the cerebral and spinal centres on the, 393 ; action of drugs on the, as aphrodisiacs, 395 ; as anaphrodisiacs, 396, as emmenagogues, 397 ; and as ecbolics, 398 ; action of drugs upon milk, 399
Genito-urinary tract, action of opium on, 777
Gentian, 893
Root, characters, and composition of, 893 ; preparation and use of, 894
Gentianaceæ, 893
Geraniaceæ, 783
Geranium (cranesbill), characters, composition, and action of, as an astringent, 783
Gianuzzi, references to, 204, 893
Giant cells, action of iodoform on, 729
Gilbert, reference to, 112
Gin, as a cardiac stimulant, 286 ; and as a stimulant diuretic, 379
Ginger, as a carminative, 330
as a sialagogue, 312, 313 ; characters, action, and uses of, 970 ; as a carminative, 970
Gingerbread, as a laxative, 339
Glanders, caused by a species of bacillus, 81
Glands, poisonous action of the heavy metals on the, 595
Glandular system, antagonistic action of drugs on the, 436
Glauber's salt, 554
Glaucoma, nature of, and mode of treatment, 192
Glomeruli, the result of arterial pressure on the, 374, 375 ; poisonous action of the heavy metals on the, 595
Glycerine, action of, on enzymes, 63 ; on bacteria, 75 ; as a demulcent, 304 ; characters and uses of, 882, 883
Glycerines, 452
Glycerinum, 452
Acidi Carbolici, 452, 735, 883
Gallici, 452, 882, 944
Glycerinum Acidi Tannici, 452, 882, 942
Amyli, 452, 882, 974
Boracis, 452, 882
Glyceritum vitelli, 452, 883, 995
Glycogen, formed and stored up by the liver, 352 ; glycogenic function of the liver destroyed by phosphorus, arsenic, and antimony, 352
Glycyrrhizinum ammoniatum, 814
Gold, symbol and atomic weight of, 9 ; as an alterative, 362 ; properties, action, and uses of, free from metallic impurities, 679 ; solution of chloride of, 679; chloride of, and sodium, 679
Goltz, reference to, 152, 244
Gonorrhœa, caused by micrococci, 81
Gout, rheumatic. *See* Rheumatic Gout
Granville, Mortimer, his proposed mode of relieving pain, 171
Grass, couch, 974
Graves, Dr., reference to, 653
Grawitz, references to, 66
Griffith's mixture, 668
Grindelia, characters and uses of, 874 ; in asthma, dyspnœa, and as a local application, 875
Groups, arrangement of the elements in, 15
Grützner, reference to, 31
Guaiac resin, and tincture of guaiac, experiments with, on oxygen, 54, 55 ; as a stimulant diuretic, 379
Guaiaci resina, 460
Guaiacum, as an alterative, 362 ; as a direct emmenagogue, 398 ; guaiacum resin, characters, composition, action, and uses of, chiefly in the treatment of tonsillitis, 801 ; guaiacum wood, nature and composition of, 800
Guanidine, action of, destroyed by extremes of heat or cold, 33 ; effect of temperature on, extraordinary, 145 ; action of, on the motor ganglia, 275 ; on the cardiac muscle, 276
Guarana, characters, composition, and uses of, 786
Guareschi, references to, 81, 351
Guinea-pigs, the cerebral hemispheres of, more developed than in the frog, 253
Gum, as a demulcent, 304
Gum acacia, characters, &c., and use of, 828 ; gum arabic, 828
Gumchi, 817
Gun cotton, preparation and use of, 789
Gutta-percha, characters and use of, 879
Guttiferæ, 799
Gymnosperms, 949

H.

HABIT, effect of, on the action of drugs, 32
Hæmatemesis, value of astringents and styptics in, 306

Hæmatin, nature and spectrum of, 56
Hæmatinics, or blood tonics, nature, actions and uses of, 361
Hæmaturia, value of astringents and styptics in, 306
Hæmodromometer, Marey's, 253
Hæmoglobin, solution of, 54; power of, 55; spectroscopic examination of, 55, 57; action of, on the frog's heart, 266; treatment to be adopted when there is a deficiency of, in the blood, 360; the quantity of, increased by hæmatinics, 361
Hæmoptysis, value of astringents and styptics in, 306
Hæmorrhage, action of astringents and styptics in lessening or arresting, 306, 307; importance of absolute quiet in severe, 307; emetics to be avoided in persons suffering from, 327
Hall, Marshall, reference to, 210
Halogen elements, the general source, characters, and mode of preparation of, 483-492
Haloid Compounds—
Bichloride of methylene, 718
Bromal hydrate, 718
Bromide of ethyl, 713
Chloral, 714
Hydrate, 714
Chloroform, 719
Purified, 719
Croton chloral hydrate, 718
Hydrate of chloral, 714
Iodide of ethyl, 714
Hamamelaceæ, 943
Hamamelis, as a vascular sedative, 296; characters and use of, 940
Harley, reference to, 58
Harnack, references to, 96, 104, 124, 255*n.*, 262*n.*, 266, 270
Haywood, Dr., reference to his use of ether, 179
Head, action of gelsemium on the, 891
Hearing, action of drugs on, 193
Heart and vessels, comparative effect of, on blood-pressure in different animals, 246, 247; in dogs and rabbits, 246, 247; action of the, on blood-pressure, 252; various modes of estimating the action of the, on the circulation, 252, 253; cause of the stoppage of the, in rabbits, dogs, and men, 255; stimulation of the, by increased blood-pressure, 256; difference betwixt the tortoise and the mammalian heart, 256, 257; palpitation of the, 257; the, of the frog, 258; diagram of the heart of the frog, 258; action of drugs on the, of the frog, 259; instrument for showing the action of heat and cold, and of poisons on the frog's heart, 259; diagram of Ludwig and Coats's frog-heart apparatus, 261; diagram of Williams's apparatus for investigating the action of drugs on the heart of the frog, 262; action of drugs on the muscular substance of the, 263; apparatus for ascertaining the action of drugs on the muscular substance of the, 263; tracings showing changes in the action of the frog's heart, 264; difference between the heart-apex and the, 266; diagram to show the difference in the mode of experimenting with the heart and with the apex alone, 267; diagram showing the periodic rhythm of the, 267; tracings of the pulsations of a ventricle of the, 268; action of drugs on inhibition of the, 268; theories regarding the mode of action of drugs upon the, 270; hypothetical view of the nervous system of the, 270, 272; diagram of the hypothetical nervous apparatus in the, 271; detailed description of the physiology of the, 273-285; diagram of the heart and vessels to illustrate the action of drugs on the circulatory apparatus of the, 273; drugs which stimulate, or depress, or paralyse the vagus centre of the, 274; the accelerating centre, 274; the vaso-motor centre, 274; the vagus ends in the, 275; the inhibitory and motor ganglia, 275; the cardiac muscle, 276; the vaso-motor nerves, 276; the capillaries, 277; Stannius's experiments regarding the action of the various cavities of the frog's, 277-280; diagrams illustrative of this, 277, 278; Gaskell's experiments on the same subject, 279; diagram to illustrate this, 279; general considerations regarding the, 280, 281; regulating action of the nervous system of the, 281-283; diagrams illustrating this, 282, 283; hypothesis regarding the action of the vagus of the, 283; illustrative diagrams, 284; inhibition of the, 285; no satisfactory explanation can as yet be given of the action of drugs on the, 285; knowledge in this respect at present in a progressive state, 285; drugs which act on the circulation of the, their divisions and subdivisions, 285; cardiac stimulants, 286; vascular, 287; cardiac tonics, 288; various conditions and diseases of the, in which tonics are most useful, 289-292; the question of the use of digitalis in aortic regurgitation considered, 291; precautions as to position of the, during the administration of cardiac tonics, 292; action of sedatives on the, 295; diagram to show the nervous mechanism by which the action of the, may be depressed by irritation of the stomach, 346; action of manganese salts on the, 679; of alcohol, 695; of spirit of ether, 706; of bromal hydrate, 718; of purified chloroform, 722-726; of iodoform, 729; of aconitia, 749, 750;

of staphisagria, 752 ; of quillaia (saponin), 832 ; of quinine, 861 ; of ipecacuanha, 865 ; of strychnine, 887 ; of gelsemium, 891 ; of solanine, 898 ; of tobacco, 907 ; of digitalin, 911 ; of camphor, 929 ; of extract of ergot, 981
Heat, effect of, on the power of poisons, 33-36 ; power of, to preserve life in narcotic poisoning, 35 ; effects of, in accelerating death from muscular and metallic poisoning, 35 ; effect of, on protoplasmic movement, 46 ; on the action of infusoria, 50 ; on mould fungi, 68 ; on bacteria, 70 ; as a disinfectant, 86 ; effects of, on muscle, 96, 100, 108, 114 ; on the action of strychnine, 145 ; in inducing sleep, 166 ; as a local anodyne, 168 ; dry, in the form of a poultice, relieves pain, 171 ; action of, on the respiratory centre, 205 ; apparatus for ascertaining the effect of, on the vessels of the frog's lung, 238 ; instrument for showing the action of, on the frog's heart, 259 ; the most powerful of all cardiac stimulants, 286 ; as a vascular stimulant, 287 ; action of, on inflammation, 298 ; diagram to show the effect of, in lessening the pain of inflammation, 299 ; as a vesicant, 300 ; as an emollient, 304
Hedeoma, or pennyroyal, characters of, 920 ; action and uses of, 921 ; as a carminative, diaphoretic, and emmenagogue, 921
Heidenhain, originates the name of zymogens, 65 ; references to, 354, 370, 273*n*.
Hellebore, American, 963 ; hellebore root, green, 963 ; action of, on the pulse, 963
Helleborin, action of, on ascidians, 93 ; on the frog's heart, 265 ; on the cardiac muscle, 276 ; as a cardiac tonic, 289
Hemiptera, 1000
Hemidesmus root, characters, composition, and use of, 893
Hemlock (conium), composition, action, and therapeutics of, 846 ; paralysing power of, 846
Fruit, 845
Leaves, 845
Pitch, 953
Hemp, Indian, as a hypnotic, 167 ; as a narcotic, 168 ; character, action, and uses of, 946 ; on the sensory nerves, the pupil, and respiration, 947 ; on the pulse, temperature, urine, and digestion, 947 ; uses of, as a soporific, 947
Henle's loop, 371, 374, 382
Hepatic stimulants, nature of, 350 ; action of, 352 ; importance of combining intestinal and, 354, 355 ; cholagogues and, 356 ; depressants, 356 ; resin of podophyllum as a, 755 ; euonymus, (wahoo), as a, 810 ; juglans as a, 939
Hermann, references to, 25, 29, 30, 59, 266*n*.
Hernia, emetics to be used with caution in persons suffering from, 327
Hip-baths, and mustard hip-baths, utility of, as indirect emmenagogues, 398
Hips (fruit of the dog-rose), 831
Hirt, reference to, 254
Hitzig, reference to, 155
Hock, as a stimulant diuretic, 379
Hoffmann, reference to, 262
Hoffman's anodyne, 707
Holmgren, reference to, 237
Holmium, symbol and atomic weight of, 9
Homatropine, as a mydriatic, 186
Homœopathy, the principle of, 27
Homolle's digitaline, 909
Honey, as a demulcent, 304 ; as a laxative, 33 ; its characters, composition, &c., 998
Honeys, 455
Hoppe-Seyler, references to, 59*n*., 60
Hops, as a hypnotic, 167 ; characters of, 947
Horehound. *See* Marrubium
Horseradish, as a sialagogue, 312 ; as a carminative, 330 ; as a stimulant diuretic, 380 ; horseradish root, characters, composition, and uses of, 782
Hot baths, 411 ; hot foot-baths, 411 ; hot sitz baths, 412
Howard's plan of artificial respiration, 726
Hüfner, reference to, 370
Humboldt, Alexander von, references to, 33
Humulus, or hop, 947
Hunter, John, reference to, 235
Husemann on lithium, 21
Hydragogues. *See* Purgatives
Hydrargyri Chloridum mite, 616
Corrosivum, 617
Cyanidum, 617
Iodidum rubrum, 489, 617
Viride, 489, 617
Oxidum flavum, 616
Rubrum, 616
Perchloridum, 617, 620
Subchloridum, 616, 620
Sulphas, 617
Flava, 617
Sulphidum rubrum, 616
Hydrargyrum, 616
Cum creta, 581, 616
Ammoniatum, 617
Hydrastin, as a hepatic stimulant, 353
Hydrastis (golden seal), characters, composition, and uses of, 756 ; as a hepatic stimulant and as an antiperiodic, 756
Hydrate, bromal, preparation and characters, 718 ; action of, 718 ; irritates the eyes and causes running at the nose, 718 ; has a narcotic action like chloral, and a powerful paralysing action on the heart, 718 ; causes salivation and pro-

fuse secretion from bronchial mucous membrane, 718 ; uses of, 718
Hydrate, croton chloral, action, uses, and administration of, 718
Of aluminium, 587
Of chloral, action of, on bacteria, 77
Hydriodic acid, physiological action of, 24
Hydrobromic acid, action of, on the ear, 194 ; dilute ditto, properties of, &c., 516
Hydrocarbons, fatty series, 686 ; chemical nature and physical character of the, 686, 687 ; boiling point of the, 687 ; physiological action of those belonging to the marsh gas series, 687. *See* under the different names of the series.
Hydrochlorate of apomorphine, characters of, 765 ; action of, as an emetic, on the motor centres in the brain and the respiratory and vomiting centres in the medulla, 765 ; on muscular fibre, the pulse, and the secretion of bronchial mucus, 765 ; opium *versus*, 775
Hydrochlorate of morphia, 763 ; of morphine, 763
Hydrochlorate of pilocarpine, characters and composition of, 804 ; action of, on the nerves, nerve centres, and muscular fibre, 805, 806 ; and on all the secretions of the body, 805 ; on the bladder, uterus, and spleen, 806 ; on the circulation and vessels, 806 ; on the respiration and temperature, 806 ; on the eye, skin, and throat, 807 ; its chief use in dropsy, 807 ; contra-indications, 807
Hydrochlorate of rosaniline, preparation, characters, actions, and uses of, 743
Hydrochloric acid, physiological action of, 24 ; action of, on the protoplasmic movements, 46 ; on enzymes, 63 ; on bacteria, 75, 77 ; as a caustic, 301 ; arrests secretion of saliva, 316 ; as a poison, with its antidote, 429 ; properties and uses of, 500 ; preparations containing free, 501
Hydrocyanic acid, forms a compound with hæmoglobin, 56 ; nature and spectrum of this compound, 56 ; effects of, on the blood, 58 ; on bacteria, 77 ; as a local anodyne, 169 ; action of, on the respiratory centre, 199 ; on the muscles of respiration, 203 ; effects of poisoning by, on the colour of the blood, 205 ; the vapour of, has a local sedative action on the lung, 214 ; action of, on the vagus centre, 274 ; on the motor ganglia, 275 ; on palpitation of the heart, 295 ; as a local and general sedative, 327 ; as a poison, with its antidote, 429 ; antagonism of, to atropine, 433-437 ; preparation, properties, action, and uses of, 494, 512 *et seq.* ; action of, on the skin, 513 ; on the blood, 513 ; on respiration, 514 ; on the heart, 514 ; on the arteries and nerves, 514, 515 ; diagram to show the effect of, when applied locally, 515 ; uses of, 515
Hydrogen, symbol and atomic weight of, 9 ; its preparation and uses, 473
Hydrogen, peroxide of, rapidly decomposed by finely-divided platinum, 58 ; power of certain metals to absorb, 59 ; its preparation, properties, action, and uses, 476
Hydroquinone, characters, action, and uses of, 740
Hymenoptera, 998
Hyoscyaminæ sulphas, 444
Hyoscyamine, as a general anodyne, 169 ; action of, on the vagus centre, 274 ; on the vaso-motor centre, 274 ; and inhibitory ganglia, 275 ; as an antihydrotic, 387 ; as a vesical sedative, 391 ; as a poison, with its antidotes, 432 ; antagonism of, to morphine, 433-437
Hyoscyamine, sulphate of, characters, action, and uses of, 904
Hyoscyamus, a hypnotic, 167 ; as a narcotic, 168 ; as a general anodyne, 169 ; action of, on the vagus centre, 274 ; on the vaso-motor centre, 274 ; on the inhibitory ganglia, 275 ; characters, composition, and preparation of, 904
Hyoscyamus leaves, 903
Hyphomycetes, 66, 67
Hypnotics, or soporifics, nature and action of, on the brain, 164-167 ; list of the chief, 166, 167 ; bromide of potassium as a hypnotic, 547
Hypodermic administration of drugs, 418 ; advantages of this method, 418 ; nature and method of the injections, 418 ; diagram of a syringe for hypodermic injection, 418 ; objections to hypodermic injections, 419 ; method of obviating these, 419 ; account of the syringe employed by Koch, 420 ; injections of acetate of morphia, 453
Hypophosphite of soda, 57 ; of lime, 583 ; of iron, 678
Hyposulphite, test for, 520
Hysterical paralysis of the limbs and hysterical aphonia, usefulness of blisters in, 302
Hystozyme, a recently discovered ferment, 61

I.

Ice, as an anæsthetic, 128 ; action of, externally, on the mucous membrane, 216 ; the most powerful of local sedatives, 327 ; as a cardiac sedative, 296 ; as an aphrodisiac, 396
Iceland moss, as a demulcent, 304 ; composition of, 979
Ichthyocolla, 996

Idiosyncrasy, effects of, on the action of drugs, 38
Ignatia, characters and composition of, 884
Image, Mr., of Bury St. Edmunds, his plan of administering chloroform, 726
Indian hemp, 946, 947
White, 892; acts like digitalis, 892
Liquorice, 817
Indiarubber bag for holding hot water, utility of, to invalid travellers, 286 and *n.*
Indigo, preparation and use of, 829
Indol, action of, on bacteria, 76
Inflammation, chronic and acute, action of irritants and counter-irritants in, 298-303; diagrams illustrative of the action of irritants in, 298, 299; of the joints, utility of friction in, 301
Infusions, 452
Infusoria, nature of, and action of drugs on, 49 *et seq.*; mode of experimenting on, 49; effects of heat, cold, and saline solutions on, 50; of acids, alkalies, and other drugs on, 51; oxidation of, 51-54
Infusum Anthemidis, 453, 871
Aurantii, 453, 792
Compositum, 453, 792, 794, 837
Brayeræ (Cusso), 453, 854
Buchu, 453, 803
Calumbæ, 453, 757
Caryophylli, 453, 837
Cascarillæ, 453, 933
Catechu, 453, 866, 927
Cheken, 839
Chiratæ, 453, 895
Cinchonæ, 453, 864
Flavæ, 855
Fluidum, 453
Cuspariæ, 453, 803
Cusso, 453, 832
Digitalis, 453, 909
Dulcamaræ, 453, 898
Ergotæ, 453, 980
Gentianæ compositum, 453, 792, 794, 894
Krameriæ, 453, 785
Lini, 453, 783, 814
Lupuli, 453, 948
Maticæ, 453, 938
Pruni Virginianæ, 453
Fluidum, 835
Quassiæ, 453, 808
Rhei, 453, 923
Rosæ Acidum, 453, 831
Senegæ, 453, 784, 970
Sennæ, 453, 824
Compositum, 453, 590, 824, 883
Serpentariæ, 453, 932
Uvæ ursi, 453, 877
Valerianæ, 453, 867
Inhalations, of chlorine, 487
of vapours for the lungs, 423, 468
Inhalers for the lungs, 424
Inhibition, and the action of drugs on inhibitory centres, nature of, 137-141
Injectio morphiæ hypodermica, 453, 764
Injections, enemas, or clysters, 448
Inorganic materia medica, 473 *et seq.*
Insect powder, as a poison, with its antidotes, 432
Insufflator, for applying powders to the larynx, diagram of an, 422
Intestines, difference between the vessels of the, and those of the muscles, 235; action of drugs on the, 330; movements and secretion of the, 330; cause of these, 330; paralytic secretion of the, 331; diagram illustrative of the effect of section of the nerves on secretion from the, 331; certain nerve-centres possess the power of restraining the secretion from the, 331; nervous arrangements and nerve-centres of the, 332; natural and artificial circulation in the, 332; diagrams illustrating the effects of artificial circulation in the, 333; action of peptones, nicotine, and atropine, 333; of opium, 333-335; difference between the action of soda and potash on the, 334; effects of morphine on the, 334; and of sodium salts, 334; cause of constipation of the, and remedies for, 335; diagram to show how ovarian irritation probably causes constipation, 336; action of opium as a purgative on the, 336; small doses of belladonna also act as purgatives on the, 336; action of drugs on absorption from the, 337; action of astringents on the, in diarrhœa, 337; diagram illustrating diarrhœa depending on the presence of scybala in the, 338; nature and action of various kinds of purgatives on the, 339-345; of irritant poisons, 347; diagram of the liver, stomach, and, 353; application of drugs to the, 426; as enemata, 426; as suppositories, 427; action of strong solution of ammonia on the, 570; action of iron on the, 594; of copper, 597; of alcohols, 691, 692, 696; of salts of iron, 665; of gold, 680; of spirit of ether, 706; of purified chloroform, 721; of opium, 772; of sanguinaria, 778; of caffeine, 798; of pilocarpine on the glands of the, 805, 806; of physostigmine, 821; of quillaia (saponin), 832; of ipecacuanha, 864; of sulphate of strychnine, 885; of belladonna or atropine, 903; of aloes, 962
Intoxication, diagnosis between opium poisoning, apoplexy, and, 768
Inula (elecampane), characters and uses of, 875
Inunction of drugs, method of employing, 417

Inunction of the skin, advantage to be derived from, 417
Invertebrata, action of drugs on, 88-94
Iodic acid, physiological action of, 24
Iodide, test, for, 520
Iodide of ammonium, action of, on the ear, 194 ; preparation, character, and uses of, 573
Ethyl-strychnine, 317
Lead, 633
Mercury, green, 625
Red, 626
Potassium, 543
Silver, 610
Soda, 558
Sulphur, 490
Zinc, 602
Iodide of potassium, action of, on the ear, 194 ; on the sense of smell, 195 ; on taste, 195 ; difference between large and small doses of, on the secretion of mucus, 217 ; as an anaphrodisiac, 396 ; nature, action, and uses of, 543-546
Iodides, the, as alteratives, 362
Iodine, symbol and atomic weight of, 9 ; its relation to other members of a group, 15 ; action of, on infusoria, 51 ; on enzymes, 63, 64 ; on bacteria, 71, 73, 76, 77 ; on taste, 195 ; on quinine, 196 ; and its preparations, as rubefacients, 300 ; and its compounds, as a sialagogue, 312 ; as an alterative, 362 ; has little influence on the excretion of urea, 364; vapour of, as a poison, with its antidote, 428 ; characters, tests, and preparations of, 489 ; iodide of sulphur, characters and uses of, 490 ; ointment of, 490 ; physiological action of iodine, 490 ; uses of, 491 ; as an aphrodisiac, 491 ; as an anaphrodisiac, 491
Iodine water, action of, on bacteria, 75
Iodism, symptoms of, 491, 544
Iodoform, a local anæsthetic, 172 ; preparation and characters of, 727 ; mode of administration, 728 ; action of, as an antiseptic, a deodoriser, and a local anæsthetic, 728 ; action of, on the heart and nervous system, 729 ; on giant cells, 729 ; uses of, 729
Ipecac, 863
Ipecacuanha, causes vomiting in man, but not in rabbits, 40 ; action of, on the nose, 210 ; one of the most useful expectorants in sufficient doses, 218 ; as a depressant expectorant, 219 ; as a local emetic, 325, 327 ; as a hepatic stimulant, 353 ; as an antihydrotic, 387 ; characters, composition, and preparations of, 863, 864 ; physiological action of, on frogs, 864 ; locally, 864 ; on the stomach and intestine, 864 ; on the vessels, heart, and lungs, 864, 865 ; uses of,—as an emetic and diaphoretic, 865 ; as an expectorant and anti-dysenteric, 865; precautions, 865
Ipecacuanha powder, as a sudorific, 365
Iridin, as a cholagogue, 340 ; as a hepatic stimulant, 353
Iridium, symbol and atomic weight of, 9 ; physiological action of, 24
Iris of the eye, structure and action of the, 185
Iris, the, or blue flag, 972
Irish moss, 984
Iron, symbol and atomic weight of, 9 ; effects of large and small doses of, on the muscles, 104 ; causes slow contraction of the vessels, 240 ; action of, on the vasomotor nerves, 276 ; as a vascular tonic, 293 ; action of, on the liver, 354 ; as a vermicide, 357 ; action of, on the general system, 594 ; properties, sources, and reactions of, 661, 662 ; general preparations of, 662-665 ; action of, 665 ; on the skin, mouth, stomach, and intestine, 665 ; on the blood and tissues, 666 ; on the nervous system, 666 ; on frogs and mammals, 666 ; how eliminated, 666 ; the strong solution of the perchloride of, one of the most powerful styptics, 672 ; the liquor and tincture of, more often employed than any other preparation of, 672
Iron, properties, preparations, action, and uses of—
Ammonio-ferric, sulphate of, or alum, 675
Aqueous solution of ferric citrate of, 674
Arseniate of, 677
Citrate of, 674
and ammonia, 674
Ammonium, 674
Quinia, 674
Quinine, 674
Strychnine, 674
Chloride of, 671
Compound mixture of, 668
Hydrated oxide of, 669
with magnesia, 669
Peroxide of, 670
Hypophosphite of, 678
Lactate of, 675
Magnetic oxide of, 676
Mixture of acetate of, and ammonium, 671
Moist peroxide of, 669
Nitrate of, 673
Oxalate of, 676
Phosphate of, 677
Pyrophosphate of, 677
Reduced, 670
Iron, saccharated carbonate of, 668
Iodide of, 676
Solution of basic ferric sulphate of, 669
Chloride of, 671
Citrate of, and quinine, 675

Iron, Solution of Pernitrate of, 673
Persulphate of, 679
Subsulphate of, 669
Tersulphate of, 669
Strong solution of perchloride of, 671
Sulphate of, 667
and ammonium, 675
Dried, 668
Granulated, 668
Precipitated, 668
Syrup of bromide of, 676
Tartrate of, and ammonium, 673
Potassium, 673
Tartarated, 673
Tincture of acetate of, 670
Valerianate of, 678
Irritants and counter-irritants, 297-303 ; divided into four classes, 297 ; diagrams illustrating the action of, 298, 299 ; rubefacients, and their action on chronic and acute inflammation, 297-302 ; list of the principal, 300, 301 ; vesicants and their action, 302 ; pustulants, 302 ; and caustics, 302 ; oil of copaiva as an irritant, 827 ; quillaia (saponin) as an, 832 ; oil of myrtle as, 839 ; camphor as, 929 ; garlic as, 958
Isinglass, as a demulcent, 304 ; nature and properties of, 996
Isomorphism and physiological action, relation between, 23
Ivy, poison, 812

J.

Jaborandi, as a myotic, 186 ; as a depressant expectorant, 219 ; as a sialagogue, 312, 313 ; as an antihydrotic, 387 ; antagonism of, to atropine, 433-437 ; characters, action, and uses of, 804-807
Jackson, Dr., advises the use of sulphuric ether as an anæsthetic, 179
Jalap, as a drastic purgative, 340 ; as a hepatic stimulant, 353 ; as a cholagogue, 355 ; character of, 897
Resin of, characters, action, and uses of, 897
Jamaica dogwood, action and use of, 827
Sarsaparilla, 957
James's powder, 653, 656
Jankowski, reference to, 294*n.*
Jaw, lower, action of phosphorus on the, 638
Jequirity seeds, character, action, and uses of, 817
Jervine, action of, on the spinal cord and the medulla, 964 ; the cardiac ganglia and the brain, 964
Joints, inflammation of the, utility of friction in, 301 ; and of vesicants, 302 ; tartar emetic ointment and croton-oil liniment sometimes useful in, 302
Jolyet, references to, 124, 317*n.*
Juglandaceæ, 939
Juglandin, as a hepatic stimulant, 353
Juglans, characters and uses of, 939 ; as a cathartic and hepatic stimulant, 939
Jugular veins, action of poisons when injected into the, 148, 204, 209
Juices, 462
Jumble beads, 817
Juniper, as a stimulant diuretic, 379 ; composition of, 954 ; oil of, 955 ; as a stimulant and diuretic, 955

K.

Kairin, action of, as an antipyretic, and uses of, 743
Kamala, as a vermicide, 357 ; characters, action, and uses of, 935 ; as an anthelmintic, 936
Kaolin, or China clay, action of, in inflammation of the urethra, 392 ; nature and uses of, 585
Kava, as a stimulant diuretic, 379
Keratin, its preparation, characters, and uses, 992 ; its mode of application, 993
Kühne, Professor, references to, 33, 47*n.* ; his discovery of ferment-yielding bodies, 65 ; references to, 109, 146
Kidneys, precautions to be taken regarding the state of the, 360 ; action of drugs on the, 369-383 ; the threefold functions of the, 369 ; three structures connected with these functions, 369 ; nature and process of secretion in the, 369-383 ; diagram of the urinary tubules in different classes of animals, 370 ; diagram of the circulation in the kidney of the newt, 372 ; diagrammatic sketch of the blood-vessels in a mammalian kidney, 372 ; diagram of the tubules and vascular supply of the, 373 ; circumstances modifying the secretion of urine by the, 374 ; relation between sweat glands and the, 386 ; action of the heavy metals on the, 595 ; the possible effect of mercury on the, 596 ; action of phosphorus on the, 638 ; of alcohol, 691, 696 ; of pilocarpine, 805, 807 ; of tannic acid, 943 ; of oil of turpentine, 951
Kiedrowski, reference to, 515
Kino, as an astringent, 305 ; nature, action, and uses of, 816
Klein, on bacteria, 66 ; reference to, 80
Knoll, reference to, 209
Kobert, references to, 103, 104
Koch, on bacteria, 66 ; reference to, 72 ; his experiments on bacteria with disinfectants, 74-78 ; references to, 82, 85 ; account of a syringe employed by, 420
Köhler, F., reference to, 80
Kölliker, references to, 120, 124
Koppe, references to, 252*n.*, 434
Koumiss, nature and use of, 989

Kousso, as a vermicide, 357 ; nature, action, and use of, 832
Kowalewsky, reference to, 253
Kraepelin, reference to, 161
Krameria, 785
Krameriæ, 785
Kratschmer, reference to, 209
Kronecker, references to, 34, 101, 102, 356
Krukenberg, reference to his researches on the medusæ, 81, 91, 93, 94
Kunde, references to, 145
Küntzer, reference to, 642
Kymograph, the, for ascertaining blood-pressure, description and diagram of, 227, 228

L.

Labiatæ, 916
Laburnum, as a poison, with its antidote, 432
Lachrymal secretion, action of drugs on the, 184
Lac sulphuris, 480
Lactate of iron, 675
Lactic acid, action of, on bacteria, 76 ; a hypnotic, 167 ; properties of, &c., 516
Lactucarium, character, action, and use of, 873 ; has a soporific action, and allays cough, 873
Langendorf, reference to, 207
Langley, reference to, 310*n*.
Lanthanum, symbol and atomic weight of, 9
Lappa, characters and uses of, 875 ; as an alterative, and in skin diseases, 876
Larch bark, 952, 953
Lard, prepared, 993
  Benzoated, 994 ; as an emollient, 994
Larynx, irritation of the, a cause of cough, 211-213 ; application of drugs to the, 422 ; diagram of insufflator for applying powders to the, 422 ; various modes of applying different drugs to, 422, 423
Laudanum, use of, in maintaining anæsthesia, 179
Lauraceæ, 926
Lautenbach, references to, 349, 350*n*.
Lavender, characters of, 917
  Oil of, characters of, 917
    Flowers, 917 ; characters, action, and uses of, 918 ; as a stimulant and carminative, 918
Laxatives. *See* Purgatives
Lead, symbol and atomic weight of, 9 ; action of, on the kidneys, 382 ; sources and reactions of, 627, 628 ; action of, 627 ; in the mouth, stomach, and intestine, 627 ; general sources of lead poisoning, 627 ; treatment for, 628 ; symptoms of chronic poisoning by, 628 ; lead colic and cramps, 628 ; paralysis, 629 ; known as wrist-drop, 629 ; action of, on the general system, 629 ; how eliminated, 629 ; uses, 629
Lead, acetate of, action of, on bacteria, 76 ; as a vascular sedative, 296 ; as an astringent, 305 ; as a styptic, 307 ; as a poison, with its antidote, 432
Lead, acetate of, 631
  Carbonate of, 631
  Iodide of, 633
  Nitrate of, 633
  Oxide of, 630
  Plaster of, 631
  Solution of subacetate of, 632
Leaf, digitalis, 908
  Tobacco, 906
Leaves, Aconite, 747
  Bearberry, 877
  Belladonna, 899
  Buchu, 803
  Cherry-laurel, 836
  Hemlock, 845
  Hyoscyamus, 904
  Matico, 938
  Stramonium, 906
Leech, the, 1,003 ; its action and uses, 1003
Leeches, action of chloroform on, 94 ; and of anæsthetics, 173 ; to genitals and thighs, as indirect emmenagogues, 398
Lemon, decoction of, 795
  Juice, characters, preparations, and uses of, 795 ; it is refrigerant, antiscorbutic, and a powerful antiperiodic, 795
  Peel, characters, composition, and preparations of, 794
Lemons, oil of, characters, preparation, and action of, 794
Leguminosæ, 813, 823
Leprosy, produced by the bacillus lepræ, 81
Leptandra, characters, and action of, 916 ; on the bile and as a cathartic, 916
Leptandrin, as a hepatic stimulant, 353
Lettuce, experiments with the protoplasm of, and water on oxygen, 54, 56 ; as a hypnotic, 167 ; composition of, 872
Leucin, action of, on bacteria, 76
Leucocytes, nature of, action of drugs on, and method of experimenting on, 45 *et seq.* ; diagram to illustrate the action of quinine on, 48 ; the protoplasm of, contracts in any direction, 95 ; anæsthetics act as poisons to, 173
Lewin, reference to, 887*n*.
Lichens, 979
Liliaceæ, 958
Lime, as a caustic, 301 ; as an astringent, 305 ; composition of, 579
Lime, character, tests, and preparations of, 579

Lime as an astringent and as an antacid, 580
Chlorinated, 486, 487, 584
Hypophosphate of, 583
Liniment of, 580
Phosphate of, 583
Precipitated carbonate of, 582
Saccharated solution of, 579
Slaked, 579
Sulphurated, 584
Syrup of, 579
Lime salts, sources and test of, 577; general preparation of, 578; impurities and tests of, 578
Lime water, action of, on bacteria, 75; as a direct antacid, 321; as a vermicide, 357; composition of, 579
Limonis succus, 462
Linaceæ, 782
Liniments, or embrocations, 453
Linimentum Aconiti, 454, 748, 928
Ammoniæ, 454, 543, 789, 881
Belladonnæ, 454, 900, 928
Fluidum, 900
Calcis, 454, 543, 789, 881
Camphoræ, 454, 789, 881, 928, 929
Camphoræ compositum, 454, 543, 917, 928, 929
Cantharidis, 454, 950, 1001
Chloroformi, 454, 720, 882, 928
Crotonis, 454, 839, 934
Hydrargyri, 454, 616, 928
Iodi, 454, 489, 543, 928
Opii, 454, 760, 928
Plumbi subacetatis, 454, 633, 789
Potassii iodidi cum sapone, 454, 489, 543, 794, 882, 883
Saponis, 454, 882, 917, 928
Sinapis compositum, 454, 781, 928, 934, 935
Terebinthinæ, 454, 882, 928, 950
Terebinthinæ aceticum, 454, 504, 928, 950
Linseed, and linseed tea, as demulcents, 304; composition, action, and use of, 782; chief use is as a demulcent, 783
Meal, 783
Oil, 783
Lippia Mexicana, composition, action, and uses of, 881
Liqueurs, as cardiac stimulants, 286
Liquor Acidi Arseniosi, 455, 647
Ammoniæ, 286, 569
Ammonii acetatis, 455, 751
Citratis, 455, 569
Fortior, 455
Antimonii chloridi, 455, 501, 653, 654
Arsenicalis, 455, 647
Arsenici hydrochloricus, 455, 647
Arsenici et hydrargyri iodidi, 455, 617
Atropiæ, 455
Liquor Atropiæ sulphatis, 455, 901
Bismuthi et ammoniæ citratis, 455, 659
Calcis, 455, 579
Calcis chloratæ, 455, 487
Saccharatus, 455, 579, 976
Chlori, 455
Epispasticus, 455, 504, 705, 1001
Ferri acetatis, 455
Chloridi, 455
Citratis, 455
Et quininæ citratis, 455, 674, 857
Nitratis, 455
Perchloridi, 455, 672
Fortior, 455
Pernitratis, 455, 502
Persulphatis, 455
Subsulphatis, 455
Tersulphatis, 455
Gutta-percha, 455, 879
Hydrargyri Nitratis acidus, 455, 502, 617
Perchloridi, 455, 617, 622
Iodi, 455, 489, 543
Iodi compositus, 455, 489, 543, 544
Lithiæ, 321
Lithiæ effervescens, 455, 562
Magnesiæ carbonatis, 455, 592
Citratis, 455, 592
Magnesii citratis, 455
Morphiæ acetatis, 455, 504, 764
Hydrochloratis, 455, 501, 764
Nitro-glycerini, 712
Pepsini, 455, 990
Plumbi subacetatis, 455, 631, 632
Dilutus, 455, 633
Potassæ, 321, 455, 533, 534
Effervescens, 455, 534
Permanganatis, 455
Potassii, 455
Arsenitis, 455, 647
Citratis, 455
Sodæ, 321, 455
Arseniatis, 455, 648
Chloratæ, 455
Effervescens, 455, 553
Sodii arseniatis, 455
Silicatis, 455
Strychniæ, 455, 885
Zinci chloridi, 455, 599, 601
Liquorice, as a stimulating expectorant, 219
Liquorice root, characters and composition of, 813; preparation, action, and uses of, 814
Lister, Sir Joseph, originates the antiseptic mode of treatment, 84; on the untoward consequences of operations, 737
Lithia, benzoate of, 563
Bromide of, 563
Carbonate of, 562
Citrate of, 562
Salicylate of, 563

Lithium, symbol and atomic weight of, 9 ; more poisonous than sodium or potassium, 21 ; its relation to other members of a group, 15 ; physiological action of, 23 ; causes contraction of the vessels, 240 ; sources, reaction, impurities, and tests of, 561 ; general action of, 562
Lithium, bicarbonate, as a direct antacid, 321
Carbonate, as a direct antacid, 321
Citrate, as a direct antacid, 321
Lithontriptics, nature and uses of, 382
Litmus, 979
Paper, blue, 979
Red, 979
Tincture, 979
Solution of, 979
Littlejohn, Dr., reference to, 336
Liver, effect of the, on the action of drugs, 29, 32 ; caustics employed to open abscesses of the, 303 ; action of drugs on the, 349 ; important function of the, in the general system, 349 ; action of hepatic stimulants and cholagogues on, 349, 350 ; power of the, in destroying the poisonous properties of some vegetable alkaloids, 350 ; five principal functions of the, 351 ; experiments on the action of hepatic stimulants, 352 ; list of these stimulants, 353 ; diagram of the stomach, intestines, and, 353 ; experiments on the action of cholagogues, 353-355 ; importance of combining hepatic and intestinal stimulants to ensure complete cholagogue effect, 355 ; adjuncts to cholagogues, 355 ; uses of hepatic stimulants and cholagogues on the, 356 ; action of hepatic depressants on the, 356 ; action of acids on the, 498 ; of chloride of ammonium, 568 ; of mercury, 614 ; of phosphorus, 638 ; of alcohol, 691, 696 ; of dandelion, 872
Liversedge, references to, 65
Lobelia, as a depressant expectorant, 219 ; as a poison, with its antidote, 432 ; characters and composition of, 876 ; action of, on the respiratory centre, the blood-pressure, the vaso-motor centre and the vagi, 877 ; uses of, 877
Lobeliaceæ, 876
Lobeline, as a myotic, 186 ; as a depressant expectorant, 219 ; action of, on the vagus-ends of the heart, 275
Lockyer, J. N., propounds the hypothesis that all the elements are compounds, 10 ; reference to, 22
Loganiaceæ, 884
Logwood, characters, composition, and uses of, 822
Long, Dr. C. W., first uses ether as an anæsthetic, 179
Loos, reference to, 124
Lotio Hydrargyri flava, 579, 671
Nigra, 579, 616, 621
Lovèn, reference to, 250
Lozenges, 466
Luchsinger, Dr., references to, 33-35, 113, 114, 385, 903
Luciani, reference to, 267*n*.
Ludwig, references to, 146, 151*n*., 227, 237*n*., 238, 240, 241, 250, 253, 280, 349
Ludwig and Coats's apparatus for experimenting on the frog's heart, 260, 261, 262, 268, 369, 370, 373, 374
Lumbar genital centre, connection of the, with the generative organs, 393
Lungs, application of drugs to the, 423 ; by inhalation of vapours, 423 ; by the bronchitis kettle, 424 ; and by smoke, 424 ; action of gold on the, 680 ; of ipecacuanha, 865
Lupuline, as a general anodyne, 169, 170 ; characters, composition, action, and uses of, 948 ; as a tonic, stomachic, and soporific, 948
Lupulinum, 948
Lupulus, as a general anodyne, 169
Lussana, reference to, 354
Lymph, an abnormal condition of, one of the chief causes of dropsy, 291, 292

M.

Mace, as a carminative, 330 ; characters and uses of, 826
McKendrick, reference to, 237
Mackenzie, J. N., reference to, 212*n*.
Maclagan, Dr. Craig, reference to, 642
Magendie's experiments on the spinal cord, 144 ; references to, 324, 888
Magenta, 743
Magnesia, as a direct antacid, 321 ; as a laxative and purgative, 339 ; carbonate of, as a purgative, 339 ; characters and action of, 590, 591 ; sulphate of, 590 ; enema of sulphate of, 590 ; carbonate of, 591 ; light ditto, 591 ; solution of carbonate of, 592 ; solution of citrate of, 592
Magnesium, symbol and atomic weight of, 9 ; its relation to other members of a group, 15 ; physiological action of, 23 ; causes contraction of the vessels, 240 ; sources, reactions, and preparations of, 589 ; impurities, tests, and action of, 590 ; sulphate of, 590 ; carbonate of, 591
Magnesium, carbonate and bi-carbonate, as a direct antacid, 321
Magnetic oxide of iron, 676
Magnoliaceæ, 756
Malaria, and all diseases of malarious origin, quinine and cinchona bark are almost specifics in, 87 ; condition of vaso-motor centre in, 778, 867

Malpighian corpuscles, the, 369, 371, 372, 374
Malt, extract of, 975 ; as a digestive ferment, 975
Malvaceæ, 788
Mammalia, 987
Mammals, action of nitro-glycerine on, 712 ; of chloral hydrate, 716 ; of opium, 768 ; of erythroxylon, 787
Manganese, symbol and atomic weight of, 9 ; as an indirect emmenagogue, 398 ; properties, action, and uses of black oxide of, 678 ; of sulphate of, 679
Manna, as a laxative, 339 ; characters, composition, and use of, 883 ; as a laxative, 884
Manometers, fallacies of mercurial, 228
Mansell's solution of iron, 669
Marble, white, 578
Marey, references to, 105
Marey's levers, 208; pneumograph, 208 ; and hæmodromometer, 253 ; reference to, 256
Marigold, 874
Marjoram, wild. *See* Origanum
Marrubium, characters and use of, 921 ; as an expectorant, 921 ; and in large doses a laxative, 921
Marsh damp, as a poison, with its antidote, 429
Marshmallow. *See* Althæa
Marshmallows, as demulcents, 304
Marx, reference to, 30
Maryland pink. *See* Spigelia
Massa copaibæ, 455, 826
Ferri carbonatis, 455
Hydrargyri, 455, 616
Massage, action of, on muscles, 107
Masses, 455
Mastication, arteries of the brain dilated in animals by the movements of, 161
Masticatories, nature and use of, 425
Mastich, characters, composition, and uses of, 811
Materia medica, definition of, 1
Inorganic, 473 *et seq.*
Organic, 685 *et seq.*
Proper, 1
Vegetable, 747 *et seq.*
Matico, as a styptic, 307 ; and stimulant diuretic, 379 ; characters, action, and uses of, 938 ; as a styptic, 938 ; leaves, 938
Maynard, reference to, 186
Mays, reference to, 263
Meconic acid, 762
Medicated baths, 413
Medicine, materia medica gives an account of the various remedies used in, 1 ; preventive medicine, or prophylaxis, growing importance of, 2 ; cause of the rapid advance of, 2
Medulla oblongata, nature and functions of, 197 *et seq.* ; diagram representative of various groups of ganglion cells or "centres," in the, 200 ; experiments on the, 209 ; blood vessels relax after section of the, 221 ; stimulating effect of asphyxial blood on the, 256 ; the nerve-centre which regulates the secretion of the saliva situated in the, 311 ; the nerve-centre which regulates the movements of vomiting is situated in the, 322 ; the nervous centre for the renal arteries in the, 376 ; action of spirit of ether on the, 706 ; of carbolic acid, 735 ; of aconitine, 750 ; of delphinine, 752 ; of hydrochlorate of apomorphine, 765 ; of caffeine, 798 ; of physostigmine, 819 ; of oil of eucalyptus, 840 ; of thymol, 920
Medusæ, action of drugs on, 88-92 ; effect of stimuli on the rhythmical movements of, 88-90 ; and of various poisons on, 90, 91 ; general results of various experiments on, 91, 92
Mel boracis, 456, 998
Depuratum, 456, 998
Despumatum, 456, 998
Rosæ, 456, 831, 998
Meliaceæ, 801
Mendelejeff, perfects the classification of the elements in series, 16-19 ; table of his arrangement, 17 ; his predictions regarding gallium, 18 ; reference to his classification, 518
Menispermaceæ, 756
Menispermum (Canadian moonseed), characters, composition, and uses of, 757
Menstruation, action of emmenagogues on, 396
Menthol, action of, on the brain and spinal cord, 181 ; as a rubefacient, 300
Mercurial cachexia, 613 ; tremors, 613 ; and paralysis, 613
Mercurial preparations, as cholagogues, 340
Mercurialism, nature and cause of, 613 ; one of the best preparations for producing, 619
Mercuric chloride, effects of, on the blood, 58 ; on annulosa, 94 ; as a caustic, 301 ; as a hepatic stimulant, 353
Mercuric nitrate, as a caustic, 301
Mercuric oxide, as a caustic, 301
Mercury, symbol and atomic weight of, 9 ; physiological connection between calcium and, 19 ; causes salivation, 22 ; action of, on muscle, 104 ; on the vaso-motor nerves, 276 ; and its compounds as a sialagogue, 312 ; as an alterative, 362 ; its power in fibrin and syphilitic deposits, 364 ; used to break up deposits of lymph, and to prevent adhesions in iritis and pericarditis, 365 ; and in the treatment of the secondary stage of syphilis, 365 ; action of, on the kidneys, 382 ; sources and reactions of, 610 ; general impurities and tests, 611 ; general action of, 611-

616 ; on the skin, 611 ; effects of, on the body termed "mercurialism," 612 ; action of, on the mouth, 612 ; salivation, 612 ; causes fever, 612 ; the fumes of, produce a state called mercurial cachexia, 613 ; which results in mercurial tremors in the muscles, 613 ; and paralysis, 613; mental powers also affected, 613 ; special action of, on the brain, 613, 614 ; action of, modified by sex, age, and idiosyncrasy, 614 ; action of, on the stomach, 614 ; the liver, 614, 615 ; and blood, 615 ; has the power of causing the absorption of fibrinous exudations, 615 ; action of, on the pulse, 615 ; on respiration, 616 ; and the temperature, 616 ; cause of the salivation produced by, 616 ; action of, on the urine, 616
Mercury, nature, preparations, action, and uses of, 616-620
Acid solution of nitrate of, 625
Ammoniated, 624
Black lotion of, 622
Corrosive chloride of, 622
Cyanide of, 626
Green iodide of, 625
Mild chloride of, 621
Ointment of nitrate of, 625
Perchloride of, 622
Red iodide of, 626
Red sulphide of, 627
Red oxide of, 624
Subchloride of, 621
Sulphate of, 620
Yellow oxide of, 623
Yellow subsulphate of, 620
Mercury salts, as a cholagogue, 355
Metallic salts, as poisons, with their antidotes, 432 ; general tests for the acid radicals in, 519 ; list of tests for the different acids, 520
Metals, general classification of the, 518 ; I., monad metals, 518 ; 1, metals of the alkalis, 523 ; 2, ammonia, 522 ; general characters and reactions, 522 ; physiological action, 522 ; general action of the alkaline group, 523-525 ; and of the group of chlorides, 525-527 ; general action of the sub-group of sulphates, 527 ; comparative action of the alkaline metals, 528 ; 1, metals of the alkalis—potassium, 529-548 ; sodium, 548-561 ; lithium, 561-563 ; monad metals, group 2, ammonium salts, 564-574 ; II., dyad metals, 575 ; reactions of the metals in class II., 576 ; group 1, metals of the alkaline earths, 576 ; general action, 576 ; calcium, 577-585 ; appendix to group 2, aluminium, 585-588 ; and cerium, 588 ; group 2, magnesium, 589-592 ; general action of heavy metals on the circulation, intestinal canal, blood, tissue, muscles, nerves, nerve-centres, and glands, 593-596 ; group 3, 596 ; general action of, on the system, 596 ; zinc, 597-603 ; copper, 604-606 ; cadmium, 606 ; argentum, 606-610 ; mercury, 609-627 ; lead and tin, 627-634
Methæmoglobin, origin, nature, and changes of, 56, 57
Methyl, effect of the introduction of, into the molecule of the strychnine, brucine, and thebaine, 23
Methyl-atropine, -codine, -morphine, -nicotine, -quinine, and -veratrine, paralysing action of, 23
Methyl-atropine, action of, on the motor-nerves, &c., 903
Methyl-conine, action of, on the spinal cord, 846
Methylene, bichloride of, preparation, character, and action of, 718
Methyloxychinicine, constitution of, 744
Methylstrychnine, action of, on muscle, 119; on the vagus-ends in the heart, 275 ; methylstrychnine, characters of, 888
Meyer, reference to, 235
Meyer, Hermann, reference to, 62
Meyer, Lothar, his labour in completing the classification of the elements in series, 16
Meyer, R., reference to, 213
Meyer, Sigmund, reference to, 114*n*.
Mezereon, as a vesicant, 301 ; as a sialagogue, 312
Mezereum, as an alterative, 362
Microbacteria, 67
Microbes, recent increase in knowledge of, 2 ; destruction or prevention of, diminishes disease, 2 ; references to, 80, 81, 84
Micrococci, references to, 67, 69, 70, 72, 80 ; list of diseases caused by, 81
Microzymes, references to, 74, 75, 86
Milk, action of drugs upon, 399 ; what the character of the, depends upon, 400 ; substances excreted by the, 400 ; various drugs administered to the mother react upon the child through the, 400, 401 ; action of pilocarpine on the secretion of, 805 ; its composition, therapeutics, and use, 989
Milk, sugar of, its characters, 989 ; and uses, 990
Milk of sulphur, 480
Mills, Mr., reference to, 724
Mimoseæ, 828
Mistura ammoniaci, 456, 848
Amygdalæ, 456, 834
Asafœtidæ, 456, 847
Chloroformi, 456, 720
Creasoti, 456, 504, 738
Cretæ, 456, 828
Ferri aromatica, 456, 837, 854
Composita, 456, 813, 926, 976
et ammonii, 456
Acetatis, 456, 672

Mistura Gentianæ, 456, 792, 852, 894
Glycyrrhizæ composita, 456, 708
Guaiaci, 456, 801, 828, 976
Magnesiæ et asafœtidæ, 456, 847
Potassii citratis, 456, 794, 795
Rhei et sodæ, 455, 924
Scammonii, 456, 896, 988
Sennæ composita, 456, 814, 824
Spiritus vini gallici, 456, 701, 995
Mixtures, 456
Molecules, origin and nature of, 10 ; simple and complex, 10, 11 ; condition of, in a solid and gaseous state, 11 ; the vibrations of, determined by their weight, 21
Mollusca, action of drugs on, 92 ; effects of various poisons on, 93
Molybdenum, symbol and atomic weight of, 9 ; its relation to other members of a group, 15
Mommsen, reference to, 125
Monobromo-camphor as a hypnotic, 117 ; action of, on the cardiac muscle, 276
Morat, reference to, 236, 256
Moreæ, 945
Mori succus, 462
Morphia, acetate of, characters and preparations of, 764
Hydrochlorate of, ditto, ditto, 763
Morphiæ acetas, 760
Acetatis liquor, 761
Hydrochloras, 444, 761
Hydrochloratis liquor, 761
Morphina, 444
Morphine, effect of habit on the quantity that can be taken, 32 ; action of, on oxidation, 55 ; on the blood, 58 ; as a sedative, 128 ; action of, on the spinal cord, 132, 142, 143 ; as a spinal stimulant, 151 ; as a powerful hypnotic, 166, 167 ; induces sleep and lessens pain, 167 ; as a local and general anodyne, 169 ; as a myotic, 186, 187 ; action of, in diminishing the excitability of the respiratory centre, 214 ; and when combined with atropine, 215 ; as an antisialic, 316 ; as a local and general sedative, 327 ; action of, on the intestines, 334 ; action of, on urea, 363 ; value of, in laryngeal phthisis, 423 ; as a poison, with its antidote, 432 ; antagonistic action of, to certain alkaloids, 436, 437
Morphine, characters, reactions, of, &c., 763 ; opium *versus*, 775
Acetate of, character and preparations of, 764
Hydrochlorate of, characters of, &c., 763
Apo-, characters, action, and uses of, 765, 766
Sulphate of, preparations of, 764
Morshead, reference to, 187
Morton, Mr., his use of ether in dentistry, 179
Moseley, reference to, 93, 94*n*.
Moss, Iceland, its characters, composition, and therapeutics, 979
Moss, Irish, characters and use of, 984
Mosso, references to, 81, 105, 124, 240, 241, 351
Motion and oxidation, relations of, in the animal economy, 51
Motor ganglia, action of oatmeal on the, 976
Motor nerves. *See* Nerves
Mould fungi, origin, nature, and effects of, 66-68 ; diseases caused by, 68
Mouth, application of drugs to the, 426 ; as washes, 424 ; as caustics, by rubbing, 424 ; as masticatories, 425 ; as gargles, 425 ; action of acids in the, 496 ; action of alkalis in the, 524 ; of the metals, zinc, copper, cadmium, and silver, 596 ; of silver, 608 ; of alcohol, 691, 692 ; of spirit of ether, 706 ; of chloral hydrate, 715 ; of purified chloroform, 721 ; of creosote, 739 ; of tannic acid, 942 ; of aloes, 962
Mucilages, 456
Mucilaginous remedies, useful in cases of irritating cough, 214
Mucilago Acaciæ, 456, 828
Amyli, 456, 974
Cydonii, 456, 829
Sassafras medullæ, 456, 931
Tragacanthæ, 456, 815, 883
Ulmi, 456, 945
Mucous membranes, action of morphine and atropine on the secretions of the, 215 ; character and action of the secretion of the, 215 ; of heat and cold on the circulation and secretion of the, 216 ; of drugs on the secretion of the, 216-218 ; drugs which increase the ciliary motion in the tracheal, 219 ; action of chloride of ammonium on the gastric, 568 ; of tannic acid, 942
Mulberry juice, characters and use of, 945
Murrell, references to, 643, 648
Muscarine, action of, on mollusca, 93 ; as a myotic, 186, 187 ; action of, on the respiratory centre, 205, 210 ; on the frog's heart, 266 ; on the inhibitory power of the vagi, 269 ; on the ganglia, 271 ; action of, neutralised by atropine, 272 ; action of, on inhibitory ganglia, 275 ; on the cardiac muscle, 276 ; as a sialagogue, 312, 313 ; as a general emetic, 325 ; as an antihydrotic, 387 ; antagonism of, to atropine, 433-437
Muscle, action of drugs on, 95-118 ; on voluntary, 95 ; elasticity, extensibility, and retractility of, 95, 96 ; irritability of, 96 ; contraction of, 96 ; latent period of, 97 ; muscle-dynamite, nature and action of, 97*n*. ; summation of stimuli, 99 ; contraction, 99 ; fatigue, 100 ; contracture of, 101 ; tetanus, 102 ; poisons, 103-107 ;

massage of, 107 ; propagation of the contraction wave in, 108 ; rhythmical contraction of, 108 ; connection between chemical constitution and physiological action on, 110 ; action of drugs on, relative, not absolute, 111 ; action of drugs on involuntary muscular fibre, 112 ; contraction, 112 ; effect of stimuli on the, 113 ; of cold and heat, 114 ; relation of the contractile tissue to the nerves, 114 ; propagation of contraction waves, 115 ; effects of stimulation of the vagus and a weak interrupted current, 115 ; artificial rhythm, 115 ; hypothetical considerations regarding the action of drugs on muscle, 116

Muscles, spasms and cramps of the, nature, cause, and general treatment of, 180-182 ; of the eye, 184 *et seq.* ; of respiration, 200 ; difference between the vessels of the intestines and those of the, 235 ; the vaso-motor centre has no power over the vessels of the, 235 ; action of chlorides on the, 528 ; of ammonium salts, 528 ; of potash salts, 531 ; of ammonium chloride, 567 ; poisonous action of the heavy metals on the, 595 ; of platinum, 680 ; of spirit of ether, 706 ; of nitrite of amyl, 710 ; of nitro-glycerine, 712 ; of chloral hydrate, 716 ; hydrochlorate of apomorphine on the fibres of the, 765 ; of caffeine on ditto, 798 ; of pilocarpine on muscles and muscular fibre, 805, 806 ; of physostigmine on ditto, 819 ; of quinine, 862 ; of strychnine, 887 ; of curare, 889 ; of belladonna or atropine, 891 ; of digitalin, 910 ; of veratrine, 965 ; of oatmeal, 976

Muscular contraction, apparatus for registering, 97 ; muscular poisons, number and action of, 103-107 ; muscular fibre, importance of the action of chloroform and ether on, 174, 175 ; nerves die sooner than the, 240

Mushrooms, as poisons, with their antidotes, 432

Musk, antispasmodic action of, 181, 182, 987 ; as an antispasmodic and stimulant, 988 ; its action on the respiratory centre, 988

Mustard leaves and liniment of, as rubefacients, 300-302 ; as a sialagogue, 312 ; as a local emetic, 325 ; as a carminative, 330 ; as a stimulant diuretic, 379 ; baths, poultices, and stupes, as indirect emmenagogues, 398 ; bath, 413 ; powdered, 779 ; white, 779 ; black, 779 ; characters and compositions of the powdered, 780 ; preparations of, 780

Mustard, oil of, action of, on enzymes, 63 ; on bacteria, 73, 76, 77 ; as a vesicant, 301, 780 ; characters and preparations of, 781 ; action of, on the skin, and internally as a prompt emetic, 781 ; it is also used externally as a counter-irritant, in the form of a poultice, &c., 781

Mycoderma vini, nature and action of, 66

Mydriatics, and their action in dilating the pupil of the eye, 186-189

Myositis, infective, micrococci present in, 81

Myotics, and their action in contracting the pupil of the eye, 186-190

Myristicaceæ, 925

Myrrh, as a direct emmenagogue, 398 ; characters and composition of, 812 ; action and uses of, as an astringent and expectorant, 813

Myrtaceæ, 837

Myrtle, oil of, action and uses of, 839 ; is an antiseptic, rubefacient, internal irritant, and expectorant, 839

N.

Nægeli, references to, 66, 80

Naphthalin, source and characters of, 742 ; mode of administration, 742 ; action of, in destroying low organisms and preventing the germination of their spores, 742 ; as an antiseptic, and when used internally, 742 ; uses of, 749

Naphthol, characters, action, and uses of, 742

Narcotics, nature and action of, 167

Nasal douche, diagram of a, 421

Nataloïn, nature and action of, 960

Nativelle's digitaline, 909

Nauseant, antimony as a, 653

Nerein, action of, on the cardiac muscle, 276

Neroli, oil of, 791

Nerve centre, the, which regulates the movements of vomiting, 322

Nerve centres, in respiration, nature and functions of the, 199-210 ; for the secretion of sweat situated in the spinal cord, 384 ; how they may be stimulated, 385 ; situation of the, for the movements of the bladder, 390 ; action of potash salts on the, 532 ; poisonous action of the heavy metals on the, 595 ; action of gold on the, 680 ; of alcohol, 689, 694 ; of erythroxylon, 787 ; of caffeine, 798 ; of hydrochlorate of pilocarpine, 805, 806 ; of physostigmine, 819 ; of quillaia (saponin), 832 ; of oil of eucalyptus, 840 ; of thymol on the, of the cord and medulla, 920 ; of camphor, 929 ; of oil of turpentine, 951

Nerve stimulants divided into two kinds, 160 ; tonics, when necessary, 360

Nerves, relation of the contractile tissue to the, 114 ; action of drugs on, 119-128 ; on motor, 119-125 ; paralysis of the motor endings of the, 118, 121 ; paralysis

may be due to disturbance of rhythm between muscle and, 118; experiments illustrative of paralysis, 121-123; list of drugs which have the same paralysing action on the, as curare, 123; irritation of the motor endings of the, by drugs, 125; action of drugs on the trunks of the motor, 125; on sensory, 126; the general action, 126; the local action, 127; action and uses of local sedatives and anæsthetics on, 127; and of drugs on the peripheral ends of the sensory, 128; pain ascribed to vibrations of, or of the sheaths, 171; action of anæsthetics on the, 171 *et seq.*; the chief afferent, expiratory, and inspiratory, 206-209; of drugs on the respiratory, 209; the, die sooner than the muscular fibres, 240; action of drugs on the vaso-motor and vaso-dilating, 242; action of the, on the vessels of circulation, 245; influence of, on blood-pressure, 248-250; inhibitory nerves, 248; quickening nerves, 248; vaso-motor nerves, 249; depressor nerves, 250; action of drugs on the accelerating, 256; action of the, on the secretion of saliva, 309-315; diagrams illustrating this action, 310, 311, 314; action of the afferent on vomiting, 322; diagram showing the afferent, by which the vomiting centre may be excited, 323; of the kidney, 375, 376; action of ammonium salts on motor, 528; of potash salts on ditto, 532; of strong solution of ammonia, 570; poisonous action of the heavy metals on the, 595; action of silver on the, 608; of salts of iron, 666; of manganese salts, 679; of alcohol, 694-696; of spirit of ether, 706; of nitrite of amyl, 710; of chloral hydrate, 716; of purified chloroform, 721; of carbolic acid, 735; of codeine, 766; of opium on the sensory, 770; of pilocarpine on the efferent and other, 805, 806; of physostigmine on the motor and sensory, 819; of sulphate of strychnine on the sensory, 885; of belladonna or atropine on the motor, 901; of tobacco on the motor and secreting, 907; of Indian hemp on the sensory, 947; of veratrine 966; of colchicum, 968; of extract of ergot, 981

Nervine tonics, zinc salts as, 599; sulphate of copper as, 605

Nervous debility and irritability, relieved by mustard applications, 301

Nervous ganglion in some lower organisms, nature and functions of the, 197 *et seq.*

Nervous system, general irritability of the, generally precedes an attack of gout, 182; regulating action of the, 280-283; action of silver on the, 608; of purified chloroform on the, 721, 723; of iodoform, 729; of aconitine, 751; of opium on the central, 767, 770, 777; of pilocarpine, 505, 506; of elaterin, 844; of quinine, 861; of strychnine, 887; of solanine, 898; of tobacco, 907; of digitalin, 910; of extract of ergot, 981

Neuralgia, blisters and cautery of great use in, 302

Neuralgic pains, relieved by rubefacients, 301

Newlands, Mr., makes the first natural classification of the elements, 15, 16; points out a curious relationship between the lithium and calcium group of elements, 15; and notes that the eighth element is a kind of repetition of the first, 16

Newman, reference to, 237

Newt, diagram of the circulation in the kidney of the, 372

Nickel, symbol and atomic weight of, 9; physiological action of, 23; causes slight contraction of the vessels, 240

Nicotia, action of, on oxidation, 55, 58

Nicotine, action of, on medusæ, 90; on mollusca, 93; on ascidians, 93; on the spinal cord, 132; as a spinal stimulant, 151; as a myotic, 186; on the respiratory centre, 205; on the vessels of circulation, 241; on the vagus roots, 253; on the heart of the frog, 267; on the inhibitory power of the vagi, 268, 269; on the vagus centre, 274; on vagus-ends in the heart, 275; action of, on the intestines, 333; on the sweat centres, 385; antagonism of, to morphine, 433-437. *See* also Tobacco

Niobium, symbol and atomic weight of, 9

Nitrates, test for, 521

Nitrate of ammonia, 573
- Iron, 673
- Lead, 633
- Potash, 537
- Potassium paper, 538
- Silver, 607
  - Diluted, 607
  - Moulded, 607

Nitrate of silver, action of, on the mucous membrane, 17; difference of the action of, on the mucous membrane and on the trachea, 217; value of, in laryngeal phthisis, 423

Nitric acid, as a caustic, 301; as a poison, with its antidote, 429; properties and uses of, 501

Nitrite of amyl, ethyl, &c. *See* Amyl, Ethyl, &c., nitrite of

Nitrites, effects of mixing, with freshly-drawn blood, 57; of poisoning by, on the colour of the blood, 204; on the capillaries, 277; all nitrites act as vascular stimulants, 288

Nitro-benzol, as a poison, with its antidote, 432

Nitrogen, 635; symbol and atomic weight

of, 9 ; its relation to other members of a group, 15 ; experiments as to the excretion of, in the body, 363
Nitrogen monoxide, nature, action, uses, and mode of administration of, 636
Nitro-glycerin, as a poison, with its antidote, 432
Nitro-glycerine, glonoine, preparation and properties of, 712 ; action of, similar to that of nitrite of amyl and other nitrites, 712 ; in frogs and mammals, 712, 713 ; on the blood and blood-pressure, 713 ; why it acts more powerfully than other nitrites, 713 ; uses of, 713
Nitrohydrochloric acid, properties and uses of, &c., 503 ; dilute ditto, 503
Nitro-muriatic acid, action of, on the urine, 383
Nitrous ether, as a vascular stimulant, 287 ; as a refrigerant diuretic, 379
Nitrous oxide, as an anæsthetic, 172 *et seq.* ; nature and action of, 636, 657
Nose, application of drugs to the, 421 ; as snuff, 421 ; by insufflation, 421 ; by the nasal douche, 421 ; diagram of nasal douche, 421 ; action of pilocarpine on the, 805
Nothnagel, reference to, 316, 334, 753
Nowak, reference to, 112
Nussbaum, reference to, 371
Nut, areca, 972 ; as an anthelmintic, 973
Nutgalls, action and uses of, 941
Nutmeg, characters and composition of, 926 ; volatile oil of, 926 ; expressed oil of, as a stimulant and carminative, 926
Nutmeg and oil, as carminatives, 330
Nutrition, remedies which improve, 362 ; what healthy nutrition depends on, 362
Nux vomica, as a stimulating expectorant, 219 ; as a cardiac tonic, 289 ; as an antihydrotic, 387 ; characters, composition, and preparations of, 884

O.

Oak-bark, as an astringent, 305 ; action and use of, 941
Oatmeal, 976 ; action and uses of, 976
Œsophagus, the, of various animals, muscular structure of, 114
Offenburg, reference to, 896
Officinal preparations. *See* the different drugs
Oil, castor. *See* Castor oil
Oil, cod-liver, 996 ; its characters and composition, 996 ; its physiological action, 996 ; powers of absorption and assimilation, 996 ; therapeutics, 997
Oil, ethereal, 707
Oil of allspice, 838
Almonds, 834
Bitter, 433, 834
Amber, 952
Oil of Anise, 949
Bergamot, characters and use of, 793
Cajuput, 839
Caraway, 851
Castor, 934
Chamomile, 871
Cinnamon, 927
Cloves, 77, 337
Copaiva, 826
Coriander, 852
Croton, 933
Cubebs, 937
Dill, 850
Eucalyptus, 840
Firwool, 951
Gaultheria, 878
Juniper, 955
Lavender, 917
Flowers, 917
Lemons, 794
Mace, 104
Mustard. *See* Mustard oil
Myrtle, 839
Neroli, 791
Nutmeg, expressed, 926
Volatile, 926
Orange flowers, 791
Peel, 793
Peppermint, 918
Pimenta, 838
Pimento, 838
Rue, 802
Rosemary, 274, 917
Santal, 932
Scotch fir, 951
Spearmint, 919
Sesamum, 922
Tar, 954
Theobroma, 796
Turpentine, 71, 218, 286, 300
Valerian, 867
Oil of turpentine, action of, on bacteria, 77 ; of the vapour of, on the mucous membrane, 218 ; great therapeutical value of the vapour of, in bronchitis, 218 ; as a cardiac stimulant, 286 ; as a rubefacient, 300 ; as an antidote to phosphorus, 433
Oils, ethereal, action of, on bacteria, 82 ; on the vaso-motor centre, 274 ; aromatic volatile, as cardiac stimulants, 286 volatile, as rubefacients, 300 ; as an antidote to phosphorus, 433
Oils, fixed and volatile, 457
Ointment, sulphur, 480 ; alkaline sulphur, 480 ; various kinds of iodine, 489 ; iodide of sulphur, 490. *See* Unguentum
Ointments, their nature, number, and uses, 467
Oleaceæ, 881
Oleate of mercury, 517
Of veratrinum, 517
Oleates, 458
Oleatum hydrargyri, 458, 517, 616, 623
Veratrinæ, 458, 517, 965

Oleic acid, action of, on bacteria, 76 ; properties and uses of, 517
Oleoresina Aspidii, 458, 978
Capsici, 458, 899
Cubebæ, 458, 937
Lupulini, 458, 948
Piperis, 458, 936
Zingiberis, 458, 970
Oleoresins, 458
Oleum Adipis, 457
Æthereum, 457
Amygdalæ, 457, 834
Amaræ, 457
Expressum, 457
Anethi, 457, 850
Anisi, 457, 756
Anthemidis, 457, 871
Aurantii corticis, 457
Florum, 457
Bergamii, 457
Cajuputi, 457, 458
Cari, 458, 851
Carui, 457, 851
Caryophylli, 457, 458, 837
Chenopodii, 458
Cinnamomi, 457, 458, 927
Copaibæ, 457, 458, 826
Coriandri, 457, 458, 852
Crotonis, 457
Cubebæ, 457, 458, 937
Erigerontis, 458
Eucalypti, 458, 840
Fœniculi, 458
Gaultheriæ, 458
Gossypii seminis, 457
Hedeomæ, 458, 920
Juniperi, 457, 458
Lavandulæ, 457, 458
Florum, 458
Limonis, 457, 458, 794
Lini, 457, 783
Menthæ piperitæ, 457, 458
Viridis, 457, 458
Morrhuæ, 457
Myrciæ, 458
Myristicæ, 457, 458, 925
Expressum, 457, 925
Olivæ, 457
Phosphoratum, 457, 637
Picis liquidæ, 458
Pimentæ, 457, 458, 838
Ricini, 457
Rosæ, 458
Rosmarini, 457, 458
Rutæ, 457, 458
Sabinæ, 457, 458, 955
Santali, 458
Sassafras, 458, 930
Sesami, 457
Sinapis, 458, 780
Volatile, 458, 780
Succini, 458
Terebinthinæ, 457, 458
Theobromæ, 457
Oleum Thymi, 458
Tiglii, 457
Valerianæ, 458, 867
Oleum animale, action of, on bacteria, 76
Oleum pini pumilionis, as a stimulating expectorant, 219
Oleum pini sylvestris, as a stimulating expectorant, 219
Olive oil, as a demulcent, 304 ; characters, composition, and preparations of, 881 ; action and uses of, 882, 883
Oleum menthæ piperitæ action of, on bacteria, 76
Onion, as a stimulating expectorant, 219
Ononis spinosum, as a stimulant diuretic, 380
Operations, surgical, Sir Joseph Lister on the best mode of performing, 737
Ophthalmia, gonorrhœal, contagious, and neanotorum, caused by micrococci, 81
Opium, effect of habit on the quantity that can be taken, 32 ; abnormal effects of, in some cases of fever, 35, 36 ; some persons very slightly affected by, 39 ; as a sedative, 128 ; as a spinal stimulant, 151 ; different actions of, in different doses, on the brain, 163 ; one of the most powerful hypnotics, 166, 167 ; induces sleep and lessens pain, 167 ; as a local and general anodyne, 169, 179 ; as a myotic, 186 ; action of, on the respiratory centre, 205 ; on the brain, 209 ; in diminishing the excitability of the respiratory centre, 214 ; action of, on the vessels of circulation, 243 ; as a vascular sedative, 296 ; as an antisialic, 316 ; as a local and general sedative, 327 ; action of, on the intestines, 333-335, 337 ; as a purgative, 336 ; as a vesical sedative, 391 ; as a poison, with its antidotes, 433 ; antagonistic action of, and belladonna, 436, 437 ; antagonism of, to other drugs, 433-437 ; characters and preparations of, 760, 761 ; alkaloids of, 762 ; physiological action of, 767 ; general action of, exclusively on the central nervous system, 767 ; and in mammals especially on the brain, 767 ; in the frog it acts on the motor ganglia of the heart, 767 ; action of, on frogs, 767 ; on birds, 768 ; on mammals, 768 ; on man, it acts chiefly on the brain, 768 ; in producing sleep and, in large doses, death, 769 ; diagnosis between poisoning by, and intoxication and apoplexy, 769 ; treatment in poisoning by, 769 ; precautions, 770 ; treatment of the symptoms after an ordinary dose, 770 ; action of, on special organs, 770 ; on the sensory nerves, the spinal cord, and the brain, 770 ; on the pupil, the circulation, and the vaso-motor centre in the medulla,

770, 771 ; has a peculiar action on the peripheral vaso-motor apparatus, 771 ; on secretion, 771 ; on sweat and the urine, 772 ; on the intestines, 772 ; elimination, 772 ; circumstances modifying the action of, 772 ; sex and idiosyncrasy, 772 ; habit, 773 ; opium-eating, 773 ; action of, in disease, 774 ; and in combination with other drugs, 774 ; action of the alkaloids of, 774 ; the morphine group and the codeine group, 774 ; how codeines are produced, 775 ; action of apo-morphine and morphine, 775 ; therapeutics—general uses and local uses, 775 ; on the digestive system, 776 ; the respiratory tract, 778 ; the circulatory system, 777 ; the genito-urinary tract, 777 ; the skin, 777 ; two most important uses of opium and morphia to relieve pain and produce sleep, 777 ; action of, on the nervous system, 777 ; contra-indications, 778
Opium denarcotisatum, 761, 762
Opium-eating, the effects of, 241
Opium, powdered, preparations and composition of, 761
Orchidaceæ, 969
Organism, the animal, general relations between, and substances affecting it, 9-24 ; circumstances which affect the action of drugs on the, 25-42 ; effects of oxidation on, 51 *et seq.* ; relations of motion and oxidation in, 51 ; excess of temperature injurious to, 82
Orange, bitter, 792
Flower water, 791
Flowers, character, composition, and uses of, 791
Oil of, 791
Peel, bitter, 792
Oil of, 793
Sweet of, 792
Origanum, characters, action, and uses of, 921 ; as a diaphoretic and emmenagogue, 921
Orthospermæ, 847
Osmic acid, action of, on bacteria, 76, 77 ; as a caustic, 301
Osmium, symbol and atomic weight of, 9 ; physiological action of, 24
Ovarian irritation, diagram showing how, probably causes constipation, 336
Oxalates, test for, 521
Oxalate of cerium, 588 ; of iron, 676
Oxalic acid, as a poison, with its antidote, 429 ; nature and use of, 507
Oxidation, relations of motion and, 51 ; of protoplasm, 53 ; action of drugs on, 54 ; methods of ascertaining the effects of drugs on, 57
Oxide of lead, 630
Manganese, black, 678
Red, 624
Mercury, yellow, 623
Oxide of Silver, 609
Zinc, 600
Ox bile, purified, 991
Ox gall, 991 ; inspissated, 991
Oxygen, symbol and atomic weight of, 9 ; broken up by electricity, and forms a new element, ozone, 13 ; its relation to other members of a group, 15 ; necessary for protoplasmic life, 47 ; power of protoplasm over, 54 ; action of hæmoglobin on, 55 ; effects of other gases on, 55 ; of carbonic oxide on, 56 ; of charcoal, 59 ; effects of, on mould fungi, 68 ; on bacteria, 68 ; excess or absence of, causes tetanus, 145 ; effects of the presence or absence of, on the blood, 201-205 ; its preparation, 473 ; properties, physiological action, and uses, 474, 475
Oxyhæmoglobin, 54-57
Oxymel, 456, 504, 998
Scillæ, 456, 504, 959, 998
Ozone, origin and nature of, 13 ; action of, on albumen, 44 ; power of protoplasm in forming, 54 ; action of phosphorus in forming, 54 ; nature and uses of, 475, 476 ; diagram illustrating the formation of, by electricity, 475 ; diagram representing the formation of, by the oxidation of phosphorus, 476

P.

Pachydermata, 993
Paget, Sir James, reference to his lecture on "Elementary Pathology," 38
Pain, origin and nature of, 169 ; where seated, 169 ; how caused, and how relieved, 169 ; action and uses of anodynes in, 169, 170 ; relieved by an effort of the attention, 170 ; action of anæsthetics in relieving, 171 *et seq.* ; and of electricity and cold, 179 ; Mortimer Granville's treatment of, 171 ; action of anæsthetics in alleviating or destroying, 171 *et seq.*
Pale catechu, 866
Pale cinchona bark, 854
Pale rose, composition and uses of, 830
Palladium, symbol and atomic weight of, 9 ; physiological action of, 24
Palmitic acid, action of, on bacteria, 76
Palpitation, of the heart, effect of blood-pressure on, 256, 257 ; the principal drugs which diminish it, 295
Pancreas, action of drugs on the, 357
Pancreatic juice, importance of the, in the process of digestion, 357 ; effects of the secretion of the, 357 ; and of different drugs on the, 357
Pancreatin, utility of, in aiding digestion, 319
Papain, 836
Papaveraceæ, 759
Papayacea, 836

Papayotin, preparation, action, and uses of, 836 ; digestive power of, on muscular fibre and connective tissue, 836
Paper, litmus, blue, 979
Red, 979
Paper, turmeric, 970 ; as a test for alkalis, 971
Papers, 446
Papilionaceæ, 813
Papillon, M., reference to, 22
Paracoto bark, 928
Paraffin, as an emollient, 304
Paraldehyde, a hypnotic, 167 ; a general anæsthetic, 172
Paralysis, of the respiration and heart, danger from anæsthetics, 175 ; treatment necessary when this occurs, 175 ; of the sphincter muscle of the iris of the eye, 187 ; and of the dilator muscle of the same, 189
Parasiticide, balsam of Peru as a, 817
Pardington, Dr., reference to, 136
Paré, Ambrose, reference to, 84
Pareira, as a stimulant diuretic, 380 ; brava, action of, on the bladder, 391
Pareira root, characters and composition of, 758 ; action and uses of, 758
Parsley, as a stimulant diuretic, 379
Passifloræ, 836
Pasteur, divides bacteria into two classes, 68
Paton, reference to, 815
Pavy, reference to, 767*n*.
Pearl barley, 974
Pedaliaceæ, 922
Pellitory root, characters, action, and uses of, 868
Pennyroyal, 920
Pentad elements, 635-681
Pepper, as a carminative, 330
Pepper, black, as a stimulant diuretic, 379 ; characters, composition, and preparations of, 936 ; action and uses of, 937 ; as stomachic, &c., 937
Peppermint camphor, characters, action and uses of, 918 ; as an antiseptic and antineuralgic, 919
Peppermint and oil, as a carminative, 330
Peppermint oil, action of, on bacteria, 77 ; characters, action, and use of, 918 ; as a carminative and stimulant, 918
Pepsin, action of, on fibrine, 60-62 ; action of, as an artificially digestive substance, 319 ; nature of, 990
Pepsinum saccharatum, 990 ; its therapeutics, 990, 991
Peptogens, their action in increasing the gastric juice, 319
Peptones, action of, on the intestines, 333 ; action of the liver on, 349
Perchloride of mercury, 622
Perinæum, a wet sponge applied to the, causes the evacuation of urine, 390, 391
Peristalsis, and mode of increasing, 180 ; some hepatic stimulants which increase, 355
Permanganate of potash, action of, on bacteria, 77 ; as a powerful antiseptic, may be used to wash out abscesses, and as a lotion for ulcers or wounds, 85 ; action of, on muscle, 98, 101 ; characters, action, and uses of, 540, 541
Peroxide of hydrogen, preparation, properties, action, and uses of, 476
Perspiration, antipyrin causes profuse, 744
Peru, balsam of, as a parasiticide, 817
Pessaries, nature and uses of, 427
Petals, cabbage-rose, 830
Red poppy, 778
Red rose, 831
Petrolatum, properties and uses of, 688
Petroleum benzin, or ether, properties and uses of, 688 ; petroleum ointment, 688
Petroleum ether, action of, on bacteria, 75
Pettenkofer, reference to, 354, 363
Pharmaceutical preparations, 441-469 ; general principles which govern, 441, 442 ; the following are the principal abstracts, 443 ; vinegars, 443 ; alkaloids, 443 ; waters, 444 ; cataplasms or poultices, 445 ; cerates, 445 ; papers, 446 ; collodions, 446 ; confections, electuaries, or conserves, 446 ; decoctions, 446 ; elixirs, 447 ; plasters, 447 ; injections, enemas, or clysters, 448 ; essences, 448 ; extracts, 448-453 ; fluid or liquid extracts, 449 ; fresh or green extracts, 451 ; glycerines, 452 ; infusions, 452 ; hypodermic injection, 453 ; liniments or embrocations, 453, 454 ; solutions, 455 ; masses, 455 ; honeys, 455 ; mixtures, 456 ; mucilages, 456 ; oils, fixed and volatile, 457 ; oleates, 458 ; oleoresins, 458 ; pills, 459 ; powders, 460 ; resins, 460 ; spirits, 461 ; suppositories, 461 ; juices, 462 ; syrups, 462 ; tinctures, 463-466 ; triturations, 466 ; ointments, 467 ; vapours, inhalations, 468 ; wines, 469
Pharmacology, definition of, 1 ; one of the most important subdivisions of materia medica, 1 ; rapid advances of, of late years, 1 ; difficulty students find in dealing with, 1 ; the great object of, 18 ; the connection between chemical constitution and physiological action the most important one in, 23 ; importance of comparative, 37, 38 ; inhibition, and the action of drugs on inhibitory centres play a very important part in, 137-141
Pharmacy, definition of, 1, 441
Pharyngeal irritation the probable origin of the so-called stomach cough, 213
Pharynx, structure and functions of, 213 ; cough caused by irritation of the, 213 ; application of drugs to the, 424 ; as washes, 424 ; as caustics, 424
Phenol. *See* Carbolic acid.

Phenyl-alcohol. *See* Carbolic acid
Phosphates, test for, 521
Phosphate of soda, as a cholagogue purgative, 355 ; nature of, 566 ; of sodium, as a saline purgative, 340 ; of lime, 583 ; of iron, 677
Phosphides, test for, 521
Phosphide of zinc, 603
Phosphoric acid, physiological action of, 24 ; as a poison, with its antidotes, 429 ; properties, &c., 505 ; dilute ditto, 505
Phosphorus, symbol and atomic weight of, 10 ; occurs in two forms, red and yellow, 13 ; in combination sometimes pentad and sometimes triad, 13 ; its relation to other members of a group, 15 ; secondary effects of, as an irritant poison, on the system, 348 ; destroys the glycogenic function of the liver, 352 ; has a special action on tissue change, 364 ; in poisoning by, action of, on the urine, 364 ; used in nervous debility, 365 ; as a poison, with its antidotes, 433 ; preparation and characters of, 637 ; action of, 637 ; on the liver and bones, 638 ; on the lower jaw, 638 ; in poisonous doses, 638 ; produces fatty degeneration of the liver, stomach, and kidneys, 639 ; treatment in cases of poisoning by, 639 ; cause of the fatty degeneration, 639 ; action of compounds containing, 639 ; uses of, 640
Phthisis, caused by the bacillus tuberculosis, 81 ; when accompanied by a copious secretion of mucus, a combination of morphine and atropine useful in, 215 ; the atropine beneficial also in lessening sweating in, 215 ; alkalies useful in diminishing the moist *râles* heard in the lungs in, 217 ; tartar emetic ointment and croton-oil liniment sometimes useful in, 302 ; on the night sweats of, 388 ; diagram illustrating the action of antihydrotics in diminishing sweating in, 388 ; probable mode of action of arsenic in, 645 ; how the disease originates and increases, 645
Phylolaccin, as a hepatic stimulant, 353
Physiological action, relation between atomic weight and, 21 ; between spectroscopic characters and, 21 ; between isomorphism and, 23 ; Blake's division of the elements into nine groups, according to their, 23
Physiological reactions, 20, 21 ; divided into groups, 20
Physostigma, lethal dose of, 28 ; action of, on muscle, 107 *et seq.* ; effects of a solution of, applied locally to the nerve trunk, 125 ; action of, on the motor centres of the brain, 156 ; as a myotic, 186 ; on the respiratory centre, 205, 210 ; on the blood-pressure, 244 ; chiefly affects the heart, 255 ; action of, on the vagus, 256 ; on the frog's heart, 265 ; on the ganglia, 271, 272 ; on the vagus-ends in the heart, 275 ; on the cardiac muscle, 276 ; action of, on the secretory and sympathetic nerves, 312, 313 ; as a sialagogue, 312, 313 ; as an antisialic, 316 ; the paralysing action of atropine counteracted by, 317 ; as a hepatic stimulant, 353 ; as a poison, with its antidotes, 432 ; antagonism of, to atropine, 433-437 ; antagonistic action of, 435-437 ; nature, physiological action, and therapeutics of, 819-822. *See* also Physostigmine
Physostigminæ salicylas, 444
Physostigmine, salicylate of, characters of, 818 ; action of, on the muscular fibres and nerve centres, 819 ; general action on the muscles, spinal cord, medulla, and motor and sensory nerves, 819 ; on the brain, eye, respiration, and circulation, 820 ; on muscle, stomach, and intestines, 821 ; on the spleen, bladder and uterus, 821 ; on the secretions and secreting cells, 821 ; uses of, 822 ; treatment of poisoning by, 822
Phytolacca berry, 924
  Root, characters, and action of, 924 ; as an emetic, narcotic, and alterative, 924
Picric acid, action of, on bacteria, 73, 77
Picrotoxin, effect of temperature on the action of, 35 ; action of, on oxidation, 55 ; powerful convulsant action of, 158, 159 ; action of, on the accelerating centre, 274 ; as an antihydrotic, 387 ; as a poison, with its antidotes, 433 ; antagonism of, to chloral, 433-437 ; characters of, 758 ; action of, on the medulla, motor centres, spinal cord, and temperature, 758, 759 ; uses of, 759
Picrotoxinum, 444
Pills, 459
Pilocarpine, effects of cold on the action of, 34 ; as a myotic, 186 ; action of, on the mucous membrane, 218 ; as a depressant expectorant, 219 ; effect of, on the frog's heart, 266 ; on the cardiac muscle, 276 ; as a sialagogue, 312 ; action of, on the peripheral ends of the sweat nerves, 385 ; as an antihydrotic, 387 ; as a poison, with its antidote, 433 ; antagonism of, to atropine, 433-437
Pilocarpinæ hydrochloras, 444
Pilocarpus (jaborandi), characters of, 804
Pilula aloes, 459, 882, 961
Pilula aloes barbadensis, 459, 851, 882, 962
  et asafœtidæ, 459, 847, 882, 960, 961
  et ferri, 459, 668, 961, 962
  et mastiches, 459, 811, 831, 961
  et myrrhæ, 459, 813, 960, 961, 972

Pilula aloes Socotrinæ, 459, 882, 926, 960
Antimonii compositæ, 459, 616, 621, 653, 655, 801
Asafœtidæ, 459, 847, 882
Composita, 459, 813, 847, 848, 976
Cambogiæ composita, 459, 799, 882, 962
Catharticæ compositæ, 459, 616, 621, 799, 842, 897, 961
Colocynthidis composita, 459, 537, 837, 842, 896, 962
et hyoscyami, 459, 537, 837, 842, 896, 962
Conii composita, 459, 845, 864, 976
Ferri carbonatis, 459, 668, 976
Iodidi, 459, 489, 676, 614, 976
Compositæ, 459, 813
Galbani compositæ, 459, 813, 847, 848
Hydrargyri, 459, 616, 814
Subchloridi composita, 459, 616, 621, 653, 655, 801, 934
Ipecacuanhæ cum scillâ, 459, 537, 761, 864, 959, 976
Nitro-glycerini, 712
Opii, 459, 761, 882
Phosphori, 459, 637
Plumbi cum opio, 459, 632, 761
Quiniæ, 459, 857
Composita, 459, 813, 882, 918, 923, 924, 960, 961, 976, 1005
Rhei, 459, 882, 924
Saponis composita, 459, 761, 882
Scammonii composita, 459, 896, 988
Scillæ composita, 459, 882, 959, 970, 976
Pimenta, 838
Oil of, 838
Pimento, characters and composition of, 838
Oil of, 838
Pine bath, 414
Pinkroot. *See* Spigelia
Piperaceæ, 935
Piperine, 444; character, action, and uses of, 936, 937
Pisces, 996
Pitch, Burgundy, 953
Canada, 953
Hemlock, 953
Pitres, reference to, 155*n.*, 156*n.*
Piturine, as a mydriatic, 186
Plasters, 447
Plasters, utility of, in chest complaints and in bronchitis, 220
Platinum, symbol and atomic weight of, 10; physiological action of, 24; action of, on muscle, 104; causes powerful contraction of the vessels, 240; properties, action and uses of foil, 680; of solution of perchloride of, 680; of platinum black, 681
Pleurisy, tartar emetic ointment and croton-oil liniment sometimes useful in, 302
Pleurisy root. *See* Asclepias
Plumbi acetas, 681
Iodidum, 489, 633
Pneumonia, contagious, micrococci present in, 81
Podophylli resina, 756
Podophyllin, as a drastic purgative, 340; and as a cholagogue, 340; as a hepatic stimulant, 393. *See* also Podophyllum root, and Resin of podophyllum
Podophyllum root, characters, properties, and composition of, 754; resin of, nature, properties, and uses of, 754
Poisoning, what is necessary to be done in all cases of, before administering the antidote, 428; by acids, 498; chronic, by copper, 597; by phosphorus, and its treatment, 638, 639; by arsenic, and its treatment, 641; chronic, by arsenic, 642; by antimony, 649; chronic alcoholic, 696; treatment of, by chloral, 717; by opium, 769; by physostigmine, 822; by strychnine, and its treatment, 886; by belladonna or atropine, 904; by digitalis, and its treatment, 916; by croton oil, and its treatment, 933; by colchicum, 969; treatment of, by cantharides, 1002
Poisonous gases, with their antidotes, 428
Poisons, effect of heat on the power of, 33-36; different effects of, on different animals, 32-36; effects of various, on medusæ, 90, 91; list of muscular, 103-107; effects of certain, on the colour of the blood, 205; on the muscular fibre of the ventricle of the heart, 265; on the heart itself, 267; of two classes of, on the vagus, 269-272; list of cardiac, 276; most suitable emetics for removing, from the stomach, 327; action of various irritant, on the general system, 345-347; peculiarities in the action of different irritant, 347; secondary effects of irritant poisoning, 348; list of the more common, with their antidotes, 428-433; carbonic acid as a, 510; has three stages—dyspnœa, convulsions, paralysis, 511; copper as a, 597
Poke berry. *See* Phytolacca berry
Root. *See* phytolacca Root
Polygalaceæ, 784
Polygonaceæ, 923
Pomeæ, 829
Pomegranate, as a vermicide, 357; characters, composition, and use as an anthelmintic, 841
Root bark, 841
Poppy capsules, character of, 760; composition, action, and uses of, 760
Poppy petals, red, characters, composition, and use of, 778

Potash, physiological action of, 24 ; action of, on protoplasm, 46 ; permanganate of, effect of, on infusoria, 51 ; on bacteria, 73 ; on muscle, 99 ; salts of, effects of, on muscular contraction, 106 ; action of, on the ends of the vaso-motor nerves, 243 ; action of, combined with other ingredients, on the frog's heart, 265 ; as a caustic, 301 ; difference between the action of, and soda, on the intestines, 334 ; used in gout, 365
Potash salts, preparation, nature, and uses of the following—
Potassium acetate, 530, 535
Acid tartrate, 531, 536
Bicarbonate, 530, 534
Bichromate of, 542
Bitartrate of, 536
Bromide, 531, 546-548
Carbonate, 530, 533
Caustic potash, 530, 533
Chlorate, 530, 538
Citrate, 530, 538
Cyanide, 531
Ferrocyanide, 531, 542
Hypophosphite, 530
Iodide, 531, 543
Liquor potassæ, 530, 533
Potassii, 530
Nitrate, 531, 537
Nitrate of potash, 537
Permanganate, 531, 540
Potassa with lime, 534
Solution of potash, 533
Sulphate, 531, 537
Sulphite, 530
Sulphurata, 531, 541
Tartrate, 531, 536
Tartrate of potash, 536
Potash salts, general sources and reactions, of, 529, 530 ; action of, on the general system, 531-533
Potassæ cum calce, 579
Permanganas, 534
Tartras, 536
Potassæ, liquor, singular effect of a single drop of, 434
Potassic picrate, effects of, in destroying bacteria, 71
Potassii iodidum, 489
Potassium, symbol and atomic weight of, 10 ; its relation to other members of a group, 15 ; and specially to lithium, 15 ; action of, on muscles, 104, 106, 110, 117, 118 ; on the vaso-motor centre, 274
Potassium acetate, action of, on bacteria, 76 ; as a remote antacid, 321 ; as a refrigerant diuretic, 379
Potassium bicarbonate, as a direct antacid, 321
Potassium bichromate, action of, on bacteria, 76
Potassium bitartrate, as a remote antacid, 321 ; as a saline purgative, 340 ; a hydragogue, 340 ; and a refrigerant diuretic, 379
Potassium bromide, action of, on bacteria, 75 ; on the nervous system, 171, 172
Potassium carbonate, as a direct antacid, 321
Chlorate, action of, on bacteria, 76 ; as a refrigerant diuretic, 379
Potassium chloride, causes great contraction of the vessels, 240 ; neutralises the action of veratrine in certain cases, 266
Potassium chromate, action of, on bacteria, 76
Potassium citrate, as a remote antacid, 321 ; and refrigerant diuretic, 379
Potassium iodide, action of, on bacteria, 75 ; as a depressant expectorant, 219
Potassium nitrate, as a refrigerant diuretic, 379
Potassium permanganate, action of, on bacteria, 76
Potassium salts, action of, on the cardiac muscle, 276 ; on the vaso-motor nerves, 276 ; on the capillaries, 277 ; as refrigerant diuretics, 379 ; antagonism of, to barium, 433-437
Potassium sulphate, as a hepatic stimulant, 353
Potassium tartrate, as a remote antacid, 321 ; as a saline purgative, 340 ; and sodium, as ditto, 340
Potato and potato water, experiments with, on oxygen, 54, 55
Poultice, action of a warm, on the mucous membrane, 216 ; and on the chest, 220 ; use of a warm, in inflammation, 298, 299 ; as an emollient, 304 ; uses of, and how to apply different kinds of, 412 ; a linseed, 783
Poultices, or cataplasms, 445
Powders, 460
Power, Mr., reference to, 377, 912
Prayer beads, 817
Precipitated sulphur, its preparation, &c., 480
Pregnancy, best mode of treating the vomiting of, 328
Preventive medicine, growing importance of, 2 ; chiefly owing to recent increase in knowledge of microbes and their action in causing disease, 2
Prevost on poisoning by mercury, 19
Preyer, reference to, 124, 434
Prickly ash, 804
Prinos (black alder), characters and action of, as an astringent, 810
Prolapsus of the uterus, emetics to be used with caution in persons suffering from, 327
Prophylactic, quinine as a, 863
Prophylaxis. *See* Preventive medicine
Protoplasm, action of drugs on, 45-49 ; method of experimenting on amœbæ and

leucocytes, 45-47 ; relations of motion and oxidation to, 51 ; oxidation of, 63 ; oxygen-carrying power of, 54 ; potash salts poisons or destroys, 531
Protoplasmic poison, anæsthetics act as a, 173 ; and potash salts, 531
Prune, composition and use of, 835 ; Virginian prune, or wild cherry, 835
Prunes, as a laxative, 339
Prussic acid, 512
Ptomaïnes, alkaloids formed by putrefaction, 81 ; action of, on muscle, 105 ; how formed, 351
Ptyalin, 60, 61
Puerperal fever, micrococci present in, 81 ; singular cause of an epidemic, 84
Pulmonary sedatives, nature, number, and uses of, 211-215 ; divided into three classes, 211
Pulsatilla, characters and composition of, 752 ; action of the oil of, as a vesicant, 753 ; pure anemonin has a depressant action on the circulation, respiration, and spinal cord, 753 ; causing feeble pulse, slow respiration, paralysis, dyspnœa, and death, 753 ; uses of, as a diaphoretic and emmenagogue, 753
Pulse-rate, relation of, and arterioles, to blood-pressure, 230 ; diagrams of a pulse curve, 231 ; effect of the arterioles on pulse curves, 234 ; effect of drugs on the, 253 ; of irritant poisons on, 347 ; of arsenic, 642 ; of nitrite of amyl, 709, 711 ; of chloral hydrate, 716 ; of purified chloroform, 722 ; of carbolic acid, 736 ; of creosote, 739 ; of staphisagria, 752 ; of anemonin, 753 ; of hydrochlorate of apomorphine, 765 ; of erythroxylon, 787 ; of caffeine, 798 ; of Jamaica dogwood, 827 ; of oil of valerian, 867 ; of gelsemium, 891 ; of tobacco, 907 ; of camphor, 930 ; of Indian hemp or American cannabis, 947 ; of squill, 959 ; of hellebore, 963 ; of veratrine, 966
Pulvis amygdalæ compositus, 460, 828, 834, 976
Antimonialis, 460, 583, 653, 656
Aromaticus, 460, 925, 927, 970, 971
Catechu compositus, 460, 785, 816, 866, 925, 927
Cinnamomi compositus, 460, 927, 970, 971
Cretæ aromaticus, 460, 581, 925, 927, 971, 972, 976
Aromaticus cum opio, 460, 581, 761
Compositus, 460, 581, 976
Effervescens compositus, 460
Elaterii compositus, 460, 843
Glycyrrhizæ compositus, 460, 480, 814, 824, 976
Ipecacuhana compositus, 460, 536, 761, 864
Et opii, 460, 761, 864
Pulvis Jalapæ compositus, 460, 537, 897, 970
Kino compositus, 460, 761, 816, 927
Morphinæ compositus, 460, 764, 765
Opii compositus, 460, 761, 815, 851, 936, 970
Rhei, 923
Rhei compositus, 460, 923, 924, 970, 1005
Scammonii compositus, 460, 896, 897, 970
Tragacanthæ compositus, 460, 815, 828, 974, 976
Pumpkin seed, composition and uses of, as an anthelmintic, 844
Pupil of the eye, structure of, and action of drugs on the, 184-192
Purgatives, aid the action of antiperiodics, and sometimes cure ague without them, 87 ; nature of, 339 ; divided into laxatives (list of the chief), 339 ; simple, 339 ; drastic, 339 ; saline, 340 ; hydragogues, 340 ; and cholagogues, 340 ; action of, 340, 341 ; Dr. Hay's researches into the action of, 342-344 ; the various uses of, 344, 345 ; to remove fœcal matters from the intestinal tube, 344 ; to remove liquid from the body, 344 ; to lower the temperature in fever, 345 ; to lower the blood-pressure, 345 : they act as hepatic depressants, 356 ; as antipyretics, 367 ; as anaphrodisiacs, 396 ; as indirect emmenagogues, 398 ; resin of podophyllum as a, 755 ; gamboge as a, 799 ; buckthorn as a, 809 ; senna as a, 824 ; tamarind as a, 825 ; olive oil as, 883 ; manna as, 884 ; rhubarb as, 924 ; castor oil as, 934 ; oil of turpentine as, 951 ; aloes as, 962 ; treacle as, 976 ; oatmeal as, 977
Putrefaction, alkaloids formed by, 81 ; antiseptics arrest the, 84, 85
Pyæmia, micrococci present in, 81
Pye, Mr., references to, 254, 377
Pye-Smith, Dr., reference to, 332*n.*, 903
Pyrethrum, 868
Pyrethrum, as a sialagogue, 312, 313
Pyrocatechin, characters, action, and uses of, 740
Pyrophosphate of iron, 677
Pyrophosphate of soda, 558 ; action of, on the nerve centres of the spinal cord, &c., 639
Pyroxylin, 789
Pyroxylinum, 789

Q.

Quassia, as a vermicide, 357
Quassia and quassia wood, properties and composition of, 808 ; action and uses of, 808 ; is simply a pure bitter stomachic, 808

Quebracho, as a depressant expectorant, 219
Quebracho bark, white, characters, action, and uses of, 892
Queen's root. *See* Stillingia
Quercus alba, the bark of, 941 ; characters, action, and use of, as a local astringent, 941
Quillaia (saponin), characters, composition, action, and uses of, 832, 833 ; action, of, as a local irritant, 832 ; produces local paralysis and anæsthesia, 833 ; action of, on the voluntary muscles, the intestine, and the heart, 833 ; on digitalis, and on the nerve centres, 833
Quince seed, characters and use of, 829
Quinia, sulphate of, 857
Quininæ sulphas, 444, 855
Quinicine, constitution of, 744
Quinidinæ sulphas, 444, 859
Quinidine, sulphate of, 858
Quinina, 444, 859
Quininæ sulphas, 859
  Bisulphas, 859
  Hydrobromas, 859
  Valerianas, 859, 867
Quinine, example of the empirical use of, 1 ; utility of, in ague, 1 ; action of, on protoplasmic movements, 47-49 ; on the mesentery of a frog, 48 ; on infusoria, 51 ; effects of, on oxidation, 55, 58 ; on bacteria, 71, 76, 77 ; as a disinfectant, 86 ; as an antiperiodic almost a specific in intermittent fevers, periodic headaches, neuralgias, &c., 87 ; action of, on ascidians, 93 ; on annulosa, 94 ; on muscle, 104 *et seq.* ; on the spinal cord of a frog, 136 ; on the ear, 194 ; on taste, 195 ; on the respiratory centre, 205 ; on the frog's heart, 264 ; on the motor ganglia, 275 ; on the capillaries, 277 ; on the secreting cells of a gland, 310 ; arrests secretion of saliva, 316 ; lessens tissue change, 364 ; as an antihydrotic, 387 ; value of, in the high temperature of the night sweats of phthisis, 390 ; as a direct emmenagogue, 398 ; one of the chief ecbolics, 399 ; as a poison, with its antidotes, 431 ; antagonism of, to atropine, 433-437
Quinine, characters and action of, 856
  Bisulphate of, 857
  Hydrobromate of, 858
  Hydrochlorate of, 858
  Sulphate of, 857
  Valerianate of, 858
  Physiological action of—general action, 859, 860 ; special action—on the alimentary canal, 860 ; on the stomach, 860 ; on the blood, 861 ; on the circulation, 861 ; on the heart and respiration, 861 ; on tissue change, and on the nervous system, 861 ; on the spinal cord, 862 ; on the muscles and uterus, 862 ; uses—as an antiseptic, a tonic, and an antiperiodic, 862 ; as an antipyretic and a prophylactic, 863

R.

Rabbits, experiments with drugs on, 40-42 ; two kinds of muscles in, red and white, 96 ; number of stimuli necessary to cause tetanus in the latter, 102 ; Stenson's experiment on the abdominal aorta of, 134 ; the cerebral hemispheres of, more developed than those of the frog, 153 ; effect of the removal of the cerebrum on, 153 ; easiest way of anæsthetising, 177, 178 ; effect of injecting drugs into the jugular veins of, 204 ; effect of the inhalation of tobacco smoke on, 209 ; experiment on the ear of, 237 ; method of maintaining artificial circulation in the ear of, 238 ; action of the heart in, 246, 247 ; difference between dogs and, in this respect, 247 ; the vagus centre in, stimulated through the nasal nerves, 255 ; Zülzer's experiments with, 299 ; experiments with, as to the antagonism of drugs, 435*n*.
Rabuteau, M., references to, 21, 22, 24
Radicals, compound, nature of, 19 ; most of them possess a paralysing power over the motor nerves, 23
Raisins, composition and uses of, 800
Râles, moist, nature and treatment of, 217
Ranke, references to, 145
Ranunculaceæ, 747 *et seq.*
Ranvier, L., references to, 38, 146, 293, 294
Raspberry, characters and use of, 830
Rat paste, as a poison, with its antidote, 433
Rational therapeutics, explanation and example of, 1
Rattle-snake poison, action of, on the red corpuscles of the blood, 49
Rectum, action of aloes on the, 962
Red cinchona, 855
  Bark, 855
Red poppy petals, characters, composition, and use of, 778
Red rose, and red rose petals, 831
Red sandal wood, 816
Red saunders, nature and use of, 816
Refined silver, 606
Refrigerants, nature and uses of, 315 ; tamarind as a, 825
Regnard, reference to, 76
Regurgitation, mitral and tricuspid, nature and cause of, 289 ; value of digitalis and other cardiac tonics in, 289, 290 ; the question of the use of digitalis in aortic regurgitation considered, 291 ; diagram to illustrate the tendency to syncope in aortic, 291

Reichert, reference to, 515
Remedies acting on the surface of the body, 297-307; irritants and counter-irritants, 297-303; subdivided into four classes, 297; rubefacients and their uses in chronic and acute inflammation, 297-301; diagrams illustrative of the action of, 298,299; list of the principal rubefacients, 300; friction one of the simplest, 301; vesicants and their uses, 302; pustulants, 302; and caustics, 303; general uses of caustics, 303; emollients and demulcents, 303; list of the principal demulcents, 304; and emollients, 304; action of demulcents and emollients, 304; their therapeutic uses, 305; astringents, local and remote, and their uses, 305, 306; styptics and their action, 306, 307
Resin, composition and use of, 952
Resin of podophyllum, preparation, characters, and composition of, 754; action of, as a drastic purgative, and a hepatic stimulant, 755; uses of, 755
Resin of scammony, 896
Jalap, 197
Resina Copaibæ, 460
Guiaci, 460
Jalapæ, 460, 897
Podophylli, 460, 755
Scammoniæ, 460, 895, 896
Scammonii, 460, 895, 896
Resins, 460
Resorcin, characters of, 739; action of, as an antiseptic, 739; on frogs, warm-blooded animals, and man, 739; uses of, 739; utility of, as an antipyretic, 739
Respiration, action of drugs on, 197-220; respiratory stimulants and depressants, 197; mechanism of, in some of the lower organisms, 197, 198; diagrams illustrative of this, 198; in the higher organisms, 199; muscles of, 199, 200; centres of, 199-202; certain conditions of, called apnœa, dyspnœa, and convulsions, 202; action of certain conditions of the blood on, 202, 203; result of the presence or absence of air on external and internal, 203-205; action of drugs on the centre of, 205-209; diagram showing position of the centre of, and the afferent nerves which influence it, 207; method of testing the movements of, 208; action of drugs on the nerves of, 209; of irritant poisons on, 347; action of hydrocyanic acid on, 514; of mercury, 516; of strong solution of ammonia, 569; of gold, 680; purified chloroform, 722-724; of creasote, 739; of salicylic acid, 741; of antipyrin, 744; of aconitia, 750; of staphisagria, or stavesacre, 752; of anemonin, 753; of erythroxylon, 787; of caffeine, 798; of pilocarpine, 506; of physostigmine, 820; of quinine, 861; of strychnine, 887; of solanine, 898; of belladonna or atropine, 902; of digitalin, 910; of thymol, 920; of monobromated camphor, 930; of Indian hemp or American cannabis, 947; of oil of turpentine, 950; of veratrine, 966; of extract of ergot, 982
Respiratory centre, nature and functions of, 199-202; action of drugs on the, 205, 206; diagram showing the position of the, and the afferent nerves which influence it, 207-209; action of drugs on the respiratory nerves, 209; of sternutatories, 210; of pulmonary sedatives, 211-215; drugs which increase the activity of the, 219; connection of the, with the sweat glands, 389; action of gold on the, 680; of alcohol, 695; of carbolic acid, 736; of quillaia (saponin), 833; of musk, 988
Respiratory passages, in disease of the, warmth usually applied by means of inhalation, 305; action of gold on the, 680
Respiratory tract, action of opium on the, 776
Rhamnaceæ, 809
Rhamni succus, 462
Rhamnus, as a purgative, 339
Rhatany root, composition, action, and use of, chiefly as an astringent, 785
Rheochord, Du Bois-Reymond's, 96
Rheum, 924
Rheumatic gout, remarkable instance of accidental cure in, 298
Rhodium, symbol and atomic weight of, 10
Rhubarb, as a sialagogue, 312, 313; as a purgative, 339; and as a cholagogue, 340; as a hepatic stimulant, 353; as a cholagogue purgative, 353
Rhubarb, 922
Root, characters and composition of, 923; action and uses of, 924; as a tonic, astringent, and purgative, 924
Rhus aromatica, in incontinence of urine, 812
Rhus glabra (sumach), nature and uses of, as an astringent, 811
Rhus toxicodendron (poison ivy), as a vesicant, 301; characters, action, and uses of, 812
Ribbert, reference to, 371 and *n*.
Richardson, B. W., reference to, 636*n*
Richet, references to, 102
Rigollot's mustard leaves, usefulness of, 780, 781
Ringer, Dr. S., references to, 34, 187, 264, 266, 296, 434, 496, 601, 618, 643, 648, 752, 888, 911
Roberts, reference to, 319*n*.
Rochelle salt, as a hepatic stimulant, 353; nature and uses of, 554
Rodentia, 987
Röhrig, reference to, 352
Romanes, reference to his researches on the medusæ, 88, 89, 91

Root, Aconite, 747
Arnica, 873
Bark, cotton, 788
Bark, pomegranate, 841
Belladonna, 900
Black snake-, 753
Blood, 778
Calumba, 756
Colchicum, 967
Culver's, 916
Dandelion, 872
Gentian, 893
Green hellebore, 963
Hemidesmus, 892
Horse-radish, 782
Liquorice, 813
Pareira, 758
Pellitory, 868
Phytolacca, 924
Pink-, 891
Pleurisy, 892
Podophyllum, 754
Poke, 924
Queen's, 933
Rhatany, 785
Rhubarb, 923
Sassafras, 930
Scammony, 895
Senega, 784
Serpentary, 932
Sumbul, 851
Valerian, 866
Rosaceæ, 829
Rose, dog-, fruit of the, 831
Oil of, characters, &c., of, 830
Pale, 830
Red, 831
Petals, 831
Roseæ, 830
Roséine, 743
Rosemary, characters of, 917
Oil of, characters, actions and use of, 917; as a stimulant and carminative, 917
Rosenberger, on bacteria, 70
Rosenthal, Professor J., references to, 104, 144, 207, 910
Rossbach, references to, 45, 50, 212, 216, 217, 217*n*., 365, 387, 434, 532, 789, 942; on bacteria, 70
Rovighi, reference to, 159*n*.
Roy's tonometer, 228
Rubefacients, and their action in chronic and acute inflammation, 297-300; list of the principal, 300; friction one of the simplest, 301; acids as, 496; oil of rue as a, 802; oil of myrtle as a, 839; oil of cajeput, 839; camphor as, 929
Rubiaceæ, 854
Rubidium, symbol and atomic weight of, 10; physiological action of, 23; action of, on the muscles, 110, 117
Rubus, characters and uses of, 830
Rue, as a direct emmenagogue, 398
Rue, oil of, nature and use of, 802; is a rubefacient, antispasmodic, and an emmenagogue, 802
Ruminantia, 987
Russell and Lapraik, references to, 22
Russian bath, account of the so-called, 414
Rutaceæ, 802
Ruteæ, 802
Ruthenium, symbol and atomic weight of, 10
Rutherford, reference to, 352, 356, 756
Rye, ergot of, 979

S.

Saccharated carbonate of iron, 668
Ferrous carbonate of iron, 669
Iodide of, 676
Saccharatum, pepsinum, 990
Saccharine substances are stimulating expectorants, 219
Saccharine solution of lime, as a direct antacid, 321
Sachs, reference to, 124
Saffron, 971; as a colouring agent and carminative, 972
Sage. *See* Salvia
St. Bartholomew's Hospital Reports, reference to, 639*n*.
Salad oil (French), action of, on bacteria, 75
Salicaceæ, 938
Salicin, character, action, and uses of, 938; as an antipyretic, 939
Salicinum, 444
Salicylates, test for, 521
Salicylate of lithium, 563
Salicylate of soda, action of, in producing visions, 193; on the ear, 194; nature of, 559
Salicylates, antiperiodics, 87
Salicylic acid, action of, on enzymes, 63; bacteria, 73, 76, 77; an antiperiodic, 87; on the vaso-motor centre, 274; on the cardiac muscle, 276; on the pancreatic juice, 357; characters and tests of, 740; action of, in preventing the development of bacteria, 741; on the temperature, pulse rate, blood-pressure, and respiration, and the ears, 741; on the circulation, 741; how excreted, 741; uses of, 741
Saline solutions, effects of, on infusoria, 50
Saliva, cause of, and mode of secretion, 309-312; diagram representing the general relation of nerves to the secreting cells and vessels of a gland, 310; diagram to show the nerves by which the secretion may be excited, 311; various causes which stimulate the secretion of, 312; action of sialagogues on the secre-

tion of, 312, 313 ; excretion by the, 313 ; diagram of the gastro-salivary circulation, 314 ; uses of, 315 ; action of erythroxylon on the secretion of, 787 ; of caffeine on ditto, 798 ; of Jamaica dogwood, 827 ; of pellitory root, 868
Salivary centres, action of carbolic acid on the, 736
Salivary glands, action of cantharides on the, 1001
Salivation, produced by mercury, 612 ; what it is in part due to, 616 ; action of gold in producing, 680 ; of curare, 889
Salix, characters, composition, and use of, 938
Salt, effects of common, on protoplasmic movement, 46 ; on bacteria, 75 ; as a local emetic, 325 ; as a refrigerant diuretic, 379 ; effects of, in large quantities, on the general system, 526
Salts, inorganic, isomorphic, ferrous, manganous, ferric, physiological action of, 23 ; of barium, action of, on muscles, 106 ; of zinc and copper, action of, on the respiratory centre, 205 ; results of experiments with several metallic, 240 ; of calcium and distilled water, prolong the beating of the frog's heart, 264, 265
Salts of the cinchona alkaloids, 859
Salts of the heavier metals as astringents, 305
Salvia, characters, action, and uses of, 922 ; as a tonic, carminative, and an astringent, 922
Sal volatile, as a cardiac stimulant, 286
Sal volatile, 571
Samarium, symbol and atomic weight of, 10
Sandal wood, red, 816
Sanguinaria (bloodroot), action of, on the vaso-motor centre, 274 ; as an alterative, 362 ; characters and composition of, 778 ; action of, on the intestinal canal, and the medullary centres, 778 ; on the brain and spinal cord, 779 ; chiefly used as a stimulant expectorant, 779
Sanitas, nature and use of, 952
Santal, oil of, characters, action, and use of, 932
Santalacea, 932
Santini, reference to, 159*n*.
Santonica, as a vermicide, 357 ; as a stimulant diuretic, 380 ; characters and composition of, 869
Santonin, as a vermicide, 357 ; characters and preparation of, 870 ; action of, on the cerebrum and medulla of the frog, 870 ; effects of large doses on man, 870 ; action of, on the vision and on the urine, 870 ; used only as a vermicide, 870
Santoninate of soda, 559
Santoninum, 444, 869
Sapindaceæ, 786
Saponin, nature, action, and uses of, 832
Saponin, action of, on the respiratory centre, 205 ; on the nose, 210 ; as a stimulating expectorant, 219 ; action of, on the vagus-ends of the heart, 275 ; on the inhibitory ganglia, 275 ; on the cardiac muscle, 276 ; on the heart, 295 ; antagonistic action of, 436, 437
Sapotaceæ, 879
Sarsaparilla, as an alterative, 362 ; as a stimulant diuretic, 380 ; nature and action of, 957 ; as a diuretic, tonic, and alterative, 957
Sassafras, characters of, 930
Pith, characters and uses of, 931 ; as a demulcent, 931
Root, characters and composition of, 930
Oil of, 930 ; action and use of, as a diaphoretic, 930
Sassy bark, action of, on the nose, 210 ; composition, action, and use of, 829
Savine, as a stimulant diuretic, 379 ; as a direct emmenagogue, 398 ; a chief ecbolic, 399 ; as a poison, with its antidotes, 433
Savine, 955
Tops, 955
Saunders, red, nature and use of, 816
Scammony, as a drastic purgative, 340 ; as a vermifuge, 357
Scammony, characters, &c., of, 895
Resin of, 896 ; action and use of, as a drastic purgative and a vermifuge, 896
Root, 895
Scandium, symbol and atomic weight of, 10
Scharrenbroich, reference to, 58
Schiff, Professor, references to, 201, 255, 319, 349, 643
Schizomycetes, 67. *See* Bacteria
Schlesinger, references to, 82
Schmidt-Mülheim, reference to, 349
Schmiedeberg, Professor, references to, 42, 81, 117, 252*n*., 270, 434, 910, 911
Schönlein, reference to, 109*n*.
Schroeder, Von, reference to, 775*n*
Schroff, Von, references to, 124, 128, 193*n*.
Schroff (junr.), reference to, 779
Schulte, reference to, 58
Schultzen, Otto, reference to, 767*n*.
Schweigger-Seidel, reference to, 373*n*.
Scillain, action of, on the cardiac muscle, 276 ; as a cardiac tonic, 289
Scoparin, 815
Scurvy, due to imperfect nutrition, 361 ; is supposed to be due to a deficiency of potash in the blood, 361 ; is removed by fresh vegetables or lime juice, 361
Scutellaria, characters and uses of, 922 ; has been used as a nervine tonic, 922
Scybala, diagram illustrating diarrhœa depending on the presence of, in the intestine, 338

Sea-bathing, 413
Secretion, from the bronchial tubes, 214 ; from the air passages, 215 ; nature of the, from the mucous membrane, 215 ; action of drugs on the, 216 ; action of belladonna or atropine on, 902
Secretions, action of opium on the, 771 ; physostigmine, 821
Sedatives, nature and uses of, 127 ; pulmonary, 211-215 ; cardiac, 295, 296 ; vascular, 296 ; gastric, 327 ; vesical, 391 ; urinary, 392
Seed, American worm-, 925
Oil, cotton, 788
Oil of flax, 783
Pumpkin, 844
Quince, 829
Seeds, Colchicum, 967
Jequirity, 817
Stramonium, 906
Seegen, Professor, reference to, 349*n.*, 474
Selenic acid, physiological action of, 24
Selenium, symbol and atomic weight of, 10
Senega. *See* Saponin
Senega, as a general emetic, 325
Senega root, composition, preparation, action, and use of, 784, 785 ; is a stimulating expectorant, diuretic and diaphoretic, 785
Senna, characters, composition, action, and uses of, 823
Alexandrian, 823
Tinnevelly, 823
Sensation, anæsthetics destroy, 171
Septic poisoning, and bacteria, 70 ; effects of, and modes in which it may be produced, 84, 85
Series, arrangement of the animal kingdom and of the elements in, 16 ; Mendelejeff and Meyer the perfecters of this system of classification, 16 ; Mendelejeff's classification in, 17 ; difference in the even and uneven series, 18 ; irregularities in the system, 18, 19
Serpentaria, 932
Serpentary root, characters, action, and uses of, 932 ; as a tonic, diaphoretic, and diuretic, 932
Serum, and blood, action of, on the frog's heart, 266, 267
Sesamum, oil of, characters and action of, 922
Setschnow's centres, 135 ; experiment on a frog, 135, 136
Severini, reference to, 241
Shenstone, Mr., reference to, 888
Sherry, characters and uses of, 702 ; wine, 800
Shorthouse, Dr., reference to, 183*n.*
Sialagogues, nature and action of, 309-311 ; diagrams illustrative of the nerves and glands acted on by, 310, 311 ; divided into two classes, topical and remote, 312, 313
Sialics, and anti-, nature and action of, 316
Silicon, symbol and atomic weight of, 10 ; its relation to other members of a group, 15
Silver, symbol and atomic weight of, 10 ; physiological action of, 23
Silver, characters, action, and uses of—
Cyanide of, 609
Iodide of, 610
Nitrate of, 607
Diluted, 607
Moulded, 607
Oxide of, 609
Refined, 606
Silver nitrate, as a caustic, 301 ; as an astringent, 305 ; as a local sedative, 327
Simarubaceæ, 808
Simpson, Sir J. Y., his mode of administering chloroform, 177 ; and discovery of the use of, as an anæsthetic, 179
Sipping, the action of, a powerful stimulant to the brain, 162 ; increases the secretion of the bile, 356 ; and abolishes the inhibitory action of the vagus on the heart, 356 ; the value of Carlsbad water in hepatic disease is probably owing to its being taken in sips, 356
Sitz bath, cold 409 ; hot, 412
Skatol, action of, on bacteria, 76
Skin, action of drugs on the, 383-390 ; as diaphoretics and sudorifics, 383 ; effects of warmth on the, 384 ; excretion by the sweat glands, 385 ; relation between sweat glands and kidneys, 386 ; action of the, in regulating temperature, 386 ; antihydrotics or anhydrotics, 387 ; diagram to illustrate the action of anhydrotics, 388 ; the night sweats of phthisis, 388 ; cause of profuse sweating, 389 ; application of drugs by the, 402 ; three methods of applying drugs to the — (1) by epidermic application, 402-404 ; power of absorption of the, 403, 404 ; by baths, 404 ; the cold bath, 405 ; objects of the cold bath, 405-407 ; the cold pack, 407 ; cold sponging, 408 ; cold douches, 408 ; the sitz bath, 409 ; cold foot bath, 410 ; cold compresses, 410 ; tepid baths, 411 ; warm baths, 411 ; hot baths, 411 ; hot foot bath, 411 ; hot sitz bath, 412 ; poultices, 412 ; medicated baths, 413 ; acid bath, 413 ; alkaline baths, 413 ; sulphurous baths, 413 ; the mustard baths, 413 ; the pine bath, 414 ; vapour baths, 414 ; calomel fumigation, 414 ; air baths, 415 ; the Turkish bath, 415 ; by friction, 415 ; by inunction, 417 ; (2) by endermic application, 417 ; (3) by hypodermic application, 418 ; diagram of syringe for hypodermic injection, 418 ; objections to hypodermic injections, 419 ; action of hyodrocyanic acid on the, 513 ; of alkalis,

523, 524 ; soda as a stimulant to the, 551 ; of dried alum, 586 ; of nitrate of silver, 608 ; of arsenic, 641 ; of antimony, 649 ; of iron salts, 665 ; of alcohol, 692, 696 ; of spirit of ether, 705 ; of purified chloroform, 720 ; of opium, 777 ; of mustard, 781 ; of pilocarpine, 807 ; of chrysarobin, 823 ; of oil of copaiva, 826 ; of Jamaica dogwood, 827 ; of oil of eucalyptus, 840 ; of ipecacuanha, 864 ; of tannic acid, 942 ; of colchicum, 968
Skull-cap. *See* Scutellaria
Sleep, remedies which induce, 164 ; the cerebro-spinal system functionally inactive in, 164 ; certain parts of the nervous system may still remain active, 164 ; the inactivity caused by anæmia, 164 ; state of the arteries of the brain during, 165 ; and in normal, 165 ; the brain anæmic during, 165 ; two things necessary to produce, 165 ; to lessen circulation in the brain, and to lessen its functional activity, 165 ; position may sometimes induce, 165 ; cold to the abdomen prevents, and warmth procures, 166 ; warmth to the stomach in the shape of warm food and drinks, causes, 166 ; efficacy of the wet pack in inducing, 166 ; cold feet prevents, 166 ; and cooling the surface of the body sometimes induces, 166 ; opium and morphia the chief hypnotics or inducers of, 167 ; list of the principal hypnotics, 166, 167 ; nature of the reflexes in ordinary and mesmeric, 172
Slippery elm, 945
Smell, action of drugs on, 194
Smelling salts, stimulating action of, on the brain, 162
Smells, remedies for destroying disagreeable, 83-86
Smilaceæ, 957
Smoke, utility of inhaling certain kinds of, in asthma, 424
Smut, corn, characters and action of, 983
Snail, structure of the heart of the, 280
Snake-bite, as a poison, with its antidote, 433 ; action of strong solution of ammonia in, 569, 570
Snake poison, effects of, on the blood, 58 ; action of ammonia in, 287
Sneezing, drugs which cause, their number, nature, and uses, 210, 211
Snuff, Ferrier's, composition and use of, 658
Soap, as an emollient, 304
Soap, curd, 988
Soap, hard, characters, &c., of, 882
  Soft, 882
Soap, soft, action of, on bacteria, 76, 77
Socaloïn, nature and action of, 960
Soda, as a caustic, 301 ; difference between the action of, and potash on the intestines, 334
Soda, nature, action, and uses of—
  Acetate of, 555
  Benzoate of, 558
  Biborate of, 555
  Bicarbonate of, 553
  Bisulphite of, 560
  Borate of, 555
  Borax, 555
  Bromide of, 558
  Carbonate of, 552
  Caustic, 552
  Chlorate of, 557
  Chloride of, 550
  Effervescent, citro-tartrate of, 554
  Hypophosphite of, 557
  Iodide of, 558
  Nitrate of, 550
  Phosphate of, 556
  Pyrophosphate of, 558
  Salicylate of, 559
  Santoninate of, 559
  Solution of, 552
  Sulphate of, 555
  Sulphite of, 560
  Sulphocarbolate of, 560
  Tartarated, 554
  Valerianate of, 561
Soda salts, sources of, 548 ; reactions of, 548 ; preparations of, 549 ; impurities of, 550 ; tests for impurities in, 550 ; general action of, 550 ; their action, in large doses, on muscle and nerve, 550
Soda tartarata, 536
Sodæ arsenias, 647
  Arseniatis, liquor, 647
  Citro-tartras effervescens, 553
  Valerianas, 703
Sodic hyposulphite, 71
Sodic sulphate, action of, on bacteria, 71
Sodii Iodidum, 489
  Santoninas, 870
Sodium, symbol and atomic weight of, 10 ; its relation to other members of a group, 15 ; physiological action of, 23
Sodium Acetate, as a remote antacid, 321
  Benzoate, as a hepatic stimulant, 353
  Bicarbonate, action of, on the ear, 194 ; as a direct antacid, 321
  Carbonate, as a direct antacid, 321
  Chloride, as a vermicide, 357
  Citrate, as a remote antacid, 321
  Phosphate, as a hepatic stimulant, 353
  Salicylate, as a hepatic stimulant, 353
  Salts, action of, on the intestines, 334 ; as a refrigerant diuretic, 379
  Sulphate, as a hepatic stimulant, 353 ; antagonism of, to barium, 433-437
Sokoloff, reference to, 114*n*.
Solanaceæ, 898
Solution of—
  Acetate of ammonia, 572
  Ammonia, 570
  Basic ferric sulphate of iron, 669
  Bichromate of potassium, 542

Solution of Carbonate of magnesia, 592
Chloride of calcium, 582
Chloride of iron, 671
Chloride of tin, 634
Chloride of zinc, 601
Chlorinated lime, 487
Citrate of ammonia, 572
Citrate of bismuth, 660
Citrate of iron and quinine, 675
Citrate of magnesia, 592
Iodide of arsenic and mercury, 648
Liquor potassæ permanganitis, 540
Litmus, 979
Perchloride of (strong), 671
Pernitrate of iron, 679
Persulphate of iron, 679
Potash, 533
Red prussiate of potash, 542
Soda, 552
Subacetate of lead, 632
Subsulphate of iron, 669
Tersulphate of, 669
Turmeric, 970
Yellow prussiate of potash, 542
Solution, test-, of albumen, 995
Solutions, 455
Sonnenschein, references to, 81
Soporific, Indian hemp or American cannabis as a, 947 ; lupulin as, 948
Soporifics, 164. *See* Hypnotics
Spanish flies, 1000
Sparteine, action of, on inhibitory ganglia, 275
Spasm, nature and cause of, 180 ; general mode of treatment, 180-182 ; list of antispasmodics and adjuvants, 181, 182
Spearmint and oil, as a carminative, 330
Spearmint, oil of, characters, action, and use of, 919 ; as a carminative and stimulant, 919
Spectrum of simple and compound bodies, 11 ; of calcium chloride, 11 ; of lithium, 12 ; of calcium, 13 ; hæmoglobin and its derivatives, 57
Spence, Dr. A. J., references to, 150
Spermaceti, 994 ; as an emollient, 995
Sphacelinic acid, 981
Sphærobacteria, 67
Sphincter muscle of the iris, nature and functions of, 185
Spider's-web, as a styptic, 307
Spigelia, characters and use of, 891 ; as an anthelmintic, 891
Spinal centre for respiration, 201 ; vasomotor, 245, 246, 887 ; for secretion of sweat, 384 ; for the generative organs, 393
Spinal cord, action of drugs on the, 129-151 ; the three functions of the, 129 ; action of drugs on the conducting power of the, 129 ; mode of testing this, 129 ; mode of ascertaining the power of the, to conduct sensory impressions, 130 ; and reflex stimuli, 130 ; and of the time required for transverse and longitudinal conduction, 130 ; diagrams illustrative of this, 131, 133 ; mode of experimenting on the action of drugs on the reflex action of the, 133 ; direct, indirect, and inhibitory paralysis of the, by drugs, 134, 135 ; list of, and uses of, depressants for the, 135 ; inhibitory paralysis of the, 135 ; experiments illustrative of this, 136 ; diagram to illustrate inhibition in the, 139 ; explanation of the actions of certain drugs on the, on the author's hypothesis, 141-146 ; stimulating action of drugs on the reflex powers of the, 147 ; Magendie's series of experiments on the action of poison on, 147-151 ; diagram illustrating Magendie's method of investigating the mode of action of strychnine on, 148 ; stimulants for the, and their uses, 151 ; antagonism between drugs acting on the respiratory centre and the, 438 ; action of ammonium salts on the, 528 ; of bromide of potassium, 547 ; of ammonium chloride, 567 ; of manganese salts, 679 ; of spirits of ether, 706 ; of nitroglycerine, 712 ; of chloral hydrate, 716 ; of carbolic acid, 736 ; of aconitia, 750 ; of delphinine, 752 ; of codeine, 766 ; of opium, 770 ; of sanguinaria, 778 ; of physostigmine, 819 ; of Jamaica dogwood, 827 ; of oil of eucalyptus, 840 ; of conïne, 846 ; of quinine, 862 ; of oil of valerian, 867 ; of strychnine, 888 ; of curare, 889 ; of gelsemium, 890 ; of belladonna or atropine, 891 ; of tobacco, 907 ; of digitalin, 910 ; of thymol, 920 ; of colchicum, 968
Spinal depressants, number, nature, and uses of, 135 ; stimulants, 151
Spirit, proof, 701 ; rectified, 701 ; of French wine, 701
Spirit of chloroform, as a cardiac stimulant, 286
Spirit of ether, as a cardiac stimulant, 286
Spirits, 461
Spirits, as a carminative, 330
Spiritus ætheris, 461, 705
Compositus, 461, 705, 707
Nitrosi, 461
Ammoniæ, 461
Aromaticus, 461, 569, 570, 571, 794, 926
Fœtidus, 461
Anisi, 461, 850
Armoraciæ compositus, 461, 782, 792, 925
Aurantii, 461, 793
Cajuputi, 461, 839
Camphoræ, 461, 928
Chloroformi, 461, 720

Spiritus Cinnamomi, 927
Cinnamonii, 461
Frumenti, 461
Gaultheriæ, 461, 878
Juniperi, 461, 955
Compositus, 461, 851, 955
Lavandulæ, 461, 917, 918
Limonis, 464, 794
Menthæ piperitæ, 461, 918
Viridis, 461, 919
Myrciæ, 461, 793, 838
Myristicæ, 461, 926
Odoratus, 461, 791, 793, 794, 917, 918
Rectificatus, 461
Rosmarini, 461, 917
Tenuior, 461
Vini gallici, 471
Spiritus vini gallici, mistura, 995
Spirobacteria, 67
Splanchnics, the, and the kidneys, 375, 376
Spleen, action of alcohol on the, 691; action of physostigmine, 821; of oil of eucalyptus, 840
Squill, action and use of, 959; in large doses, 959; on the pulse, and as a diuretic and expectorant, 959
Squills, action of, on the blood vessels, 214; as a stimulating expectorant, 219; as a cardiac tonic, 289; as a general emetic, 325; as a refrigerant diuretic, 379
Squirting cucumber fruit, 843
Stannius, reference to, 887
Stannius's experiments as to the actions of the various cavities of the frog's heart, 277-280
Staphisagria, or stavesacre, characters and composition of, 752; action of, in frogs, 752; delphinine acts like aconitine on the pulse and respiration, 752; on the spinal cord and medulla, 752; on the vagus and the heart, 752; uses of, 752
Star-anise, character and composition of, 756
Starch, 973; characters and uses, 974
Starch, is converted into dextrin and sugar by boiling with acids, 58; as a demulcent, 304
Stavesacre, 752
Stearic acid, action of, on bacteria, 76
Stenhouse, Dr., reference to, 815
Stenosis, mitral, cardiac tonics useful in, 290; aortic, digitalis of doubtful use in, 290
Stenson's experiment on the abdominal aorta of a rabbit, 134
Sterculiaceæ, 796
Sternutatories or errhines, number, nature, and uses of, 210, 211; contra-indications of, 211; must be used with caution in certain cases, 211
Stevens, reference to, 911
Stewed apples, as a laxative, 339
Stillingia, as an alterative, 362; characters and uses of, 933; as an alterative, 933
Stimulant, beef-tea *versus* alcohol as a, 699
Stimulants, spinal, 151; nerve, 161; cerebral, 161; cardiac, 286; vascular, 287; hepatic, 353; diuretic, 379
Stirling, references to, 102
Stolnikow, reference to, 775*n*.
Stomach, impaired power of the, in the aged, 308; normal and abnormal condition of, 317; irritability of the, 318; diagram to illustrate the supposed nervous connections of the, 318; three factors in the process of digestion in the, 318; action of drugs on secretion in the, 319; drugs which stimulate the secretion of the gastric juice, 319; importance of thorough mastication, 319; supply of artificially digestive substances to the, 319; action of drugs on the movements of the, 320; absorption from the, 320; action of calomel on the, 320; use of gastric sedatives in relieving pain in the, 328; and vomiting from the, 328; list of sedatives which have the most powerful action on the, in certain circumstances, 328; action of, in expelling gases from the, 328, 329; drugs which tend to prevent fermentation in the, 329; they remove pain and distension of, and diminish local spasm, 330; action of irritant poisons on the, 346, 347; diagram to show the nervous mechanism by which the action of the heart may be depressed by irritation of the, 346; diagram of the liver, intestines, and, 353; application of drugs to the, 425; the stomach-pump, 425; the gastric syphon, and its use, 426; action of acids in the, 497; of alkalis, 524; of the metals zinc, copper, cadmium, and silver, 596, 597; of nitrate of silver, 608; of mercury, 614; of phosphorus, 638; of arsenic, 641; of antimony, 649; of iron salts, 665; of gold, 680; of alcohol, 691, 692; of spirit of ether, 706; of chloral hydrate, 715; of purified chloroform, 731; of creasote, 730; of aconitia, 751; of pilocarpine, 505; of physostigmine, 821; of quinine, 860; of tannic acid, 942; of oil of turpentine, 950
Stomach cough, probable origin of the so-called, 213; rationale of the, 213
Stomachic, black pepper as a, 937; lupulin as, 948
Storax, characters, composition, and use of, 940; prepared, 340
Stramonium, as a narcotic, 168; as a general anodyne, 169; action of, on the lung, on the respiratory centre, and on the ends of the vagi, 214; on the vagus centre, 274; on the vaso-motor

centre, 274 ; as a poison, with its antidote, 433
Stramonium leaves, characters of, 906
Seed, 906
Seeds, characters, action, and use of, 906 ; as an antispasmodic, 906
Stricker's stage, uses of a, 46
Stromuhr, Ludwig's, 253
Strontium, symbol and atomic weight of, 10 ; physiological action of, 23 ; action of, on the muscles, 110, 117 ; causes contraction of the vessels, 240
Strophanthine, as a cardiac tonic, 289 ; as a refrigerant diuretic, 379
Strophanthus hispidus, action of, on the cardiac muscle, 276 ; as a cardiac tonic, 289
Strychnina, 444, 884
Strychnine, cumulative action of, 31; effect of, on protoplasm, 47 ; has little power on infusoria, 51 ; effects of, on oxidation, 55, 58 ; action of, on medusæ, 90 ; on mollusca, 93 ; on ascidians, 93 ; and on annulosa, 94 ; on muscle, 99, 119 ; effect of, on the spinal cord, 132, 142 ; effect of, in causing tetanus, 143, 144-146 ; Magendie's series of experiments on the action of, 147-151 ; as a spinal stimulant, 151 ; action of, on the brain of dogs, 156 ; and of men, 163 ; on the ear, 194 ; on taste and the sense of smell, 195 ; on the respiratory centre, 205 ; as a stimulating expectorant, 219 ; action of, on the vaso-motor centre, 246, 274 ; as a cardiac tonic, 289 ; as a vascular tonic, 293 ; fails to poison when the vagi are divided, 320 ; as an antihydrotic, 387 ; action of, in lessening the night sweats in phthisis, 388, 389 ; as an aphrodisiac, 395 ; as an indirect emmenagogue, 398 ; as a poison, with its antidote, 433; antagonism of, to other drugs, 433-437 ; antagonistic action of, to chloral, 436, 437
Strychnine, 884
Sulphate of, preparation and characters of, 885 ; action of, on low organisms, on oxidation, and fermentation, 885 ; on the reflex nerve centres, on the intestines and sensory nerves, 885 ; poisoning by, and treatment for, 886 ; action of, on the alimentary canal, on the blood and circulation, 886 ; on the heart, respiration, and muscles, 887 ; on the nervous system and brain, 887 ; on the spinal cord, 888 ; uses of, 888
Stuart, Anderson, references to, 104, 117
Sturiones, 996
Styptic, action of dried alum as a, 586 ; strong solution of perchloride of iron one of the most powerful styptics, 672 ; matico as a, 938
Styria, arsenic-eaters of, account of the, 642
Subchloride of mercury, 621
Sublimed sulphur, its preparation, characters, &c., 479
Subnitrate of bismuth, 659
Subsulphate of mercury, as a local emetic, 325
Succus belladonnæ, 462, 899
Conii, 462, 845
Hyoscyami, 462, 905
Limonis, 507
Scoparii, 462, 814
Taraxaci, 462, 872
Sudorifics, action of, on the secretion of sweat, 383
Suet, 988 ; prepared, 988
Suffocation, cause of, 204 ; produced by the action of certain poisons on the respiratory tract, 348
Sugar, 975 ; as a vehicle and corrigent, 976 ; preservative and antiseptic, 976 ; sugar, refined, 975
Sugar of milk, 989
Sulphæmoglobin, 57
Sulphate of aluminium, action of, on bacteria, 75
Sulphate of aluminium, 587
Ammonium, 573
Atropine, 901
Beberia, 931
Hyoscyamine, 905
Iron, 667
and Ammonium, 675
Dried, 668
Granulated, 668
Precipitated, 668
Magnesia, 590
Mercury, 620
Morphine, 764
Potash, 537
Soda, 555
Zinc, 601
Sulphate of beberine, action of, on protoplasm, 47
Sulphate of potash, as a cholagogue purgative, 355
Sulphate of potassium, sodium, and magnesium, as saline purgatives, 340
Sulphate of soda, as a cholagogue purgative, 355
Sulphates, general action of, 527
Sulphide of mercury, red, 627
Sulphites, test for, 521
Sulphite of soda, 560
Sulphocarbolate of soda, 560
Sulphocyanide of potassium, action of, on mollusca, 93
Sulpho-vinate of sodium, as a saline purgative, 340
Sulphur, symbol and atomic weight of, 10 ; its relation to other members of a group, 15 ; as a stimulating expectorant, 219 ; as a laxative and purgative, 339
Sulphur and its elements, 479-483 ; sublimed sulphur, flowers of sulphur, 479,

480; confection of sulphur, 480; sulphur ointment, 480; washed sulphur, 480; alkaline sulphur ointment 480; precipitated sulphur, lac sulphuris, or milk of sulphur, 480; sulphuretted hydrogen, or hydrogen sulphide, 481; general action of sulphuretted hydrogen, 481; special action, 482; action and uses of sulphur, 482; iodide of, 490
Sulphur lotum, 480
Precipitatum, 480
Sulphurated potash, 541
Sulphuretted hydrogen, action of water of, on bacteria, 76; as a poison, with its antidote, 428; its preparation and properties, 481, 482
Sulphuric acid, physiological action of, 24; direct and local action of, 26; effects of, on alcohol, 58; on bacteria, 73, 75; as a caustic, 301; as a poison, with its antidote, 429; properties and uses of, 498
Sulphuris iodidum, 480, 489
Sulphurous acid, action of, on enzymes, 63; on bacteria, 73; properties and uses of, 498
Sulphurous bath, uses of a, 413
Sumach as an astringent, 811
Sumbul, as an antispasmodic, 182; characters and use of, chiefly in hysteria, 851
Root, 851
Suppositoria acidi carbolici cum sapone, 462, 735, 988
Acidi tannici, 462, 796, 942, 1000
cum Sapone, 462, 988
Hydrargyri, 462, 616, 796, 1,000
Morphiæ, 462, 764, 796, 1000
cum Sapone, 462, 764, 988
Plumbi composita, 462, 632, 796, 1000
Suppositories, nature and uses of, 427
Suppositories, 461
Surgical operations, use of antiseptics in, 84; Sir Joseph Lister on the best mode of performing, 737
Sustschinsky, reference to, 271
Sweat, mode of secretion of, 383; various causes which arrest or increase the secretion of, 384; excretion by the sweat glands, 385; relation between the sweat glands and the kidneys, 386; uses of diaphoretics and sudorifics in increasing the secretion of, 383; action of antihydrotics on the secretion of the, 387; the night sweats of phthisis, 388; diagram to illustrate the action of antihydrotics, 388; connection of the respiratory centre with the sweat glands, 389; various drugs which act on the secretion of, 389; action of carbolic acid on the sweat centres, 736; action of opium on the secretion of, 772; and of erythroxylon, 787
Sylvester's plan of artificial respiration, 726
Syncope, caused by sudden change of posture, 172, 173; by the use of anæsthetics, 175-177; by fainting and shock, 223, 224; by the incautious use of cardiac tonics, 292; by the lowness of the blood-pressure, 291; by the administration of digitalis, 291
Syphon, gastric, nature and uses of, 426
Syringe, diagram of a, for hypodermic injection, 418; of a vulcanite, for injecting solutions into the ear, 420; of a vulcanite, for injecting solutions into the urethra, 427
Syrupus acaciæ, 463, 828
Acidi citrici, 463, 507
Hydriodici, 463
Allii, 463, 958
Althææ, 463, 791
Amygdalæ, 463, 834
Aurantii, 462, 463, 792
Floris, 462, 792
Calcii lactophosphatis, 463, 583
Calcis, 463, 579
Cheken, 839
Chloral, 462, 715
Ferri Bromidi, 463
Iodidi, 462, 463, 489, 676
Phosphatis, 462, 506, 555, 677
Quininæ et Strychninæ Phosphatum, 463, 677, 857, 885
Hemidesmi, 462, 893
Hypophosphitum, 463, 557, 585
cum ferro, 463, 676
Ipecacuanhæ, 463, 864
Krameriæ, 463, 785
Lactucarii, 463, 873
Limonis, 462, 463, 507, 794, 795
Mori, 462, 945
Papaveris, 462, 760
Picis Liquidæ, 463, 953
Pruni Virginianæ, 463
Fluidum, 835
Rhamni, 462, 809, 838, 970
Rhei, 463, 852, 923, 924, 1005
Aromaticus, 463, 837, 924, 1005
Rhœados, 463, 778
Rosæ, 463, 831
Gallicæ, 463, 831
Rubi, 463
Idæi, 463, 830
Sarsaparillæ compositus, 463, 824, 831, 878, 930, 957
Scillæ, 463, 534, 959
Compositus, 463, 653, 657, 784, 959
Senegæ, 463, 784
Sennæ, 463, 824, 852
Tolutanus, 463, 817
Zingiberis, 463, 970
Syrup of bromide of iron, 676
Syrups, 462
Szpilman, reference to, 114

T.

Tamarind, character, composition, and use of, 825
Tannate of soda, action of, on the kidneys, 382
Tannic acid, 941
Tannic acid, as an astringent, 305 ; preparation and properties of, 942 ; action of, on the skin, mucous membranes, mouth, and stomach, 942 ; on the blood and kidneys, 943 ; uses of, externally and internally, 943
Tannin, action of, on bacteria, 76 ; on the mucous membranes, 217 ; as a styptic, 307 ; as a vermicide, 357 ; action of, on the kidneys, 382 ; indigestibleness of tea partly due to the tannin it contains, 797
Tansy, characters and uses of, 869 ; as a diuretic, stimulant, emmenagogue, and anthelmintic, 869
Tantalum, symbol and atomic weight of, 10
Tar, as a stimulating expectorant, 219 ; action and use of, 953 ; as a stimulant, 954
Tar, oil of, 953
Taraxacum, 872
Taraxacum, as a stimulant diuretic, 380
Tartar emetic, effects of, on the blood, 58 ; as a depressant expectorant, 219 ; action of, on the system, in causing vomiting, 324 ; as a general emetic, 325 ; nature and use of, 562, 563 ; ointment, 657
Tartarated soda, as a remote antacid, 321
Tartaric acid, as a poison, with its antidote, 429 ; properties of, &c., 506
Tartrate, test for, 521
Tartrate of iron and ammonium, 673
Potassium, 673
Potash, 536
Soda, 554
Taste, action of drugs on the sense of, 195
Tea, characters, action, and uses of, 796 ; a powerful cerebral stimulant, 797 ; indigestibleness of, partly due to the tannin it contains, 797
Teeth, danger of extracting the, with chloroform, in certain cases, 176 ; action of drugs on the, 308 ; importance of the, for mastication, 308 ; what the decay of the, is chiefly due to, 308, 583 ; the best substances for cleansing the, 308 ; and for protecting and preserving the gums, 309, 524 ; remedies for toothache, 309, 583, 736, 738, 775
Tellurium, symbol and atomic weight of, 10 ; its relation to other members of a group, 15
Teleosteæ, 996
Temperature, effect of, on the action of drugs, 32, 36 ; on the secreting nerves, 34 ; of the body half a degree higher in India, 36 ; effects of, on ferments, 60 ; on mould fungi, 68 ; on bacteria, 70 ; excess of, injurious to the human organism, but destructive of bacteria, 82 ; effects of, on the rhythmical action of medusæ, 89 ; on mollusca, 93 ; on muscles, 105 *et seq.* ; effects of, on the poisonous action of guanidine, 145 ; the, of warm-blooded animals ; 365 ; action of antipyretics on, 365 ; action of the skin in regulating the, 386 ; action of salicylate of soda on the, 559 ; of mercury on the, 616 ; of alcohol, 693 ; of chloral hydrate, 716 ; of carbolic acid, 736 ; of salicylic acid, 741 ; of aconitine, 750 ; of erythroxylon, 787 ; of caffeine, 798 ; of pilocarpine, 806 ; of oil of eucalyptus, 840 ; of solanine, 898 ; of belladonna or atropine, 903 ; effects of, on the action of digitalin, 912 ; of thymol, 920 ; of camphor, 929, 930 ; of Indian hemp or American cannabis, 947 ; of oil of turpentine, 950 ; of thuja, 954 ; of veratrine, 966
Tents, nature and uses of, 427
Tepid baths, 411
Terbium, symbol and atomic weight of, 10
Terebinthaceæ, 811
Tetrachloride of carbon, as an anæsthetic, 172
Thalamifloræ, 747 *et seq.*
Thallium, symbol and atomic weight of, 10 ; physiological action of, 23
Thebaine, as a spinal stimulant, 151 ; action of, on the respiratory centre, 205 ; on the vaso-motor centre, 274 ; antagonism of, to chloral, 433-437 ; acts like strychnine, 888
Theobroma, oil of (cacao butter), characters, uses, &c., of, 796
Theobromine, action of, on muscles, 107
Therapeutics, definition of, (1) may be either empirical or rational, 1 ; explanation and example of empirical therapeutics, 1 ; and also of rational, 1, 2 ; first stage of rational, 2 ; what should follow this, 2
Thermometer, importance of cleansing and disinfecting, 84, 85
Theveresine, action of, on the cardiac muscle, 276
Thevetin, action of, on the cardiac muscle, 276
Thighs, utility of mustard stupes, poultices, and leeches, to the, as indirect emmenagogues, 398
Thirst, two kinds of, local and general, 315, 316 ; nature of local, and how it is lessened or quenched, 315 ; general, and the means of alleviating, 315, 316
Thomas, reference to, 35
Thorium, symbol and atomic weight of,

Thoroughwort, 872
Throat, action of pilocarpine on the, 807
Thuja, characters and action of, 954; in producing abortion, convulsions, and paralysis, 954; on the vessels and temperature, 954; uses of, as a diuretic, astringent, aromatic, and vermifuge, 954
Thulium, symbol and atomic weight of, 10
Thymol, action of, on enzymes, 63; on bacteria, 73, 76, 77; preparation and characters of, 919; action of, as a disinfectant, and on the nerve centres of the medulla and cord, 920; on the respiration, blood-pressure, and temperature, 920; how eliminated, 920; uses of, as an antiseptic, 920
Tiçunas. *See* Curare
Tinctura Aconiti, 464, 465, 748
Aloes, 464, 465, 814, 960, 961
et Myrrhæ, 465, 813, 961
Arnicæ, 464, 873
Florum, 465, 874
Radicis, 465, 873
Asafœtidæ, 464, 465
Aurantii, 464, 792
Recentis, 464, 792
Amari, 465, 792
Dulcis, 465, 792
Belladonnæ, 464, 465, 899
Benzoini, 465, 879
Composita, 84, 464, 465, 817, 879, 940, 960, 961
Bryoniæ, 465, 845
Buchu, 464, 803
Calendulæ, 465, 874
Calumbæ, 464, 465, 757
Camphoræ composita, 464, 761, 849, 880, 928
Cannabis indicæ, 464, 465, 946
Cantharidis, 464, 465, 1001
Capsici, 464, 465, 899
Cardamomi, 465, 971
Composita, 464, 465, 800, 851, 927, 971, 1000
Cascarillæ, 464, 933
Castorei, 464, 987
Catechu, 464, 566, 927
Composita, 465, 828
Chiratæ, 464, 465, 895
Chloroformi composita, 464, 720, 971
Cimicifugæ, 465, 754
Cinchonæ, 465, 855
Composita, 464, 465, 792, 854, 856, 932, 972, 1000
Flavæ, 464, 855
Cinnamomi, 464, 465, 927
Cocci, 464, 1000
Colchici, 456
Seminum, 464, 968
Seminis, 988
Conii, 464, 465, 846
Croci, 464, 465, 972
Tinctura Cubebæ, 464, 465, 937
Digitalis, 464, 465, 909
Ergotæ, 464, 980
Erythrophlœi, 829
Ferri Acetatis, 464, 465, 535, 669
Chloridi, 465, 672
Perchloridi, 464, 672
Gallæ, 464, 465, 941
Gelsemii, 465, 890
Gentianæ composita, 464, 465, 792, 894, 971
Guaiaci, 464, 801
Ammoniata, 464, 465, 572, 801
Herbarum recentium, 465
Humuli, 465, 948
Hydrastis, 465, 955
Hyoscyami, 464, 465, 905
Ignatiæ, 466, 884
Iodi, 464, 466, 489, 543
Ipecacuanhæ et Opii, 466, 761, 762, 864
Jalapæ, 464, 897
Kino, 464, 466, 816
Krameriæ, 464, 466, 785
Laricis, 464, 953
Lavandulæ composita, 464, 466, 816, 837, 917, 925, 927
Limonis, 464, 794
Lobeliæ, 464, 466, 876
Ætherea, 464, 705, 876
Lupuli, 464, 948
Maticæ, 466, 938
Moschi, 466, 988
Myrrhæ, 464, 466, 813
Nucis vomicæ, 464, 466, 884
Opii, 464, 466, 761
Ammoniata, 464, 569, 761, 849, 880, 972
Camphorata, 466, 761, 762, 850, 880, 928
Deodorata, 464, 761, 762
Physostigmatis, 466, 818
Pyrethri, 465, 466, 868
Quassiæ, 465, 466, 808
Quebracho, 892
Quiniæ, 465, 857
Ammoniata, 465, 857
Rhei, 465, 466, 852, 923, 924, 971, 972, 1005
Aromatica, 466, 837, 924, 1005
Dulcis, 466, 924, 1005
Sabinæ, 465, 955
Sanguinariæ, 466, 779
Saponis viridis, 466, 882
Scillæ, 465, 466, 959
Senegæ, 465, 784
Sennæ, 465, 800, 824, 851, 852
Serpentariæ, 465, 466, 932
Stramonii, 465, 466, 906
Sumbul, 465, 466, 851
Tolutana, 465, 466, 817
Valerianæ, 465, 466, 572, 867
Ammoniata, 465, 466, 867

Tinctura vanillæ, 466, 969
Veratri viridis, 465, 466, 970
Zingiberis, 465, 466, 970
Fortior, 465, 970
Tin, symbol and atomic weight of, 10; causes powerful contraction of the vessels, 240; general action of, 627; nature and uses of granulated, 634; of solution of chloride of, 634
Tincture, litmus, 979
Tincture, turmeric, 970
Tincture of acetate of iron, 670
Tinctures, 463-466
Tissue change, action of drugs on, 359-368; of tonics, 359; of hæmatinics, or blood tonics, 361; of alteratives, and their action on the tissues, 362-365; of antipyretics, or febrifuges, 365; list of the chief, their action, 366; and their uses, 367; experiments as to the action of drugs on, 363; action of the heavy metals on, 595; of silver, 608; of salts of iron, 666; of alcohol, 693; of quinine, 861
Titanium, symbol and atomic weight of, 10
Tobacco, effect of the inhalation of the smoke of, on a rabbit, 209; snuff, action of, on the nose, 210; the vapour of tobacco has a local sedative action on the lung, 214; tobacco as a sialagogue, 312, 313; as a poison, with its antidote, 433
Tobacco, 906; tobacco leaf, character of, 906; general action of, 907; on the motor and secreting nerves, the intestine, the heart, and vaso-motor system, 907; in frogs and warm-blooded animals, 907; special action of, on the spinal cord, circulation, and vagus, 907; on the blood-pressure, heart, and alimentary canal, 907; uses of, 908; on the effects of tobacco smoking, 908
Toldt, reference to, 112
Tolu, balsam of, characters and uses of, as an expectorant, 817
Tonics, as adjuvants to antispasmodics, 181; list of cardiac, 288-292; of vascular, 293; of gastric, 317; nature and action of, 359; subdivisions of, 359; states in which gastric, digestive, vascular, and nerve tonics are indicated, 360; hæmatinics, or blood tonics, 361; their mode of action on the blood, 361; alteratives and their action, 362-365; nature, action, and uses of antipyretics or febrifuges, 365-368; quassia as a tonic, 808; cheken as, 838; quinine as a, 862; wormwood as, 869; oil of chamomile as, 871; eupatorium as, 871; rhubarb as, 924; sulphate of beberia as, 931; serpentary root as, 932; cascarilla bark as, 933; elm as, 945; lupulin as, 948; sarsaparilla as, 957; Iceland moss as, 979
Tonometer, Roy's, 228
Toothache, may frequently be removed by means of a brisk purgative, 170; various remedies for alleviating, 309, 736, 738, 775
Tortoise, experiments on the muscular structure of the, 102, 115; difference betwixt the mammalian heart and that of the, 256, 257
Tragacanth, characters, composition, and uses of, 815
Traube, references to, 27, 254*n*.
Traube's curves, nature of, 227
Treacle, as a laxative, 976
Trephining, utility of, in investigating the functions of the brain, 156, 165
Trichlorhydrin, as an anæsthetic, 172
Trimethylamine, action of, on bacteria, 76
Triticum, 974
Trituratio Elaterini, 466, 844
Triturations, 466
Trochisci, 828
Acidi tannici, 467, 942
Ammonii chloridi, 467, 567
Bismuthi, 467, 659, 660
Catechu, 467, 828, 866
Cretæ, 467, 581
Cubebæ, 467, 987
Ferri, 467, 669, 670
Redacti, 467
Glycyrrhizæ et opii, 467, 761, 850
Ipecacuanhæ, 467, 864
Krameriæ, 467, 785
Magnesiæ, 467
Menthæ piperitæ, 467, 918
Morphiæ, 467, 764
et Ipecacuanhæ, 467, 764, 864, 878
Morphinæ et Ipecacuanhæ, 467, 764
Nitro-glycerini, 712
Opii, 467, 761, 814
Potassæ chloratis, 467, 539
Potassii chloratis, 467
Sodii bicarbonatis, 467, 553
Santoninatis, 870, 559
Santoninatis, 467
Zingiberis, 467
Trypsin, action of, on fibrine, 60-62
Tungsten, symbol and atomic weight of, 10; its relation to other members of a group, 15
Türck's method of experimenting on reflex action, 133
Turmeric, 970; as a condiment, 971
Paper, 970
Solution of, 970
Tincture, 970
Turpentine, as a stimulating expectorant, 219; action of, on the vaso-motor centre, 274; as a vermicide, 357; as a stimulant diuretic, 379
Turpentine, oil of, action of, on the mucous membranes, 218; importance of, in bron-

chitis, 218; as a poison, with its antidote, 433
Turpentine, characters of, 950
Canada, 949
Oil of, characters and action of, 950; when inhaled and internally, 950; on the stomach, respiration, and temperature, 950; on the nerve centres and the kidneys, 951; use of, externally and internally, and as a vermifuge, 951
Turpentine water, action of, on enzymes, 63
Tweedy, Mr. J., reference to, 184, 191

U.

Ulcers, chronic, use of vesicants in, 302; of astringents, 306
Ulmaceæ, 944
Umbelliferæ, 845
Unguentum, 994, 999
Acidi Carbolici, 467, 735, 994, 999
Gallici, 467, 944, 994
Tannici, 467, 942, 994
Aconitiæ, 467, 748, 994
Antimonii tartarati, 467, 653, 657
Aquæ rosæ, 467, 831, 834, 995, 1000
Atropiæ, 467, 994
Belladonnæ, 467, 899, 994
Cadmii Iodidi, 489, 606
Cantharidis, 467, 881, 999, 1001
Chrysarobini, 467, 823, 994
Cetacei, 467, 834, 995, 1000
Creasoti, 467, 738
Diachylon, 467, 631, 881
Elemi, 468, 813
Gallæ, 467, 468, 941, 994
cum Opio, 468, 761, 941
Hydrargyri, 468, 616, 988, 944
Ammoniati, 468, 617, 624, 994
Compositum, 468, 616, 881, 928, 999
Iodidi rubri, 468, 617, 626
Nitratis, 468, 502, 617, 881, 994
Oxidi flavi, 468, 616, 623, 994
Rubri, 468, 616, 624, 834, 994, 999
Subchloridi, 468, 621, 994
Iodi, 468, 543, 994
Iodoformi, 468, 728, 994
Mezerei, 498, 994, 999
Picis Liquidæ, 468, 953, 999
Plumbi Acetatis, 468, 632
Carbonatis, 468, 631, 994
Iodidi, 468, 543, 633, 994
Subacetatis compositum, 468, 834, 928, 1000
Plumbi potassæ sulphuratæ, 468, 541, 994
Potassii iodi, 489
Iodidi, 468, 994
Resinæ, 468, 952, 999
Sabinæ, 468, 955, 994, 999
Simplex, 468, 834, 944, 1000
Stramonii, 468, 906, 994
Sulphuris, 468, 480, 994
Alkalinum, 468, 480, 994
Iodidi, 468, 490, 994
Terebinthinæ, 468, 950, 952, 994, 999
Veratriæ, 468, 881, 965, 994
Veratrinæ, 468, 965, 994
Zinci, 468, 599, 600
Oxidi, 468, 599, 600, 994
Uranium, symbol and atomic weight of, 10
Urari. *See* Curare
Urea, drugs which act on the excretion of, 363; excreted by the tubules, 371
Urechitine, as a general emetic, 325
Ureter, rhythmical contraction of the, 113
Urethra, drugs employed in inflammation of the, 392; application of drugs to the, 427; diagram of a vulcanite syringe for injecting solutions into the, 427
Uric acid, effects of, on the blood, 58; action of lithontriptics on, 383
Urinary sedatives and astringents, 392; urinary organs, action of cantharides on the, 1001
Urine, circumstances modifying the secretion of, 374-383; the rapidity of the secretion of, depends on two factors, 374; arterial pressure in the glomeruli and the composition of the blood, 374-376; curves showing the effect of erythrophlœum on blood-pressure and secretion of the, 377; action of lithontriptics on the, 382; how evacuation of the, is promoted, 391; action of the bladder on the, 390-392; action of mercury on the, 616; of nitrite of amyl, 710; of belladonna or atropine, 903; of Indian hemp or American cannabis, 947; of colchicum, 968; of extract of ergot, 982
Urticaceæ, ulmeæ (ulmaceæ), 944
Ustilago, 983
Uterus, action of ecbolics, on, 398; the involuntary muscular fibres of the, controlled by two nerve-centres, 399; nature of the nerves which stimulate the, 399; mode of aiding the expulsive power of the, 399; application of drugs to the, 427; as pessaries, 427; as caustics, 427; utility of tents inserted in, 427; action of borax on the, 555; of pilocarpine, 806, 807; of physostigmine, 821; of quinine, 862; of aloes, 962; of extract of ergot, 982
Uva ursa (bearberry), action of, on the bladder, 301; as an astringent, 305; as

a stimulant diuretic, 380 ; characters and uses of, 877 ; as an astringent and diuretic, 877

V.

Vagina, application of drugs to the, 427 ; as pessaries, 427 ; as caustics, 427
Vagus, effects of stimulation of the, 115 ; contains both expiratory and inspiratory fibres, 206 ; diagram illustrating this, 207 ; reference to the, 208 ; experiments on the, 209 ; cough chiefly excited by branches of the, 211 ; heart's beats chiefly regulated by the inhibitory fibres of the, 253 ; action of drugs on the cardo-inhibitory functions of the, 254 ; reflex stimulation of the, 255 ; quickened pulse may be caused by paralysis of the, 255 ; action of drugs on roots of the, 255 ; irritation of the, causes still-stand of the heart, 268 ; action of two classes of poisons on the, 269 ; position of the accelerating nerves of the, in frogs and warm-blooded animals, 269 and *n.* ; vagus centre in the heart, 274 ; and ends, 275 ; nature of the action of the, upon the heart, 281 ; antagonistic action of certain drugs on the, 435 ; of delphinine, 752 ; of pilocarpine, 506 ; of tobacco, 907 ; of digitalin on the roots and ends of the, 911
Valerianic acid, action of, on bacteria, 76
Valerian, antispasmodic action of, 181, 182
Valerian, characters, &c., 866
  Oil of, 867 ; action of, on the brain and spinal cord, 867 ; on the blood-pressure and the pulse, 867 ; as an antispasmodic, 867
  Root, 866
Valerian and oil, as a carminative, 330
Valerianaceæ, 866
Valerianate of soda, 561 ; of zinc, 561, 603 ; of iron, 678
Valerianate of zinc, 867
Vanadium, symbol and atomic weight of, 10
Vanilla, characters and action of, 969 ; as an aromatic stimulant, 969
Vapor Acidi Hydrocyanici, 468, 513
  Chlori, 468, 487
  Coniæ, 468, 845
  Creasoti, 468, 738
  Iodi, 468, 489
Vapour baths, 414
Vapour of hydrocyanic acid, 513
Vapours, inhalations, 468
Vascular stimulants, nature and uses of, 287 ; tonics, 293 ; and sedatives, 296 ; when vascular tonics are serviceable, 360 ; antipyretics, more useful in symptomatic fevers than in specific ones, 367
Vaseline, properties and uses of, 688
Vaso-motor and vaso-dilating nerves, action of drugs on, 242 ; the vaso-motor centre paralysed by various drugs, 245 ; action of, on the smaller arteries and capillaries, 249 ; how the activity of the vaso-motor centre may be increased, 249 ; vaso-motor centre of the heart, 274 ; and nerves, 276 ; action of the salts of iron on the, 666 ; of platinum on the, of mammals, 680 ; of alcohol, 695 ; of carbolic acid, 736 ; of aconitine, 750 ; of opium on the peripheral, 771 ; of quillaia (saponin), 833 ; of tobacco, 907 ; of extract of ergot, 981
Vegetable alkaloids, poisonous properties of some, destroyed by the liver, 359
Vegetable bitters, strong infusions of, as local emetics, 325
Veins, nature and functions of, 221 ; blood in the, useless for nutrition, 221 ; action of the nervous system on the, 221 ; of the heart, 222 ; effect of an upright and of a horizontal position on the circulation of the blood in the, 222, 223 ; arrest of circulation in the, the cause of fainting and shock, 223, 224 ; schema of the circulation from the heart to the arterial system and the, 224-226 ; action of blood-pressure on the, 226 ; method of ascertaining the blood-pressure on the, 227-229 ; causes of alterations in blood-pressure in the, 229 ; how blood-pressure may be raised and lowered in the, 230
Venesection, as an antipyretic, 367
Veratria, 444, 964
Veratrina, 444
Veratrine, effects produced by different doses of, on frogs, 21 ; effects of heat or cold on the action of, 33 ; action of, on oxidation, 55 ; on medusæ, 90 ; on mollusca, 93 ; on ascidians, 93 ; on annulosa, 94 ; power of, for restoring muscle after fatigue, 99 ; as a muscular poison, 105-128 ; as a sedative, 128 ; action of, on the spinal cord, 132 ; as an anodyne, 170 ; on the respiratory centre, 206, 210 ; action of, on the vagus roots, 254 ; on the heart of the frog, 265, 266 ; on the vaso motor centre, 274 ; on the cardiac muscle, 276 ; as a poison, with its antidote, 433 ; antagonism of, to opium, 433-437 ; physiological action of, in large doses and externally, 965 ; internally, action of, on the brain, spinal cord, and muscles, 965 ; on the motor and sensory nerves, the circulation, and the pulse, 966 ; on blood-pressure, respiration, and temperature, 966 ; uses of, locally and internally, 966, 967
Veratroidine, 964 ; action of, on the vagus centre and ends, 964 ; on the spinal cord and respiratory centre, 964 ; on the vaso-motor centre, blood-pressure, and the pulse, 964

Veratrum album, action of, on the nose, 210
Veratrum viride, action of, on the vagus centre, 274 ; on the cardiac muscle, 276 ; on the palpitation of the heart, 296 ; nature and action of, 963
Verbenaceæ, 881
Vermicides. *See* Anthelmintics
Vermifuges. *See* Anthelmintics
Vesical sedatives and tonics, action of, on the bladder, 391
Vesicants, 302; strong solution of ammonia as a, 569
Vesication, produced by acids, 496
Vessels, blood, 221 ; reflex contraction of the, 244 ; experiments with bromide of potassium on the, 244, 245 ; action of drugs on this reflex contraction, 245 ; comparative effect of heart and, on blood-pressure on different animals, 246 ; influence of nerves on blood-pressure in the, 248-250 ; action of pilocarpine on, 806 ; of thuja on, 954. *See* Arteries and Arterioles
Viburnum (black haw), characters and uses of, 868
Vienna paste, as a caustic to extirpate malignant growths, 303
Vignal, reference to, 351
Vinegar, properties and uses of, &c., 504, 505
Vinegar, aromatic, stimulating action of, on the brain, 162 ; action of the, on the heart in man, 246 ; in dogs and rabbits, 246, 247
Vinegars, 443
Vini gallici, mistura spiritus, 995
Vinum aloes, 469, 960, 961, 970, 971
Album, 469
Fortuis, 469, 800
Antimoniale, 469, 653, 657
Antimonii, 469, 653, 657
Aromaticum, 469, 917, 921, 922
Aurantii, 792
Colchici, 469, 967
Radicis, 469, 967
Seminis, 469, 968
Ergotæ, 469, 980
Ferri, 469, 667
Amarum, 469, 675
Citratis, 469, 674
Ipecacuanhæ, 469, 864
Opii, 469, 761, 762, 837, 927
Quiniæ, 469, 507, 857
Rhei, 469, 800, 923, 924, 1005
Rubrum, 469
Xericum, 469
Viola tricolor (pansy), characters, composition, and uses of, 782
Violaceæ, 782
Virchow, references to, 146
Visions, action of drugs in producing, 193
Vitaceæ, 800
Voit, reference to, 365
Volatile oils, 457
Vomiting, relieved by blisters, 302; description of the act of, 321 ; and of the nerve centre which regulates the act of, 322 ; action of the brain and afferent nerves on, 322 ; diagram showing the afferent nerves by which the vomiting centre may be excited, 323 ; the action of drugs in causing, 323-325 ; the various uses of emetics in causing, 325-327 ; action of the most powerful sedative in persistent, is ice, 327 ; gastric sedatives in relieving, 328 ; list of sedatives useful in vomiting arising from different causes, 328 ; the action of irritant poisons on the stomach gives rise to, 346 ; action of pilocarpine on, 506

W.

Warburg's tincture, 863
Warm, foot, and hip baths, utility of, as indirect emmenagogues, 398 ; warm baths, 411
Warm-blooded animals, action of tobacco on, 907 ; of thuja on, 954
Warm clothing, importance of, to delicate people, 220
Warmth. *See* Heat
Warmth and moisture, importance of, in rooms occupied by patients having bronchial or chest complaints, 220 ; as an emollient, 304 ; poultices made of substances which retain, 304 ; action of, on the circulation of the blood and the secretion of sweat, 384
Warren, Dr., reference to his use of ether, 179
Washed sulphur, its preparation, &c., 480
Wassilieff, reference to, 85
Water, lukewarm, as a local emetic, 325 ; in large quantities, as refrigerant diuretics, 379
Water of ammonia, 570
Waters, nature of, uses, and doses, 444
Watts's modification of Mendelejeff's tables, reference to, 518
Wax, white, 999
Wax, yellow, 999 ; its characters, composition, tests, and uses, 999
Weber, E. H., reference to, 187
Wedenskii, reference to, 108
Wells, Mr. H., his use of nitrous oxide as an anæsthetic, 179
Wernitz, reference to, 62
Wheaten flour, 973
White, reference to, 117
Indian hemp, 892
Precipitate, 624
Quebracho bark, 892
Wax, 999
Wigner, reference to, 628

Wild marjoram. *See* Origanum
Williams's apparatus used in researches in digitalin, 260, 262
Willow. *See* Salix
Wilwhite, Dr., reference to his use of ether, 179
Wine, spirit of French, 701 ; red wine, 702, 800 ; white wine, 702, 800 ; stronger ditto, 702 ; sherry, 702, 800
Wines, 469
Wines, strong, as cardiac stimulants, 286
Witchhazel. *See* Hamamelis
Witkowski, reference to, 96
Wood, Dog-, 827, 853
Guaiacum, 800
Log-, 822
Quassia, 808
Red sandal-, 816
Worm-, 869
Wood, H. C., references to, 80
Wood charcoal, its preparation and characters, 477 ; its action, uses, and administration, 478
Wood tar, as a stimulating expectorant, 219
Woorari. *See* Curare
Worms, the three chief kinds which infest the intestines, 357 ; list of the principal vermicides, 357 ; and vermifuges, 358 ; and their adjuncts, 358
Wormseed, American. *See* Chenopodium
Wormwood, nature, action, and use of, 869 ; as a stomachic tonic and anthelmintic, 869
Wounds, value of astringents in, 306 ; of styptics, 307
Wourali. *See* Curare
Wundt, references to, 131, 132, 144, 146
Wurrus. *See* Kamala

X.

Xanthine, action of, on muscles, 107
Xanthoxyleæ, 804
Xanthoxylum (prickly ash), as an alterative, 362 ; characters and use of, 804
Xylol, action of, on bacteria, 76

Y.

Yeast, beer, character and uses of, 984
Yeasts, origin and nature of, 66
Yellow cinchona bark, 854
Calisaya bark, 854
Prussiate of potash, 542
Yellow wax, 999
Yolk of egg, 995
Young, Dr., his table for dosage, 438
Ytterbium, symbol and atomic weight of, 10
Yttrium, symbol and atomic weight of, 10 ; physiological action of, 23

Z.

Zabludowski, reference to, 108*n*.
Ziegler's *Pathological Anatomy*, reference to, as translated and edited by Mac-Alister, 69*n*.
Zinc, symbol and atomic weight of, 10 ; physiological action of, 23 ; double salts of, action of, on the cardiac muscle, 276 ; on the capillaries, 277
Zinc, nature, characters, and uses of—
Acetate of, 602
Bromide of, 602
Carbonate of, 600
Precipitated, 600
Chloride of, 601
Iodide of, 602
Oxide of, 600
Of commerce, 599
Phosphide of, 603
Sulphate of, 601
Valerianate of, 603
Zinc chloride, as a caustic, 301
Zinc salts, as an antihydrotic, 387 ; sources of, 597 ; general reactions and preparation of, 598 ; impurities, tests, and general action of, 599
Zinc sulphate, as a caustic, 301 ; as an astringent, 305 ; as a local emetic, 325
Zinci acetas, 599
Bromidum, 599
Carbonas, 599
Precipitatus, 599
Chloridum, 599
Iodidum, 489, 599
Oxidum, 599
Phosphidum, 599
Sulphas, 599
Valerianas, 599, 867
Zincum granulatum, 599
Zingiberaceæ, 970
Zirconium, symbol and atomic weight of, 10
Zuelzer, references to, 81, 299
Zuntz, reference to, 58
Zygophyllaceæ, 800
Zymogens, ferment-forming substances, 65

INDEX OF DISEASES AND REMEDIES.

Abscess.

Belladonna 903. Internally and locally as plaster or liniment.
Calcic Phosphate, 583. Where abscess is large.
Calcic Sulphide, 584. Small doses frequently repeated, to hasten maturation or healing.
Carbolic Acid, 736-738. As dressing, and as injection after evacuation.
Caustic Potash, 533. For opening abscess in liver.
Cod-Liver Oil, 361, 997. In scrofulous cases.
Counter-irritation, 297. To surrounding parts, to check formation or hasten irritation.
Creasote, 609. Same as carbolic acid.
Iodine, 491. As injection into the sac.
Permanganate of Potash, 85. As antiseptic.
Poultices, 412, 783.
Salicylic Acid.
Sulphides, 541, 584. To hasten suppuration.

Acidity.

Acids, 497. Before meals.
Alkalis, 524. After meals.
Bismuth, 658.
Carbolic Acid, 738. To stop fermentation.
Creasote, 739.
Ipecacuanha, 864, 865. In pregnancy.
Kino, 816. Useful along with opium.
Manganese Oxide, 678. Sometimes relieves, probably acting like charcoal.
Mercury, 618. When liver deranged and stools pale.
Nux Vomica, 884. In small doses before meals, especially in pregnancy.
Pulsatilla, 753. 5 m. every four hours in water.
Silver Nitrate, 327, 607. Same as silver oxide.
Silver Oxide, 609. Especially useful when acidity is accompanied by neuralgic pains in stomach.
Tannic Acid, 942.

Acne.

Alkaline Lotions, 534, 535. When skin is greasy.
Arsenic, 643. In chronic acne; generally, though not always, prevents the acne from bromides or iodide of potassium.
Belladonna, 168, 170. As local application.
Bismuth, 658. As ointment or powder.
Borax, 555. Solution very useful.
Glycerine, 883. Both locally and internally.

Acne.

Iodide of Sulphur, 490. In chronic cases.
Mercury, 618. Weak lotions.
Phosphorus, 640. In chronic cases in place of arsenic.
Potassic Bromide, 171, 172. Sometimes useful in moderate doses.
Sulphur, 482. Internally and externally.
Water. Hot sponging several times aday.

Addison's Disease.

Iron, 181 *et seq.* Antemetics and tonics.

After-pains.

Belladonna, 903. As ointment.
Camphor, 629. Useful when combined with morphia, 10 grs. with ½ gr. of morphia.
Chloroform, 703. Liniment to abdomen along with soap liniment.
Chloral, 717. In large doses arrests the pains.
Cimicifuga, 754. Diminishes excitement.
Ergot, 982. To keep the uterus constantly contracted and prevent accumulation of clots in its cavity, and consequently the pains which they would occasion.
Gelsemium, 891. In 20 m. doses stops pains.
Morphia and Atropia, 766, 903. Hypodermically very useful, $\frac{1}{6}$-$\frac{1}{4}$ gr. morphia with $\frac{1}{100}$ gr. of atropia.
Opium, 775. The same as Morphia.
Poultices, 412. Warm to the hypogastrum, relieve.
Quinia, 862. 5-10 grs. night and morning, with neuralgic after-pains which do not yield to opiates.

Albuminuria.

Aconite, 751. In high temperature.
Alkalies, 525. Diuretics.
Arbutin, 877.
Cannabis Indica, 947. In hæmaturia.
Cantharis, 1002. In hæmaturia, after acute symptoms have gone—1 m. every three hours.
Chalybeate Waters, 595, 672. Not very useful in chronic cases.
Chimaphila, 380, 878. Decoction of extract when urine scanty, or in hæmaturia.
Gallic Acid, 944. In acute cases 5-10 grs.
Iron, 672. Useful often—best as chalybeate waters.
Lead, 630. Lessens albumen.

Albuminuria.

Milk Cure, 989.
Turkish Baths, 415. Useful in chronic cases.
Turpentine, 379, 951. Sometimes very useful, diminishes albumen, and acts as diuretic.

Alcoholism.

Ammonia, 321. Aromatic spirits of, as substitute for alcohol, to be taken when the craving comes on.
Arsenic, 643. To lessen vomiting in drunkards.
Bromides, 547. Useful during delirium tremens, or to lessen irritability.
Capsicum, 879. As substitute for alcohol.
Chloral, 717. To quiet nervous system and induce sleep.
Lupuline, 948. Along with capsicum as substitute for alcohol, also to quiet nervous system in delirium tremens.
Nux Vomica, 884. As tonic and stimulant, both to nervous system, and generally to aid digestion.
Opium, 775. May be necessary to produce sleep.
Orange, 161, 162. Slowly sucked, a substitute for alcohol.
Phosphorus, 365, 640. In chronic cases as nervine tonic.
Picrotoxine, 274, 758, 759. For tremors.
Quinia, 862. As tonic and in gastric catarrh.
Water, Cold, 162. A glass taken in small sips at a time as substitute for alcohol.
Zinc Oxide, 599, 600. In chronic alcoholic dyspepsia, and nervous debility.

Alopecia.

Ammonia, 568. Very useful—℞ ol. amygd. dul. Liq. ammoniæ āā f. ʒj spt. Rosmarini, aquæ, mellis āā f. ʒiij mm. ft. lotio (E. Wilson).
Arsenic, 644. Internally.
Cantharides Tinc., 1002. One part to eight of castor oil rubbed in roots of hair morning and night.
Glycerine, 883. Very useful; either alone or in combination, appears greatly to assist
Nitric Acid, 501. With olive oil in sufficient quantity just to make it pungent.
Shaving. Sometimes useful after illness.
Sulphur Iodide, 490. Useful both internally and externally.

Amaurosis and Amblyopia.

Arnica, 873. Sometimes useful.
Rue, 802. In minute doses in functional dimness of vision.
Santonin, 870. Sometimes useful in later stages of iritis and choroiditis.
Seton, 297. In temple for a long time sometimes useful.
Strychnine, 246, 883. Sometimes very useful.
Veratrine, 965. To eyelids and temples. Care must be taken to keep out of the eye.

Amenorrhœa.

Aconite, 751. When menses suddenly checked, as by cold, &c.
Aloes, 961. Alone or with iron.
Ammonium Chloride, 567. In headache, malarial.
Apiol (oil of parsley), 879. 15 grs. just before a period, or for some days before.
Arsenic, 643, 644. Along with iron in anæmia.

Amenorrhœa.

Cimicifuga, 754. Sometimes gives good results.
Colocynth, 842, 843. In anæmia with constipation.
Electricity. Locally applied, sometimes useful.
Ergot, 393.
Gold, Salts, 679.
Ignatia, 884. In hysteria.
Iron, 666, 672. In anæmia.
Manganese, 398, 679. Sometimes very useful.
Nux Vomica, 887, 884.
Pulsatilla, 753. Like Aconite.
Rue, 393. In atonic condition of ovaries of uterus.
Sanguinaria, 862, 779. Like Rue.
Savin, 393. Like Rue.
Senega, 785. A saturated decoction in large doses of a pint daily about two weeks before period.
Serpentaria, 932. In anæmia.
Silver Nitrate, 305, 607. Locally, to os uteri at period.
Sitz Baths, 409. Hot, alone, or with mustard, for some days before the period.
Spinal Ice Bag, to lumbar vertebræ.

Anæmia.

Acids, 496, 497.
Arsenic, 643, 644. Very useful, along with, or in place of, iron.
Cold Sponging, 367, 408.
Galvanization.
Hypophosphites of Lime, 583, or Soda, 557. In cases of nervous debility care must be taken that they do not derange the digestion.
Iron, 666, 672. Very useful where stomach is at all irritable. The carbonate is often best. Where mucous membrane very flabby large doses of the perchloride. Chalybeate waters more often succeed than pharmaceutical preparations. They may be mutated by one drop of the solution in a tumbler of water.
Lactophosphate of Lime, 583. During nursing, or where drain has taken place from body in shape of pus.
Manganese, 678, 679. May be given along with iron—not much use alone.
Nux Vomica, 289, 884. Useful sometimes along with iron.
Pancreatin, 319. In feeble digestion.
Pepsin, 319. In feeble digestion.
Phosphate of Lime, 583. During growth, or where system enfeebled by drain of any kind.
Quinia, 87, 862.
Wines, 236. Along with food to aid digestion.

Aneurism.

Aliment. Low diet; absolute rest.
Chloroform, 726, 727. Inhaled to relieve dyspnœa.
Electrolysis. Sometimes useful in causing coagulation within the sac.
Ergot, 980, 981. As adjunct to rest.
Lead Acetate, 631. Useful, combined with rest.
Potassic Iodide, 219, 545. Very useful in doses of 30 grs.
Veratrum Viride, 276, 296. Along with opium in quieting circulation.

Angina Pectoris.

Aconite, 296, 749, 751.
Arsenic, 643, 644. To prevent paroxysms.
Chamomile, 871 In hysterical symptoms.

Angina Pectoris.

Ether, 706. To diminish pain.
Laurocerasus, 836.
Morphia, 167, 169, 766. Hypodermically.
Nitrite of Amyl, 710, 711. Gives great relief during paroxysms.
Nitrite of Soda, 550. Less rapid than nitrite of amyl, but has more power to prevent return of symptoms.
Nitro-Glycerine, 712, 713. Like nitrite of soda.
Phosphorus, 365, 640. During intervals to lessen tendency.
Quinia, 862. When any malarious taint is present.
Strychnia, 205, 274, 888. Sometimes useful in mild cases, in very small doses.
Turpentine, 218, 951. Locally to the chest during paroxysms.

Anus, Fissure of.

Belladonna, 168, 170, 903. Locally, relieves spasms.
Castor Oil, 339, 935. To keep motions soft.
Collodion, 790. Locally, to protect.
Hydrastis, 756. Local application.
Iodoform, 728, 729. Locally, to heal and relieve pain.
Iodo-tannin (solution of iodine in tannin). Useful locally.
Opium and Gall Ointment, 761. Relieves pain.
Potassic Bromide, 547. With five parts of glycerine locally.
Rhatany, 785. Injected after the bowels have been opened by enema.
Sulphur, 339. To keep motions soft.
Tannin, 943. Useful as local application.

Aphonia.

Alum, 585-587. As spray in chronic congestion of throat and larynx, with hoarseness.
Ammonium Chloride, 567. As vapour in laryngeal catarrh.
Atropia, 903. In hysterical aphonia.
Benzoin, Tincture of, 219, 880. Inhaled in laryngeal catarrh.
Borax, 555. A piece the size of a pea slowly sucked.
Glycerine of Tannin, 882, 942. Locally, to pharynx.
Ignatia, 884. Like Atropia.
Ipecacuanha, 864, 865. Wine as spray in laryngeal catarrh.
Nitrate of Potash, 537. Like Borax.
Nitric Acid, 502. In hoarseness from fatigue or indigestion.
Rue, Oil of, 802. As inhalation in chronic catarrh.
Sulphurous Acid, 498. As spray or inhalation, in clergyman's sore throat.
Turkish Bath, 415. In acute laryngeal catarrh.
Uranium, Nitrate of, 10. As spray in very chronic catarrh.

Aphthæ.

Bismuth, 658. As local application.
Borax, 555. As honey or as glycerine, either alone or with chlorate of potash.
Copper Sulphate, 605. Weak solution painted over the aphthæ.
Coptis. Infusion is employed in New England.
Glycerine, 883.
Mercury, 616. In the form of hydr. cum creta in children, to remove the indigestion on which aphthæ frequently depends.
Mineral Acids, 496. Dilute solution as paint.

Aphthæ.

Potassic Chlorate, 379. Exceedingly useful as wash, 10 grs. to the oz., alone or with borax, also given internally.
Potassic Iodide, 545. As local application, solution of 1-5 grs. to the oz.
Quinia, 862. 1 gr. every two or three hours in aphthæ in infants, consequent on diarrhœa.
Rhubarb, 924. To remove indigestion, as compound rhubarb powder.
Salicylic Acid, 741. As local application.
Sulphurous Acid, 498. As solution or spray.

Apoplexy.

Aconite, 751. To lower blood-pressure and prevent further hæmorrhage, where pulse strong and arterial tension high.
Cold Water, 367. To the head when face congested.
Colocynth, 340, 843. As purgative.
Croton Oil, 340, 934. As purgative, one drop on back of tongue, or part of a drop every hour.
Diet and Hygiene, Prophylactic, Butcher's meat and stimulants to be taken very sparingly, exposure to heat, over exertion, and especially anger, to be avoided.
Elaterium, 340, 844. In suppository, or as enema, during attack.
Electricity. To promote absorption, after partial recovery has taken place.

Appetite, Impaired.

Food. Savoury, well-cooked.
Ignatia, 884. Corrects diseased appetite and hysteria.

Atheroma.

Ammonium Bromide, 572. To promote absorption.
Arsenic, 643. Often useful, especially when symptoms of imperfect action of kidneys.
Cod-Liver Oil, 997.
Digitalis, 915. Requires caution.
Phosphorus, 365, 640. In minute doses, along with cod-liver oil.
Quinia, 862.

Ascites.

Apocynum Cannabinum, 892. As diuretic.
Arsenic, 643, 644. In old persons with feeble heart.
Copaiba, 379, 826. Especially useful in hepatic dropsy.
Digitalis, 915. Best in cardiac dropsy; its action is increased by combination with squill and blue pill.
Elaterium, 340, 844. As hydragogue cathartic.
Jaborandi, 897. In anasarca.
Jalap, 897. In compound powder as hydragogue cathartic.
Milk Diet, 989. Sometimes very useful when kidneys are inadequate.
Stillingia, 862, 933. In hepatic dropsy.

Asthenopia.

Atropia, 904. To prevent spasms.

Asthma.

Aconite, 751. In spasmodic cases, also in asthma consequent on nasal catarrh in children.
Amyl Nitrite, 710. Sometimes checks paroxysm.

ASTHMA.

ANTIMONY, 657. In asthmatic conditions in children, $\frac{1}{30}$ gr. of tartar emetic every quarter of an hour.
ARSENIC, 643, 644. In small doses in cases associated with bronchitis or hay fever. Inhaled as cigarettes.
ASAFŒTIDA, 847.
BELLADONNA, 904. Internally, in large doses or as cigarettes.
BROMIDES.
CANNABIS INDICA, 947.
CHLORAL, 717. During paroxysm.
CHLOROFORM, 722. Relieves when inhaled from tumbler or with warm water.
COFFEE, 865. Very strong during paroxysm.
COLCHICUM, 968, 969. In gouty cases.
DATURA. *See* STRAMONIUM.
ETHER, 705. In full doses at commencement of attack.
EUCALYPTUS, 840, 841. Sometimes along with stramonium, belladonna, and tobacco.
GALVANISM OF PNEUMOGASTRIC REGION. Positive pole beneath mastoid process, negative pole to epigastrium.
GRINDELIA, 875. To prevent or cut short attack.
IPECACUANHA, 865. As spray in bronchial asthma, especially in children.
LOBELIA, 877. To prevent and cut short paroxysm.
NUX VOMICA, 219.
OPIUM, 214. Hypodermically, during paroxysm.
OXYGEN, 474, 475. As inhalation during paroxysm.
PEPSINE, 319, 990. Exceedingly useful in preventing attacks
POTASSIC IODIDE, 545. In large doses, when asthma due to acute bronchial catarrh.
POTASSIC NITRATE, 538. Inhalation of fumes of touch paper relieves paroxysm. Sometimes advisable to mix a little chlorate with it.
QUINIA, 205, 862. During intervals when attacks are periodical.
SILVER NITRATE, 607. Has been injected into trachea.
STRAMONIUM, 906. Sometimes very useful. May be made into cigarettes, or 20 grs. of dried leaves may be mixed with nitrate of potash, and the fumes inhaled. A little powdered ipecacuanha may often be added.
SULPHUROUS ACID, 498.
TOBACCO, 908. Smoking is sometimes beneficial.

ASTIGMATISM.

SUITABLE GLASSES.

ATROPHY.

ARSENIC, 644. In muscular atrophy.
ELECTRICITY.
MASSAGE, 107, 416.
OLIVE OIL, 882, 883. Inunction to atrophied parts.

BALANITIS.

ASTRINGENT LOTIONS. Alum, 587; sulphate of zinc, 601.
LIME WATER, 579. As lotion.
MERCURY, 621. $\frac{2}{3}$ gr. chlor. con. to an oz. lime-water as lotion.
OIL, 882.

BED SORES.

ALCOHOL, 300, 692. As wash, to prevent.
ALUM, 586. With white of egg, as local application.

BED SORES.

CHARCOAL, 477. As poultices, to stop bed sores.
GALVANIC COUPLET. Of zinc and silver; one element on sore, the other on adjacent part.
GLYCERINE, 883. Prophylactic local application.
IODOFORM, 729.
SILVER NITRATE, 607. Dusted over open bed sores.

BILIOUSNESS.

ACONITE, 750. As adjunct to podophyllum.
ALKALIES, 523, 524.
ALOES, 339. In constipation.
AMMONIUM IODIDE, 573. In catarrh of duodenum and biliary ducts.
ANGOSTURA, 802. In bilious fevers.
BRYONIA, 885. In bilious headache.
CALUMBA, 757. As stomachic tonic.
CARLSBAD WATER, 556. A tumbler sipped warm during dressing very useful.
HORSE EXERCISE.
HYDRASTIS, 756. When chronic gastric catarrh is present.
MANGANESE, 678, 679. In gouty cases.
MERCURIAL CATHARTICS, 618. In moderate doses night and morning, or in small doses more frequently repeated. Especially useful when stools are pale.
MILK CURE, 989. In obstinate cases.
MINERAL ACIDS, 503. Nitro-hydrochloric acid especially useful.
PODOPHYLLUM, 340, 755. In place of mercury when stools dark.
RHUBARB, 339, 353, 355, 922, 1005.
SAL-AMMONIAC, 568. In hepatic abscess.
STILLINGIA, 362, 933. In place of mercury.

BLADDER, IRRITABLE.

AQUAPUNCTURE.
BELLADONNA, 391, 903.
BENZOIC ACID, 383. In large, prostate, and alkaline conditions of urine.
BENZOATE OF AMMONIA, 880. Like Benzoic Acid.
CANTHARIDES, 1001. In women, without acute inflammation.
CUBEBS, 379, 937. Like Cantharides.

BLADDER, PARALYSIS OF.

ARNICA, 873.
CANNABIS INDICA, 947. In retention, from spinal disease.
CANTHARIDES, 391, 1001. In atonic bladder.
ERGOT, 983. In paralysis, either in bladder or sphincter, when bladder so that urine is retained, and incontinence in sphincter.
GALVANISM.
STRYCHNIA, 888.

BLEPHARITIS.

ALUM, 585-587. After acute symptoms subside.
BISMUTH, 327, 658. Equal parts of the subnitrate and glycerine as local application.
HYDRASTIS, 756. As lotion.
MERCURY (UNGUENTUM HYDRARGYRI NITRATIS), 625. Most useful application. If too strong, dilute with vaseline or simple ointment.
PULSATILLA, 753. Internally and locally.
TANNIN, 382.

Boils.

Arsenic, 365, 643. To lessen tendency to recurrence.
Belladonna, 903. Internally, or as local application.
Camphorated Alcohol, 698. As local application in early stage.
Carbolic Acid, 736-738. Injection.
Collodion, 790. Painted over whole surface to abort in papular stage, and over base, leaving centre free, in pustular stage.
Counter-irritation, 447. By plasters surrounding the boil.
Opium, 775. Locally to remove pain.
Poultices, 412. To relieve pain and hasten maturation.
Silver Nitrate, 607. Strong solution painted over the skin round boil.
Strapping, 631. Properly applied gives great relief.
Sulphides, 541, 584. In small doses to abort or hasten maturation.

Bone, Diseases of.

Cod-liver Oil, 218, 997. In scrofulous conditions.
Iodine, 491, 997. Alone, or with cod-liver oil.

Breath, Fœtid.

Camphor, 929.
Carbolic Acid, 736-738. Dilute solution as wash to mouth.
Chlorine, 487, 587. Liq. chlor. and chlor. of lime as lotion.
Permanganate of Potash, 85, 540. As wash to mouth.

Bright's Disease.

Baths, 405 *et seq.* Warm water and hot air and Turkish, to increase action of skin.
Broom, 379, 815. As diuretic.
Caffeine, 798. To increase secretion of solids.
Cannabis Indica, 947. As diuretic when hæmaturia.
Chimaphila, 878.
Cod-Liver Oil, 218, 997.
Counter-irritation, 297, 298. Dry cupping most useful when tendency to uræmia.
Elaterium, 844. As hydragogue cathartic for dropsy.
Eucalyptus, 841.
Gallic Acid, 944. Lessens albumen.
Gold, Chloride of, 679. In contracted kidney.
Hydrastis, 756. Lessens albumen.
Iron, 672. To diminish anæmia.
Jaborandi, 807. In uræmia and dropsy.
Juniper, Oil of, 955 Diuretic.
Lead, 629. Lessens albumen.
Milk Cure, 989. Pure skim milk diet sometimes very useful when tendency to uræmia.
Nitrous Ether, 379. As diuretic.
Potassic Bitartrate, 340, 379. As hydragogue cathartic and diuretic.
Potassic Bromide, 171, 172. In uræmic convulsions.
Potassic Iodide, 545.
Tartrates, 536, 554, 673. As diuretics.
Turpentine, 379. As diuretic.
Water. In large draughts as diuretic when excretion of solids is deficient, and in dropsy.

Bronchiectasis.

Chlorine, 487. As inhalation to lessen fœtor.

Bronchiectasis.

Creasote, 739. As inhalation.
Iodine, 491. As inhalation.
Phosphates and Hypophosphites, 556, 583, 677.
Quinia, 205, 862.

Bronchitis, Acute.

Aconite, 199, 751. ½-1 m. every hour at commencement.
Ammoniacum, 848. Very useful in old people.
Ammonium Carbonate, 570. Where much expectoration and much depression.
Asafœtida, 847. Like Ammoniacum.
Cimicifuga, 754. In acute catarrh and acute bronchitis when active symptoms have subsided.
Colchicum, 365. In gouty cases.
Counter-irritants, 302, 398, 781. Dry cupping most efficient, in acute cases; mustard leaves; mustard poultices.
Cubebs, 938. When secretion copious.
Ipecacuanha, 218, 219, 220. When expectoration scanty, dryness in chest, ipecacuanha in large doses; also when expectoration has become more abundant, but difficult to expel.
Lobelia, 219. When cough paroxysmal, and expectoration slight.
Nitric Acid, 501, 502. When expectoration free and too copious.
Opium, 214, 287, 288. As Dover's powder to cut short attack, and along with expectorants to lessen cough.
Quinia, 857. To reduce temperature.
Sanguinaria, 779. After acute symptoms have subsided.
Tartar Emetic, 219, 324, 325. In dry stage to promote secretion.
Turpentine, 218. When expectoration very profuse; also as inhalation.

Bronchitis, Capillary.

Ammonium Carbonate, 570. Much expectoration and lividity commencing, and emetic.
Ammonium Chloride, 219
Ammonium Iodide, 573. In small rapid doses relieves much.
Camphor, 929. As expectorant.
Cupping, 367. Four to six dry cups over the back often give very great relief, and if the pulmonary congestion appears very great wet cups should be placed instead, and 8-10 oz. of blood withdrawn from adult.
Ipecacuanha, 218, 219, 220. As expectorant and emetic.
Mustard, 220. As poultices.
Poultices, 220. Over whole chest.
Serpentaria, 932. In children.

Bronchitis, Chronic.

Ammonia, 219. When there is difficulty in bringing up expectoration.
Ammoniacum, 848. Very useful, especially in elderly people.
Ammonium Chloride, 219
Antimony, 219. When secretion scanty.
Arsenic, 643, 644. In emphysema and asthmatic attack as cigarettes.
Asafœtida, 847.
Balsam of Peru, 219. When expectoration copious.
Balsam of Tulu, 219. The same.
Benzoin, 219. As inhalation or as spray.
Camphor, 929.
Carbolic Acid, 737. As inhalation or as spray.
Codeia, 767. In place of opium when the latter disagrees.

Bronchitis, Chronic.

Cod-Liver Oil, 218, 996, 997. One of the most useful of all remedies.
Colchicum, 969. In acute cases.
Copaiba, 826. Like Balsam of Peru.
Digitalis, 214, 219. Where heart feeble.
Emetic, 219.
Eucalyptus, 841.
Galbarum, 848.
Gallic Acid, 944.
Hydrastis, 756. In chronic coryza.
Iodine, 491. As inhalation.
Iron, 665. When expectoration is profuse.
Koumiss Cure, 989. Sometimes very useful.
Lobelia, 877. When there is spasmodic dyspnœa.
Opium, 214. To lessen secretion and cough.
Phosphates, 556, 583, 677.
Senega, 219, 325, 785. When expulsive efforts are feeble.
Serpentaria, 932. Like Senega.
Squill, 219, 325, 959. Where expectoration is thick.
Sulphur, 219, 482. Where expectoration copious.
Sulphurous Acid Gas, 498. As inhalation or spray.
Sumbul, 182, 851.
Tar, 219, 954. To lessen secretion and allay cough.
Turpentine, 218.

Bronchorrhœa.

Ammoniacum, 848.
Ammonium Iodide, 573. Small doses frequently repeated.
Asafœtida, 847.
Eucalyptus, 841. Sometimes very useful.
Grindelia, 874, 875.
Iodine, 491. As counter-irritant to chest, and as inhalation.
Lead Acetate, 631. To lessen secretion.
Spinal Ice Bag. To lessen secretion.
Sulphurous Acid Gas, 499. As inhalation or spray.

Bruises.

Aconite, 748. Liniment locally, to relieve pain.
Arnica, 873. As local application, no more use than alcohol, and sometimes gives rise to much inflammation.
Capsicum, 899. To remove discoloration of bruise.
Oil of Bay. Same as Capsicum.
Opium, 169. Local application to relieve pain.
Sulphurous Acid, 499. As local application constantly applied.

Bubo.

Ice, 216. To relieve pain and lessen inflammation.
Iodine, 491. As counter-irritant applied round the bubo.
Iodoform, 728, 729. As local application.
Mercury, 625. As local application after opening bubo, when syphilitic infection is great.
Nitric Acid, 502. As local application to indolent bubo.
Potassio-tartrate of Iron, 534. Local and general.
Silver Nitrate, 608. Lightly applied to surface in indolent bubo.
Sulphides, 541, 584. To check suppuration.
Tartar Emetic, 224, 225. When inflammation acute and fever considerable.

Bunion.

Iodine, 491. Painted on in indolent forms.
Rest. When thickened and painful. Pressure is removed by thick plasters, with a hole in the centre.

Burns and Scalds.

Boracic Acid, 503. Saturated watery solution.
Carbolic Acid, 735-738. One to six of olive oil, locally.
Collodion, 790. Flexible, to protect from air.
Cotton Wool. To protect from irritation and lessen pain.
Lead Carbonate, 631. As white paint for small burns.
Lime, 543, 579, 789. As lin. calc., or lime water with linseed oil.
Phytolacca, 924. To relieve pain.
Salicylic Acid, 740, 741. 1 to 60, olive oil.
Turpentine, 951. Local, to severe burns.
Warm Bath, 411. Keep whole body, with exception of head, totally immersed for some days in very extensive burns or scalds. It relieves pain, although it may not save life.

Bursitis.

Blisters, 302. Most useful.
Fomentations. To relieve pain.
Iodine, 543. When chronic, lin. iodi. may be used as a blister, or the liquor, after blistering or aspiration.

Cachexiæ.

Air. Fresh.
Aliment. Nutritious.
Arnica, 873. Internally, in bad cases.
Arsenic, 643, 644. In malarial, also in cancerous, cachexiæ.
Baths, 415. Turkish bath useful.
Cholagogues, 340, 356. Most useful before, or along with, other remedies.
Eucalyptus, 841.
Eunonymin, 340. As cholagogue.
Grape Cure.
Hydrastis, 756. In malaria.
Iron, 666. In all anæmic conditions.
Lime Phosphates, 583. In scrofulous phthisis and mal-nutrition.
Manganese, 678. Along with iron and iodine.
Massage, 107, 416. Exceedingly useful.
Mercury, 340. In syphilitic cases. *See* Cholagogues.
Nitric Acid, 288, 501. In debility after acute disease.
Oil and Fats, 218, 997. Cod-liver oil very useful. Cream as an addition to food.
Phosphates, 355, 556, 583, 677. In cachexiæ attended with much discharge.
Podophyllin, 340, 754. As cholagogue.
Potassic Iodide, 545. In syphilitic and resulting conditions.
Purgatives, Saline, 340. As adjuncts to cholagogues.
Sarsaparilla, 957. In syphilis.

Calculi, Biliary.

Aliment. Absence of starch and fat recommended.
Alkalies. Vichy water useful.
Carlsbad Water, 556. Useful as prophylactic.
Chloral, 717. To relieve pain during paroxysm.
Chloroform, 726, 727. Inhalation from tumbler, most useful to relieve paroxysm.

Calculi, Biliary.

Counter-Irritants, 413. Mustard poultices to relieve pain during paroxysm.
Morphia, 766. ¼ gr. with $\frac{1}{120}$ gr. atrophia. subcutaneously to relieve pain and vomiting in paroxysm.
Nitro-Muriatic Bath, 383, 413. To cause expulsion of calculus, and to relieve pain.
Salicylate of Soda, 741. As prophylactic.
Sodium Phosphate, 353. In 20 or 30 gr. doses before each meal as prophylactic. Should be given in plenty of water.
Turpentine and Ether, 379, 951. Equal parts to relieve pain during paroxysm; also occasionally as prophylactic along with a course of Carlsbad or Vichy water.

Calculi, Renal and Vesical.

Alkalies, 535, 554. To resolve calculi, potash and soda to be used.
Alkaline Mineral Waters. Especially Vichy.
Ammonium Benzoate, 574. To resolve phosphatic calculi.
Anæsthetics, 175, 177. To relieve pain during passage of calculus.
Calumba, 757. To relieve vomiting.
Castor Oil, 339, 935. As purgative.
Chloroform, 726, 727. As in biliary calculi.
Cotton Root, 788. As decoction to relieve gravel and strangury.
Counter-Irritants. To lessen pain during passage of calculus.
Mineral Waters, especially Wildungen.
Morphia, 766. Hypodermatically, as in biliary calculi.
Nitric Acid, 502. Dilute, as injection into the bladder to dissolve calculi.
Potassium Citrate, 379. In hæmaturia with uric acid crystals.
Water, Distilled. As drink.

Cancer.

Acetic Acid, 503. As injection into tumours.
Arsenic, 641. As local application, causes cancer to slough out. Sometimes successful when the knife fails, but is dangerous. Internally, in cancer in stomach lessens vomiting. Supposed to retard growth of cancer in stomach and other parts.
Belladonna, 903. Locally relieves pain. Used internally also.
Bismuth, 658, 659. To relieve pain and vomiting in cancer of stomach.
Bromine, 488. As caustic to use round cancer.
Carbolic Acid, 736-738. As application or injection into tumour to lessen pain, retard growth, and diminish fœtor.
Carbonic Acid, 509. To relieve pain in uterine cancer.
Charcoal Poultices 477. To relieve pain and fœtor.
Chloral, 717. To lessen pain.
Chloroform, 726, 727. Vapour as local application to ulcerated cancer.
Chromic Acid, 301. As caustic.
Citric Acid, 507. As lotion to allay pain $\frac{1}{60}$.
Condurango, 893.
Conium, 846. As poultices to relieve pain. Used internally also.
Glycerine of Tannin, 882, 942. Mixed with iodine, to check discharge and remove smell in uterine cancer.
Hydrastis, 756.
Hyoscyamus, 903. Bruised leaves locally applied.
Iodoform, 172, 729. Locally, to lessen pain and fœtor.

Cancer.

Iron and Manganese, 672, 678. Internally, as tonics.
Opium, 16, 169. Locally and generally, to relieve pain.
Papain, 836. As local application or injection.
Pepsin, 990. As injection into tumour.
Potassa Fusa, 534. As escharotic.
Poultices, 412. To relieve pain.
Salicylic Acid, 741. Locally applied as powder or saturated solution.
Vienna Paste, 534.
Warm Enemata. To lessen pain in cancer of rectum.
Zinc Chloride, 301, 607. As caustic.
Zinc Sulphate, 301, 599. As caustic.

Cancrum Oris.

Arsenic, 643, 644. Internally.
Nitric Acid, 502. Undiluted as local caustic.
Potassic Chlorate, 379. Internally.
Quinia, 862. As syrup or enema.

Carbuncle.

Belladonna Extract, 899. With glycerine, as local anodyne.
Calcic Sulphate, 584. $\frac{1}{10}$ gr. hourly useful.
Carbolic Acid, 737. As wash and injection after spontaneous discharge, or on lint after opening.
Collodion, 790. Round base, leaving opening in centre.
Iodine, 491. Locally, to lessen pain and inflammation.
Opium, 169. Locally, mixed with glycerine.
Poultices, 412. To relieve pain.
Strapping. Concentrically, leaving centre free, lessens pain.

Caries.

Cod-Liver Oil, 218, 997.
Gold, 679. In syphiloma of bone.
Iodine, 491. Locally and internally.
Phosphates of Lime and Iron, 583, 687. Useful.
Phosphoric Acid, 505. Diluted, 1 in 8 of water, locally.
Potassic Iodide, 545. In syphilitic cases.
Sarsaparilla, 957.
Villate's Solution—Cupri. sulph.zinc.sulph. āā partes xv,liq. plumb. subacetat part xxx, acid acet. part cc. as injection.

Catalepsy.

Turpentine, 950, 951. As enemata and embrocations to spine during paroxysms.

Cataract.

Codeia, 766. In diabetic cases.
Diet and Regimen. Nutritious in senile cases. Sugar and starch to be avoided in diabetic cases.
Galvanism. In early stage.
Mydriatics, 186-189. To dilute pupil as a means of diagnosis.

Catarrh, Acute Nasal.

Aconite, 199, 206, 750. Internally at commencement.
Aconite and Belladonna, 758, 899. In sore throat and cold, one drop of tinct. aconite to two of belladonna every hour.
Aconite Liniment, 748. To outside of nose in paroxysmal sneezing and coryza.
Ammonia, 162. As inhalation in early stage

Catarrh, Acute Nasal.

Ammonium Iodide, 573. 1 gr. every two hours.
Arsenic, 643, 644. Internally or as cigarettes in paroxysm and chronic cases.
Baths. Hot foot bath, 411; Turkish, at commencement, 415; cold bath is prophylactic, 405.
Belladonna, 899. 5 m. of tinc., and afterwards one or two every hour, to throat, dry in acute nasal catarrh, with profuse watery secretion, and in ordinary sore throat.
Bismuth, as Ferrier's snuff—Bismuth subnit. ʒii, acacia pulv. ʒii, morph. hydrochlor. gr. ii.
Camphor, 929. As inhalation.
Carbolic Acid, 736-738. An inhalation, or much diluted as spray. As gargle, 1 in 100, when catarrh tends to spread from nose into throat and chest, or to ascend from throat into nose.
Cimicifuga, 754. In coryza accompanied by rheumatic or neuralgic pains in head and face.
Cold Powder—Camph. partes v, dissolved in ether to consistence of cream, add ammon. carbonat. partes iv, and pulv. opii pars j. Dose, grs. iij-x. To break up or modify cold.
Cubebs, 937. Powder as insufflation; also smoked.
Eucalyptus, 841.
Ferrier's Snuff, *vide* Bismuth.
Hydrastis, 756. Externally and internally.
Iodine, 491. As inhalation.
Iodoform, 729, and Tannin, 943. As insufflation.
Ipecacuanha, 865.
Nux Vomica, 219. In dry cold in the head.
Oil, 883. Inunction to whole body to lessen susceptibility. Locally to nose. Sometimes ointment may be used instead.
Opium, 368. As Dover's powder at commencement.
Potassic Bichromate, 542. Solution locally, 1 to 10 gr. in 4 oz.
Potassic Chlorate, 538. Eight or ten lozenges a day to check.
Potassic Iodide, 545. 10 gr. at bedtime to avert acute coryza.
Pulsatilla, 753. Warm lotion applied to interior of nares.
Quinia, 205, 861. 10 gr. of quinia to ½ gr. morphia at commencement.
Salicylic Soda, 559. 2½ gr. every half hour to relieve headache and neuralgia associated with coryza.
Sanguinaria, 779. Internally, and powder locally.
Sea-water Gargle.
Senega, 785.
Spray. Useful means of applying solutions already mentioned.
Sulphurous Acid, 498. As inhalation, spray, or fumigation.
Tartar Emetic, 324, 325. $\frac{1}{20}$ to $\frac{1}{12}$ gr. at commencement.
Veratrum Viride, 963. If arsenic fails.

Catarrh, Chronic Nasal.

Alum, 586, 587. In powder, insufflation, or in solution by douche.
Ammonia, 569. Inhalation.
Bromine, 488. As powder.
Carbolic Acid, 737. 1 to 100 as spray, or 1 to 200 as douche. 1 part with 4 of iodine tinc. as inhalation.
Cod-Liver Oil, 218, 297

Cerebral Anæmia.

Amyl Nitrite, 710, 711. To act on vessels.
Camphor, 158, 929.
Chloral, 716, 717. In small doses, with stimulants.

Cerebral Anæmia.

Digitalis, 165.
Electricity.
Glycerine, 882, 883. Like Nitrate of Amyl.
Iron, 672
Nux Vomica, 289, 884.
Phosphorus, 365, 640. To supply nutriment.

Cerebral Concussion.

Rest. Absolute to be enjoined.
Stimulants. To be avoided.
Warmth. To extremities.

Cerebral Congestion.

Aconite, 750, 751. In acute cases.
Arsenic, 643, 644. In commencing atheroma of cerebral vessels and tendency to drowsiness and torpor.
Belladonna, 901, 903. Very useful.
Bromides, 546, 558. Very useful.
Cathartics, 339 *et seq.* To lessen blood-pressure.
Chloral, 716, 717. When temperature high.
Colchicum, 968, 969. In plethoric cases.
Colocynth, 842, 843. As purgative.
Diet, moderate, animal food sparingly, and stimulants to be avoided.
Galvanism of head and cervical sympathetic.
Hydrocyanic Acid, 515.
Venesection, 367
Water, 408, 411. Cold douche to head, and warm to feet, alternately hot and cold to nape of neck.

Cerebritis.

Ammonium Chloride, 567. Locally.
Ice, 410.

Chancre.

Carbolic Acid, 736-738. Locally.
Caustics, 301, 488, 625. Chromic acid, bromine, and acid nitrate of mercury.
Hydrogen Peroxide, 476. Constantly applied to destroy specific character.
Iodoform, 729. One of the best remedies.
Mercury, 614, 615, 622. Internally. Black wash locally.

Chancroid.

Carbolic Acid, 736-738. As injection and local application.
Caustics, 302. Sometimes necessary.
Ferric Iodide, 489. Internally in phagedenic cases, or debility.
Ferrum Tartaratum, 536, 669. Like Ferric Iodide.
Iodoform, 729. Very useful.
Mercury, 625. Acid nitrate as local application.
Nitric Acid, 502. Locally as caustic.

Chapped Hands and Lips.

Benzoin, 879. Compound tincture, 1 part to 4 of glycerine.
Collodion, 790.
Glycerine, 882, 883. Saturated with half the quantity of eau de cologne.
Hydrastis, 756. As lotion.
Sulphurous Acid, 498. As lotion or as fumigation.

Chest Pains.

Belladonna, 901, 903. In pleurodynia, as plaster or ointment.
Iodine, 491. In myalgia.

Chicken Pox.

Aconite, 751.
Ammonia, Acetate of, 287, 288, 569.
Bath, 405, 411. Cold in hyperpyrexia. Warm, as diaphoretic.
Compress, Cold, 410. If sore throat.
Laxatives, 339.

Chilblains.

Arnica, 300, 873. Useful.
Balsam of Peru, 816, 817. As ointment when broken.
Basilicon, 952. Ointment.
Cajeput Oil, 300, 839.
Capsicum, Tincture, 899. Locally, when unbroken.
Carbolic Acid, 489, 735, 941. With tinc. of iodine and tannic acid as ointment.

Chlorosis.

Arsenic, 365. In place of, or along with, iron.
Benzoin, 880.
Cocculus Indicus, 757. In amenorrhœa and leucorrhœa.
Ergot, 983. In chlorotic amenorrhœa.
Galvanization.
Hypophosphites of Lime, or Sodium, 557, 583.
Iron, 668. Carbonate, useful form. Sometimes best as chalybeate waters.
Manganese, 398, 678. In amenorrhœa.
Massage, 107. Useful.
Nux Vomica, 289. 884. Useful.
Oils and Fats. As inunction.
Pepsin, 319, 990. When digestion imperfect.
Purgatives, 339. Useful; often indispensable.

Choking.

Potassic Bromide, 171, 172. In children who choke over drinking, but who swallow solids readily.

Cholera Asiatica.

Alcohol, 698, 701. Iced brandy, to stop vomiting.
Arsenic, 641. In small doses, has been used to stop vomiting.
Camphor, 929. 5 m. of strong tincture every ten minutes, while the symptoms are violent.
Carbolic Acid, 761, 849. ½ gr. along with 2 m. of iodine every hour.
Chloral, 717. Subcutaneously, alone, or with morphia.
Chloroform, 726, 727. 2 or 3 m., either alone or with opium, every few minutes.
Copper Salts, 605. Sometimes used to stop vomiting.
Corrosive Sublimate, 622, 623.
Lead Acetate, 631. Has been used as an astringent in early stages.
Naphthalin, 742. May be useful.
Opium, 333-335. In subcutaneous injection $\frac{1}{10}$-$\frac{1}{2}$ gr. to check the preliminary diarrhœa, and arrest the collapse.
Saline Injections, 541. Into the veins have a marvellous effect during collapse, in apparently restoring the patient; but their use is generally merely temporary.
Spinal Ice Bag has been used to relieve cramps.
Strychnia, 151, 887, 888. Has been used during the preliminary diarrhœa, and also as a stimulant to prevent collapse.
Sulphuric Acid, 498. Alone, or with opium, is very effective in checking the preliminary diarrhœa.

Cholera Asiatica.

Transfusion of Milk has been used in collapse.
Turpentine, 950, 951. Has sometimes appeared serviceable in doses of 10-20 m. every two hours.

Cholera Infantum.

Aliment. Milk, 989.
Arsenic, 641. For vomiting in collapse.
Caffeine, 798.
Camphor, 929.
Carbolic Acid, 658, 736-738. With bismuth.
Ipecacuanha, 865. When stools greenish or dysenteric.
Lead Acetate, 631. Very useful.
Mercury, 618. ⅛ gr. of grey powder, hourly.
Potassic Bromide, 171, 172, 547. In nervous irritation.
Silver Nitrate, 327, 607. After acute symptoms are past.
Zinc Oxide, 599, 600. With bismuth and pepsin.

Cholera Simplex.

Alcohol, 701. Dilute and iced.
Arsenic, 641. To stop vomiting.
Cajeput Oil, 839. Used in India.
Calumba, 757. As anti-emetic.
Camphor, 929. Very useful.
Carbolic Acid, 736-738. With bismuth.
Chloral, 717. Subcutaneously, very useful.
Copper Salts, 305, 605. As astringent.
Ipecacuanha, 865, very useful.
Lead Acetate, 631. At commencement.
Mustard, 325, 398. Internally, as emetic, poultice over chest.
Opium, 775. Hypodermically.
Sumbul, 182, 851.
Veratrum Album, 210.

Chordee.

Aconite, 751. 1 m. every hour.
Belladonna, 903. With camphor and opium, internally, very useful.
Camphor, 929. Internally, useful.
Cannabis Indica, 946.
Cantharis, 1001. One drop of tincture three times a day as prophylactic.
Colchicum, 969. ½ dr. at night.
Lupulin, 948. As prophylactic.
Morphia, 766. Hypodermically, in perinæum at night, most useful.

Chorea.

Arsenic, 643. Useful sometimes; must be pushed till eyes red or sickness induced, then discontinued and then used again.
Chloral, 717. sometimes very useful in large doses carefully watched.
Chloroform, 726, 727. As inhalation in severe cases.
Cimicifuga, 754. Often useful, especially when menstrual derangement.
Cocculus, Picrotoxine, 759. In large doses.
Cod-Liver Oil, 997.
Conium, 846. Sometimes useful, must be given in large doses.
Copper, 325, 604. In increasing doses till sickness produced.
Iron, 672. In anæmia.
Morphia, 766. Subcutaneously, in severe cases.
Musk, 988.
Physostigma, 107.
Strychnia, 99, 119. Useful at puberty, or in chorea from fright.
Valerian, 181, 182, 887.
Veratrum Viride, 274, 276

Chorea.

Water. Cold affusion to spine useful.
Zinc, 276. Like Copper.

Choroiditis.

Mercury, 618.
Opiates, 166, 167.

Climacteric Disorders.

Aconite, 751. 1 m. hourly for nervous palpitations and fidgets.
Ammonia, 162. As inhalation.
Ammonium Chloride, 567. Locally in headache.
Camphor, 158, 929. For drowsiness and headache.
Change of air and scene useful adjunct.
Cimicifuga, 754. For headache.
Iron, 665, 672. For vertical headache, giddiness, and feeling of heat.
Nitrate of Amyl, 710. Where much flushed.
Nux Vomica, 289, 884. Useful.
Potassic Bromide, 171, 172, 546-548. Very useful.
Warm Bath, 411.
Zinc Valerianate, 603.

Coccygodynia.

Belladonna, 881, 903. Plaster useful.
Chloroform, 726, 727. Locally injected.
Counter-Irritation.
Electricity.
Surgical Treatment in obstinate cases.

Coldness.

Cold Water, 408. As prophylactic with friction.
Strychnia, 887, 888.

Colic, Intestinal.

Ammonia, 568, 569.
Arsenic, 32, 648. When pain is neuralgic in character.
Asafœtida, 330, 847. To remove flatulence.
Belladonna, 903. Especially in children.
Chamomile Oil, 871. In hysterical women, 871
Chloral, 337, 717.
Chloroform, 726, 727. To remove pain and flatulence.
Cocculus, 757. During pregnancy.
Essential Oils. Aniseed, 756, 949. Cardamom, 971. Cinnamon, 927. Cloves, 337. Peppermint, 918. Rue, 802. Spearmint, 919. All useful.
Lime Water, 579. In children.
Milk Cure, 989 In enteralgia.
Morphia, 766. Very useful.
Nux Vomica, 289, 884. Useful.
Potassic Bromide, 171, 172, 546-548.
Poultices, 412. Large and warm, of great service.
Tobacco, 908. Dangerous.

Colic, Lead.

Alum, 585-587.
Castor Oil, 935. Given twice a day to eliminate.
Iodide of Potassium, 543. Most useful in eliminating lead from the system, and combined with mag. sulp. to evacuate it.
Magnesium Sulphate, 340, 543. Most useful along with iodide of potassium.
Opium, 776.
Sulphur, 482. To aid elimination.

Colic, Lead.

Sulphur Baths, 413.
Sulphuric Acid, 493.
Tobacco, 908. Dangerous.

Colic, Renal and Hepatic, *vide* also Calculi.

Aliment. Abstain from starches and fats.
Alkalies. Alkaline waters very useful.
Bath, 411. Warm, to remove pain.
Chloroform, 726, 727. Inhalation from tumbler during fit.
Counter-Irritation, 297. *See* Irritants, &c.
Ether, 704. Like chloroform.
Opium, 775. In small doses frequently repeated, or hypodermatically.
Turpentine, 379, 951.

Coma.

Cold Douche, 408. In drunkenness of opium care must be taken not to chill, and it is best to alternate the cold with warm water.
Croton Oil, 340. As a purgative.
Potassic Bitartrate, 340. Purgative.
Mustard, 781. To surface, to stimulate.
Turpentine, 951. Enema as stimulant.

Condylomata.

Arsenic, 643, 644. As caustic.
Carbolic Acid, 736-738. Locally.
Chromic Acid, 301. 1-4 of water, locally, as caustic.
Mercury, 487, 621. Wash with chlorine water, or chlorinated soda, and dust with calomel.
Nitric Acid, 502. As caustic, or twenty per cent. oleate.
Thuja, 954. Strong tincture, locally, small doses internally, useful.
Zinc, 301. Locally, as a caustic or astringent.

Conjunctivitis.

Alum, 585, 687. After acute symptoms have subsided.
Belladonna, 901-903. Locally and internally.
Bismuth, 658, 659. Locally, in chronic cases.
Blisters, 302. Behind ear.
Cadmium, 305. As a wash.
Castor Oil, 935. A drop in eye to lessen irritation from foreign body.
Copper Sulphate, 604. As Collyrium.
Euphrasia. As a mild astringent.
Mercury, 625. As citrine ointment, very useful.
Opium, 169, 170. Liquid extract in eye relieves pain.
Pulsatilla, 572, 573. As wash and internally.
Silver Nitrate, 327, 607. Local application.
Tannin, 943 As Collyrium.
Zinc, 801. As Collyrium.

Constipation.

Aloes, *vide* Dinner Pill.
Alum, 585-587.
Ammonium Chloride, 557. In bilious disorders.
Apples, 339. Stewed or roast.
Arsenic, 362. In small doses.
Belladonna Extract, 899. $\frac{1}{12}$-$\frac{1}{2}$gr.
Cascara Sagrada, 810.
Castor Oil, 935. 10-20 m. in a teaspoonful of brandy and peppermint water before breakfast.
Cocculus, 757. When motions hard and lumpy, and much flatus.

CONSTIPATION.

COLOCYNTH COMPOUND, 837, 842. Colocynth pill at night.
CROTON OIL, 934. When no inflammation is present, very active.
DINNER PILLS. Aloes and myrrh; aloes and iron; with nux vomica and belladonna or hyoscyamus, taken just before dinner.
ENEMATA, 426. Soap and water, or castor oil.
ERGOT, 983. To give tone.
FIG, 339, 949. One before breakfast.
HONEY, 998. With breakfast.
HYDRASTIS, 759. Useful in biliousness.
IPECACUANHA, 865. One grain in the morning before breakfast.
LIQUORICE POWDER, COMPOUND, 814. A teaspoonful at night or in the morning.
MAGNESIA, 592. Solution of bicarbonate, useful for children and pregnant women.
MERCURY, 618. In bilious disorders, stools light.
NUX VOMICA, 884. 5-10 ♏. in a glass of cold water before breakfast or before dinner.
PHYSOSTIGMA, 353. 10 ♏. of tincture along with belladonna and nux vomica.
PODOPHYLLUM, 340. Very useful, especially in biliousness; ten drops of the tincture at night alone, or the resin along with other purgative pills, specially when stools are dark.
PRUNES, 339. Stewed, often efficient. If stewed in infusion of senna they are still more active.
RHUBARB COMPOUND PILL, 353. At night.
SALINE WATERS. In morning, before breakfast; Friedrichshall, Hunyadi Janos, or Pullna.
SENNA, 824. As confection, &c.
STILLINGIA, 362, 933. 10 ♏. fluid extract.
SULPHUR, 339, 482. Sometimes very useful as a good addition to compound liquorice powder, as in that of the Prussian Pharmacopœia.
TREACLE, 976. With porridge, useful for children.
TURPENTINE, 950, 951. In atonic constipation with much gaseous distension of colon.
WATER. Draught in the morning before breakfast.

CONVALESCENCE.

ALCOHOL, 698. With meals.
BITTERS.
COCA, 787. Either extract, or as coca wine.
COD-LIVER OIL, 997.
CREAM.
EUCALYPTUS. 841. A tonic.
GUARANA, 786.
KOUMISS, 987.
LIME, 579. As limewater or carbonate.
OPIUM, 167, 169. As enema for insomnia.
SUMBUL, 182, 851. Where great nervous excitability

CONVULSIONS, INFANTILE.

ACONITE, 751.
ALCOHOL. A small dose of wine or brandy arrests convulsions from teething.
ASAFŒTIDA, 847. A small dose in an enema arrests convulsions from teething.
BATHS, 411. Warm, with cold effusions to the head.
BELLADONNA, 903. Very useful.
BROMIDE OF POTASSIUM, 181, 182. Exceedingly useful; children bear it in large doses; 5 gr. three times a day or oftener, for a child a year old in convulsions from teething.
CHLORAL, 717. In large doses, 5 gr., per mouth or rectum.

CONVULSIONS, INFANTILE.

CHLOROFORM, 726, 727. To arrest fit.
IGNATIA, 884. When intestinal irritation.
MORPHIA, 766. Hypodermically.
POTASSIUM BITARTRATE, 349, 536.
SPINAL ICE BAG.
VALERIAN, 181, 182, 867. When due to worms.
VERATRUM, 274, 276.

CORNEAL OPACITIES.

CADMIUM, 305.
IODINE, 491. Internally and locally.
MERCURY, 618. Internally and locally.
SILVER NITRATE, 607. Locally.
SODIC CHLORIDE, 551. Injected under conjunctiva.
SULPHUR NITRATE, 482. Locally.

CORNS.

ACETIC ACID, 301.
CHROMIC ACID, 509.
IODINE, 491.
POULTICES, 412. And plaster with hole in centre to relieve pressure.
SILVER NITRATE, 607.

COUGH.

ACONITE, 199, 206, 750. In throat-cough and emphysema.
ALUM, 585-587. As spray or gargle.
APOMORPHIA, 205, 218. In bronchitis, with deficient secretion.
ASAFŒTIDA, 847. In the after-cough from habit, and in the sympathetic whooping-cough of mothers.
BELLADONNA, 903.
BLUE PILL, 619. In gouty or bilious pharyngeal irritation.
CAMPHOR, 929. Internally, or locally, painted over the larynx with equal parts of alcohol.
CHLORAL, 717.
CHLOROFORM, 726, 727,
COD-LIVER OIL, 218, 997. One of the most useful of all remedies in cough.
CONIUM, 846.
GELSEMIUM, 891. In convulsive and spasmodic cough.
GRINDELIA, 874. In habitual or spasmodic cough.
HYDROCYANIC ACID, 515. For irritable cough, and in phthisis.
HYOSCYAMUS, 169. In tickling night-coughs.
IODINE, 491. As inhalation.
IPECACUANHA, 865. Internally and as spray locally.
IPECACUANHA AND SQUILL PILL, 864. In chronic bronchitis at night.
LACTUCARIUM, 873.
LAUROCERASUS, 836. Substitute for hydrocyanic acid.
LINSEED, 783. In throat-cough.
LIQUORICE, 219, 814. In throat-cough.
LOBELIA, 872.
NASAL DOUCHE, 421. In nasal cough, 212.
OPIUM, 167, 169. Morphia locally to the throat, and generally.
PLASTERS, 220, 447. Calefaciens and picis to the chest.
POTASSIC BROMIDE, 547. In reflex coughs.
PRUNUS VIRGINIANA, 339.
PULSATILLA, 753. Anemonine ½-1 gr. dose in asthma and whooping-cough.
SANGUINARIA, 778, 779. In nervous cough.
TANNIN, 942. As glycerine to the fauces.
TAR WATER, 219, 953, 954. In winter-cough, bronchitis, and phthisis.
VALERIAN, 181, 182, 867. In hysterical cough.

Croup.

Alum, 325, 586. Teaspoonful, with honey or syrup, every ½ or ½ hour until vomiting is induced; most useful emetic.
Copper Sulphate, 604. 1-5 gr., according to age of child, until vomiting is induced.
Ipecacuanha, 865. Must be fresh; if it does not succeed, other emetics must be taken.
Lactic Acid, 516. To dissolve membrane (1 in 20).
Mercury Subsulphate, 620. One of the best emetics; 3-5 gr. given early.
Sanguinaria, 779. A good emetic. ℞ syr. ipecac., ʒij; pulv. sanguin. gr. xx; pulv. ipecac. gr. v; mix a teaspoonful every quarter hour till emesis, then half a teaspoonful every hour.
Senega, 785. As an auxiliary.
Sulphurous Acid, 493. As spray.
Tannin, 942. As spray.
Tartar Emetic, 219. Too depressant.
Zinc Sulphate, 325, 601.

Cystitis.

Aconite, 751. When fever present.
Alkalies, 525. When urine is acid.
Belladonna, 903. Most useful to allay irritability.
Buchu, 391, 803. Especially useful in chronic cases.
Cantharides, 1002. In small doses long continued.
Chimaphila, 878. In chronic cases.
Copaiba, 392. Useful.
Cubebs, 379, 937.
Eucalyptus, 841. Extremely useful in chronic cases.
Iodiform. 729. As suppository.
Opium, 167, 169. As enema, or suppository, to relieve pain.
Pareira, 758. In chronic cases.
Quinine, 682. In acute cases.
Sulphites, 560. To prevent putrefaction of urine.
Turpentine, 379, 950, 951.
Uva Ursi, 877. In chronic cases.

Cysts.

Chloride of Gold, 679. In ovarian dropsy.
Galvano Puncture.
Iodine, 491. As an injection after tapping.
Silver Nitrate, 607. As an injection.

Deafness.

Cantharides, 881. As ointment behind the ear.
Colchicum, 969. In gouty persons.
Gargles, 425. In throat deafness.
Glycerin, 882, 883. Locally.
Quinine, 862. In Menière's disease.
Tannin, 942, 943. In throat deafness.

Debility.

Alcohol, 698. Along with food often very useful. Liable to abuse—not to be continued too long.
Arsenic, 87, 365. In young anæmic persons alone or with iron, and in elderly, with feeble circulation.
Bitters. Useful as tonic.
Cholagogue Purgatives, 355. When debility is due to defective elimination of waste.
Cinchona, 862, 863.
Digitalis, 915. When circulation is feeble.
Eucalyptus, 841. In place of quinine.
Hydrastia, 756. The same.

Debility.

Iron, 672. Anæmia.
Lime Salts; 583. Phosphates, if from overwork and town life; hypophosphites in nervous debility.
Manganese, 678. In place of iron.
Nux Vomica, 884. Most powerful general tonic.
Sanguinaria, 362, 778, 779. When gastric digestion is feeble.
Sarsaparilla, 957. When syphilitic taint is present.
Sea Bathing, 404.

Delirium.

Alcohol, 699. When delirium is due to exhaustion.
Antimony, 652. Along with opium in fever.
Bath, Cold, 405. In fever.
Belladonna, 903.
Bromide of Potassium, 546-548. In fevers.
Camphor, 929. In 20-gr. doses every two or three hours in low-muttering delirium.
Cannabis Indica, 946, 947. In nocturnal delirium occurring in softening of the brain.
Morphia, 766. Hypodermically.
Opium, 167, 169. With tartar emetic.

Delirium Tremens.

Alcohol, 697. Sometimes necessary.
Ammonium Carbonate, 570. In debility.
Beef Tea, 699. Most useful.
Belladonna, 901, 903. In insomnia when coma vigil.
Bromide, 547, 563, 572, 582. In large doses.
Cannabis Indica, 947, 947. Useful, and not dangerous.
Capsicum, 899. 20-30 gr. doses, repeated after three hours, to induce sleep.
Chloral, 717. At commencement requires caution.
Cimicifuga, 754. As a tonic.
Coffee, 865.
Conium, 846. As an adjunct to opium.
Digitalis, 915. In large doses has had some success.
Enemata, 426. Nutritive, when stomach does not retain food.
Food, nutritious, more to be depended upon than anything else.
Hyoscyamus, 167-169. Useful, like belladonna.
Ice, 327. To check vomiting.
Lupulin, 948.
Opium, 775. To be given with caution.
Potassium Bromide, 547.
Quinine, 862.
Stramonium, 906 More powerful than belladonna.
Sumbul, 182, 851. In insomnia.
Tartar Emetic, 219. Along with opium.

Dentition.

Belladonna, 903. In convulsions.
Bromide of Potassium, 547. To lessen irritability and to stop convulsions.
Calumba, 757. In vomiting and diarrhœa.
Hypophosphites, 557, 583, 678. A tonic.
Phosphates of Lime, 583. When delayed or defective.

Diabetes Insipidus.

Alum, 586, 587.
Atropia, 903.
Creasote, 739

Diabetes Insipidus.

Ergot, 983.
Gallic Acid, 944. Combined with opium.
Jaborandi, 804.
Krameria, 785. To lessen the quantity of urine.
Nitric Acid, 502.
Opium, 772. Most useful; large doses, if necessary.
Valerian, 867. In large doses.

Diabetes Mellitus.

Alkalies. Akaline waters are useful.
Ammonium Carbonate, 570.
Ammonium Citrate, 660
Ammonium Phosphate, 572.
Arsenic, 643, 644.
Belladonna, 903. Full doses.
Calcium Sulphide, 584.
Codeia, 767. A most efficient remedy. Sometimes requires to be pushed to the extent of 18 grs. or more per diem.
Creasote, 739.
Glycerin, 882, 883. As remedy, and as food in place of sugar.
Hydrogen Peroxide, 476.
Iron, 672. Most useful along with morphia.
Jaborandi, 804.
Krameria, 705.
Lactic Acid, 516.
Opium, 772. Most useful.
Phosphoric Acid, 505. To lessen thirst.
Potassium Bromide, 547.
Quinine, 861, 862.
Quinine Bromide, with morphia.
Quinine Sulphate, 857.
Rhubarb, 924.
Salicylic of Soda, 559.
Skim Milk Diet.
Sodium Citrate, 321.
Sodium Phosphate, 556. As purgative.

Diarrhœa.

Aconite, 751. In high fever and cutting abdominal pains.
Alkalies, 523, 524. In small doses in diarrhœa of children.
Alum, 585-587.
Ammonium Carbonate, 570.
Arsenic, 643, 644.
Bael, 795.
Bismuth, 658, 659.
Calcium Carbonate, 582.
Calcium Carbolate, *vide* 738.
Calcium Phosphate, 583.
Camphor, 929. In summer diarrhœa at commencement.
Capsicum, 89, 90. From eating fish.
Carbolic Acid, 736-738.
Cascarilla, 933.
Castor Oil and Opium, 935. Most useful at commencement.
Catechu, 828.
Copper Sulphate, 604. In chronic cases.
Corrosive Sublimate, 85, 623. In small doses for children.
Creasote, 739.
Dulcamaria, 898. In diarrhœa of children from teething or exposure.
Ergot, 983.
Erigeron Canadense.
Galls, 941.
Hæmatoxylon, 822
Iron Pernitrate, 673.
Iron and Potash Tartrate, 673.
Kino, 816.
Krameria, 785.
Lead Acetate, 631. By mouth or suppository.
Matico, 938.

Diarrhœa.

Naphthalin, 742.
Nitrous Oxide, 172.
Nux Vomica, 884. In chronic cases.
Oak Bark, 305, 941.
Opium, 775. Most useful.
Potassium Chlorate, 539. In chronic cases with mucilage-like stools.
Pulsatilla, 752, 753.
Rhubarb, 924. In early stages.
Rumex Crispus, 451, 924. In morning diarrhœa.
Salicin, 939. In chronic cases along with ipecacuanha.
Salicylic Acid, 741. In summer diarrhœa and in diarrhœa of phthisis
Tannin with Opium, 943.
Zinc Oxide, 600.
Zinc Sulphate, 305, 601.

Diphtheria.

Alcohol, 698, 699. Freely given, very useful.
Ammonium Chloride, 567.
Apomorphia, 766. As an emetic.
Arsenic, 643, 644. Internally.
Belladonna, 903. At commencement, especially useful when tonsils much swollen.
Bromine, 488. As inhalation.
Carbolic Acid, 736-738. As spray or painted on throat, internally with iron.
Chloral, 717.
Chlorinated Lime, 486, 487. Locally, as gargle or wash.
Chlorine Water, 487, 488. Internally.
Copper Sulphate, 604. As emetic.
Guaiacum, 801. Internally.
Hydrochloric Acid, 500. Dilute as gargle, or strong as caustic.
Iodine, 491. As inhalation.
Iron Perchloride, 671.
Iron Persulphate, 679.
Lactic Acid, 516. As solvent of false membrane.
Lemon-juice, 795. As gargle.
Mercury, 618. Internally as calomel or cyanides, $\frac{1}{20}$-$\frac{1}{10}$ of a grain.
Papain, 836. As solvent of false membrane.
Potassium Bichromate, 542. As emetic.
Potassium Chlorate, 538. Internally in large doses frequently repeated, and locally as a gargle.
Potassium Liquor, 533. Internally.
Potassium Permanganate, 540. As gargle.
Salicylic Acid, 741. Locally as gargle, or internally.
Sanguinaria, 779. As emetic. *Vide* Croup.
Sassafras, Oil of, 930. As local application.
Soda, Chlorinated, 557. In a solution as gargle.
Soda Hyposulphate and Sulphites, 557, 560. Internally and locally.
Strychnia, 887, 888. Subcutaneously for paralysis.
Sulphurous Acid, 493.

Dropsy.

Ammonium Benzoate, 574. In hepatic dropsy.
Ammonium Chloride, 567. In hepatic dropsy.
Arsenic, 643, 644. From fatty heart, debility, and old age.
Asclepias Syriaca, 892.
Asclepias Syriaca and Apocynum, 892.
Blatta, 379.
Broom, 815, 881. One of the most useful diuretics, especially in scarlatinal, renal, and hepatic dropsy.
Bryonia, 844, 845. As drastic, purgative, and diuretic.
Cannabis Indica, 946, 947. As diuretic.

Dropsy.

Chenopodium Anthelminticum, 925. In scarlatinal dropsy.
Chimaphila, 878. In renal dropsy.
Colchicum, 969. In hepatic, cardiac, and scarlatinal dropsy.
Copaiba, 381. Especially in hepatic dropsy.
Digitalis, 380, 915. In all dropsies, but especially in cardiac dropsy; infusion is the best form.
Elaterium, 340, 483. Useful hydragogue cathartic.
Erythrophlæum, 380. In cardiac dropsy.
Hellebore, 963. In post-scarlatinal dropsy.
Iron, 672. Along with saline purgatives.
Juniper, 381, 955. Exceedingly useful.
Nitrous Ether, 379, 381. Useful alone, or with other diuretics.
Potassium Bitartrate, 379. With compound jalap powder, most useful of the hydragogue cathartics.
Potassium Nitrate, 379. As diuretic.
Senega, 785. In renal dropsy.
Squill, 380. In cardiac dropsy.
Strophanthus, 380. In cardiac dropsy.
Taraxacum, 380.
Turpentine, 379. In albuminaria.

Duodenal Catarrh.

Arsenic, 643, 644.
Bismuth, 658.
Ipecacuanha, 865.
Nitro-Muriatic Acid, 383.
Podophyllum, 754.
Rhubarb, 924.

Dysentery.

Aconite, 751. With much fever.
Arnica, 873. With much depression.
Arsenic, 643, 644.
Belladonna, 903.
Benzoin, 880. In chronic cases.
Carbolic Acid, 736-738.
Castor Oil, 935. In small doses, with opium.
Corrosive Sublimate; 85. In small doses in chronic cases.
Creasote, 739.
Ergotine, 983.
Glycerin, 882, 883. With linseed tea to lessen tenesmus.
Hamamelis, 940. Where much blood in motions.
Iodine, 491.
Ipecacuanha, 865. In 30 gr. doses on empty stomach, with complete rest.
Iron, 672. Internally, or as enemata.
Lead Acetate, 631. By mouth, or as enemata or suppository.
Lemon Juice, 795.
Magnesium Sulphate, 590. In acute cases.
Nux Vomica, 884. In epidemic cases, and where prune juice stools and much depression.
Opium, 775.
Potassium Bitartrate, 340, 536. In advanced stages where much mucus.
Potassium Chlorate, 538. As enema.
Quinine Sulphate, 857. In large doses in malarious cases, followed by ipecacuanha.
Soda, Chlorinated, 557. As enema.
Sulphur, 482. In chronic cases.
Tannin, 943.
Zinc Oxide, 600.
Zinc Sulphate, 305, 601. By mouth or enema.

Dysmenorrhœa.

Aconite, 751.
Ammonium Acetate, 572.

Dysmenorrhœa.

Amyl Nitrite, 710. In neuralgic form
Apiol (Oil of Parsley). As emmenagogue in neuralgic form.
Arsenic, 643, 644. When membranous discharge from uterus.
Belladonna, 903. In neuralgic form.
Borax, 398, 555. In membranous form.
Cajeput Oil, 839.
Camphor, 929. Frequently repeated.
Cannabis Indica, 946, 947. Very useful.
Cimicifuga, 754. In congestive cases at commencement.
Croton Chloral, 934. In neuralgic form.
Ergot, 982, 983. In congestive cases at commencement.
Gelsemium, 891.
Guaiacum, 398. In rheumatic cases.
Ipecacuanha, 865. As an emetic.
Iron, 672.
Nux Vomica, 884. In neuralgia form.
Opium, 775, 777. Exceedingly useful in small doses of 3 to 5 ms. of tincture alone or along with 3 or 4 gr. of chloral.
Putsatilla, 753.
Rue, 398, 802.
Sumbul, 851.

Dyspepsia.

Acids, 501. Before or after meals, especially nitro-muriatic acid.
Alcohol, 698. Along with food.
Alkalies, 524. Very useful before meals, or two hours after.
Alkaline mineral waters.
Aloes, 961. As dinner pill.
Arsenic, 643, 644. 1 ♏. of liquor before meal in neuralgia of the stomach, or diarrhœa excited by food.
Asafœtida, 847.
Belladonna, 903. To lessen pain and constipation.
Berberine, 931.
Bismuth, 658. When stomach irritable.
Bryonia, 844, 845. In bilious headache.
Calumba, 757. Very useful.
Capsicum, 899. In atonic dyspepsia.
Cardamom, 971
Castor Oil, 935.
Cerium Oxalate, 588.
Chamomile, 871.
Charcoal, 479. For flatulence.
Cholagogues, 340. Often very useful.
Cinchona, 862, 863.
Gallic Acid, 944. In pyrosis.
Hydrastis, 756. In chronic dyspepsia.
Hydrocyanic Acid, 515. In irritable cases.
Ipecacuanha, 865. Useful adjunct to dinner-pill.
Kino, 816. In pyrosis.
Lactic Acid, 516. In imperfect digestion.
Lime Water, 579.
Magnesium Sulphate, 590.
Manganese, 678. In gastrodynia and pyro
Mercury, 618. As cholagogue.
Nux Vomica, 884. Exceedingly useful.
Pancreatin, 319. 1½ or 2 hours after meals, very useful.
Pepsin, 319. Sometimes very useful with meals.
Potassium Iodide, 543.
Potassium Sulphide, 530.
Quassia, 808.
Rhubarb. 353, 924.
Sanguinaria, 778. In atonic dyspepsia.
Silver Nitrate, 607. In nervous and neuralgic cases.
Silver Oxide, 609.
Sulphurous Acid, 498. In acid pyrosis and vomiting.

Dyspepsia.

Tannic Acid, 305.
Taraxacum, 872.
Xanthoxylin, 804. As stomachic tonic.

Dysphagia.

Bromide of Potassium, 546-548. In hysterical dysphagia, or dysphagia of liquids in children.
Cajeput Oil, 839. In nervous dysphagia.
Iced Fluids. Slowly swallowed in spasmodic dysphagia.

Dyspnœa.

Vide Asthma, Bronchitis, Croup, Emphysema, Phthisis.

Dysuria.

Alkalies, 525-527. When urine very acid.
Belladonna, 903.
Camphor, 929. In strangury.
Cannabis Indica, 946, 947. In hæmaturia.
Cantharides Tincture, 1001.
Chimaphilia, 380, 878.
Ergot, 983. In paralysis, when bladder feels imperfectly emptied.
Gelsemium, 891.
Nitrous Ether, 379.
Opium, 775, 777.

Earache.

Almond Oil, 834.
Blisters, 302. Behind the ear.
Glycerin, 882, 883.
Lead, Acetate and Opium, 631. As wash.
Opium, 775.
Pulsatilla, 753.

Ecchymoses.

Alcohol, 698. Externally.
Arnica, 873. Internally and externally.

Ecthyma.

Cod-Liver Oil, 997. Internally and locally.
Grape Cure. Useful.
Lead, 631. Locally.
Quinine, 860-862.
Zinc Oxide, 599. Locally.

Ectropium and Entropium.

Collodion, 790.
Silver Nitrate, 607.

Eczema.

Alkalies. Weak solutions of, as constant dressing.
Anacardium Orientale, *vide* Cashew Nut Oil.
Arsenic, 643, 644. Most generally useful.
Benzoin, 879. Compound tincture locally, to allay itching.
Bismuth, 658. Locally.
Carbolic Acid, 736-738. Internally and externally.
Carron Oil, 581. To allay irritation.
Cashew Nut Oil. As ointment in chronic cases.
Citrine Ointment, 625. Locally, alone or mixed with tar ointment.
Croton Seeds, 934. Tincture of, as ointment.

Eczema.

Electricity. In obstinate cases.
Glycerin, 882.
Hamamelis, 940. Locally, to allay itching.
Iris Versicolor, 972. In chronic gouty cases.
Lead Salts, 631. Locally.
Lime Water, 579. Alone, or with glycerin or oil.
Mercury, 618.
Milk Cure, 989. Sometimes useful.
Phytolacca, 924. In obstinate cases.
Rhus Toxicodendron, 812. Internally and externally. With much burning and itching, and in chronic eczema of rheumatism, worse at night-time.
Sulphides, } 413, 482, 541, 584. Internally,
Sulphur, } and as baths.
Tannin, 942. Glycerin of, most useful application.
Viola Tricolor, 782. Infusion along with senna.

Elephantiasis.

Anacardium Orientale.
Arsenic, 643, 644. Along with five or six times as much black pepper.
Cashew Nut Oil.
Gurjun Oil.
Sarsaparilla, 957.

Emaciation.

Arsenic, 643, 644.
Cinchona, 862, 863.
Cod-Liver Oil, 361, 997.
Iodine, 491.
Iron, 672.
Pancreatin, 319.
Pepsin, 319.
Phosphate of Lime, 583.

Emphysema.

Apomorphia, 765, 766. When secretion is scanty.
Arsenic, 643, 644.
Bleeding, 367. When right side of heart engorged.
Chloral, 717. In acute.
Cod-Liver Oil, 361, 997. One of the best remedies.
Ether, 705. Internally, as inhalation.
Grindelia, 874.
Hypophosphites, 557, 583, 678.
Iodide of Ethyl, 704-706. As inhalation.
Iron, 672.
Oxygen, 474.
Senega, 785.
Stramonium, 906.
Turpentine, Oil of. 950, 951.

Empyæma.

Aspiration, or free incision.
Carbolate of Iodine, 491.
Carbolic Acid, 736-738.
Chlorine Water, 486.
Iodine, 491.
Quinine, 860-863.
Salicylic Acid, 741.
} All used as injections to wash out cavity.

Endocarditis.

Aconite, 296, 749, 751. In small doses frequently at commencement.
Blisters, 302.
Bryonia, 845.
Mercury, 615. To prevent fibrinous deposits.
Opium, 775.
Quinia, 862.
Salicylic Acid, 741.

ENDOMETRITIS.

CARBOLIC ACID, 736-738. Locally.
CHROMIC ACID, 301.
ERGOT, 983. Subcutaneously.
GLYCERIN, 882, 882. Locally.
HOT WATER INJECTIONS.
IODINE, 491.
IODOFORM, 729.
IODO-TANNIN—solution of iodine in tannic acid.
NITRIC ACID, 502.
USTILAGO MAYDIS, 983.

ENTERITIS.

ACONITE, 751. In acute cases.
ARSENIC, 643, 644.
CASTOR OIL, 935. Very useful along with opium.
IRON, 672.
OPIUM, 775.
PODOPHYLLUM, 754.
POULTICE HOT, 412.
SKIM MILK. As diet, alone or with lime-water.

ENURESIS.

ATROPIA, 900.
BELLADONNA, 903. Very useful for children, but the dose must be large.
BUCHU, 803. In chronic cases.
CANTHARIDES, 1001, 1002. Internally very useful.
CHLORAL HYDRATE, 717. In children.
COLLODION, 790. To form a cap over prepuce.
ERGOT, 983. In paralytic cases.
IODIDE OF IRON, 676.
LUPULINE, 948.
RHUS TOXICODENDRON, 812.
RHUS AROMATICA, 812.
SANTONIN, 870. When worms present.
STRYCHNIA, 888. Very useful.
TURPENTINE, 951.

EPIDIDYMITIS.

ACONITE, 751. In small doses frequently repeated.
MERCURY AND MORPHIA, 618. Locally as oleate.
PULSATILLA, 753. In very small doses along with aconite.
SILVER NITRATE, 607. Strong solution locally applied to abort.

EPILEPSY.

ARSENIC, 643, 644. In epileptiform vertigo.
ASAFŒTIDA, 847.
BELLADONNA, 963. In *petit mal*.
BLISTERS, 299, 300, 312. Over seat of aura.
BROMIDES OF POTASSIUM, SODIUM, LITHIUM, AND IRON, 547, 558, 563. Most generally useful; dose should be large.
BRYONIA, 845.
CAMPHOR, 929.
CAUTERY. Frequently and lightly repeated.
CHLOROFORM, 726, 727. As inhalation in hystero-epilepsy.
COD-LIVER OIL, 998.
CONIUM, 846.
COPPER SALTS, 604.
HYDROBROMIC ACID, 516.
IGNATIA, 884.
NITRITE OF AMYL, 710. As inhalation at commencement of aura.
NITRITE OF SODA, 550.
NITRO-GLYCERIN, 712, 713.
PHOSPHORUS, 365, 640.

EPILEPSY.

PICROTOXIN, 758, 759.
QUINIA, 862.
RUE, 802. When seminal emissions present.
SETON at back of neck.
STRYCHNIA, 888.
TURPENTINE, 357, 951. When worms present.
VALERIAN, 867.
ZINC OXIDE, 599.

EPISTAXIS.

ACONITE, 751.
ALUM POWDER, 585-587. Snuffed or blown up the nostrils
ARNICA, 873. In traumatic cases.
BELLADONNA, 903.
DIGITALIS, 915.
ERGOT, 983.
GALLIC ACID, 944. Along with ergot and digitalis.
HAMAMELIS, 940.
ICE over nose and head.
IPECACUANHA, 865.
IRON, 672. As spray.
PLUGGING anterior and posterior nares necessary, if epistaxis obstinate.
TURPENTINE, 951. Internally.
WARM BATH, 411. To feet and hands.
WARM WATER BAG to spine.

ERYSIPELAS.

ACONITE, 751. At commencement.
AMMONIUM CARBONATE, 570. When tendency to collapse.
BELLADONNA, 903.
COLLODION, 790. Locally.
DIGITALIS, 915. Locally.
IODINE, 491.
IRON, 672. Large doses frequently.
QUININE, 862. In large doses.
RHUS TOXICODENDRON, 301, 812.
SILVER NITRATE, 607. Strong solution locally applied.
SULPHUROUS ACID, 498. Equal parts with glycerin locally.
TARTAR EMETIC, 652, 653. Small doses frequently.

ERYTHEMA.

ACIDS. In cases of indigestion.
BELLADONNA, 903.
BISMUTH, 658. Locally.
QUINIA, 852. In erythema nodosum,
RHUS TOXICODENDRON, 301, 812.
ZINC, 301. Locally.

EXOPHTHALMOS.

BELLADONNA, 903.
DIGITALIN, 915.
GALVANISM of the cervical, sympathetic, and pneumogastric.
IRON, 672.

EXOSTOSIS.

ACONITE, 751.
IODIDE OF POTASSIUM, 545.
MERCURY, 618.

FEVER.

ACIDS, 496-498. To allay thirst.
ACONITE, 751. Small doses frequently, in all sympathetic fevers.
ALCOHOL, 698. Often useful.

Fever.

Ammonium Acetate, 572. Very useful as diaphoretic.
Ammonium Carbonate, 570. In scarlet fever and measles.
Antipyrin, 744.
Arnica, 873.
Arsenic, 643, 644. In malarious fevers.
Belladonna, 903. In eruptive fevers and delirium.
Camphor, 929. In adynamic fevers.
Cimicifuga, 754.
Cinchona, 862, 863.
Cocculus, 757. In typhoid, to lessen tympanitis.
Coffee, 865. In place of alcohol.
Digitalis, 915.
Gelsemium, 891.
Hydrastia, 756.
Mercury, 618. Small doses at commencement of typhoid or scarlet fever.
Opium, 167, 169. In sleeplessness, alone or with tartar emetic.
Quinine, 87, 863. In hyperpyrexia.
Rhus Toxicodendron, 301, 812. In rheumatic fever and scarlet fever with typhoid symptoms.
Salicin, 939 } In rheumatic
Salicylate of Soda, 559 } fevers, or in
Salicylic Acid, 741 } hyperpyrexia.
Tartar Emetic, 652, 653. In small doses, with opium.
Turpentine, 379. As stimulant in typhoid, puerperal, and yellow, and to stop hæmorrhage in typhoid.
Veratrum Viride, 963. In delirium ferox.

Fistula.

Capsicum, 899. As weak infusion locally.
Pepper, 937. The confection as laxative.
Sanguinaria, 362, 778. As injection.

Flatulence.

Alkalies, 319, 524. Before meals.
Asafœtida, 847.
Calumba, 757.
Carbolic Acid, 736-738.
Carminatives, 328, 329.
Charcoal, 329.
Creasote, 739.
Mercury, 618. When liver sluggish.
Nux Vomica, 884.
Physostigma, 353. In women at change of life.
Potassium Permanganate, 540. In fat people.
Turpentine, 950. Few drops internally, or as enema.

Flushing and Heat.

Iron, 672. Most useful.
Nitrite of Amyl, 710.
Nux Vomica, 884.
Potassium Bromide, 546-558.
Valerian, 867.
Valerianate of Zinc, 603.

Fractures and Dislocations.

Aconite, 751. If febrile symptoms ar present.
Arnica, 873. Internally and locally.
Iodine, 491.
Opium, 775.
Phosphate of Lime, 583. Quickens union.

Freckles.

Benzoin, 880.
Borax, 555.

Freckles.

Iodine, 491.
Lime-Water, 579.
Mercuric Chloride, 58, 621. Locally, with glycerine, alcohol, and rose water. ¼ of gr. to the oz.
Olive Oil, 882, 883.
Potassium Carbonate, 321, 533.

Gangrene.

Balsam of Peru, 816, 817.
Bromine, 488.
Charcoal, 477. As poultice.
Cinchona, 862, 863.
Creasote, 739.
Lime Juice and Chlorine Water in hospital gangrene.
Nitric Acid, 502.
Opium, 775.
Oxygen, 474. As a bath.
Potassium Chlorate, 379, 538.
Salicylic Acid, 741. Locally.
Sanguinaria, 778, 779.

Gastralgia.

Acupuncture. Sometimes gives great relief.
Alum, 585-587.
Arsenic, 643, 644. In small doses.
Atropia, 903, 904.
Bismuth, 328.
Chloroform, 726, 737. Two or three drops on sugar.
Creasote, 739.
Ergot, 983.
Galvanism.
Hydrocyanic Acid, 328.
Milk Cure, 989.
Morphia, 766. Subcutaneously, in epigastrium. Very useful, or with bismuth and milk before each meal.
Nux Vomica, 884.
Pancreatine, 319.
Pepsine, 319.
Silver Nitrate, 607.
Silver Oxide, 609.
Zinc Oxide, 599.

Gastric Ulcer.

Arsenic, 643, 644.
Atropia, 903.
Bismuth, 658.
Cannabis Indica, 946, 947.
Carlsbad Salts, 556. Before meals.
Castor Oil, 935.
Charcoal, 479.
Ice Bag. To epigastrium.
Lead Acetate, 631. To check hæmatemesis.
Lime-Water with Milk, 579.
Mercuric Chloride, 58, 621. Small dose before meals.
Milk, 989.
Morphia, 765, 766.
Nutritive Enemata.
Opium, 775.
Pepsine, 319.
Potassium Iodide, 543. With bicarbonate, to lessen flatulent dyspepsia.
Silver Nitrate, 607.
Silver Oxide, 609.
Turpentine, 950, 951. Frequently repeated to check hæmorrhage.

Gastritis.

Alum, 585-587. When vomiting of glairy mucus.
Ammonium Chloride, 567.

Gastritis.

Arsenic, 643, 644.
Atropia, 903. In chronic cases.
Bismuth, 659.
Caffeine, 797, 798. Especially when associated with migraine.
Calumba, 757.
Cinchona, 862, 863.
Eucalyptus, 841.
Hydrastis, 756.
Ipecacuanha, 865.
Lead Acetate, 631. Along with opium.
Nux Vomica, 884.
Opium, 776.
Pulsatilla, 753.
Silver Nitrate, 607.
Silver Oxide, 609.
Tannic Acid, 942.

Glanders.

Ammonium Carbonate, 570. Every hour in concentrated solution, followed by opiate.
Arseniate of Strychnia, 888.
Carbolic Acid, 736-738. Locally
Chlorinated Soda, 487. Locally.
Creasote, 739.
Iodine, 491.
Iodine of Sulphur, 490.
Potassium Bichromate, 76, 534.
Sulphites, 560.

Glandular Enlargements.

Ammonium Chloride, 567.
Arsenic, 643, 644.
Barium Chloride, 240.
Belladonna, 903.
Cadmium Chloride, 240.
Calcium Sulphide, 584. For glands behind jaw, with deep-seated suppuration.
Carbolic Acid, 736-738. Injections, a 2 per cent. solution.
Gold Chloride, 679.
Guaiacum, 801.
Hydrastis, 756.
Iodine, 491.
Iodoform, 729.
Mercury, 618. Internally and locally.
Sulphides, 541, 584.
Valerian, 867.

Glaucoma.

Atropia, 902, 903. Has caused this disease.
Dubosia, 186. Like Atropia.
Eserine, 818. Lowers intraocular tension.
Iridectomy. The only cure.

Gleet.

Aloes, 961.
Blisters, 302. To perinæum useful.
Cantharides, 382, 1002. Minim doses of tincture.
Copaiba, 392, 826. Internally and locally smeared on a bougie and introduced.
Copper Sulphate, 604. As injection.
Iron, 672.
Juniper Oil, 955. Like Copaiba.
Kino, 816.
Peru, Balsam of, 817.
Piper Methysticum, 937.
Sandal Wood Oil, 816. Useful both locally and generally.
Tannin, Glycerine of, 943. As injection.
Tolu, Balsam of, 817.
Turpentine, 379, 951.

Glossitis.

Bismuth, 685. As lotion.
Purgatives, 339.

Glottis, Œdema of.

Ammonium Carbonate, 570. As emetic.
Inhalations, 423, 468, 487.
Scarification especially useful.
Tracheotomy.

Goître.

Iodine, 491. Internally and locally, as ointment or tincture, and as injection.
Mercuric Biniodide, 625. As ointment.
Potassic Iodide, 543.
Aconite, 903. In acute stage.

Gonorrhœa.

Alkaline salts or waters.
Alum, 585-587. As an injection.
Cannabis Indica, 946, 947. To relieve pain and lessen discharge.
Cantharides, 1002. In small doses.
Colchicum, 379, 969.
Copaiba, 392, 826.
Cubebs, 937. Either alone or mixed with copaiba.
Hydrastis, 756. As injection.
Kaolin, 392, 583.
Lead Salts, 629. As injection.
Mercuric Chloride, 621. Weak solution, locally.
Pulsatilla, 753.
Sandal Wood Oil, 816. Internally and locally.
Silver Nitrate, 607. As injection.
Turpentine, 379, 951.
Zinc Salts, 599. As injection.

Gout.

Aconite, 751.
Alkalies, 522-526.
Arsenic, 643, 644.
Belladonna, 903.
Colchicum, 365.
Iodine, 491.
Lithium, 562, 563.
Manganese, 678, 679.
Strychnia, 888.
Sulphides, 541, 584. In chronic cases.
Sulphur Baths, 413.
Veratria, 964. As ointment.

Gums, Spongy.

Alum, 586.
Areca, 972.
Iodine Tincture, 543. Locally
Krameria, 785.
Myrrh, 813.
Pomegranate Bark, 841.
Potassium Chlorate, 538.

Hæmatemesis.

Alum, 585-587.
Ammonium Chloride, 567.
Ergot, 983. Hypodermically.
Gallic Acid, 306, 307.
Hamamelis, 940.
Ice. Exceedingly useful.
Ipecacuanha, 865.
Iron Perchloride, or Pernitrate, 671, 673.
Lead Acetate, 631.
Magnesium Sulphate, 340.
Sulphuric Acid, 498.
Tannic Acid, 942, 943.
Turpentine, 274, 950, 951.

Hæmaturia.

Alum, 585-587. Internally, or as injection into the bladder.
Bitartrate of Potash, 536.
Chimaphila, 878.
Copaiba, 826.
Creasote, 739.
Digitalis, 915.
Gallic Acid, 944.
Hamamelis, 940.
Ipecacuanha, 865.
Iron Perchloride, or Pernitrate, 671, 673.
Krameria, 785. Extract in large doses.
Lead Acetate, 631.
Matico, 938.
Tannic Acid, 942, 943.
Turpentine Oil, 950, 951.

Hæmoptysis.

Acetic Acid, 494, 503.
Aconite, 199, 206, 751.
Alum, 585-587.
Ammonium Chloride, 567.
Arnica, 873.
Chloroform, 726, 727. Outside of chest.
Copaiba, 826.
Copper Sulphate, 604.
Digitalis, 915.
Dry Cups to chest.
Ergot, 983.
Ferric Acetate, 670. Added to water, so as to take away the taste; a little constantly sipped.
Gallic Acid, 944. Very useful.
Hamamelis, 940. Very useful.
Ipecacuanha, 865.
Iron, 672. And absolute rest.
Lead Acetate, 631. Very useful.
Matico, 307.
Phosphoric Acid, 505.
Potassium Nitrate, 537. When fever present, along with digitalis or antimony.
Silver Oxide, 609.
Sodium Chloride, 550. In drachm doses.
Tannin, 307.

Hæmorrhage, Intestinal.

Belladonna, 903. For rectal ulcers.
Castor Oil, 934.
Ferric Chloride, 307.
Iodine, 491.
Sulphuric Acid, 498.
Turpentine, 379, 951. Very useful.

Hæmorrhage, Postpartum.

Acetate Acid, 494, 503.
Achillea.
Capsicum, 899.
Cimicifuga, 754.
Digitalis, 915.
Enemata, Hot.
Ergot, 983. Most efficient.
Ether Spray, 128, 704-706.
Gallic Acid, 944.
Hamamelis, 940. For persistent oozing.
Hot Water, 110-112. Injection into uterus.
Hydrastis, 756.
Ice, 407. To abdomen, uterus, or rectum.
Iodine, 491.
Ipecacuanha, 865. An emetic dose; good.
Iron Perchloride Diluted, 671. 1-4 injected into uterus.
Nux Vomica, 884. Along with ergot.
Opium, 775. 1 dr. dose of tincture, with brandy, in profuse bleeding.
Pressure over Uterus.

Hæmorrhoids.

Alkaline Mineral Waters useful.
Aloes, 339, 961. As purgative.
Alum, 585-587. In bleeding piles, powder, crystal, or ointment.
Carbolic Acid, 736-738. Injection into piles.
Ergot, 983
Galls Ointment, 944. With Opium very useful.
Grape Cure.
Hamamelis, 940. Internally and locally, as lotion, injection, enema, or suppository.
Hydrastis, 756. As lotion and internally.
Hyoscyamus, 904. Bruised leaves or ointment locally.
Iodiform, 729. As ointment or suppository.
Iron Protosulphate, 679. As lotion.
Leeches, 1003.
Nitric Acid, 502. As caustic; dilute as lotion.
Nux Vomica, 884. Very useful.
Senna, 823. As confection, or better, compound liquorice powder of Prussian pharmacopœia.
Stillingia, 933. In constipation and hepatic disease.
Sulphur, 482. As confection.

Hay Fever.

Aconite, 751.
Arsenic, 643, 644. As cigarette.
Coffee, Strong, 865.
Iodide of Potassium, 543, 545. Internally and locally.
Ipecacuanha, 865.
Quinia, 862. Locally, as injection or douche.

Headache.

Aconite, 751. When circulation excited.
Ammonia, 571. Aromatic spirits in ½-2 dr. doses. Raspail's lotion very useful; often relieves nervous headache.
Ammonium Chloride, 567. 10-15 gr. doses in hemicrania.
Arsenic, 643, 644. In brow ague.
Atropia, 903. Locally to eye in migraine.
Belladonna, 903. Frequently given in frontal headache, especially at menstrual period, or from fatigue.
Bicarbonate of Soda, 319, 553. With bitters before meals in frontal headache at the junction, for pain in upper part of forehead without constipation. As wash to the mouth when headache depends on decayed teeth.
Bromide of Potassium, 163, 547. In large doses.
Bryonia, 844, 855. In bilious headache.
Caffeine, 163, 798.
Cajeput Oil, 839. Locally.
Camphor, 929. Internally, and saturated solution externally.
Cannabis Indica, 946, 947. In neuralgic headache.
Chamomile, 871.
Chloroform, Spirits of, 726, 727. In nervous headache.
Cimicifuga, 754. In nervous and rheumatic headache, especially at menstrual period.
Croton Oil, 934.
Digitalin, 915. $\frac{1}{50}$ of a grain twice a day for congestive hemicrania.
Ether Spray, 128, 209. Locally, for frontal headache after illness or fatigue.
Guarana, 786.
Heat, 302, 412. As hot water bag or poultice to nape of neck.
Hydrastis, 756. In congestive headache with constipation.

Headache.

Ignatia, 884. In hysterical headaches.
Iodide of Potassium, 543-545. In rheumatic headache, with tenderness of scalp.
Iris, 972. In supra-orbital headache with nausea.
Magnesia Sulphate, 590. For frontal headache with constipation.
Menthol, 181. As local application.
Mercury, 618. In bilious headache.
Mustard, 302, 398. As foot-bath, or poultice to nape of neck.
Nitrite of Amyl, 710, 711. As inhalation when face pale.
Nitro-Hydrochloric Acid, 503. For pain just above eyeballs without constipation, also for pain at back of neck.
Nux Vomica, 884. Frequently repeated in nervous or bilious headache.
Picrotoxine, 758, 759. In periodical headache.
Podophyllum, 754. When constipation.
Potassium Cyanide, 531. As local application.
Salicylate of Soda, 559. 3-gr. dose every half hour, exceedingly useful.
Sanguinaria, 778, 779. In gastric derangement.
Skull-cap as prophylactic.
Sodium Phosphate, 353, 556. As laxative in bilious headache.
Spectacles. Where the headache depends on inequality of focal length or astigmatism.
Tea, 797. Strong black or green, often relieves nervous headache quickly.
Valerian, 867. In nervous and hysterical cases.
Zinc Oxide, 600.

Heartburn.

Almonds, 534. Six or eight blanched.
Capsicum, 899.
Nux Vomica, 289, 884. Very useful.
Podophyllum, 754.
Pulsatilla, 753.

Heart, Dilated.

Digitalis, 289, 290, 915.
Iron, 672.
Morphia, 765, 766.
Nitrite of Amyl, 710, 711.
Nitrite of Soda, 550.
Nitro-Glycerin, 712, 713.

Heart, Fatty.

Arsenic, 643, 644.
Belladonna, 903.
Cimicifuga, 754.
Cod Liver Oil, 218.
Ergot, 296.
Iron, 672.
Strychnia, 888.

Heart, Hypertrophied.

Aconite, 751. To be used with care when valvular disease is present.
Camphor, 287. In palpitation and dyspnœa.
Digitalis, 257. In small doses.
Ergot, 296.
Lead Acetate, 631. In palpitation.
Nitrite of Amyl, 710.
Veratrum Viridi, 274, 276, 296.

Heart, Palpitation of.

Aconite, 296, 751. Internally.
Belladonna, 903. Internally, useful in cardiac strain.

Heart, Palpitation of.

Bromide of Potassium, 546-548. In fluttering heart.
Camphor, 286, 287.
Cimicifuga, 754.
Digitalis, 257, 289.
Eucalyptus, 841.
Hot Bath, 287.
Hyoscyamus, 274, 904. In nervous palpitation.
Milk Cure, 989. In gouty persons.
Posture. Head hung forward, body bent, arms by the sides, and breath held for a few seconds.
Senega, 325, 784, 785.
Valerian, 867. In nervous cases with dyspnœa.
Veratria, 444, 964. As ointment to chest.

Heart, Valvular Disease of.

Aconite, 296, 749, 751. To quiet action; to be used with caution.
Digitalis, 289-292. In mitral disease, to be avoided in purely aortic disease, but useful when this is complicated with mitral.
Morphia, 765, 766. To relieve pain and dyspnœa.
Nitrites, 288. To lessen vascular tension.
Purgatives, 339. To lessen tension and remove fluid.
Strychnia, 289, 888. As cardiac tonic.

Hectic.

Antipyrin, 744.
Calumba, 757.
Digitalis, 915.
Gelsemium, 891.
Ipecacuanha, 865.
Iron, 672, 813. Especially mistura ferri composita.
Lime Phosphate, 583.
Prunus Virginiana, 835. To lessen cough.
Salicin, 939. To lessen perspiration.
Salicylate of Soda, 559.
Strychnia, 389, 888. To lessen night sweats.

Hemeralopia.

Blisters, 299, 300, 302. Small, to external canthus of the eye.
Electricity.
Mercury, 618. Locally.
Quinine, 860-862. In large doses internally.

Hepatitis.

Ammonium Chloride, 567.
Bryonia, 844, 845.
Chelidonium, 779.
Iodine, 491. As enemata.
Leeches, 1003.
Nitro-Hydrochloric Acid, 503.
Tartar Emetic, 652, 653. With Opium.

Hernia.

Chloral, 717. As enema.
Chloroform, 726, 727.
Coffee, 865.
Ether Spray, 128, 704.
Opium, 775.

Herpes Zoster.

Aconite and Opium, 169, 173, 751, 775. Locally.
Alcohol, 698. Locally.
Celandine, 779.
Dulcamara, 898.

Herpes Zoster.

Galvanism.
Morphia, 765, 766.
Rhus Toxicodendron 301, 812.
Silver Nitrate, 607. Strong solution locally.
Veratria, 964. As ointment.

Hiccough.

Amber, Oil of, 952.
Belladonna, 903.
Bismuth, 658.
Camphor, 929.
Cannabis Indica, 946, 947.
Chloral, 717.
Chloroform, 726, 727.
Ether, 205, 704-706.
Iodoform, 729.
Jaborandi, 804.
Laurel Water.
Morphia, 765, 766. Hypodermically.
Musk, 988.
Mustard and Hot Water.
Nux Vomica, 884.
Pepper, 330, 937.
Pressure over Phrenic, Hyoid, or Epigastrium.
Quinine, 860-862. In full doses.

Hydrocephalus, Acute.

Blisters, 302. To the nape of the neck useful.
Bromide of Potassium, 163, 546-548.
Croton Oil, 839, 934. Liniment.
Elaterium, 843.
Ergot, 983.
Iodide of Potassium, 543-545.
Iodoform, 729. Dissolved in collodion, or as ointment to neck and head; along with small doses of calomel, as enemata.
Leeches, 1003.
Mercuric Chloride, 621. Small doses internally.
Tartar Emetic, 652. Ointment.
Turpentine, 951. By mouth or as enema, at commencement.

Hydrocephalus, Chronic.

Blisters, 302.
Cod-Liver Oil, 996-997.
Iodide of Iron, 676.
Iodide of Potassium, 543-545.
Iodine, 491.
Mercury, 618.

Hydrophobia.

Actual Cautery, combined with excision is best.
Acupuncture. To wound immediately.
Belladonna, 903.
Bromide of Potassium, 546-548.
Chloroform, 726, 727. To control spasms.
Excision of bitten part.
Morphia, 765, 766.
Permanganate of Potash, 540. As lotion to wound.
Quinine, 862.
Silver Nitrate, 607. To wound, no use, even though applied immediately.

Hydrothorax.

Blisters, 299, 300, 302.
Broom, 815.
Digitalis, 915. As diuretic.
Elaterium, 843.
Iodine, 491. Injections after tapping.
Jaborandi, 804.
Sanguinaria, 778, 779.

Hypochondriasis.

Alcohol, 699. As temporary stimulant.
Arsenic, 643, 644. In the aged.
Asafœtida, 847.
Bromide of Potassium, 546-548.
Caffeine, 796-798.
Cimicifuga, 754. In puerperal, and spermatorrhœa.
Creasote, 739.
Gold Chloride, 679. When giddiness and cerebral anæmia, 679.
Hyoscyamus, 904. In syphiliphobia.
Ignatia, 884.
Musk, 987, 988.
Opium, 775-778. Small doses.
Ox Gall, 991.
Sumbul, 851.

Hysteria.

Aloes, 339, 961. In constipation.
Ammonia, Aromatic Spirits of, 571.
Amyl Nitrite, 710.
Apomorphia, 765, 766.
Arsenic, 643, 644.
Asafœtida, 847.
Atropia, 903. In hysterical aphonia.
Belladonna, 903.
Bromide of Camphor, 181.
Bromide of Potassium, 546, 548.
Camphor, 929. In hysterical excitement.
Cimicifuga, 754. In hysterical chorea.
Cold Water poured over mouth to cut short attack.
Electricity, to cut short attack.
Ether, 704-706.
Galbanum, 848. Internally, and as plaster to sacrum.
Garlic, 958. To smell during the paroxysm.
Ignatia, 884.
Ipecacuanha, 865. As emetic.
Iron, 672.
Lupulin, 948. When sleepless.
Musk, 987, 988.
Opium, 775-777. In small doses.
Pellitory, 868. For globus.
Phosphorus, 365, 640. In hysterical paralysis.
Santonin, 357, 850. If worms present.
Spiritus Etheris Nitrosi, 705. To relieve spasm.
Tartar Emetic, 652, 653.
Valerian, 867.
Zinc, Valerinated, 603.

Ichthyosis.

Baths, 404 *et seq.*
Cod-Liver Oil, 997.
Elmbark Decoction, 945. Useful.
Glycerin, 882, 883.
Zinc Oxide, 600.

Impetigo.

Arsenic, 643, 644.
Boracic Acid, 508.
Calcium Chloride, 582.
Cod-Liver Oil, 996-998.
Grape Cure.
Gutta-percha, 879.
Hydrocyanic Acid, 494, 513. To relieve itching.
Laurel Water. To relieve itching.
Mercury, 618. Locally.
Nitric Acid, 502. Internally.
Oil of Cade.
Potassium Chloride, 240.
Quinine, 860-862.
Sulphur, 482. Internally.
Tannin, 943. Locally.
Tar, 953.
Zinc Ointment, 468.

Impotence.

Arseniate of Iron, 676.
Cannabis Indica, 946, 947.
Cantharides, 1001, 1002.
Cubebs, 937.
Ergotine, 983. Hypodermically about dorsal vein of penis, when it empties too rapidly.
Gold Chloride, 679. To prevent decline of sexual power.
Nux Vomica, 884. Very useful.
Phosphoric Acid, 505.
Phosphorus, 365, 640.
Sanguinaria, 779.
Serpentaria, 932.
Zinc Phosphate, 603. Very useful.

Inflammation.

Aconite, 751. At the commencement of all inflammations, superficial or deep-seated; best given in small doses frequently repeated until pulse and temperature are reduced.
Alcohol, 699. As antipyretic and stimulant, especially useful in blood-poisoning.
Antimony, 652. 10-15 m. of vini antimonii frequently repeated at commencement.
Arnica, 873.
Belladonna, 903. In gouty and rheumatic inflammation and cystitis.
Bryonia, 844, 845. In serous inflammations after heart or pulse lowered by aconite.
Chloral, 716, 717. When temperature is high and much delirium.
Cod-Liver Oil, 997. In chronic inflammations.
Digitalis, 915.
Fomentations, 299.
Ice, 299. Locally applied.
Iodine, 490. Locally.
Mercury, 618. In deep-seated inflammations, especially those of serous membranes and iritis, and in syphilitic cases.
Opium, 775-777. Exceedingly useful to check it at commencement, and relieve pain afterwards.
Pack, 166.
Poultices, 412.
Pulsatilla, 753. In inflammation, when purulent discharge from eyes, ears, and nose, and in epididimitis.
Purgatives, 339 *et seq.*
Quinine, 87, 860-863. In peritonitis and in acute inflammations along with morphia.
Salicine, 939.
Salicylate of Soda, 559. Most useful, especially in rheumatic affections.
Salicylic Acid, 741. Most valuable.
Sulphides, 541, 584. To abort or to hasten maturation.
Veratrum Viridi, 963.

Influenza.

Ammonium Acetate, 572; with Nitrous or Chloric Ether, 379.
Carbolic Acid, 736-738. As spray and gargle.
Cimicifuga, 754.
Opium, 169, 173, 775-777. With Ipecacuanha useful for cough.
Potassium Nitrate, 538. Freely diluted, as lemonade.
Quinine, 860-862. Useful, especially in later stages.
Sanguinaria, 779. Sometimes very useful.
Spiritus Etheris Nitrosi, 461.
Sulphurous Acid, 498. By fumigation or inhalation.
Turkish Baths, 415. Useful.

Insomnia.

Aconite, 751. 1 m. every quarter of an hour, when skin dry and harsh.
Alcohol, 699. Sometimes very useful.
Atropia, 903. With opium, $\frac{1}{100}$ - $\frac{1}{60}$ gr. atropia, to $\frac{1}{4}$ or $\frac{1}{2}$ gr. morphia.
Camphor, 929.
Cannabis Indica, 166, 946, 947. Alone, or with hyoscyamus.
Chloral, 166, 717. Most useful alone, or with bromide of potassium; the addition of a small quantity of opium to the chloral and bromide assists their action.
Chloroform, 726, 727.
Coffee, 865. Causes insomnia, but has been recommended in insomnia from deficient nervous power, or chronic alcoholism.
Croton Chloral, 717. If heart weak.
Digitalis, 915. When deficient tone of vasomotor system.
Ether, 704-706. In full dose.
Gelsemium, 891. In simple wakefulness.
Humulus, 948. A hop-pillow sometimes useful.
Hyoscyamus, 166, 904. Alone, or with cannabis indica, useful to combine with quinine.
Ignatia, 884. In nervous irritability.
Lupuline, 948. In aged people.
Musk, 987, 988. In irritable and nervous cases.
Opium, 166, 777. Most powerful hypnotic, given alone or in combination.
Phosphorus, 640. In the aged.
Potassium Bromide, 171-172. In full doses, alone or with other hypnotics.
Sumbul, 182, 851. In nervous irritability and chronic alcoholism.
Tartar Emetic, 652, 653. Along with opium, when there is a tendency to congestion of brain, which opium alone would increase.
Warmth, 166. Internally and externally.
Wet Compress, 166.
Wet Pack, 166.

Intercostal Neuralgia

Is very commonly connected with Leucorrhœa *q.v.* (*Vide* also Neuralgia.)

Intermittent Fever.

Ammonium Carbazotate. $\frac{1}{2}$-1 gr. in pill.
Ammonium Chloride, 567.
Apiol. In mild cases, 15 gr. during an hour, in divided doses four hours before the paroxysm.
Arsenic, 643, 644. Exceedingly useful, especially in irregular malaria.
Atropia, 903. Subcutaneously, to arrest or cut short cold stage.
Berberin, 757. In chronic cases.
Brucine, 888.
Camphor, 929. Taken before the fit to prevent it.
Capsicum, 899. Along with quinine as adjuvant.
Carbolic Acid, 736-738.
Chloral Hydrate, 717. As antipyretic when fever high; and to check vomiting or convulsions in adults and children during malarious fevers.
Chloroform, 726, 727. To prevent or cut short cold stage.
Cimicifuga, 574. In brow ague.
Cinchonidine, 859. Like Cinchonine.
Cinchonine, 87, 104. Useful and cheap.
Cornus Florida, 853. A substitute for quinine.
Eucalyptus Globulus, 841. During convalescence.

Intermittent Fever.

Ferric Sulphate, 668.
Ferrous Iodide, 489.
Gelsemium, 891. Pushed until it produces dilated pupils or double vision.
Grindelia Squarrosa, 874, 875. In hypertrophied spleen.
Hydrastis, 756. In obstinate cases.
Iodine Tincture, 489, 543. To prevent recurrence of ague.
Ipecacuanha, 865. Most useful as emetic.
Leptandra Virginica, 916. After disease is lessened by quinine.
Morphia, 765, 766. Along with quinine an adjuvant.
Narcotin, 762. 2-5 gr. three times a day sometimes very useful.
Nitric Acid, 502. In obstinate cases.
Nitrite of Amyl, 710. By inhalation to relieve or shorten cold stage.
Opium, 775. In full doses, to prevent chill.
Pepper, 937. Along with quinine.
Potassium Nitrate, 537. 10 gr. in brandy and water, or dry on the tongue to prevent fit.
Quinine, 87, 860-863. As prophylactic to abort fit and to prevent recurrence; its action is aided by purgatives, emetics, and aromatics.
Quinine Bromohydrate, 858. Like quinine, and less liable to produce cinchonism.
Salicin, 939.
Sodium Chloride, 550. Tablespoonful in glass of hot water at a draught on empty stomach.
Sodium Hyposulphate, 557. In mild cases.
Spider-Web. As pill.
Strychnine.

Intertrigo.

Bismuth, 658. Locally.
Camphor, 929. Added to dusting powders to allay heat and itching.
Carbolic Acid, 736-738.
Fuller's Earth, 585.
Lead Lotion, 629, 632.
Lime-Water, 579.
Soap, 304.
Tannin, 942.

Iritis.

Atropia, 903.
Belladonna, 903. Internally and locally.
Duboisia, 186. Substitute for atropia.
Mercury, 618. Most serviceable.
Opium, 765, 766. To lessen pain.
Turpentine, 951. In rheumatic iritis.

Irritability.

Alkaline Waters.
Bromide of Potassium, 547.
Chloral, 168, 717.
Colchicum, 969. With potash in large quantity of water when gouty.
Ignatia, 884. In small doses.
Laxatives, 339. In constipation.
Strychnia, 888. In small doses.

Jaundice.

Alkaline mineral waters in catarrh of duodenum or bile ducts.
Aloes, 861.
Ammonium Chloride, 567. In scruple doses in jaundice from mental emotion.
Ammonium Iodide, 573. When catarrh of bile ducts.
Arsenic, 643, 644. In malarious cases.
Benzoic Acid, 880.

Jaundice.

Calomel Purgative, 621. Followed by saline, often very useful.
Carlsbad Salts, 556. Very useful.
Carlsbad Water, 556.
Celandine, 779.
Colchicum, 969.
Dulcamara, 898.
Enemata. Cold water, one or two litres once a day.
Enonymine, 340, 353.
Ether, 704-706. When due to gallstones.
Hydrastis, 756. In cases of catarrhal ducts.
Iridin, 340, 353.
Magnesium Sulphate, 590.
Manganese, 678. In malarious or catarrhal cases.
Nitro-Muriatic Acid, 383, 413. Internally, and as local application over liver, or as bath in catarrhal cases.
Podophyllum, 754. In catarrhal conditions very useful.
Potassium Chloride, 240.
Potassium Sulphate, 537. As laxative.
Quinine, 862. In malarious cases.
Rhubarb, 353. Jaundice in children.
Sanguinaria, 362.
Sodium Phosphate, 353. Very useful in catarrhal bile ducts.
Stillingia, 362, 933. After ague.

Lactation, Defective.

Calabar Bean, 821.
Castor Oil Leaves, 935.
Jaborandi, 804.
Mustard Poultice, 398.
Vanilla, 969.

Lactation, Excessive.

Belladonna, 903. Internally and locally.
Camphor and Glycerin, 883, 929.
Chloral, 717.
Coffee, 865.
Hempseed Oil, 946.
Iodide of Potassium, 545.

Laryngismus Stridulus.

Aconite, 751.
Belladonna, 903.
Bromides. Very useful in large doses.
Chloral, 717.
Chloroform, 726, 727. As inhalation to stop spasm.
Cold Sponging, 367.
Conia, 846. Pushed until physiological action observed.
Emetics, 321.
Ipecacuanha, 865. As emetic.
Morphia, 765, 766. Hypodermically.
Quinine, 862.

Laryngitis, Acute.

Acetic Acid, 503. As inhalation.
Aconite, 751.
Benzoin, 880. As inhalation.
Iodine, 491. As inhalation and counter-irritant over neck.
Leeches, 367, 1003. To larynx, or nape of neck.
Morphia, 765, 766.
Quinine, 862
Scarification of Larynx.
Silver Nitrate, 607. As spray.
Sulphurous Acid, 498. As inhalation or spray.
Zinc Sulphate, 601. As emetic.

Laryngitis, Chronic.

Alum, 585-587. As gargle.
Ammonium Chloride, 567. As spray.
Bismuth, 658. Locally by insufflation.
Carbolic Acid, 736-738. As spray.
Ferric Chloride, 305, 307. As spray, or brushed on interior of larynx.
Guaiacum, 801. As lozenges or mixture.
Iodine, 491. As counter-irritant.
Morphia, 765, 766. Mixed with bismuth or starch as insufflation, most useful when much irritation, as in laryngeal phthisis
Silver Nitrate, 607. As solution to interior of larynx.
Sulphurous Acid, 498. As fumigation, inhalation, or spray.
Tannin, 307. As gargle or spray.
Uranium Nitrate. As spray.

Leucorrhœa.

Alum, 586, 587. As injection.
Balsam of Peru, 817. Internally.
Balsam of Tolu, 817. Internally.
Belladonna, 903. As pessary, for over-secretion, and pain.
Bismuth, 658. As injection or pessary.
Borax, 555. As injection.
Carbolic Aicd, 736-738. As injection.
Cimicifuga, 754.
Cocculus Indicus, 757.
Copaiba, 826.
Copper Sulphate, 604. As injection.
Ergot, 983.
Glycerin, 883.
Hydrastis, 756. Locally.
Iodoform, 738, 729. As local application, alone, or mixed with tannic acid.
Iron, 672. Internally.
Myrrh, 813. Internally.
Phosphate of Lime, 583. Internally.
Potassium, Bicarbonate, 534. Dilute solution as injection.
Potassium, Permanganate of, 540.
Sumbul, 851.
Tannin, 307. As injection or suppository.

Lichen.

Arsenic, 643, 644.
Mercury, 618. Locally.
Silver Nitrate Solution, 607. Locally.
Sulphides.
Sulphur, 482.
Tar Ointment, 953.
Thymol, 920.

Locomotor Ataxia.

Belladonna, 903.
Cannabis Indica, 946, 947.
Electricity.
Ergot, 983.
Hyoscyamus, 905.
Nitro-Muriatic Acid, 383.
Phosphorus, 640.
Physostigma, 819-822.
Potassium Iodide, 343. For syphilitic taint.
Silver Nitrate, 607.
Strychnia, 888.

Lumbago.

Aconite, 750, 751. Small doses internally, and liniment locally.
Acupuncture.
Aquapuncture. Sometimes very useful.
Capsicum, 899. Locally.
Chloroform, 720, 882. Liniment.
Cimicifuga, 754. Sometimes very useful internally.

Lumbago.

Carbolic Acid, 736-738. Hypodermically.
Cautery.
Ether Spry, 128, 704.
Eucalyptus Oil, 840. As liniment.
Guarana, 786 In large doses.
Hot Douche, 411, 412. Or hot poultice.
Ice, rubbed over back.
Iodide Potassium, 543.
Morphia, 765, 766. Hypodermically.
Quinine, 862.
Rhus Toxicodendron, 812.
Turpentine, 951. Internally and locally.

Lupus.

Arsenic, 643, 644.
Carbolic Acid, 736-738.
Cautery.
Chalmugra Oil.
Chromic Acid, 307.
Creasote, 739.
Iodide of Potassium, 490
Iodide of Starch,
Iodide of Sulphur, 490. Externally.
Iodine, 491, 883. In glycerine.
Iodoform, 729.
Lead Lotion, 629, 632.
Mercury, 618. Internally and locally.
Phosphorus, 640.
Pyrogallic Acid.
Salicylate of Soda, 559.
Silver Nitrate, 607.
Sodium Acetate, 321, 525.
Sodium Ethylate.
Zinc Chloride, 601

Mania.

Belladonna, 903. Useful.
Bromide of Potassium, 546-548.
Camphor, 929.
Cannabis Indica, 946, 947.
Chloral, 717. As narcotic and carminative.
Conia, 846. Alone, or with morphia.
Croton Oil, 340, 934. As purgative.
Daturin, 274.
Digitalis, 915. In acute and chronic mania, especially when complicated with general paralysis and epilepsy.
Duboisia, 905. As calmative.
Ergot, 983. In recurrent mania.
Ether, 704. In maniacal paroxysms.
Galvanism, to head and cervical sympathetic.
Gelsemium, 891. With much motor excitement and wakefulness.
Hyoscyamus, 905. In hallucinations and hypochondriasis.
Iron, 672.
Opium, 775. Alone or with tartar emetic.
Physostigma, 819-822.
Stramonium, 168, 906.
Veratrum Viride, 963.
Wet Pack, 166, 495.

Mastitis.

Ammonium Chloride, 567. As lotion, locally.
Belladonna, 903. Locally as liniment or ointment.
Calcium Sulphide, 584. Internally, if abscess is forming.
Digitalis, Infusion, 915. Locally as fomentation.
Friction, with oil.
Hyoscyamus, 905. As plaster to relieve painful distention from milk.
Iodine, 491.
Mercury and Morphia Oleate, 618. Locally, in mammary abscess.

Mastitis.

Phytolacca, 924. To arrest inflammation, local application.
Plaster, 220, 447. To support and compress mammæ.
Stramonium, 906. Fresh leaves as poultice.
Tartar Emetic, 324, 325. In small doses frequently repeated at commencement.
Tobacco Leaves, 908. As poultice.

Measles.

Aconite, 751.
Ammonium Acetate, 572.
Ammonium Carbonate, 570.
Antimony, 652, 653.
Camphor, 929.
Carbolic Acid, 736-738. Internally, at commencement.
Digitalis, 915.
Ipecacuanha, 865.
Mustard Bath, 413. When retrocession of rash.
Potassium Bromide, 546-548. When sleeplessness.
Potassium Chlorate, 538. In adynamic cases.
Pulsatilla, 753.
Quinine, 862.
Veratrum Viride, 963.

Melancholia.

Arsenic, 643, 644. In aged persons, along with opium.
Bromide of Potassium, 546-548. Often very useful.
Caffeine, 798.
Cannabis Indica, 946, 947.
Chloral, 717. As hypnotic.
Cimicifuga, 754. In puerperal, or uterine despondency.
Galvanism.
Gold, 679.
Ignatia, 884.
Iron, 672.
Opium, 775. In small doses especially useful.
Valerian, 867. In hysterical and suicidal cases.

Menière's Disease.

Quinine, 862.

Meningitis, Cerebral.

Aconite, 750, 751.
Belladonna, 903.
Blisters, 302. To nape of neck.
Bromide of Potassium, 546-548. In convulsions consequent on meningitis.
Bryonia, 845. When effusion.
Cold, to head.
Gelsemium, 891.
Hyoscyamus, 905.
Iodide of Potassium, 545.
Mercury, 618. As ointment, or internally.
Opium, 775. In small doses, alone or with tartar emetic.
Pulsatilla, 753. In acute cases.
Purgatives, 340, 621. At commencement; calomel and jalap most useful.
Venesection, 367. When much excitement.

Meningitis, Cerebro-Spinal.

Aconite, 750, 751. Along with opium.
Antimony, 652, 653. Alone, or with opium.
Belladonna, 903.
Cautery, 307. Freely to back.
Cold, to spine.
Digitalis, 915. In early stage.

Meningitis, Cerebro-Spinal.

Ergot, 933. Useful.
Gelsemium, 891. Useful.
Opium, 775. Very useful in large doses.
Quinine, 862. At commencement, large doses.
Turpentine, 951. As enema.
Venesection, 367.

Menorrhagia.

Aloes, 961. As adjuvant to iron.
Ammonium Chloride, 567. For headaches.
Arsenic, 643, 644. With iron.
Bromide of Potassium, 546-548.
Calcium Phosphate, 583. In anæmia.
Cannabis Indica, 946, 947. Sometimes very useful.
Cimicifuga, 754.
Cinnamon, Oil of, 927.
Digitalis, 915. Sometimes useful.
Ergot, 933. Most useful.
Gallic Acid, 944. Very useful.
Hamamelis, 940. Useful.
Hot Water Bag to dorsal and lumbar vertebræ.
Ipecacuanha, 865. In emetic doses in evening, followed by acidulated draught in morning.
Iron, 672.
Magnesium Sulphate, 590. Sometimes useful.
Quinine, 862.
Rue, 802.
Savine, 955.
Senega, 785.
Sulphuric Acid, 498. When due to fibroid or polypus.

Mentagra.

Arsenic, 643, 644.
Canada Balsam, 949.
Carbolic Acid, 736-738.
Cod-Liver Oil, 997.
Copper, 604. Locally, as lotion.
Goa Powder, 823.
Iodide of Sulphur, 490.
Mercury, 618.
Oil of Turpentine, 951.
Oleate, Bichloride, or Nitrate of Mercury, 623. As ointment or lotion.
Petroleum, 688.
Sulphurous Acid, 493. With glycerin.

Metritis, Acute.

Aconite, 751.
Hot Water. Vaginal injection frequently for a length of time.
Leeches, 1003.
Opium, 775. As suppository or enema.
Poultices, 412.
Turpentine Stupes, 951.

Milk Deficiency.

Gossypium. Decoction of seeds, two or three times every hour.
Ricinus, 934. Poultices or infusion of leaves to the mammæ.

Muscæ Volitantes.

Blue Pill, 619. In biliousness.
Iodide of Potassium, 545.
Iron, 671. Perchloride in anæmia and climacteric.
Valerian, 866, 867.

Myalgia.

Ammonium Chloride, 567.
Arnica, 873. Internally and locally.

Myalgia.

Belladonna Liniment, 903. Locally.
Belladonna Plaster, 881.
Chloroform Liniment, 726. With friction.
Cimicifuga, 754.
Friction, 301, 415.
Gelsemium, 891. Large doses.
Iodine, 491.
Iodide of Potassium, 545. In rheumatic cases.
Opium, 775.
Packing, 166, 405.
Salicylate of Soda, 741.
Veratria, 966, 967. Externally.
Xanthoxylum, 804. Internally and externally.

Myelitis.

Belladonna, 903.
Electricity in chronic cases.
Ergot, 983.
Phosphorus, 640. In paraplegia from excessive venery.
Silver Nitrate, 607. Useful.

Nævus.

Chromic Acid, 508.
Creasote, 739.
Electrolysis.
Ferric Chloride, 305, 307.
Galvano Cautery.
Nitric Acid, 502.
Zinc Chloride, 601.

Nails, Ingrowing.

Glycerin, 883.
Lead Carbonate, 631. Locally.
Liquor Potassæ, 533, 534.
Silver Nitrate, 607.

Nausea.

Bismuth, 658.
Calumba, 757.
Cinnamon, 927.
Cloves, 837.
Cocculus Indica, 575. In violent retching without vomiting.
Hydrocyanic Acid, 515.
Ice, 216.
Ipecacuanha, 865. In sickness of pregnancy and chronic alcoholism; very small dose, 1 ♏. of wine.
Morphia, 766.
Nutmeg, 926.
Pepper, 937.
Peppermint, 918.
Pimento, 838.
Pulsatilla, 753. In gastric catarrh.

Nephritis, Acute.

Aconite, 748, 751. At commencement.
Belladonna, 903.
Cannabis Indica, 946, 947. As diuretic, especially in hematuria.
Cantharides, 1002. 1 ♏. of tincture every three hours to stop hæmaturia after acute symptoms have subsided.
Digitalis, 915. As diuretic.
Eucalyptus, 841. Given cautiously.
Gallic Acid, 944.
Hyoscyamus, 905.
Jaborandi, 804.
Juniper, 955.
Poultices, 412. Over loins, very useful.
Turpentine, 950. ½-1 ♏. doses, every two to four hours.

Nervousness.

Aconite, 748, 751. 1 ♏. of tincture at bedtime for restlessness and fidgets.
Bromide of Potassium, 546-548. Over-work and worry.
Caffeine, 798. Where much debility.
Camphor, 929.
Chamomile, 871.
Chloral, 717.
Chloroform, 726, 727.
Hops, 947. Internally, and as pillow.
Ignatia, 884.
Musk, 988. In uterine derangement.
Strychnine, 888. Where wandering.
Sumbul, 851. In pregnancy, and after acute illness.

Neuralgia.

Aconitia, 748. As ointment.
Acupuncture.
Alcohol, 698.
Ammonium Chloride, 567. ½ dr. doses.
Ammonium Valerianate, 573.
Amyl Nitrite, 710.
Aquapuncture.
Atropine, 903. As liniment, or hypodermically near the nerve.
Belladonna, 903.
Bebeeru Bark, 931.
Blisters, 302.
Bromide of Potassium, 546-548.
Caffeine, 798.
Cannabis Indica, 946, 947.
Capsicum, 899. Locally.
Carbonic Acid, 509. Locally, for uterine neuralgia.
Chalmugra Oil.
Chamomile, 871.
Chelidonium, 779.
Chloral and Camphor, 717, 929. Equal parts locally applied.
Chlorate of Potash, 538. In facial neuralgia.
Chloroform, 726, 727. Locally, and by inhalation, when pain very severe.
Cimicifuga, 754. In neuralgia of fifth nerve, and ovarian neuralgia.
Cod-Liver Oil, 997.
Croton Chloral, 274, 717. For neuralgia of the fifth nerve.
Digitalis, 915.
Electricity.
Ergot, 983. In visceral neuralgia.
Gelsemium, 891.
Ignatia, 884. In hysterical cases and in intercostal neuralgia.
Iodides, 545. Especially when nocturnal.
Iodoform, 729.
Iron, 672.
Morphia, 766. Hypodermically.
Mustard Poultice, 398, 412.
Narcein, 762.
Nitro-Glycerin, 712.
Nux Vomica, 884. In visceral neuralgia.
Oil of Cloves, 337. Locally.
Peppermint, 918. Locally.
Pulsatilla, 753.
Pyrethrum, 868. As masticatory
Quinine, 862. In periodical cases.
Salicylic Acid, 741.
Stavesacre, 752.
Sumbul, 851. Sometimes very useful
Thermo-cautery.
Valerian, 867.
Valerianated Zinc, 603.
Vibration, 171.

Neuralgic Pains.

Cold Sponging, 367
Friction, 301, 415. Along back or on limbs.

Neuralgic Pains.

Rubefacients, 301. Useful.
Valerian, 867.
Warm Sponging.

Nightmare.

Bromide of Potassium, 546-548.
Camphor-Water, 929.

Nipples, Sore.

Alcohol, 698. Locally.
Arnica, 873.
Balsam of Peru, 817.
Balsam of Tolu, 817.
Benzoin, 879.
Borax, 555. Saturated solution locally.
Carbolic Acid, 736-738.
Collodion, 790.
Ferrous Subsulphate, 668. Locally.
Lead Salts, 629.
Rhatany, 785. 1 part extract to 15 of cacao butter.
Shield.
Silver Nitrate, 607.
Sulphurous Acid, 493.
Tannin, Glycerin of. 943.

Nodes.

Mercury Oleate, 618. With morphia, locally.
Potassium Iodide, 545. Internally and externally.
Stramonium Leaves, 906. As poultice.

Nyctalopia.

Blisters, 299, 300, 302. Small to external canthus.
Quinine, 862.
Strychnine, 888.

Nymphomania.

Bromide of Potassium, 390, 556-548. In large doses.
Camphor, 929. In large doses.
Lupuline, 948.
Sulphur, 482. When due to hemorrhoids.
Sulphuric Acid. Internally.
Tobacco, 303. So as to cause nausea, effectual, but depressing.

Obesity.

Alkaline Waters, especially those of Marienbad.
Ammonium Bromide. 572.
Banting's System—living on meat and green vegetables, and avoiding starch, sugars, and fats.
Potassium Permanganate, 540.
Sulphurous Waters. 493.
Vinegar, 505. Very injurious.

Onychia.

Carbolic Acid, 172, 736-738. As local anæsthetic.
Chloral, 168, 170, 717. Locally.
Iodoform, 729. Locally.
Lead Nitrate, 633.
Mercury, 618. As ointment, alternately with poultices.
Silver Nitrate, 607. At commencement.
Tartar Emetic, 652, 653.

Otitis (*vide* Earache).

Ophthalmia (*vide* Conjunctivitis).

Orchitis (*vide* Epididymitis).

Otorrhœa.

Alcohol, 698.
Alum, 585-587. Insufflation.
Boracic Acid, 503.
Cadmium, 305. Locally.
Carbolic Acid, 736-738.
Chloral, 717.
Iodide, 573. 2 grs. to an ounce, locally.
Iodoform, 729.
Lead Acetate, 631.
Liquor Sodæ, 455. Locally, when discharge is fœtid.
Mercury Ointment and Nitrate, 618.
Permanganate of Potassium, 540. As injection or spray.
Quinine, 862.
Silver Nitrate, 607. Locally,
Tannin, Glycerin of, 942. Very useful.
Zinc Sulphate, 601.

Oxaluria.

Nitro-Muriatic Acid, 383.

Ozæna.

Alum, 586. As powder or wash.
Bromine, 488. As inhalation.
Carbolic Acid, 736-738.
Chlorinated Lime, 488. Injections of the solutions of.
Gold Salts, 679.
Hydrastis, 756. Internally and locally.
Iodine, 491. As inhalation. Much benefit derived from washing out the nose with a solution of common salt, to which a few drops of the tincture of iodine have been added.
Iodoform, 729.
Mercuric Oxide, or Ammoniated Mercury, 491, 624.
Potassium Permanganate, 540.
Tannin, Glycerin of, 942.

Parotitis.

Aconite, 751.
Emetics, 321.
Jaborandi, 804.
Mercury, 618. ½ gr. of grey powder three or four times a day.
Poultice, 412.

Pediculi.

Anise, 849.
Bake Clothes to destroy ova.
Cocculus Indicus, 757.
Mercury, 618. As ointment or wash.
Pyrethrum, 868.
Stavesacre, 752.

Pemphigus.

Arsenic, 643, 644.
Chlorate of Potash, 533.
Cod-Liver Oil, 997.
Iodide of Potassium, 545.
Mercury, 618.
Phosphorus, 640.
Silver Nitrate, 607.
Sulphides, 541, 584.
Tar, 953.

Pericarditis.

Aconite, 296, 751.
Alcohol, 300, 693. Sometimes very useful.
Blisters, 300, 302. Near heart very useful.
Bryonia, 845. Useful in exudation.
Calomel and Opium. Formerly much used.
Digitalis, 915. When heart is rapid and feeble with cyanosis and dropsy.
Opium, 775. In grain doses every three to six hours, very useful.
Quinine, 862.
Veratrum Viride, 296, 963.

Periostitis.

Iodide of Potassium, or Ammonium, 545, 573.
Iodine, 491. Locally.
Mercury, 618. Internally.
Mercury and Morphia Oleate, 623. Externally.
Mezereum, 301. In rheumatic and scrofulous cases.
Poultices, 412.
Stavesacre, 752. When long bones affected.

Peritonitis.

Aconite, 751. At commencement.
Bryonia, 845. When exudation.
Cocculus Indicus. 757. For tympanites.
Iron, 672. To abdomen.
Leeches, 1003.
Mercury, 618. When there is a tendency to fibrous exudation.
Opium, 775. Freely, most useful.
Poultices, 412.
Quinine, 862.
Steam applied to the abdomen under a cloth when poultices cannot be borne.
Turpentine, 218, 951. For tympanites.

Perspiration.

Agaric. In phthisis.
Aromatic Sulphuric Acid, 499. In phthisis.
Atropia, 903. In sweating of phthisis internally.
Belladonna, 903. As liniment for local sweats.
Carbolic Acid, 736-738. With glycerin locally for fœtid sweat.
Ergot, 983.
Gallic Acid, 944. In phthisis.
Jaborandi, 804.
Neat's Foot Oil rubbed over the surface.
Opium, 281, 288, 363. As Dover's powder in phthisis.
Permanganate of Potash, 540. Locally for fœtid perspiration.
Quinine, 862.
Salicin, 939. In phthisis.
Salicylic Acid, 741. With borax in fœtid perspiration.
Sponging, very hot.
Strychnine, 888. In phthisis.
Vinegar, 505. Locally.
Zinc Oxide, 630. In phthisis.

Pertussis.

Aconite, 751.
Alum, 585-587.
Belladonna, 903.
Bromide of Ammonium, 572.
Bromide of Potassium, 546-548.
Carbolic Acid, 737. As spray.
Castanea Vesca, 944.
Cerium Oxalate, 588.
Cheken, 838.

Pertussis.

Chloral, 717. In spasmodic stage.
Chloroform, 726. As inhalation during paroxysm.
Cod-Liver Oil, 218, 997.
Coffee, 865.
Croton Chloral, 274.
Decoction of Chestnut Leaves, *ad. lib.*, 944. Sometimes useful.
Ergot, 983.
Gelsemium, 891. In spasmodic stage.
Hydrocyanic Acid, 515. In habitual cough when the true hooping cough has ceased.
Ipecacuanha, 865. Sometimes very useful alone, or combined with bromide of ammonium.
Lobelia, 877. In spasmodic stage.
Monobromide of Camphor, 276.
Opium, 775. In convulsive conditions.
Salicylic Acid, 741. As spray.
Silver Nitrate, 607.
Tannin, 943.
Tar, 933. For inhalation.
Tartar, Emetic, 652.
Valerian, 867.
Zinc Sulphate, 601.

Pharyngitis.

Aconite, 751.
Alcohol, 698. Dilute as gargle.
Alum, 586. As gargle.
Belladonna, 903.
Capsicum, 899. As gargle.
Cimicifuga, 754. Internally when pharynx dry.
Copper Sulphate, 325, 605. Locally.
Cubebs Powder, 938. Locally applied.
Ferric Chloride, 305, 307. Locally as astringent, internally as tonic.
Glycerin, 883. Locally alone, or as glycerin and tannin.
Hydrastis, 756. Internally and locally.
Ipecacuanha, 865. As spray.
Pomegranate Bark, 841. As gargle.
Potassium Chlorate, 538. Locally.
Quinine, 862. As tonic.
Silver Nitrate, 607. In solution locally.
Strychnine, 888. As tonic.
Tannin, 943. As powder or glycerine locally.
Zinc Sulphate, 601. As gargle.

Phimosis.

Belladonna. 901, 903. Locally.
Lupulin, 948. After operation.

Phlebitis.

Hamamelis, 940.
Hot Fomentations.
Opium, 775. To allay pain.
Rest, absolute.

Phlegmasia Alba.

Ammonium Carbonate, 571. In full doses, when much prostration.
Belladonna Extract, 903. With mercurial ointment locally.
Blisters, 299, 300, 302. In early stage.
Creasote, 739. As enemata.
Hamamelis, 940.
Hydrochloric Acid, 500, 538. With potassic chlorate, in barley water.
Leeches, 1003. During active inflammation.
Opium, 775. Internally and locally to allay pain.

PHOTOPHOBIA.

BELLADONNA, 902, 903. To eye.
BROMIDE OF POTASSIUM, 547.
CALABAR BEAN, 186.
CHLOROFORM VAPOUR, 171, 726, 727.
COLD.
CONIA, 846. In scrofulous photophobia locally.
CROTON CHLORAL, 717.
MERCURIC CHLORIDE, 301. By insufflation.
POTASSIUM CHLORIDE, 621. In large doses.
TONGA.

PHTHISIS.

ALCOHOL, 693. Along with food or cod-liver oil, 218, 997
ANTIPYRIN, 744. To reduce temperature.
ARSENIC, 643, 644. To remove commencing consolidation, and also when tongue is red and irritable.
ATROPIA, 214, 903. To check perspiration.
BELLADONNA, 903. Locally for pain in muscles.
BENZOIN, 879. As inhalation to lessen cough and expectoration.
BLISTERS, 302.
CHLORAL, 167. As hypnotic.
CHLOROFORM AS LINCTUS, 726, 727. To check cough.
COCAINE, 787 Solution 4-20 per cent. locally to throat and mouth to relieve irritation, soreness and aphthæ, especially in the latter stages.
COD-LIVER OIL, 996-997. Most useful as nutrient.
CREASOTE, 739. As inhalation.
CROTON CHLORAL, 274. To check cough.
CROTON OIL, 934. To chest as counter-irritant.
GELSEMIUM, 891.
GLYCERIN, 883. As nutrient in place of cod-liver oil, locally to mouth in the last stages to relieve dryness and pain.
HYPOPHOSPHITES, 357, 383, 678. Very useful in early stage.
INULIN, 875. Possibly useful.
IODINE LINIMENT, 491. As a counter-irritant to remove consolidation in early stage, and to remove pain and cough later; as inhalation to lessen cough and expectoration.
IODOFORM, 729. As inhalation.
IPECACUANHA, 865. As spray to the throat to relieve bronchial asthma and emphysema, combined with fibroid phthisis.
MERCURIC CHLORIDE, 58. In minute doses for diarrhœa.
MORPHIA, WITH STARCH OR BISMUTH, 765, 766. Locally to larynx, and in laryngeal phthisis most useful.
MUSTARD LEAVES, 302. Most useful to lessen pain and prevent spread of subacute intercurrent inflammation.
OPIUM, 775. To relieve cough, and, with ipecacuanha and Dover's powder, to check sweat.
OXYGEN, 475.
PHOSPHATE OF LIME, 583. As nutrient, and to check diarrhœa.
PICROTOXIN, 759. To check perspiration.
PILOCARPIN, 385, 387, 406. To check sweats.
QUININE, 862. As tonic to lessen temperature to check sweat.
SALICYLIC ACID, 741. When breath foul and expectoration offensive.
SILVER NITRATE, 607.
SULPHUROUS ACID, 499. As fumigation.

PITYRIASIS.

ARSENIC AND MERCURY, 618, 643. Internally.

PITYRIASIS.

BORAX, 355. Saturated solution or glycerin locally.
CARBOLIC ACID, 736-738. With glycerin and water, locally.
CHRYSAROBINUM, 823.
LEAD, 629. Locally.
MERCURIC OINTMENT, 988. Locally.
SULPHIDES, 541, 584. Locally.
SULPHUROUS ACID, 498.

PLEURISY.

ACONITE, 751. In early stage.
ANTIMONY, 652.
BELLADONNA PLASTER, 903. Most useful to relieve pain in old adhesions.
BLISTERS, 302.
BRYONIA, 845. After aconite.
COD-LIVER OIL, 218, 996, 997.
DIGITALIS, 915. When much effusion.
IODIDE OF POTASSIUM, 545. To aid absorption.
IODINE, 491. As a liniment externally, to assist absorption, or as a wash, or injection, to cavity after tapping.
LEECHES, 1003
LOCAL WET PACK, 405. To chest.

PLEURODYNIA.

BELLADONNA, 903. Plaster or liniment very useful.
CHLORAL, 717, 929. With camphor locally.
CROTON OIL, 934. Locally in obstinate cases.
ETHER, 704. As spray, locally.
IODINE, 490. Locally.
IRON, 672. When pleurodymia associated with leucorrhœa.
MUSTARD LEAVES, 302.
OPIUM, 760. Liniment rubbed in after warm fomentations or hypodermic injections.
OPIUM, 775. Most useful to cut short attack and relieve pain.
PLASTERS, 220. To relieve pain and give support.
POULTICES, 412.
QUININE, 862.
STRAPPING, 631.
VERATRUM VIRIDE, 963.
WET-CUPPING, 367. When pain severe and fever high.

PLEURO-PNEUMONIA.

BRYONIA, 845.
CARBOLIC ACID, 736-738. 2 per cent. solution injected locally.
SANGUINARIA, 778.
TURPENTINE, 951. Locally.

PNEUMONIA.

ACONITE, 751. Very useful, especially at commencement.
AMMONIUM CARBONATE, 570. As stimulant.
BELLADONNA, 903. At commencement.
BLISTERS, 302. At beginning to lessen pain.
BRYONIA, 844, 845. When pleurisy present.
COPPER ACETATE, 605.
DIGITALIS, 915. To reduce temperature.
IODIDE OF AMMONIUM, 573.
PHOSPHORUS, 640.
POULTICES, 412, 414. To lessen pain.
QUININE, 862. To lower temperature.
SALICYLATE OF SODA, 559. As antipyretic.
SENEGA, 785. As expectorant.
SERPENTARIA, 932. With carbonate of ammonia as stimulant.
TURPENTINE, 950. As stimulant at crisis.

Polypus.

Alum, 585-587. As insufflation.
Tannin, 943. As insufflation.

Prolapsus Ani.

Alum, 586, 587. In solution locally.
Hydrastis, 756. As enema or lotion.
Ice, 327. When prolapsed parts inflamed.
Pepper, 937. Confections.
Podophyllum, 754. In small doses.
Strychnia, 888. As adjunct to laxatives.
Tannin, 862. As enemata.

Prolapsus Uteri.

Alum, 586, 587. As hip-bath and vaginal douche.
Cimicifuga, 754. To prevent miscarriage and prolapsus.
Galls, 941. Decoction of, as injection.
Ice, 327. Locally when part inflamed, and to spine.
Oak Bark, 941. As injection.
Tannin, 943.

Prostate Enlarged.

Alkalies, 525. When irritation of the bladder with acid urine.
Ammonium Benzoate, 574. For cystitis with alkaline urine.
Ammonium Chloride, 567.
Conium, 846.
Ergot, 983.
Iodine, 491. Apply to rectum.
Iodoform, 729. As suppository very useful.

Prostatitis.

Blisters, 299, 300, 302. To perineum in chronic cases.
Buchu, 803.
Cantharides, 1002. Small doses of tincture.
Cubebs, 937.
Hot Injections.
Hydrastis, 756. Internally and locally.
Iron, 672.
Silver Nitrate, 607. Locally.
Turpentine, 950.

Prurigo and Pruritus.

Aconite, 751. Externally.
Alum, 586, 587. A strong solution for pruritus vulvæ.
Arsenic, 643, 644. Internally.
Atropine, 903.
Balsam of Peru, 817.
Boracic Acid, 508.
Borax, 555. Saturated solution.
Calomel, 621. Ointment very useful in pruritus ani.
Carbolic Acid, 736-738. Internally and locally, especially in prurigo senilis.
Chloral, 717, and Camphor, 929.
Chloroform Ointment, 726, 727.
Cod-Liver Oil, 997. As inunction.
Corrosive Sublimate, 86. For pruritus vulvæ.
Cyanide Potassic, 531. As lotion or ointment to be used with care.
Galvanism.
Gelsemium, 891.
Glycerin, 883.
Glycerole of Tar, 933.
Hydrocyanic Acid, 515. Locally.
Iodoform, 729. As ointment.
Liquor Carbonis Detergens.
Mercury, 618. Locally.
Opium, 775.

Prurigo and Pruritus.

Oil of Cade.
Petroleum Oil, 688.
Pilocarpin, 804.
Potassium Carbonate, 533.
Silver Nitrate, 607.
Sodium Carbonate, 552.
Stavesacre, 752.
Sulphate of Zinc, 601.
Sulphides, 541, 584.
Sulphites, 560.
Tar Ointment, 953.
Tobacco, 903. Useful but dangerous.

Psoriasis.

Aconite, 751.
Alkaline Bath, 413.
Ammonium Carbonate, 570.
Ammonium Chloride.
Arsenic, 643, 644.
Baths, 396 *et seq.*
Berberine, 931.
Bleeding, 367.
Calomel, 621. Locally as ointment.
Carbonic Acid, 509.
Chromic Acid, 508. 10 grs. to the ounce in psoriasis of tongue.
Chrysophanic Acid, 823.
Cod-Liver Oil, 997.
Copaiba, 826.
Copper Sulphate, 605.
Creasote Baths, 739.
Cupric Sulphate, 605.
Electricity. Constant current rapidly applied.
Glycerin, 883.
Hepar Sulphuris.
India Rubber Solution.
Iodine, 491.
Iris, 972.
Lead Iodide, 633. Locally.
Mercury, 618. Locally as ointment.
Mezereon, 301.
Nitric, 502. and Nitro-Hydrochloric, 503. Acids. When eruption is symptomatic of indigestion.
Phosphorus, 640. As substitute for arsenic.
Potassium Acetate, 535.
Potassium Iodide, 543.
Silver Nitrate, 607. In psoriasis of tongue.
Sulphur Iodide, 490. Internally and externally.
Sulphur, 482. Internally.
Tar, 953. As ointment.
Thymol, 920.
Ulmus, 944.
Vaseline, 688.

Ptosis.

Arseniate of Soda, 647.
Ergot, 983.
Paregoric Acid, 761.
Salicylic Acid, 741.
Veratria, 966. Locally to the eyelids and temples.
Zinc Chloride, 601.

Ptyalism.

Acids. In small doses internally and as gargles.
Alcohol, 701. Dilute as gargle.
Atropia, 903. Hypodermically.
Belladonna, 168, 170, 903. Very useful.
Calabar Bean, 186.
Chlorate of Potash, 538. As gargle.
Iodide of Potassium, 545.
Iodine, 491. As gargle, 1 of tincture to 30 of water.
Tannin, 943.

Puerperal Convulsions.

Aconite, 751. In small doses frequently.
Belladonna, 903. Useful.
Chloral, 717. In full doses.
Chloroform, 726, 727. By inhalation.
Dry Cupping over Loins.
Ice, 327. To head.
Morphia, 765, 766. Hypodermically very useful.
Mustard, 300. To feet.
Nitrite of Amyl, 710. Of doubtful utility.
Veratrum Viride, 963. Pushed to nausea very useful.

Puerperal Fever.

Aconite, 751. Useful at commencement.
Alkaline Sulphate, 527. In early stages.
Calumba, 465. As tincture.
Opium, 775. For wakefulness and delirium very useful.
Permanganate of Potash, 540.
Quinine, 862. In large doses.
Stramonium, 906. When cerebral excitement.
Turpentine, 950. When much vascular depression and tympanites.

Puerperal Mania.

Aconite, 751. With much fever.
Anæsthetics, 727. During paroxysm.
Bromide of Potassium, 547, 548.
Chloral, 717.
Cimicifuga, 754. Useful in hypochondriasis.
Hyoscyamus, 905. In mild cases.
Iron, 762. In anæmia.
Opium, 775.
Poultices, 412.
Quinine, 862. When much sickness.
Stramonium, 906. When delirium furious but intermittent, or suicidal, or when impulse to destroy child.
Tartar Emetic, 652, 653. Frequently repeated.

Puerperal Peritonitis.

Aconite, 751. At commencement.
Antimony, 652.
Cimicifuga, 754. In rheumatic cases.
Laxatives, 339. Useful combined with Dover's powder and hyoscyamus.
Opium, 775. Very useful.
Quinine, 862. In large doses.
Turpentine, 950. As stimulant, 10 ♏. frequently repeated.

Purpura.

Alum, 586, 587. Locally with brandy.
Ergot, 983. Very useful.
Gallic Acid, 944.
Iron, 672. Internally.
Nitrate of Potash, 537.
Nux Vomica, 884.
Quinine, 862.
Tannic Acid, 943.
Turpentine, 950.

Pyæmia.

Boracic Acid, 508.
Oil of Cloves, 837. Locally.
Permanganate of Potash, 540. Internally.
Quinine, 862. In large doses.
Salicin, 939.
Salicylic Acid, 741.
Turpentine, 950. As stimulant.

Pyelonephritis.

Eucalyptus, 844.
Hydrastis, 756.

Pyrosis.

Bismuth, 658.
Camphor, 929.
Carbolic Acid, 737, 738.
Creasote, 739.
Gallic Acid, 944.
Glycerin, 883.
Manganese Oxide, 673
Mineral Acids.
Nux Vomica, 884.
Pulvis Kino Compositus, 761.
Sulphur Oxide and Nitrate, 482.
Sulphuric Acid, 493.

Relapsing Fever.

Laxatives, 339.
Leeches, 1003. As cupping for headache.
Quinine, 862.

Remittent Fever.

Aconite, 751.
Emetics, 326.
Gelsemium, 891. In bilious remittents.
Morphia, 766. Hypodermically.
Packing, 166. Useful.
Quinine, 862. 20-30 grs. for a dose, once or twice daily.

Renal Calculi, *vide* Calculi.

Alkaline Waters.
Ammonium Benzoate, 574.
Chalebiates.
Wildungen Water.

Rheumatic Arthritis.

Aconite, 751. Locally.
Arnica, 873. Internally and externally.
Arsenic, 643, 644.
Cimicifuga, 754. When pains and nocturnal.
Cod-Liver Oil, 361, 997.
Colchicum, 969.
Guaiacum, 800.
Iodine, 491. Internally as tonic.
Lithium, 562. Internally and locally.
Potassium Bromide, 546-548. Sometimes relieves pain.
Sulphur, 483.
Turkish Bath, 415.

Rheumatism, Acute.

Aconite, 751.
Alkalies, 525.
Ammonium Bromide, 572.
Arnica, 873.
Blisters, 302, 366. Very efficient around joints near to the cardiac region.
Bryonia, 845.
Cimicifuga, 754.
Colchicum, 969.
Cold Baths, 405.
Digitalis, 915.
Dulcamara, 898. In persons liable to catarrh.
Iron, 672.
Lime Juice, 795.
Lithium Bromide, 563. Especially when insomnia and delirium present.
Opium, 775. One gr. every 2 or 3 hours, especially when cardiac inflammation.
Permanganate of Potash, 540.
Quinine, 87, 862. As antipyretic.
Rhus Toxicodendron, 812. Exceedingly useful in after stage and subacute forms.
Salicin, 939.
Salicylate of Soda, 559. Relieves pain most quickly.
Sulphurous Acid, 498. Fumigation.
Trimethylamine.
Veratrum Viride, 963.

Rheumatism, Chronic.

Aconite, 751.
Arnica, 873.
Belladonna, 903.
Bryonia, 845.
Burgundy Pitch, 953. As plaster locally.
Cajeput Oil, 839. Internally and externally.
Chimaphila, 878.
Cimicifuga, 754.
Cod-Liver Oil, 361, 997. Internally and
Colchicum, 969.
Dulcamara, 898.
Guaiac, 801.
Iodide of Potassium, 545. Especially when pain worse at night.
Iodine, 491, 545. Locally.
Lithium Bromide, 563. When smaller joints affected.
Lupulin, 948.
Mercury and Morphia, 618, 765. Oleate locally.
Mezereon, 957.
Phytolacca, 924.
Quinine, 862. When much debility and night sweats.
Rhus Toxicodendron, 812. Internally and locally.
Sulphur, 482. Locally and as sulphides or sulphur waters internaliy.
Thuja Occidentalis, 954.
Turkish Baths, 415.
Xanthoxylum, 804.

Rickets.

Calcium Phosphate, 583. If child is sucking it may be given to nurse.
Cod-Liver Oil, 361, 997.
Cold Sponging, 367.
Ferric Iodide, 489.
Nitro-Hydrochloric Baths, 413.
Quinine, 862.

Sarcinæ.

Carbolic Acid, 737.
Creasote, 739.
Gastric Syphon. To wash out stomach.
Sulphitis.
Sulphuric Acid, 498.

Scabies.

Anise, 849. As ointment.
Arsenic, 643, 644.
Baking of clothes to destroy ova.
Balsam of Peru, 816, 817. Locally, agreeable and effective.
Benzoic Acid, 880. As ointment or lotion.
Carbolic Acid, 737. Dangerous.
Coaltar Naphtha, 749.
Cocculus Indicus, 757. As ointment.
Copaiba, 826.
Copper Sulphate, 605.
Hog's Lard, 993.
Kamala, 935. As ointment.
Mercury, 618. White precipitate ointment.
Oil, 881. Inunction.
Petroleum, 688.
Soft Soap, 882.
Stavesacre, 752. As ointment.
Storax, 834, 940. With almond oil, when skin cannot bear sulphur.
Sulphide of Calcium, 584.
Sulphur, 480. As ointment.
Sulphuric Acid, 498. Internally as adjuvant.
Sulphurous Acid, 498.
Tar, 953. Ointment.
Vaseline, 688

Scarlet Fever.

Aconite, 751.
Arsenic, 643, 644. If tongue remains red and irritable during convalescence.
Belladonna, 903.
Carbolic Acid, 737. As gargle.
Carbonate of Ammonium, 570. Greatly recommended in frequent doses given in milk or cinnamon water.
Chlorine Water, 487, 488. As gargle.
Cold Compress to throat, 415.
Cold Affusion, 406.
Digitalis, 915.
Fat as inunction to hands and feet during the rash, and over the whole body during desquamation.
Ferric Perchloride, 671. In advanced stage with albuminuria and hematuria, very useful.
Ice, 327. To suck especially at commencement.
Juniper Oil, 955. As diuretic when dropsy occurs.
Mercury, 618. ½ of a gr. of grey powder every hour to lessen inflammation of tonsils.
Mineral Acids, 497. Internally and as gargle.
Mustard Bath, 413. When rash recedes.
Packing, 405. Useful and comforting.
Potassium Permanganate, 540. As gargle to throat.
Purgatives, 339. More useful to prevent albuminuria.
Rhus Toxicodendron, 812
Salicylate of Soda, 559. As antipyretic.
Salicylic Acid, 741.
Strychnine, 888. Hypodermically in paralysis.
Sulphurous Acid, 498. Inhalation when throat much affected.
Veratrum Viride, 963.

Sciatica.

Aconite, 748. As ointment or liniment.
Acupuncture.
Aquapuncture.
Atropia, 903.
Belladonna, 903.
Blisters, 299, 300, 302.
Cautery. Exceedingly useful, slight application of Paquelin's thermo-cautery.
Chloride of Ammonium, 567.
Chloroform, 327, 726. Locally as liniment, inhalation when pain excessive.
Croton Oil, 934. Internally as purgative.
Electricity.
Ether, 128, 705. As spray.
Iodide of Potassium, 545.
Morphia, 766. Hypodermically most useful.
Poultices, 412.
Stramonium, 906. Internally pushed until physiological action appears.
Sulphur, 482. Tied on with flannel over painful spot.
Turkish Bath, 415.
Turpentine, 950. In ½ oz. doses internally for 3 or 4 nights successively.
Veratria, 966, 967. As ointment.

Scrofula.

Blisters, 302. To enlarged glands.
Calcium Phosphate, 583.
Chloride of Calcium, 582.
Cod-Liver Oil, 361, 997. Exceedingly serviceable.
Iodides, 545.
Iodide of Iron, 676.
Iodine, 490, 491. Locally to glands and internally.
Sulphides, 541, 584.

Scurvy.

Acids, 507. As preventive in the absence of lime juice.
Aconite, 751. In acute stomacaæ with salivation in scorbutic conditions.
Alcohol, 701. Diluted as gargle.
Alum, 586. Locally with myrrh for ulcerated gums.
Ammonium Carbonate, 570. In scorbutic diathesis.
Arsenic, 643, 644. In some scorbutic symptoms.
Atropia, 903. Hypodermically when salivation.
Cinchona, 862, 863. As decoction, or diluted with myrrh as gargle.
Citric Acid, 507. As substitute for lime juice.
Lemon Juice, exceedingly useful as preventive and curative.
Liberal Diet, often sufficient.
Liquor Sodæ Chlorinatæ, 455. Locally to gums.
Oranges, useful.
Quinia, 862. With mineral acids internally.
Silver Nitrate, 607.
Tartar Emetic, 652, 653.
Vegetable Charcoal, 478. As tooth powder to remove fœtid odour.
Vinegar, 505. Substitute for lime-juice.

Sea-Sickness.

Apomorphia, 765, 766.
Arsenic, 643, 644.
Atropia, 903. Hypodermically in epigastrium.
Bromide of Potassium, 547. Very useful in large doses.
Bromide of Sodium, 558.
Calumba, 751.
Cannabis Indica, 947.
Capsicum, 899.
Champagne Iced.
Chloral, 717. 15 to 30 grs. every 4 hours most useful.
Chloral Hydrate, 717.
Chloric Ether, 706.
Chloroform, 726. Pure, 2-5 ms. on sugar.
Creasote, 739.
Ice, 327. To spine.
Magnetic Belt.
Morphia, 766. Hypodermically.
Nitrite of Amyl, 710. Inhalation.
Nitroglycerine, 713.
Nux Vomica, 884. When indigestion with constipation.
Petroleum, 688.
Quinine, 862.

Seborrhœa.

Borax, 555, with Glycerin, 883, and Lead Acetate, 631.
Glycerin, 883.
Iodine, 491.
Lead Acetate with borax and glycerine, as above.
Phosphorus, 640.
Sodic Chloride, 550.
Zinc Oxide, 630.

Sneezing.

Arsenic, 643. In paroxysmal sneezing.
Belladonna, 903.
Chamomile Flower, 871. In nares.
Camphor, 929. As powder.
Cotton Plug, in nares.
Gelsemium, 891. In excessive morning sneezings with discharge.
Iodine, 491. Inhalation.

Sneezing.

Mercury, 618. Heaviness of head and pain in limbs.
Potassic Iodide, 545. 10 gr. doses frequently repeated.
Pressure beneath Nose, 211.

Somnambulism.

Opium, 775.
Potassic Bromide, 547.

Spasmodic Affections.

Aconite, 903. Externally and internally.
Ammonia, 571.
Amyl Nitrite, 710.
Arnica, 873.
Belladonna, 903.
Camphor, 929.
Cardamoms, 971.
Chamomile Oil, 871.
Chimaphila. 878.
Chloroform, 726.
Cimicifuga, 754.
Colocynth, 843.
Conium, 846.
Copper Sulphate, 605. In chorea.
Electricity.
Gelsemium, 890.
Hyoscyamus, 904.
Ice, 327. Ice to spine.
Ipecacuanha, 865.
Leeches, 1002.
Lobelia, 877.
Local Pressure, 137, *vide* Sneezing. Over the ovary in hysteria.
Lupuline, 948.
Nux Vomica, 884.
Opium, 775.
Oxygen, 475.
Physostigma, 821.
Plumbum, 681.
Potassium Bromide, 547.
Poultices, Mustard, 412.
Secale, 983.
Silver Nitrate, 607.
Strychnia, 868.
Sulpho Carbolate, 482.
Sulphur, 482.
Sumbul, 851.
Tobacco, 908.
Veratria, 966.
Veratrum Viride, 963.

Spermatorrhœa.

Arsenic, 643.
Atropia, 903.
Belladonna, 903.
Bromides, 546.
Camphor Bromide, 930.
Cannabis Indica, 946.
Cantharides, 1002.
Cimicifuga, 754.
Digitalis, 915.
Electricity.
Ergot, 983.
Ferric Bromide.
Ferric Iodide, 489.
Gold Chloride, 679.
Hydrastis, 756.
Iron, 672.
Nitrate of Silver, 607.
Nux Vomica, 884.
Phosphorus, 640.
Physostigma, 822.
Potassic Bromide, 547.
Quinia, 862.
Silver Nitrate, 607.
Strychnia, 888.
Sulphur, 482.
Turpentine, 950.

Spina Bifida.

Collodion, 790. As means of compression.
Cotton Wool over tumor.
Glycerin, 882. Injection after tapping.
Iodine, 865. Injections.
Lime Phosphate, 583.
Potassic Iodide, 545.

Spinal Concussion.

Arnica, 873.
Bleeding, 367. To relieve heart.
Lead-Water and Opium. As lotion.
Leeches, 1001.
Vinegar, 505. To restore consciousness.

Spinal Congestion.

Aconite, 903.
Antiphlogistic Treatment.
Cold Affusions, 403. To spine.
Ergot, 983.
Gelsemium, 891.
Nux Vomica, 884.
Turpentine, 950.
Wet Cupping, 367.

Spinal Irritation.

Aconite Ointment, 748. Locally.
Arsenic, 643.
Atropia, 903.
Belladonna, 903.
Blisters, 302.
Cimicifuga, 754.
Cocculus Indicus, 757.
Conium, 846.
Counter-irritation, 297-303.
Digitalis, 915.
Electricity.
Ergot, 983.
Ignatia, 884.
Leeches, 1001.
Nux Vomica, 884.
Opium, 775. Small doses.
Oxalic Acid, 507.
Phosphoric Acid, 585.
Phosphorus, 640.
Picrotoxin, 759.
Sinapis, 302.
Sodium Hypophosphite, 590.
Strychnia, 888.
Veratrum Viride, 963.

Spinal Paralysis and Softening.

Belladonna, 903.
Electricity.
Ergot, 983.
Oxalic Acid, 507.
Phosphorus, 640.
Plumbic Iodide, 633.

Splenic Affections.

Aconite, 751.
Ammonium Iodide, 573.
Bryonia, 845.
Ferrum, 672.
Grape Cure.
Iodine, 491.
Iodide of Ammonium, 573.
Mercuric Biniodidi, 625.
Quinia, 888.

Sprains.

Aconite, 751.
Ammonium Chloride, 567.

Sprains.

Arnica, 873.
Bandaging.
Cold Douche, 408.
Collodion, 790.
Hot Fomentations, 411.
Inunction, 417.
Iodine, 491.
Massage, 107.
Oil of Bay.
Rest.
Rhus Toxicodendron, 812.
Shampooing.
Strapping.
Turpentine, 950.

Stammering.

Hyoscyamus, 905.
Stramonium, 906.
Vocal Training.

Sterility.

Alkaline Injections, 448.
Aurum, 679. When the result of chronic metritis or amenorrhœa.
Borax, 555.
Cantharides, 1002.
Cimicifuga, 754.
Conium, 846.
Dilatation, of os and cervix when obstruction, with dysmenorrhœa.
Gossypium, 788.
Guaiacum, 801.
Intra-Uterine Stems.
Iodine, 491.
Metallic Bougies,
Potassic Iodide, 545.

Stings and Bites.

Aconite, 751.
Allium, 953.
Ammonia, or Alkalies, 571.
Aqua Calcis, 579.
Aqua Potassæ, 333.
Arsenic, 643, 644.
Camphor, 929.
Carbolic Acid, 736-738.
Chloroform, 726. On lint.
Fennel, 849 Keep away fleas.
Ipecacuanha, 865.
Liquor Ammoniæ, 569.
Peppermint, 918. Soap scented with it and rubbed over face keeps off mosquitos.
Rosemary, 917.
Sage, 922.
Silver Nitrate, 607.
Stimulants, 975.
Sugar, 976.
Tobacco, 906. Moistened and squeezed on spot.

Stomatitis.

Acids, Mineral.
Alcohol, 628.
Alum, 386.
Carbolic Acid, 736-738.
Chlorate of Potassium, 538.
Copper Sulphate, 605.
Cornus, 853.
Eucalyptus, 841.
Glycerin of Tannin, 885.
Hydrastis, 756.
Iris, 952.
Mercury, 618.
Nitric Acid, 502.
Phytolacca, 924.
Potassium Chlorate, 538.
Salicylic Acid, 741.

STRABISMUS.

ATROPIA, 902.
BELLADONNA, 903.
BRYONIA, 845.
ELECTRICITY.
HYOSCYAMUS, 905.
OPERATION.
SPIGELIA, 891.

STROPHULUS.

ANTIMONIUM CRUDUM, 652.
CARBONATE OF LIME, 582.
CHAMOMILE, 871.
GLYCERIN, 883.
LANCING THE GUMS.
PULSATILLA, 753.

SUNSTROKE.

APOMORPHIA, 765, 766.
ARTIFICIAL RESPIRATION.
BELLADONNA, 903.
BLEEDING, 367.
BRANDY, 693, 701. In small doses.
CAMPHOR, 929.
CHLOROFORM, 726, 727.
ERGOT, 983.
GELSEMIUM, 891.
HOT BATH, 411.
LEECHES, 367, 1002.
NITRITE OF AMYL, 710.
NITRO-GLYCERIN, 713.
POTASSIC BROMIDE, 547.
QUININE, 862.
SCUTELLARIA, 922.
TEA, 796.
VERATRUM VIRIDE, 963.
WATER, COLD, 367. Affusion.
WET SHEET, 166, 450.

SUPPURATION.

ALCOHOL, 693.
ARNICA, 873.
BARK, 834, 835.
CALENDULA, 874.
CHAMOMILE, 871.
HYPOPHOSPHITES, 557, 583, 678.
IODIDE OF IRON, 676.
IODIDE OF MANGANESE, 678.
MERCURY, 618.
PHOSPHATES, 566, 583, 677.
QUINIA, 862.
SARSAPARILLA, 957.
SULPHIDES, 340, 355, 541, 584.

SURGICAL FEVER.

ACONITE, 751.
CHLORAL, 717.
CINCHONA, 854, 855.
SALICYLIC ACID, 741.

SYCOSIS.

ARSENIC AND MERCURY, 618, 643.
CARBOLIC ACID, 736-738.
CHLORIDE OF ZINC, 601.
COD-LIVER OIL, 997.
NITRIC ACID, 502.
SODIC SULPHITE, 560.
SULPHUROUS ACID, 498.
THUJA, 954.
TURPENTINE, 950.

SYNCOPE.

ACONITE, 751.
ALCOHOL, 693.
AMMONIA, 569.
ARSENIC, 643.
BELLADONNA, 903.
CAMPHOR, 929.
CHAMOMILE, 871.
CHLOROFORM, 726.
CINNAMON, 927.
COCCULUS INDICUS, 757.
COLD WATER over face and volatile substances to the nose.
COUNTER-IRRITATION TO EPIGASTRIUM.
DIGITALIN, 915.
GALVANISM.
HEAT, 2-6.
IODINE, 491.
LAVANDULA, 918.
MUSK, 988.
NITRITE OF AMYL, 710.
POSITION. Head between knees.
VERATRUM ALBUM, 210.

SYNOVITIS.

ACONITE, 751.
ALCOHOL AND WATER, 693. Equal parts.
ARNICA, 873.
BANDAGE OR STRAPPING.
BLISTERS, 302.
BRYONIA, 845.
CALCIC SULPHIDE, 584.
CARBOLIC ACID, 736-738. Injections.
CARBONATE OF LIME, 582.
COD-LIVER OIL, 361, 997.
COLOCYNTH, 843.
HEAT.
IODINE, 491. Injection.
MERCURY, 618.
OLEATE OF MERCURY, 517.
POTASSIC IODIDE, 545.
PRESSURE.
PULSATILLA, 753.
SHAMPOOING AND ASPIRATION, 301.
SILVER NITRATE, 607.
SPLINTS.
SULPHUR, 482.

SYPHILIS.

ARSENIC, 643.
AURUM, 679.
CALCIC SULPHIDE, 584.
CALENDULA, 874.
CALOMEL, 621.
CAMPHOR, 929.
CARBOLIC ACID, 736-738.
COD-LIVER OIL, 361, 997.
CREASOTE, 739.
CAUTERIZATION. Of primary sore.
GOLD, 679.
GUAIACUM, 801.
HYDRASTIS, 756.
IODIDES, 362.
IODINE, 491.
IODOFORM, 729.
IRON, 672.
MANGANESE, 678, 679.
MERCURY, 618.
MONSEL'S SOLUTION, 669.
NITRATE OF SILVER, 607.
NITRIC ACID, 502.
NITRO-MURIATIC ACID, 383.
OPIUM, 775.
POTASSIC BICHROMATE, 542.
POTASSIC CHLORIDE, 533.
POTASSIC IODIDE, 543.
SALICYLIC ACID, 741.
SANGUINARIA, 778.
SARSAPARILLA, 957.
STILLINGIA, 933.
SUPPOSITORIES, 427.
TURKISH BATHS, 415.
ZINC CHLORIDE, 601.

Tabes Mesenterica.

Alcohol, 698.
Arsenic, 648.
Barium Chloride, 577.
Chloride of Lime, 584.
Cod-Liver Oil, 997.
Diet. Simple and nourishing.
Fatty Inunction, 415.
Ferri Pernitrate, 673.
Gallic Acid, 944.
Gelsemium, 891.
Iodine, 491.
Olive Oil, 882.
Phosphates, 566, 583, 677.
Phosphoric Acid, 505.
Sarsaparilla, 957.

Teeth.

Alum, 586, 587.
Arnica, 873.
Arsenic, 643.
Calcium Phosphate, 583.
Carbonate of Lime, 582.
Charcoal, 308.
Cinchona, 862, 863.
Collodion, 790.
Creasote, 739.
Iodine, 491.
Liquor Sodæ Chlorinatæ, 455.
Mercury, 618.
Phosphorus, 640.
Potassic Iodide, 545.
Sodium Bicarbonate, 553.
Stavesacre, 752
Washing and Brushing, 308.

Testicles.

Belladonna, 903.
Collodion, 790.
Compression.
Conium, 846
Copaiba, 826.
Digitalis, 915.
Gold, 679.
Hamamelis, 940.
Heat and Cold.
Iodine, 491.
Iodoform, 729.
Magnesium Sulphate, 590.
Mercury and Morphia Oleate, 517.
Nux Vomica, 884.
Phosphoric Acid, 505.
Plumbago, 629.
Potassic Bromide, 546.
Rest.
Silver Nitrate, 607.

Tetanus.

Aconite, 751.
Acupuncture.
Apomorphia, 765, 766.
Arnica, 873.
Arsenic, 643.
Atropine, 903.
Belladonna, 903.
Bromides, 512, 547, 558, 563, 582.
Bryonia, 844.
Calabar Bean, 822.
Cannabis Indica, 946, 947.
Chloral, 717.
Chloroform and Ether, 706, 726.
Conium, 846.
Curare, 890.
Freezing Nerve.
Gelsemium, 891.
Hyoscyamus, 905.
Ice Bag to Spine.
Nerve Stretching.

Tetanus.

Neurotomy.
Nicotia, 908.
Nitrite of Amyl, 710.
Opium, 775.
Physostigma, 819.
Potassic Bromide, 546, 548.
Quinine, 862.
Strychnia, 888.
Tobacco, 908.
Vapour Bath, 414.
Warm Baths, 411.

Throat, Sore.

Aconite, 751.
Alum, 586, 587.
Apis, 996
Arsenic, 643.
Balsam of Peru, 817. Externally.
Balsam of Tolu, 817. Externally.
Belladonna, 903.
Capsicum, 899.
Carbolic Acid, 736-738.
Catechu, 828.
Cimicifuga, 754.
Cold Compress, 410.
Ferri Perchloride, 671.
Glycerin of Tannin, 943.
Guaiacum, 801.
Hydrastis, 756.
Ice, 216. Sucked.
Inhalations, 423. Steam of boiling water and vapour of hot vinegar.
Iodine, 491.
Ipecacuanha, 865.
Mercury, 618.
Myrrh, 813.
Nightshade, 846.
Nitre, 538.
Nitric Acid, 501
Phytolacca, 624. Internally and as gargle.
Podophyllum, 754.
Pulsatilla, 753.
Sanguinaria, 779
Silver Nitrate, 607.
Sulphurous Acid, 498.
Veratrum Viride, 963.
Zinc Chlorate, 601.
Zinc Sulphate, 601.

Tic Douloureux.

Aconite, 751.
Ammonii Chloridum, 567, 568.
Aqua Ammoniæ, 445.
Arsenic, 643.
Atropia, 903. Hypodermically.
Beberiæ Sulphas, 931.
Caffein, 798.
Cannabis Indica, 946, 947.
Croton, Chloral, 718.
Counter-Irritation, 297-303.
Delphinia. Externally.
Electricity.
Ergot, 983.
Ferrum, 536, 669.
Heat.
Hyoscyamus, 905.
Hypodermic Injection, 764.
Iodides.
Lauro-Cerasus.
Morphia, 765, 766.
Morphia, 766. Hypodermically.
Neurotomy.
Nitrate of Silver, 607.
Oleum Tiglii, 457.
Phosphorus, 640.
Physostigma, 819-822.
Stramonium, 906.
Sulphur, 482.
Thuja, 954.
Veratria, 964.

Tinea Circinata.

Boracic Acid, 508.
Carbolic Acid, 736-738.
Carbonate of Lime, 582.
Chromic Acid, 508.
Cocculus Indicus, 757.
Cod-Liver Oil, 997.
Goa Powder, 823.
Mercury, 618.
Oil of Cade.
Sulphur, 482.
Sulphurous Acid, 498.

Tinea Decalvans.

Cantharides, 1002.
Carbolic Acid, 736-738.
Iodoform, 729.
Parasiticide Lotions, 817.
Pilocarpin, 804.
Raw Onion. Rubbed on.
Sapo Viridis, 882.
Tannin, 943.

Tinea Favosa.

Arsenic, 643.
Calcic Sulphide, 584.
Carbolic Acid, 736-738,
Cleanliness.
Dulcamara, 898.
Epilation.
Hyposulphites, 560.
Mercury, 618.
Nitric Acid, 502.
Oils, 300.
Oleander.
Petroleum, 688.
Sulphides, 541, 584.
Sulphurous Acid, 498,
Turkish Bath, 415.
Viola Tricolor, 782.
Zinc Chloride, 601.

Tinea Tonsurans.

Arsenic Iodide, 648.
Carbolic Acid, 736-738.
Cocculus Indicus, 757.
Cod-Liver Oil, 997.
Creasote, 739.
Croton Oil, 934.
Epilation.
Goa Powder, 823.
Iodine, 491.
Lead, 629.
Manganese, 678. In porrigo capitis.
Mercury Oleate, 517.
Menthol, 181.
Sulpho-Cyanide of Potassium, 537.
Thymol, 920.
Turpentine, 950.
Vaseline, 688.
Viola Tricolor, 782.

Tongue.

Potassic Bromide, 546-548.
Potassic Chlorate, 538.
Potassic Iodide, 543.
Pyrethrum, 868.
Rhus Toxicodendron, 812.
Silver Nitrate, 607.

Tonsillitis.

Aconite, 751.
Alum, 586, 587.
Apis, 999.
Arsenic, 643.
Belladonna, 903.
Capsicum, 899.
Carbolic Acid, 736-738.
Cold Wet Compress, 410.
Eucalyptus, 841.
Gallic Acid, 944.
Guaiac, 801.
Ice and Wet Pack, 166, 327, 405.
Iodine, 491.
Iodides, 545, 558, 573.
Mercury, 618.
Milk and Water Gargle.
Nitrate of Silver, 607.
Opium, 775.
Phytolacca, 924.
Potassic Iodide, 343.
Quinine, 862.
Silver Nitrate, 607.
Steam of Hot Water,
Tannic Acid, 943.

Tonsils, Enlarged.

Ammonium Iodide, 573.
Belladonna, 903.
Bryonia, 845.
Calcic Phosphate, 583.
Catechu, 828.
Excision.
Ferri Tincture, 535.
Iodine Tincture, 489.
Massage, 107.
Oxgall. 991. Locally.
Silver Nitrate, 607.
Tannin, 943.

Tonsils, Ulcerated.

Ailanthus Glandulosa.
Cantharides, 1002.
Mercuric Iodide, 625.
Potassium Iodide, 543.
Sulphurous Acid, 498.

Toothache.

Aconite, 751.
Alum, 585-587.
Arsenic, 643.
Belladonna, 903.
Bryonia, 845.
Camphor, 929.
Capsicum, 899.
Carbolic Acid, 736-738. Very useful.
Caustic Potash, 533.
Chamomile, 871.
Chloral, 717.
Chloroform, 726.
Coffee, 865.
Colchicum, 969.
Collodion, 790.
Conia, 846.
Creasote, 738. Very useful.
Croton Oil, 734.
Electricity.
Gelsemium, 891.
Ginger, 970.
Mercury, 618.

Tonguf.

Aconite, 751.
Borax, 555.
Cinnamon, 927.
Cloves, 837. As gargle.
Conium, 846.
Ginger, 970.
Hydrastis, 756.
Iodine, 491.
Mercury, 618.
Mezereon.
Nitric Acid, 502.
Nux Vomica, 884.
Pepper, 937.
Phytolacca, 924.

Toothache.

Morphia, 765, 766.
Nitrate of Silver, 607.
Nitric Acid, 502.
Nitro-Glycerin, 713.
Nux Vomica, 884.
Oil of Cloves, 337.
Opium, 775.
Pulsatilla, 753.
Sodium Bicarbonate, 553.
Staphisagria, 752.
Tannin, 943.
Xanthoxylum, 804.
Zinc Chloride, 601

Torticollis.

Aconite, 751.
Arsenic, 643.
Belladonna, 903.
Capsicum, 899.
Cimicifuga, 754.
Conium, 846.
Dulcamara, 898.
Electricity.
Ether Spray, 123.
Galvanization.
Local Pressure.
Mercury, 618.
Nerve Stretching.
Nux Vomica, 884.

Trismus.

Aconite, 751.
Anæsthetics, 127, 171.
Belladonna, 903.
Calabar Bean, 822.
Cannabis Indica, 757.
Chloral, 717.
Conium, 846.
Ether, 704.
Gelsemium, 891.
Opium, 775.
Physostigma, 819-822.

Tumors.

Acupuncture.
Arnica, 873.
Barium Carbonate.
Belladonna, 903.
Bryonia, 845.
Carbonate of Lime, 582
Chloroform, 726, 727.
Conium, 846.
Electrolysis.
Galbanum, 848.
Hyoscyamus, 905.
Iron, 672.
Pepsine, 990.
Plumbago, 629.
Potassic Carbonate, 533.

Tympanitis.

Acids and Alkalies.
Arsenic, 643.
Asafœtida, 847. Most useful.
Aspiration.
Bismuth, 658.
Camomile, 871.
Capsicum, 898.
Carbolic Acid, 736-738.
Chloral, 717.
Cocculus, 757.
Colchicum, 969.
Cubebs, 937.
Ginger, 970.
Glycerin, 882.
Hyoscyamus, 905.
Iris, 972.

Tympanitis.

Nux Vomica, 884.
Rue, 802.
Sumbul, 851.
Turpentine, 950.
Vegetable Charcoal, 477.

Typhilitis.

Arsenic, 643.
Belladonna, 903.
Ice Bag.
Leeches, 1001.
Magnesium Sulphate, 390.
Mercury.
Opium, 775. Most useful.
Veratrum Viride, 963.

Typhoid Fever.

Aconite, 751.
Alcohol Aliment, 693, 698, 699.
Arnica, 873.
Arsenic, 643.
Baths, 396 *et seq.*
Bismuth, 658.
Bryonia, 845.
Calomel, 622.
Carbonate of Ammonia, 570.
Cold Compress, 410.
Digitalis, 915.
Ergot, 983.
Hydrastis, 756.
Hydrochloric Acid, 500.
Hyoscyamus, 905.
Lead Acetate, 631.
Mercury, 618.
Muriatic Acid, 500
Opium, 775.
Phosphoric Acid, 505.
Phosphorus, 640.
Purgatives, 339.
Quinine, 862.
Rhus Toxicodendron, 812.
Serpentaria, 932.
Sodic Chloride, 550.
Sulphur, 482.
Tartar Emetic. 653.
Turpentine. 950.
Veratrum Viride, 963.

Typhus Fever.

Aconite, 751.
Arnica, 873.
Arsenic, 643.
Baths, 396 *et seq.*
Belladonna, 903.
Camphor, 929.
Chloral, 717.
Coffee, 865.
Counter-Irritation.
Diet, Nutritious.
Digitalis, 915.
Erythroxylon, 787.
Expectant Treatment.
Hydrochloric Acid, 500.
Hyoscyamus, 905.
Iodine, 491.
Mercury, 618.
Mineral Acids.
Muriatic Acid, 501.
Musk, 988.
Opium, 775.
Phosphoric Acid, 505.
Phosphorus, 640.
Podophyllin, 754.
Potassic Chlorate, 538.
Potassic Nitrate, 537.
Quinine, 862
Rhatany, 785.
Rhus Toxicodendron, 812.

Typhus Fever.

Serpentaria, 932.
Stimulants, 699.
Stramonium, 906.
Strychnia 888.
Sulphuric Acid, 498.
Tar. 953.
Tartar Emetic. 653.
Turpentine Oleate, 950.
Yeast, 984.

Vomiting.

Alcohol, 698.
Ammonia Salts, 566.
Ammonium Carbonate, 570.
Apomorphia, 765, 766.
Arsenic, 643.
Belladonna, 903.
Bismuth, 578.
Blisters, 302.
Bromides, 546, 558.
Bryonia, 845.
Calumba, 757.
Carbolic Acid, 736-738.
Carbonate of Ammonia, 570
Cerium Oxalate, 588.
Champagne.
Chloroform. 726
Cinnamon, 927.
Cloves, 837.
Cocculus Indicus, 757.
Conium, 846.
Creasote, 739.
Counter-Irritation, 297-303.
Emetics, 326.
Horseradish, 782.
Hydrocyanic Acid, 315.
Ice, 327. Sucked.
Iodi, 492. The liquor, administered internally in 3—5-m. doses.
Ipecacuanha, 865.
Iris, 972.
Koumiss, 989.
Leeches. 1001.
Lobelia, 877.
Magnesia. 591.
Mercury, 618.
Milk and Lime-Water, 597.
Morphia, 765, 766.
Nutrient Enemata.
Nux Vomica, 884.
Opium, 775.
Pepsine, 990.
Pulsatilla, 753.
Sanguinaria, 779.
Secale. 933.
Serpentaria, 932.
Silver Nitrate, 607
Strychnia, 888.
Sulphites, 560.
Sulphurous Acid, 498.
Tartar Emetic, 653
Veratrum Viride, 963.
Zinc, 602.

Vomiting of Pregnancy.

Aconite, 751.
Apomorphia. 765, 766.
Arsenic, 643.
Atropia, 903.
Bismuth, 658.
Bromide of Potassium, 328.
Calumba, 757.
Carbolic Acid, 736-738.
Cerium Oxalate, 588.
Champagne.
Coffee, 865.
Copper Sulphate, 605.
Creasote, 739.
Emetics, 321.

Vomiting of Pregnancy.

Hydrocyanic Acid, 515.
Iodine, 491.
Tincture of Iodine, 489.
Ipecacuanha, 865.
Koumiss, 989.
Morphia, 765, 766.
Nux Vomica. 884.
Pepsine. 990.
Potassic Bromide, 546-548.
Pulsatilla, 753.
Spinal Ice Bag.
Staphisagria, 752.
Strychnia, 888.
Sulphate of Copper, 605.

Warts.

Antimonic Chloride, 656.
Arsenious Acid, 646, 647.
Caustic Alkalies.
Carbolic Acid. 736-738.
Carbonate of Lime, 582.
Chloral, 717.
Chromic Acid, 503.
Corrosive Sublimate.
Creasote, 739.
Dulcamara, 893.
Magnesic Carbonate, 591.
Mercuric Nitrate, 625.
Nitric Acid, 502.
Permanganate of Potash, 540.
Phosphoric Acid, 505.
Poultice, 412.
Rhus Toxicodendron, 812.
Rue, 802.
Savine, 955.
Silver Nitrate, 607.
Sodic Carbonate, 552.
Staveacre, 752.
Sulphur, 482.

Wen.

Baric Carbonate.
Calcic Sulphide, 584.
Carbonate of Lime, 582.
Conium, 846.
Extirpation.
Plumbago, 629.

Worms.

Aconite, 751.
Aloes, 961.
Alum, 357. As an injection for thread-worms.
Ammonium Chloride, 358. As an adjunct.
Areca Nut, 357. For tape-worms.
Azedarach, 802.
Castor Oil, 358
Eucalyptol, 357. As an injection for thread-worms.
Ferric Perchloride, 671.
Filix Mas, 357. For tape worms.
Ignatia, 884.
Iron, 357, 358. As an injection for thread-worms, and as a tonic.
Kamala, 357. For tape-worms.
Kousso, 357. For tape-worms.
Lard or Oil.
Lime-Water, 357. As an injection for thread-worms.
Malefern, 978.
Pepo, 844,
Quinia, 862.
Quassia, 357. As an injection for thread-worms.
Santonica, 357. For round worms.
Santonine, 357. For round worms.
Scammony, 358.
Silver Nitrate, 607.
Sodium Chloride, 357. As an injection for thread-worms, 357.

Worms.

Tannin, 357. As an injection for thread-worms.
Tonics, 358. To prevent secretion of intestinal mucus.
Turpentine, 357. For tape worms.
Valerian, 867.

Wounds.

Aconite, 751.
Alcohol, 698.
Aloes, 961.
Arnica, 873.
Asafœtida, 847.
Balsam of Peru, 817.
Benzoin, 879.
Blotting Paper.
Boracic Acid, 308.
Calendula, 874.
Carbolic Acid, 733-738
Carbonic Acid, 509.
Chloral, 717.
Collodion, 790.
Conium, 846.
Eucalyptus, 841.
Glycerine, 883.
Hamamelis, 940.
Heat, 171.
Iodine, 491.
Iodoform, 729.
Lead Dressings, 629.
Nitrate of Silver, 607.
Nitric Acid, 502.
Opium, 775.
Petroleum, 688.
Permanganate of Potassa, 540.
Potassic Chloride, 533.
Poultices, 412.
Salicylic Acid, 741.

Wounds.

Sodium Chloride, 551. ½ per cent. solution.
Sugar, 976.
Sulphurous Acid, 498.
Tannin, 943.
Turkish Baths, 415.
Turpentine, 950.
Zinc Sulphate and Chloride, 601.

Yellow Fever.

Aconite, 751.
Arsenic, 643.
Belladonna, 903.
Bryonia, 845.
Calomel, 622.
Camphor, 929.
Cantharides, 1002.
Capsicum, 898.
Charcoal, 477, 478.
Chlorate of Potash, 538.
Chlorodyne.
Cimicifuga, 754.
Gelsemium, 891.
Iodide of Potassium, 543.
Ipecacuanha, 865.
Lead Acetate, 631.
Liquor Calcis, 579.
Mercury, 618.
Nitrate of Silver, 607.
Nux Vomica, 884.
Quinine, 862.
Salicylic Acid, 741.
Soda Benzoate, 558.
Stimulants, 699.
Sulphur Baths.
Tannic Acid, 943.
Tartar Emetic, 653.
Turpentine, 950.
Vegetable Charcoal, 477, 478.
Veratrum Viride, 963.

BIBLIOGRAPHICAL INDEX.

ACIDS.

Bertram, Z. f. Biol., xiv. p. 558.
Bobrik, Königsberger Diss., 1863.
Brunton and Cash, Phil. Trans. Pt. i., 1884, p. 231.
Buchheim, Arch. f. physiol. Heilk., 1857, p. 122; Pflüger's Arch., Bd. xii., 1876.
Cyon, Arch. f. Anat. u. Physiol., 1866, p. 416.
Edelfsen, Centralbl. f. d. med. Wiss., 1878, p. 513 (Phosphoric acid).
Elsässer, Die Magenerweichung d. Säuglinge, 1846.
Feitelberg, Dorpat. Diss., 1883.
Gähtgens. Centralbl. f. d. med. Wiss., 1872. vol. x. p. 833.
Gamgee, Centralbl. f. d. med. Wiss., 1879, p. 253 (different kinds of Phosphoric acid).
Gaskell, Jour. of Physiol., vol. iv. p. 48.
Goltz, Virch. Arch., Bd. xxvi. p. 1.
Heiss, Zeitschr. f. Biologie, 1876, Bd. xii. p. 151.
Hermann, Toxicolog., 1874, p. 160.
Hertwig, Thierheilkunde.
Hofbauer, Rossbach's pharmacol. Unters., Bd. iii.
Hofmann, Zeitschr. f. Biologie, 1871, Bd. vii. p. 338.
Höppener, Dorpat. Diss., 1863.
Kobert, Schmidt's Jahrb., Bd. clxxix. p. 225.
Koch, Zeitschr. f. rat. Medicin, 3 R. Bd. xxiv. p. 264.
Kühne, Unters. üb. d. Protoplasma, Leipzig, 1864.
Kurtz, Joh., Alkalientzieh. a. d. Thierk. Dorpat. Diss., 1874; u. Centralb. f. d. medicin. Wiss., 1874, vol. xii. p. 569.
Lassar, O., Pflüger's Arch., 1874, vol. ix. p. 44.
Leyden u. Munk, Virch. Arch., Bd. xxii. p. 237.
Maly, Liebig's Annal., Bd. clxxiii. p. 227, 1874.
Meissener, G., Zeitschr. f. rat. Med., 3 R. Bd. xxiv. p. 97.
Miquel, Arch. f. physiol. Heilk., 1851. p. 479.
Onsum, Arch. f. path. Anat., Bd. xxviii.
Piotrowski, Dorpat. Diss., 1856.
Quincke, Corr. Blatt. f. Schweizer Aertze, iv. No. 1, 1874.
Salkowski, Virch. Arch., Bd. lviii. p. 460.
Sieber, N., Journ. f. pract. Chemie, N. F., Bd. xix. 1879, p. 433 (Antiseptic action).
Strassburg, Pflüger's Arch., Bd. iv. p 454.
Strübing, A. f. exp. Path. u. Pharm., Bd. vi. 266 (Phosphoric acid).
Szabó, Z. f. physiol. Chem, i. p. 140 (complete literature of the acids in gastric juice).
Trachtenberg, Dorp. Diss., 1861.
Walter, Arch. f. exp. Path. u. Pharm., 1877, p. 148.
Zülzer, Virch. Arch., Bd. lxvi. pp. 223 and 282 (Phosphoric acid).

ACONITINE.

Achscharumoff, Reichert u. Du Bois's Archiv. 1866, p. 255; Schmidt's Jahrb., cxxxvi. p. 157, 1867.
Berthemot, Pharmaz. Centralbl., 1837, p. 733.
Böhm u. Ewers, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 385
Böhm und Wartmann, Verh. d. physik. med. Ges. in Würtzburg, N. F., Bd. iii.
Brodie, Phil. Trans. 1811, p. 178.
Coulson, Schmidt's Jahrb., xix. 285.
Cramoisy, E. P., Paris, J. B. Baillière & fils, p. 30. 1865.
Debout & Gubler, Schmidt's Jahrb., cxxv. 19, 1864.
Dyce Duckworth, Brit. Med. Journ., vol. i. p. 224, 1861; Schmidt's Jahrb, cxi. p. 23, 1861.
Ferrand, de l'Aconit. Lyon. Chauvine, 1861.
Fleming, An Inquiry into the Phys. & Medicinal Properties of the Aconitum napellus, Edinb. 1845.
Fothergill, Digitalis, London, 1871, p. 6.
Fristedt, Nord. Med. Ark. iii. 3, No. 18, p. 38, 1871.
Geiger, Hesse, Brandes Pharmaz. Centralbl., 1835, p. 85.
Gréhant & Duquesnel, Bull, gén. de Therap., Aug. 1871, p. 492.
Gubler, Bull. gén. de Thérap., lxvi. p. 385, May, 1864.
Hahn, Essai sur l'Aconit, Strasbourg, 1863.
Harley, St. Thomas' Hosp. Reports, v. p. 149.
Hottot et Debout, Bull. Thér., lxvi. p. 360, Ap. 1864.
Janus, Corn. de Man. Spec. Medic. inaug. de Aconito Lugd. Batav, 1841, 8vo. p. 68.
Lewin, Präger Vierteljahrs, Bd. cxxxi. p. 20
Liégeois & Hottot, Journ. de Physiol., iv. p. 520, Oct. 1861; Schmidt's Jahrb., cxiv. p. 291, 1862; Bull. de Thérap., Paris, lxv. p. 203, 1863.
Mackenzie & A. Guillaud, Arch. d. Physiol., 1875, p. 766.
Mackenzie, G. H., London Practitioner, xx. p. 100.
Mammi, Dell' Aconito Napello, Reggio, 1866, p. 30.
Nunneley, F. B., Proceed. of the Royal Society, vol. xviii. p. 46, 1870.
Orfila on Poisons (translated by Waller), 7th ed. vol. ii. p. 46.
Pereira, Elements of Mat. Med., 4th ed. ii. pt. ii. p. 684.
Praag, L. von, Virchow's Archiv, Bd. vii. 438-478, 1854.
Ringer, S., & W. Murrell, Journ. of Phys., i. p. 232, Nos. 4, 5.
Schroff, von, sen., Präger Vierteljahrs, xlii. p

ACONITINE.

129, 1854; Oest. Med. Jahrb., xvii. p. 57, 1861; Schm. Jahrb., cxii. 15, 1861.
Schulz, Marburger Diss., 1846.
Simon u. Sobernheim, Handb. d. Tox., p. 60.
Skey, Froriep's Not., ii. 80, 1837; Schmidt's Jahrb., xvii. p. 306.
Soubeiran, Schmidt's Jahrb., xix. 285.
Turnbull, On the Preparations and Medical Properties of the Natural Order Ranunculaceæ, London, 1835; Froriep's Not., i. 302, ii. 252 1837; Schmidt's Jahrbüch, xix. 285.
Weyland, Eckhard's Beitr., v. 1, p. 29.
Wibmer, Wirkungen, i. p. 33.

ALCOHOL.

Anstie, Stimulants and Narcotics, London, 1864; Lond. Practitioner, viii. p 148, Mar. 1872. July, 1874; Lond. Med. Review, 1862; reprint. Lancet, ii. Sep. 18, 1865, p. 343.
Baudot, E., L'Union Médicale, 1863.
Béchamp, London Lancet, 1873, vol. i. p. 846.
Bernard, Cl., Leçons sur les Effets des Substances toxiques, Paris, p. 397; Gaz. Méd. de Paris, 1856, p. 295.
Binz, Virchow's Archiv, 1871, iv. p. 529, Bd. liii.; Berl. Klin. Woch., xi. 11, p. 129, 1874-1876, p. 54; Archiv für exp. P. u. Ph., vi. 287.
Blair, Glasgow Med. Journ., Feb. 1870, p. 204.
Boeck, v., Unters. üb. d. Zersetz. d. Eiweiss. München, 1871.
Boeck, v., u. Bauer, Zeitschrift f. Biol. Bd. x. p. 361.
Boeker, Beitr. z. Heilkde., i. p. 247, 1849.
Bonwetsch, Dorpat Diss., 1869, p. 39.
Bouvier, Cuny, Pflüger's Arch., Bd. ii. p. 370; Wirk. der Alcohol auf d. Körpertemperatur, Bonn, 1869; Centralb. f. d. med. W., vol. ix. p. 807, 1871.
Brodie, Phil. Trans. Lond., 1811, p. 178.
Brunton, Lauder, Book of Health, Cassell & Co., p 183. Practitioner, xvi. p. 56; Contemporary Review, xxxiii. p. 691.
Carpenter, Alcohol in Health and Disease, Lond. 1851, 2d ed.
Clemens, Theodor, of Frankfort, Deutsch Klinik, 1874, 1875.
Daub, P., Centralb. f. d. med. Wiss, 1873, p. 466.
Davies, N. S., Trans. of the American Med. Assoc., 1855; Diction. encyclopéd., ii. Alcohol. p. 582.
Dogiel, J., Pflüger's Arch., 1874, Bd. viii.
Dupré, The Doctor, Feb. 1, 1873; Lond. Practitioner, vol. viii. 148, ix. 1872, p. 28, vol. xiii. p. 15.
Edes, R. D, Bost. Med. & Surg. Journ., 1872, vol. lxxxvi.
Flourens, Système Nerveux. Paris, 1842, p. 400.
Fokker, Nederlandsch. Tijdschrift vor Geneeskunde, 1871.
Fontana, Berlin, 1787, p. 439.
Ford, N. Y. Med. Journ., Jan. 1872.
Giacomini, Traité Philos. de Mat. Med. et Thérap. Paris, 1842.
Hammond, Phys. Memoirs, Philadelphia, 1863; Amer. Journ. Med. Sci. Oct. 1856, p. 305.
Horwath, Gaz. des Hôpitaux, Sep. 1878.
Huss, Magnus, Chron. Alkoholkrankh., Stockholm, 1852.
Leuret & Lassaigne, Paris, 1825, p. 200.
Leudet, Arch. Gén. de Méd. Jan. 1867, vol. ix. pp. 5–39.
Lichtenfels u. Fröhlich, Denkschr, d. k. k. Acad. d. W. in Wien, 1852; Math. Nat. Cl. Bd. iii. 113.
Lieben, A., Ann. d. Chemie u. Pharm. 1870, vii.; Suppl. Bd. p. 236.
Ludger, Lallemand, Perrin, Duroy, Paris, 1860, p. 424, Chameret édit.

ALCOHOL.

Magendie, Précis Elém. de Phys., Paris, 1825.
Magnan, de l'alcoolisme, Paris, 1874; Gaz. Méd. de Paris, No. xl. p. 444, 1871.
Manassein, Centralbl. f. d. Med. Wiss., ix. p. 689 1871.
Marvaud, Paris, Baillière et fils, 1re ed. 1871 p. 89, 169.
Meihuizen, Arch. d. Ges. Phys. vii. 4 u. 5. p. 201, 1873.
Obernier, Pflüger's Archiv. Bd. ii. p. 494.
Ortila, Tox Gén., 1818.
Parkes u. Wollowicz, Proceedings of the Royal Society, 1870.
Percy, Exp. Inquiry on Alcohol in Ventricles of Brain, Lond. 1839.
Perrin, Arch. Générales, 6th series, tome ix.
Rabow, Berl. klin. Wochenschrift, 1871, p. 257.
Rabuteau, l'Union Méd., 1870, pp. 154 and 165.
Rajewsky, Ueber das Vorkommen von Alcohol im Organismus. Pflüger's Archiv. Bd. xi. p. 122.
Riegel, F. Deutsch. Arch. für Klin. Med., 1873.
Ringer and Rickards, London Lancet, 1866, vol. i. p. 208.
Ruge, P., , Virch. Arch., Bd. xlix. p. 272.
Schulinus, Unters. über die Vertheilung des Weingeistes, im thier. Organismus, Diss. Dorpat., 1865; Arch. Heilk., 1866, p. 97.
Smith, E., Brit. Med. Journ., March, 1859. 255.
Strauch, Dorpater Diss., 1852.
Subbotin, Phys. Bedeutung des Alcohols, Z. f. Biol. vii. 361; Schmidt's Jahrb., 1872, Bd. cliv. p. 261.
Suessarott, Phila. Med Times, vol. iv. p. 774.
Sulzynski, Dorpat. Disser., 1865.
Thudichum & Dupré, Tenth Rep. of Med. Officer of the Privy Council, London, 1868.
Voit, Zeitschr. f. Biologie, Bd. vii. p. 341.
Wibmer, Wirk. d. Arzte u. Gifte, i. 90.
Complete list of Literature on Alcohol, given in the Index Catalogue of the Surgeon General's Library, U. S. Army, vol. i.

ALKALIES.

Aubert, Z. f. rat. Med., 1852, p. 225.
Aubert and Dehn, Pflüger's Arch. 1874, Bd. ix. p. 115.
Bernard, Cl. u. Grandeau, Journal de l'Anatomie et de Physiol., Bd. i. p. 378.
Bischoff, Zeitschr. f. Biologie, Bd. iii. p. 309.
Blake, Edinburgh Med. & Surg. Journal, 1838.
Böhm, A. f. exp. P. u. Ph. viii p. 68.
Bouchardat, du Diabète Sucré, Paris, 1852.
Boussingault, Ann. de Ch. et Phys., Bd. xix., p. 117, xx. p. 113, xxii. p. 116.
Buchheim, Vierordt's Arch. f. Phys. Heilk., 1853, liv., lv., lvii.; Archiv. f. exp. P. & Pharm., Bd. iii., p. 252.
Bence Jones, Lect. on Application of Chem. & Mechan. to Path. and Therap. Lond., Churchill and Sons, 1867, pp. 41, 70, 107, 125; Pflüg. Arch. iv. p. 235, 1871.
Bernard, C., Leçons de Physiol. experiment, tom. ii. p. 404.
Brunton, Lauder, The Practitioner, London, 1874, No. 71 & 72, p. 342 and 403, vol. xii.
Bunge, Z. f. Biologie, 1873, p. 101, and 1874, p. 111, Bd. ix. & x.
Durand-Fardel, Lettres Méd. sur Vichy, Paris, 1855.
Falck, Arch. f. path. Anat., Bd. lvi.
Förster, Z. f. Biologie, Bd. ix. p. 207.
Förster, R. Arch. d. Heilk. v. 521. 1864.
Grandeau et Bernard, L'Institut, 1863, No. 1555.
Guttmann, Berl. klin Wochenschrift, 1865, Nos 34-36; Virch. Arch. xxxv.
Heubel, Wirk. wasseranziehender Stoffe auf die Linse, Pflüger's Archiv., Bd. xx. p. 114.

ALKALIES.

Hirtz, Nou. Dic. de Méd., tom. i. A. p. 594.
Hoffmann, F. Zeits. f. Biol. vii. p. 338.
Hoppe-Seyler, Med. Chem. Unters.; and his pupils, Sertoli, Kaupp; Arch. f. Phys. Heilk. 1855.
Kemmerich, Pflüger's Archiv, 1869, p. 49.
Klein u. Verson, Sitzungsber. d. Wien. Akad. Bd. lv. p. 627.
Köhler, H. Centralbl. f. d. med. Wiss., 1877; vol. xv. No. 38, p. 673.
Liebig, V. Ann. d. Chem. u. Pharm. lxxvii. p. 25.
Löffler (Saltpeter), Schmidt's Jahrb., 1848, Bd. lx. p. 18.
Lomikowsky, Berl. klin. Woch., 1873, p. 475.
Magendie, Union Méd., 1852, p. 498.
Marchand, Virchow's Archiv., Bd. lxxvii. 1879.
Mauricet, Schmidt's Jahrb., cxviii. 18, 1863.
Mérandon, Act. Phys. des Sels de Potasse, Thèse de Paris, 1868.
Mialhe, Chimie Appliqué, Paris, 1856, p. 58; Bull, Thérap. lxxxiv. p. 154, 28 Feb. 1873
Nasse, H. Wagner's Handwörterbuch der Phys. i. p. 167 (Blut.)
Podcopäw, Virch. Arch. xxxiii. 505.
Ranke, F., Reichert's u. Du Bois-Reymond's Arch., 1864, p. 320.
Rabuteau, Gaz. Hebdom., 1871, 43, 46, 48.
Rilliet, Arch. Gén. de Méd., iv. 35, 1848.
Röhrig, Arch. f. wissensch. Heilk. vi. 3, 4, p. 396, 1863.
Salkowski, Archiv. f. path. Anat., Bd. liii.; Centralbl. Med. Wiss. xi. 1873, p. 774.
Schmidt, Al. u. Aronstein, Pflüger's Archiv., Bd. viii. p. 75.
Setschenow, Centralbl. f. d. med. W. 1873, p. 355.
Sertürner, Ann. f. d. Universal System d. Elements, Jahrg. 1826.
Tilt, Lancet, i. 1861, p. 556, June.
Traube, Berl. klin. Wochenschrift, 1864, p. 18.
Trousseau, Clin. Méd. de l'Hôtel Dieu., Paris, 1861.
Trousseau and Pidoux, Traité de Thérap., Paris, Asselin, 1868, 8e éd. p. 420.
Voit, Unters. üb. d. Einflus. d. Kochs. auf die Stoffwechsel, München, 1860; und Ber. d. München. Acad., 1869.
Voit, Z. f. Biol., Bd. i. p. 195 (Glaubersalz, Stoffwechsel).
Voit und Bauer, Zeitschrift f. Biol., 1869, Bd. v. p. 536.
Zuntz, Pflüg. Arch. i. p. 361.

ALKALINE EARTHS.

Bence-Jones, Chem. Soc. Quart. Journ., xv.
Beneke, Pathologie des Stoffwechsels, 1876.
Boussingault, Ann. d. Chem. u. Pharm., lix. (Phosphors. alk. Erden).
Chossat, Gaz. Méd. de Paris, 1842 (Phosphates).
Diakonow, Centralbl. f. d. med. W., 1867, vol. v. p. 673.
Dussart, Beneke, & Feissier, Arch. Gén., 6e sér. tome xiv. p. 670, xv. pp. 66 and 198.
Neubauer u. Vogel, On Urine, etc. 1863.
Piorry, Journal de Chem. Méd., tome ix. 1863.
Roloff, Virchow's Archiv., Bd. xlvi. p. 305.
Weiske, Zeitschrift f. Biol., Bd. vii. p. 333.
Zalesky in Hoppe-Seyler's Med.-chem. Unters.

ALKALOIDS.

Heger, Journ. d. med. Chir. et Pharm. de Bruxelles, 1879 (Sur l'Absorption des Alcaloides dans la Foie, les Poumons et les Muscles).
Rossbach, Verh. d. Würzb. physiol. medic. Ges. N. F., Bd. v. 1, vi. 162 u. 190, vii. 20; Pflüger's Archiv. x. 438. xxi. 1 (Antagonism); Verhandlung d. Würzb. physiol. medic. Ges. N. F., Bd iii. 346, 1872, Bd. vi. p. 162, 1874: Pflüger's Arch. xxi. 213, 1880.

ALOES, *see* PURGATIVES.

Buchheim, Die scharfen Stoffe, p. 27.
Barker, Fordyce, American Practitioner, 1872.
Gerhard, North American Med. and Surg. Journ.
Groves, Pharm. Journ. xvi.
Husemann, Pflanzenstoffe, p. 1047.
Lienau, Oldenb. Corresp. Blatt, 9, 10, 1861.
Smith, T. and H., Chem. Gaz., 1851, 107.
Stillé, Therapeutics, vol. ii. p. 444.
Trousseau and Pidoux.

ALUM.

Barthez, Frank's Magazin, iii.
Blanc, l'Union, 117, 120, 1873.
Gamgee, Schmidt's Jahrb., cli. p. 23, 1871.
Homolle, Paris, Malteste, 1861, p. 125; l'Union, 15, 17, 1861.
Mitscherlich, Lehrb. d. Artzneimittellehre, 1847.
Paulier, Gaz. Hebd. (2), x. p. 717, 1873.
Rosenstirn in Rossbach's Pharmakolog. Unters. 1874, Bd. ii. p. 78.
Schreber, Jahrb. f. Kinderheilk., iii. 2, p. 138, 1860.
Smith, Curtis, Philad. Med. and Surg. Report. xxiv. p. 409.

AMMONIACAL SALTS.

Barclay, Med. Times & Gaz., Nov. 1853, p. 553.
Bellini, Lo Sperimentale, 1872, Giugno, 561.
Bence-Jones, Philos. Trans., London, 1851. p 399.
Bichlmayr, Z. für. Biol. 1867, 381.
Billroth, Arch. f. klin. Chirug., Bd. vi. p. 421.
Blake, St. George's Hosp. Rep., v. p. 73, 1870.
Bohm u. Lange., A. f. exp. P. u. Pharm., ii. s. 364; und Dorpater Diss., 1874.
Cazenave, Bull. Gén. de Thérap., xxxi. 70.
Cholmeley, St. Andrew's Med. Grad. Assoc. Trans., iii. 102, 1870.
Fayrer, Indian Annals of Med. Science, 1872.
Delioux, Bull. de l'Acad., xxxv. No. 23, 15 Dec 1870, p. 883.
Feder, Z. f. Biol. xiii. p. 256.
Feltz, V., and E. Ritter, Journ. d'Anatomie et de la Physiol., 1874, p. 326.
Funke u. Deahna., Pflüg. Arch., 1874, ix. p. 416.
Gmelin, Apparatus Medicamin., ii. 1, 48.
Halford, G. B., Melbourne Argus, 1872.
Hallervorden, A. f. exp. P. u. Pharm., x. p. 125.
Huxham, On Fevers, p. 299.
Knieriem, von, Zeitschr. f. Biol. 1874, Bd. x. p. 263.
Knoll, Wien. Acad. Sitzber., 1874, Bd. lxviii.
Kühne u. Strauch., Centralbl. Med. Wiss., 1864, No. 36, pp. 561, 577.
Lange, F., Arch. f. Exp. Path. u. Pharm., Bd. ii. p. 368.
Maurecet, Schmidt's Jahrb., clxviii. p. 18, 1863.
Mitscherlich, Zeits. des Preuss. Vereins f. Heilk., Nos. 43, 44, 45, 46, 1841; Lehrb. der Arztn., ii. 228.
Munk, Zeitschr. f. physiol. Chem., ii. p. 29.
Priestley, On Air, ii. p. 369, 1790.
Salkowski, Zeitsch. f. phys. Chem., Bd. i. pp. iv, 1, 374.
Rabuteau, Gaz. Hebd., 43, 46, 48, 1871; Comptes Rend., lxx. 25, p. 1356, 1870.
Schiffer, Berl. klin. Wochenschr., 1872.
Schmiedeberg, A. f. exp. P. u. Pharm., viii. p. 1.
Stevenson, Guy's Hosp. Rep., 3rd ser. xvii. 225, 1872.
Thiry, Henle u. Pfeufer's Zeits. (3) xvii. p. 166, 1864.
Trousseau & Pidoux, Traité, 9th ed. 1, p. 453.
Walter, A. f. exp. P. u. Pharm.. vii. p. 148, u. Wibmer, Wirk. d. Arzneim. u. Gifte, Munich, 1831, pp. 123, 127, 139, 144.

ANILINE.

Bergmann, Präger Vierteljahrsschr., Bd. lxxxviii. p. 109, 1865.
Feltz u. Ritter, Compt. Rend., lxxxii. p. 1512, 1876.
Schuchhardt, Virch. Arch., Bd. xx. p. 446.

ANTIMONY.

Ackermann, Virch. Arch., Bd. xxv. 1862, p. 531; Rostock, 1856 (Ader) iv. p. 44; Henle u. Pfeufer's Zeits. f. ration. Méd., 3, R. ii. Heft. 3, 1858
Balfour, Tartar emetic in Fever, Inflam., Asthma, etc., Lond., 1818.
Buchheim u. Eisenmenger, Eckhardt's Beitr. Bd. v.
Brinton, Todd's Cyclop. of Anat. and Physiol. Suppl. p. 319.
Böcker, Beitr. z. Heilk., ii. p. 234, 1849.
Corput, van den, Journ. méd. de Brux., xxxv. p. 491, Nov. 1863.
Denny, Brit. Med. Journ., Jan. 28, 89, 1871.
Duffin, Edin. Med. & Surg. Journ., xix. 3, p. 354, 1823.
Eisenmenger, U. d. Einfl. Gifte a. d. Zuckungscurve d. Froschesmuskels, iv., Giessen, 1869, p. 7.
Forget, Bull. gén. de Thérap., lviii., June, 1860, p. 481.
Fonssagrives, Bull. gén. de Thérap., lvii., Aug. 1859, p. 145.
Gianuzzi, Centralbl. med. Wiss., 1865, p. 129.
Grimm, Pflüg. Arch., iv. p. 205.
Jankowich, Oesterr. Jahrb. N. F. xxxviii. p. 53, 1842.
Jones, Handfield, Med. Times & Gaz., Dec. 1852, p. 362.
Koschlakoff u. Bogomoloff, Centralbl. med. Wiss., 1868, p. 628; Pflüger's Arch., v. p. 280, 1872.
Kleiman u. Simonowitsch, Arch. f. d. ges. Physiol., Bd. v. p. 280.
Lange, D., Klinik, 28, 30, 31, 1863; Schmidt s Jahrb., cxxiii. 283, 1864.
Lepelletier, Paris, 1835, p. 171.
Long, Bull. gén. de Thérap., lix. Oct. 1860, p. 317.
Magendie, Paris, 1813.
Mayerhofer, Heller's Arch., iii. 3-5, p. 356, 1846.
Mosso, Schmidt's Jahrb., Bd. clxix. p. 236.
Nöbiling, Zeits. f. Biol., Bd. iv. p. 40, 1868; Schmidt's Jahrb., cxl. 24.
Orfila, Mémoires de l'Acad. roy. de Méd., viii. 1840, p. 509.
Papillaud, Schmidt's Jahrb., clvi. p. 267, 1872.
Pécholier, Comptes Rend., lvi. 1863, p. 718; Gaz. Hebd., 17 Ap. 1863, p. 275.
Rasori, Milano, 1830; Arch. gén. de Méd., 1824, iv. pp. 300, 415.
Rayer & Bonnet, Dict. de Méd. et de Chir., iii. 69, Paris, 1829.
Radziejewski, Arch. f. Anat. u. Phys., 1871, p. 472.
Richardson, Med. Times and Gaz., May, 1856, p. 473.
Saïkowski, Virch. Arch., xxxiv. p. 73.
Solon, Martin, Mémoires de l'Acad. roy. de Méd., viii. 1840, p. 518.
Stedmann, Med. Times & Gaz., Dec. 1852, 641.
Taylor, Guy's Hosp. Rep., 1860, p. 397.
Traube, Centralbl. med. Wiss., 1864, p. 490.
Trousseau & Pidoux, Traité de Thérap. et de Mat. Med., 9e ed. 1870, ii. p. 954.
Viborg and Hertwig quoted by Wibmer, Wirk. d. Arzneim. u. Gifte, v. 187, 194.
Witt, J. H. D. de, Groningae apud Wilkens, 8, 1847, p. 32.
Wood, Philad. Med. Times, vol. iii.

APIOL.

Gallico u. Poggeschi, Bull. gén. Thérap. 1861, ii. p. 279.
Joret. Bull. Thérap. Feb. 1860, lix. p. 97.
Joret & Homolle, Journ. de Pharm. et de Chim. 3e sér. xxviii. 212.
Marotti. Bull. Thérap., lxv. p. 295 and 341, 1863, Gaz. Hebd. 45.

APOMORPHIA.

Bourgeois, Thèse de Paris, 1874, No. 19, Bull. gén. de Thérap. lxxxvi. p. 236, 1874.
Chouppe, Soc. de Biol, 18 July, 1874, Arch. de Physiol., 1875, p. 101.
David, G., Gaz. méd. 1874, p. 465.
Dujardin-Beaumetz, Bull. gén. de Thérap. lxxxvii. Oct. 8, 1874, p. 345.
Eichberg, Wurtemberg. Corr. Bl. 89, p. 1819-1873.
Fronmüller, Memorabil., xviii. 9, 1873.
Ganghofner, Böhn. Corrs. Blat., i. 3, p. 65, 1873.
Gee, St. Barth. Hosp. Reports, vol. v. p. 215, Trans. Clin. Soc., ii. p. 166, 1870.
Gellhorn, Allgem. Ztschr. f. Psych. xxx. 46, 1873.
Greve, Berl. klin. Wochens., xi. 28, 29, 1874.
Harnack, Arch. f. exp. Path. u. Pharm., Bd. ii. p. 291, 1874.
Huchard, H., Union méd., Oct. 1874, p. 493.
Juratsz's Centralbl. f. d. med. Wiss., p. 499, 1874.
Löb, Berlin, Klin. Wochens. 1872, p. 400.
Mattheissen, R. & C. R. A. Wright, Proceedings Roy. Soc., xvii. 455.
Mayer, E. L., Berichte Deutsch. Chem. Gesell., Berlin, 1871, iv. 121.
Meyer, De, Bull. de la Soc. roy. de Pharm. de Bruxelles, 1872.
Möller, Bull. de l'Acad. de Méd. de Belgique, viii. 3, 1873, p. 749.
Moerz, A. Präger Vierteljahr. 1872, Bd. cxv. p. 82.
Oberlin, Revue Méd. de l'Est, Aug. 1874, ii. p. 98.
Onsum, Norsk Mag., 3 R. iii. 155, 1872.
Quehl, Hallenser Diss. 1872.
Pierce, British Med. Journ., 1870, vol. i. p. 204.
Riegel u. Boehm, Deutsch Arch. f. klin. Medicin, Bd. ix. 211, 239, 1871.
Routy, Thèse de Paris, 1874, No. 437.
Siebert u. Boehm, Arch. d. Heilk., Bd. xii. 6 Heft, 1871, p. 522.
Wertner, M., Wien. Med. Presse, 1876, 269.
Ziolkowski, Apomorphin, Inaug. Diss. Greifswald, 1872.

ARAROBA or Chrysaroba.

Fayrer, Med. Times, ii., 1874, pp. 470, 547, 1876; ii. p. 711.
Thompson, I. Ashburton, Brit. Med. Journ., May, p. 607, 1877.

ARNICA.

Balding, C. C., Lancet, vol. ii. p. 885, Dec. 1870.
Fayrer, Practitioner, xvi. p. 52.
White, Boston Med. and Surg. Journ., Jan. 1875, p. 61.

AROMATIC COMPOUNDS.

Baumann u. Herter, Z. f. physiol. Chem. i. 244, ii. 335.
Brieger, A. f. Anat. u. Phys., 1879, Physiol. Abth. Suppl. Bd. s. 61 (Pyrocatechin, Hydrochinon, Resorcin).

ARSENIC.

Binz u. Schulz, Arch. f. exp. Path. u. Pharm. Bd. xi. p. 200.

ARSENIC.

Bergeron and Lemaître, Brit. & For. Med. Chir. Review, vol. xlviii. p. 226, 1871.
Blake, Edin. Med. and Surg. Journ. 1839.
Boeck, Von, Zeitschr. f. Biol., Bd. vii. p. 418, u. xii. p. 512; u. Centralbl. d. Med. Wiss. 1876, üb. d. Zersetzung des Eiweisses, München, G. Himmer, 1871, p. 41.
Böhm u. Schäfer, üb. den Einfluss des Arsen. auf Ungeform. Fermente, Würtzburg Verhandlgen. N. F. Bd. iii. 1872.
Brodie, Phil. Trans., 1811, 1812.
Unterberger, Arch. f. exp. P. u. Pharm. Bd. xi. p. 89.
Cunze, Henle u. Pfeufer's Ztschr. f. rat. Med., 3, xxviii. p. 33, 1866, Schmidt's Jahrb., cxxxi. 19.
Downie, K. M., Indian Medical Journ., 1872.
D'Etiolles, Leroy, Gaz. Hebd., 1857, vol. iv.
Fleck, Arch. f. Biologie, Bd. viii. p. 444.
Flandin and Danger, Husemann, Toxicologie, p. 823.
Fokker, Schmidt's Jahrb., clviii. 15.
Fowler, Med. Rep. on Arsenic in Ague, etc., Lond. 1786.
Gaethgens, Arch. f. exp. P. u. Pharm., Bd. v. p. 128 u. Centralbl. f. med. W., 1876.
Gies, Arch. f. exp. Path. u. Pharm., Bd. viii. p. 175.
Grohe, Fr. and Fr. Mosler, Virch. Arch., Bd. xxxiv. p. 213.
Herapath, Philosophical Mag., 1851, p. 345.
Heisch, Chas., Pharmaceutical Journ. and Trans., vol. i. 2nd series, 1859, 1860, p. 556.
Hoffman, Virch. Arch. Bd. l. (50) p. 456.
Imbert-Gourbeyre, Histoire des Eruptions arsenicales, Monit. des Hôpit., 1857.
Jäger, Wirk. d. Arseniks auf Pflanzen, Stuttgart, Schweizerbart, 1864, p. 113.
Johannsohn, Arch. f. exp. P. u. Pharm., Bd. ii. p. 106.
Jackson, W. C., Amer. Journ. of the Med. Sciences, July, 1858, p. 57.
Karajau, Tardieu, Sur l'empoisonnement, p. 335.
Kendall and Edwards, London Pharmaceutical Journal, ix. 1850.
Köhler, H. of Halle, Brit. and Foreign Med. Chir. Rev., 1870, vol. xlv. p. 538.
Kossell and Gaethgens, Arch. exp. Path. et Pharm. Bd. v. 133, and Centralbl. Med. Wiss. 1875, 530, 1876, 833.
Lachèse, Ann. d'Hyg. et de Méd. légale, 1837, le série, tome xvii. p. 334.
Lesser, A., Virch. Arch., Bd. lxxiii. p. 398, and lxxiv. p. 125, 1878.
Leube, Deutsch. Arch. f. klin. Medicin, Bd. v. 372, 1869.
Maas, Verhandl. d. Leipziger Naturforsch. Vers. 1872.
Mackenzie, Ind. Med. Gazette, 1872.
Maclagan, C., Edin. Med. Journal, vol. x. 1864, p. 203.
Nunn, Emily A., Journ. of Physiology, i. 247.
Pinkham, Boston Med. and Surg. Journ., 1878, vol. xcix. 358.
Renner, Würtzburger Diss., 1876.
Ringer and Murrell, Journal of Physiol., i. p. 213.
Saikovski, Virch. Arch. Bd. xxxiv. p. 77.
Saikowsky, Mosler u. Grohé, Virch. Arch. 1865, Sept. u. Oct., p. 208.
Salomon, Alex., Wirk. kleiner Dosen Arsenik, Diss. Berl., 1873, p. 35.
Sawitsch, Dorpater Dissert., 1854.
Schmidt and Stürzwage, Moleschott's Unters., vi. 3, p. 283, 1859.
Schroff (senior), v. Zeitschr. d. Wiener Aerzte, N. F. ii. 44, Schmidt's Jahrb., 1860, cv. 176, 1860.
Schulz, Arch. f. exp. P. u. Pharm., Bd. xi. p. 131.

ARSENIC.

Sklarek, W., of Berlin, Reichert's Archiv, 1866, p. 481, Schmidt's Jahrb., cxxxii. 290.
Stürtzwage, Dorpater Dissert., 1859.
Taylor, Guy's Hosp. Reports, vol. x. 3rd series, 1864, p. 227.
Unterberger, S., u. Bohm, Arch. f. exp. Path. u. Pharm., Bd. ii. p. 89, 99, 1874.
Virchow, Virchow's Archiv, Bd. xlvii. p. 524.
Vogt, Lehrbuch d. Pharmacodynamik, 3te Aufl., Bd. i.
Weir-Mitchell, New York Med. Journ., vol. i.
Wyss, Arch. d. Heilkde., 1870, p. 15.

ASPIDOSPERMIN, *vide* QUEBRACHO.

ATROPIA.

Anrep, Pflüger's Arch., Bd. xxi., 1880 (chron. Atropinvergiftung.)
Arlt, Arch. f. Opthalmolgie, 1869, p. 294.
Bennett, Hughes, Brit. Med. Journ., 1874, vol. ii. 547, London Med. Record, 1877, p. 341.
Bernard, Cl., Physiol. u. Path. du Système Nerveux, Paris, vol. ii. p. 212.
Bezold, V., u. Blöbaum, Unters, a. d. physiol. Labor. in Würtzburg, Bd. i., 1867.
Boehm, Studien über Hertzgifte, Würtzburg, 1871.
Borelli, Ed. Med. Journ., Nov. 1871, vol. xvii. p. 480.
Braun, Arch. f. Opthalmologie, Band. v. Abth. ii. p. 112.
Botkin, Virchow's Arch., Bd. xxiv. p. 83.
Budge, Ueb. d. Bewegung der Iris, 1855.
Chambers, Lancet, 1864, vol. i. p. 8.
Da Costa, Amer. Journ. Med. Sciences, July, 1865, p. 71; Pennsylvania Hosp. Rep., 1858; Philad. Med. Times, Feb. 15, 1871.
Dogiel, J., Max Schultze's Arch. f. microscop. Anat., Bd. vi. Heft. i., 1870, p. 85.
Donders, The Accommodation and Refraction of the Eye, Syd. Soc. ed., p. 584, 588.
Fraser, Transactions of the Royal Society of Edinburgh, May, 1869, vol. xxv., 450, Bd. xxvi., 1872, with complete *résumé* of older literature.
Fraser, T. R., Bartholow, Oglesby, Nunnely, The Practitioner, iv. 65, 27, and 217.
Graefe, Von, Deutsches Klinik, 1851.
Harley, The Old Veg. Neurotics, London, 1869, p. 220.
Hayden, Dublin Quarterly, Aug. 1863, p. 51.
Heidenhain, Pflüg. Arch., Bd. v. p. 309.
Hirschmann, L., Zur Lehre v. d. durch Arzneim. etc., Reichert's Arch., 1863, p. 309.
Iwanoff, Alex. and Alex. Rollett, Arch. f. Ophtham., vol. xv. p. 17.
Jones, Wharton, Med. Times and Gazette, p. 28, vol. i. 1857.
Ladenburg, Ber. d. deutsch. chem. Ges. Jg. xii. 1879, p. 941.
Lemattre, Arch. Générales, Aug. 1865, p. 173.
Lichtenfels u. Fröhlich, Denkschr. d. Wien. Acad. Math. Naturw. Cl. 1852, p. 113.
Meuriot, De la Méthode physiol. en Thérapeutique et de ses Applications à l'Étude de la Belladonne, Paris, 1868, p. 73.
Norris, Wm. F., Amer. Journ. of Med. Sci., Oct. 1862, p. 395.
Putnam, Miss Mary, New York Med. Record, 1873.
Rossbach, Pharmakol. Unters, Bd. i. ii. iii. Würtzburg, 1873 (*vide* also Aikaloids).
Rossbach u. Frölich, Pharm. Unters. Würtzburg, i. p. 6, N. F., v. 1874.
Schroff, Zeitschr. d. Wien. Aerzte, 1852
Schmiedeberg, Arb. des Phys. Instit. z. Leipzig, v. p. 41, 1870.
Stellwag v. Carion, Der intraoculare Druck u. d. Innervations-Verhältn. der Iris, Wien, 1868.

Atropia.

Valentin, Y., Versuch einer physiol. Pathologie der Nerven, Leipzig, 1864, 2e Abth. p. 368.
Weir-Mitchell, Injuries of Nerves, Philadelphia, 1872, p. 258.
Wood, Amer. Journ. Med. Sci., Ap. 1873, p 332; N. S. p. 128, Jan. 1871; Philadelphia Med. Times, vol. i. p. 290.
Zeller, Virch's. Archiv, lxvi. p. 384.

Barium.

Böhm u. Mickwitz, Arch. f. exp. Path. u. Pharm., 1875, Bd. iii. p. 216.
Brunton and Cash, Roy. Soc. Proc., No. 226, 1883; Phil. Trans., 1884; Cent. d. Med. Wiss., 1884, p. 545.
Hermann, Toxicologie, 1191.
Onsum, Arch. f. path. Anat., Bd. xxviii. p. 233.

Bebeeru Bark.

Albers, Virch. Arch., Bd. xxiv. p. 304.
Binz, Virchow's Arch., Bd. xlvi. p. 130.
Flückiger, N. Jahrb. Pharm., 1869.
Gamgee and Maclagan, Edin. Roy. Soc. Trans., 1869, p. 567.
Walz, N. Jahrb. Pharm., xii. 1861, p. 302.

Benzoic Acid.

Bird, Golding, Urinary Deposits, Philad., 1859, p. 160.
Bucholtz, Arch. exp. Path. u. Pharm., Bd. iv. p. 1.
Brown, Zur Therapie der Diphtheritis, Arch. f. exp. Path. u. Pharm., Bd. viii. p. 140.
Bryant, Lancet, ii. 1876, 747.
Dougall, Med. Times & Gazette, i. p. 495, 1872
Delcours, Gaz. des Hôp., Dec. 1844.
Fleck, Benzoesäure, Carbolsäure, Zimmtsäure, München, 8vo. Oldenburg, 1875.
Garrod, Memoirs of the Chem. Soc., i. 1842; London Lancet, ii. p. 239, 1844.
Grübe W., Centralbl. f. Chim., 1876, pp. 777, 778.
Hallwachs u. Kühne, Götting. Nachr., 8, 1857.
Jaarsveld, A. f. exp. P. u. Pharm., x. 268.
Jaffé, Ber. d. deutsch. chem. Ges., 1877, p. 1925.
Keller, Ann. der Chem. und Pharm. xliii. 108; Lancet, ii. Nov. 1844, p. 239.
Lamaire, Phil. Med. Times, iv. 638.
Meissener u. Shepard, Unters. üb. d. Enstehen des Hippurs. i. thier. Organismus. Hannover, 1866.
Morri, Trans. Phil. Coll. of Med., Mar. 7, 1855.
Rohde, Berl. klin. Woch., 1871, 10.
Salkowski, E., Berl. klin. Wochens., 1875, 297.
Seligsohn, Chem. Centralbl., 1861.
Shepard, U. C., Der Hippursäure im thier. Organismus, Hannover, 1866.
Ure, Medico. Chir. Trans., xxiv. p. 30, 1841.
Ure & Wood, Phil. Trans., March 7, 1856.

Benzol.

Hoffmann, F. A., quoted by Böhm, Ziemssen's Cyclopædia., vol. xvii. p. 513.
Perrin, L'Union Méd., 1861, No. 6, p. 92.

Bichloride of Methylene.

Richardson, B. W., Med. Times & Gaz., 1867, p. 479; Medical Times and Gazette, 1869, ii., 524; Brit. Med. Journ., vol. i. p. 332, 1871; vol. ii. p. 249, 1872; London Lancet, 1877, ii. 26.

Bismuth.

Becker & Jansen, Arch. der Pharm., lv. 31, lxviii. 129, lxxvii. 231. lxxviii. 18.
Bergerat & Mayençon, Journ. de l'Anatomie, 1873, p. 242.

Bismuth.

Feder-Meyer, Würtzburg Diss., 1879.
Stefanowitsch-Lebedeff, Virch.'s u. Hirsch's Jahresb., 1869, p. 335.
Wiggers, Canstatt's Jahresb. Pharm., 1848, p. 104, 1851, p. 105, 1854, 109.

Bitters.

Buchheim u. Engel, in Buchheim's Beitr. z. Arzneimittellehre, Leipzig, 1849.
Koehler, H., Tageblatt. d. 46 Naturforscher Versamml. zu Wiesbaden, 1873, s. 70.

Blatta Orientalis.

Bogomolow, Lond. Record., 1877, p. 502.
Unterberger, Petersburg. Med. Wochensch. 1876

Blood Root.

Smith, R. M., Amer. Journ. Med. Sci., Oct. 1876 p. 346.

Borax.

Binswanger, Pharm. Würdigung der Borsäure des Borax, etc., 1846.
Buchholz, Arch. exp. Path. u. Pharm., .Bd iv. p. 1.
Copland, Dict. of Pr. Med. (Art., Abortion.)
Dumas & Schnatzles, Pharmac. Journ., Ap. 1874.
Gmelin, App. Medicaminum, i. p. 104.
Guibourt, Histoires des Drogues simples, i. p. 191.
Homberg, Mém. de l'Acad. des Sci. de Paris, 1702, 33.
Richter, Ausführl. Arzneiml., iii. p. 558.
Vogt, Pharmakol., ii. 587.
Wibmer, Wirk. d. Arzneim. u. Gifte, v. 51.

Brayera.

Bedall, Sydenh. Year Book, 1868, p. 476; l'Union, 116, p. 596, 1863.
Leidesdorf, Wien. Med. Woch., xii. 26, 1871.
Viale, Journ. de Chimie méd., 5, ii. p. 207 1866.

Bromine and Bromide of Potassium.

Anstie, Practitioner, xii. p. 19, 1874.
Bartholow, The Bromides, 1871.
Binz, Practitioner, xii. p. 6, Jan. 1874.
Blake, Journ. of Anat., iv. 1, 1870.
Clouston, Journ. Mental Sci., Oct. 1868, vol. xiv. p. 305.
Clarke & Amory, Bromide of Potass., Boston, 1872.
Eulenburg u. Güttmann, Schmidt's Jahrb., cxxxvii. p. 158, 1868.
Hammond, Quart. Journ. of Psycholog. Med. vol. iii. p. 46, 1869.
Laborde, Paris, A. Delahaye, p. 30, 1870.
Marchand, R., Thèse de Paris, 1868, p. 32.
Namias, Compt. Rendus, lxx. 16, p. 882, 1870.
Ozanam. Gaz. des Hôp., No. 66, 1856.
Podcopäw, Virch. Arch., xxxiii. p. 505, 1865.
Paul, C., Gaz. des Hôp., 91, 1866.
Purser, J. M., Dub. Quart. Journ., xlii, 94, May 1869.
Ringer, Sidney Lancet, i. p. 392, 1869.
Teissier, Gaz. méd. de Lyon., p. 501, Nov. 15, 1868.
Williams, Obstet. Trans., xii. 249, 1871.
Complete Literature, see Krosz, Arch. f. exp. P. u. Pharm., 1876, Bd. vi. p. 46.

Bromal Hydrate.

McKendrick, J. G., Ed. Med. Journ., July, 1874. p. 1.
Rabuteau, Gaz. Hebdom., xliii. p. 681.
Steinauer, E., Virch. Archiv, 1870, Bd. l. p. 235, lix. p. 65.

Brominated Camphor.

Besnier, Gaz. des Hôp., 35, 1865.
Bourneville, Le Progrès Méd., 1874; The Practitioner, Aug. 1874, p. 119; Comptes Rend., Aug. 1875.
Crichton-Brown, Edinb. Med. Journ., June, 1865, p. 1085.
Deneffe, Presse Méd. Belge, 1871, p. 405.
Hammond, Wm., N. Y. Med. Journ., Dec. 1871, p. 594.
Hamilton, McLean, N. Y. Med. Journ., July, 1872, p. 72.
Lawson, Practitioner, vol. xiii. p. 324, 1874, vol. xiv. p. 262, 1875.
Mussy, Guénau de, Union Méd., 83-86, 1866.
Pathault, Bromure de Camphor, Paris, 1875.
Ricard, Union Méd., cxi. p. 417, 1869.
Soulez, Amer. Journ. Med. Sci., July, 1877, p. 237; Lond. Med. Rec., 1877, p. 196.

Broom.

Fick, Arch. f. exp. Path. u. Therap., i. 397, 1873.
Husemann, Die Pflanzenstoffe, p. 64.

Cacodyl Compounds.

Lebahn, Rostocker Inaug. Diss., 1868.
Renz, Deutsch. Arch. f. klin. Med., 1865, i. 2, 235.
Schmidt u. Chomse, in Moleschott's Unters., vi. 122.

Cadmium.

Marmé, Zeitschr. f. rat. Med., 1867, Bd. xxix. p. 113.

Caffein.

Albers, Deutsches Klinik, 1853, p. 370.
Amory, Boston Med. Journ., May 28, 1868, p. 261.
Aubert, Pflüger's Arch. v. p. 589, 1872.
Bennett, Alex., Brit. Med. Journ., 1874, vol. p. 510; Edin. Med. Journ., ccxx. p. 328, 1873.
Bennett, J. Hughes, Brit. Med. Journ., 1874, vol. ii. p. 697.
Binz, Arch. f. exp. Path. u. Ph., 1878. ix. p. 31; Berl. Klin. Wochenschr., xlv. p. 545, 1872.
Böcker, Beiträge z. Heilk., Bd. i. 1849; Arch. d. Vereins f. Gemeins. Arb. z. Förd. d. Wiss. Heilkunde, Bd. i. p. 213.
Brown-Séquard, Arch. de Phys. Norm. et Path., 1868.
Brill, Marburger Dissert., Elwert, 1862.
Eggerth, Diss. de Coffea, Pesth, 1833, p. 31.
Eisenmenger, Ueb. d. Einfluss. v. Gifte a. d. Zuckungscurve, &c., Giessen. Pietsch, 1869, p. 49
Falck und Stuhlmann, Virchow's Archiv, Bd. xi. p. 325.
Garrison, J. B., Phila. Med. and Surg. Reporter, xxx. Feb. 6, p. 111, 1874.
Gubler, Bull. thér., xciii. 523.
Hoppe, F., l'Écho Médical, 1858; Deutsches Klinik, 1857, p. 181.
Johannsen, O., Dorpater Diss., 1869.
Leven, Arch. de Phys., 1868, vol. i. p. 178.
Marvaud, Angel, Effets physiol. et thérap. des Aliments d'Épargne, Paris 1869-71, p. 118.
Meihuizen, Pflüg. Arch., vii. 4-5, p. 201, 1873.
Mitscherlich, Der Cacao und Chocolade, Berl. 1859.

Caffein.

Payen, Compt. Rend., xxii. p. 724, xxiii pp. 8 and 244, 1846.
Roques, Schmidt's Jahrb., x. p. 18.
Runge, Schweigg. Journ. Chem. Phys., xxxi. 1820.
Schmiedeberg, Arch. f. exp. P. u. Ph., Bd. ii. p. 62, 1874.
Smith, H. M., Journ. of Applied Sciences, Sept. 1874.
Stuhlmann u. Falk, Virch. Arch., Bd. xi. p. 481.
Thompson, Med. Times & Gaz., Feb. 12, p. 185, 1871.
Uspensky, Reichert's Arch., 1868, p. 522; Centralbl., 1868, p. 677.
Voit, Ueber d. Wirk. d. Kochsalzes u. Kaffees auf d. Stoffwechsel, München, 1860, p. 135.

Calabar Bean.

Arnstein u. Sustschinsky, Würzb. Arbeit., iii. 1867.
Bezold, Von, & E. Götz, Centralbl. f. d. med. Wiss., 1867, 241.
Complete Literature by Harnack, Arch. f. Exp. Path. u. Pharm., Bd. v. p. 401.
Fraser, Ed. Med. Journ. ix., Aug. and Sep. pp. 123 and 235, 1863. Trans. Roy. Soc., Edin. xxiv. 73, 1867, xxvi. 1872.
Fronmüller, Deutsch. Klinik, 32, 35, 1864.
Gräfe, A. von, Deut. Klinik, No. xxiv. 1863.
Harley, Journ. de l'Anat. et de la Phys., 1864, p. 140-152
Hirschler, Wien. med. Woch., 13, xlii., 1863.
Höring, Würtemberg. Correspblatt., xli., 1863.
Köhler, H., Arch. f. exp. Path. u. Pharm., i. p. 277, 1873.
Laschkewitsch, Virch. Arch., xxxv. p. 291, 1866.
Laurence, Ophthal. Hosp. Reports, iv. 1, 129, 1863.
Leven & Laborde, Schmidt's Jahrb., Bd. cxlvi. p. 136.
Ogle, Brit. Med. Journ., vol. i. p. 673, 1863.
Papi, Schmidt's Jahrb., Bd. cxlii. p. 286.
Röber, Berlin. Diss., 1868.
Rossbach, Pharmak. Unters., Heft i. 1873.
Schiff, Centralbl. f. d. med. Wiss., 1873, p. 37.
Vintschgau, Moleschott's Unters., ix. 800, 1865.
Watson, E., Ed. Med. Surg. Journ., xii. p. 11, May 1867. Centralbl. f. d. med. Wiss. 1868, p. 143.
Weber, Klin. Monatsschr. f. Augenheilk., Aug. 1863.

Camphor.

Baum, Centralbl. f. d. med. Wiss., 1870, p. 467.
Flückiger, Neues Repertor. f. Pharm., xvii. 28, 1868.
Gübler, Bull. de Thérap., Dec. 30, 1871, p. 529.
Grisar, Bonnar Diss., 1873, u. Centralbl. f. d. med. Wiss., 1874, p. 77.
Harley, Practitioner, ix. 210, 1872.
Heubner, Arch. Exp. Path. u. Pharm., v. p. 427.
Hoffmann, Beitrag. z. Kenntn. d. Physiolog. W. d. Carbolsäure u. d. Camphors. Diss. Dorpat, 1866.
Schmiedeberg u. Meyer, Z. f. phys. Chem., iii. 422, 1879.
Wiedemann, Arch. f. exp. Path. u. Pharm., Bd. vi. s. 216 (with complete list of Literature).

Cannabis Indica.

Christison, Edin. Monthly Journ. of Med. Sci., July, 1851, p. 26.
Fronmüller, Klinische Studien üb. d. Schlafmachende Wirkung, etc., Erlangen bei Enke 1869.
Lawrie, Stille's Therap., vol. i. p. 772.

Cannabis Indica.

O'Shaugnessy, on the Preparations of Indian Hemp, Calcutta, 1839.
Preobraschensky, Dragendorf's Jahresb., 1877, p. 98.
Roemer, St. Louis Med. and Surg. Journ., p. 363, 1873.
Schroff, V., Zeitschrift d. Wien. Aerzte, 1857, u. Lehrbuch d. Pharmakologie, Aug. 3, 1868, p. 499.
Wood, Proceed. Amer. Philos. Society, 1869, vol. xi. p 226.

Cantharidin.

Cautieri, Schmidt's Jahrb., Bd. clxv. p. 237.
Cornil, Practitioner, xxvii. p. 110.
Galippe, Gaz. Hebdom., 1874, p. 439.
Husemann, Handb. d. Toxicol., 1862, p. 264.
Pallé, Journ. de Pharm. et de Chimie, June, 1871.
Radecki, Dorpater Diss., 1866.
Schwakowa, Berner Diss., 1876.
Stüler, Deutsche Z. f. Chir., 1872, xii. 377.

Carbazotic Acid.

Binz, Virch. Arch., Bd. xlvi. p. 130.
Erb, W., Die Rikrinsäure, Würtzburg, 1865.

Carbolated Camphor.

Soulez, Amer. Journ. Med. Sci., July, 1877, p. 237, and London Med. Record, May, 1877.

Carbolic Acid.

Almén, Zeitschr. f. Anal. Chimie, Bd. x., p. 125, Heft 7.
Aufrecht, Centralbl. med. Wiss., 1874, p. 129.
Baumann, Pflüger's Archiv, Bd. xiii. p. 285; Zeits. f. phys. Chimie, v. Hoppe-Seyler, i. p. 244; Du Bois' Arch. physiol., Abth. 1879, iii. 245.
Baumann u. Sonnenburg, Med. Times and Gaz., ii. 1878.
Bill, J. H., Amer. Journ. Med. Sci., Oct. 1870, p. 573.
Brieger, Zeitschr. f. physiol. Chemie, iii. p. 134.
Buchholtz-Waldemar, Dorp. Diss., 1866.
Buchholtz, Einwick. a. Gährungs Processe, Dorpat., 1866, p. 50.
Buliginski, Hoppe-Seyler's Med. chem. Unters., Berlin, 1867, p. 234.
Dougall, John, Lancet, 1870, vol. ii. p. 176.
Eames, J. H., Brit. Med. Journ., May, p. 490, 1873.
Erb, E., Schmidt's Jahrb., Bd. clxiv. p. 148.
Hagen, Schmidt's Jahrb., Bd. clxiv. p. 147.
Hoffmann, W., Dorpat. Diss., 1866.
Hoppe-Seyler, Pflüger's Arch., 1872, Bd. v., pp. 470, 475, 476, 479.
Hueter, C., Deutsch. Zeits. f. Chir., iv. p. 508, 1874; Schmidt's Jahrb., clxiv. p. 144.
Husemann, Schmidt's Jahrb., Bd. clv. p. 274.
Husemann u. Ummethun, Deutsch. Klinik, 1870 and 1871.
Kempster, W., Amer. Journ. Med. Sci., July, 1868, p. 31.
Kunze, Centralbl. med. Wiss., 1874, p. 479.
Labée, E. Arch. Gén. de Sér., t. xviii. p. 451, 1871.
Lemaire, J., De l'Acide phénique, 2e éd., Paris, 1865.
Lister, J., Lancet, vol. ii. 1867, p. 353.
Mader, Centralbl. f. Chir., 1877, p. 376.
Neumann, I., Arch. f. Dermat. u. Syphil. Jahrg. i. 1869, p. 425.
Oberst, Berl. klin. Woch., 1878, p. 157, No. xii. (Acute Poisoning).

Carbolic Acid.

Patrouillard, Journ. de Pharm. et de Chimie, Dec. 1871, p. 459.
Plugge, P. C., Pflüger's Arch., 1872, Bd. v. p. 540.
Reuder, Journ. de Pharm. et de Chimie, p. 456, Dec. 1871.
Rosenbach, Ueb. d. Einfluss. Carbolsäure, &c., Göttingen, 1873.
Salkowski, Pflüger's Arch., Bd. v. p. 210, 335, 1872, Centralbl. med. Wiss., 1876, p. 818.
Schaffer, Journ. f. pract. Chimie, N. F. xviii. p. 282.
Senator, Berl. klin. Wochenschr., 1876, p. 69.
Sonnenburg, Deut. Zeits. f. Chir., Bd. ix. p. 356.
Städeler, Ann. d. Chem. u. Pharm., Bd. lxxxvii. p. 17.
Stevenson, Brit. Med. Journ., vol. i. p. 442, 1870; and Guy's Hosp. Rep. 1868, p. 407.
Schmidt, T., Centralbl. f. Chir., 1876, 552.
Tauber, Z. f. phys. Chem. ii. 366.
Ummethun, Göttingen Diss., 1873.
Volkmann, Volkmann's Samml. Klin. Vortr., 1875, No. xcvi. in Beit. z. Chir., p. 42.
Waldenström, Zeitschr. d. Allgemein. Apothek. Vereins, Jan. 10, 1872.
Wilson, Erasmus, Journ. Cutaneous Med., June, 1870.

Carbon.

Liebermann, Sitzber. d. k. k. Acad. d. Wiss. Wien., 1877, p. 331.
Stenhouse, Economical Applications of Charcoal, 3rd ed. Lond., 1855.

Carbonic Acid.

Basch, Von, u. Dietl, Wien. m. Jahrb., 1870, xxvi. 3.
Beddoes, on the Med. Effects of Factitious Airs, p. iv. p. 42.
Bernard, Cl., Subst. toxiques, etc., p. 135.
Bert. Comptes Rend. T. lxxxvii. p 628.
Buchheim, A. f. Exp. P. u. Ph., Bd. iv. p. 137.
Christison, on Poisons, 3rd ed. p. 745.
Donders, Pflüger's Arch., Bd. v. p. 20.
Friedländer u. Herter, Z. f. physiol. Chem., 1878, ii. 99, and 1879, iii. 19.
Heidenhain u. L. Meyer, Stud. d. physiolog. Instit. zu Breslau, Bd ii.
Hickmann, Séance de l'Acad. Roy., Sep. 24, 1828.
Humboldt, Von, U. üb. d. gereizte Nerven u. Muskelfaser, ii. p. 321.
Hermann, L. Exper. Toxikologie, 1874, p. 118.
Liebig, G., Arch. f. Anat. u. Physiol., 1850, p. 401.
Pflüger, Pflüger's Arch., Bd. i.
Priestley, on Airs, vol. i. p. 302.
Preyer, Wiener Acad. Sitzber. Math.-nat. Cl., Bd. xlix.; Pflüger's Arch., Bd. i. p. 395.
Quincke, A. f. exp. P. u. Ph., vii. p. 101, 1877.
Setschenow, Wiener Acad. Sitzungsber. Math.-nat. Cl., Bd. xxxvi.; Z. f. rat. Med., Bd. x. p. 101; Centralbl. f. d. med. Wiss., 1873, p. 355, 1877, 625, u. 1879, p. 369.
Zuntz, Centralbl. f. d. med. Wiss., Bonner Diss., 1868, Berl. klin. Wochenschr., 185, 1870.

Carbonic Oxide.

Friedberg, Die Vergift. durch Kohlendunst, Berlin, 1866.
Hoppe-Seyler, Virch. Arch., 1857, Bd. xii.
Kühne, Centralbl. f. d. med. Wiss., 1864, p. 134.
Lothar Meyer, Breslauer Diss., 1858.
Pokrowsky, Arch. f. Anat. u. Phys., 1866, p. 59.
Senff, Dorpater Diss., 1862.
Traube, Gesammelte Beiträge, Berlin, 1878, iii.

Chloral Hydrate.

Adams, Lancet, i., pp. 212 and 567, 1870.
Adrian, New York Med. Journ., 1870.
Andrews & Da Costa, Amer. Journ. Med. Sci., April, 1870, p. 359.
Anstie & Andrews, Amer. Journ. of Insan., July, 1871.
Beck, Jos. R., St. Louis Med. and Surg. Journ., June, 1872.
Bouchut, N. Y. Med. Gaz., Dec. 1870.
Bradbury, J. B., Brit. Med. Journ., vol. i. p. 363. 1871.
Brunton, Lauder, Journ. Anat., viii. p. 332, 1874.
Clarke, Lancet, May 2, 1874, p. 643.
Clemens, Schmidt's Jahrb., Bd. cli. p. 105.
Demarquay, Bull. Thérap., t. lxxvii. p. 307.
Dieulafoy & Krishaber, Amer. Journ. Med. Sci., Jan. 1870, p. 234.
Djurberg, Schm. Jahrb., Bd. cli. p. 84.
Dujardin-Beaumetz & Hirne, Bull. Thérap., lxxxvi. p. 224, 1872.
Elliott, G. F., Lancet, 1873, i. 754.
Fuller, H. W., Lancet, March, 403, 1871.
Gascoyen, Brit. Med. Journ., vol. i. p. 91, 1872.
Giovanni & Bauzoli, Schmidt's Jahrb., Bd. cli. p. 91.
Hammarsten, Deutsche Klinik, 1870; Schmidt's Jahrb., Bd. cli. p. 90.
Keen & Personne, Phil. Med. Times, vol. iv. p. 385.
Keen, Schmidt's Jahrbücher, clxxvii. p. 139; Am. Journ. Med. Sci., July, 1875, pp. 76 and 150.
Kirn, Ludwig, Allgem. Zeits. f. Psychychiatrie, xxix, 1872; Practitioner, vol. x. p. 361.
Leavitt, Amer. Journ. Med. Sci., Ap. 1871, p. 363.
Levinstein, Lancet, i. p. 279, 1874.
Lewisson, Reichert's Arb. f. Anat. u. Phys. 1870, p. 348.
Liebreich, Chloralhydrat, ein neues Hypnoticum, Berlin, 1869; Wiener Med. Wochens., Aug. 1869, p. 1087.
Macnamara, Pract., vol. ix. 257.
Morgenstern, Wien. Med. Presse, Nov. 1871, p. 1212.
Mosso, Schmidt's Jahrb., clxxvii. p. 138.
Murchison, Lancet, ii. p. 596, 1870.
Owsjannikow, Leipz. Acad. d. W., 1871.
Pellogio, Schmidt's Jahrb., Bd. cli. p. 89.
Personne, Journ. de Pharm. et de Chimie, 1870, p. 1.
Playfair, Lyon, Lancet, 1874, vol. i. p. 263.
Rajewski, Centralbl. f. d. med. Wiss., 1870. p. 211; Schmidt's Jahrb., Bd. cli. p. 90.
Rehn, Jahrb. f. Kinderkrankh., 1871, p. 430.
Reynolds, Practitioner, 1870, iv. p. 188.
Richardson, Med. Times and Gaz. vol. ii. p. 374, 1870.
Rigden, Practitioner, vol. v. p. 151, 1870.
Russell, Glasgow Med. Journ., Feb. 1870, p. 209.
Schmidt's Jahrb, Bd. cli.; Köhler's Abstracts of papers.
Schule, Allgem. Zeits. f. Psych., xxviii. p. 1.
Smith, N. R., Bost. Med. & Surg. Journ., vol. viii. p. 33, 1871.
Tomasczewitz, Pflüger's Arch., Bd. ix. p. 35.
Watson, Med. & Surg. Reporter, Jan. 27, 1871.
Waterhouse, Practitioner, Dec. 1870, vol. v. p. 344.
Widenhofer, Boston Med. & Surg. Journ., 1874.

Chloride of Sodium.

Becquerel & Rodier, Gaz. de Paris, xlviii. 1844.
Bert, P., Comp. Rend., lxxiii. p. 382.
Berzelius, Lehrbuch, ix. p. 98.
Guttmann, Klin. Woch., 1865, xxxiv.-xxxvi.
Hoppe, Deutsche Klinik, xxxii. 1863.
Klein u. Verson, Centralbl. f. med. Wiss., 1867, p. 788.
Lehmann, Physiol. Chem., i. p. 440, ii. 171, 241, iii. 141, 255.

Chlorate of Sodium.

Nasse, H., R. Wagner's Handwörterbuch, i. (Art. Blut.), p. 167.
Panum, Virch. Arch., iv. 1852.
Poggiale & Plouviez, Comp. Rend., xxv. p. 110.
Rabuteau, Bull. de Thérap., lxxxi. 1871, p. 562.
Voit, Unters. üb. d. Einfluss d. Kochsalzes, etc. München, 1860.
Wiscknewsky, Canstatt's Chimie, p. 116, 1867.

Chloroform.

Anstie, Stimulants and Narcotics, p. 321.
Baudin, Le Progrès Med., Sep. 1874.
Bernard, Cl., Leçons sur les Anesthésiques, Paris, 1875.
Bernstein, Centralbl. f. d. med. W., 1867, Bd. v. p. 38; Schmidt's Jahrb., Bd. clxii. p. 218.
Bert, Comp. Rend., t. lxiv. 1867; Journ. of Anat. & Phys., May, 1870, p. 312.
Bonwetsch, Dorpater Dissert., 1869.
Böttcher, Virch. Arch., Bd. xxxii. p. 126.
Bowditch, H. P., & C. S. Minot, Boston Med. & Surg. Journ., May, 1874.
Carter, Brit. Med. Journ., vol. i. p. 208, 1867.
Chloroform Committee, Med. Chir. Trans., vol. xlvii. p. 326.
Dogiel, Arch. f. Anat. u. Phys., 1866.
English Chloroform Committee, Medico-Chir. Trans., 1864, vol. xlvii.
Glover, Ed. Med. Journ., 1842, pp. 709 and 1009
Gosselin, Arch. Gén., 1848, vol. xviii. p. 385.
Harley, Phil. Trans., London, 1865.
Hartmann, Giessener Dissert., 1855.
Hermann, Arch. f. Anat. u. Phys., 1866, p. 27.
Holmes, E. L., Chicago Med. Examiner, Sep. 1868.
Husemann's Abstracts in Virchow-Hirsch's Jahresber; Schmidt's Jahrb., Bd. cli. p. 80.
Knoll, Wien. Acad. Sitzber., 1874, 1876 u. 1877
Lallemand, Perrin, Duroy, du Rôle de l'Alcohol et des Anesthésiques, Paris, 1860.
Leute, T. D., Psychol. & Med. Legal Journ., Feb. 1875.
Noel, Lond. Med. Record, 1877, p. 457.
Nothnagel, Berl. klin. Wochenschr., 1866, Bd. iii.
Ranke, H., Centralb. f. med. W., 1867, p. 209, u. 1877, No. 34, p. 608.
Richardson, Med. Times & Gazette, 1866-1870.
Sabarth, Das Chloroform, Würtzburg, 1866.
Sansom, Chloroform, p. 55, Philadelphia, 1866.
Scheinesson, Dorpater Diss. 1868, u. Arch. d. Heilk., Bd. x. p. 36.
Schenk, Sitzbericht d. Wien. Acad. M. N. Cl., 1868, Bd. lxviii.
Schmidt's Jahrb., Bd. cxlii. cxlv. cli. H. Köhler's Abstracts.
Schmidt, A., u. F. Schweiger-Seidel, Ber. d. König. Sachs. Gesell. d. Wiss. Math. Phys. Klin., 1867, p. 190.
Schmiedeberg, Dorpater Diss., 1867.
Simpson, Edin. Month. Journ. of Med. Sci., 1847, p. 33, and 1848, p. 315.
Simonin, Centralbl. Chir., 1876, p. 234.
Snow, On Chloroform & other Anæsthetics, London, 1858.
Westphal, Virch. Arch., Bd. xxvii. p. 409.
Winslow, W. H., Phil. Med. Times, vi. p. 275.

Chrysophanic Acid.

Gehe's Handelsberichte, 1878, u. 79.
Squire, Centralbl. f. d. med. Wiss. 1877, p. 384, u. 1878, s. 699.

Cimicifuga.

Chapman, N., Elements of Therap., 6th ed. vol. i.
Davies, N. S., Trans. Amer. Med. Assoc., 1848, vol. i. p. 351.
Young, Amer. Journ. Med. Sci., vol. ix. 1831, p. 310.

Cocaïn.

Anrep, Pflüger's Arch. Bd. xxi., 3, 38 (with complete list of literature.)
Bennett, A. Hughes, Edin. Med. Journ., Oct. 1873.
Koller, *vide* Cent. f. d. med. Wiss., 1884, p. 870.
Jessop, Practitioner, xxxiv. p. 1.

Codeia, *vide* Opium Alkaloids.

Barbier, Gaz. méd., ii. p. 147, 1834.
Barnay, De la Codeïne, Paris, 1877.
Baxt, W., Reichert's Arch., 1869, p. 125.
Berthé, Compt. Rend., lix., p. 914, 1865.
Crum Brown and Fraser, Proceed. Roy. Soc. of Edin., xxv. Jan. 6, 1868.
Des Brulais, Mon. des Hôp., xcvi. p. 767, 1856.
Dumont, Mon. des Hôp., xxviii. p. 221, 1858.
Falck, Deutsches Klin., 1870.
Guibert, Nouveaux Méd., p. 397.
Husemann, Pflanzenstoffe, p. 155.
Harley, Old Veg. Neurotics, p. 179.
Krebel, Med. Ztg. Russlands, 1856, p. 59.
Kunkel, Journ. de Chimie Méd., xi. 223, 1833.
Mitchell, Weir, Amer. Journ. Med. Sci., Jan. 1870, p. 26.
Myrtle, Brit. Med. Journ., 1874, i. 478.
Ott. Opium Alkaloids.
Schroff, Von., Pharmakologie, 3 Aufl. p. 483.
Wachs, L., Das Codein, Diss. Marburg, 1858.

Colchicum.

Albers, Deutsche Klinik, 1856.
Bacmeister, Arch. d. Pharmacie, 1857.
Bird, Urinary Deposits, Phila., 1859, p. 354.
Garrod, A. B., Med. Chir. Trans., 1858, xli. 348.
Geiger, Annal. Chem. Pharm., vii. 274.
Hammond, Proc. Phila. Acad. Nat. Sci., Dec. 1858.
Hoppe u. Aschoff, Vierteljahrs. f. Prakt. Pharm. vi.
Krahmer, Journ. f. Pharmacodynamik, ii. 561.
Lewins, R. Ed. Med. and Surg. Journ., 1841, vol. lvi. p. 200.
Ludwig and Pfeiffer, Arch. der Pharm. cxi. 3.
Maclagan, Ed. Monthly Journ. of Med. Sci., 3rd series, vol. xiv. p. 24.
Major, G. W., Canada Med. Surg. Journ., Dec. 1873.
Percy, S. R. Amer. Med. Times, Ap. 1862, p. 173.
Rossbach, Pharm. Unters. Bd. ii. 1876, s. 1-58.
Schroff, V., Zeitschr. d. Ges. d. Aerzte, 1851, u. österr. Zeitschr. f. pract. Heilk., 1856.
Scudamore, On Gout, Lond. 1835.
Taylor, Med. Juris, 2nd ed. vol. i.
Wood, Geo. B, U.S. Dispensatory, 13th ed. p. 1504.

Colocynth, *vide* Purgatives.

Buchheim, Die scharfen Stoffe, etc.
Husemann, Handbuch d. Toxicol., p. 525.
Marmé, W., Zeits. f. rat. Mediz., xxvi. 61.
Schroff, Von, Pharmacologie, 4 Aufl., p. 368, 1873.

Condurango.

Brunton, Lauder, Journ. of Phys. v. 17.
Ernst, Vjhrschr. f. ger. Med. xvi. 2, p. 321, u. Schmidt's Jahrb., clvii. p. 121.
Friedreich, Berliner klin. Wochenschr. 1874, No. 1.
Gianuzzi, Cent. f. d. med. Wiss., 1873, p. 824.
Hulke, Centralb. f. d. med. Wiss. 1872, p. 111.
Obalinski, Centralbl. f. Chir. 1874, No. 12. p. 177.
Riegel, Berl. klin. Wochenschr., 1874, No. 35, u. 36.
Sanctis, De, Schmidt's Jahrb., clvii. p. 121.
Sandahl, Hygiea, 1872, p. 14, and Schmidt's Jahrb., clviii. p. 121.
Schroff, un., Schmidt's Jahrb., clviii. p. 211.

Copaiba.

Bernatzik, Präger. Vierteljahrs., Bd. c. 1868, p. 239.
Blanchard, Gaz. des Hôp., xl. 1852.
Gubler, Comment. thérap. du Code, p. 88; Bull. de la Soc. de Thérapeut., 1, serie. xvi.
Mitscherlik, Preuss. Vereinsz., xix., 22, 1848.
Rees, Guy's Hosp. Rep., vol. xvii.
Schweitzer, Poggend. Ann., Bd. xvii. pp. 487, and 1095.
Valentine, Grundriss der Phys.
Weikart, H., Arch. d. Heilk., 1860, p. 176.
Wilks, Lancet, i. 12, Mar. p. 410, 1873.

Copper.

Bailly, L'Union, 6, 1874; Schmidt's Jahrb., clxiii. 1874, iii. Bd. p. 61.
Bergeret u. Mayençon, Journ. de l'Anat. et Phys., 1873.
Blake, Frank's Magaz., ii. 405.
Blasius, Zeitschr. f. rat. Med., 3 Reihe, Bd. xxvi. p. 240.
Buchner, Toxikol., 2. Aufl., p. 525.
Burq, Ducom, Schmidt's Jahrb., 1878, Bd. clxxviii. 14; Arch. de Phys. Norm. et Path., 1877, t. iv. 183.
Clapton, Med. Times and Gaz., vol. i. p. 658, June, 1868.
Clemens, Schmidt's Jahrb., cxxxi. p. 82, 1866.
Falck, Deutsches Klinik, xi. 1859.
Faulk, Deutsch. Klin., x. 430.
Galippe, Étude toxicol. sur la Cuivre, Paris, 1875; Comptes Rendus, t. lxxxiv. pp. 404 and 718.
Harnack, Arch. f. exp. P. u. Pharm., Bd. iii. p. 46, u. Bd. ix. p. 162, 1874.
Hönerkopff, Ueb. d. Anwend. d. schwefelsäuren Kupferoxydes gegen Croup. Leipzig, 1852, p. 60.
Lieberkühn, Poggendorff's An., 1852, Bd. lxxxvi.
London Clinical Soc. Transactions, 1870, p. 13.
Mérat et de Lens, Dict. univ. de Mat. Méd., ii., p. 67.
Mitscherlich, Müller's Arch., 1837, p. 91.
Neebe, Marburger Diss. 1857.
Pierre, St. and Pécholier, Med. Centralbl., 1854, p. 270.
Wibmer, Wirk. der Arzneim. u. Gifte, ii. 260, 1838.

Coto.

Albertoni, Arch. f. Path. u. Pharm. xviii., 291.
Burkhart, Berl. klin. Woch., 1877, p. 276.
Jobst, Ber. d. deutsch. chem. Ges., 1876, No. 17.

Croton Oil, *vide* Purgatives.

Adams, Husemann, Toxicol., Bd. ii. p. 443.
Brunton, Lauder, Practitioner, xii. 346.
Buchheim, Virchow's Arch., xii. i.
Giacomini, Stillé, Therapeutics, vol. ii. p. 451.
Hertwig, Stillé, Therapeutics, 2nd ed. vol. ii. p. 449.
Joret, Bull. de Thérap., lxi. p. 385, 1861.
Radziejewsky, Casuistik der Vergift. bei Husemann. Handbuch, p. 442, u. Pflanzenstoffe, p. 1113.
Wibmer, Wirkungen, etc., ii. 222.

Cubebas.

Adams, Edinb. Med. Surg. Journ., xv. 61.
Bernatzik, Präg. Vierteljahrs., 1864, Bd. lxxxi. p. 9.
Clarus, Arzneiml., p. 728.
Crawford, Edin. Med. Surg. Journ., xiv. 32.
Crane, Edin. Med. Surg. Journ., xxi. 302.
Gödecke, Preuss. Vereinsz., 34, 35, 1850.

CURARE.

Buchheim u. Loos, Ueber d. pharmakolog. Gruppe des Curarins, Giessener Dissert., 1870.
Bernard, Cl., Leçons sur les Substances toxiques, Paris, 1857, p. 338.
Bezold, Reichert's u. Bois Arch., 1859
Colasanti, Pflüger's Arch., Bd. xvi. p. 157.
Eckhardt, Beitr. z. An. u. Physiol., Bd. vi. p. 19, Giessen, 1871 (Historical).
Funke, Ber. d. k. sächs. Acad., 1869.
Hermann, Pflüger's Arch., Bd. xviii., p. 458, 1878.
Kölliker, Virch. Arch., Bd. x. p. 1.
Kühne, Reichert's u. Du Bois' Arch., 1860, p. 477.
Röhrig u. Zuntz, Pflüger's Arch., Bd. iv. p. 57, 1871.
Steiner, J., Reichert's u. Du Bois' Arch., 1875, u. eigene Schrift. Leipzig, 1877.
Zuntz, Pflüger's Arch., Bd. xii. p. 522, 1876.

CYANOGEN, *vide* PRUSSIC ACID.

DATURIA.

Laurent, Ch., Thèse, Paris, 1870, p. 22.

DIGITALIS.

Ackermann, Deutsch. Arch. f. klin. Medicin., Bd xi. 9, p. 135; Volkmann's samml. klin. Vorträge, No. 48, Leipzig, 1872.
Bert, P., Gaz. méd. de Paris, xi. 1873.
Boldt, Inaug. Diss., Schmidt's Jahrb., March, 1872.
Böhm, Pflüger's Arch., Bd. v. 4 u. 5, p. 153, 1872.
Bordier, Bull. Thérap., 1868, vol. lxxiv. p. 110.
Brunton, Lauder, On Digitalis, London, 1868.
Brunton & Meyer, Journ. of Anat. and Phys. vii. 1872, p. 134.
Coblentz, Z. E., Strasburg Thesis, 1862.
Costa, Da, Amer. Journ. Med. Sci., Jan. 1871, p. 1.
Dybkowsky, W., and E. Pelikan, Zeitschr. f. Wiss. Zool., Bd. xi. 1852.
Dickinson, Med. Chir. Trans., vol. xxxix. p. 1.
Eulenburg u. Ehrenkaus, Med. central. Z., xxviii. 777, 1859.
Fagge and Stevenson. Proceed. of the Royal Soc. London, vol. xiv. p. 270.
Fothergill, Digitalis, London, 1871; Brit. Med. Journ., pp. 5, 27, 57, 90, 115, and 146, 1871.
Görtz, Schmidt's Jahrb., Bd. clviii. Unters. üb. Digitalis Präparationen, Dorpat., 1873.
Gourvat, Gaz. Méd. de Paris, 1871.
Gaunot, Phila. Med. Times, iv. 30.
Hammond, Proc. Biol. Dep. Acad. Nat. Sci. Phila., Dec. 1858; Am. Med. Journ., Jan. 1859 p. 275.
Homolle, Arch. Génér. de Méd., July, 1861, p. 5; Journ. de Pharm. et de Chimie (3), vii. p. 57.
Köhler, H., Arch. exp. Path. u. Pharm. i. 2. p. 138, 1873.
Köhnhorn, Lancet, 1876, i. p. 582.
Koppe, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 274.
Kosmann, Bull de Thérap., lix. July, p. 60, 1860.
Lorain, Paul, Journ. de l'Anat. et Phys., 1870, p. 128.
Meihuizen, Arch. f. Phys., vii. p. 201, 1873.
Meusnier, Aug., De l'Action de la Digitale sur la Fonction glycogénique, Paris, Thesis, 1868.
Meyer, A. B., Arb. u. d. Phys. Instit. zu Zürich, Centralbl. f. med. Wiss., xvii. p. 270, 1869.
Onimus, Journ. de l'Anat. et Phys., ii. 337, July, 1865.

DIGITALIS.

Paul, C. Bull. Thérap., 1868, lxxiv. p. 193.
Perrier, Arch. f. exp. Path. u. Pharm., Bd. iv. p. 191.
Quevenne, Homolle et, Arch. de Phys. de Thérap., etc., par Bouchardat, i. 1854.
Ranvier, Comptes Rendus, 1869, vol. lxix. p. 1327.
Roucher, Practit., ix. p. 304, 1872.
Sanders, Edin. Med. Journ., iv. 369.
Schmiedeberg, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 16.
Schroff, v., Wien. W. S., xxiv. Wochenblatt d. k.k. G. der Aerzte z. Wien, xx. xxii., 1868.
Skoda, Wien m. Presse, xiii. Jahrb., 142, p. 21, 1864.
Stadion, Präger Vierteljahrs. f. d. prak. Heilk., 1862, Bd. lxxiv.; p. 97, 1872; Sydenham Soc. Year-book, 1862, p. 451.
Stannius, Arch. f. phys. Heilk., Bd. x. 1851, p. 177.
Tardiau, Clinique, p. 685, Obs. viii. Paris, 1867.
Traube, Annalen. d. Charitékrankenh. in Berlin 1851, Bd. ii. p. 1; Gesammelte Beiträge. z. Path. u. Physiol., Bd. i. Berlin, 1871; Med. Central. Z. xxx. 94, 1863; Berl. klin. Woch., vii. 201, 213, 1870, xxxi. xxxiii. 1871.
Vulpian, Comptes Rendus de la Soc. de Biol., 1855, p. 70.
Weil, A., Reich. Arch. f. Anat., 1871, p. 252.
Winkel, Phila. Med. Times, 1874, iv. p. 6, p. 554, 1861.
Winogradoff, Virch. Arch. f. Anat., Bd. xxii p. 457.
Wood, Amer. Journ. Med. Sci., July, 1871.
Wunderlich, Manual Med. Therm., Sydenham Soc. Transl., p. 325.

DUBOISIN.

Marmé, Nachr. v. d. k. Ges. d. Wiss. u. d. G. A. Universit. zu Göttingen, 1878, No. xii. p. 413.

ELATERIUM.

Gibson, Brit. Med. Journ., Nov. 1861.
Köhler, Virch. Arch., Bd xlix. p. 408, L. 2, p. 273, 3, 375, 1870.
Morries, Repertor. f. Pharm., xxxix. p. 134.
Schroff, Von, Pharmakologie, 4 Aufl., 371, 1873.
Stillé, Therap., vol. ii. p. 459.

EMETINE.

Ackermann, Rostocker Diss., 1856.
Carriger, J. H., New York Med. Journ., 491, 1878.
Chouppe, Le Progrès Méd., 1874, p. 425; Bull. de Thérap., June, 1874, 86, p. 481.
D'Ornellas, Gaz. Méd. 1873, p. 537.
Duckworth Dyce, Bartholomew Hosp. Reports, vol. v. p. 218, 1869, vol. vii. p. 91, 1871.
Foulkrod, Phila. Med. Times, viii. p. 554.
Harnack, E., Arch. f. exp. Path. u. Pharm., Bd. ii. p. 299, iii. 44.
Magendie u. Pelletier, Journ. d. Pharmacie, lix. p. 223, 1817.
Orfila, Toxicol., i. 551.
Pecholier, Comptes Rendus, Bd. lv. 1862; p. 771, Gaz. Méd. 1862.
Podwyssotski, A. f. exp. Path. u. Pharm., Bd xi. p. 231, 1879.
Pollichronie, L'Ipecacuanha, Paris, 1874.
Weylandt, Eckhardt's Beiträge z. Anat. u. Physiol., Giessen., 1869, v. i. u. Inaug. Dissert.
Woodhull, A. A., Atlanta Med. and Surg. Journ. 1875.

Ergot, *vide* Secale cornutum.

Bailly and Sée, Bull. Thérap., t. lxxviii. p. 435.
Barlau-Fontayral, Journ. des Sci. méd. pratiques de Montpellier, tomes vi. vii.
Boldt, Schmidt's Jahrb., March, 1872.
Bonjean, Traité de l'Ergot de Seigle, Paris, 1845.
Boreischa, Arbeit. Pharm. Lab. Moskaw, i. 55.
Bodin, Journ. des Connaissances Méd., 1842.
Brown-Séquard, Arch de Phys., 1870, t. iii. p. 434.
Buchheim, Berl. klin. Wochenschr., 1876, p. 309, No. xxii.; Arch. exp. Path. u. Pharm., Bd. iii. p. 1,
Clemens, Deutsches Klinik, 1865, 267.
Christmann, Centralb. f. d. med. Wiss., p. 800, Nov. 1869.
Costa, Da, Amer. Med. Journ. Sci., Jan. p. 117, 1875.
Diez, Stillé, Therapeutics, 2 ed. vol. ii. p. 585.
Dragendorff u. Podwissotzky, Arch. f. exp. Path. u. Pharmak., Bd. vi. p. 153, 192.
Duboué, Récherches sur les Propriétés thérap. du Seigle ergoté, Paris, 1873.
Eberty, Hallenser Diss., 1873; Schmidt's Jahrb., Bd. clviii. p. 127.
Goodall, Proceed. Med. Soc. Pennsylvania, 1873.
Hampel, Practitioner, vol. i. p. 263
Haudelin, Dorp. Diss., 1871; Schmidt's Jahrb., Bd. clv.p. 143.
Hensinger, Journ. f. Pharmacodyn, Bd. i. p. 405.
Hermann, Büchner's Repertor. f. Pharm., 1871.
Hildebrandt, Berl. klin. Woch., p. 297, 1872.
Holmes, Ch. L., Arch. de Physiol., t. iii. p. 384, 1870.
Kersch, Betz's Memorabilien, vol. xviii.
Kitchen, Amer. Journ. Insan., July, 1873.
Kobert, Practitioner, xxxiii., 409.
Köhler, H., Virch. Arch., Bd. lx. p. 384.
Langenbeck, Berl. klin. Woch., p. 117, 1869.
Le Gendre, Bull. Thérap., t. lxxvii. p. 232.
Levi, Lo Sperimentale, Aug. 1875.
Luton, A., Gaz. Hebdom., Oct. 1871, p. 610.
Meadows, Practitioner, vol. i. 166.
Nicitin, Rossbach's Pharm. Unters., Bd. iii. 1878.
Nicoll, P., & Mossop, Brit. & For. Med. Chir. Rev., vol. l. 1872, p. 252.
Oldwright, Canada Med. Journ., 1870, 320, 321, 404.
Ostere, Stillé, Therap., 2 ed. vol. ii.
Poyet & Commarmond, Annal. de la Soc. de Méd. de St. Etienne et de la Loire, 1863.
Ramsbotham, Principles & Practice of Obstetric Med. & Surg., Phila. 1860, p. 318.
Rossbach, Pharm. Unters., Bd. i.
Salkowski, Berl. klin. Wochenschr., 1876, p. 228.
Schüller, Berl. klin. Wochenschr., 1874, p. 305.
Tauret, Bull. Thérap., xciii. p. 231.
Tulasne, Ann. Sien. Natur. Botan., 3e série, t. xx. 1853.
Vogt, P., Berl. klin. Wochenschr., 1869, No. xii. p. 117, March, 1872, p. 115.
Wernich, Virch. Arch., Bd. lvi. p. 505, 1872; u. Beitr. z. Geburtsh., Bd. iii. Berlin, 1874.
Winckler, Amer. Journ. Pharm., May, 1864.
Woakes, Practitioner, vol. i. p. 257.
Wood, Phila. Med. Times, vol. iv.
Wright, S. A., Ed. Med. & Surg. Journ., Oct. 1839, vol. lii. p. 293.
Zweifel, Arch. f. exp. Path. u. Pharm., Bd. iv. p. 387.

Erigeron.

Starke, Lond. Med. Rec., 1876, p. 267.

Ether Oil.

Binz, Arch. f. exp. Path. u. Pharm., Bd. v. p. 109, Bd. viii. p. 50.
Böhm u. Kobert, C. f. d. med. Wiss., 1879, p. 689.
Grisar, Bonner Dissertation, 1873.
Högyes, Centralblatt f. d. med. Wissen., 1879, p. 32.
Köhler and his pupils, Schmidt's Jahrb., Bd. clxxiv. p. 19, 80, 121.

Eucalyptus Oil.

Aron, Schmidt's Jahrb., Bd. clvii. p. 239.
Binz, Brit. Med. Journ., i. 1874, p. 15.
Bohn, Berl. klin. Wochens., p. 110, 1872.
Brudell, Bull. Thérap., May 1875, p. 108, vol. lxxxix.
Cortau, Montpellier Méd., May 1872.
Gimbert, Arch. Gén., 1873, xxi. p. 141.
Haller, Wien. med. Wochens., xxvi.
Keller, Wien. med. Wochens., xxii.p. 227, 1872.
Köhler, H., Arch. d. Pharm. 3. Reihe, Bd. iii. Heft 2.
Lorrinser, Wien. med. Wochens., xix. xx.
Martin, S., Bull. Thérap. lxxxiii. p. 453.
Mosler, Deutsch. Arch. Klin. Med., 1872, x. 160.
Pappillon, Gaz. Hebdom., 1872, p. 501.
Rabuteau, Bull. Thérap., lxxxiii. 549.
Schläger, Inaug. Diss. Göttingen, 1874.
Seitz, Bayer. Arztl. Intell. Blatt, 1870, p. 310.
Siegen, Bonner Diss., 1873.
Tristany, Buchner's Repertor., xix. 1870.

Fat.

Lassar, Berl. klin. Wochenschr., 1879, No. xviii. p. 261.
Munk, J., Verh. d. physiol. Ges. in Berlin, Jahrg., 1877-79, No. 13.

Gelsemium.

Bartholow, Lond. Practitioner, v. p. 203.
Centralbl. f. d. med. Wiss., 1876, p. 128, 320, 384, 608, 927; 1877, p. 783; 1878, p. 652; 1880, s. 74.
Courtwright, Cincinnati Lancet & Obs., 1876, p. 963.
Ott, Phila. Med. Times, v. p. 691, vii. p. 289.
Ringer & Murrell, Lancet, ii. 1875, p. 908, 1876, i. p. 83, 1876, vol. ii. p. 78 and 569.
Tweedy, J., Lond. Lancet, 1877, i. p. 833.
Wormley, Amer. Journ. Pharm., 1870.

Glycerine.

Dujardin-Beaumetz & Audigé, Bull. Thérap., xci. p. 62.
Eckhard, Centrabl. med. Wiss., 1876, p. 273.
Luchsinger, Pflug. Arch., Bd. xi. p. 502; Centralbl. med. Wiss., 1877.
Lewin, L., Z. f. Biologie., 1879, Bd. xv. p. 243.
Munk, J., Verh. d. physiol. Ges. zu Berlin, 13, Dec. 1878, u. Virch. Arch., Bd. lxxvi. Heft 1. p. 119.
Schultzen, Berliner klin. Wochenschr., 1872, No. xxxv. p. 417.
Schwann, Enkhart's Beitrage z. Anat. u. Physiol. viii. p. 159..
Ziemssen's Encyclop., vol. xvi. for Literature.

Guaiac.

Bell, Lond. Med. Gaz., Oct. 1840, p. 202.
Bryden, Brit. Med. Journ., No. 47, 1857, p. 967, No. 97, p. 927, 1858.
Husemann, Die Pflanzenstoffe, p. 1106.
Sandras, Bull. de Thér., v. 371.
Walker, Brit. Med. Journ., vol. i. p. 528 and 660, 1864.
Wood, U.S. Dispensatory, p. 1223.

Hellebore.

Helm, Würzburger m. Z.S., ii. 5, 6. p. 448, 1861.
Marmé, Z. f. rat. Med. 3 Reihe., Bd. xxvi. p. 1098.
Scattergood, H. Journ. de Bruxelles, xxxix. p. 550, 1864.
Schroff, Von, Präger. Vierteljahrss., lxii. 1859, p. 49, 95, 106, lxiii. p. 95.

Hyoscyamia.

Harley, Old Veg. Neurotics.
Hellmann, Beitr. d. phys. Wirk. des Hyoscyamins, Diss. Jena, 1873.
Heilmann, Beitr. z. Kenntniss d. phys. Wirk. des Hyoscyamins, Jen. 1873.
Höhn, Arch. d. Pharm. 1868, p. 215.
Laurent, De l'Hyoscyamine et de la Daturine, p. 15, Paris, 1870.
Lemattre, Arch. Gén., 1865, vol. vi.
Oulmont, Bull Gén. de Thérap., lxxxiii. p. 481, 1872; Practitioner, vol. x. p. 1, 1873.
Schroff, V., Woch. d. Zeits. d. Gesellsch. d. Aerzte z. Wien, 1865.

Iodine and Iodide of Potassium.

Annuschat, A. f. exp. P. u. Pharm., x. 261 (Action in Lead Poisoning).
Bachrach, Berl. Diss., 1878.
Balfour, Ed. Med. Journ., xiii. p. 775, xiv. p. 33, xv. p. 47, xvi. p. 704; Brit. Med. Journ., 1874, i. 112.
Béhier, Nerven Centralorg., Schmidt's Jahrb., cxxvi. 162, 1865.
Bernard, Cl., Arch. Génér., 1853, Bd. i. p. 5.
Benedikt, M., Wien. Jahrb., xviii. ii. 94, 1862.
Binz, Virch. Arch., Bd. lxii. p. 124, u. Arch. f. exp. P. u. Ph. Bd. viii. s. 309.
Böck, V., Z. f. Biol., 1869; Bd. iii. 126; Bd. v. 393; Schmidt's Jahrb., Bd. cxlv. p. 142.
Böhm u. Berg, A. f. exp. P. u. Ph., v. 337, 1876.
Branne, Diss. Leipzig, 1856.
Buchheim, Arch. f. exp. Path. u. Pharm., Bd. iii. 104.
Chuckerbutty, Brit. Med. Journ., vol. ii. pp. 61 and 85, 1862 (in Aneurysm).
Cogswell, Edinburgh, 1837.
Coindet, Froriep's Notizen, i. 55, 89, 1822.
Devergie, Arch. gén. de Méd., x. 2, p. 255, 1826; Frank's Mag., iii. i. p. 201.
Dorpater Diss. v. Arroneet, 1852; Strauch, 1852; Heubel, 1865; Sartisson, 1866.
Eulenburg, Berlin. Klin. W.S., xvi. 1870.
Fournier, Centralb. f. d. med. W., 1878, p. 55.
Issersohn, Berl. Diss. 1877.
Greenhalgh, Brit. Med. Journ., vol. i. p. 52, 1868.
Handfield Jones, Beale's Arch., i.
Heubel, E., Dorpat. Diss., 1865, p. 70.
Kämmerer, Virch. Arch., Bd. lix. p. 459; Bd. lx. p. 527.
Keith, Edin. Med. Journ., xviii. p. 1077, 1873
Kochler, Deutsche Zeitschr. f. pract. Med., 1877, No. xl.
Melsens, Schmidt's Jahrb., Bd. cxxxiv. 19, 1867; Mémoire sur l'Emploi de l'Iodure de Potassium pour combattre les Affections Saturnines mércurielles et les allid. consécut. de la Syphilis. Bruxelles, 1868.
Pellikan, V., Beiträge zur Pharm. u. Tox. Würzb., 1858, p. 118.
Rabuteau, Gaz. Méd. de Paris, xix. p. 190. xxii. p. 302, xxiii. p. 313, 1869.
Rilliet, Bull. de l'Acad. Roy. xxv.
Ringer, Practit., March, 1872, vol. viii. p. 129.
Rose, Arch. f. path. Anat., 1866; Bd. xxxv.
Rösler, Frank's Mag., ii. p. 120, 136.
Sée, Lond. Med. Rec., i. p. 757, 777.
Sharpe, T. S., Amer. Journ. Med. Sci., Jan. 1876, p. 124.

Iodine and Iodide of Potassium.

Taylor, R. W., Amer. Journ. Syphil. & Derma., April 1873.
Wallace, I., Liverpool Med. & Surg. Rep., 1871.

Iodoform.

Binz, Arch. f. exp. P. u. Ph., viii. 309.
Elsberg, Phila. Med. Times, Oct. 4, 1873, vol. iv. p. 4.
Féréol, Bull. Thérap. t. lxxiv. p. 400, May, 1868.
Högyes, Arch. f. exp. P. u. Ph. x. 228.
Izard, A. A., New Treat. of Vener. Diseases, Boston, 1872.
Kennedy, S., Med & Surg. Rep., Jan. 1870, p. 50.
Lazansky, Centralbl. Chir., 1876, 219.
Moleschott, Wien. med. Wochenschr., 1878; Lond. Med. Rec., Nov. 1878, pp. 350 and 464.
Oberländer, Centralbl. f. d. Med. W., 1879, s. 336.
Pelletan, Phila. Med. Times, iv. 695.
Völker, G., Bull. Thérap., t. lxxiii. p. 493, Dec. 1867.

Ipecacuanha, *vide* Emetia.

Ackermann, Beobachtungen üb. physiol. Wirk. d. Emetica, Rostock, 1856, 4 Diss.
Cunningham, Edin. Med. J., vii. p. 25, July, 1861.
Duckworth, Dyce, St. Barth. Hosp. Rep., v. p. 230, 1869, vii. p. 98, 1871.
Higginbottom, Brit. Med. Journ., vol. i. p. 143, 1869,
Pécholier, Comp. Rend., vol. lvi. p. 718, 1863.
Schuchard, Arzneim., p. 586.
Wibmer, Wirk. d. Arzneim. u. Gifte, ii. 77.

Irritants, *vide* Oil of Mustard.

Iron.

Bernard, Cl., L'Union Méd., 1854.
Becquerel, Simon's Chemistry, vol. ii. p. 254.
Blake, Journ. of Anat. & Phys., p. 280, Nov. 1868.
Cutler & Bradford, Amer. Journ. Med. S. f. 1878, p. 78.
Complete list of Literature (228 Nos.) by Scherpf in Rossbach's pharmakolog. Unters., 1877, Bd. ii.; later works, Hamburger Z. f. phys. Chem. v. 1; Hoppe-Seyler, ii. p. 191.
Mialhe, Chim. Appliquée, Paris, 1856.
Mitscherlich, C. g. Preuss. Vereins. Z., 1846, xxi.
Nasse, Lond. Med. Rec., 1877, p. 498; Wagner's Handwörterb., Bd. i. (Art., Blut.)
Podrowsky, W., Virch. Arch., Bd. xxii. 5 & 6, p. 476, 1861.
Quincke, Ueb. Siderosis, Festschr. z. Haller's Jubelf. Bern. Reichert u. Du Bois' Arch., vi. p. 757, 1868.
Quevenne, Mémoire sur l'Action phys. et thérap. des Ferrugineux, Arch. de Phys., de Thérap. et d'Hygiène, Oct. 1854, p. 93.
Sasse, A., Vierteljahrs. f. Prakt. Heilk. 1866, 2 Bd.
Scherpf, Resorpt. u. Assim. d. Eisens, Würzb., 1878.
Simon, Animal Chem., Lond., 1845, Syd. Soc. ed.
Tiedemann u. Gmelin, Heidelberg, 1820.

Jaborandi, *vide* Pilocarpin.

Carville, Journ. de Thérap., 1875, p. 81.
Féréol, Journ. de Thérap., Jan. 1875, p. 45.
Galezowski, Med. Times & Gaz., 1877, ii. 558.

JABORANDI, *vide* PILOCARPIN.

JALAP, *vide* PURGATIVES.

LACTIC ACID.

Auerbach, A., Deutsch. Zeitschr. f. pract. Medicin, 1877, No. xlvii.
Erler, Centralbl. med. Wiss., 1876, p. 658.
Fischer, Lond. Med. Rec., 1877, p. 193.
Lothar, Meyer, Virch. Arch., Bd. lxvi. p. 120.
Meudel, Deutsch. med. Wochens., 1876, No. 17.
Preyer, Centralbl. med. Wiss., 1875, p. 577.
Bötticher, Berl. klin. Wochens., 1877, p. 537.

LEAD.

Annuschat, A. f. exp. Path. u. Pharm., Bd. vii. p. 45, and Bd. x. p. 261.
Bardenhewer, E., Berl. klin. Wochens., 1877, 126.
Blake, Edin. Med. & Surg. Journ., lvi. 1, p. 116, 1841.
Chatin, Comptes Rendus. Soc. Biolog., t. iv. 1862, p. 84.
Cours, De, A., De l'Hemianæsthesia saturnine, Paris, 1875.
Debove et Renaut, Le Progrès Méd., 1876, 151.
Eulenburg, A., Deutsch. Arch. für klin. Med., Bd. iii. p. 506.
Falck, Virch. Handbuch d. spec. Path. und Ther., ii. 1, 1855.
Frank, A., Deutsch. Arch. klin. Med., xvi. 423.
Friedländer, Virch. Arch., Bd. lxxv. p. 24, 1879.
Gusserow, Arch. f. path. An., Bd. xxi.
Harnack, A. f. exp. P. u. Pharm., Bd. iii. 54, 1874, Bd. ix. 152.
Henle, Zeitschrift f. rat. Med., 3 R. Bd. iv., u. Handb. d. rat. Path. 1847, Bd. ii. 179.
Hermann, Arch. f. Anat. u. Phys., 1867, 64.
Heubel, Pathogen. u. Sympt. d. chron. Bleivergift, 1871; Virch. u. Hirsch's Jahrbücher, 1871, vol. i. p. 316.
Hitzig, Studien ü. Bleivergiftg., 1868.
Kussmaul u. Meyer, Arch. f. klin. Med., Bd. ix. 283.
Lancereaux, E., Comptes Rendus de la Soc. Biol., liv. 3rd ser. 1862, p. 84.
Lewy, E., Schmidt's Jahrb., Bd. clii. p. 250.
Lewald, Unters. üb. d. Ausscheid. von Arzneim. aus dem Organismus, Breslau, 1861.
Malassez, Arch. de Phys., 1874, p. 50.
Manouvriez, Arch. d. Phys. Normal et Pathol., 1870, 411, 1876, 762; Recherches cliniques sur l'Intox. Saturnine locale et directe, Paris, 1874.
Paul, C., Arch. Gén., 5th series, vol. xv. 1860, p. 513.
Remak, Arch. f. Psychiatr. u. Nervenkr., Bd. ix. Heft 3, p. 510.
Renaut, Gazette med., 1878, No. 32, u. Centralb. f. d. med. W., 1879, p. 159.
Rosenstein, Arch. f. path. Anat., Bd. xxxiv. 1867, p. 4.
Rosenstirn, Rossbach's pharmak. Unters. Würtzburg, 1874.

LEAD.

Tanquerel des Planches, Die gesammten Bleikrankh., übers v. Frankenberg, 1842.
Trousseau, Froriep's Notiz., xviii. No. 13, p. 207, 1827.
Wood, Geo. B., Therapeutics, vol. i. p. 158.

LITHIUM, *vide* ALKALIES.

Gibb, Report of Brit. Assoc. for Advancement of Science, 1864.
Mitchell, Weir, Amer. Journ. Medical Science, Oct. 1870, p. 443.

LOBELIA.

Ott, I., Bost. Med. and Surg. Journ., 1875, vol. xcii. p. 124; Phila. Med. Times, vi. p. 121.

MAGNESIUM, *vide* ALKALINE EARTHS.

MANGANESE.

Charvet, Bull. de Thérap., lxxviii. p. 80, 1870, Lungengangrän.
Garrod, Med. Times & Gaz..
Gmelin, U. S. Dispensatory.
Laschkewitz, Journ. de Bruxelles, Bd. xliv. p. 534, June, 1867.
Leared, Glasgow Med. Journ., Jan. 1865, p. 488.
Pétrequin, Nouvelles Recherches du Manganèse, 2 ed. Paris, 1852; Bull. Thérap., Mar. 1852, p. 193.
Williams, American Journ. N. S. cxvii. p. 74, Jan. 1870.

MERCURY.

Baerensprung, Ann. d. Charité, 1856, Bd. vii. p. 2.
Bamberger, Wien. med. Wochenschr., 1876, Nos. xi. u. xiv.
Boeck, V., Z. f. Biologie, v. 3, 1869; Schmidt's Jahrb., Bd. cxlv. p. 142.
Foot, A. W., Dub. Journ. Med. Sci., 1873.
Fürbringer, Berl. klin. Wochenschr., 1878, No. xxiii. p. 332.
Hassenstein, Königsberger Diss., 1879.
Heilborn, Arch. f. exp. Path. u. Pharm., Bd. viii. s. 361.
Keyes, E. L., Amer. Journal Med. Sci., Jan. 1876, p. 17.
Kolliker, Th., Verh. d. Würtzburger phys. med. Ges., N. F., Bd. x. 1877.
Kussmaul, Unters. üb. d. constit. Mercurial, 1861, p. 17.
Lewin, Charité-Ann., Bd. xiv.
Mussy, N. G. de, Gaz. des Hôpitaux, 1868.
Oetlingen, V., Dorp. Diss., 1848.
Overbeck, Mercur. u. Syphil., Berlin, 1861.
Rindfleisch, Arch. f. Dermatol., 1870.
Saikowski, Virch. Arch., Bd. xxxvii. p. 346.
Sigmond, Mercury, Blue Pill, and Calomel, Lond., 1840.
Sigmund, Wien. med. Wochenschr., 1859.
Stern, Berl. klin. Wochenschr., 1878, p. 59.
Voit, Ueb. d. Aufnahme des. Q. u. seiner Verb. and Körper in his Phys. chem. Unters., 1857.
Wilbouchewitcz, Arch. de Physiol., Sep. 1874. p. 509.

MORPHIA, *vide* OPIUM ALKALOIDS.

MUSCARIN.

Bäuerlein, Zur Accommodat. des menschl. Auges Würtzburg, 1876.

MUSCARIN.

Bogoslowsky, Centralb. f. d. med. Wiss., 1870, p. 97.
Harnack, Arch. f. exp. Path. u. Pharm., Bd. iv. p. 168, 1875.
Krenchel, Arch. f. Ophthalm., xx. ii. p. 134.
Schmiedeberg u. Koppe, Das Muscarin, Leipzig, 1869.
Schmiedeberg u. Harnack, Arch. f. exp. Path. u. Pharm., Bd. vi. s. 101, 1876.

MUSK.

Barbier, Mat. Méd., ii. p. 217.
Filehne, Sitzungsber. der Erlanger phys. med. Ges., 1876; u. Centralb. f. d. med. Wiss., 1876, p. 880.
Jörg, Materialien z. e. z. Arzneimittellehre, p. 285, Leipzig, 1825.
Tralles, Com. de rebus in Sc. Natur et Med. gestis, xxvi. p. 434.
Trousseau & Pidoux, Traité, etc., 8, ed. ii. p. 187.

NARCIA, *vide* OPIUM COMPOUNDS.

Albers, Virch. Arch., vol. xxvi. p. 225.
Baxt, Reichert's Arch., 1869, p. 112.
Belner & Debout, Bull. Thérap., t. lxvii. p. 145.
Bernard, Cl., Arch. Générales, 1864, 6e sér. t. iv. p. 459.
Eulenburg, Schmidt's Jahrb., Aug. & Oct. 1866, cxxxi. p. 22.
Fronmüller, Schmidt's Jahrb., Bd. cxli. p. 15.
Harley, The Old Veg. Narcotics, p. 143; Pennsyl. Hosp. Reports, 1868.
Husemann, Pflanzenstoffe, p. 184.
Kersch, S., Schmidt's Jahrb., Bd. cxli. p. 15.
Liné, Journ. de Pharm. et de Chémie, 4e sér. t. iii. p. 386.
Mitchell, Weir, Amer. Journ. Med. Sci., Jan. 1870, p. 17.
Oetlinger, Inaug. Diss., Tübingen, 1866.

NARCOTICS, *vide* OPIUM ALKALOIDS.

Rumpf, Centralb. d. Med. Wiss., 1884, p. 366.

NICOTIN.

Albers, Deutsche Klinik, 1851, No. 32.
Anrep, V., Du Bois-Reym, A. f. An. u. Phys.; Phys. Abth., Jg. 1879; Suppl. Bd. p. 167; u. Jg. 1880, p. 209.
Basch, V., u. Oser, Wien Med. Jahrb. 1872, p. 367.
Bernstein u. Dogiel, Verhandl. des nat. Med. Vereins. zu Heidelberg, iv. 28.
Benham, W. T., West Riding Lunatic Asylum Rep., vol. iv. p. 307, 1874.
Bernard, Cl., Substances Tox., p. 399, 410.
Bibra, V., Die Narkot Genussmittel, 1855, p. 297.
Blatin, Recherches phys. and clin. sur la Nicotine et le Tabac, Paris, 1870.
Bohm, Herzgifte, Würzburg, 1871, p. 12.
Bon, Le, Med. Centralzeit, xli. 1, June, 1872.
Böttger, Buchner's Neue Repert. der Pharm., xvi. 579.
Brodie, Phil. Trans., 1811, p. 178.
Buchheim u. Loos, üb. d. Grüppe d. Curarius, Diss. Giessen, p. 48.
Eulenberg u. Vohl, Vierteljahrsschr. f. Gerichtl. Medicin, Bd. No. 6, p. 249, xiv.
Grünhagen, Centralb. für med. Wiss., 1863, p. 577.
Hammond, Amer. Journ. Med. Sci. p. 282, 1857.
Haughton, p. 55.
Hirschmann, L. Reich. Arch., 1863, p. 309.
Husemann, Handb. d. Toxicol., vol. ii. 483.
Kölliker, Virch. Arch. x. p. 253, 1856.

NICOTIN.

Krocker, Berl. Diss. 1855.
Nasse, V., Beitr. z. Darmbewegung, Leipzig, 1866.
Namias, Comp. Rend. lix. p. 90, 1864.
Orfila, Mémoire sur la Nicotine et sur la Conicine, Bruxelles, Youker, frères, 1851.
Praag, L. v., Virch. Arch. Bd. viii. p. 56.
Rogow, Zeitschr. f. rat. Med., xxix. p. 1.
Reil, Journ. f. Pharmacodyn, Bd. ii. p. 203.
Rosenthal, Centralb. f. d. med. Wiss., 1863, p. 737.
Schmiedeberg, Sitzber. d. K. Sächs Acad., 1870.
Sée, Nouveau Dict. de Méd. V. art. Asthma, p. 715, 1865; Journ. of Anat., May, 1870, p. 315.
Savory, The Lancet, 1863, vol. i. p. 549.
Surminsky, Ztschr. f. rat. Med. (3), xxxvi. p. 205.
Tscheschichin, Reich. u. Dubois' Arch., 1866, p. 151.
Traube, Allgemeine Med. Central. Zeit., 1862.
Truhart, Dorpater Diss., 1869.
Uspensky, Reich. u. Dubois' Arch., 1868, p. 522.
Vulpian, Comptes Rend. de la Soc. de Biol., 1851, p. 151.
Wertheim, Zeitschr. d. k. k. Gesellsch. d. Aerzte z. Wien 1851. 8.

NITRITE OF AMYL.

Aldridge, Ch., West Riding Lunatic Reports, vol. i. p. 71.
Amez-Droz, Arch. de Phys. Norm. et. Path., Sept. 1873, p. 467.
Arb, a. d. physiol. Inst. z. Leipzig, 1869; Journ. of Anat. and Phys., vol. v. p. 93; Lond. Clin. Soc. Reports, vol. iii.
Balard, Ann. de Chimie et de Phys., xii. 1844, p. 294.
Berger, O., Allgem. Med. Central. Zeit., May, 1871.
Brunton, Lauder, Lancet, vol. ii. p. 97, 1867.
Filehne, Pflüger's Archiv, Bd. ix. p. 40; and Arch. f. Anat. u. Physiol., 1879, p. 385.
Fothergill, Brit. Med. Journ., 1874, i. 77.
Gamgee, A., Philos. Trans., 1868, p. 589.
Giacosa, Z. f. physiol. Chimie, iii. p. 54.
Gray, St. Clair, Glasg. Med. Journ., 1871, p. 188.
Guthrie, Ann. d. Chem. u. Pharm., Bd. iii.
Hoffmann, F. A., Reichert's Arch., 1872, 747.
Jolyet u. Regnard, Centralbl. f. d. med. Wiss., 1876, p. 860; Gaz. Méd. de Paris, 1876, No. 29.
Ladendorf, Berl. klin Wochens., No. 43, 1874, 537.
Mayer, S., A. f. exp. P. u. Pharm., v. 55, 63.
Mitchell, Weir, Phila. Med. Times, 1872, vol. v. p. 353.
Pick, über d. Amylnitrit, 2 Aufl., bei Hirschwald, Berlin, 1877; mit ausführlicher älterer Literaturangabe, Centralbl. med. Wiss., No. 55, p. 865, 1873; Deutsch. Arch. Klin. med. xvii. 143.
Putnam, Mary, Jacobi's New York Med. Rec., Jan. 1875, p. 11.
Richardson, B. W., Trans. Brit. Med. Assn. for Adv. of Science, 1864-1872.
Schuller, Berl. klin. Wochens., No. 25, 1874, 294.
Urbantschitsch, Wien. Med. Presse, 1877.
Wood, Amer. Journ. Med. Sci., July, 1871, p. 39.

NITROBENZOLE.

Bahrdt, Arch. f. physiol. Heilk., 1871, p. 320.
Filehne, A. f. exp. P. u. Ph., ix. p. 339.
Guttmann, Arch. f. Anat. u. Phys., 1866.
Helbig, Deutsche mil.-arztl. Zeitschr., Bd. ii. 1873.
Letheby, Med. Chirurg. Review.
Lewin, Virchow's Arch., lxxviii. p. 193, 1879.
Poincaré, Centralbl. f. d. med. Wiss. 1879, p. 937.

Nitrogen.

Chevreul, Nouv. bullet. d. l. soc. philomet. 1816.
Meyer, L. Zeitschr. f. r. Med., N. F., Bd. viii. p. 256.
Regnault u. Reiset, Compt. Rend., Bd. xxvi.

Nitroglycerin.

Brunton, Lauder and Tait, St. Bartholomew's Hosp. Rep., 1876, p. 140.
Green, Practitioner, xxviii. 102.
Murrell, Lancet, 1879, pp. 80, 113, 225.
Pelikan, Beiträge.

Nitric Oxide.

Podolinsky, Arch. f. ges. Physiol., 1872, Bd. vi. p. 553.

Nitrous Oxide.

Amory, N. Y. Med. Journ., Aug. 1870, p. 1.
Bert, Gaz. d. Hôp., 1879, No. xxxvii. u. xli.
Cotton, Phys. Action of Nitrous Oxide Gas, Phila. 1871.
Goltstein, Pflüger's Arch., 1878, Bd. xvii. 331.
Hermann, L. Arch. f. Anat. u. Physiol., 1864, p. 521.
Jolyet and Blanche, Arch. de Phys., July 1873, p. 364.
Thomson, E., Phil. Med. Times, Nov. 15, 1873, p. 97, vol. iv.
White, T. W. Dental Mat. Med., Phila. 1868.
Zuntz, Pflüger's Arch., xvii. 135.

Oil of Mustard.

Heidenhain, Pflüger's Arch., Bd. iii. p. 504; Bd. v. p. 309; Bd. vi. s. 20.
Köhler, Centralb. f. d. med. W., 1878, p 433, u. 450.
Naumann, Prag. Vierteljahrsschr. Bd. lxxvii. p. 1.
Paalzow, Pflüger's Arch., 1871, vol. iv. p. 492.

Opium Alkaloids.

Albers, Arch. f. path. Anat., Bd. xxvi. p. 229.
Baxt (Thebaia), Wien. Acad. Sitzber., 2 Abth., Bd. lvi. p. 189; u. Arch. f. Anat. u. Phys., 1869, p. 128; Ludwig's Arbeiten.
Bernard, Cl. Leçons sur l'Anesth. et s. l'Asphyxie, Paris, 1875; Arch. Gén. p. 455, vol. iv. 6th ser. 1864.
Bouchardat, Schmidt's Jahrb., Bd. cxx. p. 280.
Boeck, V., Unters. üb. p. Zersetz d. Eiweiss. München, 1871.
Buskirk, Washington Post, Jan. 33, 1878.
Chalkius, Quart. Journ. Psychol. Med., 1868, vol. ii. 739.
Charvet, Pereira's Mat. Med., vol. ii. p. 1035, Phila. 1854.
Dain, Amer. Med. Journ., July, 1874.
Dietl and Vintschgau, Pflüg. Arch., Bd. xvi. p. 316.
Dragendorff, Pharm. Zeitschr. f. Russland, 1866.
Eckhard, C. u. F. Eckhard's Beiträge z. An. u. Phys., Bd. viii. s. 79, 138. 1878.
Eulenberg (Narcein), Deutsch. Arch. f. klin. Med., Bd. I. p. 55.
Fiset, Morrison, N. Y. Med. Rec., July, 1874, p. 342.
Gscheidlen (Morphin), Unters. a. d. physiol. Lab. in Würtzburg, Bd. ii. 1869.
Harley, Old. Veg. Neurotics, 107, London, 1869.
Kauzmann, Dorpater Diss., 1868.
Kölliker, Arch. f. path. Anat., Bd. x.; Virch. Arch., Bd. x. p. 248.
Literature, complete, Arch. f. Path. u. Pharm. vii. 24.

Opium Alkaloids.

Loomis, A. New York. Med. Rec., 1873.
Melhuizen, Pflüger's Arch., Bd. vii. 1873, p. 201.
Mitchell, Weir, Amer. Journ. Med. Sci., Jan. 1869, p. 37, Jan. 1870, p. 17.
Müller (Thebaia), Marburger Dissert., 1868.
Nasse, Beitr. z. Physiol. d. Darmbeu, Leipzig, 1866.
Nothnagel, Handb. d. Arzneim., Berlin, 1870, p. 8.
Oetinger (Narcein), Tübinger Diss., 1866.
Paby, Med. Times and Gaz., June, 1869, p. 641.
Reese, Amer. Journ. Med. Sci., Jan. 1871, pp. 133 & 373.
Salvioli, Ludwig's Arbeiten.
Smith, E. Lancet, vol. i. p. 419, 1854.
Wachs, üb. (Codeia), Marburger. Diss., 1868.
Witkowski (Morphia), Arch. f. exp. Pathol. u. Pharm., Bd. vii. p. 247, Complete Literature.
Wood, Bost. Med. Surg. Journ., vol. lix. p. 268, 1858.

Organic Acids, *vide* Acids.

Oil of Turpentine.

Crucis, Léon, De la Térébinthine, Paris thesis, 1874.
Fleischmann in Rossbach's pharm. Unters., Bd. ii. Vgl. ätherische Oele.
Hoppe, Journ. f. Pharmacodyn., Bd. i. p. 105.
Kobert, R., Centralb. f. med. Wiss., 1877, p. 129.

Oxygen.

Afanassiev, Ber. d. k. sächs Ges. d. Wiss., 1873.
Assmuth, Dorp. Diss., 1864.
Bert, Leçons sur la Respiration.
Buchheim, Arch. f. exp. P. u. Ph., Bd. iv. p. 137.
Donders, Pflüger's Arch., Bd. v. p. 20.
Dybkowski in Hoppe-Seyler's Med. Chem. Unters., Bd. i.
Estor u. St. Pierre, Journ. de l'Anatomie et de la Phys., Bd. ii. 106.
Fernet, Ann. d. Sciences nat., vi. Bd. viii.
Friedländer u. Herter, Z. f. physiol. Chem., iii. 19.
Gorup-Besanez, Annal. d. Chem. u. Pharm., Bd. cx. u. cxxv.
Häcker, Dissert. Dorpat. Riga., 1863.
Herter, Ueber d. Spannung des O. in arteriellen Blut. Z. f. Physiol. Chem., iii. 98, 1879.
Hoppe-Seyler, Med. Chem. Unters. Bd. i. in Arch. f. Physiol., Bd. vii. 9; Physiol. Chimie, i. s. 7, u. 39.
Hüfner, Zeits. f. phys. Chimie, i. p. 317, u. 386, u. Centralbl., 1878, p. 710.
Liebig, G., Aerztl. Intelligenzbl., 1879, No. xix.
Magnus, Poggendorf's Ann., Bd. xl. p. 583, u. lxvi. p. 177.
Manassein, Centralbl. f. m. Wiss., 1871, xliv. p. 688.
Meyer, Lothar, Zeitsch. f. rat. Med., No. i. Bd. viii. p. 256.
Muller, W., Wien. Acad. Sitzber., Bd. xxxiii. 99.
Pflüger in Seinem Arch., Bd. 1, p. 274.
Regnault u. Reiset, Compt. Rend., Bd. xxvi. pp. 3, 4, 17.
Schmidt, Al., Ozon. im Blut. Dorpat, 1872; Hämatol. Studien Dorpat, 1865; Centralbl. f. d. Med. Wiss., 1867; Ber. d. k. sachs Ges. d. Wiss. M. phys. Cl., Bd. xix.; Arch. f. path. Anat. u. Phys., Bd. xlii.
Schönbein, Roy. Soc. Proc., 1840.

Pellitory.

Browne, London Practitioner, xvii. p. 86.

PEPPERMINT.

Marcusson, Hallenser Diss., 1877.

PEPSIN.

Albertoni, Centralb., f. d. med. Wissen. 1878, p. 641.
Beale, Arch. f. 1850, i. iv.
Davidson, Practit., March, 1872, vol. viii. p. 131.
Dowdeswell, Pract., Papain, vol. xxx. p. 485.
Ewald, Frerichs u. Leyden's Z. f. klin. Med., i. 231.
Gray, Jas., Edin. Med. Journ., Jan. 1853, p. 31.
Joynes, L. S., Richm. and Louisville Med. Journ., 1869.
Leube, W. O., Deutsches Arch. f. klin. Med. ix. 532, x. 1, 1872.
Manassein, Virch. Arch., 1872, vol. lv. p. 413.
Roberts, W.
Tuson, Med. Times and Gaz., vol. ii. 1882.
Wayne, Amer. Journ. Pharm., 1868.

PEPTON.

Penzoldt, Deut. med. Wochensschr., Bd. iv. s. 413, 425.
Schmidt-Mühlheim, Ludwig's Arb.
Seegen, Pflüger's Arch. vol. xxv. p. 165.

PEROXIDE OF HYDROGEN.

Assmuth, Dorp. Diss., 1864.
Guttmann, Virch. Arch., Bd. lxxiii. p. 23, u. lxxv. p. 255.
Richardson, Lancet, vol. i. p. 383, 1862.
Stöhr, Arch. f. klin. Med., 1867, Bd. iii. p. 421.

PETROLEUM.

Lassar, Berl. klin. Wochensschr., 1879, No. xviii. s. 261.

PHOSPHORUS.

Abstract of the Literature up to 1867, in Schmidt's Jahrb., Bd. cxxxvi. p. 209.
Andant, Journ. de Méd. de Bruxelles, 1868-79.
Anstie, Pract. 1873, vol. xi. 103.
Aufrecht, Deut. Arch. f. klin. Med., xxiii. 331.
Bauer, Zeitschr. f. Biologie, Bd. vii. to xiv.
Bollinger, Deutsch. Arch. klin. Med. Bd. v. p. 149, 1869; Bd. vi. p. 94, 1870.
Demarbaix and Wilmart, Presse Med. belge, xxi. p. 197, xxv. 1869; Schmidt's Jahrb., b. cxliv. v. p. 152.
Dybkowsky, Hoppe-Seyler's Med. Chem. Unters., Heft i. p. 54.
Eames, H., Dub. Journ. Med. Sci., Jan. 1872, p. 1
Eulenberg and Guttman, Aertz Literaturblatt, 1868, No. 12; Syd. Year Book, 1868, p. 450.
Falk, jun., Arch. f. exp. Path. u. Pharm., Bd. vii. 1877.
Friese, Berl. klin. Wochens., 1877, p. 437.
Hartmann, Dorp. Diss., 1866.
Hermann u. Brunner, Pflüger's Arch., Bd. iii.; p. 1; Deut. Arch. klin. Med., p. 198.
Kohts, O. Pflüg. Arch., vol. xiii. p. 84, Deutsch. Arch., f. klin. med. Bd. v. p. 168.
Köhler, Berl. klin. Wochens., 1870.
Lebert and Wyss, Arch. Gén., 1868.
Mayer, Canstatt's Jahresb., Bd. v. 1862, p. 123.
Munk and Leyden, Die Acute Phosphorverg. Berl. 1865.
Ossikowsky, Wien. Med. Presse, 1872.
Percy, S. R., Prize Essay, Trans. Amer. Med. Assoc., 1872, p. 659.
Poulet, Gaz. Méd. de Paris, Aug. 1872.
Schiff, Arch. Exp. Path. u. Pharm., Bd. ii. p. 347.

PHOSPHORUS.

Schulzen u. Riess, Ann. de Charité, Bd. xv.
Schuchardt, Henle and Pfeufer's Arch., N. F., Bd. viii. p. 235.
Sotnitschewsky, Z. f. physiol. Chimie, iii. p. 391, 1879.
Thompson, J. A., Lond. Pract., vol. xi. pp. 13 & 27. July, 1873.
Vetter, Virch. Arch., Bd. liii. p. 186, p. 21.
Vigier, Bull. Thérap., xc. Jan. 1876.
Virchow, Sein. Archiv., Bd. xxxi. p. 399, 1864.
Wegner, Virch, Arch., Bd. lv. p. 11, June 22, 1872; Wien. Med. Presse, Jan. 1872.
Weyl, Arch. d. Heilk., 1878, p. 163.

PHYSOSTIGMA.

Amagat, Journ. de Thérap., 1876.
Arnstein, C., and Sustschinsky, Unters. Phys. Lab. Würzberg, 2 Th. p. 86.
Edwards, J. B., Med. Times and Gaz., vol. ii. p. 212, 1864.
Engelhardt, Unters. a. d. Phys. Lab. Würzburg, 2 Th. 526.
Fraser. Trans. Royal Society of Edin., vol. xxiv.
Frölich, Pharm. Unters., i. 56.
Grünhagen, Virch. Arch., Bd. xxv. p. 521.
Harnack u. Witkowski, Arch. f. Exp. Path. u. Pharm. v. 142.
Jones, W., Pract., 1869, vol. iii. p. 163.
Keyworth, Glasg. Med. Journ., N. S. 1869, i. p. 54.
Kleinwächter, Revue Photogra. des Hôpitaux, 1870.
Köhler Arch. Exp. Path. u. Pharm. Bd. i. 280.
Laschkewitch, Virch. Arch., 1866, Bd. xxxv. 294.
Leven and Laborde, Schmidt's Jahrb., Bd. cxlvi. p. 136.
Lewisson, Reich. Arch., 1870, p. 346.
Merson, Journ. of Mental Sci., Jan. 1875, vol xx. p. 602.
Papi, C., Schmidt's Jahrb., cxlii. 287; Gaz. Lomb., 1858.
Robertson, Argyll, Edinb. Med. Journ., 1863.
Roemer, St. Louis Med. and Surg. Journ., 1873, 367.
Rosenthal, Reich. Arch.
Subbotin, Arch. f. klin. Med., Bd. vi. 285, 1869.
Tachau, Arch. d. Heilk., 1865, p. 70.
Vée and Leven, Comptes Rend. de la Soc. de Biol., 1865, p. 161.
Westermann, Schmidt's Jahrb., Bd. cxxxviii. p. 290.

PILOCARPIN.

Complete List of Literature (117 Authors), bei Lewin, Berl. Charité Annal., v. Jahrg. 1878, p. 559.

PRUSSIC ACID.

Bernard, Cl., Leçons sur les Subst. toxiques, p. 193, Paris, 1857.
Bischoff, Ueb. Vergift. Wien, 1844.
Böhm, Arch. f. exp. P. u. Pharm., Bd. ii.
Böhm u. Knie, Arch. f. exp. Path. u. Therap., Bd. ii. p. 135, 137.
Bunge, A. f. exp. P. u. Pharm., xii. 1 (Gangas).
Coze, Gaz. Méd. de Paris, 1849; Comptes Rend., t. xxviii. 1849, p. 780.
Fagge, Hilton, Guy's Hosp. Rep., 1868, p. 259.
Funke, Ber. d. K. sächs Gesell. d. Wiss. z. Leipzig, Bd. xl. 1859, p. 28.
Gähtgens in Hoppe-Seyler's Med. Chem. Unters. Berl., 1866, 324, s. 346.
Geinitz, E., Pflüger's Arch., Bd. iii. 1870, p. 46.
Harley, Lond. Phil. Trans., 1865, p. 706.
Hiller, Centralbl. f. d. med. W., 1877, 577.
Hiller and Wagner, Lancet, 1877, ii. 933.

Prussic Acid.

Hoppe-Seyler, Med. Chem. Unters. Berl., 1867, 140; Virch. Arch., Bd. xxxviii. p. 475.
Hünefeld, Der Chemismus in d. thierischen Organisation, Leipsic, 1840.
Jones, J., N. Y. Med. Rec., vol. ii. p. 459.
Keen, Proc. Phil. Acad. Nat. Sci., 1869.
Kiedrowski, Virch. Jahresb., 1858, vol. i. p. 48.
Kölliker, Virch. Arch., Bd. x. p. 272.
Lankester, Ray, Pflüger's Arch., vol. ii. 1869, p. 492.
Laschkewitch, Reich. Arch. f. Anat., 1868, p. 653.
Lecorché and Meuriot, Arch. Gén., t. xi. 6e série, pp. 539, 543.
Lewisson, Reich. Arch., 1870, p. 352.
Preyer, Die Blausäure physiol. Unters., 2 Thle. Bown, 1868 u. 1870, contains a full *resumé* of literature on the subject up to 1870.
Preyer, Arch. f. exp. Path. u. Ph., Bd. iii. p. 381.
Rossbach u. Papilsky in Rossbach's pharm. Unters., Bd. iii. 1877.
Schönbein, Schmidt's Jahrb., Bd. cxl. 1868, p. 161.
Schubarth, Horn's Arch. f. med. Erf., Berl. 1824.
Sobernheim, J. F., Handb. d. Prakt. Toxicol., Berlin, 1838.
Stannius, Arch. f. Anat., 1858, p. 95.
Vietz, F. B., Med. Jahrb. d. k. k. oesterreich. Staates, Bd. ii. 1814.
Wahl, De Vi et Effectu Acido Hydrocyanato, Bonn, 1865.
Wallach, Ber. d. deutsch. chem. Ges. x. 2120.

Purgatives.

Asp, Ludwig's Arbeiten, 1868.
Brieger, Arch. f. exp. Path., Bd. viii. p. 355.
Brunton, Lauder, Med. Press & Circular, Dec. 31, 1873, p. 590; Pract. vol. xii. pp. 342 & 403.
Buchheim, Arch. f. physiol. Heilk., Bd. xiii. u. xiv. Virchow's Archiv, Bd. xii. p. 1.
Falck, Virchow's Archiv, Bd. liv. p. 173.
Headland, Action of Medicines, London, 1867, p. 443.
Hay, Matthew, Journ. of Anat. & Physiol., vol. xvi.
Köhler, H., Virchow's Archiv, Bd. xlix. p. 408.
Moreau, F. A., Mémoires de Physiologie, Paris, 1877; Comp. Rend., t. lxvi. 1868; Arch. Générales, 6e sér. t. xvi. p. 234.
Mosler, Berl. klin. Wochens., No. xlv. 1873, p. 533.
Nasse, O., Beitr. z. Physiol. der Darmbewegung, Leipzig, 1866.
Radziejewski, Reichert's und Du Bois-Reymond Arch., 1870, p. 37.
Röhrig, A., Strickers Med. Jahrb., 1873, p. 240; Exp. Unters. ü. d. Phys. d. Gallenabsonderung, Wien, 1873.
Rutherford, British Med. Journ., vol. i. p. 362, 1877; Schmidt's Jahrb., 1878, Bd. clxxvii. p. 11, u. folgende.
Schiff, Il Morgagni, 1867.
Simon, Gus., Arch. d. klin. Chir., xv. p. 99.
Thiry, Sitzungsber. d. Wiener Acad. Math. Naturw. Cl., 1864, Bd. i. p. 95; Gaz. Méd., 1871.
Vulpian, Gaz. Méd., 1873, p. 300.
Wood, Amer. Journ. Med. Sci., vol. lix. p. 395, 1870.

Quinine.

Albertoni & Ciotto, Bull. Thérap., xc. p. 403.
Appert, Virch. Arch., Bd. lxxi. p. 364.
Baldwin, W. O., Amer. Journ. Med. Sci., Ap. 1847, p. 292.
Bauer u. Künstle, Deutsch. Arch. f. klin. Med., Bd. xxiv. s. 53.

Quinine.

Binz, Zur Salicylsäure-u. Chininwirkung, Arch. f. exp. Path. u. Pharm., Bd. i. p. 18, 1873, Bd. v. p. 39, Bd. vii. p. 275; Lond. Pract., p. 4, vol. v. 1870; Virch. Arch., Bd. xlvi. 1864, p. 138.
Bochefontaine, Recherches exp. à la Contractilité de la Rate, Paris, 1873; Arch. de Physiol. July, 1873.
Boeck, Von, Unters. u. d. Zersetzung des Eiweises im Thierkörper, Munich, 1871.
Briquet, Traité Thérap. de Quinquina, Paris, 1855.
Brunton, Lauder, and Pardington, St. Bartholomew's Hosp. Rep., 1876, p. 150.
Burt, Med. & Surg. Reporter, 1870.
Chalvet, Schmidt's Jahrb., Bd. cxli. p. 152; Gaz. Hebdom., 2nd ser. t. v. 1868
Chaperon, Pflüg. Arch. f. Phys., 1869, vol. ii. p. 295.
Chiara, L'Un. Méd., Nov. 20, 1873, p. 795.
Clapton, Med. Times & Gaz., vol. i. p. 462. 1864.
Complete Collection of Literature up to 1875 (82 Nos.) in Binz., Das Chinin Berlin bei Hirschwald, 1875.
Cutler, J. R., Psych. & Med. Legal Journ., 1875.
Dietl. Wien. Med. Wochens., 1852.
Dupuis, L'Action Phys. de Quinine, Paris, 1877.
Eulenburg, A., Reich. Arch. f. Anat. 1865, p. 423.
Geltowsky, Lond. Pract., vol. viii. p. 321.
Hallier, Das Cholera-Contagium, Leipsic, 1867.
Hamilton, J. B., Ind. Med. Gaz., 1873.
Henbach, Arch. f. exp. Path. u. Pharm., Bd. v., p. 233; Centralbl. med. Wiss, 1874, p. 673.
Henke, Deutsch. Arch. f. klin. Med., Bd. xii. p. 630.
Hesse, Ber. d. deutsch. Chem. Ges., x. 2152.
Jacobowitch, Magnan, Revue des Sci. Méd., 1873.
Jerusalimsky, ueb. d. phys. Wirk. d. Chinin. Berl. bei Hirschwald, 1875; Centralbl. med. Wiss., 1876, p. 476.
Jones, Bence, Lectures on Path. and Therap., London, 1867.
Kerner, Lond. Pract., vol. x. 169; Pflüg. Arch. f. Phys., 1870, p. 93
Köhler, Zeitschrift f. d. ges. Naturwiss. f. Sachsen in Thüringen, Bd. xlix. u. Sitzber. der Naturforscher Gesellsch. zu Halle, 1876.
Lauderer, Repertorium f. Pharm., Bd. xxv. 1836, 1839, 1842.
Liebermeister, Deutsch. Arch. f. klin. Med., Bd. iii. 1867.
Magendie, Gaz. Med., 1847.
Martin, A., Inaug. Dies. Giessen., 1868.
Melier, Mémoires de l'Acad., t. xii. p. 722, 1843.
Mosler, Path. d. Leukaemie, Berl., 1872, p. 451.
Monteverdi, Ann. et Bull. de la Société de Med. de Gand, May, 1871.
Naunyn & Quincke, Reich. Arch. f. Anat., 1869.
Pagès, Gaz. Méd., 1846.
Personne, Centralbl. f. d. med. Wiss., 1879, s. 110.
Piorry, Arch. Gén. de Méd., 1847.
Pringle, Abs. on Diseases of the Army, Lond., 1765.
Rabuteau, Bull. Thérap., t. lxxv. p. 475.
Raucillia, L'Union Méd., 1873.
Rapmund, Deutsch. klin., 1874, p. 51.
Rausoné, Inaug. Diss. Bonn., 1871.
Renzi, D., Bull. Thérap. xci. p. 45.
Rhoads, E., & W. Pepper, jun., Pennsyl. Hosp. Rep., vol. i. 1868.
Rich, Charleston Med. Journ. & Review.
Rossbach, Pharm. Unters., Bd. i. Heft iii.
Sayre, Amer. Pract., 1871, p. 260.
Scharrenbroich, Inaug. Diss. Bonn., 1867.
Schlockow, De Chini sulfurici Vi physinonnulla Exp. Vratisl., 1860.

Quinine.

Schroff, Stricker's Med. Jahrb., 1875, p. 175.
Schulte, A., Centralbl. f. d. med. Wiss., p. 727, Nov. 1871.
Walranen, Boston Med. & Surg. Journ., 1873.
West, Jos. J., Savannah Journ. Med., vol. i. p. 19, 1858.
Wilson, J. S., South. Med. & Surg. Journ., p. 341, 1855, Sept. 1860
Zunst, Beit. z. Phys. des Blutes, Inaug. Diss. Bonn., 1868; Arch. f. Exp. Path., Bd. ii. p. 343.

Rhubarb, *vide* Purgatives.

Ricin, *vide* Purgatives.

Rue.

Cahours et Gerhard, Annales de Chim. et de Physique, xxiv. p. 227, ser. iii.; Pharmaz. Jahresb. v. Wiggers, viii. 50.
Cooper, G. T., Med. Exam., N. S. ix. 720.
Gorup-Besanez, Neues Report. für Pharmaz., xix. 385.
Hélie, Bull. de Thérap., xv. 75; Schmidt's Jahrb., xxi. p. 275.

Salicylate and Salicylic Acid.

Bälz, Arch. d. Heilk., xviii. p. 60.
Bochefontaine & Chabret.
Bochefontaine, Le Progrès Méd., 1877, p. 630.
Buchholtz, Arch. exp. Path. u. Pharm., Bd. iv.; Dorpat. Diss., 1866.
Byasson, Centralbl. f. Chir., 1877, p. 809.
Callender, Trans. Lond. Clin. Soc., ix. p. 9.
Danewsky, Arbeit. in Pharm. Lab. Moskaw, i. p. 190.
Drasche, Centralbl. f. Chir., 1876, p. 777.
Farsky, Sitzber. d. k. Akad. d. Wiss. Bd. ii. lxxiv. p. 49.
Jacoud, Le Progrès Méd., 1877, pp. 528, 745.
Laborde, Bull. de Thérap., xciii. p. 276.
Marmé, Göttinger Nachricht, 1878, No. vii. p. 229.
Martenson, Petersb. Med. Zeits., 1875, p. 343.
Meyer & Kolbe, Journ. f. prakt. Chem., Bd. xii. p. 9.
Musey, Bull. Thérap., xiii. p. 318.
Riess, Berl. klin. Wochens., xii. 1875, pp. 674, 675.
Robin, Lond. Med. Rec., 1877, p. 151.
Scheffer, Marburger Diss., 1860.
Schroeder, Deutsch. Arch. f. klin. Med., xviii. 516.
Sée, Bull. de l'Acad. Méd., 1877, p. 697.
Senator, Berl. klin. Wochens., 1875, p. 461.
Stricker, A. E., Berl. klin. Wochens., xiii. p. 1, 1876.
Weber, Bull. de Thérap., xciii. p. 328.
Wolffberg, Deutsch. Arch. klin. Med., xv. p. 403.
Wolfsohn, Königsberg Diss., 1876; Centralb. f. med. Wiss., 1877, p. 30.

Salicylic Acid.

Bertagnini, Annal. d. Chemie u. Pharm., Heft xcvii. s. 248, 1856.
Binz, Niederrh. Ges. f. Nat. u. Heilk. Sitz, v. 6, Dec. 1875, u. 20 März, 1876; u. Berl. klin. Wochenschr., 1876, No. xxvii.
Butt, Centralbl. f. d. med. Wiss., 1875, No. xviii. p. 276; u. zur antipyret. Bedeutung d. Salicylsäure u. d. salicyls. Natrons, Stuttgart, 1876.
Ebstein, Berl. klin. Wochenschr., 1873, 1875, 1876.
Feser u. Friedberger, Arch. f. wiss. u. prac. Thierheilk., 1875, Heft ii. iii. u. vi. 1876, Heft ii. u. iii.
Fleischer, Centralbl. f. d. med. Wiss., p. 628, 1876, No. xxxvi.; u. Arch. f. klin. Med., 1877, Bd. xix.
Fleck, Benzoësäure, Carbolsäure, Salicylsäure, Zimmetsäure, Vergl. Versuche., München, 1875.
Fürbringer, Centralb. f. d. med. Wiss., p. 273, 1875, No. xviii.
Goltdammer, Berl. klin. Wochenschr., 1876, No. iv.
Köhler, H., Centralb. f. d. med. Wiss., 1876, 161, 195; Deutsch. Zeitschr. f. pract. Med. v. Kunze, 1877.
Kolbe, Journ. f. pract. Chem., N. F. Bd. xii 1875, B. xi. p. 9.
Möli, Berl. klin. Wochenschr., 1875, No. xxviii.
Salkowski, Berl. klin. Wochenschr., 1875, No. xxii.
Thiersch. Klin. Ergebnisse der Lister'schen Wundbehandl. in Volkmann's Samml. klin. Vorträge. Nos. lxxxiv. & lxxxv.
Wolfsohn, Dissert. Königsberg, 1876.

Sanguinaria.

Smith, R. M., Amer. Journ. Med. Sci., Oct. 1876. p. 346.

Santonin.

Andaul, Brit. Med. Journ., vol. i. p. 186, 1872.
Berg, Württemberg Medic. Correspond., 1862.
Binz, Arch. f. exp. P. u. Ph., Bd. vi. p. 300.
Brown, Dyce, Brit. and For. Med. Chir. Rev., April, 1871, p. 472.
Falck, Deutsche Klinik, 1860.
Guépin & Martin, Ann. de Thérap., 1862.
Krauss, Inaug. Diss. Tübingen, 1869.
Manns, Marburger Diss., 1858.
Rose, Virch. Arch., Bd. xvi. p. 233, Bd. xviii. p. 15, Bd. xix. p. 522, Bd. xx. p. 245, Bd. xxviii. p. 30, Bd. xxx. p. 442.
Wälz, Jahresber. f. Pract. Pharm., Bd. xv.

Saponin.

Buchheim u. Eisenmenger, Eckhardt's Beiträge, v. 3, Giessen, 1869.
Harnack, Arch. f. exp. Pharm., ii. 1874.
Keppler, Berl. klin. Wochenschr., 1878, p. 475.
Köhler, H., Die totale Anästh. durch Saponin, Halle, 1873.
Lautenbach, Phila. Med. Times.
Pelikan, Berl. klin. Wochenschr., xxxvi. 1867, p. 375; u. Bulletin d. k. Acad. zu S. Petersburg, xii. 1867, p. 253.

Savin.

Letheby, London Lancet, vol. i. p. 677. 1845.

Silver Nitrate, etc.

Bogolowski, Arch. f. path. Anat., Bd. xlvi. p. 413.
Charcot and Ball, Gaz. Méd., 1864.
Curci, Lond. Med. Rec., 1877, p. 72.
Eichmann, Husemann Toxicologie, 871.
Fragstein, Berl. klin. Wochens., 1877, 294.
Frommann, Virch. Arch., Bd. xvii. p. 135.
Jacobi u. Gissmann, A. f. exp. P. u. Pharm., Bd. viii. p. 217, 1878.
Higginbottom, Lond. Pract., vol. ii. p 34, 1869.
Kramer, Das Silber als Arzneim, Halle, 1845.
Neumann, Med. Jahrb., 1877, p. 369.
Pepper, Trans. Phila. Coll. Phys., 1877.
Riemer, Arch. f. Heilk., Bd. xvi p. 296.
Rosenstirn in Rossbach's pharmak. Unters. Bd. i.

Silver Nitrate, etc.

Rouget, Arch. de l'Anatom. et de Physiol., July, 1873, p. 356, u. Jahresber. d. ges. Med., 1870; Bd. i. p. 363.
Roszahegzi, A. f. exp. P. u. Pharm. Bd. ix. p. 289, 1878.
Weichselbaum, Centralb. f. d. med. Wiss., 1878, p. 954.
Yandell, Amer. Pract., June, 1872.

Soda, *vide* Alkalies.

Barnard, Phys. Exp., t. ii. p. 393, Phila. Med. Times, vol. v.
Bidder and Schmidt, Canstatt's Jahresb., 1852.
Grandeau, Robin's Journ. de l'Anat., 1864, p. 378.
Guttmann, Virch. Arch., Bd. xxxv. p. 450.
Longet, Physiologie, Paris, 1861, t.i. p. 196.
Münich, Arch. Vereins Gemeinsch. Arb., Bd. vi. p. 369, 1863.
Nothnagel, Virchow's Archiv.
Plouviez, Com. Rend., t. xxv. 1847, p. 113.
Podkaepow, Virch. Arch., Bd. xxxiii. p. 507.
Rabuteau, L'Union Méd. t. xii. p. 186, 1871.
Roberts, Urinary and Renal Diseases, Am. Ed., 1866, p. 240.

Spigelia.

Eberle, Materia Med. and Therap., vol. i.
Spalsbury, Bost. Med. and Surg. Journ., vol. liii. p. 72, 1855.

Squill.

Dassen, Groninger Diss., 1834.
Husemann, Arch. d. Pharmacie. Bd. vi., Heft iv. 1876; Deutsch. Med. Wochens., xiii. p. 149, 1875; Lond. Med. Rec., 1876, p. 120, Toxicologie, Bd. i. 413.
Jarmersted, A. f. exp. P. u. Pharm., 1879, Bd. ii. p. 22.
Schroff, Wien. Wochenschr., 1864, 43, p. 673.
Wolfring, Bayer. ärztl. Intelligenzbl., 1842.

Strychnine.

Amagat, Journ. d. Thérap., 1875, p. 467.
Ambrosoli, Gaz. Méd., 1857, p. 525.
Bennett, Brit. Med. Journ., vol. ii. p. 436, 1874.
Bernard, Cl., Leçons sur les Substances Toxiques, Paris.
Bochefontaine, Arch. de Phys. norm. et path., 1873, p. 664.
Brown-Séquard, Comptes Rendus, 1849, 29, p. 672.
Buchheim u. Engel, Beitr. z. Arzneiml., Leipzig, 1849, i. p. 92.
Cohn, Wien. Med. Wochens., Nos. xlii. xlvii., 1873.
Deen, Van, Phys. de la Moelle épinière.
Falck, F. A., jun., Vierteljahrsschr. f. gerichtl. Med., N. F. Bd. xx. 2, 193, xxi. 12, u. xxiii. 1874.
Falck, Senior, Virch. Arch., xlix. 1870, p. 458.
Freusberg, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 204, and. 348, 1875.
Harley, Lancet, July, 1856, p. 40.
Heinemann, C., Virch. Arch., Bd. xxxiii. p. 394.
Hippel, V., Wirk. des Strych. auf Augen. Berlin, 1873, p. 77.
Husemann, Arch. d. Pharm., Bd. viii. Heft. 3, 1877.
Jacond, Pathol. Interne., i. 441.
Jochelsohn, Rossbach's pharm. Unters., Bd. i.
Klapp, Journ. Mental Diseases, Oct. 1878.
Kölliker, Virch. Arch., Bd. x. p. 239, 1856.
Lange, F., Königsberger Diss., 1874.
Leube, Arch. f. Anat. u. Phys., 1867, p. 629.
Magendie, Paris Soc. Philom., N. Bull. i. 363, 1808.
Mager, S. Wiener. acad. Sitzungsber. Math. Nat. Wiss. Cl. 3 Abth. 1871.

Strychnine.

Martin-Magron and Buisson, Brown Séquard's Journ. de la Phys. 1860, t. iii. pp. 130, 342.
Matteucci, Traité des Phénom. electro-physiol. Paris, 1844.
Meschede, Berl. klin. W. 1878, No. xxiv.
Moreau, Comptes. Rend. Soc. de Biol. 1855, p. 173.
Nagel, Die Behandl. d. Amaurosen u. Amblyopeen m. Strych. Tübingen, 1871.
Nasse, O., Centralbl. f. med. Wiss., 1865, p. 787.
O'Farrell, L., Phila. Med. Times, vol. iii. p. 311.
Orr, Gaz. Méd., July 6, 1872.
Pelikan, E., Beitr. z. ger. Med. p. 92, 1858.
Ranke, Virch. Arch., lxxv. p. 1, 1878.
Richter, Zeitschr. f. rat. Med., iii. Bd. xviii. p. 76.
Rosenthal u. Leube, Arch. für Anat. u. Phys., 1867, p. 629.
Rosenthal, Compt. Rend. lxiv. p. 1142.
Rossbach, Centralbl. f. med. Wiss., p. 369, 1873, xxiv.
Rossbach u. Jochelsten, Würtzburg. Abhandl., 1873, p. 92.
Savory, Lancet, May, 1863, Schmidt's Jahrb. cxix. p. 236, 1863.
Schiff, Schmidt's Jahrb., Bd. cxli. p. 25.
Schlesinger, Wien. Med. Jahrb., 1874.
Schroff, V., jun., Wien. Med. Jahrb., 1872, p. 420.
Schultzen, Arch. f. Anat. u. Phys. (Dubois), p. 491, 1864.
Spence, A. T., Edin. Med. Journ., July, 1866, xii. i. p. 44.
Tschepke, Deut. Klinik., xiii. 1861.
Uspensky, Arch. f. Anat. u. Phys., 1868, iv. p. 522.
Valentin, Path. der. Nerven, p. 327, pt. ii. Leipzic, 1864; Arch. de Physiol., Nov. 1870, p. 125, d.t. iii. p. 120.
Wittich, Bericht Fortschritte Anat., 1857, p. 434.
Wundt, Unt. d. med. d. Nerven, Stuttgart, 1871.

Sugar.

Mering u. Musculus, Hoppe-Seyler's Z. f. phys., Ch. i. p. 395, and ii. 177.

Sulphide of Calcium.

Ringer, Sidney, Lancet, Feb. 1874, vol. i, p. 264.

Sulphur and Sulphuretted Hydrogen.

Dorpater Diss. Krause, 1853, Trachtenberg, 1861, Höppener, 1863.
Hermann, Toxicologie.
Hoppe Seyler, Centralbl. f. d. med. Wiss., 1863, p. 433; Med. chem. Unters., 1867, Bd. ii.
Kunkel, Pflüger's Arch., Bd. xiv. p. 344.
Poleck, Die chem. Natur. der Minengase, etc., Berl., 1867.
Regensburger, Centralbl. med. Wiss., 1877, p. 328.
Rosenthal u. Kaufmann, Reichert's Arch., 1866, p. 647.
Schmiedeberg, Arch. d. Heilk., 1867, Bd. viii. p. 422.
Sertoli, Instituto fisiol. di. Pavia, 1869.

Tannic Acid.

Hennig, Arch. d. Pharm., Bd. cxxxiii.
Rosenstirn, Rossbach's pharmak. Unters., Bd. i.
Schroff, Die Pflanzenstoffe, Lehrb. d. Pharm., i. Auflage.

Tannin, *vide* Tannic Acid.

THUJA.

Köhne, Göttingen Diss., 1883.

THYMOL.

Husemann, Arch. f. exp. Path. u. Pharm., Bd. iv. 1875, p. 288.
Lewin, Centralbl. f. d. med. Wiss., 1875, p. 324.

TOBACCO, *vide* NICOTINE.

Benham, W. T., West Riding Lun. Reports, vol. iv. p. 305, 1874.
Bernard, Cl., Substances Toxiques, p. 410.
Copeland, Dict. of Pract. Med. art. Colic.
Hirschmann, Reich. Arch., 1863, p. 309.
Husemann, Handb. d. Toxicol., vol. ii. 483.
Nasse, Beiträge z. Phys. der Darmbewegung, Leipsic, 1866.
Reil, Journ. f. Pharmacodyn, Bd. ii. p. 203.
Rosenthal, Centralbl. f. med. Wiss., 1863, p. 738.
Traube, Allegm. Med. Central. Zeit., 1862.
Uspensky, Reich. Arch., 1868, p. 525.
Vulpian, Comptes Rendus. de la Soc. de Biol., 1859, p. 151.

TRIMETHYLAMINE OR (PROPYLAMIN.)

Husemann, Selige, Arch. f. exp. Path. u. Pharm., Bd. vi. p. 55.

VALERIANATE OF AMYL.

Wade, W. F. Brit. Med. Journ., i. 1874, p. 741.

VERATRINE.

Bezold, V., u. Hirst, Unters. a. d. Würtzburger-physiol. Laborator. Bd. i. 1869. (Contains the entire older Literature.)

VERATRINE.

Brunton and Cash, Cent. f. d. med. Wiss., 1883, p. 81; Journ. of Physiol. iv. 1.
Claus, Journ. of Anat. viii. p. 228.
Eisenmenger, Ueb. d. Einfluss d. Gifte. u. d. Zuckungscurve des Froschmuskels. Diss. Giessen., 1862, p. 40.
Fick u. Böhm, Verhandl. d. phys. med. Ges. in Würtzburg., N. F. Bd. iii. p. 198, 229.
Guttmann, Reich. Arch. f. Anat., 1866, p. 498.
Jones, Phila. Med. and Surg. Reporter, xvii. p. 361, 1872.
Kölliker, Virch. Arch., Bd. x. p. 257, exp. ix.
Ott, Toxicol. Studies. Phila., 1874.
Pellikan, V., u. Kölliker, Würzburg. Verh., ix. p. 106.
Praag. L. von., Virch. Arch., vii. p. 252, 1854.
Ringer, Arch. of Med. vii., Feb., 1882.
Robin's Journ. de l'Anat., 1868; t. v. p. 206, Gaz. Méd. de Paris, No. 5, p. 69, 8, p. 120, 10, p. 148, 11, p. 167, 1857.
Rossbach, Clostermeyer u. Harteneck, in Rossbach's pharm. Unters. Bd.i ii. and. Pflüger's Arch., Bd. xiii. u. xv.
Rossbach u. Anrep, Pflüger's Arch., Bd. xxi. 240, 1880.
Taylor, Med. Jurispr., 2nd ed. Lond. 1873.
Turnbull, Investigation of Extern. Applic. of Veratria, London, 1829; Schmidt's Jahrb., ii. 379.
Weyland, vergleich. Unters. üb. Veratrin Sabadillin. Delphinin. etc., Giessen, 1869.
Wood, H., Amer. Journ. Sci., Jan. 1870, p. 36.

WHEY.

May, Bair. Arztl. Intelligenzbl., 1879, No. xii. s. 123.

ZINC.

Harnack, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 44.
Meihuizen, Arch. f. ges. Physiol., Bd. vii. p. 212.
Michaëlis, Arch. f. phys. Heilk., 1851, p. 109.
Schlokow, Deutsch. Med. Wochenschr., 1879, Nos. xvii. u. xviii. pp. 208 & 221.

THE END

WELLCOME LIBRARY INSTITUTE

RICHARD CLAY AND SONS,
BREAD STREET HILL, LONDON, E.C.,
And at Bungay, Suffolk.

706
b. 1. 2